## **Golder Brawner Associates**

CONSULTING GEOTECHNICAL ENGINEERS

H. Q. GOLDER C. O. BRAWNER V. MILLIGAN J. L. SEYCHUK N. R. McCAMMON R. M. WILSON D. B. CAMPBELL A. A. GASS D. L. PENTZ

.

REPORT TO

COMINCO LTD.

RE

HB TAILINGS DAM NEAR SALMO, B.C.

Distribution: 6 copies - Cominco Ltd. Trail, B.C. 2 copies - Golder, Brawner & Associates Ltd. Vancouver, B.C.

V72109

June 22, 1972

## TABLE OF CONTENTS

4

1.0

i i i i

1

-

-4

-

÷.

TABLE OF CONFERENCES	
	Page 10.
INTRODUCTION	1
SUMMARY OF COUCLUSIONS AND RECOMMENDATIONS	1
PROCEDURE	2
HB TAILINGS DAM	3
FOUNDATION SOILS	5
EMBANKMENT STABILITY	5
SAFETY AGAINST OVERTOPPING	6
SEEPAGE	7
SURFACE EROSION	7

# GOLDER, BRAWNER & ASSOCIATES

. .

Page 2 EGM-2013-00163

11

1.1

#### INTRODUCTION

This report presents the results of an investigation of the existing NM Tailings Dan south of Salmo, B.C., together with an assessment of its stability. An assessment is also made of the suitability of the existing dam to impound tailings that would be generated in the event that Cominco decide to put the HB mine and concentrator back into operation. The investigation and this report were authorized by Cominco Purchase Order HB2 dated June 1, 1972.

#### SUMMARY OF CONCLUSIONS AND RECOMMENDATIONS

- 1) The water level in the existing tailings pond can be raised to elevation 2502; 3 ft. below the crest of the existing HE Tailings Dam.
- Normal water surface in the tailings pond should be maintained at a level not higher than elevation 2502 to assure that adequate freeboard is maintained.
- The results of stability analyses indicate that the existing embankment has an adequate factor of safety with respect to a shearing failure of the downstream slope.
- 4) The foundation soils on which the UP Tailings Dam has been constructed consist of dense glacial till. These glacial till soils exhibit high shear strength characteristics, and are relatively incompressible. They provide unyielding foundation support for the tailings dam, and preclude the possibility of a shearing failure through the foundation.
- 5) In the event that Cominco decide to raise the crest of the existing tailings dam, this should be done by placing additional fill on the crest, and on the downstream fill slope. A drainage blanket consisting of clean, well-graded sand and gravel should be provided adjacent to the existing downstream fill slope prior to placement of new fill.

GOLDER, BRAWNER & ASSOCIATES

#### PROCEDURE

The UB Tailings Dam was insepcted by the writer in company with Mr. G. Shoblow of Cominco Ltd. on May 24th and 25, 1972. At the time of this inspection, the existing bourow pits at the east and west abutments of the dam were examined to gain an appreciation of the nature and type of soils that had been used in its construction.

Two test pits were excavated into the existing embankment fill. Test pit no. 1, located on the crest of the tailings dam was excavated to a depth of 4 1/2 ft. using a small backhoe. Owing to difficulty of access, test pit no. 2, located at the toe of the fill slope was excavated by hand. Representative samples of soil from test pits 1 and 2 were retained for laboratory testing.

A 20 ft. long section of perforated pipe was installed in a drilled hole on the centraline of the dam crest to permit measurement of the phreatic water surface within the section.

Representative samples of the embankment fill, materials were subjected to grain size analysis to determine the particle size distribution of the fill material. Two typical grain size curves are shown on Fig. 5. Samples of the no. 4 minus fraction of the material were subjected to laboratory shear strength tests to evaluate the shear strength parameters of the soils used in the construction of the embankment (see Fig. 6). A ground survey by Mr. H. Dixon of Cominco Ltd. established the configuration of the existing downstream fill slope.

Using the data collected in the course of the field and laboratory investigations, stability analyses were performed to

## GOLDER, BRAWNER & ASSOCIATES

assess the factor safety of the dam with respect to potential shearing failure through the embankment.

#### HB TAILINGS DAM

The HB Tailings Dam is located approximately four miles south of Salmo, B.C. (see Fig. 1). The dam was originally constructed in 1955 for retention and storage of tailings produced at the HB Mine, which operated from 1955 to 1966. The mining operations were suspended in 1966.

The creat of the MB Tailings Dam is approximately 650 ft. long, and is curved in the upstream direction. The maximum height of the dam is of the order of 50 to 60 ft. above the original ground surface. Contours on the downstream face of the tailings dam, together with three typeial cross sections are shown on Fig. 2. Photographs of the tailings dam are shown on Figs. 3 and 4.

The HE Tailings Dan is equipped with two decant outlets to pass water from the upstream to the downstream side of the structure. Each decant consists of a timber tower on the upstream side of the dam, with a 24 in. diameter steel corrugated pipe passing through the embankment from the upstream to the downstream side of the dam. The present inlet elevation at the easterly decant tower is 2496.3, while the inlet elevation at the westerly decant tower is 2499.6. The east decant tower passes normal flows which enter the tailings dam, while the west decant tower would serve as an energency outlet in the event that the capacity of the east decant were exceeded.

## GOLDER, BRAWNER & ASSOCIATES

Page 5 EGM-2013-00163 3.

The HB tailings dam is an earthfill entantment constructed of materials borrowed from the east and west abutments. I'e understand that the borrow materials were excavated and transported to the section by bulldozers. Compaction within the section was achieved by the traffic of the construction equipment used to spread and place the fill.

The materials used in construction of the dam consist of silty sand and gravel with scattered cobbles and shall boulders. Nost of the available borrow materials have now been removed from the east abutment. The limited amount of material which remains on the east abutment consists predominantly of slightly silty find to medium sand. The materials from the west borrow pit consist of a well graded heterogeneous mixture of silt, sand, gravel, cobbles and boulders (glacial till). The materials incorporated within the west half of the dam contain more stone than those within the east half, reflecting the higher stone content of the borrow materials that were available from the west abutment.

The crest of the dam was raised periodically during the period 1955 to 1966 as the tailings storage requirements increased. The crest of the dam was raised by the downstream method of construction, i.e. additional fill was placed on the crest and on the downstream slope of the dam.

We understand that the original dam was constructed with an earthfilled timber crib retaining wall at the downstream toe. Subsequent to construction of this retaining wall, a flat

## GOLDER, BRAWNER & ASSOCIATES

Page 6 EGM-2013-00163 earth fill supporting berm has been constructed on its downstream side, and the crib has been covered over. Prior to placement of this stabilizing fill, several concrete pipe drains were installed at the downstream too of the dam. The outlets of some of these drains were seen during the site inspection on May 25th.

#### FOUNDATION SOILS

Soil exposures at the downstream too of the dam were examined during the May 24th - 25th inspection. The in situ soils exposed at the downstream too of the MB Tailings Dam consist of dense glacial till composed of a heterogeneous assortment of silt, sand, gravel and occasional small cobbles. The material is very dense, and exhibits high shearing strength characteristics. These materials are capable of providing foundation support for the structure without any danger of shearing failure or significant settlement under the weight of the embankment fill.

#### EIBAIKIEIT STABILITY

Direct shear tests on representative samples of the embankment fill show that the fill material has an angle of internal friction of approximately 35 1/2° with 0 cohesion. The flat toe berm below elevation 2470 on the downstream side of the dam provides a high degree of stability to the structure, and precludes the possibility of a deep seated shearing failure within the embankment. This toe berm reduces the effective height of the embankment to approximately 35 ft.

#### GOLDER, BRAWNER & ASSOCIATES

Page 7 EGM-2013-00163 5.

The stability of the existing embankment between elevation 2470 and the present creat at elevation 2505 is governed by the gradient of the downstream fill slope between these elevations, the shear strength characteristics of the embandment fill, and the position of the phreatic surface within the section. The approximate position of the phreatic surface for a tailings pond level at elevation 2503 is shown on section BB, Fig. 2. The phreatic surface shown on Section ED is based on the water level measurement in the observation well installed at Section AN on the centreline of the dam, a water level at elevation 2503 on the upstream face, and the approximate position of the drains on the downstream side of the buried timber crib.

The stability analyses indicate that the minimum factor of safety of the embankment, for potential failure surfaces which intersect the upstream slope at or below the crest is 1.3. The factor of safety is considered adequate, although it is near the lower limit of the range considered acceptable by conventional engineering practice.

#### SAFETY AGAINST OVERTOPPING

The size of the catchment area surrounding the UB Tailings Pond is approximately 480 acres. The approximate boundaries of the catchment area are indicated on Fig. 1. The closest station at which long term percipitation records have been maintained is Nelson, B.C., which is approximately 26 miles north of the UB Tailings Dam. The long term percipitation

## GOLDER, BRAWNER & ASSOCIATES

6.

records at Nelson indicate a maximum rainfall of 2.6 in. in 24 hrs. Assuming a runoff coefficient of 0.8, a rainfall of 2.6 inches in 24 hours over an area of 430 acres would result in an average runoff rate of approximately 40 cu.ft./sec. The two 24 in. diameter decant pipes are created of passing between 50 and 60 cu.ft./sec. Thus, the existing decant system at the T3 Tailings Daw is considered to have sufficient capacity to pass the maximum anticipated flot into the tailings pond. We therefore conclude, that the existing outlet capacity is adequate, and that the structure would not be over topped during the maximum anticipated.runoff.

#### SEEPAGE

Based on examination of the ground surface at the downstream too of the existing dam, the total leakage was estimated to be of the order of 5 to 10 gallons per minute. If the water surface in the pond is raised from its present level to elevation 2502, the rate of scepage will increase only slightly. Examination at points where drains exit on the downstream slope indicated that the existing drains are not carrying soil particles. The existing drains appeared to be operating satisfactorily.

#### SURFACE EROSION

The presence of cobbles and gravel within the embankment fill affords a degree of erosion protection on the downstream face of the existing embankment. Examination of the dam indicates

## GOLDER, BRAWNER & ASSOCIATES

Page 9 EGM-2013-00163 that no significant surface erosion has occurred on the downstream fill slope during the six year interval 1966 to 1972. Also, there is no evidence that wave action in the tailings pond has resulted in any significant deterioration of the upstream fill slope. The performance of the existing structure indicates that the day has adomate protection against surface erosion.

In conclusion, our analyses and studies indicate that the existing NB Tailings Dam will perform satisfactorily after the water level in the tailings pend has been raised to elevation 2502. If during operation, it is decided that the crest of the dam should be raised to provide a greater depth of water for clarification of the tailings effluent, the crest of the dam should be raised by placing additional fill on the crest, and on the downstream fill slope. To assure that the phreatic surface within the section does not rise above the level of the existing downstream fill slope, a laver of free draining granular fill should be placed adjacent to the existing downstream slope, as illustrated on Fig. 7. The fill placed on the crest and on the downstream slove should be spread in horizontal layers not exceeding 12 in. thickness, and each laver should be compacted to a minimum density equivalent to 95 percent of maximum dry density as determined by the Standard Proctor Compaction Test prior to placement of each succeeding layer.

GOLDER BRAWNER & ASSOCIATES LTD.


Jains B, Complete

D.B. Campbell, P. Eng.


DBC/sm


GOLDER, BRAWNER & ASSOCIATES


Page 10 EGM-2013-00163 8.





PROJECT No. -











Specification No. HB0.005-1

1

COMINCO LTD.

H.B. MINE TAILINGS DIKE EXTENSION

INSTRUCTIONS TO TENDERERS FORM OF TENDER SCHEDULE OF QUANTITIES & UNIT PRICES FORM OF CONTRACT AGREEMENT GENERAL CONDITIONS OF CONTRACT SPECIFICATION

DRAWINGS

Prepared by COMINCO LTD. June 1974

164

Page 17 EGM-2013-00163

#### COMINCO LTD.

#### H.B. MINE TAILINGS DIKE EXTENSION

INDEX

Pages

Instructions to Tenderers Form of Tender Schedule of Quantities and Unit Prices Form of Contract Agreement General Conditions of Contract Specification - Section 1 - Special Provisions - Section 2 - Earthwork

> Page 18 EGM-2013-00163

# SPECIFICATION SECTION 2 EARTHWORK

#### 2-01 SCOPE

The work covered in this section includes all earthwork, clearing and development of borrow pits, establishment and maintenance of access and haulroads, dewatering and extending of the decant discharge culvert necessary for the fulfillment of the contract.

#### 2-02 GENERAL ARRANGEMENTS

All excavation, fill placing and other construction work shall be completed to the lines, elevations and sections shown on the drawings or as directed by the Engineer.

Fill material shall be obtained from borrow areas suggested in Section 1 and as approved by the Engineer.

#### 2-03 CLEARING

The work to be done under this Clause shall comprise the supply of all labour, material and plant and the performance of all work necessary for clearing of the site as shown on the drawings, as required by the Engineer and as specified herein.

Clearing shall consist of cutting and disposing of all trees, shrubs, brush, debris and all other perishable materials, including fallen trees and logs within the areas to be cleared.

All trees, shrubs and brush shall be cut to within 2" above the ground surface. The organic cover of topsoil on the ground surface shall be left intact, except where excavation is required as stated in these documents.

All vegetation and debris resulting from clearing operations regardless of size, shall be removed from the areas cleared, and shall be disposed of by the following methods, upon written approval of the Engineer.

- (a) Combustible materials may be piled and burned on open fires as specified herein. Material to be disposed of in this way shall be completely burned so that it is all reduced to ashes.
- (b) Materials obtained from clearing which cannot be burned may be placed in nearby disposal areas as directed by the Engineer. The material placed in disposal areas shall be crushed with a tractor or other heavy equipment to a thickness of not more than 5 feet.

#### 2-03 CLEARING (Cont'd)

The Contractor shall be responsible for any damage done by fire resulting from the work under this item and shall at no time leave a fire unattended until it is fully extinguished. All burning shall be done in strict conformance with the rules and regulations of local, provincial, and federal agencies and it shall be the responsibility of Contractor to obtain all burning permits.

Sufficient equipment shall be ready and available together with a sufficient force of men to control burning operations at any time.

Measurement for payment for clearing will be made of the number of acres cleared in accordance with these specifications, measured to the nearest 1/10 acre as the projection onto a horizontal plane.

Payment for clearing will be made at the unit price per acre bid in the Schedule of Quantities and Unit Prices.

#### 2-04 FOUNDATION PREPARATION

The work to be done under this item shall comprise the supply of all labour, material and plant for the performance of all work necessary for the preparation of the foundations for the dike as shown on the drawings, as specified herein and as required by the Engineer.

Foundation preparation shall be scheduled such that the appropriate fill material may be placed shortly thereafter. No fill material shall be placed on any part of the foundation area until each part of the foundation has been approved by the Engineer.

Foundation preparation shall include the removal of any coarse rock or boulders that are laying where construction is to take place. The coarse rock and boulders shall be removed to ensure a good contact between the new and the existing work. The coarse rock may be removed by bulldozing the rock off the crest and down the downstream slope so that the remaining rock protruding above the general surface is not larger than 6 inches in size.

If necessary, the Engineer may require that the foundation surface be moistened or dried prior to compaction, and scarified, moistened or dried prior to placing of the fill material to create a satisfactory bond between the foundation and the fill materials.

The foundation surface shall be compacted by four complete passes of compaction equipment as specified herein. Pockets of poor or unsuitable materials, which during this operation cannot be satis-

#### EARTHWORK

#### 2-04 FOUNDATION PREPARATION (Cont'd)

factorily compacted, shall be excavated to the limits ordered by the Engineer.

Unsuitable materials excavated and disposed of when ordered by the Engineer shall be measured by cross-sectioning the area to be excavated before and after removal. Payment will be made at the unit price bid for "Unsuitable Material" in the Schedule of Quantities and Unit Prices.

Foundations soils which become soft due to inadequate control of surface or subsurface water, or for any other reason become unacceptable due to the Contractor's operations, shall be removed and replaced with fill material and compacted as specified herein at no additional expense to the Owner.

The placing of fill will not be permitted on foundation soils which 'are frozen. The removal of any frozen foundation soils shall be accomplished at no additional expense to the Owner.

Measurement for payment for the preparation of the foundations will be made of the actual prepared surface area, projected onto a horizontal plane, measured in square yards, prepared as specified herein, with no allowance made for irregularities.

Payment for the preparation of the foundation soil complete in every respect and as specified herein, will be made at the unit price per square yard bid in the Schedule of Quantities and Unit Prices.

#### 2-05 FILTER ZONE

#### 2-05 (a) Scope of Work

The work to be carried out under this item shall comprise the supply of all labour, material, plant, equipment, fuel and the performance of all work necessary to prepare, develop, excavate, load, haul, rehandle if necessary, place, compact, upgrade the existing haul road, maintain, leave in good condition and any other operations necessary to carry out the work as required by the Engineer.

#### 2.05 (b) Fill Material

This material is a clean sand and gravel or clean gravel and cobbles, the gradation of which lies within the shaded envelope shown on Figure 1. Material in this size range is available about  $1\frac{1}{2}$  miles from the dike.

All fill shall be free of organic materials, roots, and other perishable materials. No fill material shall contain ice or 'snow, or shall be placed in a frozen condition.

Cobbles and boulders larger than 9" shall be removed from all fill prior to compaction.

#### 2.05 (c) Borrow Operations

Fill materials shall be obtained from the borrow areas as indicated in the Tender Documents and as approved by the Engineer. Approval by the Engineer of a source of fill material shall not be construed as constituting approval of all materials to be taken from that source.

The Contractor shall conduct his operations in borrow areas in such a manner which shall ensure that the maximum possible volume of suitable construction material may be obtained. Measures shall be taken to ensure adequate drainage of water from the borrow areas so that the borrow material is obtained at a water content suitable for compaction and so that the borrow operations are not affected adversely. Ponding and infiltration of water shall be prevented.

Some of the material in the borrow areas may be frozen. The Contractor shall conduct his operations in such a manner to ensure that the frozen material shall be thawed prior to placement in the dikes. To meet this requirement the Contractor shall open and work as large an area of the borrow areas practical, and shall rip, scarify, disc, harrow or use any other similar means to expose the frozen material to permit thawing.

The detailed planning of the operation of the borrow area shall be the responsibility of the Contractor and shall be subject to the approval of the Engineer.

#### EARTHWORK

#### 2-05 (c) Borrow Operations (cont'd.)

Prior to commencement of the work, the Contractor shall submit for approval by the Engineer, a plan showing the details of his proposed methods and the sequence and schedule of operations to be followed for the utilization of the borrow area to obtain the required fill material. During construction the plan shall be reviewed and modified as required. A copy of the modified plan and schedule shall be provided for the Engineer's approval prior to implementation of any changes.

Unsuitable material shall be disposed of as directed by the Engineer and graded off to present a reasonably uniform appearance.

The Contractor shall be responsible at all times for the safe operation of the borrow area. All slopes left permanently exposed shall be approved by the Engineer.

#### 2-05-(d) Haul Roads

Approval by the Engineer of any proposed haul roads shall be obtained before commencing construction of the haul roads.

All haul roads built and maintained by the Contractor shall be available, without charge, for use by the Engineer and by others authorized by the Engineer, and at completion of the Contract, shall become the property of the Owner.

#### 2-05 (e) Compaction Equipment

The Filter Zone shall be compacted with a grid-roller towed by a suitable tractor. The grid-roller shall be a Hyster Model D with concrete ballast weighing approximately 13 tons, or an alternative approved by the Engineer.

Power tampers for compaction near structures shall weigh not less than 200 pounds and shall have a ramming foot area not exceeding 80 square inches. The rammer shall be capable of delivering at least 200 foot pounds of compacting energy per blow.

#### 2-05 (f) Placing and Compacting

No fill material shall be placed in any section of the dike until the foundation soil for that section has been suitably prepared according to the requirements of these specifications.

### 2-05 (f) Placing and Compacting (cont'd.)

The placing of fill material shall be directed at obtaining a stable and a reasonably homogeneous fill. The fill material shall be spread in approximately horizontal layers of uniform thickness by bulldozers or other approved means. If necessary, discing, harrowing, or other approved means shall be employed to break up the material and to blend it before compaction.

The thickness of fill layers shall not exceed twelve inches before compaction.

Four passes of the compaction equipment shall be made over each layer before a succeeding layer is placed.

No separate payment will be made for compaction.

The fill shall be placed in such a way that the top surface of any section, along the axis of the dike, shall remain approximately level. During spreading and compaction, a slope towards the downstream toe shall be maintained on the fill surface providing a transverse grade not exceeding ten percent so that water from precipitation will drain. In order that the effect of precipitation on placed fill be minimized, the surface shall be rolled smooth, and adequate drainage shall be provided prior to periods of precipitation when operations must be suspended.

The elevation of the filter blanket shall be so maintained that it is no more than four feet higher than the adjacent Common Fill. Care shall be maintained so that the mixing of the Filter Zone and Common Fill is not allowed to take place. Each zone shall be kept clearly separate.

All openings through the dike for construction purposes shall be subject to the Engineer's approval. The slope of openings left through dikes and at the end of any unfinished section shall not be steeper than four horizontal to one vertical.

The water content of the fill prior to and during compaction shall be distributed uniformly throughout each layer. The water content shall be within the range required to obtain the specified soil density during compaction.

Overbuilding or under building shall be remedied at the Contractors expense to the satisfaction of the Engineer.

#### EARTHWORK

#### 2-05 (g) Measurement and Payment for "Filter Zone" and "Overhaul -Filter Zone"

The unit price tendered for "Filter Zone" shall include all costs to complete the work as described under paragraph 2-05 (a), and as detailed elsewhere in the Tender Documents. A free-haul distance of 2 miles is to be included in the tender price for the ltem "Filter Zone"

The unit of measure is the cubic yard and is the volume measure in place on the dike by cross-sectioning before and after the placement and compaction of the filter zone.

All measurements for payment purposes shall be carried out by a survey crew as laid out in paragraph 2-08. Measurement will be made to the theoretical neat lines where a zone is built to or beyond the theoretical neat line. Measurement will be made to the actual surface where the surface of a zone is not built out to the theoretical neat line. Payment for all work carried out under this Section and completed in all respects will be the product of the volume measured and the unit price tendered for "Filter Zone".

An overhaul unit price for hauling beyond the 2 mile freehaul limit is to be tendered under the Item "Overhaul-Filter Zone". The tendered price is to include for all additional costs incurred for the haul and return of haulage vehicles. The unit of measure is the cubic yard-station. This unit is the product of the volume of materials moved and the distance beyond the free-haul limit measured in one direction in stations. One station is one hundred feet.

#### 2-06 SELECT IMPERVIOUS AND COMMON FILL

2-06 (a) Scope of Work

The work to be carried out under this item shall comprise the supply of all labour, material and plant, fuel and the performance of all work necessary to prepare and maintain borrow areas and haul roads, rip, excavate, load, transport, dump, spread and compact fill material for the tailings dikes as shown on the drawings, as required by the Engineer and as specified herein.

#### 2-06 (b) Fill Material

Select impervious fill shall be a glacial till, well graded with a maximum size of 9 inches and with at least 20% finer than the No. 200 U.S. Standard sieve size. 2-06 (b) Fill Material (cont'd.)

Common fill shall be a glacial till, well graded with a maximum size of 9 inches.

Both select impervious fill and common fill must be of a gradation and moisture content that allows them to be placed and adequately compacted as specified herein.

All fill shall be free of organic materials, roots, and other perishable materials. No fill material shall contain ice or snow, or shall be placed in a frozen condition.

Cobbles and boulders larger than 9 inches shall be removed from all fill prior to compaction.

#### 2-06 (c) Borrow Areas

Fill material shall be obtained from the Borrow Areas near the east and west abutments of the existing dike and as approved by the Engineer. Approval by the Engineer of a source of fill material shall not be construed as constituting approval of all materials to be taken from that source.

#### 2-06 (d) Borrow Operations

The Contractor shall conduct his operations in borrow areas in such a manner which shall ensure that the maximum possible volume of suitable construction material may be obtained. Measures shall be taken to ensure adequate drainage of water from the borrow areas so that the borrow material is obtained at a water content suitable for compaction and so that the borrow operations are not affected adversely. Ponding and infiltration of water shall be prevented.

Some of the material in the borrow areas may be frozen. The Contractor shall conduct his operations in such a manner to ensure that the frozen material shall be thawed prior to placement in the dikes. To meet this requirement the Contractor shall open and work as large an area of the borrow area as practical, and shall rip, scarify, disc, harrow or use any other similar means to expose the frozen material to permit thawing.

The detailed planning of the operation of the borrow area shall be the responsibility of the Contractor and shall be subject to the approval of the Engineer.

Prior to commencement of the work, the Contractor shall submit for approval by the Engineer, a plan showing the details of his

#### EARTHWORK

#### 2-06 (d) Borrow Operations (cont'd.)

proposed methods and the sequence and schedule of operations to be followed for the utilization of the borrow area to obtain the required fill material. During construction the plan shall be reviewed and modified as required. A copy of the modified plan and schedule shall be provided for the Engineer's approval prior to implementation of any changes.

The Contractor shall be responsible at all times for the safe operation of the borrow area. All slopes left permanently exposed shall be approved by the Engineer.

Unsuitable materials shall be removed and placed in disposal areas as directed by the Engineer. The disposal area and pile shall be kept neatly graded for appearance, drainage and stability.

#### 2-06 (e) Haul Roads

Approval by the Engineer of any proposed haul roads shall be obtained before commencing construction of the haul roads.

All haul roads built and maintained by the Contractor shall be available, without charge, for use by the Engineer and by others authorized by the Engineer, and at completion of the Contract, shall become the property of the Owner.

#### 2-06 (f) Compaction Equipment

The filter zone shall be compacted with a grid-roller towed by a suitable tractor. The grid-roller shall be a Hyster Model D with concrete balast weighing approximately 13 tons or an alternative approved by the Engineer.

Power tampers for compaction near structures shall weigh not less than 200 pounds and shall have a ramming foot area not exceeding 80 square inches. The rammer shall be capable of delivering at least 200 foot pounds of compacting energy per blow.

#### 2-06 (g) Placing and Compacting

No fill material shall be placed in any section of the dike until the foundation soil for that section has been suitably prepared according to the requirements of these specifications.

The placing of fill material shall be directed at obtaining a stable and a reasonably homogeneous fill. The fill material

#### 2-06 (g) Placing and Compacting (cont'd.)

shall be spread in approximately horizontal layers of uniform thickness by bulldozers or other approved means. If necessary, discing, harrowing, or other approved means shall be employed to break up the material and to blend it before compaction.

1....

The thickness of fill layers shall not exceed twelve inhces before compaction.

The fill shall be placed in such a way that the top surface of any section, along the axis of the dike, shall remain approximately level. During spreading and compaction, a slope towards the downstream toe shall be maintained on the fill surface providing a transverse grade not exceeding ten percent so that water from precipitation will drain. In order that the effect of precipitation on placed fill be minimized, the surface shall be rolled smooth, and adequate drainage shall be provided prior to periods of precipitation when operations must be suspended.

Each zone shall be kept clearly separate by a small difference in elevation.

If the impervious fill material is too dry or too wet, water shall be added or removed by working the fill with a harrow, scarifier or other approved equipment until the water is uniformly distributed and satisfies the requirements of these specifications. Any conditioning of the fill material that may be required to obtain fill with a water content within the required range may be undertaken in the borrow area or after placement in the layer.

Each layer of fill shall be compacted by at least four complete coverages of the compaction equipment as specified in paragraph 2-06 (f). Additional coverages with the compaction equipment shall be made if necessary to ensure both the select impervious and the common fill materials are compacted to a dry density at least equal to 95% of the laboratory maximum dry density as determined from the Product compaction tests as specified in ASTM D698.

The surface of the existing dike, against which the select impervious fill or common fill is to be placed, is to be bladed and scarified and then blended in with the new materials to create a homogeneous fill free of any unconformity.

#### 2-06 (g) Placing and Compacting (cont'd.)

The fill within any zone shall be effectively bladed and mixed so as to create a homogeneous gradation. Care shall betaken to avoid building horizontal layers into the dike that are of a gradation differing largely from the adjacent layers.

If, in the opinion of the Engineer, the surface of the prepared foundation, or the rolled surface of any layer of the fill is too dry or too smooth to bond properly with the layer of material to be placed thereon, it shall be moistened and worked with a harrow, scarifier, or other suitable equipment, in an approved manner and to a sufficient depth to provide a satisfactory bonding surface, before the succeeding layer of material is placed.

If, in the opinion of the Engineer, the surface of the prepared foundation, or the rolled surface of any layer of the fill is too wet for proper compaction of the layer of fill material to be placed thereon, it shall be removed and allowed to dry, or worked with harrow, disc, or other suitable equipment, to reduce the moisture content to the required amount; then it shall be recompacted before the succeeding layer of fill is placed thereon.

Ruts in the surface of any layer shall be graded level and recompacted to the approval of the Engineer.

Any and all materials not approved as fill which accumulate on the surface of any layer or prepared foundation, shall be removed by the Contractor before placing the succeeding layer.

Final acceptance of the fill material will only be made after the material has been placed, spread and compacted in place. Rejection by the Engineer of fill material may be made in the borrow area, in the transporting vehicle, or in place. The Contractor shall co-operate with the Engineer to ensure that only acceptable fill material will be hauled from the borrow area to the work.

Particular care shall be taken to ensure that the compaction requirements are satisfied in areas of fill adjacent to any structure. Compaction adjacent to the structures shall be carried out carefully and thoroughly utilizing approved power tampers where necessary to ensure that the material is tightly compacted at the boundaries of the structure. The thickness of these fill layers compacted by power tampers shall not exceed four inches before compaction. No cobbles or pebbles large than two inches in size will be permitted in the fill material within one foot of structures. Fill shall be placed and compacted against the structures only during daylight hours, unless adequate lighting is provided to the satisfaction of the Engineer.

Page 29 EGM-2013-00163

#### Placing and Compacting (cont'd.) 2-06(q)

Any layer or layers which, in the opinion of the Engineer, have suffered a reduction in density after compaction due to the action of frost, rain or for any other reason, shall be removed by the Contractor at no additional compensation, before placing operations are resumed.

Fill shall not be placed in a frozen condition and shall not be placed on a surface which is frozen or on which there is any snow or ice. Placing of fill in freezing weather shall not be permitted except when approved by the Engineer, and when proper measures are taken to prevent freezing of the material.

No separate payment will be made for compaction, or work entailed to adjust the moisture content or removal and disposal of materials rejected after being placed on the dike. All openings through the dike for construction purposes shall be subject to the Engineer's approval. The slope of openings left through dikes and at the end of any unfinished section shall not be steeper than four horizontal to one vertical.

Overbuilding or underbuilding shall be remedied at the Contractor's expense to the satisfaction of the Engineer.

2-06 (h)

#### Measurement and Payment for "Select Impervious and Common Fill"

The unit price tendered for "Select Impervious and Common Fill" shall include all costs to complete the work described in this Section 2-06, and as detailed elsewhere in the Tender Documents. A free-haul distance of 2500 feet is to be included in the tender price for the Item "Select Impervious and Common Fill".

The unit of measure is the cubic yard and is the volume measured in place on the dike by cross-sectioning before and after the placement and compaction of the fill.

All measurements for payment purposes shall be carried out by a combined survey crew as laid out in paragraph 2-08. Measurement will be made to the theoretical neat lines where a zone is built to or beyond the theoretical neat line. Measurement will be made to the actual surface where the surface of a zone is not built out to the theoretical neat line.

An overhaul unit price for hauling beyond the 2500 feet freeboard limit is to be tendered under the Item "Overhaul -Select Impervious and Common Fill". The tendered price is to include for all additional costs incurred for the haul and

2-06 (h)

# h) <u>Measurement and Payment for "Select Impervious and Common Fill</u> (cont'd)

return of haulage vehicles. The unit of measure is the cubic yard-station. This unit is the product of the volume of materials moved and the distance beyond the free-haul limit measured in one direction in stations.One station is one hundred feet.

Payment for all work carried out under this Section and completed in all respects will be the product of the volume measured and the unit price tendered for "Select Impervious and Common Fill".

#### 2-06 (i) Measurement and Payment for Unsuitable Materials

The unit price tendered for "Unsuitable Materials" shall include all costs to complete the work as described in this Section and as detailed elsewhere in the Tender Documents. No overhaul will be paid on this item.

The unit of measure is the cubic yard and the volume for payment purposes is measured by cross-sectioning the area to be excavated before removal and after removal.

Only material designated as "Unsuitable Material" by the Engineer and removed and disposed to his satisfaction will be paid for.

All measurements for payment purposes shall be carried out by a Combined Survey Crew as laid out in paragraph 2-08.

#### 2-07 DECANT OUTLET

#### 2-07 (a) Scope of the Work

The Contractor shall remove the existing wood flume; purchase, have delivered and handle the pipe; haul, place, and compact bedding and backfill material; install and connect the pipe; backfill and compact and carry out all other works necessary to extend the east decant culvert. The cost of all labour, materials, plant, equipment, fuel and other items necessary shall be included in the unit price tendered for "Decant Outlet" in the Schedule of Quantities and Unit Prices.

The Owner will arrange to divert the flow through the emergency decant during the period of alterations to the east decant. The Owner will connect the wood flume to the finished culvert.

The Contractor is to co-operate with the Owner's forces and to keep the work necessary to rebuild the flume to a minimum.

#### 2-07 (b) Materials

The decant pipe shall be  $24^{\prime\prime}$  diameter, 12 gauge, standard 2 oz.galvanized corrugated (2  $2/3^{\prime\prime} \times 1/2^{\prime\prime}$ ) pipe. Connections shall be by bands supplied and installed to the instructions of the manufacturer.

the

The bedding and backfill material shall be a clean coarse sand with a maximum size of 3/4". Not more than 15% by weight shall pass the No. 200 U.S. Standard sieve.

#### 2-07 (c) Installation

The culvert shall be installed to the manufacturers recommendations. A bed of sand 18" thick shall be laid and compacted in layers not exceeding 4" thick, each layer being tamped to 95% of maximum density as established by ASTM D698. A bed shaped to the outside of the pipe and sloped to the correct grade shall be scraped from this bed to a depth of 6". The pipe shall be laid in this trench, connected to the existing pipe, and backfill placed on each side of the pipe in 4" layers and tamped to 95% of maximum density. The backfill shall be continued in this manner until 18" has been placed on top of the pipe. Care shall be taken to save the culvert from damage by the passage of vehicles.

The tamper shall be as specified in paragraph 2-05 (e).

2-07 (d) Measurement and Payment of "Decant Outlet"

The unit price tendered for "Decant Outlet" shall include all costs to cover the work as described in this Section and as detailed elsewhere in the Tender Documents.


The payment for the work shall be the product of the length of culvert installed from centre of joint to end and the unit price tendered in the Schedule of Measurement and Unit Prices.

2-08

#### COMBINED SURVEY CREW

Survey control, layout and measurements of all work performed are to be carried out by a combined Survey Crew supplied by the Owner and under the jurisdiction of the Engineer. The Contractor shall assign one or more members of his staff to serve on the crew at the expense of the Contractor. The representative supplied by the Contractor to the survey crew shall satisfy the Contractor as to the accuracy of the survey work. In case of conflict over measurements the Engineer and the Contractor shall exhaust all means of arriving at a satisfactory agreement before applying the arbitration clause referred to in the General Conditions.

The Contractor shall employ a grade foreman to bring up slope stakes and to ensure the work is kept to the correct  $s_2$  lopes. EGM-2013-00163



# **Golder Brawner Associates**

CONSULTING GEOTECHNICAL ENGINEERS

H. O. GOLDER C. O. BRAWNER V. MILLIGAN J. L. SEYCHUK N. R. McGAMMON R. M. WILSON D. B. CAMPBELL A. A. GASS D. L. PENTZ H. G. GILCHRIST

REPORT TO COMINCO LTD. ON SITE INVESTIGATION AT EXISTING H.B. MINES TAILINGS POND

SALMO

B.C.

Distribution:

4 copies - Cominco Ltd. Trail, British Columbia
2 copies - Golder Brawner & Associates Ltd. Vancouver, British Columbia

January, 1974

V 73218



# **Golder Brawner Associates**

CONSULTING GEOTECHNICAL ENGINEERS

H. Q. GOLDER C. O. BRAWNER V. MILLIGAN J. L. SEYCHUK N. R. McCAMMON R. M. WILSON D. B. CAMPBELL A. A. GASS D. L. PENTZ H. G. GILCHRIST

January 2, 1974

Cominco Ltd., Engineering Dept., Trail, B.C.

ATTENTION: Mr. D. Boyle

Re: Site Investigation at Existing H.B. Mines Tailings Pond, Salmo, B.C.

Dear Sir:

As requested by your Purchase Order No. HB 15017 dated October 26, 1973, and in accordance with our proposal of September 20, 1973, we have carried out a detailed drilling program at the above site. The purpose of this investigation was to determine the condition of the existing dyke and foundation soils to enable a detailed stability analysis to be carried out. This report is further to our report No. V 72109 of June, 1973.

#### FIELD INVESTIGATION

Three boreholes were drilled at the site between October 29, 1973 and November 1, 1973 using a truck-mounted rotary drill rig. These boreholes were drilled to depths varying from 45 to 85 ft. and extended approximately 20 ft. into bedrock. One borehole was drilled from the crest and two boreholes from the lower slope of the existing tailings dyke as shown on Fig. 1. Standard split spoon samples were obtained of the overburden and wash samples of drill cuttings were obtained of the bedrock. All samples were identified in the field and returned to our laboratory for classification and testing.

Perforated plastic standpipes were installed in the open boreholes to enable groundwater levels to be monitored.

#### SITE CONDITIONS

The existing tailings pond is located approximately 4 miles south of Salmo, B.C. The tailings lyke is located at the southern end of a valley and has been constructed 50 to 60 ft. high using borrow fill obtained from the abutment slopes. Contours of the downstream face of the dyke together with a typical cross section are shown on Fig. 1.

The borehole results indicate that the dyke is generally comprised of soft to firm brown sandy silt containing varying amounts of medium to coarse sand and fine gravel. Standard penetration test results gave average 'N' values of the order of 10 blows/ft. indicating a loose to compact state of relative density.

Examination of the overburden samples enabled an approximate estimate of the location of original ground surface beneath the dyke fill. The approximate location of the existing ground surface is shown on Fig. 2. In borehole 1, the natural ground surface was estimated to be located approximately 59 ft. below the crest of the dyke. Underlying the fill, a 4 ft. thick stratum of very dense silty till was identified overlying a 5 ft. thick layer of hard desiccated silt. Bedrock was encountered at approximately 68 ft. below the crest of the dyke.

In borehole 2, the original ground surface was estimated as being located approximately 27 ft. below the dyke fill surface. The boreholes en-

## GOLDER, BRAWNER & ASSOCIATES

Page 36 EGM-2013-00163 countered a 7 ft. thick stratum of soft to firm silt beneath the fill. Underlying the silt, a 2 ft. thick layer of sand and gravel was identified overlying bedrock.

In borehole 3, the original ground surface was estimated to be located approximately 20 ft. below the fill. The borehole encountered a 3 ft. thick stratum of dense silty till beneath the dyke fill. Underlying the silt, a 3 ft. thick layer of sand and gravel was identified overlying bedrock.

More detailed descriptions of the soil conditions are given on the Record of Boreholes. A cross section showing the inferred soil stratigraphy is shown on Fig. 2.

## GROUNDWATER CONDITIONS

The standpipes installed in the boreholes were monitored for approximately 4 weeks after installation to enable the water levels to stabilize. From the recorded water levels, we have inferred the phreatic surface in the dyke to be located as shown on Figure 2.

Inspection of the dam during the period of the drilling program indicated that seepage was occurring near the toe of the upper slope of the dam and at each abutment. Soft saturated soil was observed at several locations in the middle slope of the dam and very soft saturated soil was encountered at the east abutment.

This seepage and degree of saturation was not observed at the time of the original site investigation in May 1972. The occurrance of seepage above the phreatic line as inferred from the standpipe levels is believed to be caused by local variations in the permeability of the dam material. The location of the phreatic line is gapected to vary somewhat across the dam.

# GOLDER, BRAWNER & ASSOCIATES

Page 37 EGM-2013-00163

## DYKE STABILITY

The investigation has indicated that the existing dyke has been constructed essentially with silty soils which have been placed in a loose condition. The design parameters used in our previous calculations are considered to be still applicable although the phreatic surface assumed in our original report appears to have been somewhat lower than now exists. This present condition may be a result of a change in ponded water level upstream. Stability calculations for the present condition indicate a safety factor against a shearing type failure of the order of 1.3 which is considered adequate.

It is understood that it is proposed to eventually raise the pond water level to a maximum elevation of 2502 ft. behind the existing dam. As the pond water level is raised, the phreatic surface will also rise. Stability calculations for these future conditions indicate a factor of safety against a shearing type failure of the order of 1.1 which is lower than is normally acceptable. To increase the dyke stability, it is recommended that a berm be constructed on the downstream section of the dam as shown on Fig. 3. Provision of this berm will increase the factor of safety to approximately 1.3 which is adequate.

## SEEPAGE

At present, seepage is occurring at the intersection of the upper and middle slope of the dyke and at the abutments. Examination of this seepage during the drilling program indicated that the flow was clear and did not appear to be carrying any soil particles. However, the dyke is essentially homogeneous and has been constructed with silty soils which are most susceptible to internal backward erosion. The potential for this type of erosion will increase as the ponded water level is raised. To provide protection against internal backward

## GOLDER, BRAWNER & ASSOCIATES

Page 38 EGM-2013-00163

5.

erosion, filter material should be placed on the downstream slope of the dyke. This can be accomplished by constructing the previously recommended stability berm (Figure 3) of a suitable filter material which satisfies the gradation requirements shown on Figure 4. It is possible that mine waste rock will be suitable.

The berm should be adequately compacted to provide the required strength for support of possible future dyke extensions, yet should not be over-compacted so as to reduce its permeability. Generally, if heavy equipment is available and if the gradation of the filter material tends to be towards the coarser fraction of the range shown on Figure 4, satisfactory compaction without excessive reduction in permeability will be achieved by spreading the material in 16 in. lifts using a heavy crawler tractor.

We would be pleased to provide more specific construction details when the gradation of material and type of construction equipment are known.

To accommodate the scepage at the abutment, a filter blanket should be placed at these locations as shown on Fig. 3. This blanket should consist of similar filter material to that described above and should have a minimum thickness of 2 ft. This filter material should also be placed as described above.

It is pointed out that the specification given above for the filter material is critical if the filter blanket is to perform satisfactorily. As a result, we recommend, that when potential sources of material have been established, that we review the suitability of the material. In addition during raising of the ponded water level to elevation 2502, we recommend that the dyke be inspected by a member of our staff to ensure that the filter blanket is performing as desired.

GOLDER, BRAWNED & ASSOCIATES

Page 39 EGM-2013-00163 At the time of the drilling, examination of the upper face of the dyke indicated that some surface erosion had occurred due to water ponding on the crest of the dyke and flowing downstream. It is recommended that these slopes be renovated by using granular material. In addition some surface grading should be carried out on the crest of the dyke to prevent ponding of rain water. During this work the crest could be sloped inwards towards the pond in order to direct run-off in that direction.

## FUTURE DYKE EXTENSION

If the height of the existing dyke and pond level are increased in the future to elevations 2511 ft. and 2508 ft. respectively, the crest of the dyke should be raised by placing additional fill on the crest and on the downstream slope. In addition, the filter material recommended above should be extended as shown on Fig. 5 to a maximum elevation of 2500 ft. The additional filter material should be placed as previously recommended while the fill material should be placed in horizontal lifts of 12 inch maximum and compacted to at least 95 per cent of Standard Proctor Density.

We trust that this is the information you require. We would be pleased to discuss the report in more detail should you desire.

> Yours very truly, COLDER BRAWNER & ASSOCIATES LTD.

.M. Wilson, P.Eng.


Stelly

H.H. Hawson, P.H

RIW/1000/sm V73218

Page 40 EGM-2013-00163

GOLDER, BRAWNER & ASSOCIATES



AND	FLINUL	LUNIN	ESOURCES
Rec'd	IUN	6 19	776
	0.014	0 10	
			1

# SPECIFICATIONS

Section	1	-	General Provisions
Section	2	4	Miscellaneous Works
Section	3	-	Structures
Section	4	-	Drainage Pipe
Section	5	ū.	Block Existing Decants

GRIT 1636

#### SPECIFICATION

#### SECTION 1

## GENERAL PROVISIONS

## 1-01 LOCATION

The site of the H.B. Mine Tailing Dam is located four and one half miles south of Salmo, B.C., one half mile south of Sheep Creek and about one mile east of Provincial Highway No. 3.

#### 1-02 ACCESS TO SITE

Access to the site is by two lane gravel public road towards the Canex Mine from Highway No. 3 immediately south of Sheep Creek. An unimproved single lane bush road starting three quarters of a mile north of Highway No. 3 leads one mile south to the tailing dike.

## 1-03 SCOPE OF THE WORK

Except as otherwise specified, the work described in this specification comprises the furnishing of labour, materials, transportation, tools, equipment, supplies, supervision, and all other things necessary for the construction of the H.B. Mine Tailing. Dam Spillway.

The works are broken down generally into the following sections and reference is made to the appropriate section for details.

- 1. Build a cofferdam around the new spillway structure (Section 2)
- 2. Realign the access road (Section 2)
- Excavate inside the cofferdam for the spillway structure, construct and backfill the structure (Section 3).
- 4. Excavate for the manhole, construct and backfill (Section 3).
- 5. Excavate for the culvert, construct and backfill (Section 4).
- 6. Remove the cofferdam (Section 2).
- 7. Plug the existing decants (Section 5).

## 1-04 STORAGE

The Contractor shall, to the approval of the Engineer, erect within his working areas, buildings and other facilities necessary for the safe storage of materials and equipment

#### GENERAL PROVISIONS

#### 1-05 CONTRACTOR'S CAMP

Contractor shall be responsible for supplying his own accommodation.

#### 1-06 UTILITIES

The Contractor shall, to the approval of the Engineer, make all necessary arrangements for the supply of water needed for all purposes at the site.

The Contractor shall be responsible for the provision of all necessary lighting and power for the works.

#### 1-07 COMMUNICATIONS

The Contractor shall be responsible for providing his own communication.

## 1-08 SEWAGE DISPOSAL AND SANITATION

The Contractor shall, to the approval of the Engineer, provide and maintain adequate toilet facilities at the site and no pollution shall result from these installations.

#### 1-09 FIRE PRECAUTIONS

The Contractor shall provide all necessary precautions against fire and shall rigidly comply with all laws, rules and regulations relating thereto.

In the event of fire the Contractor will be required to fight the fire to the full limit of his available manpower and equipment,

#### 1-10 DECANT WATER

The Contractor is advised that water from the tailing pond is decanted beneath the dike. It shall be the responsibility of the Contractor to select a method of construction that will in no way impair the current rate of discharge until the final diversion is made through the new works.

## 1-11 ESCAPE OF TAILING FROM TAILING POND

The Contractor is advised of the potential danger of an escape of Eluid tailing through the works under construction and all efforts are to be exerted to obviate such an occurrence.

## 1-12 AVAILABILITY OF BUILDING MATERIALS

It is proposed to use impervious soil from the existing borrow pit at the east abutment and granular soils will come from the existing borrow pit located approximately one quarter mile east of the turn-off to the dam on the Canex Road.

## 1-13 SURVEYS

A control survey and a benchmark in the site area will be provided by Cominco Ltd. Layout work, batterboards, slope stakes etc. will be the responsibility of the Contractor.

Where a cross-section for payment purposes is required, a combined crew of Owner's and Contractor's personnel shall be used. The Contractor shall provide 24 hours notice to the Engineer for such surveys.

## 1-14 ACCESS AND HAUL ROADS

The Contractor will have free use of the access and haul roads around the site area. It will be his responsibility to maintain the roads and leave them in their original condition.

Particular care shall be taken to keep open all drainage ditches and culverts.

The passage of vehicles across the top of the dam when the surface is damp, thereby causing ruts, is to be avoided. Any ruts created shall be graded over immediately to shed surface water.

Additional access or haul roads that the Contractor may require shall be constructed by the Contractor at no expense to the Owner after approval by the Engineer. The area shall be maintained in a neatly graded to drain condition

#### 1-15 DISTURBANCE OF THE EXISTING DAM

Any disturbance of any part of the existing dam structure and surroundings by the Contractor shall be repaired to the original specifications at no cost to the Owner.

## 1-16 DEWATERING

All construction work shall be carried out in dry ground conditions and the Contractor shall supply, install, operate and maintain necessary pumping equipment at no cost to the Owner.

ACY: L

22.

#### GENERAL PROVISIONS

## 1-17 EXCAVATION - COMMON

The excavation for structures and drainage pipe shall be kept to a minimum width compatible with the use of power compaction equipment.

The trench shall be dug so that the pipe can be laid to the alignment and depth required, and it shall be excavated only so far in advance of the pipe laying as safety, weather conditions, and traffic requirements permit. The trench shall be so braced and drained that the workmen may work therein safely and efficiently. The discharge of the trench dewatering pumps shall be conducted to natural drainage channels or drainage pipes.

The width of the trench at the bottom shall be such as to permit the pipe to be laid and jointed properly and backfill to be placed and compacted properly. Trenches shall be of such extra width, when required, as will permit for convenient placing of timber supports, sheeting and bracing, and handling of specials.

When the bottom of a trench is found to be unstable or unsuitable below the depth of normal bedding, the Contractor shall excavate and remove such material to the width and depth required to establish a firm, stable base. The subgrade shall be replaced by backfilling with granular material as specified. This material shall be compacted in 3-inch layers by hand or mechanical equipment to provide thoroughly consolidated pipe base.

Additional compensation shall be allowed for this work when, in the opinion of the Engineer, it is necessitated by the existence of unsatisfactory soil conditions. No compensation will be allowed when these conditions have resulted from the acts, neglects, or delays on the part of the Contractor or when working in a trench excavated in rock.

During compacting operations care must be taken to backfill equally on each side of the pipe or structure to prevent movement or warping.

Compaction must be carried out to either the spring-line or original ground level, whichever is higher.

The cost of borrowing, hauling, backfilling and compaction is to be included in the specific structure or drain pipe pay item and no extra payment will be considered.

The cost of common excavation and shoring is to be included in the specific structure or drain pipe item and no extra payment will be considered except as indicated above.

#### GENERAL PROVISIONS

## 1-18 EXCAVATION - ROCK

No blasting is allowed in the vicinity of the dam. All rock excavation must be carried out by jackhammer or wedging and barring.

The only rock excavation contemplated is at the foundation to the spillway structure. This will be to provide a level base on sound rock as judged by the Engineer. Measurement will be by the cubic yard as determined by surveyed cross-sections, and the cost to the Owner shall be at the price stipulated in the Schedule of Prices.

Boulders larger than 1 cubic yard in volume, if encountered, will be paid by the same method.

Additional rock excavation encountered elsewhere in the trenching or manhole will be treated as Extra Work.

## 1-19 EARTH FILLS

The Contractor is hereby cautioned that the earth fills forming the present tailing dam have been carefully laid using specified grain sizes, slopes, water contents and compaction.

Excavation through the dike will require similar material to be replaced. If the material removed is too wet to achieve the required compaction, it will have to be replaced with dry material.

#### Scope of Work

The work shall include the supply of all labour, material and plant, fuel and the performance of all work necessary to prepare and maintain borrow areas and haul roads, rip, excavate, load, transport, dump spread and compact fill material used as backfill in the various parts of the works.

#### Fill Material

Select impervious fill shall be a glacial till, well graded with a maximum size of 6 inches and with at least 20% finer than the No. 200 U.S. Standard sieve size.

Common fill shall be a glacial till, well graded with a maximum size of 6 inches.

Both select impervious fill and common fill must be of a gradation and moisture content that allows them to be placed and adequately compacted as specified herein.

## 1-19 EARTH FILLS (continued)

## Fill Material (cont'd)

Filter material or granular material shall be a well graded clean sand and gravel with not more than 15% passing a No. 200 sieve.

Cobbles and boulders larger than 6" shall be removed from the fill.

The minimum thickness of bedding shall be eight (8) inches. Bedding material for the drainage pipe where it passes through the impervious zone of the drain shall be of impervious material.

Bedding material for the remainder of the length of drainage pipe shall be granular material as specified above.

No bedding or backfill against the pipe shall be larger than 3/4" in size.

All fill shall be free of organic materials, roots, and other perishable materials. No fill material shall contain ice or snow, or shall be placed in a frozen condition.

#### Compaction

Backfill in trenches or around structures shall be placed in layers not exceeding 6" in thickness when loose.

Backfill other than in trenches or around structures shall be placed in layers not exceeding 9" in thickness when loose.

Compaction in all cases shall be not less than 95% of the laboratory maximum dry density as determined by the Proctor Compaction test as specified in ASTM D698.

If the impervious fill material is too dry or too wet, water shall be added or removed by working the fill with a harrow, scarifier or other approved equipment until the water is uniformly distributed and satisfies the requirements of these specifications.

Particular care shall be taken to ensure that the compaction requirements are satisfied in areas of fill adjacent to any structure. Compaction adjacent to the structures shall be carried out carefully and thoroughly utilizing approved power tampers where necessary to ensure that the material is tightly compacted at the boundaries of the structure. Fill shall be placed and compacted against the structures only during daylight hours, unless adequate lighting is provided to the satisfaction of the Engineer.

#### 1-19 EARTH FILLS (continued)

#### Compaction

Any layer or layers which, in the opinion of the Engineer, have suffered a reduction in density after compaction due to the action of frost, rain or for any other reason, shall be removed by the Contractor at no additional compensation, before placing operations are resumed.

Fill shall not be placed in a frozen condition and shall not be placed on a surface which is frozen or on which there is any snow or ice. Placing of fill in freezing weather shall not be permitted except when approved by the Engineer, and when proper measures are taken to prevent freezing of the material.

#### Borrow Areas

The Contractor shall conduct his operations in borrow areas in such a manner which shall ensure that the maximum possible volume of suitable construction material may be obtained. Measures shall be taken to ensure adequate drainage of water from the borrow areas so that the borrow material is obtained at a water content suitable for compaction and so that the borrow operations are not affected adversely. Ponding of water shall be prevented.

Some of the material in the borrow areas may be frozen. The Contractor shall conduct his operations in such a manner to ensure that the frozen material shall be thawed prior to placement in the dikes. To meet this requirement the Contractor shall open and work as large an area of the borrow area as practical, and shall rip, scarify, disc, harrow or use any other similar means to expose the frozen material to permit thawing.

The detailed planning of the operation of the borrow area shall be the responsibility of the Contractor and shall be subject to the approval of the Engineer.

Unsuitable material shall be disposed of as directed by the Engineer and graded off to present a reasonably uniform appearance.

The Contractor shall be responsible at all times for the safe operation of the borrow area. All slopes left permanently exposed shall be approved by the Engineer.

## 1-20 CLEARING

The work to be done under this clause shall comprise the supply of all labour, material and plant and the performance of all work necessary for clearing of the site as shown on the drawings, as required by the Engineer and as specified herein.

Clearing shall consist of cutting and disposing of all trees, shrubs, brush, debris and all other perishable materials, including fallen trees and logs within the areas to be cleared.

All trees, shrubs and brush shall be cut to within 2" above the ground surface. The organic cover of topsoil on the ground surface shall be left intact, except where excavation is required as stated in these documents.

All vegetation and debris resulting from clearing operations regardless of size, shall be removed from the areas cleared, and shall be disposed of by the following methods, upon written approval of the Engineer.

- (a) Combustible materials may be piled and burned on open fires as specified herein. Material to be disposed of in this way shall be completely burned so that it is all reduced to ashes.
- (b) Materials obtained from clearing which cannot be burned may be placed in nearby disposal areas as directed by the Engineer. The material placed in disposal areas shall be crushed with a tractor or other heavy equipment to a thickness of not more than 5 feet.

The Contractor shall be responsible for any damage done by fire resulting from the work under this item and shall at no time leave a fire unattended until it is fully extinguished. All burning shall be done in strict conformance with the rules and regulations of local, provincial, and federal agencies and it shall be the responsibility of Contractor to obtain all burning permits.

Sufficient equipment shall be ready and available together with a sufficient force of men to control burning operations at any time.

There will be no separate payment for clearing and the cost of clearing is to be included in the price of installation of the drainage pipe.

#### GENERAL PROVISIONS

#### 1-21 CONCRETE

All concrete work shall conform to the standards specified in the current edition of CSA A23.1 "Concrete Materials and Methods of Concrete Construction".

Concrete shall be supplied by a ready-mix concrete company which is satisfactory to the Engineer. Otherwise the proposed method of production and the mix design shall be submitted to the Engineer for approval.

Care shall be taken to avoid excessive mix time due to the remoteness of the site.

Concrete aggregate shall have a maximum size of 3/4".

The required strength of concrete is specified in the appropriate section.

#### 1-22 CONCRETE FILL

The work in this paragraph shall conform to all conditions specified in paragraph 1-21, except that the maximum size of aggregate shall be 1-1/2".

Payment for this item shall include for all costs to supply, deliver and place the concrete.

Measurement of the volume placed shall be calculated from cross-sections.

Payment will be at the contract unit price stated in the Schedule of Prices.

## 1-23 DRAINAGE PIPE

The drainage pipe shall be corrugated steel pipe to Specification No. 501-74 of the Corrugated Steel Pipe Institute.

The size shall be 36 inch diameter, 12 gauge (0.109") galvanized with 2 oz. zinc per square foot,  $2-2/3" \ge 1/2"$  corrugations, Helcor Lokseam construction with a neoprene cord seal. The ends shall be end-rolled (Armco or similar) to accept corrugated bands.

Coupling shall be 2 piece corrugated bands with angles 24" width, neoprene gaskets 12" wide by 1/4" thick shall be installed between the coupling and the culvert. A heavy bead of caulking compound, specified below, shall be applied to the culvert side of the neoprene gasket.

The caulking compound shall be thiocaulk (polysulphide-architectural grade) by Steelcote Manufacturing Ltd., and shall be applied in accordance with their specifications.

Rev. 2

## GENERAL PROVISIONS

#### 1-24 MISCELLANEOUS METALWORK

The Contractor is to detail, fabricate, deliver, install and paint all steelwork shown on the drawings.

Steelwork embedded in concrete shall be unpainted.

The finish for all other metals is as follows:

Blastclean all surfaces to SSPC-SP6 Commercial Blast Degree

Prime coat - 1 coat of Bapco Ethyl Silicate Zinc Rich Primer, at the rate of 315 square feet per gallon to produce a dry film thickness of 2.5 mils.

Finish coats - for parts submerged or inside the structures:

2 coats of grey Bapco Arocoat High Build at 115 square feet per gallon (10 mil dry film thickness per coat).

- for other parts:

2 coats of grey Bapco Paralite Enamel High Build at 160 square feet/gallon (4 mils dry thickness per coat).

The cost of work carried out in this paragraph is to be included in the cost of the structures and no separate payment will be made.

### 1-25 ADDITIONAL DRAINAGE PIPE

In the event that it is necessary to increase by a small amount the length of the 36" diameter drainage pipe, payment shall be made for the supply, delivery and installation at the Contract Unit Price stated in the Schedule of Prices.

Excavation, backfill and compaction required for the additional drainage pipe shall be paid for at the Contract Unit Price stated in the Schedule of Prices.

The measurement shall be established from cross-sections taken at the discharge end of the drainage pipe.

100

#### SPECIFICATION

#### SECTION 2

#### MISCELLANEOUS WORKS

#### 2-01 SCOPE

The work included in this section includes the installation and removal of the cofferdam, realignment of the access road, relocation of the 8" diameter culvert.

#### 2-02 GENERAL ARRANGEMENTS

All excavation, placement of fill and other construction work shall be completed to the lines and grades as shown on the drawings or as directed by the Engineer.

#### 2-03 COFFERDAM

The Contractor shall build and remove on the completion of construction of the complete spillway facilities a cofferdam as shown on the drawings and as described herein.

Alternative designs of the cofferdam will be considered by the Engineer, but the Contractor must obtain approval in writing from the Engineer before starting construction of any alternative arrangement.

The Contractor will be held fully responsible to construct and maintain the effectiveness of the cofferdam.

The cofferdam shall have a minimum top width of twelve (12) feet with side slopes of 2:1 and a minimum freeboard of three feet above the current pond water level shall be maintained.

Foundation preparation for the construction of the cofferdam shall consist of the systematic squeezing out of tailings by the placement of the impervious soil.

The cofferdam shall be constructed of impervious soil, compacted, as described in Clause 1-19, to achieve a watertight structure.

After the completion of the spillway and drainage pipe and after returning the dike to its original condition and before blocking the existing decant systems, the cofferdam shall be removed in entirety, and the excavated material placed neatly in a local disposal area as designated by the Engineer.

41 .

## 2-03 COFFERDAM (continued)

Payment for the cofferdam shall be the lump sum stated in the Schedule of Prices and shall include all work necessary to construct, maintain, dewater and remove the cofferdam and to realign the access road and relocate the culvert.

## 2-04 REALIGNMENT OF THE ACCESS ROAD

The access road is to be moved about 10 feet to the east to bypass the new spillway structure to maintain access onto the top of the dam.

The material to be used shall be common earth compacted as specified in Section 1-19.

The present culvert beneath the road will also have to be moved to accommodate the 10 foot realignment.

There is no separate payment for the realignment of the road and the cost is to be included in the cost of the cofferdam.

42 .

#### SPECIFICATIONS

#### SECTION 3

#### STRUCTURES

## 3-01 SCOPE

The work included in this section includes the common excavation, drilling for and installation of rock anchors, construction and removal of all temporary works, supply and installation and vibration of all concrete to the strengths as specified, testing of cylinders, supply and installation of all embedded and nonembedded metal work, painting of metalwork, supply and installation of precast concrete members, concrete curing and backfilling to provide a completed structure as shown on the drawings.

#### 3-02 SPILLWAY STRUCTURE

The structure shall be constructed as shown on the drawings and to the standards specified in paragraph 1-21.

Particular care shall be taken with the alignment of the stop-log guide and the accuracy of forming the pre-cast stoplogs to provide an accurate fit.

The strength of concrete shall be 3,000 p.si. at 28 days.

The structure shall be founded on sound bedrock. Payment for excavation to bedrock is included in this pay item.

Rock excavation will be paid for at the "Rock Excavation" contract unit price per cubic yard as explained in paragraph 1-18.

Fill concrete to elevation 2511.5 will be paid for at the "Concrete" <u>Rev.</u> Fill" contract unit price as explained in paragraph 1-22.

The strength of the concrete fill shall be 2,000 p.s.i. at 28 days.

The cost of all other work necessary to complete the spillway structure is to be included in the sum stated for "spillway structure" in the Schedule of Prices.

#### 3-03 MANHOLE

The structure shall be constructed as shown on the drawings and to the standards specified in paragraph 1-21.

The strength of concrete shall be 3,000 p.s.i. at 28 days.

Payment shall be the sum stated for "manhole" in the Schedule of Prices".

#### SPECIFICATION

## SECTION 4

#### DRAINAGE PIPE

## 4-01 SCOPE

The work included in this section is supply, delivery and installation of the drainage pipe, clearing, excavation, showing, dewatering, supply and placement of bedding, backfill, compaction and all other operations necessary to complete the works as indicated on the drawings.

#### 4-02 REFERENCES

The drainage pipe and connections shall be as specified in paragraph 1-23.

Excavation is covered in paragraph 1-17 and backfill in paragraph 1-19.

#### 4-03 GENERAL

The pipe shall be laid to the grades shown on the drawings.

Care shall be exercised to avoid damage to the pipe in handling and placing and damaged galvanizing shall be repaired to the Engineer's satisfaction.

#### 4-04 PRESSURE TEST

The Contractor's attention is drawn to the fact all joints must be watertight, particularly between the spillway structure and the manhole.

A pressure test shall be conducted on the spillway to manhole section before backfilling, to ensure the watertightness of the system.

No pipe installation will be accepted until the leakage is less than the number of gallons per hour as determined by the formula:

 $L = \frac{ND \times \text{the square root of P}}{1850}$ 

in which L = the allowable leakage in U.S. gallons an hour

N = the number of joints in the test section

D = the nominal diameter of the pipe in inches

P = 10 p.s.1.

44 .

## 4-04 PRESSURE TEST - continued

Leakage is defined as the quantity of water which must be added to the test section to maintain the specified test pressure after the pipe has been filled with water and the air expelled.

Should any test disclose leakage greater than that specified above, the Contractor shall, at his own expense, locate and repair the defect.

## 4-05 SEEPAGE CUT-OFF RING

An annular ring 48" in diameter x 1/4" thick shall be welded around the culvert to provide a seepage cut-off. It shall be located in the centre of the impervious zone.

All metal must be painted as specified in paragraph 1-24.

## 4-06 PAYMENT

Payment for work carried out under this section will be paid for at the contract stipulated sum in the Schedule of Prices.

#### SPECIFICATIONS

新生产中学生的主义。这些中学生的中学生的中学生。

## SECTION 5

#### BLOCK EXISTING DECANTS

The Contractor is to supply all labour, equipment and supplies to block off the east and west decants.

The decants consist of built-up wooden towers about 50 feet high extending down from the water surface to the original ground level.

A 24" diameter culvert connects from the base of each decant tower and exits from the fill at the downstream toe of the dam.

After the spillway and drainage pipe are completed and backfilled and the cofferdam removed, it is necessary to permanently plug off both decants.

This is most easily achieved by blocking off the culverts near the base of the tower and pumping the culverts full of concrete.

A suggested method of operation will be to raise the top of the decants until they are clear of the water thereby considerably reducing the flow down the tower.

By lowering burlap bags filled with dry mix to the bottom of the tower, a plug will be formed. The tower will gradually fill with seepage water and the pond water will escape through the new spillway structure.


Depending on the degree of blockage attained, it may be necessary to add additional bags of dry concrete.


When an effective seal has been accomplished, it will be necessary to fill the culverts with 2,000 p.s.i. concrete.


By welding a plate with a threaded nipple to the end of the culvert, a concrete pump can be connected and the culvert pumped full of grout.

Alternative methods of blocking the culverts will be considered but must receive written approval of the Engineer before the work is commenced.


Payment for the above work will be at the Contract Unit Price stated in the Schedule of Prices.









Page 61 EGM-2013-00163







Page 63 EGM-2013-00163



Page 64 EGM-2013-00163




Page 65 EGM-2013-00163




Page 66

EGM-2013-00163




Page 67

EGM-2013-00163




-- 0....


Page 68



FOR	1 004		04	20
EGI	<b>Л-201</b>	13-0	01	63




Page 70 EGM-2013-00163




Page 71


EGM-2013-00163




Page 72 EGM-2013-00163



Page 73



Page 74 EGM-2013-00163



#### Page 75 EGM-2013-00163

GROAT RECORD OF BOREHOLE 2 See Figure / BORING DATE NOVEMBER 1, 1973 DATUM TAKEN FROM COMINCO DRAWING NO. HB: 285 P I.OCATION BOREHOLE TYPE ROTARY TRICONE BOREHOLE DIAMETER 4 W. PEN. TEST HAMMER WEIGHT LB. DROP SAMPLER HAMMER WEIGHT MO LB. DROP 30 INCHES INCHES COEFFICIENT OF PERMEABILITY K, SCALE DYNAMIC PENETRATION RESISTANCE SOIL PROFILE SAMPLES ADDITIONAL LAB. TESTING BLOWS/FT -----CM. / SEC. BLOWS / FT. STRAT PLOT ELEVATION NUMBER 1 TYPE LEVN STANDPIPE WATER CONTENT, PERCENT SHEAR STRENGTH Cu, LB./SQ.FT DESCRIPTION EPTH INSTALLATION WL WP W O 24650 GR. SURFACE  $\nabla$ 1 2' 10 2460 W.L. 5.5' NOV. 23,1973 SOFTBROWN SANDY SILT 2' 2 00 8 WITH MED. + COARSE SAND 2450 GRAVEL TO 12" DIA. 2 3 20 13 OFTEN TILL LIKE. 2' 4 00 4 2410 24384 5 20 20 WOOD SOFT TO FIRM STRATIFIED BROWN & GREY SILT WITH OCC. GRAVEL TO 1/2"DIA 27.0 2" 6 00 24310 34.0 24290 360 2430 SAND & GRAVEL. 7 WS BWS 2420 BEDROCK. 9 WS 10 W.S 2410 55.0 END OF HOLE.

15-0-5 Percent axial strain at failure

GOLDER, BRAWNER & ASSOCIATES

11.00

- - - -

VERTICAL SCALE

I INCH TO ID FEET

PROJECT No . 123218 ....

EGM-2013-00163

2

Ghai

r

PROJECT No. 173218

.1

10000


1.

DESCRIPTION	PLOT			SOIL PROFILE SAMPLES								CM./SE			
	E	NUMBER	TYPE	HS/ E	EVATION	SHEA	R STRENG	1	1		WATER		PERCENT	ADDITIONAL LAB. TESTING	STANDPIPE
	STRAT	NUN	F	BLOWS /	ELEVI			-1	1		WP			ADD LAB.	INSTALLATION
SR. SURFACE.					-						8				
ARIABLE ENSITY BROWN GREY SILT GAND & GRAVEL		1	20	>50	2450			-							° V
VOODEN CULVERT ARIABLE DENISITY	1														WL. 6.0' NOV 23,19
ROWN & GREY					2440										
FINE GRAVEL.			7												¢
	Г		2"		2430										8
AND & GRAVEL		6	w.s												
BEDROCK.					2420										2 0
		7	w,s		2410										0 0
ND.OF HOLE .															1.00
-															
											2				
	RRIABLE ENSITY BROWN GREY SILT AND & GRAVEL HODDEN CULVER ARIABLE HENSITY ROWN & GREY ILT WITH MEP. COARSE SAND FIWE GRAVEL OMPACT BROWN GREY SILT AND & GRAVEL ERY DENSE AND & GRAVEL, BEDROCK.	RRIABLE ENSITY BROWN GREY SILT AND & GRAVEL HODDEN CULVERT ARIABLE BENGTY ROWN & GREY ILT WITH MED COARSE SAND FINE GRAVEL OMPACT BROWN GREY SILT AND & GRAVEL ERY DENSE AND & GRAVEL	RRIABLE ENSITY BROWN GREY SILT AND & GRAVEL I IODDEN CULVERT ARIABLE BENSITY ROWN & GREY ILT WITH MED. COMPACT BRAVEL INTE GRAVEL SILT. AND & GRAVEL ERY DENSE AND & GRAVEL ERY DENSE AND & GRAVEL 6 BEDROCK.	REABLE ENSITY BROWN GREY SILT AND & GRAVEL DODEN CULVERT ARIABLE ENSITY ROWN & GREY ILT WITH MER COMPACT BANN AND & GRAVEL ENT DENSE AND & GRAVEL ENT DENSE AND & GRAVEL ENT DENSE AND & GRAVEL ENT DENSE AND & GRAVEL 6 WS	RIABLE ENSITY BROWN GREY SILT AND & GRAVEL IODDEN CULVERT ARIABLE ENSITY ROWN & GREY ILT WITH MER COARSE SAND FINE GRAVEL SREY SILT AND & GRAVEL ERY DENSE AND & GRAVEL SEPY DENSE AND & GRAVEL 6 WS	BR. SURFACE. BRIABLE ENSITY BROWN GREY SILT AND & GRAVEL DENSITY ROWN & GREY ILT WITH MED COARSE SAND SALEY SILT, COARSE SAND SALEY SILT, DIMPACT BROWN GREY SILT, AND & GRAVEL SREY DENSE AND & GRAVEL SERY DENSE AND & GRAVEL 5 20 8EDROCK. 7 W.5 2420 7 W.5 2420	BR. SURFACE. BRIABLE ENSITY BROWN GREY SILT AND & GRAVEL I DO RODEN CULVERT AND & GRAVEL I DO ROWN & GREY ILT WITH MED COARSE SAND SALEY SILT, COARSE SAND SREY SILT, AND & GRAVEL SALEY SILT, AND & GRAVEL SEY DENSE AND & GRAVEL	BR SURFACE. BRIABLE ENSITY BROWN GREY SILT AND & GRAVEL I 0,0 SODEN CULVERT AND & GRAVEL I 0,0 SODEN CULVERT AND & GRAVEL I 0,0 SODEN CULVERT PO SOURCE PO SOURCE SO	BR SURFACE. BRIABLE ENSITY BROWN GREY SILT AND & GRAVEL I BRIABLE DENSITY ROUN & GREY ILT WITH MED COARSE SAND SREY SILT ENSI GRAVEL. DMPACT BROWN GREY SILT SREY DENSE AND & GRAVEL 5 00 5	BR SURFACE. BRIABLE ENSITY BROWN GREY SILT AND & GRAVEL I DO GREY SILT AND & GRAVEL I DO GREY SILT AND & GREY ILT WITH MEP COARSE SAND SREY SILT AND & GRAVEL DMPACT BROWN GREY SILT AND & GRAVEL SREY DENSE ERY DENSE AND & GRAVEL GRAVE	BR SURFACE. BRIABLE ENSITY BROWN GREY SILT AND & GRAVEL I 2° PO >50 BRIABLE PO >50 AND & GREY ILT WITH MED COARSE SAND SREY SILT AND & GRAVEL. DMPACT BROWN GREY SILT AND & GRAVEL SREY DENSE AND & GRAVEL 5 20 5	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	$\begin{array}{c c} R & SURFACE \\ \hline RRMDLE \\ ENSITY BROWN \\ GREY SILT \\ GRAVEL \\ \hline 20 > 50 \\ \hline 20 > 50 \\ \hline 20 \\ \hline 20 > 50 \\ \hline 20 \hline 20$	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	BEDROCK.

PROJECT No. 123218 1.8.11 RECORD OF BOREHOLE / BORING DATE OCTOBER 29,30, 1973. DATUM TAKEN FROM COMINCO DRAWING NO. HB 285 P LOCATION See Figure / BOREHOLE TYPE ROTARY TRICONE BOREHOLE DIAMETER 4 IN. SAMPLER HAMMER WEIGHT 140 LB. DROP 30 INCHES PEN. TEST HAMMER WEIGHT - LB DROP - INCHES SOIL PROFILE SAMPLES SCALE DYNAMIC PENETRATION RESISTANCE COEFFICIENT OF PERMEABILITY k, ADDITIONAL LAB. TESTING CM. / SEC. BLOWS/FT \_\_\_\_\_ FT PLOT NUMBER ELEVATION ÷. 1 . TYPE BLOWIS / STANDPIPE WATER CONTENT, PERCENT SHEAR STRENGTH Cu, LB./SQ.FT DESCRIPTION STRAT INSTALLATION Wp -W WL -+ 2500 1 2 11 2 0.0. 4 2490 3 00 14 4 0.0 5 SOFT TO FIRM 2480 BROWN SANDY 5 6.0 15 SILT WITH SOME MED. 1 6 00 COARSE SAND FINE GRAVEL. 2070 1 20 13 8 20,13 2460 9 2 23 10 20 37 2450 2 11 00 24

LEVN DEPTH 2505.0 GR. SURFACE, W.L. 23.0' NOV. 23, 1973 2495.3 50.0 53.0 55.0 CLAYEY SILT WITH A TRACE OF MED. SAND 55.0 DARK BROWN 50.0 DARK BROWN 2455.3 12 20 2100 2440 13 2000 SAND4 GRAVEL TO I"DA. (TILL). VERY DENSE BLACK FRIABLE DESICCATED SILT WITH THIN PYRITE LENSES 1 ROLINDED GRAVEL TO 1/2"DIA. 14 W5 2430 15 WS BEDROCK. 16 WS 2420 2420.0 END OF HOLE. 16-0-s Percent axial strain at failure VERTICAL SCALE DRAWN RMO GOLDER, BRAWNER & ASSOCIATES 1 I INCH TO IO FEET Page 78 EGM-2013-00163

Pages 1 through 7 redacted for the following reasons: Not Responsive



File HB. ( 0500032 E

M-85 EXHIBIT 'C'

# DAVID MINERALS LTD.

# TailingsDisposal Scheme

# HB Mill, Salmo, B.C.

Return to: Victoria OFFICE Box 91-1956-32



Page 8 EGM-2013-00163

PROJECT:	HB Mill Tailings Disposal Scheme	
LOCATION:	Salmo, B.C.	
CLIENT:	David Minerals Ltd.	
OUR FILE:	VA 2869 November 27, 1981	

اير.

I

November 27, 1981 VA 2869

# November 27, 1981

# VA 2869

•

.,d

F

# TABLE OF CONTENTS

		PAGE
1.	INTRODUCTION AND SUMMARY	1
2.	DESCRIPTION OF EXISTING TAILINGS POND AND DAM	3
	<ul><li>2.1 Cominco's Operating History</li><li>2.2 Geotechnical Aspects of Dam Construction</li><li>2.3 Spillway</li></ul>	4
3.	TAILINGS DISPOSAL SITE	6
	3.1 Hydrological Setting	6
4.	TAILINGS DISPOSAL SCHEME	7
	<ul> <li>4.1 Existing Capacity of the Pond</li> <li>4.2 Tailings Dam Raising</li> <li>4.3 Water Balance</li> <li>4.4 Permanent Spillway</li> </ul>	8 8
.5.	CONCLUSIONS AND RECOMMENDATIONS	9
	5.1 Conclusions	-

# APPENDIX

I

-

LOGS OF BOREHOLES DRILLED BY GOLDER ASSOCIATES IN 1973

# LIST OF DRAWINGS

-	SITE LOCATION
-	LOCATION OF TAILINGS DISPOSAL POND
-	PLAN OF EXISTING TAILINGS POND
-	PLAN AND SECTION OF EXISTING DAM
-	SCHEMATIC PROFILE OF TAILINGS POND
-	STABILITY ANALYSIS OF DAM
-	WATER BALANCE

VA 2869

1.

#### INTRODUCTION AND SUMMARY

Klohn Leonoff Ltd. was requested by David Minerals Ltd. to investigate the feasibility of using the existing tailings pond at the HB Mill for the deposition of about one million tons of tailings. This report has been prepared for submission to the Nelson Branch of the B.C. Ministry of Energy, Mines and Petroleum Resources so that a permit can be obtained by David Minerals to operate the pond.

The HB Tailings Dam is located approximately four miles south of Salmo, B.C. (Drawings A-2869-1 and B-2869-2). The dam was originally built by Cominco in 1955 using a timber crib over which borrow materials from the west end of the pond were placed. The dam was raised in this manner to a height of about 40 ft. In 1964, a portion of the timber crib failed and moved about 10 to 15 ft. Drains were placed and toe protection was provided to stabilize the Construction of the dam raising continued by the failure. downstream method until operations were suspended in 1967. We understand that there was no independent geotechnical control of In 1973, Golder Associates drilled dam construction until 1973. three holes, one in the crest and two in the downstream portion of the dam. They encountered relatively soft material (as low as four They recommended measures to reduce blows per foot) in two holes. the phreatic surface within the dam, which were implemented. Subsequently, Golder Associates supervised the construction of dam The operations at the HB Mill were raisings in 1975 and 1977. suspended by Cominco in 1978.

The tailings dam is located at the southern end of a valley and has been constructed about 75 to 80 ft high using borrow materials. The tailings were deposited at the back of the pond, about 2900 ft from the crest of the dam and clarified water ponded against the upstream face of the dam (Drawing B-2869-3). Initially, two timber decant towers were used in conjunction with two 24-inch diameter steel pipes to pass water from the upstream to the downstream side of the dam. In 1977, these decant towers were filled with concrete and replaced with a new spillway and drop manhole arrangement (Drawing D-2869-4).

Dr. Rajaram of Klohn Leonoff visited the damsite on September 23, 1981. Discussions were held with Mr. Newman of Cominco Engineering to obtain details of the tailings dam operation during the period 1955 to 1978. A profile of the tailings pond from the tailings flume to the dam crest was obtained from Mr. Newman and from Mr. Girdler of David Minerals. A schematic profile of the tailings pond is presented in Drawing B-2869-5. Assuming that tailings will be deposited uniformly on the existing tailings surface, a curve relating tons of tailings to elevation was developed. Approximately 790,000 tons of tailings can be deposited in the existing pond and dam. The dam will have to be raised by about 6 ft before the anticipated one million tons of tailings are deposited.

Klohn Leonoff will assess the condition of the existing dam by conducting a program of field investigation and laboratory analysis. Based on the results of this investigation, specifications for the dam raising will be provided.

The hydrology of the site was briefly analyzed to determine the water balance in the pond. It was concluded that the present spillway, which we understand is designed for a peak flow of 80 cu ft per second, is adequate to handle the runoff from a 200 year flood.

A seismic risk analysis of the site indicated that the acceleration amplitude with return periods of 100 years is 0.015 g (1.5 percent gravity). Since this figure indicates that the site has very low seismic risk, a static stability analysis was performed. The 2.

analysis indicates that the dam has a minimum factor of safety against a shearing type failure of 1.7.

This report details the condition of the existing dam and describes the physical and hydrologic setting of the tailings pond, the tailings disposal scheme, and final abandonment of the pond.

DESCRIPTION OF EXISTING TAILINGS POND AND DAM

The existing tailings pond is located approximately four miles south of Salmo, B.C. A plan of the pond area showing the contours of the tailings surface is presented on Drawing B-2869-3. The tailings dam is located at the southern end of a valley and has been constructed about 75 to 80 ft high using borrow material obtained from the abutment slopes. The dam is about 800 ft long and the pond occupies an area of about 67 acres. A plan and section through the dam are presented on Drawing D-2869-4.

#### 2.1 Cominco's Operating History

Cominco operated the tailings pond during the period 1955 through 1978. The tailings pond was used during 1955 through 1967, and subsequently during the period 1974 through 1978. The crest of the dam was raised periodically during these years to accommodate the increasing volumes of tailings. These dam raisings were performed using the downstream method of construction, i.e., additional fill was placed on the crest and the downstream slope of the dam. It is our understanding that the dam construction during the years 1955 through 1967 was not performed under independent geotechnical control.

When the dam was initially constructed in 1955, a timber crib structure was used. This crib was covered with borrow material obtained from the west end of the pond. The dam was raised in this manner to a height of about 40 ft. In 1964, a portion of the

November 27, 1981

VA 2869

timber crib failed and moved about 10 to 15 ft. Drains were placed and toe protection was provided to stabilize this failure. Construction of the dam raising continued by the downstream method until operations were suspended in 1967.

- 4 -

Before Cominco re-opened the HB Mill in 1974, Golder Associates investigated the stability of the tailings dam in 1972 and 1973. They drilled three holes, one on the crest and two on the downstream portion of the dam. They encountered soft materials (as low as four blows per foot) in two of the three holes. They recommended that a filter blanket be placed on the downstream slope of the dam to reduce the phreatic surface and improve dam stability. This was implemented in 1974. Two subsequent dam raisings in 1975 and 1977 were supervised by Golder Associates (personal communication, Newman, 1981). Cominco has been monitoring the water levels in the dam since the installation of piezometers in 1973. These observations indicate that the phreatic surface within the dam has not changed since Cominco shut down their operation in 1978.

#### 2.2

#### Geotechnical Aspects of Dam Construction

Cominco re-opened the HB Mine and Mill in 1973. In 1972 and 1973, Golder Associates of Vancouver investigated the stability of the tailings dam. In 1973, three boreholes were drilled to depths varying from 45 to 85 ft and extended approximately 20 ft into bedrock. One borehole was drilled from the crest and two boreholes from the downstream slope of the existing tailings dam. Logs of the boreholes obtained by Golder Associates are presented in Appendix I. Samples were obtained for laboratory testing, and perforated plastic standpipes were installed in the boreholes to monitor groundwater levels. A plan and section of the dam, showing the location of these boreholes, is presented on Drawing D-2869-4. VA 2869

- 5 -

November 27, 1981

A review of Golder Associates reports dated June 1972 and January 1974, and discussions with Mr. Newman of Cominco reveal the following about the tailings dam:

- The dam is generally comprised of brown sandy silt containing varying amounts of medium to coarse sand and fine gravel.
- There are zones of soft material in the fills placed before 1967 (as low as four blows per foot).
- A timber crib was used during the initial construction of the dam, and a portion of this crib failed in 1964 and moved about 10 to 15 ft.
- The foundation material under the fill consists of bedrock overlain by 6 to 8 ft of dense silty till with minor amounts of sand and gravel.
- The fill material has an angle of internal friction of approximately 35 1/2 degrees with zero cohesion, as determined by Golder Associates' laboratory tests.
- The factor of safety against a shearing type failure is of the order of 1.3. Since this analysis was completed by Golder Associates in 1973, the phreatic surface has been lowered and so the present factor of safety is considered to be greater than this figure.

 The dam has adequate protection against surface erosion.

Golder Associates recommended that if the ponded water level is raised, the dam should be raised using a filter blanket to maintain the phreatic surface below the level of the existing downstream fill slope. The specifications for the 1975 and 1977 dam raisings were prepared by Cominco on the basis of the Golder reports, and we understand that the construction was supervised by Golder Associates. A review of the piezometer readings through July 1981 indicates that the phreatic surface has been relatively constant, since Cominco shut down in 1978.

# 2.3 Spillway

Prior to 1977, two timber decant towers were used in conjunction with two 24-inch diameter steel pipes to pass water from the upstream to the downstream side of the dam. Due to operating and maintenance problems with this system, Cominco filled these structures with concrete and installed a new spillway and drop manhole structure (Drawing D-2869-4). This structure is equipped with a 36-inch diameter steel pipe, and we understand was designed to pass a maximum flow of 80 cu ft per second (35,900 USGPM).

#### 3. TAILINGS DISPOSAL SITE

The tailings disposal area is situated in a natural basin covering about 67 acres in the Salmo Provincial Forest. It is to the east of Provincial Highway 3 and the Salmo River, about four miles south of Salmo, B.C. (Drawing B-2869-2). To the east and west of the pond are heavily treed slopes consisting of 80 to 90% of evergreens. The dam is situated at the southern end of the basin.

# 3.1 <u>Hydrological Setting</u>

Dr. McCreath of Klohn Leonoff, obtained data on snowcourse, streamflow, and precipitation from measuring stations at Creston, Nelson, Trail, and Edgren Creek. From analysis of the data, the average annual precipitation at the site is 31.5 inches, and the average annual evaporation is 16.7 inches. The average annual runoff from a catchment area of about 445 acres to the east of the tailings pond is about 14.5 inches. The water balance for the pond was calculated using these estimates for precipitation, evaporation, and runoff. 4.

4.1

The peak 200 year flood inflow into the pond is estimated to be in the order of 120 to 150 cu ft per second (cfs). About 30 to 50% of this inflow can be temporarily stored in the pond since a flood surcharge of 2 ft has been assumed in computing the volume-elevation curve. Thus, the existing spillway, which we understand has been designed for a discharge of 80 cfs, can handle the 200 year flood estimated for the site.

#### TAILINGS DISPOSAL SCHEME

#### Existing Capacity of the Pond

The tailings pond has been operated since 1955 with the tailings being deposited at the upstream end of the tailings pond and the dam being raised as necessary by the downstream method of construction using borrow materials. Klohn Leonoff recommends that this method of tailings disposal be continued by David Minerals Ltd. In an effort to estimate the present capacity of the tailings pond, and the extent of dam raising necessary to store the anticipated 1,000,000 tons of tailings, a curve relating the tons of tailings to the elevation of the dam crest was developed (Drawing B-2869-5).

A schematic profile of the existing tailings surface is presented on Drawing B-2869-5. The water level in the pond is 5 ft below the dam crest, and the depth of the ponded water on the upstream side of the dam is 9 ft. The tailings should be discharged in layers over the existing tailings surface. In June 1984, after about 790,000 tons of tailings have been deposited, the ponded water capacity and flood surcharge provision will be reduced to a minimum. At that point, the dam will have to be raised by about 6 ft before additional tailings can be deposited. During operation of the tailings pond, the elevations of the tailings should be monitored to ensure that the schematic profile presented on Drawing B-2869-5 is maintained. The depth from the crest of the slimes surface on the upstream side of the dam should be maintained as depicted in the tons of tailings versus elevation curve.

.: → ..8 °→

#### 4.2 Tailings Dam Raising

The tons of tailings versus elevation curve indicates that the dam crest has to be raised prior to June 1984. Klohn Leonoff recommends that before the dam raising is undertaken, a program of field investigation should be conducted to assess the condition of the upstream portion of the dam. The upstream portion of the dam contains some soft zones, and also has a timber crib buried within it.

During the 1982 field season, two to three boreholes should be drilled to assess the condition of the upstream side. Soil samples should be obtained for conducting laboratory tests. Based on the results of the field and laboratory testing program, Klohn Leonoff will develop detailed specifications for the dam raising.

A stability analysis of the dam was performed using the parameters presented in Drawing B-2869-6. A preliminary profile of the dam raised by 6 ft was used to perform the analysis. A seismic risk analysis of the site indicated that the acceleration amplitude with return periods of 100 years is 0.015 g (1.5% gravity). Since this represents a very low seismic risk, a static stability analysis was performed. The minimum factor of safety for the dam was found to be 1.7.

#### 4.3 Water Balance

The hydrological data given in Section 3.1 of this report was utilized to compute the water balance for the tailings pond (Drawing A-2869-7). Using a production rate of 900 tons per day, a tailings pulp density of 30%, and no recycling of the water, the tailings VA 2869

- 9 -

transport water required is 350 USGPM. Of this amount about 50 USGPM remains within the voids of the tailings. The runoff and precipitation into the pond is estimated to be 335 USGPM. Assuming that 40 USGPM are lost due to evaporation and seepage, the average amount of daily flow out of the spillway is 595 USGPM. This represents an average dilution factor of about two for the tailings water. During periods of heavy runoff and precipitation, this factor could be much higher.

# 4.4 Permanent Spillway

On final abandonment of the pond, a permanent spillway should be constructed at the east abutment of the dam. This should be an open-channel spillway which will safely pass flood water from the upstream to the downstream side of the dam. The design of this spillway is beyond the scope of the present study.

# 5. CONCLUSIONS AND RECOMMENDATIONS

# 5.1 <u>Conclusions</u>

- 1. The existing tailings dam has a capacity of approximately 790,000 tons.
- 2. The tailings should be discharged from the northern end of the pond, in layers over the existing tailings surface. The depth from the crest of the slimes surface on the upstream side of the dam should be maintained at a minimum of about 8 ft.
- The dam crest should be raised by about 6 ft during the 1983 field season to accommodate the anticipated one million tons of tailings.

#### 5.2 Recommendations

 The condition of the existing dam, especially the upstream portion, should be investigated during the 1982 field season. Based on this investigation, plans and specifications for the 1983 dam raising should be prepared.

- 2. Piezometric levels in the dam should be monitored on a monthly basis.
- 3. The tailings surface elevation should be monitored to ensure that the schematic profile presented in this report is maintained. Any significant variations in this profile will affect the tailings storage capacity.

KLOHN LEONOFF LTD.

ajoram

V. RAJARAM, Ph.D., P.E. Senior Division Engineer

Mah 20bm

MARK T. OLSEN, P.Eng. Staff Consultant

VR/MTO/jas

# APPENDIX I

ð

Turking and

ļ

# LOGS OF BOREHOLES DRILLED BY GOLDER ASSOCIATES IN 1973

GOIDER, BRAWNER & ASSOCIATES											2		KED	-	
					15-0-8 10	Percent	t axial	strain a	t failur	e					
														·	
5.0 END OF HOLE.						τ									
100 3.0 END OF HOLE.		w.s		2410										0	
BEDROCK.		w.s		<u> 2420</u>										. 0	

a ba

THAL SCALE					15-0-5 10	Percent	axial s	train at	failure				
BEDROCK	•	7	W S	2420									


# LIST OF DRAWINGS

A-2869-1	-	SITE LOCATION
B-2869-2	-	LOCATION OF TAILINGS DISPOSAL POND
B-2869-3	-	PLAN OF EXISTING TAILINGS POND
D-2869-4	-	PLAN AND SECTION OF EXISTING DAM
B-2869-5	-	SCHEMATIC PROFILE OF TAILINGS POND
B-2869-6	-	STABILITY ANALYSIS OF DAM
A-2869-7	-	WATER BALANCE


PARG NE DB KOC  $\mathbf{O}$ Μ B 1 E В R Į Ŧ A L .... E 15 LISIE 1 uniber to J Cramberry Mountair 3078 Minur Perpusanes Yar  $\cap$ Mauni Ogin m Ireu; 1 pine Mounten 2972 Monashee Provincial Park Genaria S Arron В Μ U U 5.70 wind Mour tain C Nº sur 🕫 ្ពុ ស្រ Nakusp 🌒 🛞 and the state strengt a advas the Prinacles ê Mus Hi Coner aa iyo  $\mathbf{C}$ ر عليمة " مراقحا 316.2 Route Villa tech ė Findlas C  $\sim \mathcal{P}$ Garadis e Re 3 .... 5 1.0.000 Z Mount Candle Z °. €taca⊧ កំផុរ ខេត្ St Mary & Alpine Same Land Cicia in the 5 Provincial Fark 2 Kokanee Giaasneem Glacier cań Provincia! Z Park e Haunder  $\mathcal{Z}$ Course Shi shoth Kokanee աստեր Peak Maunt Gener Sidners Corro Altor Protection Parts Altor Parts Altor Parts Altor Protection Parts Altor Altor Parts Altor e de la come de la com "mrten Queens Berg Bing @ bas Appledate o@ Baltors O Gray Creek ତ୍ ୨୦୯ 3 5 CPincle Altara Snowcrest Nours Stocian
 Pasir nuide La a blene A 2565 oriset cree-ofsecter Netson © \$ Wountain Station Vroir 5. Casswell Mountain Co; Mouri Faith @Itaums Mountain SITE LOCATION oPario Rico Ire o C.Kassalloux 🗄 🖷 Ontischema Ymer (iii) Branter Greek Subdivision CANADA - USA - BORDER 7 Genetie Meadows O-Salind Exchuant O Onsis Rivernate Ga-Warriaid Creising CP . \_\_\_\_h CParis fruitvaln (celm Trail Tingara Lake Stante @Cons Creston OReaver zana 6 Jersny Ressland m Gentles C. Encksen 0.0000 ø È. Dianica amini<mark>le</mark>\_ Reporte Of Mountain RETURN PROTECTION TO OUR CLIENT, THE PUBLIC AND OUNSELVES, ALL REPORTS AND DRAWINGS ANE SUBMITTED REF. : CANADA GAZETTEER THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR LISE AND/OR 1980 DELICATION OF DATA, STATEMENTS, CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS 1:1000.000 SCALE S RESERVED PENDING OUR WRITTEN APPROVAL PROJECT MILL TAILINGS DISPOSAL HB **V LEONOFF LTD.** TITLE ENGINEERS CONSULTING SITE LOCATION CLIENTS PROJECT No. DWG, No. RE 134116 NOV. 27, 1981 DAVID MINERALS LTE Fage 25 K. VA 2869


	44.00 42.00 4000 38.00 36.00 34.00 32.00	GARNET PEN PIT A AREA
R LIN	3000 2800 2600 2400	RIVATE TOAD BOY
GRAV W A	AREA SHEEP	UBLIC ROAD FR HBMIZE
2000000	SL 6 970 ac	LUCKY BOY SL4 38ec DOC*36556 MAYFLOWER
	3400 REFERENCE BASE PLAN TAKEN	FROM COMINCO SURFACE RIGHTS DRAWING
8 ( 5%)* Hemours Francia Million 20 Francia 20 Francia 20 Francia 20 Francia 20	KLOHN LEONOFF REPORT DATED NOV. 27, 1981	HB MILL TAILING DISPOSAL
ATN AND NE UUR	DAVID MINERALS LTD	APPROVED NOV. 27, 198 APPROVED NOVA 2869 B-2869-2 Date of ISSUE NOV. 27, 198 NOVA 2869 B-2869-2


<del>Page 26</del> EGM-2013-00163




EGM-2013-00163








EGM-2013-00163





# REFERENCE

DRAWING SUPPLIED BY COMINCO ENGINEERING, DWG. NO. HB 304 DATED FEBRUARY 7, 1977.


0'

ROCK TOE DRAIN

OVE ORGANIC OVERBURDEN

AS A MUTUAL PROTECTION TO DUR CLIENT THE PUBLIC AND DURSELVES AN APPORTS AND DRAWINGS AND REPORTS AND DRAWINGS AND REPORTS AND DE CUR CLIENT FOR A SPECTOR PROJECT AND ALL MEDIATION OF DUR ALL AND ALL MEDIATION OF DATA STATISTICS (CARCIN DE DATA STATISTICS (CARCIN

BE READ WITH KLOHN LEONOFF REPORT DATED NOV. 27, 1981	REV.	DATE		REVISION DETAILS	5					
AS SHOWN	CON	NINCO	S.S.	DATE OCT., 1981	AS SHOWN					
KLOHN LEONOFF LTD.	PROJE	ст НВ	MILL TAILI	NGS DISPOS	AL					
CONSULTING ENGINEERS	PLAN AND SECTION OF EXISTING DAM									



Pages 35 through 37 redacted for the following reasons: Not Responsive



# **Province of British Columbia**

Ministry of Energy, Mines and Petroleum Resources

# **REPORT OF INSPECTOR OF MINES**

(Issued pursuant to section 4 of the Mines Act)

# CRUSHING AND CONCENTRATING WORKS

Name of concentrator, etc. H. B. Concentrator	Locality
Owner or operator (David Minerals)	Manager Thorne, Ernst & Whitney
Superintendent None at present Property idle	Address

Number employed ... 1. (caretaker)

Method of concentration followed ... Not. Operating.

#### Persons Contacted

#### Company Representatives

M. A. Mellor

Jeff Belza (Caretaker)

Worker Representatives

The caretaker reports that the property is inspected daily.

#### CONCENTRATOR AREA

This property is acquiring an unkempt, unattended appearance with the development of scrap strewn about, also barrels, one full of xanthate pellets. This barrel shall be moved inside the mill building out of the elements and behind a locked door.

Cyanide was not found on the property, the caretaker informing such was moved to the Ainsworth Mill prior to shut-down.

One of the reagents mixing tanks appeared to be approx. 1/3 full but could not be easily opened for an inspection. A report as to the contents of this tank is requested pursuant to the Mines Act Section 5 re possible dangerous conditions.

#### MINE ADIT AREA

The mine portal area is also becoming littered with various scrap. The mine portal is open for easy access. All mine entrances shall be checked and shall be securely fenced, or sealed, to prevent inadventent access as per Mines Act Section 14 requirements.

#### TAILINGS POND

Due to a low water level, the pond was not discharging via the overflow structure. Free board was estimated at 10 feet. The activity of a very small spring at the toe of the downstream slope at the junction of the rock fill continues to be present. The dam appears stable.

America Inspector of Mines

310 Ward Street, Nelson, B. C. VIL 5S4 (Address)

Data of increation		October 23,											1086																	
CC CC	1	1	1	1	1	1	1	1	1	1		1	1	1	1	•	à	7	•	1	•	1	1	•	15		Ť	7	1	2

file MB. min

August 11, 1997

Hon. Corky Evans M.L.A. 402 Baker St. #204 Nelson BC V1L 4H8 MINISTRY OF EMPLOYMENT & INVESTMENT CRAMPRONT, B.C. AUG 2 5 1997 FILE

s.22

Dear Corky Evans:

I would like to bring to your attention an issue concerning property s.22 situated eight kilometres south of Salmo. s.22

s.22

s.22 have attached a map depicting the properties and relevant terrain details.

As shown on the map a drainage ditch passes through Blocks 3, 4, and Parcel "A" of Block 5. This ditch was constructed across the property in the early 1950's to accomodate flow from a tailings pond created behind an earth fill dam in the draw above the remainder of Block 5.

It has been brought to our attention that during the period of spring runoff when water flows through this ditch that the water has been contaminated by seepage from the RDCK (Regional District of Central Kootenay) landfill into the tailings pond. We understand that when the seepage is contained by the tailings pond that the tailings acts as a filter for the contaminated material. This is not the case during the runoff period and the discharge flows down across our property and into the Salmo river.

A further problem is the control and timing of the release of the runoff flow from the tailings pond. This spring the flow began while the ditch was still filled with snow. The water

We

flowed down over top of the snow till it reached the plowed driveway leading to the house, barn, and outbuildings on the The water travelled along the driveway entering the farm. house, flooding the barn and outbuildings, stranding our cattle, ruining stored hay, and flooding farm machinery. This required us, at some expense, to rent a bulldozer and excavator to redirect the flow.

s.22

We have the health and safety of <u>s.22</u> to consider. s.22 It is deeply s.22

upsetting to think the Salmo river where we fish and play is also affected by this problem. In giving some thought to our initial actions regarding this matter, we are requesting through yourself an investigation into the contamination of spring runoff flowing though our land from the RDCK landfill. Secondly, should the information provided us be proven accurate through this investigation, it would be prudent to deal with the containment, control, and routing of runoff in a timely manner to ensure the protection of s.22 and the Salmo river from further contamination. In any case, considering the events of this spring in regards to the flooding that occured, the control and routing of this flow must be dealt with.

We look forward to working towards a solution to this problem with the various agencies involved.


s.22 cc: RDCK Waste Management Environment and Lands,

Pollution Prevention Branch

· · · ·

Ministry of Mines ·• ,

s.22





WHALE /CRANBLOOK

October 30, 1997 File: 18040-02-07/HB/01 x M-85

Mr. Walter Kuit Manager, Environmental Affairs Cominco Ltd. 200 Burrard Street Vancouver, BC V6C 3L7

MINISTRY OF BUE & INVESTICE IT FILE

Nu-Dawn Resources Inc. 102 Piper Crescent Nanaimo, BC V9T 3G3

Dear Sir/Madam(s):

## Re: HB Mine Tailings Impoundment, Salmo, B.C.

According to our records the HB Mine near Salmo, B.C. is permitted under Mines Act Permit M-85 to Cominco, while mineral title and fee simple land is owned by Nu-Dawn Resources. Geotechnical inspections of the tailings impoundment were performed by the Mines Branch in April 1993 and June 1997. Attached you will find copies of these inspection reports.

On July 22, 1977 the Acting Chief Inspector of Mines approved construction of a spillway at the dam by letter addressed to Mr. J.S. Newman, P.Eng., Civil Engineer for Cominco. The spillway was never installed.

In summary, site conditions at HB Mine tailings impoundment have deteriorated and pose public safety and environmental hazards. The main concerns are that the impoundment was never decommissioned with a permanent spillway on closure and the current decant structure is deteriorating; the intake channel and structure are filling with debris and the discharge flume and channel on the downstream face are in need of repair. The integrity of the dam itself appears to be satisfactory except that there should be more freeboard. Overtopping and breaching of the dam or regressive erosion at the decant outlet is considered a distinct possibility in the foreseeable future.

.../2

Ministry of Employment and Investment Regional Operations, Health and Safety Branch Energy and Minerals Division Mailing Address: PO Box 9320 Stn Prov Govt Victoria BC V8W 9N3

Telephone: (250) 952-0462 Facsimile: (250) 952-0481 Location: 5th Floor, 1810 Blanshard Street Victoria

> Page 42 EGM-2013-00463



Province of British Columbia Ministry of Employment and Investment

ENERGY AND MINERALS DIVISION

## REPORT OF GEOTECHNICAL INSPECTOR

(Issued pursuant to Section 15 of the Mines Act)

Name of Property:	HB Mine	File:	18040-02-07/HB/01
Location:	Salmo		
Mine Manager:	n/a		
Company: Address:	Cominco and Nu-Dawn as per cover letter		
Persons Contacted:	n/a		
Type of Mining:	Closed, u/g, base metal		
Date of Inspection:	June 10, 1997		

An inspection of the tailings impoundment was conducted in the company of Art O'Bryan. The previous geotechnical inspection was April 29, 1993. The following areas in particular were noted:

The upstream dam face (Photo 1) is in good condition with no evidence of effects from wave action. The dam crest and downstream slope (Photo 2) are also in good condition with no evidence of cracks, settlement, slumps or erosion. Vegetation cover (mainly grasses and legumes) is healthy and thick and an alder has started on the upstream face at waterline.

The downstream toe is wet in the same areas as observed in 1993 and the toe drains appear to be functioning satisfactorily. The grouted CMP (old decant outlet) near the central toe of the dam is dry and not showing any signs of leakage inside or outside of the pipe.

The operating decant or water control structure is structurally sound. However the inlet channel to the decant is completely full if cattails and the alders are much larger. Compare Photo 3 (April 29, 1993) and Photo 4 (June 10, 1997). The log at the entrance to the channel is still in place. However the concrete water level control beams have not been removed from inside the structure as ordered in my 1993 inspection, although I note that the wooden support posts for the upper beam appear to have been replaced with steel pipe. Note that the same number of concrete beams are resting on top of the control structure in both photos.

F. vince of British Columbia Ministry of Energy, Mines and Petroleum Resources

Report of Inspector of Mines (Issued pursuant to Section 15 of the Mines Act)

## **GEOTECHNICAL - EIM**

Name of Mine: HB Mine

Locality: Salmo, B.C.

Owner or Operator: Nor-Quest Resources Ltd.

Address: 102 Piper Crescent Nanaimo, B.C. V9T 3G3

01 - 2

Manager: Mr. Raynerd Carson

Areas Inspected: Tailings Dam

Persons Contacted

Management: No one available.

The mine manager shall complete the right hand column noting specific corrective actions taken, or to be taken by a specified date, and return a copy to the Inspector within 15 days of receiving the report.

Ins	pection	Report
-----	---------	--------

Manager's Response of Action Taken

- 1. Crest good, no settlement.
- Upstream slope good, beach/ wave action/ erosion minimal.
- 3. Downstream slope covered with grass and alder, wet zones at toe and several seeps, but no seeps were obvious on downstream slope face. Stability looks good; no sloughs, settlements, toe drains operating.
- 4. Piezometer standpipe near toe at centre of dam is dry to a depth of approx. (plumbed with small stone) 45-50 feet. Check Fig. 1 from Golder Brawner 74 report (Feb. 12, 1979 Rep# E/74/124) assume it to be BH 2 which is drawn at about 50 foot depth on the section so assume piezo is dry.

	A
Copies To:	1 DA
Tim Eaton, P. Eng.	Lim Calon
Geotechnical Manager	Signature - Inspector
105-525 Superior St. Victoria, B.C., V8V 1X4	
Address	Signature - Manager

Date of Inspection: April 29, 1993

Dated:

Page 44 EGM-2013-00163

19




PHOTO 1




PHOTO 2




### рното з



РНОТО 4



РНОТО 5



РНОТО 6

Province of British Columbia

October 16, 1987

Ministry of Energy, Mines and Petroleum Resources Parliament Buildings Victoria British Columbia V8V 1X4



Rm.	105		525	Superior Street Nictoria B.C	. V8V	1X4
-----	-----	--	-----	------------------------------	-------	-----

FILE......

AND PETROLEUM RESOURCES FEBNIE, B.C. NOV 05 1987

File: 18040-02-07

Nor-Quest Resources Ltd. Box 369 Salmo, B.C. VOG 120

#### Attention: Mr. Greg Carriere, Project Manager

Dear Sir:

## Re: H.B. Mill Project

Attached is my inspection report for the geotechnical inspection of the tailings dam conducted September 28th. Please post a copy in the usual, conspicuous location. You should also forward a copy to your corporation headquarters.

As I had said during my inspection the white plastic sleeve of the piezometer could not be located; it will be useful when you submit your engineering report for approval of recomissioning. You will also need to sound the pond and present the results of the sounding survey along with the engineering report in order to recomission this pond. You would be wise to undertake the sounding survey and the restoration of the piezometer as soon as possible.

The placing of the coarse material on the upstream face can probably be delayed until next year, for I am not likely to conduct my next inspection until Autumn of 1988.

Yours truly,

R.T. Martin, P.Eng., Sr. Geotechnical Inspector

RTM:blh Attachments:

cc: A.W. Whale, Fernie R.A. Fyles, Victoria



## **Province of British Columbia**

Ministry of Energy, Mines and Petroleum Resources

## **REPORT OF INSPECTOR OF MINES**

(Issued pursuant to section 4 of the Mines Act, 1980)

#### GEOTECHNICAL INSPECTION

H.H.	B. MILL
District and Location	District no.5, Nelson, near Salmo
Owner or Agent	Nor-Quest Resources Limited
Designated Manager .	Greg Carriere

Date of Inspection	September 28, 1987
Person(s) attending	A. Whale, Inspector of Mines & Res. Eng. ) ) E.M.P.R.
	T. Martin, Sr. Geotechncial Inspector )
	G. Carriere, Manager
Part inspected	Tailings.dam

#### Remarks:

Sunny, warm, calm.

The usual springs at the junction of the downstream face and both the west abutment and the rock toe berm still exist, but they were severely reduced by the prolonged dry conditions this year. The piezometer on the toe berm seems to have been snapped off. Relocate and restore it if possible.

Freeboard was adequate, but undercutting of the upstream face of the dam is becoming significant. Place coarse gravel and cobble-sized protection over the affected area before my next inspection.

Although no overflow was occurring at the time, the overflow had obviously been functioning this year. However, one stoplog was jammed in the guides. Remove the jammed log to allow free overflow. Check overflow occasionally during periods of high runoff.

> Page 49 EGM-2013-00163

Environment Envir ement Canac

Environmental Protection


Canada

Protection de l'Environnement

H.B. Menth 35

4th Floor, Kapilano 100, Park Royal, West Vancouver, B.C. V7T 1A2

April 20, 1978



#### Effluent Quality Survey, October, 1977 Re:

As you are aware, during the period from October 4-6, 1977, the Environmental Protection Service conducted a study to determine the quality of the Cominco H.B. mine tailings pond decant. Samples were collected for chemical and bioassay analyses. We have enclosed for your information and records a copy of the results obtained.

A review of the data indicated that the decanted effluent is in compliance with the effluent quality requirements of our "Metal Mining Liquid Effluent Guidelines" for all parameters except fish toxicity. Based on the available data we are unable to determine the component or components of the effluent contributing to the toxicity.

Under normal circumstances, we would be concerned about the discharge of toxic effluent to the Salmo River and would be endeavouring to have this problem resolved. However, noting that the effluent is only marginally toxic and that your mine will be shutting down in September 1978, we are willing to live with the existing situation until the specified closure date.

With respect to site reclamation following mine closure, we have made arrangements with the Ministry of Mines and Petroleum Resources to obtain from that agency a copy of your plans for reclamation when submitted. Following our review of the plans, we will be providing comments as required to that Ministry for incorporation in their agreement with your Company.

If you have any questions or comments with respect to the enclosed data, please feel free to contact Mr. J. Villamere or Mr. G. Trasolini (telephone number 666-6711) of my staff.

Yours truly, ORIGINAL SIGNED BY. B. A. HESKIN A SIGNE L'ORIGINAL

B. A. Heskin, P. Eng., Regional Director General, Pacific Region, Environmental Protection Service, Department of Fisheries and the Environment

Encl.

cc: Mr. W.N. Venables, P. Eng., Director, Pollution Control Branch, Water Resources Administration, Ministry of the Environment, Parliament Buildings, Victoria, B. C. V8V 455.

Mr. J. McDonald, Senior Reclamation Inspector, Ministry of Mines and Petroleum Resources, 1837 Fort Street, Victoria, B.C. V8R 1J6

## COMINCO H.B. MINE

## TAILINGS POND DECANT

### COMPOSITE SAMPLE RESULTS

October 4 - 6, 1977

## A. CHEMICAL ANALYSES

PARAMETER		DAY 1	DAY 2	DAY 3
As (T)	mg/l	0.004	0.004	0.005
Cd (T)	mg/l	<0.01	<0.01	<0.01
Cd (D)	mg/l	<0.01	<0.01	<0.01
Cu (T)	mg/l	0.02	0.02	0.01
Cu (D)	mg/l	<0.01	<0.01	<0.01
Hg (T)	µg/l	<0.2	<0.2	<0.2
Ni (T)	mg/l	<0.05	<0.05	<0.05
Ni (D)	mg/l	<0.05 .	<0.05	<0.05
Pb (T)	mg/l	0.1	<0.1	0.1
Pb (D)	mg/l	0.03	0.04	0.04
Zn (T)	mg/l	0.09	0.08	0.08
Zn (D)	mg/l	0.05	0.07	0.07
N.F.R.	mg/l	< 5	<5	<5
рH		7.5	7.6	7.5

## B. TOXICITY DETERMINATION

• •	DAY 1	DAY 3
LC 50 (96 hour)	56%	73%

## COMINCO H.B. MINE

## TAILINGS POND DECANT )

GRAB SAMPLE RESULTS

October 5, 1977.

PA	RA	ME	ΤE	R
----	----	----	----	---

As	(T)	mg/l	0.004
Cd	(T)	mg/l	<0.01
Cd	(D)	mg/l	<0.01
Cu	(T)	mg/l	0.01
Cu	(D)	mg/l	<0.01
Hg	(T)	µg/l	<0.2
Ni	(T)	mg/l	<0.05
Ni	(D)	mg/l	<0.05
Pb	(T)	mg/l	.0.1
Pb	(D)	mg/l	0.03
Zn	(T)	mg/l	0.09
Zn	(D)	mg/l	0.04
N.F	.R.	mg/l	<5
pН			7.5

Page 53 EGM-2013-00163

Province of British Columbia Ministry of Energy, Mines and Petroleum Resources

Olfice address: 403 Vernon Street Nelson, B.C. V1L 4E6 Telephone: (604) 354-6125 Mailing address: 310 Ward Street Nelson, B.C. V1L 5S4

Tel: 354-6125 Fax: 354-6120

File: 18080-02-02 - H.B. MINE

May 27, 1994

Mr. R. Carson Nu-Dawn Resources 102 Piper Crescent Nanaimo, B.C. V9T 3G3

Dear Mr. Carson:

Re: Inspection - May 25, 1994

Enclosed are two copies of my Inspection Report for the above-noted date.

Would you kindly fill in the second copy in the appropriate areas responding to the Inspector's comments, sign and date the first page and initial the subsequent page(s).

Please return the copy with your comments to me at the address shown on the report. Thank you for your cooperation in this matter.

Yours very truly,

D. Roach Inspector of Mines

DR/sb

Encls.

Page 54 EGM-2013-00163

#### Province of British Columbia Ministry of Energy, Mines and Petroleum Resources

Report of Inspector of Mines (Issued pursuant to Section 15 of the Mines Act)

## MINERAL EXPLORATION

Name of Mine: H.B. MINE

Locality: Salmo, B.C.

Owner or Operator: Nu-Dawn Resources

Address:102 Piper Crescent Nanaimo, B.C. V9T 3G3

Manager: R. Carson

Areas Inspected: Sheep Creek Transformers

### Persons Contacted

Management: J. Wadsworth, Acting Mine Manager, Salmo Division

OHS Committee:

Workers:

A copy has been forwarded to the Joint Occupational Health and Safety Committee and/or the union. The mine manager shall complete the right hand column noting specific corrective actions taken, or to be taken by a specified date, and return a copy to the Inspector within 15 days of receiving the report. Further, he shall post a copy to the bulletin board.

Inspection Report	Manager's Response of Action Taken
The existence of four transformers, of probable 40 year vintage, perched across two poles near Sheep Creek was brough to EMPR's attention by E. Stockerl, MOE.	
Nu-Dawn Resources shall develop and implement on approval, a plan to safely remove, securely store, test and if required, suitably dispose of these four transformers. The plan shall be submitte to E. Stockerl, MOE with a copy to S. Wuschke, District Manager, LMPB, no later than June 13, 1994. This plan shall include the expected dates when this work is to take place.	
Copies To: MH&S Fernie, E. Stockerl, MOE, Jim Wadsworth	
Dennis Roach	Signatures
Inspector of Mines	Inspector
310 Ward St., Nelson, B.C. V1L 5S4	
Address	Manager
Date of Inspection: May 25, 1994	Dated: Page 55 , 19 EGM-2013-00163





October 30, 1997 File: 18040-02-07/HB/01 x M-85

Mr. Walter Kuit Manager, Environmental Affairs Cominco Ltd. 200 Burrard Street Vancouver, BC V6C 3L7

MINISTRY OF ENDL & INVESTMENT FILE

Nu-Dawn Resources Inc. 102 Piper Crescent Nanaimo, BC V9T 3G3

Dear Sir/Madam(s):

### Re: HB Mine Tailings Impoundment, Salmo, B.C.

According to our records the HB Mine near Salmo, B.C. is permitted under Mines Act Permit M-85 to Cominco, while mineral title and fee simple land is owned by Nu-Dawn Resources. Geotechnical inspections of the tailings impoundment were performed by the Mines Branch in April 1993 and June 1997. Attached you will find copies of these inspection reports.

On July 22, 1977 the Acting Chief Inspector of Mines approved construction of a spillway at the dam by letter addressed to Mr. J.S. Newman, P.Eng., Civil Engineer for Cominco. The spillway was never installed.

In summary, site conditions at HB Mine tailings impoundment have deteriorated and pose public safety and environmental hazards. The main concerns are that the impoundment was never decommissioned with a permanent spillway on closure and the current decant structure is deteriorating; the intake channel and structure are filling with debris and the discharge flume and channel on the downstream face are in need of repair. The integrity of the dam itself appears to be satisfactory except that there should be more freeboard. Overtopping and breaching of the dam or regressive erosion at the decant outlet is considered a distinct possibility in the foreseeable future.

.../2

Ministry of Employment and Investment Regional Operations, Health and Safety Branch Energy and Minerals Division Mailing Address: PO Box 9320 Stn Prov Govt Victoria BC V8W 9N3

Telephone: (250) 952-0462 Facsimile: (250) 952-0481 Location: 5th Floor, 1810 Blanshard Street Victoria

> Page 56 EGM-2013-00463

While it is unusual to have different entities as Permittee and Owner, you both have obligations to make the tailings impoundment safe, remove the hazard(s) and decommission the tailings site so the Mines Branch can close its file on the tailings impoundment. I must add that there are other safety concerns at the mill building which our health and safety inspectors will review next year after another safety inspection. Ultimately, Mines Branch wants to close all its files on the site and you should proceed with this in mind.

If you have any questions please do not hesitate to call me at (250) 952-0485 in Victoria. I would appreciate a response from you on this matter before the end of January 1998, with a plan to take appropriate action in the summer of 1998.

Yours sincerely,

Lin

Tim Eaton, P.Eng. Manager, Geotechnical Engineering

TE/tl

cc: Ricci Berdusco Andrew Whale

Attachments

121



Province of British Columbia Ministry of Employment and Investment

ENERGY AND MINERALS DIVISION

# REPORT OF GEOTECHNICAL INSPECTOR

(Issued pursuant to Section 15 of the Mines Act)

Name of Property:	HB Mine	File: 18040-02-07/HB/01
Location:	Salmo	
Mine Manager:	n/a	
Company: Address:	Cominco and Nu-Dawn as per cover letter	
Persons Contacted:	n/a	
Type of Mining:	Closed, u/g, base metal	
Date of Inspection:	June 10, 1997	

An inspection of the tailings impoundment was conducted in the company of Art O'Bryan. The previous geotechnical inspection was April 29, 1993. The following areas in particular were noted:

The upstream dam face (Photo 1) is in good condition with no evidence of effects from wave action. The dam crest and downstream slope (Photo 2) are also in good condition with no evidence of cracks, settlement, slumps or erosion. Vegetation cover (mainly grasses and legumes) is healthy and thick and an alder has started on the upstream face at waterline.

The downstream toe is wet in the same areas as observed in 1993 and the toe drains appear to be functioning satisfactorily. The grouted CMP (old decant outlet) near the central toe of the dam is dry and not showing any signs of leakage inside or outside of the pipe.

The operating decant or water control structure is structurally sound. However the inlet channel to the decant is completely full if cattails and the alders are much larger. Compare Photo 3 (April 29, 1993) and Photo 4 (June 10, 1997). The log at the entrance to the channel is still in place. However the concrete water level control beams have not been removed from inside the structure as ordered in my 1993 inspection, although I note that the wooden support posts for the upper beam appear to have been replaced with steel pipe. Note that the same number of concrete beams are resting on top of the control structure in both photos.

HB Mine Inspection Report Inspection of June 10, 1997 Page 2

A 900 mm CMP conducts water from the decant control structure to a drop structure (manhole) part way through the dam and another CMP from the drop structure to the downstream dam toe. The drop structure has had the steel cover secured so that we could not inspect inside and the steel plate has been removed from inside as ordered in my 1993 inspection.

The downstream outlet for the decant structure has had some minor improvements made to it, compare Photo 5 (April 29, 1993) and Photo 6 (June 10, 1997). The steel and fibreglass plume has been realigned and now carries the discharge water from the outlet CMP and discharges it into the drainage natural plunge pool, about seven metres away. However this outlet structure needs repair.

#### Discussion

The current arrangements at the dam require monitoring and maintenance to ensure satisfactory long term operation. The existing decant structure will eventually plug with debris with a potential dam breach the end result. The flume in the downstream outlet for the decant will topple out of place again in the near future. Discharge water will gradually erode and undermine the toe of the dam in this area.

As stated in my 1993 inspection report this tailings facility must be permanently decommissioned. An engineered spillway and outlet channel need to be designed and installed for the 1:200 year 24 hour flood or combination flood and freshet, whichever is determine to be the bigger event. Static stability must have a minimum factor of safety of 1.5 and seismic stability reviewed to satisfy the 1:475 year probabilistic event. In the event stability is inadequate the pond level should be further lowered by the new spillway to reduce risk and improve stability. If necessary the entire pond should be permanently drained from the impoundment by the spillway/outlet structure.

Tim Eaton, P.Eng. Manager Geotechnical Engineering

Date: October 30, 1997

F.\_\_\_ince of British Columbia 12000-02-07/42/01 Ministry of Energy, Mines and Petroleum Resources

Report of Inspector of Mines (Issued pursuant to Section 15 of the Mines Act)

## **GEOTECHNICAL - EIM**

Name of Mine: HB Mine

Locality: Salmo, B.C.

Owner or Operator: Nor-Quest Resources Ltd.

Address: 102 Piper Crescent Nanaimo, B.C. V9T 3G3

Mr. Raynerd Carson Manager:

Areas Inspected: Tailings Dam

**Persons** Contacted

Management: No one available.

The mine manager shall complete the right hand column noting specific corrective actions taken, or to be taken by a specified date, and return a copy to the Inspector within 15 days of receiving the report.

Inspection Report

Manager's Response of Action Taken

- Crest good, no settlement. 1.
- Upstream slope good, beach/ wave 2. action/ erosion minimal.
- Downstream slope covered with grass 3. and alder, wet zones at toe and several seeps, but no seeps were obvious on downstream slope face. Stability looks good; no sloughs, settlements, toe drains operating.
- 4. Piezometer standpipe near toe at centre of dam is dry to a depth of approx. (plumbed with small stone) 45-50 feet. Check Fig. 1 from Golder Brawner 74 report (Feb. 12, 1979 Rep# E/74/124) assume it to be BH 2 which is drawn at about 50 foot depth on the section so assume piezo is dry.

1. 6. 4
Kim TA LOW

105-525 Superior St. Victoria, B.C., V8V 1X4 Address

Date of Inspection: April 29, 1993

Copies To:

Tim Eaton, P. Eng. Geotechnical Manager

Signature - Manager

Dated:

Page 60 EGM-2013-00163

19

0- - 2

#### Inspection Report

Manager's Response of Action Taken

- Decant structure at E end looks 5. structurally sound, flow not impeded but bullrushes growing at inlet are being drawn into structure. Large log at entrance to outlet ditch is okay and prevents other debris from Inside the decant well passing. there are 2 concrete outlet water level control beams. One is raised approx. 18" and supported entirely by 2"x2"x4" on end which are rotting. This must be removed as soon as possible. The lower beam sits on the bottom and should be removed to create additional free board between dam crest to panel level.
- 6. Drop structure looks sound but water has flowed out of the MH as evidenced by recent erosion and flattened grass around the MH . A 1/4" steel plate inside the MH must be removed as soon as possible. It is fastened by rusting bolts to the concrete and will block the outlet when it falls.
- 7. The downstream decant outlet requires maintenance. A steel and fibreglass flume has partially collapsed and should be removed. There is some resulting erosion. The channel below the outlet should be armoured along a 15 m. stretch with rock larger than 300 m in diameter.
- Surface runoff shall be diverted from the crest of the dam, E end.
- 9. For abandonment, this facility requires a geotechnical inspection (annual report) and assessment of long term stability and capacity to accommodate 1:200 year 24 hour flood through a spillway structure. Recommendations shall be made in this report by a registered B.C. geotechnical engineer. Flood precipitation data shall be reviewed at this time. Seismic stability shall be reviewed for the 1:475 year. event.

Date of Inspection:

Initials:

Inspector

Manager Page 61 EGM-2013-00163




PHOTO 1



PHOTO 2





## РНОТО З



РНОТО 4







рното 5



рното 6

Page 67 EGM-2013-00163

Nor-Quest Resources Ltd. Kootenay Division: Box 369, Salmo, B.C., Canada, VOG 1Z0 Telephone (604) 357-2440 April 13, 19	MINISTRY OF ENERGY, MINES AND PETROLEUM RESOURCES FERNIE, B.C. APR 2.2 1988 FILE
Andrew Whale P.Eng., Inspector of Mines and Resident Engineer 310 Ward St., Nelson, B.C., VIL 5S4 RE: Tailings Pond Registration	MINISTRY OF ENERGY, MINES & PETROLEUM RESOURCES. NEC'D APR 20 1988
RE: Tailings Pond Registration NELSON, B.C.	NELSON, B.C.

Dear Sir;

Please find enclosed a completed copy of your "Questionnaire for Register of Tailings Dams in B.C."

Our H.B. Concentrator has been dormant for the past several years and as such, there has been no appreciable changes to the H.B. Tailings Dam and impoundment areas. We are, however, planning to proceed with our renovations and bring the facility to production capability during the summer of 1988. The actual production date has not been set and will depend upon the timely revival of the existing production permits as well as securing a reliable source of feed. The ore may be obtained from our own outside properties and/or from custom milling clients and since the details of these sources have not yet been formally defined, the preliminary mill circuits and intended throughputs are now only speculative. This information will be provided to your office as it becomes available.

We have recently conducted a survey of the tailings pond in order to assess the current capacity and future possibilities of this facility. Calculations and stability analysis are being carried out by Klohn Leonoff Consulting Engineers of Vancouver and once the final report is completed, I will forward a copy to your office for distribution.

Should you have any questions, please contact me at our Sheep Creek office.

Sincerely Nor-Quest Resources Ltd.

G. Carriere P.Eng. Division Manager

# QUESTIONNAIRE FOR REGISTER OF TAILINGS DAMS IN B.C.

.

•

1.	Desi	Designation:			
	(a)	Operation (Mine) H.B. Mill			
	(b)	Name of major impoundment <u>as above</u> (other than (a))			
	(c)	Name of major dam, if any <u>H.B. Tailings Dam</u> (no., location etc.)			
	(d)	Owner or Operator Nor-Quest Resources Ltd.			
	(e)	Engineer(s) or design firm Cominco Eng., Golder & Assoc.			
2.	Vici	cinity of operation:			
	(a)	Nearest town Salmo, B.C.			
	(b)	Drainage where major dam locatedSalmo River			
3.	Type	of emplacement ("X"):			
	(a)	Fluid discharge X of tailings:			
		<pre>(i) into gulley or valley X (ii) into sidehill containment (iii) into containment ringed by dykes (iv) into bowl or excavation</pre>			
۴	(b)	Dry stacked tailings:			
		<pre>(i) along a gulley (ii) along a ridge or terrace (iii) on a sidehill (iv) in a pile</pre>			
4.	Water	ater management or control ("X"):			
	(a)	Active emplacement			
,	(b)	Inactive emplacement X ( on Standby) (Underline applicable control methods: none, tower drain, <u>spiilway</u> , diversion, reclaimed surface, other.)			
5.	Impou	Impounded area up to the emergency discharge or spilling level (hectare)			
	(a)	present 20.68 ha, (b) ultimate 28.47 ha			

QUESTIONNAIRE FOR REGISTER OF TAILINGS DAMS IN B.C.

Page 2

6.	Storage capacity, including pond up to spillway (millions of cu. metres)
	(a) current 0.45 (avail) , (b) planned 1.59 (avail)
7.	Year that dam:
-	(a) started 1955 , (b) finished or expected completion ?
8.	Maximum height of dam above ground in metres:
	(a) currently 24.1m , (b) approved 28.7m
9.	Crest length of dam or dyke in kilometres:
	(a) present, (b) eventual0.26 km
10.	Foundations of dam ("X"):
	(a) Deposits: bedrock X till lacustrine fluvial
•	(b) Material type (rock, gravel, sand, silt, clay, peat) sandy-silt/gravel
	(c) Characteristics (strong, weak, pervious, etc.) strong
11.	Method of dam construction ("X"):
	(a) Upstream:
	i) mechanical raising ii) hydraulic lifts
	(b) Centreline or conventional:
	(i) zoned fill (ii) random
	(c) Downstream: X
. , I	<pre>(i) horizontal lifts (ii) inclined segmentsX</pre>
	(d) Combined
12.	Other pertinent details (abandoned, damaged, eroded, reworked, etc.):
	tailings impoundment is being maintained on a standby basis
	until a suitable ore source has been located
DATE	April 11, 1988 SIGNATURE
	Page 70 EGM-2013-00163



Ph: (250) 952-0475

June 17, 1997

File:	M-85
	14675-35-04

Mr. B. Baldigara Secretary, Assistant Administrator Regional District of Central Kootenay 601 Vernon Street Nelson, B.C. V1L 4E9



Dear Mr. Baldigara:

Re: H.B. Miné Tailings Impoundment

I have been asked to reply to your May 15, 1997 letter to Andrew Whale, Regional Manager, Ministry of Employment and Investment, regarding possible future liabilities associated with the H.B. tailings impoundment.

#### Status of Permits Covering the Tailings Impoundment

The mine is regulated under the Mines Act.

The mine, including the tailings impoundment, is covered by Permit M-85 issued to Cominco Ltd. (copy attached). However, they sold this property to David Minerals who subsequently went bankrupt, and the last record we have of an owner is Nu-Dawn Resources.

Over the years, in spite of numerous attempts to get the new owner to assume the responsibilities of the permit, Cominco still remains the permittee.

Cominco carried out considerable research in the early 1970's to determine the feasibility of establishing vegetation directly on the tailings material, and to determine the metal uptake in plants. That information is stored off-site and I do not have that information immediately available. I don't recall any major issues, however.

I could not find a closure plan and I don't believe that one was ever filed.

...2

Ministry of Employment and Investment Regional Operations, Health and Safety Branch Energy and Minerals Division Mailing Address: PO Box 9320 Stn Prov Govt Victoria BC V8W 9N3 Telephone: (250) 952-0462 Facsimile: (250) 952-0481 Location: 5th Floor, 1810 Blanshard Street Victoria

> Page 71 EGM-2013-00 63

#### Dam Safety

I have included Part 9 of our Health, Safety and Reclamation Code for Mines in British Columbia (Code). The owner and permittee have not satisified the requirements of part 9.2.4, 9.3.2 and 9.3.5 The obligations in this regard should be discussed with Tim Eaton, P.Eng., Manager, Geotechnical Engineering. At present there are no significiant dam safety issues, however some work is required.

Should the Regional District purchase this property, the tailings impoundment would still be regarded as part of a mine, albeit a closed mine, and regulated under the Mines Act. As such, there would still be requirements for maintenance, periodic inspections and monitoring. These requirements would likely not be onerous, however.

#### Contamination Level of the Liquid and Solid in the Tailings

This a potential concern especially in relation to the new Contaminated Sites Provisions of the Waste Management Act. Our own internal review several years ago made a preliminary assessment of acid rock drainage potential of these tailings and it was felt that the abundance of limestone which hosted this ore deposit was likely sufficient to prevent sulphide oxidation, and acid mine drainage from occurring. This needs to be confirmed through samples of tailings and seepage from the impoundment. If there is any metal release, it will be associated with neutral to alkaline drainage.

If you have any further questions or concerns, please do not hesitate to call either myself (250) 952-0470 or Tim Eaton (250) 952-0485.

Yours very truly,

Can Dowell

Mon John C. Errington, Ph.D., P.Ag. Manager, Reclamation and Permitting

JCE:ch Encl.

cc: Andrew Whale, Cranbrook Tim Eaton Fred Hermann

let-hb

INTEROFFICE MEMORANDUM

Created: 06-Aug-1997 01:51pm PDT Sent: 06-Aug-1997 02:13pm PDT From: Steve Wuschke of EI SWUSCHKE Title. Dept: Employment & Investment Tel No: 426-1655

TO: Tim Eaton of EI

( TEATON )

Subject: HB Tailings Dam - Discharge

Greetings

A land owner s.22 just called. Apparently the drainage from the decants / overflows goes into a ditch constructed in about 1950, to carrry away excess water. There were no easements or records that the land owner knows about for the ditch.

The land owner said that the dich overflowed and caused property damage and s.22

The land owner <u>s.22</u> would like the ditch to be removed and the drainage to be rerouted to a natural drainage route. Apparently the natural drainage was not able to handle the volumes of water when the mill was in operation.

I have not been to the site and don't know the hydraulic works associated with the dam structure. So perhaps you could provide me with some advise on this matter.

Land owner is: s.22

I suggested to the land owner that he should contact the Tailings pond owner which is NuDawn(?) and Cominco who may still have the permit. I don't know who is responsible for the tailings.

Thanks: Steve W.

## MEMORANDUM

FROM THE

## DEPARTMENT OF MINES AND PETROLEUM RESOURCES

Dept. of Mines & Petroleum Res.

Minister,

TO The Hon. L. Nimsick,

March 5 VICTORIA, B.C., .....

> WHEN REPLYING PLEASE REFER TO FILE No.

Re: Section 11, Mines Regulation Act. Cominco Ltd., H.B. Mine, Salmo, B.C.

The Advisory Committee on Reclamation, consisting of three representatives of the Department of Lands, Forests, and Water Resources, one from the Department of Recreation and Conservation, (the representative of the Department of Agriculture was unable to attend but submitted a covering memorandum), the Inspector of Mines - Reclamation, and with myself as Chairman, has studied the report submitted by Cominco Ltd., H.B. Mine, as appended hereto. The Committee has approved the report, with the additions and amendments as listed below.

A notice of the filing of the Cominco Ltd. H.B. Mine reclamation report as required by subsection 4 of Section 11 of the Act was published, for one insertion only, in the B.C. Gazette on Thursday, February 8, 1973, and in the Nelson Daily News and the Trail Times on Thursday, February 8, 1973.

The report is submitted for your approval, under subsection 5 of Section 11 of the Act, with the following additions and amendments:

1. That topsoil and overburden soil stripped from the surface shall be conserved, as feasible, for possible useage in the reclamation of disturbed areas.

> 2. That investigations and research be carried out covering: (a) the location, stability, and erosion control of waste dumps, tailing ponds, and stockpiles;

- (b) the protection of watercourses, as applicable;
- (c) the reclamation of disturbed areas;
- all to the satisfaction of the Chief Inspector of Mines.

3. That upon completion of the programme in (2) above, a plan and report describing in detail the reclamation and protection of the disturbed areas be submitted to the Chief Inspector of Mines for approval.

4. That the permit be valid for a period of five (5) years, or until approval of the report in (3) above, whichever is the sooner: the permit to be renewable upon application and upon evidence of satisfactory performance.

5. The total acreage to be disturbed during the planned life of the operation is 76.4 acres. Cost of reclamation is estimated at \$100 per acre. A bond in the amount of \$10,000 is recommended. approved Amunul

J.W. Peck, P.Eng., Page 74 Chief Inspector of Mines EGM-2013-00163

JWP:sl enc1.

H.B. MINE - SALMO, B.C.

Application for Permit Authorizing Surface Work

### I, INTRODUCTION

The H.B. Mine and concentrator is situated about seven miles south-east of the village of Salmo, B.C. on the North side of the Sheep Creek valley.

The property which was originally staked by Horton and Benson (hence H.B.) about 1907 was purchased by Cominco Ltd. in 1927. Intermittent work was carried out until 1946. Later, an extensive diamond drilling program was undertaken followed by underground exploration.

With sufficient ore outlined, construction of a 1000 ton/day concentrator was started in April of 1952 and completed in the spring of 1953. Due to unfavourable metal prices, operation did not commence until May, 1955 and was suspended in 1966. The mine is scheduled to resume production in early 1973.

The current head office address of Cominco Ltd. is 1199 West Pender Street, Vancouver 1, B.C.

### II. PRODUCTION PROGRAM

#### General

It is planned to treat up to 1200 tons of ore per day from an underground source, thereby producing separate lead and zinc concentrates which will be shipped to Cominco-owned smelters in Trail.

With current ore reserves it is expected that the mine will operate for 3 1/2 years.

### Nature of Mining and Milling Operations

(a) Geology

The main mineralization at the H.B. Mine consists of several zinc-lead sulphide ore bodies localized in the Reeves limestone member of the lower Hiab group of lower Cambrian age. The Reeves limestone has been thickened by folding to several times its original thickness. It has increased from an original thickness of 40' - 70' to a maximum of 700'. This bulge in the limestone member plunges 20° south and the ore bodies maintain their relative position in the lime band with a similar plunge. The main ore body, the No. 1 zone, is steeply dipping and varies from a depth of 400' in the northern section near 3500 level to about 10' at its southern tip where it reaches to within 200 ft. of the surface. Several other ore zones lie just to the west and below the crest of the No. 1 ore zone. The Garnet zone ore body, however, lies approximately 600' to the west of the main ore body and extends to the surface.

The chief economic constituents of the ore body are lead and zinc occurring as marmatite and galena in a gangue of cale, tremolite, limestone and dolomite. There are also considerable iron sulphides in the form of pyrite and pyrchotite.

### (b) Mining

The ore bodies will be mined from underground by both longhole and open stoping methods with a minimum of pillars remaining. No disturbance of the surface area is expected except for the Garnet Zone which will be extracted through to the surface. The final dimensions of the breakthrough will be about 1000' long by 70' wide by a maximum of 200' deep.

Access to the mine is through two main openings. The portal of the main entrance, the 2800 level haulageway, is situated about 300' above Sheep Creek and provides access from the main surface buildings. Most of the personnel and supplies are carried underground on this level and all the ore and waste is trammed out.

The 3500 level portal is located about 200' above Aspen Creek and provides access to the upper reaches of the No. 1 zone and to the hoist-room for the service shaft. Some material and a few personnel enter the mine through this opening. A third access of lesser importance, the 3300 portal, is located about the 2800 level portal and on the same slope.

Underground, the only ore tramming that is done is on the 2800 level. This is done by a Ruston-Hornsby diesel locomotive pulling eleven 6-ton cars from various areas and dumping at the coarse ore bin located on surface about 340' east of the portal. All other ore and waste movement underground is effected by 20 to 60 H.P. air or electric slushers and by gravity through a system of ore passes down to the 2800 level.

The waste produced underground is generally a limestone or dolomite with sizes ranging from 1/2 inch to 24 inches. A portion of this waste is disposed of underground into accessible mined out stopes and the remainder is removed to surface via the 2800 level portal. On surface, a waste dump has been established east of the coarse ore bin, along the hillside and extending about 500 feet along the hill and 150 feet down the slope. The resulting talus slope rests at an angle of repose of about 40° and is about 200 ft. across, from the toe to the side of the hill.

There is also an established waste dump below the 3500 level portal that may be used in future to dispose of waste from planned development of an ore body north of the service shaft and extending above the 3500 level. The expected annual waste production is about 6000 tons.

### (c) Milling

Milling of the H.B. ore is straightforward with production of separate lead and zinc concentrates. Open-circuit primary and secondary crushing is followed by open-circuit rod milling and closed circuit ball milling. The talc and tremolite which are readily floatable are floated out first to avoid contamination of the lead concentrate. This is followed by lead rougher flotation and zinc rougher flotation. The final concentrates, about 100 tons/day, are thickened, filtered and then shipped to the smelters. The talc concentrate joins the zinc rougher tails and goes to waste.

The mill waste, about 1100 tons per day of solids, flows by gravity to a surge box, some 30 feet below the mill level, from where it crosses the Sheep Creek Valley through a "U-tube". The tailings drop 180 feet down the north arm of the "U-tube" to the creek level and go up the south arm some 120 feet where it discharges to a wooden flume. The "U-tube" is of 7" wood stave pipe and approximately 750 feet in length.

The wooden flume, of which 100% has been rebuilt, carries the tailings some  $2 \ 1/2$  miles to the west to a settling pond. The tailings pond is a small depression about 1/2 mile wide by 3/4 mile long, ringed on three sides by steeply dipping hillsides and an earth fill dam on the fourth. Clear overflow is handled by a 30 inch culvert pipe through the dam with a vertical intake of 3 x 12 timber cribbing. The cribbing as well as the earth fill dam is raised as required. The clear decant water is discharged from the culvert into a ditch and flows by gravity to the Salmon River. It is estimated that the tailings area will increase in area from about 60 acres to 69 acres in the  $3 \ 1/2$  years of project operation.

### (d) Disturbed Land Area

Land area disturbed by mining and milling activity is summarized.

2800 level waste dump	2.2 acres
3500 level waste dump	0.2 acres
Tailings disposal pond	60.0 acres
Buildings and Service area	10.0 acres
Roads	4.0 acres
	76.4

### III. NATURE AND PRESENT USE OF LAND

The Sheep Creek valley is bounded on the north and south by steep mountain slopes. Relief in the area of the mine extends from 2500 to over 5500 feet. Elevation of the tailings pond is 2200 feet.

The valley is situated in the Western larch subzone of the Interior Western Hemlock biogeoclimatic zone which is characterized by total annual precipitation in the range 22-35''(1). Zonal soils include orthic ferro-humic podzol developed on shallow glacial deposits over bedrock.

Land on the south facing mountain slope surrounding the mine complex includes areas of productive and non-productive woodland<sup>(2)</sup>. Immature stands of trembling aspen, lodgepole pine and Douglas fir occupy medium quality productive sites<sup>(3)</sup>. Fire destroyed forest cover over part of the area in 1905 and in 1925. The tailings pond occupies a depression bounded on the west by unproductive land (rock) and by productive woodland in other directions<sup>(2)</sup>. Productive woodland has a cover of immature western larch with minor Douglas fir, lodgepole pine and white pine on medium quality sites<sup>(3)</sup>. Fire destroyed forest cover on part of the area in 1925.

Land surrounding the mine and tailings pond has been classified with respect to physical capability for use by agriculture, forestry, recreation, big game and waterfowl<sup>(2)</sup>. Classification was based on data from surveys conducted under the Canada Land Inventory program. Physical capability of land at the H.B. Mine for each use group listed is summarized.

### 1. Agriculture

- (a) Mine: land has severe limitations for agricultural use due to adverse topography, shallowness to bedrock and climate.
   80% of land possesses no capability for arable culture or permanent pasture. 20% is capable only of producing perennial forage crops. Improvement practices are not feasible.
- (b) Tailings pond: land has severe limitations for agricultural use due to adverse topography, stoniness and climate. 40% of land possesses no capability for arable culture or permanent pasture. 60% is capable only of producing perennial forage crops. Improvement practices are considered feasible.

### 2. Forestry

- (a) Mine: land has moderate to severe limitations to growth of commercial forest. Growth limiting factors include restriction of rooting zone by bedrock and soil moisture deficiency. A small area has severe limitations which preclude growth of commercial forests.
- (b) Tailings pond: land has slight (60%) to moderate (40%) limitations to growth of commercial forest. Growth may be limited by restriction of rooting zone by bedrock and soil moisture deficiency.

### 3. Recreation

(a) Mine and tailings pond: land lacks natural capability and significant features to rate higher than low capability for outdoor recreation, but has natural capability to engender and sustain low annual use based on dispersed activities such as hiking, nature study or for aesthetic appreciation. Land possesses continuous streams in upland areas and vegetation possessing recreational value.

### 4. Ungulates

(a) Mine and tailings pond: land classed as winter range of moderately high capability for deer and moose. Productivity may be reduced in some years due to excessive snow depth that reduces mobility of ungulates and availability of food plants.

### 5. Waterfowl

(a) Mine and tailings pond: capability for production of waterfowl is negligible or nonexistent due to adverse topography.

### IV. RECLAMATION PROGRAM

Land disturbance at the H.B. Mine will be kept to a minimum by utilizing existing waste rock and tailings disposal areas. Upon completion of mining operations, disturbed areas will be reclaimed to an appearance and use compatible with surrounding areas.

Currently in British Columbia mined land reclamation practices are not well established nor are conditions limiting plant growth on mine and mill waste well defined. To provide basic information for preparation of a reclamation program for the H.B. Mine, a research program is proposed. The general research approach is summarized:

- 1. characterize the nature of mine and mill waste by field inspection, sampling and analysis of chemical and physical properties which influence growth,
- 2. evaluate the suitability of mine and mill waste as a growth medium for plants using laboratory and growth chamber techniques,
- 3. when areas of mine and mill waste become final, initiate field investigations to determine physical treatments, plant species, planting techniques, fertilizer requirements and soil amendments necessary to establish and maintain suitable plant cover on waste disposal areas.

#### V. REFERENCES

(1) Krajina, V.J., 1969, Ecology of Forest Trees in British Columbia In Ecology of Western North America, Vol. 2, No. 1. Published by the Department of Botany, University of British Columbia.

 (2) Canada Land Inventory, Land capability analysis sector maps of Salmo area for agriculture, forestry, recreaction, ungulates, waterfowl and present land use.
 B.C. Map Librarian, B.C. Dept. of Agriculture, Victoria.

> and Canada Land Inventory: Objectives, Scope and Organization: Report No. 1, 1970. Dept. of Regional Economic Expansion, Queen's Printer, Ottawa.

(3) Forest Cover Map:

p: Salmo PSYU, 1962. Surveys Division, B.C. Forest Service, Victoria, B.C.

RTG:car January 5, 1973 Pages 80 through 287 redacted for the following reasons: Not Responsive

	omineo
AND	DEPT. OF MINES PETROLEUM RESOURCES
Rec'd	JAN 291976
1/1	

)

Mines

Mr. J. D. McDonald Senior Reclamation Inspector Department of Mines and Petroleum Resources 1835 Fort St. Victoria, B.C. V84 IJ6

)

January 27, 1976

Dear Mr. McDonald:

Enclosed is our Progress Report on Land Reclamation at our H.B. Operations.

Yours sincerely,

H. G. Barker Superintendent

HGB:mf1

Enclosure

### Mined-Land Reclamation at Cominco Ltd.

H.B. Operations Salmo, B.C.

Progress Report 1975

R.T. Gardiner, P.Ag. Reclamation Agronomist

J.E. Stathers Assistant Reclamation Agronomist

Cominco Ltd. Trail, B.C.

## Table of Contents

## Mined-Lend Reclamation at Cominco Ltd. - H.B. Operations

Salmo, B.C.

## Progress Report 1975

		Page
1.	Introduction	1
2.	Mining Program	1
3.	Reclamation Research	
	3.1 Suitability of H.B. Tailings as a Liming Material	1
	3.2 Climatic Conditions During 1975	2
4.	Operational Reclamation	2
5.	Proposed Research and Operational Reclamation Programs	
	for 1976	2
6.	References	2
7.	List of Tables	3

Mined-Land Reclamation at Cominco Ltd.

H.B. Operations

### Progress Report 1975

#### 1. Introduction

The general approach to reclamation of disturbed land surfaces at H.B. Operations is to improve growth conditions on waste disposal and other disturbed land areas and to encourage succession of native vegetation. Establishment and maintenance of an initial vegetative cover of grass and legume species will accelerate soil formation, control erosion, provide forage for wildlife, and improve the aesthetic appearance of disturbed land surfaces.

### 2. Mining Program

Land areas disturbed at H.B. Operations were described in "Application for Permit Authorizing Surface Work - Cominco Ltd., H.B. Operations, January, 1973", and the "Mined-Land Reclamation Research Report 1974"(1,2). Mining operations in 1975 conformed to the plans outlined in the original permit application. During 1975 construction of access roads to surface diamond drilling sites disturbed 0.7 acres. Land disturbed in construction of the lift to the tailings dam was inspected by Mr. Art O'Brien, Reclamation Inspector, on October 7, 1975. Improvement of drainage along the access road has been completed as suggested. Revegetation of the borrow pit will be carried out when more definite information related to future construction of the tailings dam and further disturbance to the borrow pit area is available.

The nature and extent of land surfaces disturbed to the end of 1975 are summarized in Table 1.

#### 3. Reclamation Research

### 3.1 Suitability of H.B. Tailings as a Liming Material

The feasibility of using calcareous H.B. tailings as a liming material for neutralization of acidic mill waste at Sullivan Operations has been investigated since 1973(3). Mixing H.B. tailings at 25% by weight with oxidized iron and siliceous tailings reduced salt concentrations and maintained the pH within a range tolerated by most plant species for a period of 20 weeks in growth chamber studies.

The cost of commercial liming materials varies with purity (content of magnesium and heavy metals), degree of fineness or particle size, and calcium carbonate equivalence or neutralizing capacity. In 1975 a study was carried out to determine the suitability of calcareous tailings from three Cominco Ltd. operations as liming materials (unpublished report by Stathers and Gardiner, 1975). H.B. tailings has a particle size and calcium carbonate equivalence (the major factors affecting rate of neutralization in an acid medium) comparable to agricultural grade dolomitic limestone. The total lead and zinc content of H.B. tailings is high relative to agricultural grade dolomitic limestone (Table 2).

#### Climatic Conditions During 1975 3.2

A summary of weather data recorded during 1975 at the B.C. Forest Service weather station located approximately 10 miles north-west of the H.B. mine is presented (Table 3). Precipitation during the 1975 growing season (May through September) was 283.2 mm. The period May through September 1975, had a mean monthly temperature of 13.9°C. The frost free period was 101 days, occurring between June 9 and September 18.

#### 4. **Operational Reclamation**

In April 1974, approximately 2 hectares of road cut embankments were hydroseeded in an attempt to reduce surface creep and erosion(2). Maintenance fertilizer the equivalent of 66 Kgm/ha was applied to hydroseeded areas on April 29, 1975. Subjective evaluation of vegetative growth in September, 1975 indicated that where adequate plant populations had established plant growth was vigorous. Limitations to plant growth appeared to be caused by instability of steeply sloping embankments and soil moisture deficiency, rather than nutrient deficiency. On steeply sloping road cuts constructed through coarse-textured material vegetative cover was sparse. On gradually sloping embankments composed of finertextured material, and seepage sites, vegetative cover was satisfactory.

#### Proposed Research and Operational Reclamation Programs for 1976 5.

Reclamation research investigations planned for H.B. Operations during 1976 will include:

- establishment of field experiments on shallow tailings deposited a) adjacent the tailings pipeline
- b) continuation of growth chamber studies to determine cultural techniques and plant species for revegetation of tailings and tailings slimes.

#### 6. References

(1) Barker, H.G., 1973. Application for permit authorizing surface work -Cominco Ltd., H.B. Operations, Submitted to Senior Inspector of Mines, Reclamation, Dept. of Mines and

(2) Gardiner, R.T., 1975. Mined-Land Reclamation Research at H.B. Operations, Progress Report 1974, Submitted to Senior Reclamation Inspector, Dept. of Mines and Petroleum Resources, Parliament Buildings, Victoria, January 31, 1975.

Petroleum Resources, Parliament Buildings, Victoria.

(3) Gardiner, R.T., 1975. Mined-Land Reclamation Research at Sullivan Operations, Progress Report 1974, Submitted to Senior Reclamation Inspector, Dept. of Mines and Petroleum Resources, Parliament Buildings, Victoria, January 31, 1975.

7.	Lis	t	of	Tab:	les

Table 1: Disturbed Land at H.B. Operations

Table 2: Characterization of H.B. Tailings as a Liming Material

Table 3: Weather Summary for 1975.

## Table 1: Disturbed Land at H.B. Operations

Nature of Distur	Area (Hectares)			
Waste rock dumps:	2800 level 3500 level	0.9 0.1		
Open pit	2.4			
Tailings impoundme	int	24.8		
Buildings and serv	vice area	1.6		
Roads		2.3		
		34		

Property	H.B. Tailings	Agricultural Dolomitic Limestone
Particle Distribution (%)		
mesh size _4 _8 _20 _40 _60 _80 _100	100 100 99.4 98.3 98.0 96.7 94.6	100 100 87.5 80.5 62.5 42.3 26.8
CaCO <sub>3</sub> Equivalence (%)	84	87
Total Pb content (ppm)	445	80
Total Zn content (ppm)	3000	225

Table 2: Characterization of H.B. Tailings as a Liming Material

### Table 3:

Weather	Summary	for	the	Year:	1975	
Station	B.C.	Fores	t S	ervice,	Salmo,	B.C.

		Temp	erature	Precipitation				
Month	and the second se	ans		Extremes		Rain	Snow	Total
-	Max	Min	Mean	Max	Min	0001		<u>mm</u>
Jan	-2.3	-11.3	-6.8	4.4	-23.3	5.59	111.51	117.09
Feb	1.4	-10.7	4.6	7.2	-23.3	25.40	86.61	112.01
Mar	5.3	-5.5	-0.1	8.3	-13.9	205.99	25.91	231.90
Apr	11.8	-3.3	4.2	20.0	-12.8	36.30	1	36.30
May	18.8	0.7	9.7	28.3	-7.2	38.10	-	38.10
Jun	21.1	6.0	13.5	28.9	0	71.88		71.88
Jul	28.4	10.6	19.5	37.7	1.7	69.34		69.34
Aug	23.1	7.9	15.5	31.1	3.9	94.74	-	94.74
Sep	23.1	3.5	11.6	27.8	-0.6	9.14	-	9.14
Oct	9.6	1.5	5.6	25.0	-5.6	143.00	5.59	148.59
Nov	4.1	-5.4	-1.0	16.7	-13.3	83.30	-	83.30
Dec	n.a.	n.a.	n.a.	n.a.	n.a.	n.a.	n.a,	n.a.

<sup>1</sup> In rainfall equivalents: 1 cm snow = 1 mm rain

Mean annual temperature: n.a. Mean monthly temperature: January -6.8°C Mean monthly temperature: July 19.5°C 4 Months above 10°C: 4 Months below 0°C: Months above 4.5°C: 6 Frost free days (period): June 9 - Sept. 18 (101 days) Total annual precipitation: n.a. Annual snowfall: n.a. Season occurrence of ppt: Wet season n.a. Wettest month n.a. Dryest season n.a. Sept. (9.14 mm) Dryest month

> Page 295 EGM-2013-00163

0500032

Province of British Columbia Ministry of Employment and Investment

**ENERGY AND MINERALS DIVISION** 

# REPORT OF GEOTECHNICAL INSPECTOR

(lesued pursuant to Section 15 of the Mines Act) Name of Property: HB Mine Trailing Pond File: 18040-02-07/HB Location: Salmo, β<. new Mine Manager: nta: un home · Vancomm??? Cominco?? Nu Dawn Company: Address: 222 Persons Contacted: n/a Type of Mining: Closed, u/g, base metal Date of Inspection: June 10, 1997

An inspection of the tailings impoundment was conducted in the company of Art O'Bryan. The previous geotechnical inspection was April 29, 1993. The following areas in particular were noted:

The upstream dam face (Photo 1) is in good condition with no evidence of effects from wave action. The dam crest and downstream slope (Photo 2) are also in good condition with no evidence of cracks, settlement, slumps or erosion. Vegetation cover (mainly grasses and legumes) is healthy and thick and an alder has started on the upstream face at waterline.

The downstream toe is wet in the same areas as observed in 1993 and the toe drains appear to be functioning satisfactorily. The grouted CMP (old decant outlet) near the central toe of the dam is dry and not showing any signs of leakage inside or outside of the pipe.

The operating decant or water level control structure is structurally sound. However the inlet channel to the decant is completely full if cattails and the alders are much larger. Compare Photo 3 (April 29, 1993) and Photo 4 (June 10, 1997). The log at the entrance to the channel is still in place. However the concrete water level control beams have not been removed from inside the structure as ordered in my 1993 inspection, although I note that the wooden support posts for the upper beam appear to have been replaced with steel pipe. Note that the same number of concrete beams are resting on top of the control structure in both photos.

A 900 mm CMP conducts water from the decant control structure to a drop structure (manhole) partway throught the dam and another CMP from the drop structure to the downstream dam toe. The drop structure has had the steel cover secured so that we could not inspect inside and the steel plate has been removed from inside as ordered in my 1993 inspection.

The downstream outlet for the decant structure has had some minor improvements made to it, compare Photo 5 (April 29, 1993) and Photo 6 (June 10, 1997). The steel and fibreglass plume has been realigned and now carries the discharge water from the outlet CMP and discharges it into the drainage natural plunge pool, about seven metres away.

, <u>Discussion</u>

In couri Retta to Comico??/

, fontit no ??

Cominco is still the Permittee and was the last owner/operator. The acting Chief Inspector approved the construction of a spillway July 22, 1977 by Cominco.

The current arrangements at the dam require monitoring and maintenance to ensure satisfactory long term operation. Without maintenance the current decant structure will eventually plug with debris with a potential dam breach the end result.

As stated in my 1993 inspection report this tailings facility must be permanently decommissioned. An engineered spillway and outlet channel need to be designed and installed for the 1:200 year 24 hour flood or combination flood and freshet. Static stability must have a minimum factor of safety of 1.5 and seismic stability reviewed to satisfy the 1:475 year probabilistic event.) In the event stability is inadequate the pond level should be further lowered by the new spillway to reduce risk and improve stability. If necessary the entire pond should be permanently drained from the impoudment by the spillway structure.

much a verin of boys.

Tim Eaton, P. Eng. Manager Geotechnical Engineering Date: June 18, 1997

Date:

Signature - Manager

Written response is required by the Mine Manager 15 days after receiving this report

cc: Andrew Whale (2-copies), Art O'Bryan

Page 297 EGM-2013-00163 \*\* TOTAL PAGE,003 \*\*

;	A PETROLEUM RESOURCES. REC'D MAY 0 6 1993 (Issued pursuant to Section 1)	Dr OT MINES	9
	NELSON, B.C. GEOTECHNICAL	L-EIM	(
Name	of Mine: HB Mine	Locality: Salmo, B.C	•
Owne	r or Operator: Nor-Quest Resources Ltd.	Address: 102 Piper Crescent Nanaimo, V9T 3G3	в.С
Mana	ger: Mr. Raynerd Carson	Areas Inspected: Tailings Dam	
Then	gement:No one available. nine manager shall complete the right hand column notion by a specified date, and return a copy to the inspector	ing specific corrective actions taken, or t within 15 days of receiving the report.	o be
	Inspection Report	Manager's Response of Ac	ion Ta
1.	Crest good, no settlement.		
2.	Upstream slope good, beach/ wave action/ erosion minimal.	re l	
3.	Downstream slope covered with grass and alder, wet zones at toe and several seeps, but no seeps were obvious on downstream slope face Stability looks good; no sloughs settlements, toe drains operating.	id re	
4.	Piezometer standpipe near toe at centre of dam is dry to a depth of approx. (plumbed with small stone 45-50 feet. Check Fig. 1 from Golder Brawner 74 report (Feb. 12, 1979 Rep; E/74/124) assume it to be BH 2 which is drawn at about 50 foot depth of	of er of ch	
	the section so assume piezo is dry.		
	the section so assume piezo is dry.		
Cople	·		
<u>Tim</u>	·	Lim Caton Signature - Inspector	
Geot 105-	sTo: <u>Eaton, P. Eng.</u> cechnical Manager -525 Superior St. Victoria, B.C.,	Lim Caton Signature - Inspector	
<u>Tim</u> Geot 105-	sTo: Eaton, P. Eng. Sechnical Manager 525 Superior St. Victoria, B.C., 1X4	Signature - Manager	

of Inspector of Mines · Page 2 of 2

### Inspection Report

Manager's Response of Action Taken

- Decant structure at 15.  $\mathbf{E}$ end looks structurally sound, flow not impeded but bullrushes growing at inlet are being drawn into structure. Large log at entrance to outlet ditch is okay and prevents other debris from passing. Inside the decant well there are 2 concrete outlet water level control beams. One is raised approx. 18" and supported entirely by 2"x2"x4" on end which are rotting. This must be removed as soon as possible. The lower beam sits on the bottom and should be removed to create additional free board between dam crest to panel level.
- 6. Drop structure looks sound but water has flowed out of the MH as evidenced by recent erosion and flattened grass around the MH . A 1/4" steel plate inside the MH must be removed as soon as possible. It is fastened by rusting bolts to the concrete and will block the outlet when it falls.
- 7. The downstream decant outlet requires maintenance. A steel and fibreglass flume has partially collapsed and should be removed. There is some resulting erosion. The channel below the outlet should be armoured along a 15 m. stretch with rock larger than 300 m in diameter.
- 8. Surface runoff shall be diverted from the crest of the dam, E end.

9. For abandonment, this facility requires a geotechnical inspection (annual report) and assessment of long term stability and capacity to accommodate 1:200 year 24 hour flood through a spillway structure. Recommendations shall be made in this report by a registered B.C. geotechnical engineer. Flood precipitation data shall be reviewed at this time. Seismic stability shall be reviewed for the 1:475 year. event.

.

Date of Inspection:

Initials:

Manage EGM-2013-00163

・スペーマーム Par 19日で - 19月1日 - 19日です。 - 19月2

1050-19



# **Golder Brawner Associates**

CONSULTING GEOTECHNICAL ENGINEERS

REPORT TO COMINCO LTD. ON SITE INVESTIGATION AT EXISTING H.B. MINES TAILINGS POND

B.C.

SALMO

Distribution:

4 copies - Cominco Ltd. Trail, British Columbia

2 copies - Golder Brawner & Associates Ltd. Vancouver, British Columbia

January, 1974

V 73218

Court 1969

GOLDER, BRAWNER & ASSOCIATES LTD., 224 WEST 8th AVE., VANCOUVER, B.C., V5Y 1N5 CANADA PHONE: (604) 879-9266

SOIL MECHANICS - FOUNDATIONS - GEOTECHNICAL SURVEYS - EARTH DAMS - LANDSLIDES - ROCK SLOPE STABILITY PAVEMENT EVALUATION - SOIL STABILIZATION - AIR PHOTO INTERPRETATION



# **Golder Brawner Associates**

CONSULTING GEOTECHNICAL ENGINEERS

E/74/124

February 12, 1974

Cominco Ltd., Engineering Dept., Trail, B.C.

ATTENTION: Mr. D. Boyle, P.Eng.

RE: H.B. Tailings Dam Salmo, B.C.

Dear Sir:

Enclosed please find 4 copies of amended text and drawings for our January, 1974 report on the above project. Also included are 3 complete copies of the amended report.

Yours very truly,

GOLDER BRAWNER & ASSOCIATES LTD.

B. Thompson

BT/jm V73218

Encl.

GOLDER, BRAWNER & ASSOCIATES LTD., 224 WEST 8th AVE., VANCOUVER, B.C., V5Y 1N5 CANADA • PHONE: (604) 879-9266 Page 804: 04-508800 EGM-2013-00163



# **Golder Brawner Associates**

CONSULTING GEOTECHNICAL ENGINEERS

January 2, 1974

Cominco Ltd., Engineering Dept., Trail, B.C.

ATTENTION: Mr. D. Boyle

Re: Site Investigation at Existing H.B. Mines Tailings Pond, Salmo, B.C.

Dear Sir:

As requested by your Purchase Order No. HB 15017 dated October 26, 1973, and in accordance with our proposal of September 20, 1973, we have carried out a detailed drilling program at the above site. The purpose of this investigation was to determine the condition of the existing dyke and foundation soils to enable a detailed stability analysis to be carried out. This report is further to our report No. V 72109 of June, 1973.

### FIELD INVESTIGATION

Three boreholes were drilled at the site between October 29, 1973 and November 1, 1973 using a truck-mounted rotary drill rig. These boreholes were drilled to depths varying from 45 to 85 ft. and extended approximately 20 ft. into bedrock. One borehole was drilled from the crest and two boreholes from the lower slope of the existing tailings dyke as shown on Fig. 1. Stan-

GOLDER, BRAWNER & ASSOCIATES LTD., 224 WEST 8th AVE., VANCOUVER, B.C., V5Y 1N5 CANADA • PHONE: (604) 879-9268 302 322 223 42508800

dard split spoon samples were obtained of the overburden and wash samples of drill cuttings were obtained of the bedrock. All samples were identified in the field and returned to our laboratory for classification and testing.

Perforated plastic standpipes were installed in the open boreholes to enable groundwater levels to be monitored.

### SITE CONDITIONS

The existing tailings pond is located approximately 4 miles south of Salmo, B.C. The tailings dyke is located at the southern end of a valley and has been constructed 50 to 60 ft. high using borrow fill obtained from the abutment slopes. Contours of the downstream face of the dyke together with a typical cross section are shown on Fig. 1.

The borehole results indicate that the dyke is generally comprised of soft to firm brown sandy silt containing varying amounts of medium to coarse sand and fine gravel. Standard penetration test results gave average 'N' values of the order of 10 blows/ft. indicating a loose to compact state of relative density.

Examination of the overburden samples enabled an approximate estimate of the location of original ground surface beneath the dyke fill. The approximate location of the existing ground surface is shown on Fig. 2. In borehole 1, the natural ground surface was estimated to be located approximately 59 ft. below the crest of the dyke. Underlying the fill, a 4 ft. thick stratum of very dense silty till was identified overlying a 5 ft. thick layer of hard desiccated silt. Bedrock was encountered at approximately 68 ft. below the crest of the dyke.

In borehole 2, the original ground surface was estimated as being located approximately 27 ft. below the dyke fill surface. The boreholes en-

Page 303 EGM-2013-00163

### **GOLDER, BRAWNER & ASSOCIATES**

2.

countered a 7 ft. thick stratum of soft to firm silt beneath the fill. Underlying the silt, a 2 ft. thick layer of sand and gravel was identified overlying bedrock.

In borehole 3, the original ground surface was estimated to be located approximately 20 ft. below the fill. The borehole encountered a 3 ft. thick stratum of dense silty till beneath the dyke fill. Underlying the silt, a 3 ft. thick layer of sand and gravel was identified overlying bedrock.

More detailed descriptions of the soil conditions are given on the Record of Boreholes. A cross section showing the inferred soil stratigraphy is shown on Fig. 2.

### GROUNDWATER CONDITIONS

The standpipes installed in the boreholes were monitored for approximately 4 weeks after installation to enable the water levels to stabilize. From the recorded water levels, we have inferred the phreatic surface in the dyke to be located as shown on Figure 2.

Inspection of the dam during the period of the drilling program indicated that seepage was occurring near the toe of the upper slope of the dam and at each abutment. Soft saturated soil was observed at several locations in the middle slope of the dam and very soft saturated soil was encountered at the east abutment.

This seepage and degree of saturation was not observed at the time of the original site investigation in May 1972. The occurrance of seepage above the phreatic line as inferred from the standpipe levels is believed to be caused by local variations in the permeability of the dam material. The location of the phreatic line is expected to vary somewhat across the dam.

> Page 304 EGM-2013-00163

### **GOLDER, BRAWNER & ASSOCIATES**

### DYKE STABILITY

The investigation has indicated that the existing dyke has been constructed essentially with silty soils which have been placed in a loose condition. The design parameters used in our previous calculations are considered to be still applicable although the phreatic surface assumed in our original report appears to have been somewhat lower than now exists. This present condition may be a result of a change in ponded water level upstream. Stability calculations for the present condition indicate a safety factor against a shearing type failure of the order of (1,3) which is considered adequate.

It is understood that it is proposed to eventually raise the pond water level to a maximum elevation of 2502 ft. behind the existing dam. As the pond water level is raised, the phreatic surface will also rise. Stability calculations for these future conditions indicate a factor of safety against a shearing type failure of the order of 1.1 which is lower than is normally acceptable. To increase the dyke stability, it is recommended that a berm be constructed on the downstream section of the dam as shown on Fig. 3. Provision of this berm will increase the factor of safety to approximately 1.3 which is adequate.

### SEEPAGE

At present, seepage is occurring at the intersection of the upper and middle slope of the dyke and at the abutments. Examination of this seepage during the drilling program indicated that the flow was clear and did not appear to be carrying any soil particles. However, the dyke is essentially homogeneous and has been constructed with silty soils which are most susceptible to internal backward erosion. The potential for this type of erosion will increase as the ponded water level is raised. To provide protection against internal backward

> Page 305 EGM-2013-00163

### **GOLDER, BRAWNER & ASSOCIATES**

erosion, filter material should be placed on the downstream slope of the dyke. This can be accomplished by constructing the previously recommended stability berm (Figure 3) of a suitable filter material which satisfies the gradation requirements shown on Figure 4. It is possible that mine waste rock will be suitable.

The berm should be adequately compacted to provide the required strength for support of possible future dyke extensions, yet should not be over-compacted so as to reduce its permeability. Generally, if heavy equipment is available and if the gradation of the filter material tends to be towards the coarser fraction of the range shown on Figure 4, satisfactory compaction without excessive reduction in permeability will be achieved by spreading the material in 16 in. lifts using a heavy crawler tractor.

We would be pleased to provide more specific construction details when the gradation of material and type of construction equipment are known.

To accommodate the seepage at the abutment, a filter blanket should be placed at these locations as shown on Fig. 3. This blanket should consist of similar filter material to that described above and should have a minimum thickness of 2 ft. This filter material should also be placed as described above.

It is pointed out that the specification given above for the filter material is critical if the filter blanket is to perform satisfactorily. As a result, we recommend, that when potential sources of material have been established, that we review the suitability of the material. In addition during raising of the ponded water level to elevation 2502, we recommend that the dyke be inspected by a member of our staff to ensure that the filter blanket is performing as desired.

5.

### **GOLDER, BRAWNER & ASSOCIATES**

At the time of the drilling, examination of the upper face of the dyke indicated that some surface erosion had occurred due to water ponding on the crest of the dyke and flowing downstream. It is recommended that these slopes be renovated by using granular material. In addition some surface grading should be carried out on the crest of the dyke to prevent ponding of rain water. During this work the crest could be sloped inwards towards the pond in order to direct run-off in that direction.

### FUTURE DYKE EXTENSION

If the height of the existing dyke and pond level are increased in the future to elevations 2511 ft. and 2508 ft. respectively, the crest of the dyke should be raised by placing additional fill on the crest and on the downstream slope. In addition, the filter material recommended above should be extended as shown on Fig. 5 to a maximum elevation of 2500 ft. The additional filter material should be placed as previously recommended while the fill material should be placed in horizontal lifts of 12 inch maximum and compacted to at least 95 per cent of Standard Proctor Density.

We trust that this is the information you require. We would be pleased to discuss the report in more detail should you desire.

> Yours very truly, GOLDER BRAWNER & ASSOCIATES LTD.

3' diff


1. del link


R.M. Wilson, P.Eng.


H. Oran H.H. Hawson, P HENHAWSO Page 307 EGM-2013-00163


RIM/HIH/sm V73218


GOLDER. BRAWNER & ASSOCIATES


















.



Page 315 EGM-2013-00163 I-B tk

.

PROJECT No. 123218

SOIL PROFILE SAMPLES		DYNAMIC PENETRATION RESISTANCE	COEFFICIENT OF PER		-				
LEVN. DESCRIPTION		æ	w	L Z	BLOWS/FT	CM / SE	c.	TIONAL	
		NUMBER	TYPE	BLOWS	SHEAR STRENGTH CU, LB. /SQ. FT	WATER CONTENT,	PERCENT	ADDITIONAL AB. TESTING	STANDPIPE
	STRAT	-		<u> </u>	+ + + + + + + + + + + + + + + + + + + +			A	
GR SURFACE.	+						- 1 - T		1
		-	z	250	2				
			D.0	"					
		2	0.0	11.575					
		3	00	14 2490					
SOFT TO FIRMAN		4	200	5					
BROWN SAND		5	50	5 2480					W.L 23.0' NOV. 23, 197.
SOME MED. 1 COARSE SAND			200	11					0
FINE GRAVEL.				2070					
	lt	2		3					
	F	8 1	201	1.00					
	F	9 0	20 2	3 2460				1	
STIFF STRATIFIEL		10	203	7				1	
GREY BROWN CLAYEY SILT WITH A TRACE OF MED. SAND		11	20 2	4 2450					
FIRM BROWN	H		2" >1	14.5					0
MED. & COARSE SAND, FINE GRAVEL & ORGANICS.		1		2440			-	4	
REY DENSE DARK	1 L	3 0	2">*	~					3
ERY DENSE BLACK	Η,	a 4	vs					1	
DESICCATED SILT WITH THIN PYRITE LENSES ROUNDED		5 4	45	2430					
BEDROCK		-							
END OF HOLE.		6 4	5	2420					
					Is of S Percent axial strain at failure				

ter ber

Mar

William-

with the

A ... PROJECT No . 1/73218 RECORD OF BOREHOLE 2 I.OCATION BORING DATE NOVEMBER 1, 1973 DATUM TAKEN FROM COMINCO DRAWING NO. HB-285-P See Figure / BOREHOLE TYPE ROTARY TRICONE BOREHOLE DIAMETER 4 IN. SAMPLER HAMMER WEIGHT 140 LB. DROP 30 INCHES PEN. TEST HAMMER WEIGHT LB DROP INCHES SOIL PROFILE SAMPLES SCALE DYNAMIC PENETRATION RESISTANCE COEFFICIENT OF PERMEABILITY K, BLOWS/FT ------TESTING CM. / SEC. STRAT PLOT BLOWS / FT. NUMBER TYPE ELEVATION IN IN DESCRIPTION SHEAR STRENGTH Cu. LB. /SQ. FT WATER CONTENT, PERCENT STANDPIPE ADDIT ABDIT W WL WP INSTALLATION GR SURFACE. 10 2460 1 2' 10 V WL 5.5' NOU 23,1973 SOFT BROWN SANDY SILT 2 2' 8 WITH MED. + COARSE SAND + GRAVEL TO I'S" DIA. 2450 3 20 13 OFTEN TILL LIKE. 4 20 4 2440 5 20 WOOD SOFT TO FIRM STRATIFIED BROWN & GREY SILT WITH OCC. GRAVEL TO 1%"DA 20 6 00 SAND & GRAVEL 2430 7 45 8 WS BEDROCK. 2420 9 W.S 10 W.S END OF HOLE 2410 15-0-5 Percent axial strain at failure HT. AL SCALE DRAWN Page 317 CHECKEDEGM-2013-00163 NCH TO IO FEET GOLDER, BRAWNER & ASSOCIATES 2 A -

PROJECT No. 173218

	SOIL PROFILE	1	SAL	MPLE	s w		TEST HAMMER WEIGHT - LB D		
EVN	DESCRIPTION	PLOT	T		SCAL		COEFFICIENT OF PERMEABILITY K, CM. / SEC.	STING	
этн	DESCRIPTION	STRAT	NUMBER	TYT	BLOWS / F	SHEAR STRENGTH Cu, LB /SO.FT	WATER CONTENT, PERCENT	ADDITIONAL LAB TESTING	STANDPIPE
0. 0. 0. 0. 0.	GR SURFACE, VARIABLE DENSITY BROWN I GREY SILT SAND I GRAVEL WOODEN CULVER VARIABLE DENSITY BROWN I GRAVEL COARSE SAND I FINE GRAVEL COARSE SAND I FINE GRAVEL COARSE SAND I FINE GRAVEL (TILL) WERY DENSE SAND I GRAVEL BEDROCK.		2 0 3 0		2440 7				
						15 os Percent axial strain at failure			

t . ft f .

# DAVID MINERALS LTD.

# Tailings Disposal Scheme HB Mill, Salmo, B.C.



14745-20 MINISTRY OF ENERGY, MINES AND FETROLEUM RESOURCES Rec'd JAN 11 1982 ;;

PROJECT:	HB Mill Tailings Disposal Scheme
LOCATION:	Salmo, B.C.
CLIENT:	David Minerals Ltd.
OUR FILE:	VA 2869 November 27, 1981

Page 320 EGM-2013-00163 ,121

November 27, 1981

PAGE

VA 2869

#### TABLE OF CONTENTS

#### INTRODUCTION AND SUMMARY ..... 1 1. DESCRIPTION OF EXISTING TAILINGS POND AND DAM ..... 3 2. Cominco's Operating History ..... 3 2.1 Geotechnical Aspects of Dam Construction ..... 4 2.2 Spillway ..... 6 2.3 6 TAILINGS DISPOSAL SITE ..... 3. 3.1 Hydrological Setting ..... 6 7 TAILINGS DISPOSAL SCHEME ..... 4. Existing Capacity of the Pond ..... 7 4.1 Tailings Dam Raising ..... 8 4.2 Water Balance ..... 8 4.3 Permanent Spillway ..... 9 4.4 CONCLUSIONS AND RECOMMENDATIONS ..... 9 5. 9 Conclusions ..... 5.1 Recommendations ..... 9 5.2

#### APPENDIX

- I
- LOGS OF BOREHOLES DRILLED BY GOLDER ASSOCIATES IN 1973

#### LIST OF DRAWINGS

A-2869-1	-	SITE LOCATION
B-2869-2		LOCATION OF TAILINGS DISPOSAL POND
B-2869-3	_	PLAN OF EXISTING TAILINGS POND
D-2869-4	-	PLAN AND SECTION OF EXISTING DAM
B-2869-5		SCHEMATIC PROFILE OF TAILINGS POND
B-2869-6	-	STABILITY ANALYSIS OF DAM
A-2869-7	-	WATER BALANCE

VA 2869

# 1. INTRODUCTION AND SUMMARY

Klohn Leonoff Ltd. was requested by David Minerals Ltd. to investigate the feasibility of using the existing tailings pond at the HB Mill for the deposition of about one million tons of tailings. This report has been prepared for submission to the Nelson Branch of the B.C. Ministry of Energy, Mines and Petroleum Resources so that a permit can be obtained by David Minerals to operate the pond.

The HB Tailings Dam is located approximately four miles south of The dam was origi-Salmo, B.C. (Drawings A-2869-1 and B-2869-2). nally built by Cominco in 1955 using a timber crib over which borrow materials from the west end of the pond were placed. The dam was raised in this manner to a height of about 40 ft. In 1964, a portion of the timber crib failed and moved about 10 to 15 ft. Drains were placed and toe protection was provided to stabilize the dam raising continued by the Construction of the failure. downstream method until operations were suspended in 1967. We understand that there was no independent geotechnical control of In 1973, Golder Associates drilled dam construction until 1973. three holes, one in the crest and two in the downstream portion of the dam. They encountered relatively soft material (as low as four blows per foot) in two holes. They recommended measures to reduce dam, which were implemented. the phreatic surface within the Subsequently, Golder Associates supervised the construction of dam The operations at the HB Mill were raisings in 1975 and 1977. suspended by Cominco in 1978.

The tailings dam is located at the southern end of a valley and has been constructed about 75 to 80 ft high using borrow materials. The tailings were deposited at the back of the pond, about 2900 ft from the crest of the dam and clarified water ponded against the upstream face of the dam (Drawing B-2869-3). Initially, two timber

What is metwe of the Management What is metwe was to Management whit ? Has new process. What is the new process. What about 1:200 What about 1:200 pubability earthquake?

decant towers were used in conjunction with two 24-inch diameter steel pipes to pass water from the upstream to the downstream side of the dam. In 1977, these decant towers were filled with concrete and replaced with a new spillway and drop manhole arrangement (Drawing D-2869-4).

- 2 -

Dr. Rajaram of Klohn Leonoff visited the damsite on September 23, 1981. Discussions were held with Mr. Newman of Cominco Engineering to obtain details of the tailings dam operation during the period 1955 to 1978. A profile of the tailings pond from the tailings flume to the dam crest was obtained from Mr. Newman and from Mr. Girdler of David Minerals. A schematic profile of the tailings pond is presented in Drawing B-2869-5. Assuming that tailings will be deposited uniformly on the existing tailings surface, a curve relating tons of tailings to elevation was developed. Approximately 790,000 tons of tailings can be deposited in the existing pond and dam. The dam will have to be raised by about 6 ft before the anticipated one million tons of tailings are deposited.

Klohn Leonoff will assess the condition of the existing dam by conducting a program of field investigation and laboratory analysis. Based on the results of this investigation, specifications for the dam raising will be provided.

The hydrology of the site was briefly analyzed to determine the water balance in the pond. It was concluded that the present spillway, which we understand is designed for a peak flow of 80 cu ft per second, is adequate to handle the runoff from a 200 year flood.

A seismic risk analysis of the site indicated that the acceleration amplitude with return periods of 100 years is 0.015 g (1.5 percent gravity). Since this figure indicates that the site has very low seismic risk, a static stability analysis was performed. The - 3 -

analysis indicates that the dam has a minimum factor of safety against a shearing type failure of 1.7.

This report details the condition of the existing dam and describes the physical and hydrologic setting of the tailings pond, the tailings disposal scheme, and final abandonment of the pond.

# 2. DESCRIPTION OF EXISTING TAILINGS POND AND DAM

The existing tailings pond is located approximately four miles south of Salmo, B.C. A plan of the pond area showing the contours of the tailings surface is presented on Drawing B-2869-3. The tailings dam is located at the southern end of a valley and has been constructed about 75 to 80 ft high using borrow material obtained from the abutment slopes. The dam is about 800 ft long and the pond occupies an area of about 67 acres. A plan and section through the dam are presented on Drawing D-2869-4.

#### 2.1 Cominco's Operating History

Cominco operated the tailings pond during the period 1955 through 1978. The tailings pond was used during 1955 through 1967, and subsequently during the period 1974 through 1978. The crest of the dam was raised periodically during these years to accommodate the increasing volumes of tailings. These dam raisings were performed using the downstream method of construction, i.e., additional fill was placed on the crest and the downstream slope of the dam. It is our understanding that the dam construction during the years 1955 through 1967 was not performed under independent geotechnical control.

When the dam was initially constructed in 1955, a timber crib structure was used. This crib was covered with borrow material obtained from the west end of the pond. The dam was raised in this manner to a height of about 40 ft. In 1964, a portion of the

November 27, 1981

VA 2869

timber crib failed and moved about 10 to 15 ft. Drains were placed and toe protection was provided to stabilize this failure. Construction of the dam raising continued by the downstream method until operations were suspended in 1967.

÷ 4 -

Before Cominco re-opened the HB Mill in 1974, Golder Associates investigated the stability of the tailings dam in 1972 and 1973. They drilled three holes, one on the crest and two on the downstream portion of the dam. They encountered soft materials (as low as four blows per foot) in two of the three holes. They recommended that a filter blanket be placed on the downstream slope of the dam to reduce the phreatic surface and improve dam stability. This was implemented in 1974. Two subsequent dam raisings in 1975 and 1977 were supervised by Golder Associates (personal communication, Newman, 1981). Cominco has been monitoring the water levels in the dam since the installation of piezometers in 1973. These observations indicate that the phreatic surface within the dam has not changed since Cominco shut down their operation in 1978.

# 2.2 Geotechnical Aspects of Dam Construction

Cominco re-opened the HB Mine and Mill in 1973. In 1972 and 1973, Golder Associates of Vancouver investigated the stability of the tailings dam. In 1973, three boreholes were drilled to depths varying from 45 to 85 ft and extended approximately 20 ft into bedrock. One borehole was drilled from the crest and two boreholes from the downstream slope of the existing tailings dam. Logs of the boreholes obtained by Golder Associates are presented in Appendix I. Samples were obtained for laboratory testing, and perforated plastic standpipes were installed in the boreholes to monitor groundwater levels. A plan and section of the dam, showing the location of these boreholes, is presented on Drawing D-2869-4. VA 2869

A review of Golder Associates reports dated June 1972 and January 1974, and discussions with Mr. Newman of Cominco reveal the following about the tailings dam:

- The dam is generally comprised of brown sandy silt containing varying amounts of medium to coarse sand and fine gravel.
- There are zones of soft material in the fills placed before 1967 (as low as four blows per foot).
- A timber crib was used during the initial construction of the dam, and a portion of this crib failed in 1964 and moved about 10 to 15 ft.
- The foundation material under the fill consists of bedrock overlain by 6 to 8 ft of dense silty till with minor amounts of sand and gravel.
- The fill material has an angle of internal friction of approximately 35 1/2 degrees with zero cohesion, as determined by Golder Associates' laboratory tests.
- The factor of safety against a shearing type failure is of the order of 1.3. Since this analysis was completed by Golder Associates in 1973, the phreatic surface has been lowered and so the present factor of safety is considered to be greater than this figure.
- The dam has adequate protection against surface erosion.

Golder Associates recommended that if the ponded water level is raised, the dam should be raised using a filter blanket to maintain the phreatic surface below the level of the existing downstream fill slope. The specifications for the 1975 and 1977 dam raisings were prepared by Cominco on the basis of the Golder reports, and we understand that the construction was supervised by Golder Associates. A review of the piezometer readings through July 1981 indicates that the phreatic surface has been relatively constant, since Cominco shut down in 1978.

#### 2.3 Spillway

Prior to 1977, two timber decant towers were used in conjunction with two 24-inch diameter steel pipes to pass water from the upstream to the downstream side of the dam. Due to operating and maintenance problems with this system, Cominco filled these structures with concrete and installed a new spillway and drop manhole structure (Drawing D-2869-4). This structure is equipped with a 36-inch diameter steel pipe, and we understand was designed to pass a maximum flow of 80 cu ft per second (35,900 USGPM).

#### 3. TAILINGS DISPOSAL SITE

The tailings disposal area is situated in a natural basin covering about 67 acres in the Salmo Provincial Forest. It is to the east of Provincial Highway 3 and the Salmo River, about four miles south of Salmo, B.C. (Drawing B-2869-2). To the east and west of the pond are heavily treed slopes consisting of 80 to 90% of evergreens. The dam is situated at the southern end of the basin.

#### 3.1 Hydrological Setting

Dr. McCreath of Klohn Leonoff, obtained data on snowcourse, streamflow, and precipitation from measuring stations at Creston, Nelson, Trail, and Edgren Creek. From analysis of the data, the average annual precipitation at the site is 31.5 inches, and the average annual evaporation is 16.7 inches. The average annual runoff from a catchment area of about 445 acres to the east of the tailings pond is about 14.5 inches. The water balance for the pond was calculated using these estimates for precipitation, evaporation, and runoff. VA 2869

The peak 200 year flood inflow into the pond is estimated to be in the order of 120 to 150 cu ft per second (cfs). About 30 to 50% of this inflow can be temporarily stored in the pond since a flood surcharge of 2 ft has been assumed in computing the volume-elevation curve. Thus, the existing spillway, which we understand has been designed for a discharge of 80 cfs, can handle the 200 year flood estimated for the site.

- 7 -

#### TAILINGS DISPOSAL SCHEME

#### Existing Capacity of the Pond

The tailings pond has been operated since 1955 with the tailings being deposited at the upstream end of the tailings pond and the dam being raised as necessary by the downstream method of construction using borrow materials. Klohn Leonoff recommends that this method of tailings disposal be continued by David Minerals Ltd. In an effort to estimate the present capacity of the tailings pond, and the extent of dam raising necessary to store the anticipated 1,000,000 tons of tailings, a curve relating the tons of tailings to the elevation of the dam crest was developed (Drawing B-2869-5).

A schematic profile of the existing tailings surface is presented on Drawing B-2869-5. The water level in the pond is 5 ft below the dam crest, and the depth of the ponded water on the upstream side of the dam is 9 ft. The tailings should be discharged in layers over the existing tailings surface. In June 1984, after about 790,000 tons of tailings have been deposited, the ponded water capacity and flood surcharge provision will be reduced to a minimum. At that point, the dam will have to be raised by about 6 ft before additional tailings can be deposited. During operation of the tailings pond, the elevations of the tailings should be monitored to ensure that the schematic profile presented on Drawing B-2869-5 is maintained. The depth from the crest of the slimes surface on the upstream side of the dam should be maintained as depicted in the tons of tailings versus elevation curve.

# 4.2 Tailings Dam Raising


The tons of tailings versus elevation curve indicates that the dam crest has to be raised prior to June 1984. Klohn Leonoff recommends that before the dam raising is undertaken, a program of field investigation should be conducted to assess the condition of the upstream portion of the dam. The upstream portion of the dam contains some soft zones, and also has a timber crib buried within it.

During the 1982 field season, two to three boreholes should be drilled to assess the condition of the upstream side. Soil samples should be obtained for conducting laboratory tests. Based on the results of the field and laboratory testing program, Klohn Leonoff will develop detailed specifications for the dam raising.

A stability analysis of the dam was performed using the parameters presented in Drawing B-2869-6. A preliminary profile of the dam raised by 6 ft was used to perform the analysis. A seismic risk analysis of the site indicated that the acceleration amplitude with return periods of 100 years is 0.015 g (1.5% gravity). Since this represents a very low seismic risk, a static stability analysis was performed. The minimum factor of safety for the dam was found to be 1.7.

#### 4.3 Water Balance

The hydrological data given in Section 3.1 of this report was utilized to compute the water balance for the tailings pond (Drawing A-2869-7). Using a production rate of 900 tons per day, a tailings pulp density of 30%, and no recycling of the water, the tailings



C 1875 - 19

November 27, 1981

VA 2869

transport water required is 350 USGPM. Of this amount about 50 USGPM remains within the voids of the tailings. The runoff and precipitation into the pond is estimated to be 335 USGPM. Assuming that 40 USGPM are lost due to evaporation and seepage, the average amount of daily flow out of the spillway is 595 USGPM. This represents an average dilution factor of about two for the tailings water. During periods of heavy runoff and precipitation, this factor could be much higher.

- 9 -

# 4.4 Permanent Spillway

On final abandonment of the pond, a permanent spillway should be constructed at the east abutment of the dam. This should be an open-channel spillway which will safely pass flood water from the upstream to the downstream side of the dam. The design of this spillway is beyond the scope of the present study.

# 5. CONCLUSIONS AND RECOMMENDATIONS

# 5.1 <u>Conclusions</u>

- The existing tailings dam has a capacity of approximately 790,000 tons.
- 2. The tailings should be discharged from the northern end of the pond, in layers over the existing tailings surface. The depth from the crest of the slimes surface on the upstream side of the dam should be maintained at a minimum of about 8 ft.
- The dam crest should be raised by about 6 ft during the 1983 field season to accommodate the anticipated one million tons of tailings.

### 5.2 Recommendations

 The condition of the existing dam, especially the upstream portion, should be investigated during the 1982 field season. Based on this investigation, plans and specifications for the 1983 dam raising should be prepared.

November 27, 1981

- Piezometric levels in the dam should be monitored on a monthly basis.
- 3. The tailings surface elevation should be monitored to ensure that the schematic profile presented in this report is maintained. Any significant variations in this profile will affect the tailings storage capacity.

KLOHN LEONOFF LTD.

V. RAJARAM, Ph.D., P.E. Senior Division Engineer

Marti Holsen

MARK T. OLSEN, P.Eng. Staff Consultant

VR/MTO/jas

# APPENDIX I

# LOGS OF BOREHOLES DRILLED BY GOLDER ASSOCIATES IN 1973

	SOIL PROFILE	-	SA	MPL	ES	Ш		YNAMIC	PENET	RATION							HOP	INCHES
LEVN LETH	DESCRIPTION	STRAT PLOT		TYPE	BLOWS/FT.	ELEVATION SCAL			BLO	STH Cu.	· · · · · ·	 	TER C	CM. / SE	PERCE	INT	ADDITIONAL AB TESTING	STANDPIPE
24650 0 0	GR SURFACE								1	1				F			ב ا	1
			1*	2'	10	2460												a 🔻
	SOFT BROWN SANDY SILT WITH MED. 4 LOARSE SAND 4		2	2. 200	8		4			Ì.								WL 5.5' NOU 23,197
	GRAVEL TO I'S" DIA. OF TEN TILL LIKE,		3	2' DO	13	2450												0
4386				200	4	2440		-										
215	WOOD SOFT TO FIRM STRATIFIED BROWN & GREY SILT WITH OCC ORAVEL TO IS DA	1	2	20	20													
4310 340 4290 960	SAND & GRAVEL			ws		<u>c430</u>												•
	BEDROCK.		8	ws		2420												a a
2100 550	END OF HOLE .	-	10	ws		U19_												0
	)																	
	-																	
									t									
							0		1	strain								

Page 335 EGM-2013-00163

= 94

PROJECT No . V.73218

08.14

PROJECT No V73218

BROWN SILT RAVEL	5   w	BLOWS / FT C	BLOWS/FT	- CM./SEC WATER CONTENT, PERCENT WP W WL	ADDITIONAL	STANDPIPE INSTALLATIO
BROWN SILT RAVEL						AND ALLATIO
	- 2'	50 2450			- 3	
GREY H MED	2 20 >>	2440				WL 60 NOV 23.19
BROWN CLT. RAVEL	1 20 3	7				0
RÁVEL.						
	ws	2420				0 0-
IOLE.		2410				
	H MED. SAND INVEL. BROWN LT. RAVEL RAVEL RAVEL	H MED SAND 3 UEL 3 DO 1 20UEL 3 DO 1 20 3 DO 1 20 4 DO 3 2 2 7 WS	H MED SAND 30VEL 30VEL 30VEL 300 30VEL 300 300 300 300 300 300 300 30	$\begin{array}{c c} H & MED \\ SAND \\ SAND \\ 3 & D \\ T \\$	$\begin{array}{c} H MED \\ SAND \\ SAND \\ 3 D0 \\ 15 \\ TAVEL \\ CH \\ T \\ T \\ W \\ T \\ T \\ W \\ T \\ T \\ W \\ T \\ T$	$ \begin{array}{c} H MED \\ SAND \\ SAND \\ TOPOLL \\ $


#### LIST OF DRAWINGS

A-2869-1	-	SITE LOCATION
B-2869-2		LOCATION OF TAILINGS DISPOSAL POND
B-2869-3		PLAN OF EXISTING TAILINGS POND
D-2869-4	-	PLAN AND SECTION OF EXISTING DAM
B-2869-5		SCHEMATIC PROFILE OF TAILINGS POND
B-2869-6		STABILITY ANALYSIS OF DAM
A-2869-7	-	WATER BALANCE

TO DESCRIPTION OF THE OWNER OWNER

States of a states

Second Second



12000


AND STATE

ž

1-455-

fill traile 61 Warfield Erand Rossland 🐯 Creston Montrose Mantrose 🛍 🕵 Erickson 3:19 - Rippin Mourtain IS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED CANADA GAZETTEER ATLAS, 1980 FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR REF. : PUBLICATION OF DATA STATEMENTS, CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPHOVAL 1:1000.000 SCALE PROJECT HB MILL TAILINGS DISPOSAL KLOHN LEONOFF LTD. TITLE CONSULTING ENGINEERS SITE \_OCATION CLIENT: NOV. 27, 1981 DWG. No. 2013-00163 PROJECT No. DAVID MINERALS LTD APPROVED (N) VA 2860 A

REV.



I

IJ

I

I


B

Q

l

0

Page 339 EGM-2013-00163




III.

10


Q


D

10




Page 341 EGM-2013-00163






Page 343 EGM-2013-00163




Page 344 EGM-2013-00163



Page 345 EGM-2013-00163

					\$
INCO ENGINEERING, EBRUARY 7, 1977					1 3
Ebhowiti I, istit.					
	2				1
					1
					1.40
PT DATED NOV 27, 198					1.44
RT DATED NOV 27, 198	I REV. DATE		REVISION DETAIL	5	
RT DATED NOV 27, 198	REV. DATE DESIGN	DRAWN	DATE	SCALES	
RT DATED NOV 27, 198	REV. DATE DESIGN COMINCO	DRAWN S.S. MILL TAILIN	DATE .0CT., 1981	AS SHOWN	




I

I

1

1

Page 347 EGM-2013-00163




Ì

İ

Î

1




.

PUBLICATION OF DATA, STATEMENTS, CONCLUSIONS OF ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS

	PROJECT	SCALE NTS
KLOHN LEONO		B MILL TAILINGS DISPOSAL
CONSULTING EN	GINEERS	WATER BALAN
DAVID MINERALS	LTD.	EGM-2013-00163

# THE GONSOLIDATED MINING AND SMELTING GOMPANY OF GANADA, LIMITED

CABLE ADDRESS



H.B. Mine, Salmo, B.C., March 31, 1953

4266

Mr. J.A. Mitchell, Mining Engineer, i/c Road and Trail Work, Department of Mines, Victoria, B.C.

4

Dear Sir:

In accord with Order in Council No. 967 approved April 25, 1952, in which the sum of \$8,000.00 was authorized for the construction of the H.B. Mine road, I enclose details of expenditure and affidavit pertaining to these expenditures.


It will be noted that the total costs were \$12,287.89 so that the departmental grant would only amount to \$6,143.94.


Thanking you for the interest you have shown in the development of our property, I am


Yours very truly,


Al Mu Mun-

J.E. McMynn, Property Superintendent.









Pages 354 through 366 redacted for the following reasons: Not Responsive

COMINCO LTD., H.B. MINE TAILINGS DIKE EXTENSION

SPECIFICATION NO. HBO.010-1

FEBRUARY 1977

DUPLICATE #20



## COMINCO LTD.

:

)

Ì

)

8

# H.B. TAILING DIKE EXTENSION, 1977

## INDEX

Pages	1 - 4	-	Instructions to Tenderers
	5 - 7	-	Form of Tender
	8 - 9	-	Schedule of Quantities and Unit Prices
	10 - 12		Form of Contract Agreement
	13 - 20		General Conditions of Contract
	21 - 24		Specification - Section 1 - Special Provisions
	25 - 40	-	- Section 2 - Earthwork
			Drawings - Figure 1

Figure 1 HBO-304 - Rev. O

> Page 368 EGM-2013-00163 GRIT

1.1237

Specification No. HBO.010-1

## COMINCO LTD.

,

Į.

)

## H.B. TAILING DIKE EXTENSION, 1977

INSTRUCTIONS TO TENDERERS FORM OF TENDER SCHEDULE OF QUANTITIES & UNIT PRICES FORM OF CONTRACT AGREEMENT GENERAL CONDITIONS OF CONTRACT SPECIFICATION

DRAWINGS

Prepared by

Cominco Ltd.

February, 1977



## COMINCO LTD.

-2-

## H.B. TAILING DIKE EXTENSION, 1977

#### INSTRUCTIONS TO TENDERERS

- Tenders for the construction of H.B. Tailing Dike Extension, 1977 will be received by Cominco Ltd. until twelve noon, Pacific Standard Time, March 10, 1977.
- 2. The tender shall be submitted in duplicate to:

Cominco Ltd. Attention: W. W. Thom, Assistant Purchasing Agent Trail, B. C.

upon the official form of tender marked "Original" and on the form marked "Copy No. 1" and shall include the instruction to tenderers, all statements attached to the tender, the general conditions, the schedule of quantities and unit prices, the specifications and the drawings, bound together in the condition in which they were issued. The Tenderer shall not remove any page from the documents.

 One copy of the tender, marked "Copy No. 2" shall be retained by the Tenderer.

Should there be any discrepancy between the original tender and the copies, the original shall prevail.

- 4. The contract for which a tender is made in accordance with these instructions is a schedule of quantities and unit prices contract. The Tenderer shall complete the original and the additional two (2) forms of tender. He shall insert the unit price and amount for each item in the schedule of quantities and prices, and shall total these amounts so as to show the total sum of the tender.
- 5. All prices shall be firm prices, quoted in Canadian dollars, and shall include all applicable taxes.
- Each item in the schedule of quantities and prices shall, in the judgement of the Engineer, be reasonably priced. Under no circumstances will a manifestly unbalanced tender be considered.

## INSTRUCTIONS TO TENDERERS

-3-


- 7. No oral, telegraphic or telephonic proposals or modifications will be considered, and no tender will be accepted or considered that contains an escalator clause or any other qualifying condition.
- Tenders shall be made without any connection, comparison of figures, or arrangement with or knowledge of any other person or persons making a tender for the same work and shall be, in all respects, fair and without collusion or fraud.
- The signatures of all Tenderers shall be in their respective handwriting, or if the Tenderer is a corporation, the tender shall be executed under its corporate seal.
- 10. The Tenderer is invited to inspect the site prior to submitting his tender in order to satisfy himself by personal examination as to the actual conditions and requirements of the work and as to the accuracy of the quantities in the schedule of quantities and prices.
- 11. The Tenderer shall not claim at any time after submission of his tender, or the subsequent execution of a contract, that there was any misunderstanding in regard to conditions imposed by the contract. If, during inspection of the site or at any other time before submission of his tender, the Tenderer notes facts or conditions which in any way conflict with the letter or spirit of the specification, or with any other data furnished to him, he shall apply to the Engineer for information and explanation before submitting his tender. The Tenderer will be held entirely responsible for any errors which he may make through failure to obtain such information and explanation
- 12. The Tenderer shall be prepared to enter into a contract agreement as attached.
- 13. Tender shall be accompanied by a bid bond in an amount not less than 5% of the tender price, issued by a Surety Company properly licensed to carry on such business in Canada. The Tenderer may submit a certified cheque in lieu of the bid bond, and the said cheque shall be subject to the provisions stated in the Form of Tender.

#### INSTRUCTIONS TO TENDERERS

.

)

- 14. Complete compliance with the tender documents is mandatory. Tenders not complying with these provisions will be disqualified.
- 15. Subject to the foregoing, the Tenderer may submit alternative plans or specifications for the work for consideration.
- 16. Tenders received after the time stated in Clause 1 above will not be considered.
- 17. The Owner reserves the right to reject any or all tenders and the lowest bid will not necessarily be accepted.
- 18. All recipients of the documents for the proposed contract, whether or not they submit a tender, shall treat the details of the documents as private and confidential.
- 19. The work shall be completed not later than November 1, 1977.





Specification No. HB0.010-1

COMINCO LTD.

-6-

H.B. TAILING DIKE EXTENSION, 1977

FORM OF TENDER

Tender by	
of	,
a Company duly incorporated under the laws of	
and licensed to carry on business in the Province of	
and having its head office at	
hereinafter called the Tenderer.	

## To: Cominco Ltd. Trail, B. C.

Having examined the Instructions to Tenderers, Form of Tender, Schedule of Quantities and Unit Prices, Form of Contract, General Conditions of Contract, Specification and Drawings, for the construction of the above-named work, the undersigned Tenderer hereby tenders and offers under and subject to the annexed Instruction to Tenders to construct, complete and maintain the said work in conformity with the said drawings, General Conditions of Contract and Specification for and at the unit prices set out in the annexed schedule of quantities and unit prices and by the date specified in Clause 19 of the Instructions to Tenderers.

The lump sum total of prices set out in the schedule of prices is

## (Canadian Dollars)(\$

The Tenderer also undertakes to enter into a contract incorporating said Instructions to Tenderers, Form of Tender, Schedule of Quantities and Unit Prices, Form of Contract, General Conditions of Contract, Specification and Drawings, and the Tenderer hereby agrees that until such contract is executed, the said Instructions to Tenderers, Form of Tender, Schedule of Quantities and Unit Prices, Form of Contract, General Conditions of Contract, Specification and Drawings and this tender together with your written acceptance thereof shall constitute a binding contract between us.

## FORM OF TENDER

-7-

The Tenderer agrees that this tender shall continue open to acceptance and irrevocable until the formal contract is executed by the successful Tenderer for the said work, and the bond hereinafter mentioned is executed by the approved surety; and that Cominco Ltd. may, at any time within one hundred and twenty (120) days of the closing date for tenders, accept this tender without notice, whether any other tender has previously been accepted or not, and whether notice of acceptance of another tender has been given or not. The Tenderer encloses herewith as bid bond, in accordance with the provisions of the Instructions to Tenderers, a bid bond or certified cheque for the sum of

(Canadian Dollars )(\$

per

).

, 197


The Tenderer agrees that in the event that this tender is accepted and the Tenderer fails to execute a contract in the respect thereof, then the Company shall enforce the provision of the said bid bond or confiscate the said certified cheque, at the discretion of the Company.

has executed these presents this \_\_\_\_\_ day of SEALED with the Corporate Seal of

IN WITNESS WHEREOF

And attested by its proper officers in ) that behalf.

Page 376 EGM-2013-00163



Page 377 EGM-2013-00163

Specification No. HB0.010-1

## COMINCO LTD.

-9-

# H.B. TAILING DIKE EXTENSION, 1977

# SCHEDULE OF QUANTITIES AND UNIT PRICES

	Work or	Estimated Quantity	Tender		
Item No.	Work or Material		Unit	Unit Price	Amount
1.	Clearing	2.5	acres		
2.	Stripping	4,000	cu.yd.		
3.	Foundation Preparation	10,000	sq.yd.		
4.	Unsuitable Materials	5,000	cu.yd.		
5.	Trim Existing Dike	1,500	cu.yd.		
6.	Drainage Zone - Sand and Gravel	3,000	cu.yd.		
7.	Drainage Zone - Rock Toe	1,800	cu.yd.		
8.	Select Impervious and Common Fill	18,000	cu.yd.		
9.	Decant Culverts	60	lin.ft.		
10.	Borrow Pit Treatment	12,000	sq.yd.		

It is understood and agreed that the quantities stated herein are approximate only and are given for the purpose of providing a uniform basis for the comparison of tenders. Payment will be made only on the quantities as actually determined on final measurements.

Tenderer

Page 378 EGM-2013-00163

# FORM OF CONTRACT AGREEMENT

:

)

## CONTRACT AGREEMENT

-11-

THIS AGREEMENT made this day of in the year by and between COMINCO LTD, herein called the "Owner and herein called the "Contractor".

WITNESSETH: That the Contractor and the Owner undertake and agree as follows:

ARTICLE 1.

The Contractor shall:

- (i) Provide all necessary materials, labour, supervision, and equipment and perform all work, and fulfill everything as set forth and in strict accordance with the Contract for the project entitled "H.B. Tailing Dike Extension, 1977".
- (ii) Commence to actively proceed with the work within seven (7) days of the date of receipt of a Notice to Proceed from the Owner and complete same on or before November 1, 1977.

ARTICLE 2.

The Owner will pay to the Contractor as full compensation for the performance of the work and fulfillment of this Contract, the sum or sums of money calculated in accordance with the terms of the Contract.

ARTICLE 3.

The Contract shall supersede all communications, negotiations and agreements, either written or verbal, made between the parties hereto in respect of all matters in any way pertaining thereto prior to the execution and delivery hereof.

ARTICLE 4.

All communications in writing between the parties or between them and the Engineer shall be deemed to have been received by the addressee if delivered to the individual, or to any officer of the corporation for whom they are intended, or if sent by mail or by telegram addressed as follows: -12-

The Contractor at:

The Owner at:

1 April 1

Cominco Ltd. Trail, British Columbia V1R 4L8

Attention: Manager, Engineering

ARTICLE 5.

Time shall be of the essence of the Contract.

ARTICLE 6.

)

The Contract shall enure to the benefit of and be binding upon the parties, their respective successors, administrators and assigns.


IN WITNESS WHEREOF the parties hereto have executed this Agreement as of the day and year first above written.

Contractor:

Per:

Cominco Ltd.

Per:



-14-

- As used herein and elsewhere in the Contract, unless the content requires a contrary meaning:
- 1.1 The words "The Contract" shall mean the written Agreement, the Instructions to Tenderers, the Form of Tender, the Schedule of Quantities and Unit Prices, the General Conditions of Contract, the Specification, the Drawings Figure 1 and HB-304 - Rev. 0 and the purchase order to be issued to the Contractor by the Owner, copies of all of which are annexed hereto and form part hereof, all of which shall be read together and shall constitute the entire Agreement between the parties relating to the work and its performance.
- 1.2 The words "The Engineer" shall mean and include the person holding the position or acting in the capacity of Project Superintendent, H.B. Tailing Dike Extension - 1977, appointed by the Owner to be responsible for the supervision of the work and includes any other person or persons designated by the Owner as Engineer for the purposes of the Contract.
- 1.3 The word "Materials" shall mean all machinery, tools, plant, materials, equipment, articles and things furnished by the Contractor and required for the execution of the Contract.
- 1.4 The words "The Work" shall mean and include all or any part of the work to be executed by the Contractor pursuant to the Contract, whether complete or incomplete, and as may be originally set forth or as varied by the Engineer.
- The Contractor shall execute and perform all the labour of every kind and shall supply all material required in the construction and finishing of the work.
- 3. The Engineer shall be the sole judge of the work and material in respect of both quality and quantity, and his decision on all questions in dispute with regard thereto, or as to the meaning or intention of this Contract and as to the meaning or interpretation

-15-

of the plans, drawings and specifications shall be final, and no work under this Contract shall be deemed to have been performed, nor materials or things provided, so as to entitle the Contractor to payment therefore, unless and until the Engineer is satisfied therewith, as evidenced by his estimates in writing, which estimate shall be a condition precedent to the right of the Contractor to be paid therefore. The work shall, in every particular, be under and subject to the control of the Engineer, and all orders, directions and instructions at any time given by the Engineer with respect thereto, or respecting the conduct thereof, shall be obeyed by the Contractor and promptly and efficiently performed and complied with to the satisfaction of the Engineer.

All work shall be done in a neat and workmanlike manner and according to instructions by the Engineer and the Contractor shall allow the Engineer or the Owner free access to the work and shall furnish full information concerning the work when requested by the Engineer or the Owner.

The Contractor and every one of its workmen, sub-contractors, agents and servants, shall in all things concerning the performance of the work obey, abide by and keep all the several conditions set forth herein and shall construct and execute the works in accordance with the Contract and to the satisfaction of the Engineer.

The Contractor shall submit progress payment invoices to the Owner by the 5th of the month for work performed in the preceding month. Payment for invoices shall be made 30 days after receipt of the invoice. Invoices shall be sent in triplicate to Senior Buyer, Cominco Ltd., Trail, British Columbia. The volume of material is to be approved by the Engineer prior to submission of invoice.

5.

The Owner will pay 85% of the invoice amount each month. The 15% holdback will be paid forty (40) days after the work has been completed, in compliance with the Mechanic's Lien Act. The Engineer will certify that the work has been completed to the Owner's satisfaction. The Owner shall be entitled to retain from any payment otherwise payable to the Contractor a sum sufficient in the opinion of the Engineer to provide for payment of all claims against the Contractor of any kind arising out of the work and which have not been settled. Before the issuance of the certificate indicating that the work has been completed to the Owner's satisfaction, the Contractor shall submit to the Owner's Engineer in charge evidence satisfactory to him that all payrolls and bills for materials and other indebtedness connected with the work have been paid.

-16-

The compensation herein provided shall constitute full payment for the work indicated, completed and in place, including the furnishing of all materials, tools, machinery, equipment, labour and work incidental thereto as well as any and all expenses incurred by reason of any cause whatever.

The quantities given in the Schedule of Quantities and Unit Prices are approximate only. Final payment to the Contractor will be made for the actual quantities only of work performed or materials furnished in accordance with the Contract as determined by measurements made by the Engineer. It is agreed that the quantities or work to be done or materials to be furnished may be altered by the Owner and such alterations shall not be considered as a waiver of any condition of the Contract, or as invalidating any of the provisions thereof, nor shall any changes be made in the Contract unit prices on account of such alterations, but the same unit prices shall apply as if no alteration had been made.

If the contractor suspends the construction of the work, or neglects 6. or fails to proceed with due diligence in the performance of same. the Engineer shall have the right to give notice in writing to the Contractor requiring that the work be proceeded with in a reasonable manner and with reasonable dispatch. Such notice shall not be unreasonably given, and must signify that it purports to be a notice under the provisions of this paragraph, and must specify the act or default on the part of the Contractor upon which it is based. After such notice has been given, the Contractor shall not be at liberty to remove from the site of the work or from any ground contiguous thereto, any plant or materials belonging to it; and the Owner shall have a lien upon all such plant and materials, to subsist from the date of such notice being given until the notice has been complied with: Provided always that such lien shall not under any circumstances subsist after the expiration of thirty-one (31) days from the date of such notice being given unless the Owner shall have entered upon and taken possession of the works and the site of the work as hereinafter provided. If the Contractor fails for seven (7) days after such notice has been given to proceed with the work as therein demanded, the Owner may enter upon and take possession of the work and the said site and all plant and materials thereon (or on any ground contiguous thereto) belonging to the Contractor and intended to be used in connection with the construction of the work, and all such materials shall thereupon become the property of the Owner absolutely, and the Owner shall retain and hold a lien upon all such plant until the work shall have been completed under the powers hereinafter conferred upon him. If the Owner exercises the above power he may engage any other person to complete the work, and exclude the

-17-

Contractor, his agents and servants, from entering upon and having access to the same, except that the Contractor or any one person nominated by him may have access at all reasonable times to inspect. survey and measure the work. The Owner shall take such steps as may be reasonably necessary for completing the work, using for that purpose the plant and materials above mentioned insofar as they are suitable and adapted to such use. Upon completion of the work, the Owner shall certify the amount of the expenses properly incurred consequent on and incidental to the default of the Contractor aforesaid and in completing the work by itself or by employing other persons. Should the amount of such expenses so certified be less than the amount which would be owing to the Contractor under this Agreement had it completed its obligations hereunder, the differences shall be paid to the Contractor by the Owner: should the amount of the former exceed the latter, the difference shall be paid by the Contractor to the Owner. The Owner shall not be liable to make any payment or compensation to the Contractor for or on account of the use of the said plant for the completion of the work under the provisions hereinbefore contained. After the work has been so completed by either the Owner or persons other than the Contractor under the provisions hereinbefore contained, the Owner shall give notice to the Contractor of such completion, and may require the Contractor from time to time before and after such completion to remove from the said site his plant and all such materials as aforesaid as may not have been used in the completion of the work. If such plant and materials are not removed within a reasonable time after notice has been given, the Owner may remove and sell the same, holding the proceeds. less the cost of removal and sale, to the credit of the Contractor.

- 7. The Contractor shall furnish all labour and superintendence required to complete the work in accordance with the Contract, but shall not employ on the works any unfit person or anyone not skilled in the work assigned to him. All labour shall be performed in the best and most workmanlike manner by persons skilled in their respective trades. The standards of work throughout shall be of such grade as will bring results of the first class only.
  - The Contractor shall be responsible for faulty materials supplied by it and faulty workmanship, and shall remedy same at its own expense.

8.

9.1 The Contractor shall provide, maintain, and pay for Comprehensive General Liability Insurance covering it, its sub-contractors and the Owner against damages arising from personal injury (including death) and from claims for property damage which may arise out of its or its sub-contractors' operations under this contract. Such insurance shall:

- (i) Have a limit of liability of not less than \$500,000 inclusive for any one occurrence or such greater amount as may, at the discretion of the Owner, be required.
- (ii) Cover all liability arising out of products, either the Contractor's or supplied by him, completed operations, contingent employer's liability and liability assumed by the Contractor under this Contract.
- 9.2 The Contractor shall also provide, maintain and pay for automobile insurance on its own vehicles and non-owned automobile insurance on vehicles not owned by it protecting itself and the Owner against damages arising from personal injury (including death) and from claims for property damage arising out of the use or operation of same. Limits of liability under such policies will be placed in accordance with paragraph 9.1 (1) (i) hereof.

Evidence of insurance, in such form as may be required, shall be lodged with Insurance and Risk Manager, Cominco Ltd., Vancouver, B. C., before the work is commenced.

- 10. The Contractor shall be responsible for all loss or damage to the work including materials delivered to site for incorporation therein and any materials supplied by the Owner.
- 11. Neither the final certificate nor payment thereunder, nor payment of the final balance payable pursuant to the Contract, nor any provision in the Contract shall relieve the Contractor from responsibility for faulty materials or workmanship, which appear within a period of one year from the date of completion of the works, and the Contractor shall remedy any defects due thereto which appear within the said period and pay for all resulting damage. The Owner shall give notice of observed defects promptly.
- 12. The Contractor shall not assign this Agreement, or subcontract the work, without first obtaining the written permission of the Owner. If, with the Owner's permission the work or any part of it is done by a sub-contractor, the Contractor shall be fully responsible to the Owner for the acts and omissions of such sub-contractor and of all persons employed by him.

-18-

-19-

- 13. The Contractor shall commence the work within the time provided in the Contract Agreement and shall continue with the same uninterruptedly and with diligence, with the required crew of workmen.
- 14. It is agreed that the Contractor enters into this Agreement as an independent contractor and in no sense is to be considered as an agent or employee of the Owner.
- 15. The Contractor shall save the Owner harmless from and idemnify him against all claims, demands, actions and suits arising out of or in connection with the construction of the work, whether such actions are brought by members of the public or workmen employed on the work. The Contractor shall, in carrying out the work, conform to all laws, rules, regulations and conditions applicable to the Contractor and to the work, and shall give all notices prescribed thereby and shall keep his employees covered and pay all assessments levied under, and shall keep his employees covered and pay all assessments levied under, and shall in every respect comply with, the applicable Workmen's Compensation Laws.
- 16. The Owner, or the Engineer, without invalidating the Contract, may make changes by altering, adding to, or deducting from the work, the amount to be paid pursuant to the contract sum being adjusted accordingly. All such work shall be executed under the conditions of the Contract except that any claim for extension or reduction of time caused thereby shall be adjusted at the time of ordering such change. No change shall be made unless in pursuance of a written order from the Engineer and no claim by the Contractor for compensation for any such change sum shall be valid unless so ordered and at the same time valued or agreed to be valued as provided in Paragraph 17.
- 17. The value of any change shall be determined in one or more of the following ways, prior to proceeding with the change:
  - (a) By estimate and acceptance in a lump sum.
  - (b) By unit prices agreed upon.
  - (c) By cost and percentage or by cost and a fixed fee.

-20-

18.

No implied contract of any kind whatsoever by or on behalf of the Owner shall arise or be implied from anything contained in this Contract or from any position or situation of the parties at any time, it being understood and agreed that the express contracts, convenants, and agreements contained herein and made by the parties hereto are and shall be the only contracts, convenants, and agreements on which any rights against the Owner may be founded.

19. In the case of any dispute arising between the Owner (or the Engineer acting on his behalf) and the Contractor as to their respective rights and obligations under the Contract, either party hereto shall be entitled to give to the other notice of such dispute and to request arbitration thereof: and the parties shall, with respect to the particular matters then in dispute, agree to submit the same to arbitration in accordance with the applicable law of the place of building.

Arbitration proceedings shall not take place until after the completion or alleged completion of the work except (a) on a question of certificate for payment, or (b) in a case where either party can show that the matter in dispute is of such nature as to require immediate consideration while evidence is available.

20. The Owner shall have the right to require the Contractor to furnish a bond covering the faithful performance of the Contract including the corrections after completion provided for in Paragraph 20 and the payment of all obligations arising under the Contract, in such form as the Engineer may prescribe and with such sureties as he may approve. If such bond is required by written instructions given previous to the receipt of bids, the premium shall be paid by the Contractor; if subsequent thereto, it shall be paid by the Owner.

# SPECIFICATION

ļ

)

)

## -21-

21-

#### SPECIFICATION

-22-

#### SECTION 1

## SPECIAL PROVISIONS

i.

#### 1-01 LOCATION

)

The site of the H.B. Tailing Dike is located four and one half miles south of Salmo, B. C., one half mile south of Sheep Creek and about one mile east of Provincial Highway No. 3.

### 1-02 ACCESS TO SITE

Access to the site is by two lane gravel road towards the Canex Mine from Highway No. 3 immediately south of Sheep Creek. An unimproved single lane bush road starting three quarters of a mile north of Highway No. 3 leads one mile south to the tailings dike.

### 1-03 SCOPE OF THE WORK

Except as otherwise specified, the work described in this specification comprises the furnishings of labour, materials, transportation, tools, equipment, supplies, supervision, and all other things necessary for the construction of the H.B. Tailing Dike Extension, 1977, all in accordance with the Contract.

#### 1-04 DRAWINGS

)

The following drawings are hereby incorporated in this specification:

> Figure 1 Drawing: HB-304 - Rev. 0

## 1-05 AVAILABILITY OF BUILDING MATERIALS

It is proposed to use select impervious and common materials from an extension towards the southeast of the existing borrow pit at the east abutment.

## SPECIAL PROVISIONS

-23-

The material for the filter blanket and berm will come from the existing borrow pit located approximately one quarter mile east of the turn-off to the dike on the Canex Road.

The material for the rock fill toe will come from the mine waste dump at the Canex Mine.

#### 1-06 SITE INVESTIGATION

The extension is to be built on the backslope and top of the existing dike. Seepage is apparent in several locations on the backslope and the Contractor shall place the filter blanket over these wet areas as specified herein before crossing these areas with equipment. It may be necessary to thicken the blanket in the area of haul roads to avoid disturbance of the foundations in the seepage areas.

A geotechnical report by Golder Brawner & Associates Ltd. dated December, 1976, has been made available to the Contractor. Further geotechnical information may be issued from time to time and will be available to the Contractor. Details on geotechnical information gathered before and during the construction of the existing dike will be available to the Contractor upon request. No warranty or representation is made with respect to the accuracy of such information.

The Contractor must make its own deductions and conclusions as to the nature of the materials available, the difficulties of making and maintaining the required work and of doing other work affected by site conditions and must accept full responsibility therefor.

#### 1-07 STORAGE

The Contractor shall, to the approval of the Engineer, erect within the working areas assigned to it, buildings and other facilities necessary for the safe storage of materials and equipment.

#### 1-08 CONTRACTOR'S CAMP

Contractor shall be responsible for supplying his own accommodation.

#### SPECIAL PROVISIONS

-24-

## 1-09 WATER SUPPLY

The Contractor shall, to the approval of the Engineer, make all necessary arrangements for the supply of water needed for all purposes at the site.

#### 1-10 COMMUNICATIONS

The Contractor shall be responsible for providing his own communications.

### 1-11 SEWAGE DISPOSAL AND SANITATION

The Contractor shall, to the approval of the Engineer, provide and maintain adequate toilet facilities at the site and no pollution shall result from these installations.

#### 1-12 FIRE PRECAUTIONS

)

The Contractor shall provide all necessary precautions against fire and shall rigidly comply with all laws, rules and regulations relating thereto.

In the event of fire, the Contractor will be required to fight the fire to the full limit of its available manpower and equipment. If a fire is caused by an act or omission on the part of the Contractor it shall bear all costs incurred in fighting it, including those of the Owner.

#### 1-13 DECANT WATER

The Contractor is advised that water from the tailings pond is decanted beneath the dike. It shall be the responsibility of the Contractor to select a method of construction that will in no way impair the discharge of the decant water.

# SPECIFICATION SECTION 2 EARTHWORK

#### 2-01 SCOPE

The work covered in this section includes all earthwork, clearing and development of borrow pits, establishment and maintenance of access and haulroads, dewatering and extending of the decant discharge culverts necessary for the fulfillment of the contract.

#### 2-02 GENERAL ARRANGEMENTS

All excavation, fill placing and other construction work shall be completed to the lines, elevations and sections shown on the drawings or directed by the Engineer.

Fill material shall be obtained from borrow areas suggested in Section 1 hereof or from other locations which may be located and developed during the course of construction and as approved by the Engineer. Approval by the Engineer of a source of fill material shall not be construed as constituting approval of all materials to be taken from that source.

## 2-03 CLEARING

The work to be done under this Clause shall comprise the supply of all labour, material and plant and the performance of all work necessary for clearing of the site as shown on the drawings, as required by the Engineer and as specified herein.

Clearing shall consist of cutting and disposing of all trees, shrubs, brush, debris and all other perishable materials, including fallen trees and logs within the areas to be cleared.

All trees, shrubs and brush shall be cut to within two inches above the ground surface. The organic cover of topsoil on the ground surface shall be left intact, except where excavation is required as stated in these documents.

All vegetation and debris resulting from clearing operations regardless of size, shall be removed from the areas cleared, and shall be disposed of by the following methods, upon written approval of the Engineer.

- (a) Combustible materials may be piled and burned on open fires as specified herein. Material to be disposed of in this way shall be completely burned so that it is all reduced to ashes.
- (b) Materials obtained from clearing which cannot be burned may be placed in nearby disposal areas as directed by the Engineer. The material placed in disposal areas shall be crushed with a tractor or other heavy equipment to a thickness of not more than five feet. The material shall be covered with mineral soil obtained from the borrowing operation compacted to a thickness of not less than two feet.

The Contractor shall be responsible for any damage done by fire resulting from the work under this item and shall at no time leave a fire unattended until it is fully extinguished. All burning shall be done in strict conformance with the rules and regulations of local, provincial, and federal agencies and it shall be the responsibility of Contractor to obtain all burning permits.

Sufficient equipment shall be ready and available together with a sufficient force of men to control burning operations at any time.

Measurement for payment for clearing will be made of the number of acres cleared in accorcance with these specifications, measured to the nearest 1/10 acre as the projection onto a horizontal plane.

Payment for clearing will be made at the unit price per acre bid in the Schedule of Quantities and Unit Prices.

#### 2-04 STRIPPING

The work to be done under this Clause shall comprise the supply of all labour, material and plant for the performance of all work necessary for the stripping of organic materials in order to expose underlying mineral soils in the borrow areas and new dike foundation areas as shown on the drawings and as specified by the Engineer.

The stripped material shall be stockpiled in nearby areas under the direction of the Engineer.

Payment for stripping will be made at the unit price per cubic yard shown in the Schedule of Quantities and Unit Prices.

Measurement shall be by cross-section, measured before and after construction in the borrow pit and new dike foundations. Page 395 EGM-2013-00163

-26-

-27

## 2-05 FOUNDATION PREPARATION

The work to be done under this item shall comprise the supply of all labour, material and plant for the performance of all work necessary for the preparation of the foundations for the dike as shown on the drawings, as specified herein and as required by the Engineer.

Foundation preparation shall be scheduled such that the appropriate fill material may be placed shortly thereafter. No fill material shall be placed on any part of the foundation area until each part of the foundation has been approved by the Engineer.

Foundation preparation shall include the removal of any coarse rock or boulders that are laying where construction is to take place. The coarse rock and boulders shall be removed to ensure a good contact between the new and the existing work. The coarse rock may be removed by bulldozing the rock off the crest and down the downstream slopes so that the remaining rock protruding above the general surface is not larger than six inches in size.

If necessary, the Engineer may require that the foundation surface be moistened or dried prior to compaction, and scarified, moistened or dried prior to placing of the fill material to create a satisfactory bond between the foundation and the fill materials.

The foundation surface shall be compacted by four complete passes of compaction equipment as specified herein. Pockets of poor or unsuitable materials, which during this operation cannot be satisfactorily compacted, shall be excavated to the limits ordered by the Engineer.

Unsuitable materials excavated and disposed of when ordered by the Engineer shall be measured by cross-sectioning the area to be excavated before and after removal. Payment will be made at the unit price bid for "Unsuitable Material" in the Schedule of Quantities and Unit Prices.

Foundations soils which become soft due to inadequate control of surface or subsurface water, or for any other reason become unacceptable due to the Contractor's operations, shall be removed and replaced with fill material and compacted as specified herein at no additional expense to the Owner.

The placing of fill will not be permitted on foundation soils which are frozen. The removal of any frozen foundation soils shall be accomplished at no additional expense to the Owner.

Measurement for payment for the preparation of the foundations will be made of the actual prepared surface area, projected onto a horizontal plane, measured in square yards, prepared as specified herein, with no allowance made for irregularities.

Payment for the preparation of the foundation soil complete in every respect and as specified herein, will be made at the unit price per square yard bid in the Schedule of Quantities and Unit Prices.

# 2-06 TRIM EXISTING DIKE

In order to provide sufficient working width where the existing dike was overbuilt during previous construction, this extra material shall be incorporated into the new work.

As the new fill is placed, the extra fill is to be progressively cut from the existing embankment back to the original neat line and mixed into the new fill to produce a homogeneous material within the specifications for the zone being constructed.

Care shall be taken that no excavation shall go into the dike beyond the existing neat line as shown on the drawing and as shown in the field by the Combined Survey Crew.

Payment for this work shall bear the unit price per cubic yard bid in the Schedule of Quantities and Unit Prices and shall cover all costs to carry out the work.

Measurement shall be by cross section back to the existing neat line.

## 2-07 DRAINAGE ZONE

(a) Scope of Work

The work to be carried out under this item shall comprise the supply of all labour, material, plant, equipment, fuel and the performance of all work necessary to prepare, develop, excavate, load, haul, rehandle if necessary, place, compact, upgrade the existing haul road, maintain, leave in good condition and any other operations necessary to carry out the work as required by the Engineer.

(b) Fill Material

(1.) Sand and Gravel

This material is a clean sand and gravel or clean gravel

-29-

and cobbles, the gradation of which lies within the shaded envelope shown on Figure 1. Material in this size range is available about 1-1/2 miles from the dike.

Cobbles and boulders larger than nine inches shall be removed from all fill prior to compaction.

All fill material shall be free of organic materials, roots, and other perishable materials. No fill material shall contain ice or snow, or shall be placed in a frozen condition.

(2.) Rock Toe

This material is an igneous rock to be selected from the waste pile at the Canex Mine located approximately six miles from the dike.

The rock shall be well graded within a size range of 3/4 inch to 12 inches with very few fines.

The material shall be free of organics, roots, ice or snow or other deletrious materials.

The material shall be placed in layers not exceeding 18 inches in thickness and be compacted by at least four passes of the grid-roller specified in Paragraph 2-07 (e).

Payment for this material shall be at the unit price per cubic yard bid in the Schedule of Quantities and Unit Prices and shall cover all costs to carry out the work.

Measurement shall be by cross-section from the existing ground contours to the neat line.

## )7 (c) Borrow Operations

Fill materials shall be obtained from the borrow area as indicated in the Tender Documents and as approved by the Engineer. Approval by the Engineer of a source of fill material shall not be construed as constituting approval of all materials to be taken from that source.

The Contractor shall conduct its operations in borrow areas in such a manner which shall ensure that the maximum possible volume of suitable construction material may be obtained. Measures shall be taken to ensure adequate drainage of water

2-07

from the borrow areas so that the borrow material is obtained at a water content suitable for compaction and so that the borrow operations are not affected adversely. Ponding and infiltration of water shall be prevented.

Some of the material in the borrow areas may be frozen. The Contractor shall conduct its operations in such a manner to ensure that the frozen material shall be thawed prior to placement in the dikes. To meet this requirement the Contractor shall open and work as large an area of the borrow areas practical, and shall rip, scarify, disc, harrow or use any other similar means to expose the frozen material to permit thawing.

The detailed planning of the operation of the borrow area shall be the responsibility of the Contractor and shall be subject to the approval of the Engineer.

Prior to commencement of the work, the Contractor shall submit for approval by the Engineer, a plan showing the details of its proposed methods and the sequence and schedule of operations to be followed for the utilization of the borrow area to obtain the required fill material. During construction the plan shall be reviewed and modified as required. A copy of the modified plan and schedule shall be provided for the Engineer's approval prior to implementation of any changes.

Unsuitable material shall be disposed of as directed by the Engineer and graded off to present a reasonably uniform appearance.

The Contractor shall be responsible at all times for the safe operation of the borrow area. All slopes left permanently exposed shall be approved by the Engineer.

2.07

(d)

Haul Roads

Approval by the Engineer of any proposed haul roads shall be obtained before commencing construction of the haul roads.

All haul roads built and maintained by the Contractor shall be available, without charge, for use by the Engineer and by others authorized by the Engineer, and at completion of the Contract, shall become the property of the Owner.

2-07 (e) Compaction Equipment

The Drainage Zone shall be compacted with a grid-roller towed by a suitable tractor. The grid-roller shall be a Hyster -31-

#### EARTHWORK

Model B with concrete ballast weighing approximately 13 tons, or an alternative approved by the Engineer.

Power tampers for compaction near structures shall weigh not less than 200 pounds and shall have a ramming foot area not exceeding 80 square inches. The rammer shall be capable of delivering at least 200 foot pounds of compacting energy per blow.

2-07

(f)

#### Placing and Compacting

No fill material shall be placed in any section of the dike until the foundation soil for that section has been suitably prepared according to the requirements of these specifications.

Placing of fill material shall be directed at obtaining a stable and a reasonably homogeneous fill. The fill material shall be spread in approximately horizontal layers of uniform thickness by bulldozers or other approved means. If necessary, discing, harrowing, or other approved means shall be employed to break up the material and to blend it before compaction.

The thickness of sand and gravel layers shall not exceed twelve inches before compaction.

The fill shall be placed in such a way that the top surface of any section, along the axis of the dike, shall remain approximately level. During spreading and compaction, a slope towards the downstream toe shall be maintained on the fill surface providing a transverse grade not exceeding ten percent so that water from precipitation will drain. In order that the effect of precipitation on placed fill be minimized, the surface shall be rolled smooth, and adequate drainage shall be provided prior to periods of precipitation when operations must be suspended.

Care shall be maintained so that the mixing of the Drainage Zones and Common Fill is not allowed to take place. Each zone shall be kept clearly separate.

All openings through the dike for construction purposes shall be subject to the Engineer's approval. The slope of openings left through dikes and at the end of any unfinished section shall not be steeper than four horizontal to one vertical.

The water content of the fill prior to and during compaction shall be distributed uniformly throughout each layer. The water content shall be maintained within the range required to obtain the specified soil density during compaction.

Each layer of fill of "Drainage Zone - Sand and Gravel" shall be compacted by at least four complete coverages of get too EGM-2013-00163

compaction equipment as specified in paragraph 2-07 (e). Additional coverages with the compaction equipment shall be made if necessary to ensure the fill materials are compacted to a dry density at least equal to 95% of the laboratory maximum dry density as determined from the Proctor compaction tests as specified in ASTM D698.

No separate payment will be made for compaction, watering or drying of the fill.

Overbuilding or underbuilding shall be remedied at the Contractor's expense to the satisfaction of the Engineer.

(g) Measurement and Payment for "Drainage Zone - Sand and Gravel"

The unit price tendered for "Drainage Zone" shall include all costs to complete the work as described in Section 2-07, and as detailed elsewhere in the Tender Documents. A free-haul distance of two miles is to be included in the tender price for the item "Drainage Zone - Sand and Gravel."

The unit of measure is the cubic yard and is the volume measured in place on the dike by cross-sectioning before and after the placement and compaction of the drainage zone.

All measurements for payment purposes shall be carried out by a survey crew as laid out in Paragraph 2-11. Measurement will be made to the theoretical neat lines where a zone is built to or beyond the theoretical neat line. Measurement will be made to the actual surface where the surface of a zone is not built out to the theoretical neat line. Payment for all work carried out under this Section and completed in all respects will be the product of the volume measured and the unit price tendered for "Drainage Zone."

#### 2-08 SELECT IMPERVIOUS AND COMMON FILL

2.08 (a) Scope of Work

The work to be carried out under this item shall comprise the supply of all labour, material and plant, fuel and the performance of all work necessary to prepare and maintain

2-07

borrow areas and haul roads, rip, excavate, load, transport, dump, spread and compact fill material for the tailings dikes as shown on the drawings, as required by the Engineer and as specified herein.

2-08

(b)

#### Fill Material

Select impervious fill shall be a glacial till, well graded with a maximum size of 9 inches and with at least 20% finer than the No. 200 U.S. Standard sieve size.

Common fill shall be a glacial till, well graded with a maximum size of nine inches.

Both select impervious fill and common fill must be of a gradation and moisture content that allows them to be placed and adequately compacted as specified herein.

All fill shall be free of organic materials, roots, and other perishable materials. No fill material shall contain ice or snow, or shall be placed in a frozen condition.

Cobbles and boulders larger than nine inches shall be removed from all fill prior to compaction.

2 - 08(c)

)

#### Borrow Areas

Fill material shall be obtained from the borrow areas near the east abutment of the existing dike and as approved by the Engineer. Approval by the Engineer of a source of fill material shall not be construed as constituting approval of all materials to be taken from that source.

2-08

(d)

#### Borrow Operations

The Contractor shall conduct its operations in borrow areas in such a manner which shall ensure that the maximum possible volume of suitable construction material may be obtained. Measures shall be taken to ensure adequate drainage of water from the borrow areas so that the borrow material is obtained at a water content suitable for compaction and so that the borrow operations are not affected adversely. Ponding and infiltration of water shall be prevented.

Some of the material in the borrow areas may be frozen. The Contractor shall conduct its operations in such a manner to ensure that the frozen material shall be thawed prior to placement in the dikes. To meet this requirement, the Contractor shall open and work as large an area of the borrow

area as practical, and shall rip, scarify, disc, harrow or use any other similar means to expose the frozen material to permit thawing.

The detailed planning of the operation of the borrow area shall be the responsibility of the Contractor and shall be subject to the approval of the Engineer.

Prior to commencement of the work, the Contractor shall submit for approval by the Engineer, a plan showing the details of his proposed methods and the sequence and schedule of operations to be followed for the utilization of the borrow area to obtain the required fill material. During construction the plan shall be reviewed and modified as required. A copy of the modified plan and schedule shall be provided for the Engineer's approval prior to implementation of any changes.

The Contractor shall be responsible at all times for the safe operation of the borrow area. Slopes left permanently exposed shall be not steeper than one vertical on two horizontal and shall be approved by the Engineer.

Unsuitable materials shall be removed and placed in disposal areas as directed by the Engineer. The disposal area and pile shall be kept neatly graded for appearance, drainage and stability.

2-08

(e)

### Haul Roads

Approval by the Engineer of any proposed haul roads shall be obtained before commencing construction of the haul roads.

All haul roads built and maintained by the Contractor shall be available, without charge, for use by the Engineer and by others authorized by the Engineer, and at completion of the Contract, shall become the property of the Owner.

2-08

#### (f) Compaction Equipment

The zone shall be compacted with a grid-roller towed by a suitable tractor. The grid-roller shall be a Hyster Model D with concrete ballast weighing approximately 13 tons or an alternative approved by the Engineer.

Power tampers for compaction near structures shall weigh not less than 200 pounds and shall have a ramming foot area not exceeding 80 square inches. The rammer shall be capable of delivering at least 200 foot pounds of compacting energy per blow.

### 8 (g) Placing and Compacting

No fill material shall be placed in any section of the dike until the foundation soil for that section has been suitable prepared according to the requirements of these specifications.

The placing of fill material shall be directed at obtaining a stable and a reasonably homogeneous fill. The fill material shall be spread in approximately horizontal layers of uniform thickness by bulldozers or other approved means. If necessary, discing, harrowing, or other approved means shall be employed to break up the material and to blend it before compaction.

The thickness of fill layers shall not exceed twelve inches before compaction.

The fill shall be placed in such a way that the top surface of any section, along the axis of the dike, shall remain approximately level. During spreading and compaction, a slope towards the downstream toe shall be maintained on the fill surface providing a transverse grade not exceeding ten percent so that water from precipitation will drain. In order that the effect of precipitation on placed fill be minimized, the surface shall be rolled smooth, and adequate drainage shall be provided prior to periods of precipitation when operations must be suspended.

If the impervious fill material is too dry or too wet, water shall be added or removed by working the fill with a harrow, scarifier or other approved equipment until the water is uniformly distributed and satisfies the requirements of these specifications. Any conditioning of the fill material that may be required to obtain fill with a water content within the required range may be undertaken in the borrow area or after placement in the layer.

Each layer of fill shall be compacted by at least four complete coverages of the compaction equipment as specified in paragraph 2-08 (f). Additional coverages with the compaction equipment shall be made if necessary to ensure both the select impervious and the common fill materials are compacted to a dry density at least equal to 95% of the laboratory maximum dry density as determined from the Proctor compaction tests as specified in ASTM D698.

The surface of the existing dike, against which the select impervious fill or common fill is to be placed, is to be bladed and scarified and then blended in with the new materials to create a homogeneous fill free of any unconformity.

The fill within any zone shall be effectively bladed and mixed so as to create a homogeneous gradation. Care shall be taken to avoid building horizontal layers into the dike that are of a gradation differing largely from the adjacent layers.

If, in the opinion of the Engineer, the surface of the prepared foundation, or the rolled surface of any layer of the fill is too dry or too smooth to bond properly with the layer of material to be placed thereon, it shall be moistened and worked with a harrow, scarifier, or other suitable equipment, in an approved manner and to a sufficient depth to provide a satisfactory bonding surface, before the succeeding layer of material is placed.

If, in the opinion of the Engineer, the surface of the prepared foundation, or the rolled surface of any layer of the fill is too wet for proper compaction of the layer of fill material to be placed thereon, it shall be removed and allowed to dry, or worked with harrow, disc, or other suitable equipment, to reduce the moisture content to the required amount; then it shall be recompacted before the succeeding layer of fill is placed thereon.

Ruts in the surface of any layer shall be graded level and recompacted to the approval of the Engineer.

Any and all materials not approved as fill which accumulate on the surface of any layer or prepared foundation, shall be removed by the Contractor before placing the succeeding layer.

Final acceptance of the fill material will only be made after the material has been placed, spread and compacted in place. Rejection by the Engineer of fill material may be made in the borrow area, in the transporting vehicle, or in place. The Contractor shall co-operate with the Engineer to ensure that only acceptable fill material will be hauled from the borrow area to the work.

Particular care shall be taken to ensure that the compaction requirements are satisfied in areas of fill adjacent to any structure. Compaction adjacent to the structures shall be carried out carefully and thoroughly utilizing approved power tampers where necessary to ensure that the material is tightly compacted at the boundaries of the structure. The thickness of these fill layers compacted by power tampers shall not exceed four inches before compaction. No cobbles or pebbles larger than two inches in size will be permitted in the fill material within one foot of structures. Fill shall be placed and compacted against the structures only during laylight hours, unless adequate lighting is provided to the satisfaction of Page 405 EGM-2013-00163

Any layer or layers which, in the opinion of the Engineer, have suffered a reduction in density after compaction due to the action of frost, rain or for any other reason, shall be removed by the Contractor at no additional compensation, before placing operations are resumed.

Fill shall not be placed in a frozen condition and shall not be placed on a surface which is frozen or on which there is any snow or ice. Placing of fill in freezing weather shall not be permitted except when approved by the Engineer, and when proper measures are taken to prevent freezing of the material.

No separate payment will be made for compaction, or work entailed to adjust the moisture content or removal and disposal of materials rejected after being placed on the dike. All openings through the dike for construction purposes shall be subject to the Engineer's approval. The slope of openings left through dikes and at the end of any unfinished section shall not be steeper than four horizontal to one vertical.

Overbuilding or underbuilding shall be remedied at the Contractor's expense to the satisfaction of the Engineer.

Measurement and Payment for "Select Impervious and Common Fill"

The unit price tendered for "Select Impervious and Common Fill" shall include all costs to complete the work described in this Section 2-08, and as detailed elsewhere in the Tender Documents. A free-haul distance of 3,000 feet is to be included in the tender price for the Item "Select Impervious and Common Fill".

The unit of measure is the cubic yard and is the volume measured in place on the dike by cross-sectioning before and after the placement and compaction of the fill.

All measurements for payment purposes shall be carried out by a combined survey crew as laid out in paragraph 2-11. Measurement will be made to the theoretical neat lines where a zone is built to or beyond the theoretical neat line. Measurement will be made to the actual surface where the surface of a zone is not built out to the theoretical neat line.

2-08 (h)

)

-38-

Payment for all work carried out under this Section and completed in all respects will be the product of the volume measured and the unit price tendered for "Select Impervious and Common Fill".

### 2 - 08

#### Measurement and Payment for Unsuitable Materials (i)

The unit price tendered for "Unsuitable Materials" shall include all costs to complete the work as described in this Section and as detailed elsewhere in the Tender Documents. No overhaul will be paid on this item.

The unit of measure is the cubic yard and the volume for payment purposes is measured by cross-sectioning the area to be excavated before removal and after removal.

Only material designated as "Unsuitable Material" by the Engineer and removed and disposed to his satisfaction will be paid for.

All measurements for payment purposes shall be carried out by a Combined Survey Crew as laid out in paragraph 2-11.

#### 2-09 DECANT CULVERTS

#### 2 - 09(a)

### Scope of the Work

The Contractor shall remove part of the existing wood flume as necessary; purchase, have delivered and handle the pipes, haul, place, and compact bedding and backfill material; install and connect the pipes; backfill and compact and carry out all other works necessary to extend the east decant culvert. The cost of all labour, materials, plant, equipment, fuel and other items necessary shall be included in the unit price tendered for "Decant Culverts" in the Schedule of Quantities and Unit Prices.

The Owner will arrange to divert the flow through one decant during the period of alterations to the other. The Owner will connect the wood flume to the finished east culvert.

The Contractor is to co-operate with the Owner's forces and to keep the work necessary to rebuild the flume to a minimum.

2-09

(b)

### Materials

The decant pipes shall be 24" diameter, 14 gauge, standard 2 ounce galvanized corrugated  $(2-2/3" \times 1/2")$  pipe.

Couplings shall be two-piece corrugated (or Universal Dimple) bands, 24 inches long with angle flanges drilled for bolted connection. All metal parts shall be zinc-coated.

A 3/8 inch thick by 24 inch wide continuous neoprene gasket shall be installed between the coupling and the pipes being connected.

A caulking compound of thiocaulk (polysulphide architectural grade) shall be applied on the pipe side of the neoprene gasket.

All pipe and couplings shall be fabricated in accordance with Specification 501-74 of the Corrugated Steel Pipe Institute.

The bedding and backfill material shall be a clean coarse sand with a maximum size of 3/4". Not more than 15% by weight shall pass the No. 200 U.S. Standard sieve.

2 - 09

(c)

)

### Installation

The culvert shall be installed to the manufacturer's recommendations. A bed of sand 18" thick shall be laid and compacted in layers not exceeding 4" thick, each layer being tamped to 95% of maximum density as established by ASTM D698. A bed shaped to the outside of the pipe and sloped to the correct grade shall be scraped from this bed to a depth of 6". The pipe shall be laid in this trench, connected to the existing pipe, and backfill placed on each side of the pipe in 4" layers and tamped to 95% of maximum density. The backfill shall be continued in this manner until 18" has been placed on top of the pipe. Care shall be taken to save the culvert from damage by the passage of vehicles.

Particular care shall be taken to provide a completely leakproof joint under full flow conditions. Any joint found to leak shall be disassembled and reconnected as necessary until a tight joint is achieved.

The tamper shall be as specified in paragraph 2-07 (e).

-40-

### 2-09 (d) Measurement and Payment of "Decant Culverts"

The unit price tendered for "Decant Culverts" shall include all costs to cover the work as described in this Section and as detailed elsewhere in the Tender Documents.

The payment for the work shall be the product of the length of culvert installed from centre of joint to end and the unit price tendered in the Schedule of Measurement and Unit Prices.

### 2-10 BORROW PIT TREATMENT

In the event it is found necessary to carry out a final treatment of the select impervious and common fill borrow pit, the following work shall be completed to the satisfaction of the Engineer.

Areas specifically designated for treatment shall be first scarified to a depth of twelve inches using a ripper or harrow as necessary to break down all lumps of earth to a size smaller than three inches.

Topsoil stockpiled during the stripping operations shall be hauled into the area to be treated and spread to an even depth to present a neat and smoothly graded appearance.

The area shall be left sloped to drain with no pockets of water.


Payment for this work shall be at the unit price shown in the Schedule of Quantities and Unit Prices and shall cover all costs to carry out the work.

Measurement shall be by the square yard as projected on a horizontal plane and shall be carried out by the Combined Survey Crew.


### 2-11 COMBINED SURVEY CREW

Survey control, layout and measurements of all work performed are to be carried out by a Combined Survey Crew supplied by the Owner and under the jurisdiction of the Engineer. The Contractor shall assign one or more members of his staff to serve on the crew at the expense of the Contractor. The representative supplied by the Contractor to the survey crew shall satisfy the Contractor as to the accuracy of the survey work. In case of conflict over measurements the Engineer and the Contractor shall exhaust all means of arriving at a satisfactory agreement before applying the arbitration clause referred to in the General Conditions.

The Contractor shall employ a grade foreman to bring up slope stakes and to ensure the work is kept to the correct slopes. EGM-2013-00163



\_



# **Golder Brawner Associates**

CONSULTING GEOTECHNICAL ENGINEERS

H. Q. GOLDER C. O. BRAWNER V. MILLIGAN J. L. SEYCHUK N. R. MCCAMMON R. M. WILSON D. B. CAMPBELL A. Á. GASS D. L. PENTZ

REPORT TO

COMINCO LTD.

RE

HB TAILINGS DAM NEAR SALMO, B.C.

Distribution: 6 copies - Cominco Ltd. Trail, B.C. 2 copies - Golder, Brawner & Associates Ltd. Vancouver, B.C.

V72109

June 22, 1972

GOLDER, BRAWNER & ASSOCIATES LTD., 224 WEST 8th AVE., VANCOUVER 10, B.C., CANADA • TELEPHONE 879-9265 Page 412 1648

### TABLE OF CONTENTS

-----

Page No. 1 INTRODUCTION 1 SUMMARY OF CONCLUSIONS AND RECOMMENDATIONS 2 PROCEDURE 3 HB TAILINGS DAM 5 FOUNDATION SOILS 5 EMBANKMENT STABILITY 6 SAFETY AGAINST OVERTOPPING 7 SEEPAGE 7 SURFACE EROSION

### INTRODUCTION

This report presents the results of an investigation of the existing HB Tailings Dam south of Salmo, B.C., together with an assessment of its stability. An assessment is also made of the suitability of the existing dam to impound tailings that would be generated in the event that Cominco decide to put the HB mine and concentrator back into operation. The investigation and this report were authorized by Cominco Purchase Order HB2 dated June 1, 1972.

### SUMMARY OF CONCLUSIONS AND RECOMMENDATIONS

- 1) The water level in the existing tailings pond can be raised to elevation 2502; 3 ft. below the crest of the existing HB Tailings Dam.
- 2) Normal water surface in the tailings pond should be maintained at a level not higher than elevation 2502 to assure that adequate freeboard is maintained.
- The results of stability analyses indicate that the existing embankment has an adequate factor of safety with respect to a shearing failure of the downstream slope.
- 4) The foundation soils on which the HB Tailings Dam has been constructed consist of dense glacial till. These glacial till soils exhibit high shear strength characteristics, and are relatively incompressible. They provide unyielding foundation support for the tailings dam, and preclude the possibility of a shearing failure through the foundation.
- 5) In the event that Cominco decide to raise the crest of the existing tailings dam, this should be done by placing additional fill on the crest, and on the downstream fill slope. A drainage blanket consisting of clean, well-graded sand and gravel should be provided adjacent to the existing downstream fill slope prior to placement of new fill.

Page 414 EGM-2013-00163

### PROCEDURE

The HB Tailings Dan was insepcted by the writer in company with Mr. G. Shoblom of Cominco Ltd. on May 24th and 25, 1972. At the time of this inspection, the existing borrow pits at the east and west abutments of the dam were examined to gain an appreciation of the nature and type of soils that had been used in its construction.

Two test pits were excavated into the existing embankment fill. Test pit no. 1, located on the crest of the tailings dam was excavated to a depth of 4 1/2 ft. using a small backhoe. Owing to difficulty of access, test pit no. 2, located at the toe of the fill slope was excavated by hand. Representative samples of soil from test pits 1 and 2 were retained for laboratory testing.

A 20 ft. long section of perforated pipe was installed in a drilled hole on the centreline of the dam crest to permit measurement of the phreatic water surface within the section.

Representative samples of the embankment fill materials were subjected to grain size analysis to determine the particle size distribution of the fill material. Two typical grain size curves are shown on Fig. 5. Samples of the no. 4 minus fraction of the material were subjected to laboratory shear strength tests to evaluate the shear strength parameters of the soils used in the construction of the embankment (see Fig. 6). A ground survey by Mr. H. Dixon of Cominco Ltd. established the configuration of the existing downstream fill slope.

Using the data collected in the course of the field and laboratory investigations, stability analyses were performed to

> Page 415 EGM-2013-00163

assess the factor safety of the dam with respect to potential shearing failure through the embankment.

### HB TAILINGS DA'I

The HB Tailings Dam is located approximately four miles south of Salmo, B.C. (see Fig. 1). The dam was originally constructed in 1955 for retention and storage of tailings produced at the HB Mine, which operated from 1955 to 1966. The mining operations were suspended in 1966.

The crest of the HB Tailings Dam is approximately 650 ft. long, and is curved in the upstream direction. The maximum height of the dam is of the order of 50 to 60 ft. above the original ground surface. Contours on the downstream face of the tailings dam, together with three typcial cross sections are shown on Fig. 2. Photographs of the tailings dam are shown on Figs. 3 and 4.

The HB Tailings Dam is equipped with two decant outlets to pass water from the upstream to the downstream side of the structure. Each decant consists of a timber tower on the upstream side of the dam, with a 24 in. diameter steel corrugated pipe passing through the embankment from the upstream to the downstream side of the dam. The present inlet elevation at the easterly decant tower is 2496.3, while the inlet elevation at the westerly decant tower is 2499.6. The east decant tower passes normal flows which enter the tailings dam, while the west decant tower would serve as an emergency outlet in the event that the capacity of the cast decant were exceeded.

### **GOLDER, BRAWNER & ASSOCIATES**

Page 416 EGM-2013-00163 The HB tailings dam is an earthfill embankment constructed of materials borrowed from the east and west abutments. We understand that the borrow materials were excavated and transported to the section by bulldozers. Compaction within the section was achieved by the traffic of the construction echipment used to spread and place the fill.

The materials used in construction of the dam consist of silty sand and gravel with scattered cobbles and small boulders. Nost of the available borrow materials have now been removed from the east abutment. The limited amount of material which remains on the east abutment consists predominantly of slightly silty fine to medium sand. The materials from the west borrow pit consist of a well graded heterogeneous mixture of silt, sand, gravel, cobbles and boulders (glacial till). The materials incorporated within the west half of the dam contain more stone than those within the east half, reflecting the higher stone content of the borrow materials that were available from the west abutment.

The crest of the dam was raised periodically during the period 1955 to 1966 as the tailings storage requirements increased. The crest of the dam was raised by the downstream method of construction, i.e. additional fill was placed on the crest and on the downstream slope of the dam.

We understand that the original dam was constructed with an earthfilled timber crib retaining wall at the downstream toe. Subsequent to construction of this retaining wall, a flat

## GOLDER, BRAWNER & ASSOCIATES

Page 417 EGM-2013-00163 4.

earth fill supporting berm has been constructed on its downstream side, and the crib has been covered over. Prior to placement of this stabilizing fill, several concrete pipe drains were installed at the downstream toe of the dam. The outlets of some of these drains were seen during the site inspection on May 25th.

### FOUNDATION SOILS

Soil exposures at the downstream too of the dam were examined during the May 24th - 25th inspection. The in situ soils exposed at the downstream too of the HB Tailings Dam consist of dense glacial till composed of a heterogeneous assortment of silt, sand, gravel and occasional small cobbles. The material is very dense, and exhibits high shearing strength characteristics. These materials are capable of providing foundation support for the structure without any danger of shearing failure or significant settlement under the weight of the embankment fill.

### E'BANKMENT STABILITY

Direct shear tests on representative samples of the embankment fill show that the fill material has an angle of internal friction of approximately 35 1/2° with 0 cohesion. The flat toe berm below elevation 2470 on the downstream side of the dam provides a high degree of stability to the structure, and precludes the possibility of a deep seated shearing failure within the embankment. This toe berm reduces the effective height of the embankment to approximately 35 ft.

### GOLDER, BRAWNER & ASSOCIATES

Page 418 EGM-2013-00163 The stability of the existing embankment between elevation 2470 and the present creat at elevation 2505 is governed by the gradient of the downstream fill slope between these elevations, the shear strength characteristics of the embankment fill, and the position of the phreatic surface within the section. The approximate position of the phreatic surface for a tailings pond level at elevation 2503 is shown on section BB, Fig. 2. The phreatic surface shown on Section ED is based on the water level measurement in the observation well installed at Section AA on the centreline of the dam, a water level at elevation 2503 on the upstream face, and the approximate position of the drains on the downstream side of the buried timber crib.

The stability analyses indicate that the minimum factor of safety of the embankment, for potential failure surfaces which intersect the upstream slope at or below the crest is 1.3. The factor of safety is considered adequate, although it is near the lower limit of the range considered acceptable by conventional engineering practice.

### SAFETY AGAINST OVERTOPPING

The size of the catchment area surrounding the HB Tailings Pond is approximately 480 acres. The approximate boundaries of the catchment area are indicated on Fig. 1. The closest station at which long term percipitation records have been maintained is Nelson, B.C., which is approximately 26 miles north of the HB Tailings Dam. The long term percipitation

### GOLDER, BRAWNER & ASSOCIATES

Page 419 EGM-2013-00163 records at Nelson indicate a maximum rainfall of 2.6 in. in 24 hrs. Assuming a runoff coefficient of 0.8, a rainfall of 2.6 inches in 24 hours over an area of 430 acres would result in an average runoff rate of approximately 40 cu.ft./sec. The two 24 in. diameter decant pipes are capable of passing between 50 and 60 cu.ft./sec. Thus, the existing decant system at the UB Tailings Dam is considered to have sufficient capacity to pass the maximum anticipated flow into the tailings pond. We therefore conclude, that the emisting outlet capacity is adequate, and that the structure would not be over topped during the maximum anticipated runoff.

### SEEPAGE

Based on examination of the ground surface at the downstream toe of the existing dam, the total leakage was estimated to be of the order of 5 to 10 gallons per minute. If the water surface in the pond is raised from its present level to elevation 2502, the rate of seepage will increase only slightly. Examination at points where drains exit on the downstream slope indicated that the existing drains are not carrying soil particles. The existing drains appeared to be operating satisfactorily.

### SURFACE EROSION

The presence of cobbles and gravel within the embankment fill affords a degree of erosion protection on the downstream face of the existing embankment. Examination of the dam indicates

### GOLDER, BRAWNER & ASSOCIATES

Page 420 EGM-2013-00163 7.

that no significant surface erosion has occurred on the downstream fill slope during the six year interval 1966 to 1972. Also, there is no evidence that wave action in the tailings pond has resulted in any significant deterioration of the upstream fill slope. The performance of the existing structure indicates that the dam has adequate protection against surface erosion.

In conclusion, our analyses and studies indicate that the existing HB Tailings Dam will perform satisfactorily after the water level in the tailings pond has been raised to elevation 2502. If during operation, it is decided that the crest of the dam should be raised to provide a greater depth of water for clarification of the tailings effluent, the crest of the dam should be raised by placing additional fill on the crest, and on the downstream fill slope. To assure that the phreatic surface within the section does not rise above the level of the existing downstream fill slope, a laver of free draining granular fill should be placed adjacent to the existing downstream slope, as illustrated on Fig. 7. The fill placed on the crest and on the downstream slope should be spread in horizontal layers not exceeding 12 in. thickness, and each layer should be compacted to a minimum density equivalent to 95 percent of maximum dry density as determined by the Standard Proctor Compaction Test prior to placement of each succeeding layer.

GOLDER BRAWNER & ASSOCIATES LTD.


Jaied & Campell

D.B. Campbell, P. Eng.

DBC/sm


GOLDER, BRAWNER & ASSOCIATES

Page 421 EGM-2013-00163




PROJECT No. 12/02


GR 19





102 T.S.

Contraction of the











BRAWNER &





09

Project



# **Golder Brawner Associates**

CONSULTING GEOTECHNICAL ENGINEERS

H. Q. GOLDER C. O. BRAWNER V. MILLIGAN J. L. SEYCHUK N. R. McCAMMON R. M. WILSON D. B. CAMPBELL A. A. GASS D. L. PENTZ H. G. GILCHRIST

REPORT TO COMINCO LTD. ON SITE INVESTIGATION AT EXISTING H.B. MINES TAILINGS POND

SALMO

B.C.

Distribution:

4 copies - Cominco Ltd. Trail, British Columbia

2 copies - Golder Brawner & Associates Ltd. Vancouver, British Columbia

January, 1974

V 73218

GRIT

GOLDER, BRAWNER & ASSOCIATES LTD., 224 WEST 8th AVE., VANCOUVER 10, B.C., CANADA • TELEPHONE 879-9266 • Page 480508800 / 6 EGM-2013-00163



# Golder Brawner Associates

CONSULTING GEOTECHNICAL ENGINEERS

H. Q. GOLDER C. O. BRAWNER V. MILLIGAN J. L. SEYCHUK N. R. McCAMMON R. M. WILSON D. B. CAMPBELL A. A. GASS D. L. PENTZ H. G. GILCHRIST

January 2, 1974

Cominco Ltd., Engineering Dept., Trail, B.C.

ATTENTION: Mr. D. Boyle

Re: Site Investigation at Existing H.B. Mines Tailings Pond, Salmo, B.C.

Dear Sir:

As requested by your Purchase Order No. HB 15017 dated October 26, 1973, and in accordance with our proposal of September 20, 1973, we have carried out a detailed drilling program at the above site. The purpose of this investigation was to determine the condition of the existing dyke and foundation soils to enable a detailed stability analysis to be carried out. This report is further to our report No. V 72109 of June, 1973.

### FIELD INVESTIGATION

Three boreholes were drilled at the site between October 29, 1973 and November 1, 1973 using a truck-mounted rotary drill rig. These boreholes were drilled to depths varying from 45 to 85 ft. and extended approximately 20 ft. into bedrock. One borehole was drilled from the crest and two boreholes from the lower slope of the existing tailings dyke as shown on Fig. 1. Standard split spoon samples were obtained of the overburden and wash samples of drill cuttings were obtained of the bedrock. All samples were identified in the field and returned to our laboratory for classification and testing.

Perforated plastic standpipes were installed in the open boreholes to enable groundwater levels to be monitored.

### SITE CONDITIONS

The existing tailings pond is located approximately 4 miles south of Salmo, B.C. The tailings dyke is located at the southern end of a valley and has been constructed 50 to 60 ft. high using borrow fill obtained from the abutment slopes. Contours of the downstream face of the dyke together with a typical cross section are shown on Fig. 1.

The borehole results indicate that the dyke is generally comprised of soft to firm brown sandy silt containing varying amounts of medium to coarse sand and fine gravel. Standard penetration test results gave average 'N' values of the order of 10 blows/ft. indicating a loose to compact state of relative density.

Examination of the overburden samples enabled an approximate estimate of the location of original ground surface beneath the dyke fill. The approximate location of the existing ground surface is shown on Fig. 2. In borehole 1, the natural ground surface was estimated to be located approximately 59 ft. below the crest of the dyke. Underlying the fill, a 4 ft. thick stratum of very dense silty till was identified overlying a 5 ft. thick layer of hard desiccated silt. Bedrock was encountered at approximately 68 ft. below the crest of the dyke.

In borehole 2, the original ground surface was estimated as being located approximately 27 ft. below the dyke fill surface. The boreholes en-

countered a 7 ft. thick stratum of soft to firm silt beneath the fill. Underlying the silt, a 2 ft. thick layer of sand and gravel was identified overlying bedrock.

In borehole 3, the original ground surface was estimated to be located approximately 20 ft. below the fill. The borehole encountered a 3 ft. thick stratum of dense silty till beneath the dyke fill. Underlying the silt, a 3 ft. thick layer of sand and gravel was identified overlying bedrock.

More detailed descriptions of the soil conditions are given on the Record of Boreholes. A cross section showing the inferred soil stratigraphy is shown on Fig. 2.

### GROUNDWATER CONDITIONS

The standpipes installed in the boreholes were monitored for approximately 4 weeks after installation to enable the water levels to stabilize. From the recorded water levels, we have inferred the phreatic surface in the dyke to be located as shown on Figure 2.

Inspection of the dam during the period of the drilling program indicated that seepage was occurring near the toe of the upper slope of the dam and at each abutment. Soft saturated soil was observed at several locations in the middle slope of the dam and very soft saturated soil was encountered at the east abutment.

This seepage and degree of saturation was not observed at the time of the original site investigation in May 1972. The occurrance of seepage above the phreatic line as inferred from the standpipe levels is believed to be caused by local variations in the permeability of the dam material. The location of the phreatic line is expected to vary somewhat across the dam.

### GOLDER, BRAWNER & ASSOCIATES

Page 433 EGM-2013-00163

### DYKE STABILITY

The investigation has indicated that the existing dyke has been constructed essentially with silty soils which have been placed in a loose condition. The design parameters used in our previous calculations are considered to be still applicable although the phreatic surface assumed in our original report appears to have been somewhat lower than now exists. This present condition may be a result of a change in ponded water level upstream. Stability calculations for the present condition indicate a safety factor against a shearing type failure of the order of 1.3 which is considered adequate.

It is understood that it is proposed to eventually raise the pond water level to a maximum elevation of 2502 ft. behind the existing dam. As the pond water level is raised, the phreatic surface will also rise. Stability calculations for these future conditions indicate a factor of safety against a shearing type failure of the order of 1.1 which is lower than is normally acceptable. To increase the dyke stability, it is recommended that a berm be constructed on the downstream section of the dam as shown on Fig. 3. Provision of this berm will increase the factor of safety to approximately 1.3 which is adequate.

### SEEPAGE

At present, seepage is occurring at the intersection of the upper and middle slope of the dyke and at the abutments. Examination of this seepage during the drilling program indicated that the flow was clear and did not appear to be carrying any soil particles. However, the dyke is essentially homogeneous and has been constructed with silty soils which are most susceptible to internal backward erosion. The potential for this type of erosion will increase as the ponded water level is raised. To provide protection against internal backward

### **GOLDER, BRAWNER & ASSOCIATES**

Page 434 EGM-2013-00163 erosion, filter material should be placed on the downstream slope of the dyke. This can be accomplished by constructing the previously recommended stability berm (Figure 3) of a suitable filter material which satisfies the gradation requirements shown on Figure 4. It is possible that mine waste rock will be suitable.

The berm should be adequately compacted to provide the required strength for support of possible future dyke extensions, yet should not be over-compacted so as to reduce its permeability. Generally, if heavy equipment is available and if the gradation of the filter material tends to be towards the coarser fraction of the range shown on Figure 4, satisfactory compaction without excessive reduction in permeability will be achieved by spreading the material in 16 in. lifts using a heavy crawler tractor.

We would be pleased to provide more specific construction details when the gradation of material and type of construction equipment are known.

To accommodate the seepage at the abutment, a filter blanket should be placed at these locations as shown on Fig. 3. This blanket should consist of similar filter material to that described above and should have a minimum thickness of 2 ft. This filter material should also be placed as described above.

It is pointed out that the specification given above for the filter material is critical if the filter blanket is to perform satisfactorily. As a result, we recommend, that when potential sources of material have been established, that we review the suitability of the material. In addition during raising of the ponded water level to elevation 2502, we recommend that the dyke be inspected by a member of our staff to ensure that the filter blanket is performing as desired.

5.

### GOLDER, BRAWNER & ASSOCIATES

Page 435 EGM-2013-00163 At the time of the drilling, examination of the upper face of the dyke indicated that some surface erosion had occurred due to water ponding on the crest of the dyke and flowing downstream. It is recommended that these slopes be renovated by using granular material. In addition some surface grading should be carried out on the crest of the dyke to prevent ponding of rain water. During this work the crest could be sloped inwards towards the pond in order to direct run-off in that direction.

### FUTURE DYKE EXTENSION

If the height of the existing dyke and pond level are increased in the future to elevations 2511 ft. and 2508 ft. respectively, the crest of the dyke should be raised by placing additional fill on the crest and on the downstream slope. In addition, the filter material recommended above should be extended as shown on Fig. 5 to a maximum elevation of 2500 ft. The additional filter material should be placed as previously recommended while the fill material should be placed in horizontal lifts of 12 inch maximum and compacted to at least 95 per cent of Standard Proctor Density.

We trust that this is the information you require. We would be pleased to discuss the report in more detail should you desire.

> Yours very truly, GOLDER BRAWNER & ASSOCIATES LTD.

ui

R.M. Wilson, P.Eng.

H.H. Hawson, P.Eng. HAWSON


RNW/HHH/sm V73218


GOLDER, BRAWNER & ASSOCIATES


Page 436 EGM-2013-00163

SINE


6.








CROSS SECTION A-A SHOWING		
INFERRED SOIL STRATIGRAPHY	FIGURE 2	
A PHREATIC SURFACE		




۰.

DATE Dec. 173




~




OLDER, BRAWNER & ASSOCIATES

EGM-2013-00183TE Dec. '73.



.....



<sup>1/12/17/20160</sup> 

Solu         PROFILE         SAMPLES         No           SUM         SERVICION         Status         SUMPLES         Status         Status         SUMPLES         Status         Status         SUMPLES         Status         Status<	DOCATION S BORE SAMPLER HAMMER W						
BALE         Image: Service Service         Image: Service Service Service         Image: Service Service		15		4 -	DYNAMIC PENETRATION RESISTANCE BLOWS/FT	- COEFFICIENT OF PERMEABILITY	YAL TING
SUFF TO FUNCT     2 50 4       SUFF TO FUNCT     2 50 5       SUFF TO FUNCT     3 50 5       SUFF TO FUNCT     3 50 5 <th></th> <th>STRAT P</th> <th>TYPE</th> <th>BLOWS / ELEVATIO</th> <th>SHEAR STRENGTH Cu, LB /SQ FT</th> <th></th> <th>STANDPIPE</th>		STRAT P	TYPE	BLOWS / ELEVATIO	SHEAR STRENGTH Cu, LB /SQ FT		STANDPIPE
SOFT TO FUNC SOFT TO FUNC SO	GR. SURFACE.						
SOFF TO FIRM:     4       SOFF TO FIRM:     4       BROWN SONDY       SULT WITH       SOFF TO FIRM:       BROWN SONDY       SOFF TO FIRM:       SOMM FORD I       SOFF TO FIRM:       SOMM SONDY       SOM FORD I       SOM FORD I       SOFF TO FIRM:       SOM FORD I       SOM FORD I <tr< td=""><td></td><td></td><td>2</td><td></td><td></td><td></td><td></td></tr<>			2				
SOFT TO FURN: NON-PLASTIC SMET WITH SULT WITH SULT WITH SULT WITH CORPESE SANDY 1 50 13 2 50 1		Z	2"		x-		
SOFT TO FUNC SOFT TO FUNC SROUND SANDY SILT WITH SULT WITH SOME NED 1 COARSE SAND I FINE GRAVEL. I SO I FINE GRAVEL. I SO I FINE GRAVEL. I SO I SOME NED I SOME STOREN I SOME I COARSE STORE STOREN I SOME I COARSE I SOME I COARSE				2490			
Non-Selastic     Below     Below     Below     Below       Solar With     Below     Below     Below       Solar With     Below     Below       I Below     Below     Below							
SOME MED 1 COARSE SAND 1 FINE GRAVEL. 2 50 13 2 50 13	NON PLASTIC BROWN SANDY						WL 230
I FINE GRAUEL.     I Z Z0       I Z Z0     I Z Z0	SOME MED. +		0	-			0
37/FF     57/FF			2"				
371FF     571FF     10     20     33       672FY     5700     10     20     33       CLAYEY     SLLT     10     20       05     MED     SANDE     10     20       06     MED     SANDE     10     20       07     MED     SANDE     10     10       07     MED     10     10     10       07     MED     10     10     10       07     MED     10     10     1				3			1 - A
STIFT STRATTING CARYEN SHUT CLAYEN SHUT CLAYEN SHUT WITH AT REAL OF MED SAND J. 200 STRESS SHUT SAND FINE GRAVELS SAND FINE GRAVELS SAND FINE GRAVELS SAND FINE SAND FINE S				2460			
CUT HI TRACE OF MED SAND TRAM BROWN DARK BROWN MED & CORRE SAND FINE SAND FINE CRAVELY DECRIFE REAVELY DECRIFE REAVELY DECRIFE REAVELY DECRIFE REAVELY REAVELY DECRIFE REAVELY	STIFF STRATIFIED						
HAND SADULY, F DARK BROWN SUT WITH SOME MED & COARSE SAND FINE GRAVUEL GRAVUEL GRAVUEL GRAVUEL SAND I GRAVEL TO JOHN (TILL), IN UNS SAND I GRAVEL TO JOHN (TILL), SAND I GRAVEL SAND I GRA	WITH A TRACE	-		2450			
SANDFINE GRAVEL # OFGANICS JERY DENSE DARK KEV SILT SAND4 GRAVEL SAND4 GRAVEL S	SILL WITH SOMEL					erie	a contraction and a contraction of the second se
KREY SILT SANDI GRAVEL SANDI GRAVEL SANDI GRAVEL JERY DENSE BLACK IN WS ZESKCATED SILT WITH THN' SRAVELTO IVE DIA BEDROCK	GRAVEL + ORGANICS			2440			
JERY DENSE BLACK IN WE PRABLE DESICATED SILT NITH THN VRITE LENSES IS IS WS SRAVE LO IVEDIA BEDROCK. IS WE END OF HOLE.	DAND & GRAVEL						
BEDROCK.	IERY DENSE BLACK FRIABLE DESICCATED SILT WITH THIN	14 4	15	2430			
END OF HOLE.	GRAVEL TO 1/2"DIA	15 W	N.				
IFOR Percent datal strain at tailout		16 W	5	2420			
Is Os Percent and strain at terms							
					Percent grad strain at tailor		

PROJECT No. 123218

s	AMPLER HAMMER W	EIGH	T 14	10 1	.B. DI		DROP INCHES
	SOIL PROFILE	15		MPL	ES F	DYNAMIC PENETRATION RESISTANCE COEFFICIENT OF PERMEABILITY BLOWS/FT CM./SEC.	k, al
EVN PTH	DESCRIPTION	STRAT PLOT	NUMBER	TYPE	BLOWS / F	SHEAR STRENGTH CUILBISG FT WATER CONTENT, PERCENT	SUPERAL STANDPIF
650 0'	GR. SURFACE.						
	SOFTBROWN		-1	2'	10 24		a WL 55 NOU 23
	SANDY SILT WITH MED. 4 COARSE SAND 4		-	00	8		1 1 1 1 23
	SRAVEL TO 1 <sup>1</sup> 5"DA, OFTEN TILL LIKE			2' 20			
14 11	WOOD SOFT TO FIRM				201		
0	STRATIFIED STRATIFIED STRATIFIED SROWN & GREY SILT WITH OCC. SRAVEL TO I'S" DA.		6	2"			1
0	MAND & GRAUEL.		7 u	15	243		
	BEDROCK.	+	3 W		242		
		H	e v				
	ND OF HOLE.		-		2410		
Construction of the second second							
and the second s	1						
					and the second se		
						S Percent axial strain at failure	

	SOIL PROFILE		SA	MPL	ES	SCALE	AMIC PENETRATION RESISTANCE COEFFICIENT OF F BLOWS/FT CM,/		N G	
VN TH	GESCRIPTION	STRAT PLOT	NUMBER	TYPE	BLOWS/FT	ELEVATION S	AR STRENGTH Cu, LS /SC.FT WATER CONTE WP W	NT, PERCENT WL	ADDITIONA LAB. TESTI	STANDPIPE INSTALLATIC
	<u>BR SURFACE</u> IARIABLE TENSITY BROWN I GREY SILT SAND & GRAVEL NOODEN CULVER IARIABLE DENSITY BROWN & GREY SILT WITH MED COARSE SAND FINE GRAVEL COARSE SAND FINE GRAVEL (TILL) BEDROCK. ND OF HOLE.		000 00 00 00 00 00 00 00 00 00 00 00 00	20 20 10 15	15 15	2450 2440 2430				
	4		and an a second	an state and a state of the state					an (yan mayani saya i ) an a in a na ang ang ang ang ang ang ang ang a	

RECORD OF BOREHOLE 3

1.B.1.

See Figure /

PROJECT No. V73218

CRISINAL REPORT ON MELTON CRISIN STREETS 13

11052-05



# Golder Associates CONSULTING GEOTECHNICAL ENGINEERS

REPORT TO

COMINCO LTD.

ON

**PROPOSED DAM EXTENSION 1976** 

H.B. MINE and the second second

SALMO

Distribution:

5 copies - Cominco, Trail, B.C.

2 copies - Golder Brawner Associates, Vancouver

B.C.

December, 1976

K76681

GOLDER, BRAWNER & ASSOCIATES LTD, 2224 WEST 8th AVE., VANCOUVER, B.C., V5Y 1N5 CANADA • PHONE: (604) 879-9266 • TELEX: 04-508800

SOIL MECHANICS - FOUNDATIONS - GEOTECHNICAL SURVEYS - EARTH DAMS - LANDSLIDES - ROCK SLOPE STABILITY EGM-2013-00163 PAVEMENT EVALUATION . SOIL STABILIZATION . AIR PHOTO INTERPRETATION

VANCOUVER - CALGARY - KAMLOOPS - TORGRESS HONTO - SEATTLE - GRAND JUNCTION, COLORADO - ATLANTA - LONDON, ENGLAND - BOSTON - MELBOURNE - SYDNEY



Golder Associates CONSULTING GEOTECHNICAL ENGINEERS

December 20, 1976

Cominco Ltd. Engineering Department Trail, British Columbia

ATTENTION: Mr. G. Shoblom, P.Eng.

Dear Sirs:

Re: Proposed Dam Extension 1976, H.B. Mines, Salmo, B.C.

As requested, Golder, Brawner & Associates have carried out a geotechnical study for the proposed extension to the existing H.B. Mines tailings dam. The work involved a review of the soil conditions at the existing dam and a site investigation to determine the availability of borrow material for the proposed work.

The soil and site conditions were determined during previous soil investigations at the dam site and are outlined in our report on the Site Investigation at Existing H.B. Mines Tailings Pond, Salmo, B.C., dated January 1974 (refer V73218). This report also included a stability assessment of the dam and recommendations for proposed construction measures for the dam in 1974. The recommendations for the proposed work were carried out in 1974 and 1975 when the old dam section was raised by 10 ft. The construction work was carried out under the supervision of Golder, Brawner and Associates personnel.

The field work for the proposed new extension involved an investigation of potential sources of borrow fill for the dam construction. GOLDER, BRAWNER & ASSOCIATES LTD., 224 WEST 8th AVE., VANCOUVER, B.C., V5Y IN5 CANADA • PHONE: (604) 879-9266 • TELEX: 04-508800

> SOIL MECHANICS - FOUNDATIONS - GEOTECHNICAL SURVEYS - EARTH DAMS - LANDSLIDES - ROCK SLOPE STABIL TABLE 449 PAVEMENT EVALUATION - SOIL STABILIZATION - AIR PHOTO INTERPRETATION

VANCOUVER - CALGARY - KAMLOOPS - TORONTO - SEATTLE - GRAND JUNCTION, COLORADO - ATLANTA - LONDON, ENGLAND - BOSTON - MELBOURNE - SYDNEY

The area considered as a potential borrow source is located to the south of the present general or bulk fill borrow pit. A total of 5 test pits were excavated in the area on October 28, 1976 using a bulldozer. The test pits were located in the field and inspected by a member of our engineering staff. The soil strata encountered were visually identified and classified in the field. Several representative samples of the soil encountered were obtained and sent to our laboratory for detailed inspection and classification. Detailed descriptions of the soil strata encountered in the test pits are presented on the attached Record of Test Pit Logs. The results of gradation tests carried out on selected samples are presented on Fig. 4. <u>SOIL CONDITIONS</u>

#### Foundation Soils

The tailings dam is located at the southern end of a north-south trending valley and has been constructed to a height of 60 to 70 ft. using borrow fill. The fill for the construction was obtained from borrow pits located on the abutments at the dam site.

The original dam which existed at the site prior to the 1974 construction was constructed generally of a sandy silt with varying amounts of sand and fine gravel. A chimney drain of sand and gravel and an additional 10 ft. cap of silt and fine sand were constructed in 1974. The results of the previous soil investigation indicate that the dam is underlain by a 5 ft. thick stratum of hard desiccated silt. Bedrock was encountered beneath the silt layer.

Standpipes installed during the 1974 investigation were not operational at the time of the test pit excavation program in October 1976. Inspection of the dam, however, indicated no major seepage was occurring

### Golder Associates

Page 450 EGM-2013-00163 at the toe of the dam. Some minor seepage was observed on the west abutment near the toe of the existing gulley area below the dam. Based on data from the original construction of the dam, it is considered that this seepage is associated with several buried wooden pipes and culverts in the dam fill.

3.

#### Borrow Area

The borrow area which was utilized in 1974 and 1975 to supply the required bulk fill quantities is located on the east abutment.

Test pits excavated during this investigation program south of the old borrow area indicate that the fine sand and sandy silt material obtained previously from this area extends some 300 to 400 ft. to the south. This material is suitable for future bulk fill requirements. To extend the existing borrow area would require stripping and stockpiling of the topsoil and organic forest litter which covers the area.

The sand and gravel filter material was obtained from a pit located approximately <sup>1</sup>/<sub>2</sub> mile north of the damsite. Examination of the area indicates that additional suitable material would be available from this location for the future extensions proposed.

#### PROPOSED FUTURE EXTENSIONS

It is understood that consideration is being given to increasing the present height of the existing dam to develop additional storage. The dam would be increased either 5 ft. or 15 ft. in height, using similar construction techniques to those used previously. It is proposed that the fill for the increase would be obtained by extending the previous borrow pit

on the east abutment. Select sand and gravel fills would probably be obtained from the borrow pit of the Department of Highways on the road leading up Sheep Creek. J. Carly in Crue Film Film

Based on the results of the test pit program, preliminary estimates indicate that the above sources should be adequate to provide the required bulk fill quantities for the 5 ft. extension. It may, however, be necessary, if a 15 ft. height increase is carried out to develop additional local alternative sources of borrow material. This additional fill material may be available in the area along the east side of the present access road within 1,500 ft. of the dam. Alternatively, a design utilizing cycloned tailings sand for fill could possibly be developed.

### DAM STABILITY AND PROPOSED EXTENSIONS

The design parameters used for the previous studies and given in our previous reports are still considered to be appropriate. As proposed, the increase in pond elevation will result in an increase in the phreatic surface within the dam. To accommodate the resultant higher phreatic surface, a sand and gravel filter drain is recommended. The drain material should be placed in the gulley area at the centre of the downstream side of the dam and over both abutments and should be extended to cover any seepage points which presently exist. The bulk fill required for the construction may consist of the local borrow glacial materials.

Details of the construction for the 5 ft. and 15 ft. elevation increase are shown on Figure 3.

Page 452 EGM-2013-00163

The results of stability calculations carried out for the proposed extensions gave minimum safety factors for downstream slope stability during maximum seepage conditions of 1.3. These analyses were carried out considering the maximum pond level as shown on Figure 3, and a 15 foot depth of water at the face of the dam.

In De Lange

#### DECANT SYSTEM

The present decant system consists of discharing excess water, which is free of suspended solids, through a vertical timber shaft. The water is carried through the dam by corrugated metal pipes which are located in the dam fill. This type of decant is not, in our opinion, adequate for any future increase and it is recommended that this system be discontinued and that a new method of decanting be provided. The new system could consist of a reinforced concrete culvert placed on the east abutment and provided with water control inlets. The system would be constructed on the ground surface and the increase in contour elevation would be utilized to control water levels. (See figure 3). Alternatively, a spillway type system would be developed at the same location. The flow of water from this new decant system should be channelled into a gravel lined ditch along the east abutment and hence into the existing creek channel down the valley in a controlled manner. Having constructed the new system, the present decant tower and pipes should be completely sealed. The outlet of the existing decant culvert pipe should be exposed, cleared, and then provided with a 5 foot grannular surround consisting of sand and gravel  $\mathcal{I}_{\mathcal{A}}^{\mathcal{L}}$ filter material.

#### CONSTRUCTION

The construction of the extensions will require site preparation at the base of the downstream toe of the existing dam. It is recommended that

> Page 453 EGM-2013-00163

any organic matter or topsoil be removed from within the limits of the proposed construction area. Care should be exercised in clearing the areas of seepage to prevent disturbance of the native materials.

The sand and gravel drain material and the bulk fill or sandy silt should be placed in maximum horizontal lifts of 12 in. and compacted to a minimum of 95 percent of maximum Standard Proctor dry density. The bulk fill material in the borrow area will probably require ripping to enable the material to be excavated. More specific construction details will be provided after the details and specifics of the extension are finalized. All new fills should be blended or keyed into the existing dam and the native abutment materials.

It is recommended that during the construction, several piezometers be installed in the dam so that future monitoring of the phreatic surface which develops can be carried out over the life of the ponds.

#### FILL MATERIALS

At this time, it is not known which alternative will be constructed. It is probable that if the higher dyke is selected, the borrow pit on the east abutment may not contain sufficient material for the required work. It is recommended that, if this alternative is adopted, additional fieldwork should be carried out in the borrow area prior to construction to enable a more accurate estimate of fill quantities to be made. At this time, the availability of additional material adjacent to the access road to the damsite should also be investigated.

We trust that this is the information you require. We would be pleased to discuss the report with you in more detail, should you desire.

> Yours very truly, GOLDER BRAWNER & ASSOCIATES LTD.


Per: C.M. Milan


2.H. HAWSON, P.Eng


J.A. HULL, P.Eng.


HH:mg

K76681.











Drown N+ Appid Date



Project No. K-76681



							ST PIT #/	÷	
K-76681		NTION (See Figure) HOD OF EXCAVATION <i>BOC</i>						TUM -	
		SOIL PROFILE				Γ		-	
Project No.	ELEV N. DEPTH	DESCRIPTION	STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	ELEVATION SCALE	WATER CONTENT, PERC		GROUNDWATER CONDITIONS
	1.01	Ground Surface Loose brown silt and sond some organic matter Hard grey silt trace sand and gravel-west side of pit sand f gravel seam from 6 to 10 ft.							
	9.0' 0.0' E	Cobbles up to 6" dia. End of Test Pit.							
	RTICAL			30	lde	er A	ssociates	Pa EQ	38482N HH MEOREOOI537

. . . .

с. .

Stern Section

1.110

<b></b>	SOIL PROFILE		Τ		1	<b></b>			
ELEV N. DEPTH	DESCRIPTION	STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	ELEVATION SCALE	WATER CONTE	NT, PERCENT	ADDITIONAL LAB. TESTING	GROUNDW CONDITIC
1.0'	Ground Surface Loose reddish brown sandy silt and organic matter Firm to stiff grey silt, fine sand; pocket of sand on west side of pit		-						-
5	Stiff grey silt, trace to come sand, trace clay End of Test Pit		2						

. k

3

100 and 100

.

Sect. Low He

And the second second

1

	SOIL PROFILE						 		
ELEV N. DEPTH	DESCRIPTION	STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	ELEVATION SCALE	WATER WP	NT, PERCENT	ADDITIONAL LAB. TESTING	GROUNDW CONDITIC
0.0'	Ground Surface Loose brown sarid f organic matter								
1.01									
	Loose to compact brow, silty sand with grovel and cobbles rounded								
5.01	Reddish brown talus material angular								
6.01	End of Test Pit.								
			-						
		<b>V</b>							

.

As a first man

and the state of t

;

. 3

-7 -7

100 - 100 -

ź –	SOIL PROFILE			Τ				
ELEVI DEPTI	DESCRIPTION	STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	ELEVATION SCALE	WATER CONTENT, PERCENT Wp W WL	L ADDITIONAL LAB. TESTING	GROUNDW CONDITI
	-							
0.0	Ground Surface Loose brown silt with organic matter							
1.61	Firm grey silt with some sand							
3.0'	Compact brown fine sand with silt layers							
5.0'	Compact brown sand and silt some cobbles and gravel							
	End of Test Pit. Terminated on large boulder or bedrock at 9.0 ft. on east side of test pit.							

		REC	OF	2D	OF	TE	ST PIT#5		
8	1	ATION (See Figure)		DAT	re (	Octob	per 28, 1976 DATI	лм —	
K-16601	ME	THOD OF EXCAVATION BOCK	ho	е		ł	PROJECT H.B. Mines		
No. A		SOIL PROFILE			Τ				······
Project N	ELEV N DEPTH	DESCRIPTION	STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	ELEVATION SCALE	WATER CONTENT, PERCEN WP W .WL	ADDITIONAL LAB. TESTING	GROUNDWATER CONDITIONS
	1.0'	Ground Surface Loose brown sondy silf to reganic matter Stiff to compact brown silfy fine sond and some gravel							
	CTICAL		G	0	de	r As	sociates	Ragav EGM-2	166 #4 2013-00763]

;

÷



STAGE I SUBMISSION FOR REACTIVATION OF THE HB MILL LOCATED AT SALMO, B.C.

for

DAVID MINERALS LTD.





**ITER International Environmental Consultants Ltd.** Page 467 Vancouver/Calgary/Toront6/Mi011treal<sup>63</sup>

STAGE I SUBMISSION TO METAL MINES STEERING COMMITTEE FOR REACTIVATION OF THE HB MILL, LOCATED AT SALMO, B.C.

14745-20

Prepared for

DAVID MINERALS LTD.

By:

IEC INTERNATIONAL ENVIRONMENTAL CONSULTANTS LTD. 202-5600 Cedarbridge Way Richmond, B.C. V6X 2A7

R.Y. Ting, Ph.D., Project Manager

T.C. Griffing, Ph.D., Project Principal

3089.5

March 1982

Page 468 EGM-2013-00



Province of Energy, Mines and Energy, Mines and British Columbia Petroleum Resources

To: Selected Participants, Metal Mines Guidelines Review Process Date: May 5, 1982 Our File: HB Gold Project

MEMORANDUM

Re: David Minerals Ltd. Stage I Submission for Reactivation of the H. B. Mill located at Salmo, B.C.

The Metal Mines Steering Committee has now received the Stage I submission for the above project.

This is a reactivation of an old mine and there will be no new impacts. The only change will be the ore and the milling process. David Minerals has discussed the project with the regional people and applications for amending existing permits have been made.

Since this is a reactivation of an old mine and no additional impacts are noted, it is recommended that the Stage I report is all that is required.

Review comments should be forwarded to this office no later than May 30th, 1982.

J. D. McDonald, Chairman Metal Mines Steering Committee c/o Inspection and Engineering Branch Mineral Resources Division.

JDM:vv

Attachment: David Minerals Stage I report.

Distribution

- T. Carter
- J. Errington
- W. Swanson
- M. Kent
- W. Hubbard
- R. Norrish
- L. Regan (4 copies)
- D. McDonald (4 copies)
- B. Lang
- J. Anderson
- A. Richardson
- T. Martin
- J. McDonald
- J. Schuyff
- C. Hawksworth

\_\_IEC\_

TIDEE OF CONTENTS	TABLE	OF	CONTENTS
-------------------	-------	----	----------

		1.0		Page
1.0	SUM	MARY		1
2.0	ACI	KNOWLE	DGEMENT	2
3.0	INT	RODUCT	ION	3
	3.1	Locati	ons	3.
	3.2	Histor	у	3
	3.3	Projec	t Description and Schedule of Development	4
4.0			N OF EXISTING ENVIRONMENTAL	
	ANE	SOCIAL	CONDITIONS	6
	4.1	Physio	graphy	6
	4.2	Land T	enure and Settlement Patterns	6
	4.3	Climat 4.3.1 4.3.2 4.3.3	e and Meteorology Temperature Precipitation Wind	7 7 10 10
	4.4	Air Qua	ality	11
	4.5	Surface 4.5.1 4.5.2 4.5.3 4.5.4 4.5.5	Water Drainage Water Quality Hydrology Water Licenses Fisheries	11 11 13 13 25 25
	4.6	Ground 4.6.1 4.6.2	water Quantity Quality	28 28 29
	4.7	Soils an 4.7.1 4.7.2 4.7.3	d Surficial Geology General Geology Geology of the HB Mine Mining	29 29 31 32
	4.8	Vegetat	ion	33

i

IEC

# TABLE OF CONTENTS (continued)

					Page
	4.9	Wildlife			34
		4.9.1	Ungulates		34
		4.9.2	Carnivores		35
		4.9.3	Furbearers	- A.	35
		4.9.4	Waterfowl		35
		4.9.5	Birds		37
	4.10	Land Ca	pability and Use		37
		4.10.1	Agriculture		37
		4.10.2	Forestry		38
		4.10.3	Recreation		38
		4.10.4	Ungulates		38
		4.10.5	Waterfowl		38
		4.10.6	Trapping		39
		4.10.7	Guiding		39
	4.11	Reclama	ation Work at the HB Mine Site		39
	4.12	Historic	and Archaeological Sites		44
	4.13	Existing	Social Environment		44
		4.13.1	Setting		44
		4.13.2	Population		45
		4.13.3	Employment		45
		4.13.4	Unemployment		48
		4.13.5	Housing		49
		4.13.6	Education		49
		4.13.7	Commercial Services and		47
		4.12.7	Community Facilities		49
		4.13.8	Police and Fire Protection		52
		4.13.9	Medical Service		52
		4.13.10	Transportation		53
		4.13.11			
		4.13.12	Recreation Opportunities Water/Sanitation		53
					53
		4.13.13	Utilities		54
		4.13.14	Communication		54
		4.13.15	Municipal Finance		54
5.0	PROJE	ECT DESCI	RIPTION		55
	5.1	Characte	ristics of Ore to be Processed		55
	5.2	Milling P	rocess		56
	5.3	Transport	tation		60

ii

IEC\_

# TABLE OF CONTENTS (continued)

				Page
	5.4	Sewage a	and Garbage Disposal	60
	5.5	Utilities		60
	5.6	Employm	61	
	5.7	Housing	61	
	5.8	Develop	62	
	5.9	Reclamation		62
	5.10	Effluent	Control and Monitoring	62
6.0	ENVIRONMENTAL AND SOCIAL IMPACTS			64
	6.1	Environm	ental Impacts	64
	6.2	Socio-Economic Impacts 6.2.1 Employment 6.2.2 Population 6.2.3 Summary		65 65 67 67
7.0	REFEI	RENCES		69

# LIST OF FIGURES

		Atter Page
3.1	Location of the HB Mill - Salmo, B.C.	3
3.2	Location of the HB Mill at Salmo, B.C. and the Sheep Creek Watershed.	3
3.3	HB Mine Layout.	3
4.1	Trail - Tadanac, B.C Wind Rose 1968-1982.	10
4.2	Percentage Wind Direction (and Calms) and Mean Wind Speed by Month (1968-1982) at Trail - Tadanac, B.C.	10
4.3	Locations of the Reclaimed Areas at the HB Mine.	40
		111

LIST OF FIGURES (continu	ed)

\_IEC\_

-

		After Page
5.1	HB Mill Project, Mill Flowsheet for Processing the Gold Ore from the Sheep Creek Mine, Goldbelt Mines Inc.	57
5.2	Locations of the Flowmeter on the Tailings Line, Effluent Monitoring Station and Garbage Dump Area at the HB Mine.	63
	LIST OF TABLES	
		Page
4.1	Summary of Climatic Normals between 1972 and 1980 for Salmo, B.C.	8
4.2	Summary of Climatic Normals between 1974 and 1980 for Station 808, Kootenay Pass, B.C.	9
4.3	H.B. Mine Drainage Flowrates Measured in 1979.	12
4.4	Water Quality of the Salmo River, Upstream and Downstream from the Sheep Creek Confluence.	14
4.5	Water Quality of Sheep Creek Upstream from HB Mine.	15-17
4.6	Water Quality of Sheep Creek Downstream from HB Mine.	18-20
4.7	Water Quality of the Salmo River, Downstream from Sheep Creek Confluence.	21-23
4.8	Monthly Mean Discharges in Cubic Feet Per Second for Sheep Creek and Salmo River Tributaries.	24
4.9	Monthly and Annual Mean Discharges from 1979–1976 for Salmo River Near Salmo.	26
4.10	Salmo River Near Salmo - Station No. 08NE074 Monthly and Annual Mean Discharge in Cubic Feet Per Second for 1977-1980.	27

iv

# LIST OF TABLES (continued)

		Page
4.11	Qualities of the HB Mine Drainage Water HB Mine Pollution Control P.E 1853 Monitoring Data - First and Second Quarter, 1979.	30
4.12	Species of Furbears Occurring in the Salmo District.	36
4.13	The Nature and Extent of Land Disturbances and Reclamation at HB Operations.	40
4.14	Population by Age Group and Sex (1976).	46
4.15	Experienced Labor Force by Industry (1976).	47
5.1	Head Assay of the Ore Sample from the Sheep Creek Mine, Goldbelt Mines Ltd.	55
5.2	Results of Gold Assays of Ore Delivered to the HB Mill from the Sheep Creek Mine.	56
6.1	Operating Workforce Requirements for the H.B. Mill.	66
	LIST OF APPENDICES	

A-1	Appendix A - Common and Scientific names of
	the vegetations found in the HB Mine site.

- B-1 Appendix B Mill Flowsheet and Process Description for Concentrating of Lead and Zinc from the Ore of the HB Mine - by Cominco Ltd.
- C-1 Appendix C Tailings Disposal Scheme for the HB Mill - Prepared by Klohn Leonoff Consulting Engineers.

IEC

V

## 1.0 SUMMARY

David Minerals Ltd. wishes to reactivate the HB Mill located within the property of the HB Mine to produce gold and iron concentrates. The property was purchased from Cominco Ltd. in September 1981. The lead and zinc mine and mill operations were closed in August 1978 due to depressed metal prices. The mine-mill complex is located in the Sheep Creek Valley, 10 km southeast of the village of Salmo, in the Salmo district in the southwestern portion of the Province of British Columbia.

The reactivated mill will treat high sulphide ore mined in the Salmo district by crushing, grinding, flotation and thickening. Treatment will be on a 10,000 ton batch basis at a rate of up to 1,200 tons per day. The resultant concentrate, containing gold and iron, will be transported to Helena, Montana for refining.

The tailings will be transported to the tailings pond used during Cominco's operation. An eight-inch plastic tailing line was installed in 1981 by David Minerals to replace the original wooden flume. Flow rate and sediment concentration of the tailings will be monitored. Automatic alarm systems and daily maintenance will ensure the integrity of the tailings transport system. The quality of the tailings pond overflow will also be monitored.

There will be no significant environmental impacts on the ecology of the site or Salmo district due to the reactivation and operation of the HB Mill. The operation will not only enhance the economy of Salmo village but also that of the Nelson region. This is particularly timely as the largest employer of the region, Cominco Ltd., is planning to temporarily close down, due to depressed metal market.

3089.5

## 2.0 ACKNOWLEDGEMENT

IEC International Environmental Consultants Ltd. wish to acknowledge the assistance rendered by Dr. M. Clark and Mr. R. Mickel of the Waste Management Branch, Provincial Ministry of Environment Victoria and Nelson respectively, in retrieving the water quality data of the Salmo district, and Mr. P.G. Stent, Conservation officer, Fish and Wildlife Branch in Trail, for supplying biological data.

Special thanks is due to the staff of Cominco Ltd. at Trail for their full cooperation in making the water quality and reclamation information available.

Messrs. C. Moore, R. Neri, P. Santos and other staff of David Minerals Ltd. at the HB Mill were particularly helpful in supplying the background information for this report.

3089.5

## 3.0 INTRODUCTION

## 3.1 Location

The HB Mill is situated within the property of the HB Mine (Latitude 49° 08' 40" N, Longitude 117.12' 2" W). The HB Mine is located in the district of Salmo in the southeastern part of the province of British Columbia. The town closest to the mine is the village of Salmo. Salmo is 30 km directly south of the city of Nelson and 22 km north northeast of the city of Trail (Figures 3.1, 3.2).

The property is located 7 km to the southeast of Salmo and 4 km east of the bridge of old Highway 3-6 which crosses Sheep Creek.


The HB Mine encompasses approximately 971 ha (2400 ac) in area on the north and south slopes of the Sheep Creek valley. The mine-mill complex is situated at an elevation of approximately 762 m. The layout of the mine and its property line are shown in Figure 3.3.


## 3.2 History

In September 1981, David Minerals Ltd. purchased certain Crown Granted and recorded mineral claims from Cominco Ltd. Included were surface rights, buildings, machinery and equipment associated with the HB Mine.

The property was originally staked by Messrs. Horton and Benson (hence HB) in 1907 when they discovered deeply oxidized outcrops of lead-zinc ore. There were a long and intermittent series of commercial mining operations designed mainly to develop and extract oxidized lead-zinc ore. In 1925 a determined attempt was made by a British syndicate to develop a large tonnage of sulphide ore, but this ended in failure after some 3000 ft of lateral development was done. The property was subsequently purchased by the Consolidated Mining and Smelting Co. Ltd. (later known as Cominco Ltd.) in 1927. The mine lay idle until 1946, when a geological study, followed by a program of surface drilling, encountered extensive sulphide mineralization. An extensive diamond drilling program was undertaken, followed by underground

3089.5





IEC

exploration, which revealed more details of the deposit. With sufficient ore outlined, Cominco Ltd. started the construction of a 1000 ton per day concentrator in April 1952. It was completed in the spring of 1953. Due to unfavorable metal prices, production of lead and zinc concentrates did not commence until May 1955. The production was suspended in October 1966 for the same reason. The HB Mine resumed production in February 1973. It was closed permanently in August 1978. During the life of the mine, some 7,305,599 tons of ore, grading 0.93% lead and 4.45% zinc were produced.

3.3 Project Description and Schedule of Development

David Minerals Ltd. proposes to reactivate the concentrator mill located on the HB Mine property, to custom mill gold-bearing ores produced in the Salmo district. No on-site mining is planned.

Phase I of the project consists of a general clean-up of the overall milling facilities at the HB Mine property. Renovation of one circuit to treat high sulphide ore by crushing, grinding, flotation and thickening will produce a concentrate containing gold and iron. Treatment will be on a 10,000 ton batch basis at a rate up to 1,200 tons per day. Due to the high iron content of the concentrate, arrangements for further processing will be made with Asarco in Helena, Montana. Lead and zinc ores which are known to exist in the district may be concentrated, as was done before the mine closure, if it is proven economical.

Phase II of the HB Mill project consists of constructing facilities for a second circuit, to treat 120 tons per day of concentrates or ores, which contain gold. Extraction of gold is accomplished by cyanidation. Metallurgical testing has been started but sufficient metallurgical data is not yet available to determine a flowsheet for the process.

Phase III of the project consists of the construction and activation of a third circuit of the HB Mill. David Minerals anticipates acquiring and mining certain mineral-bearing lands in the Rossland area. The ores in this area contain molybdenum, cobalt and gold. Flotation treatment would separate the minerals from the ore. The concentrate

3089.5

would then be treated in the cyanide circuit constructed in Phase II to recover the gold. The concentrate would then return to the flotation circuit, where the cobalt would be separated from the molybdenite. A considerable amount of exploration by diamond drilling of the ore bodies in Rossland in addition to metallurgical testing, must be completed to determine the feasibility of Phase III.

David Minerals Ltd. wishes to proceed with Phase I of the project immediately. It has already been granted necessary amendments to the previously existing permits, which include:

- Permit PR 2665 covering Solid Refuse Disposal issued 5 December 1973.
  - Permit PA 1854 covering Air Emissions issued 26 February 1973.
  - Permit PE 1853 covering Effluent Disposal issued 7 February 1973
  - Amendment of Licence No. 17622 Department of Land and Forests, Water Rights Branch - issued 1 March 1961.

These amendments delineated transfer of responsibility to accompany transfer of the property ownership to David Minerals Ltd.

Page 481 EGM-2013-00163

### 4.0 DESCRIPTION OF EXISTING ENVIRONMENTAL AND SOCIAL CONDITIONS

### 4.1 Physiography

IEC

According to Holland (1976) the Salmo area lies within the Interior System of the Canadian Cordillera. It is located on the southwestern slope of the Selkirk Mountains, a subdivision of the Columbia Mountains. The mountains of the southern Selkirks are more subdued and rounded than those of the north and are characterized by fewer rugged peaks and serrated ridges. The southern peaks lack these youthful glacial forms due to higher uplifts and more recent sculpture by mountain glaciers.

The Selkirk Mountains encompass an area about 220 mi long and 40 to 50 mi wide. They lie within the big bend of the Columbia River and are flanked on the west by the Monashee Mountains and on the east by the Purcell Mountains.

The Selkirk Mountains are underlain by a variety of Proterozoic and Lower Palaeozoic sedimentary and metamorphic formations, by gneisses of both sedimentary and igneous origin, by late Palaeozoic and Mesozoic sedimentary and volcanic rocks and by granitic stocks and batholiths of Cretaceous and early Tertiary age. The Proterozoic and Lower Palaeozoic rocks include prominent quartzite and limestone members which are resistant to erosion.

The Salmo area is drained by the Salmo River, which separates the Nelson Ranges, (west of south Kootenay Lake), from the Bonnington Ranges (to the east of the Columbia River). The Salmo River flows southward and joins the Pend'Oreille River, which is a tributary of the Columbia River.

#### 4.2 Land Tenure and Settlement Patterns

Settlement of the Salmo district developed as a result of the discovery and development of natural resources. Initial settlement occurred in late 1880's and early 1900's due to the mineral discoveries. Logging was developed in the surrounding areas, growing in importance when mining activities declined in the 1930's. Salmo was incorporated as a village in 1946.

3089.5

David Minerals Ltd. purchased 971 ha of land and mineral claims in the Sheep Creek Valley. The lands surrounding the property are still owned by Cominco Ltd.

### 4.3 Climate and Meteorology

IEC.

Table 4.1 summarizes data collected at the B.C. Forest Service Weather Station, located approximately 14 km northwest (Latitude  $49^{\circ}$  11' N, Longitude  $117^{\circ}$  18' W – Elevation 685 m) of the project site. Only temperature and precipitation data from 1972 to 1980 are available for this station. Table 4.2 summarizes temperature and precipitation data collected at the Kootenay Pass Weather Station (Station #808, Latitude  $49^{\circ}$  04' N, Longitude  $117^{\circ}$  02' W - Elevation 1774 m), located 14 km southeast of the site. Wind direction and velocity measurements were not available at either station.

The nearest source of wind data is the Trail-Tadanac Station (Latitude  $49^{\circ}$  06' N, Longitude  $117^{\circ}$  46' W - Elevation 579 m), 32 km west of the mill site. Figures 4.1 and 4.2 summarize wind direction and speed for the period of 1968 to 1982.

### 4.3.1 Temperature

Salmo mean daily temperatures range between -7.8°C in January and 18.0°C in July with the annual mean daily temperature of 6.3°C. Mean daily maximum temperatures varied between -2.6°C in January and 27.1°C in July, and mean daily minimum temperatures varied between -12.3°C in January and 8.8°C in July. The extreme temperatures on the record varied from 40.6°C in August to -27°C in January.

Kootenay Pass mean daily temperature varied in a range of  $-10.3^{\circ}$ C in January and  $12.2^{\circ}$ C in July with an annual mean daily temperature of  $0.7^{\circ}$ C. The extreme temperatures on record varied from  $28.3^{\circ}$ C in July to  $-33^{\circ}$ C in December.

It appears that, in the Salmo district, December and January are the coldest months with July and August being the warmest months.

#### SUMMARY OF CLIMATIC NORMALS RETWEEN 1972 AND 1980 FOR SALMO, R.C. (FORESTRY SERVICE WEATHER STATION: LATITUDE 40<sup>O</sup> 11N, LONGITUDE 117918M, ELEVATION - && m. ISOURCE: ATMOSPHERIC ENVIRONMENT SERVICE OF CANADA) LOCATED 14 KM SW OF HB MILL SITE

Temperature (PC)	JAN	FER	MAR	APR	MAY	<u>AN</u>	<u></u>	AUG	SEP	OCT	NOV	DEC	ANTAJAL	
mean daily	-7.IE	-1.8E	+1.3E	6.IE	10.1E	14.8E	18.0E	17.6E	12.8E	6.4E	-1.26	+1.5E	6.3	
mean daily miss	-2.6E	2.5	6.8E	13.9E	17.7E	73.3E	27.1E	26.6E	21.7E	(3.3E	2.9E	0.0E	12.7	
mean daily min	-12.3E	-6.1E	-4.4	-0.4E	2.4E	6.0E	8.8E	8.5E	3.9E	-0, IE	-4.7E	-J.Æ	+0.2	
extreme max	6.7	11.7	17.0	27.0	32.2	37.2	37.8	40.6	33.9	25.0	16.7	8.9	40.6	
extreme min	-27.0	-23,4	-21.7	-12.8	-5.0	+0.6	0.0	-Li	-5.6	-10.£	-14.5	-76.7	-27.0	
Precipitation (mm)														
mean rainfall	10	22.9	37.6	49.9	79.8	58.2	59.1	-65.8	45.9	5R.1	58.8	33.7E	\$80.3	
mean inowfall	69,7	50,4	16.2	3.5	0.0	0.0	0.0	0.0	0.0	1.2	31.6E	61.7E	233.3	
mean total	79.2E	73.4E	53.8	53.4E	79.8	57.2	59.)	65.8	46.7	59.3	90.6E	94.4E	813.7	
greatest rainfalt in 24 hrs	19.5	19.4	15.0	33.0	27.4	21.9	25.9	48.6	26.7	37,3	26.0	71.8	48.4	
greatest snowfall in 24 hrs	20.1	24.9+	17.7	15,0	0.0*	0.04	0.0*	0.0*	0.0+	2.5	17.8	36.8	36.R	
greatest precip. In 24 hrs	20,1	24.9*	15.0	11.0	27.4	21.9	25.3	48.4	26.7	37.3	76.0	36.R	AR.N	
no, days with measurable rain	2	3	a	10	16	11	10	17	9	10		4	105	
no. days with measurable snow	13	10	5	1	0	0	0	0	0		-6	10	46	
no. days with m. precip.	15	11	17		36	11	10	15		0	35	15	451	

8

E: Estimate M: Missing T: Troce 1: New Record

IEC\_

3089.5

SUMMARY OF CLIMATIC NORMALS BETWEEN 1974 AND 1980 FOR STATION 808, KOOTENAY PASS, B.C. LATITUDE 49'OHN, LONGITUDE 117'07=W, ELEVATION - 1774 M ISOURCE: ATMOSPHERIC ENVIRONMENT SERVICE OF CANADA, TEMPERATURE AND PRECIPITATION, 1974 - 1980, BRITISH COLUMBIA) LOCATED 10 KM SE OF HB MILL SITE

Temperature (°C)	JAN	FER	MAR	APR	MAY	JUN	*	AUG	SEP	001	NOV	DEC	ANNUAL	
mean dally	-10.3E	-4.5	-5.7	0.0	3.5E	7,7	12,2	10,8	7.6	1.5	-6.1	-7.5	0,7	
mean daily max	+7.4E	-3.9	-1.7	4.1	7,7E	12.4	17.6	15.4	12,0	5.3	-3.3	-5.0	4,5	
mean daily min	-13.0	-9.6	-8,6	-4,3	-0.6E	3,0	6.9	6.1	3,7	-1.6	-8.9	+10,0	-3,1	
extreme max	2.8	6.7	11.0	19.0	17.2	23.5	28.3	16.5	24.5	18.3	8.9	5.0	28,3	
estreme min	-29.5	-23.3	-25,0	-17,6	-7.0	-3.9	-1.0	-0.6	-5.0	-12.8	-76.8	-33,0	-33,0	
Precipitation (mm)														
mean rainfall	3.8	7.8	10,0	17.4	87,2E	95.5E	83.0	97.0	89.5E	40.3	4,5	15.6	\$48.6	
meon snowfall	1459.0	2030.0	1904.0	846.0	390.0€	109,0E	D	0	76.0E	639.0	1314.0	2030.0	10808.0	
mean total	149.7	210,8	200.4	102.0	126.2E	105.4E	83.9	97,4	91.9E	104.7	132,9	223,6	1629.4	
greatest rainfall in 24 hrs.	2.7	5.7	4.2	3,0	20,4E	31.6	17.0	29,9	24.0E	18.4	0.8	8,9	31.8	
greatest prowfall in 24 hrs	23,9	33.5	32.5	18.2	12.8€	4.5	0.9	0.3	7.0	22.7	22,8	14.7	34.7	
greatest precip, in 24 hrs	23.9	35.7	37.7	19.2	28.3E	31.0	17.0	29.9	24.0€	34,8	22.8	34.7	34,7	
na, days with measurable rain			2	3			12	14	12	5		÷.	72	
no, doys with measurable snow	19	20	20	12	5	2			1.0	8	15	21	122	
no. days with m. precipitation	20	21	27	15	14	13	12	10	12	13	16	55	194	
- New Record														

E - Estimate M - Missing T - Troce

IEC\_

3089.5

Page 485 EGM-2013-00163

#### 4.3.2 Precipitation

In Salmo district, precipitation is recorded on 9 to 16 days a month with an average of 13 days per month. The mean total precipitation varies from 46.9 mm in September to 94.4 mm in December. The precipitation averaged 813.7 mm on an annual basis and 67.5 mm on a monthly basis. Snowfall occurs between October and April and is more common from December to February. Snowfall has yet to be recorded between May and September.

Rainfall varies from a minimum average of 10 mm in January to a maximum average of 79.8 mm in May. The annual rainfall averages 580.3 mm and 45<sup>o</sup> mm on a monthly basis. Maximum daily rainfall generally occurs in August.

At the Kootenay Pass station, precipitation is recorded on 12 to 22 days per month and averaged 16 days per month. The mean precipitation varies from 83.9 mm in July to 210.8 mm in February with an average of 135.5 mm per month.

The rainfall varies from 1.5 mm in November to 97.0 mm in August with an average of 44° mm per month. The mean snowfall ranged up to 2080.0 mm in December with an average of 901.0 mm per month. The greatest rainfall (in 24 hours) of 31.8 mm was recorded in June and greatest snowfall (in 24 hours) of 34.7 mm was recorded in December.


The total annual rainfall records for the Salmo and Kootenay Pass stations are similar but snowfall was considerably higher at Kootenay Pass because of higher elevation.

### 4.3.3 Wind


The Wind Roses in Figure 4.1 indicates that winds in the Trail-Tadanac area are primarily from the northeast and southwest and, to a lesser extent, from the north and south directions.

Figure 4.2 shows that the yearly mean wind speed was 7.9 km/hr. The mean speed stayed relatively constant throughout the year. The highest mean wind speed for the 14-year period was 41 km/hr in December.

3089.5



Page 487 EGM-2013-00163



Page 488 EGM-2013-00163 IEC.

### 4.4 Air Quality

No air quality data have been collected by the Atmospheric Environment Service of Canada or by the B.C. Provincial Government in the vicinity of Salmo.

Because Salmo is a small village, located away from large population and industrial centers, air quality is excellent.

Any airborne particles picked up from the mill site will not disperse over great distances because the mill is located on the north side of a steep hill in the Sheep Creek Valley and it is relatively sheltered from the prevailing winds.

### 4.5 Surface Water

### 4.5.1 Drainage

The HB Mine property is situated within the drainage system of Sheep Creek. Figure 3.2 shows the major streams in the Sheep Creek drainage system. Those draining southward are: Woodchuck, Aspen, Hedgehog, Nugget, Clyde and Twilight Creeks. Those draining northward are Annie Rooney, Bennett, Billings, Waldie, Muskrat, Curtis, Panther and Gamble Creeks.

Aspen Creek drains southward into Sheep Creek near the eastern border of the Mine site. The creek is dammed near the mill and a portion of the overflow will be diverted to be used for the mill and the camp operation.

The surface runoff and mine drainage water are collected through ditches along the side of the mine road and then discharged into Sheep Creek. The mine drainage flow rates measured by Cominco Ltd. in 1979, are given in Table 4.3.

3089.5

HB Mine Drainage Flowrates Measured in 1979 by Cominco Ltd. (in cumecs)

Month	Average	Mininum	Maximum	
Jan	Frozen			
Feb	11.0 (388)*	8.3 (294)	12.5 (440)	
Mar	29,5 (1042)	12.5 (440)	36.0 (1272)	
Apr	3.3 (115)	2.0 (70)	4.4 (156)	
Мау	4.4 (156)	4.4 (156)	4.4 (156)	
Jun	3.5 (125)	2.7 (94)	4.4 (156)	

\* ( ) in gallons per minute.

3089.5

12

IEC

## 4.5.2 Water Quality

Water quality above and below the Salmo River/Sheep Creek confluence was determined by Cominco Ltd. in the first and second quarters of 1979, in compliance with the HB Mine Pollution Control Permit (PE 1853). The results are given in Table 4.4.

In addition, computerized summaries of the water quality data were obtained from the Waste Management Branch, B.C. Ministry of Environment, for the rivers and streams in the Salmo district. They are given in Tables 4.5 - 4.7. Analysis of the water quality samples taken at Sheep Creek upstream and downstream from the mine and at Salmo River below Sheep Creek confluence showed that the water quality was generally good. There were no significant differences in the water quality of the stations above and below the mine when the mine was operating.

### 4.5.3 Hydrology

Sheep Creek drains westward from Three Sisters Peak and the mountains of the Nelson Range, from elevations of 2000 to 2134 m (6500 to 7000 ft). It drains into the Salmo River which flows southwards and joins the Pend'Oreille River near the Canadian - U.S. border.

No hydrological information has been collected from Sheep Creek and its tributaries in recent years. The records available from the Historical Streamflow Summary, British Columbia (Fisheries and Environment Canada, 1977) indicate that some streamflow measurements were taken from the tributaries of Sheep Creek and the Salmo River in the summer months through the period of 1930-1940. These streamflow measurements are summarized in Table 4.8.

The closest hydrological station located in the Salmo district is Station No. 08NE074 (Latitude  $49^{\circ}$  04' 07" N, Longitude  $117^{\circ}$  16' 37" W) of Water Survey of Canada on the Salmo River. It is located 8 km south of the confluence of Sheep Creek and the Salmo River and 14 km south of the village of Salmo. The monthly and annual mean discharge in cubic feet per second (cfs) and annual total discharge in acre feet (ac-ft)

3089.5

Water Quality of the Salmo River, Upstream and Downstream from the Sheep Creek Confluence: Determined by Cominco Ltd. in 1979\*

		Salma Rive	er Upstreon	n	5	almo River	Downstree	ITTE
Date - 1979	Feb 22	Apr 10	<u>Moy 8</u>	Jun 5	Feb 22	Apr 10	May 8	Jun 5
рH	7.7	8.0	7.7	7.4	7.4	8.2	7.5	7.5
Total Solids	74	64	63	50	60	64	49	57
Suspended Solids	1	1	13	6	1	E.	9	a
Dissolved SO4	8.9	8.2	3,9	3.1	11	7.9	5.3	4.7
Total CN	L0.01	L0.01	L0.01	L0.01	L0.01	L0.01	L0.01	L0.01
Dissolved Fe	L.0.05	L0.05	L0.05	L0.05	L0.05	L0.05	L0.05	L.0.05
Dissolved Ph	L0.01	L0.01	1.0.01	L0.01	L0.01	1.0.01	1.0.01	L0.01
Dissolved 7n	0.07	0.01	1.0.01	0.01	0.02	0.01	L0.01	0,01
Dissolved Cu	L0.005	1,0,005	L0.005	L0.005	L0.005	L0.005	LO.MS.	L0.005

14

\* All measurements except pH are reported in milligrams per litre (mg/L) = PPM.

3089.5

IEC\_

Water Quality of Sheep Creek Upstream from HB Mine (Source: Waste Water Management Branch, Ministry of Environment)

PARAMETER	CODE	UNITS	DATE PANGE	NO. OF	HAXIMUM	MINIMUM	MEAN	DEVIATION	TEST
COL09 19	002	AFL UNIT	7001-7412 7501-7512	6 5	18:	2 5:	5.8323	2.0412	0.9
PH	0.74	DEL WITT	7001-7412	ê5.	7.9	7.2	7.4667 7.875	0.3011	3.1
965 1050	005	MGZL	7301-7412	18	78:	34.	58. 55.	15.646	0.4
RESF 105	007	MGZL	7501-7912	7	73.	28.	52 .	18.027	
DESNEL04	07-8	4571	7101-7412 7501-7912	9	25:	£ 1:	5.6667	9.5573 0.7868	5+1
SPF COND	211	USZCH	7001-7412	19	132:	56.	92.778	28.547	0.8
TEN APPV	012	056.C	7001-7412	5	18.	5.	10.667	4.5858	
T SAMPLE	013	SEG.C	7001-7412 7501-7912	11	11:	8:	4.9636	4.3243 4.6852	0.0
NAY DISS	014	4G/L	7001-7412	6	14.6	11.1	12.25	1.3766	0.2
TURNIDTY	915	N.T.U.	7001-7412 7501-7012	14	5.5	0.25	1.6633	1.9418	15
HAR.PPES	317	KPASCALS	7001-7412	ç.	94.05 103.25	91.526	93.275 93.618	0.97345 4.5267	0.2
ATP TEUD	920	DEGIC	7601-7412 7501-7912	Ě	15:	-7:	9.1667	6.6001 14.11	0.1
COLPITAC	024	T.A.C.	7501-7912	7		L.L.	3.	2.0817	
ALKALI T	105	26M	1001-7412	15	50:	30.	40.167 36.819	9.1524	0.7
CARRN 30	171	9571	7001-7412	5	۵.	5.	3,	0.63246	-
CHLOPINE	104	NG/L	7001-7412	6	2.5	1 2.5	0.5	0.0	
CYANIOC	194	MGZI	7501-7912 7501-7912	15	L 0.01 L 0.01	L 0:01	8:81	0:0	

3089.5

IEC.

TABLE 4.5 (continued)

IEG.

DARAMETER	TEST		DATE	ND. DF			MEAN	STANDARD	TEST
FLUOP IDE	166	MGYL	7301-7412 7501-7012	6 1	2 8:1	L 2.01	0.005	.036742	c real
HAPONESS	157	MGZL	7001-7412 7501-7912	13	53.6 52.5	24.7 17.9	40.65 36.431	13.946	0.7
AMMONTA	105	MG/L	7001-7412 7501-7912	6-3-	0.02	L 0.005	.013333	0.005164	2.2
EGN/SON	109	MGZL	7561-7512	3	0.1	0.03	0.06	.036055	- 013
NITRATE	110	NGAL	7001-7412 7501-7912	1	0.09	L 0.02 L 0.02	.051667	.029269	0.7
NITRITE	111	MG/L	7501-7412	6	L 0.005	L 0.005	0.005	0.0	
NIT OPGN	112	NON	7301-7412 7501-7912	1	L 0.13	L 0.02	.056667	.038816	
NIT KJEL	113	MGZL	7501-7912	7	2-1	L 2.01	-04 P571	.034365	-
NIT TOTL	114	MSZL	7501-7912	4	0.18	0.08	0.1175	0.045	
	118	MG/L	7001-7412 7501-7912	÷	3.005	L 0.003	.0038333 0.00525	-0009832 -0020616	1.5
PHOS TRT	110	NG/L	7001-7412 7501-7912	\$	0.043	0.005	-015833 -014143	.014999	0.3
	120	MG/L	7501-7912	4	7.2	4.2	6.025	1.3326	
	121	MGZL	7001-7412 7501-7912	6 5	9.8 8.7	L 5:	6.025	2.1005	0.8
DISSOLVEN	2510	MGZL	7501-7912	1	L 0.005	L 0.005	0.005		
APSENIC :	2517	NG/L	7501-7912	2	L 0.005	L 0.005	0.005	0.0	
CADM TUM	2530	467L	7501-7912	à	L 0.0005	L 0.0005	9.0005	0.0	
CADH IUN 2 TOTAL	2537	457L	7501-7912 /	7	0.0009	L 9.0005	.0006143	.0001952	
CALCIUM P	540	4GZL	7321-7412 7501-7912	17	17.	7.9	13.083	1.4223 3.7922	0.7
COPPES 2	560	MGZL	7001-7412	2	0.004	1 2.001	.0018333	.0013292	
COPPER 2	56 T	4571	7501-7912		3.011	L C.001	0.001	0.0	1.4

3089.5

Page 494 EGM-2013-00163 IEC

# TABLE 4.5 (continued)

PARAMETER	TEST	UNITS	DATE	NO. DE	MAXIMUM	MININUM	HEAN	STANDARD DEVIATION	TEST
DISSOLVED	2577	NGYL	7301-7412	5	L 0:1	L 0.04 L 0.1	0.06	+030984 0-0	3.2
TOTAL	2571	NG/L	7001-7412 7501-7912	5	1.2	L 0.04	0.28833 0.125	0.45653	1.0
DISSOLVED	CACS	46/L	7001-7412	5	0.01	L 0.001	0.003	.0036332.	1.2
TOTAL	2597	MAZL	7501-7912		500.C	L 0.001	0.001125	.0003536	
MGNESIUM	2595	4G/L	7001-7412	13	2.7	1.17	1,9917	0.58951	0.7
MANGNESE	2600	HGZL	7001-7412	6	L 0.01	L 9.01	0.01	0.0	
MERCURY	2611	MG/L	7501-7912	2	1. 0.00005	1 0.00005	0.00005	0.0	-
POTAS 1UM	2640	NG/L	7001-7412	5	0.7	0.4	0.53333	0.12111	
SOD IUM	2650	MGZL	7301-7412	(6)	0.9	0.5	0.71667	0.20412	
ZINC	2660	MGZL	7001-7412	6	0.013	L 0.005	.0063333 0.0076	0.003266	0.5
7 INC	2661	NG/L	7501-7912	8	9.008	1 2.205	0.00575	.0013887	-

Page 495 EGM-2013-00163

Water Quality of Sheep Creek Downstream from HB Mine (Source: Waste Water Management Branch, Ministry of Environment)

PARAMETER	TEST	UNITS	DATE	NO. OF VALUES	MAXIMUM	HINTHUM	MEAN	STANDARD	TEST
COLOR TR	002	REL UNIT	7001-7412 7501-7912	56	18:	L 5:	6. 6667	2.2361 2.582	0,5
РН	004	REL UNIT	7001-7412 7501-7912	27	7.9 8.5	7.2	7.6083	0.32926 0.31622	1.8
RES 105C	005	HG/L	7001-7412 7501-7912	5	100.	44.	67.571	21.476	0.4
RESF 105	007	MG/L	7501-7912	6	90.	+0 .	64.333	23.509	
RESNEIDS	008	MG/L	7001-7412 7501-7912	6	30.	£ 1:	6.9 2.	11.379	1.2
SPF COND	011	US/CH	7981-7412	20	135:	49:	111.89	37.099	1.3
TEM ARRY	012	DEG.C	7001-7412	6	18.	5.	10.667	4.5898	
TSAMPLG	013	DEG.C	7001-7412 7501-7912	12	10:	ô:	3.3333 5.2667	3.9833	0.9
OXY DISS	014	MG/L	7001-7412	9	14.6	11.2	12.517	1.4784	0.5
TURBIDTY	015	N.T.U.	7001-7412	14	8.2	0.25	2.6833	2.9554	2.6
BAR.PRES	017	KPASCALS	7001-7412	9	94.714	92.854	93.895 94.036	0.7931	0.1
ATA TEMP	020	DEG.C	7001-7412 7501-7912	4	15:	-1:	9.3333	6.6081	0.1
COLR: TAC	024	T.A.C.	7501-7912	7		11.	2.8571	1.8645	
C.D.C.	020	US/CH	7501-7912	1	134.	134.	134.		
ALKALT T	102	WG/1.	7001-7412	17	58.4	29.	46.667	14.814	0.6
CAREN DR	103	MGAL	7001-7412	1	3:	2:	2.8333	0.40825	El

3089.5

IEC

\_\_\_IEC.

TABLE 4.6 (continued)

	PARAMETER	TEST	UNITS	DATE	NO. DE	MAXINUH	MINIMUM	MEAN	DEVIATION	TEST
	CHLOPIDE	104	MG/L	7001-7412 7501-7912	62	1,2	L 0.5	0.73333	0.30111	0.3
1	CYANIDE	105	MG/L.	7001-7412 7501-7912	14	£ 8:81	L 0.01	0.01	8:8	****
Q	FLUDRIDE	196	MGZL	7001-7412 7501-7512	6	L 0.11	£ 8.1	0.10167	.0040822	
	HARDNESS	1.07	MG/L	7001-7412 7501-7912	14	73.1	25.4	50.917 44.807	20.727	0.7
	AMNONEA	108	46/L	7001-7412	63	0.02	L 0.01 0.005	+0133333	0.005164	1.5
	N02/N03	109	NG/L	7501-7912	3	0.09	0.04	0.06	.026457	
	NITRATE	110	NG/L	7001-7412 7501-7912	65	0.08	0.02 L 0.02	.048333	.027869	1.0
	NITRITE	111	9G/L	7001-7412	5	L 0.005	L 0.005	0.005	0.0	
	NIT DRGN	112	MG/L	7001-7412 7501-7912	6	L 0.09	L 0.01	.046667 0.01	.030111	-
	NIT KJEL	113	MG/L	7501-7912	7	75.0	L. 0.01	,084286	0.10990	-
	HIT TOTL	114	MG/L	7501-7912	5	0.26	L 0.02	0-108	0.10035	
6	PHOS ORT	118	NG/L	7001-7412		0.004 0.018	L 0.003	.00333333	.000 5164	1.7
	PHD5 TOT	119	MG2L	7001-7412	6	0.039	0.005	.013667 .014333	0.01314	0.1
	SILICA	120	MG/L	7501-7912	4	8+2	4.5	6.575	1.5861	
	SULPHATE	121	HG/L	7881=7412	\$	12:0	2 3:	8.5333	3.3608	1.0
	ARSENIC	2510	HG/L	7501-7912	1	L 0,005	L 0.005	0.005		
	ARSENIC	2517	HG/L	7501-7912	7	L 0.005	L 0.005	0.005	0.0	
	CADMIUM	2530	MG/L	7501-7912	5	1. 0.0005	L 0.0005	0.0005	0.0	
	-CADMIUM	2531	MG/L	7501-7912	7	0.001	L 0.0005	.0005714	0.000189	
	CALCIUM DISSOLVED	2540	MGZL	7001-7412	12	23.5	8.3	14.521	6.593 4,8776	0.1

3089.5

19

Page 497 EGM-2013-00163 TABLE 4.6 (continued)

IEC\_

PARAMETER	TEST	UNITS	DATE	NO. OF	MAXIMUM	MINIMUM	MEAN	STANDARD DEVIATION	TEST	2
DISSOLVED		MG/L	7001-7412 7501-7912	9	0:001	£ 8:001	.0012857	.0007559	0.9	
TOTAL	2561	NG/L	7501-7912	7	L 0.001	L 0.001	0.001	n.0		
IFON.	2570	MGZL	7001-7412	6	L	L 0.04	0.06	.030964		_
DISSOLVED			7501-7912	9	L 0.1	L 0.1	0.1	0.0	3.7	
TOTAL	2571	NG/L	7001-7412 7501-7912	6 3	1.1	L 0.04	0.31	0.39329	1.2	
O LSSOLVED	2580	MG/L	7001-7412 7501-7912	á	0.013	L 0:001	004 1667	0.004916	1.6	
TOTAL	2581	MG/L	7501-7912	8	0.005	L 0.001	0.001625	.0017678	-	
MGNES LUM	2590	MGZL	7001-7412	6	3.5	1+14	2.4233	1.0353	1000	
DISSOLVED			7501-7912	14	3.1	0.95	2.075	0.77429	0.8	
MANGNESE	2600	MGZL	7001-7412	6	L 0.01	L 0.01	0.01	0.0		
MERCURY	2611	HG/L	7501-7912	2	L 0.00005	L 9.00005	0.00005	0.0		
DISSOLVED	26.412	MG/L	7001-7412 7501-7912	6	0.7	0.4	0.56667	0.15055		
SOD TUM	2650	MGZL	7001-7412 7501-7912	6	1:3	0.6	1.05	0.2881		
ZINC	2660	MG/L	7001-7412 7501-7912	67	0.02	L 0.005	+01 233 3 0 +00 7	.0053541	2.2	
ZINC	2667	MG/L	7501-7912	9	0+023	L 0.005	0.009	.0060474		

3089.5

Page 498 EGM-2013-00163

Water Quality of the Salmo River, Downstream from Sheep Creek Confluence (Source: Waste Management Branch, Ministry of Environment)

PARAMETE	TEST CODE	UNITS	DATE	ND. DF VALUES	MAXINUM	MINIMUN	HEAN	STANDARD	TEST
COLOR TR	002	AEL UNT	7001-7412 7501-7912	ŝ	5:	25:	5.	8:8	
DILAGRSE	003	MG/L	7501-7912	10	L 5.	L 1.	4.6	1.2649	
ΡĤ	004	REL UNIT	7001-7412 7501-7912	59	7.9	6.5	7-3875	0.37499	1.5
RES 1050	005	MG/L	7001-7412 7501-7512	51	96 . 94 .	46. 38.	74.5 63.373	22.353 12.657	1.6
RESF 105	007	MG/L	7001-7412 7501-7912	1 6	84. 82.	84. 46.	63.833	14.511	
RESNE105	008	HGAL	7001-7412 7501-7512	46	3.6	1:	1.9	1.4731 2.9564	0.2
SPF COND	011	USZCM	7001-7412 7501-7912	17	142.	70.	115.75 96.471	33.925	1.2
TEN ARRY	012	DEG.C	7001-7412	4	18.	9.	12.5	4.3589	
T SAMPL G	51.3	DEG.C	7001-7412 7501-7912	4	13:	2:	5.4444	3.1091	0.0
2210 YX0	014	WGZL	7001-7412 7501-7912	4	13.4	11.2	12.325	1.8025	0.5
TURBIOTY	015	N.T.U.	7001-7412 7501-7912	13	2:5	1.2	0.68231	0.57373	2.6
BAR.PRES	017	KPASCALS	7001-7412 7501-7912	4	95.246 93.519	94.316 92.19	94.615	0.42165	4.4
AIR TEND	020	DEG.C	7001-7412 7501-7912			3:	11:	12.728	0.1
COLDITAC	024	1.4.5.	7501-7912	5	5.	L 1.	4.	1.8708	
ALKALIT	1.02	NGAL	7501-7412 7501-7912	13	55.8	31.	47.5 42.5	15:022 9:4692	0.8
CAPAN DA	193	MGZL	7001-7412	4	4:	1.	2.5	1.291	

3089.5

IEC

21

Page 499 EGM-2013-00163

# TABLE 4,7 (continued)

IEC.

PARAMETE	R CODE	UNITS	PANGE	NO. OF		NININUM	MEAN	STANDARD	TEST
CHEOR IDE	104	4671	7001-7412 7501-7912	- 3	0.0	L 0:5	0.625	0.15	0.1
CYANIDE	105	MGZL	7001-7412 7501+7912	49	L 0.01 2.03	L 0.01 L 0.01	.010612	.0031676	0.4
FLUORIDE	106	MGZL	7001-7412 7501-7912	1	1 0.1	1 8:1	0.1	0.0	- 53
HARDNESS	107	MG/L	7001-7412 7501-7912	13	61.9 58.6	29.	48.05	16.023	0.4
AMMONIA	108	NG/L	7001-7412 7501-7912	\$	L 0.01 0.017	L 0.01	0.01	0.0	0.5
EDN/SDN	109	HG/L	7501-7512	8	0.1	L 0.02	0.05125	.033568	
NITRATE	110	4G7L	7001-7412 7501-7912	4	0.07	L 0.03	0.045	.019149 .037749	0.1
NITRITE	111	MG/L	7001-7412	4	L 0.005	L 0.005	0.005	0.0	
NIT ORGN	112	MG/L	7301-7412 7501-7912	4 6	0.06 0.11	0.02	.056667	0.01633	0.8
NIT KJEL	113	MG/L	7501-7912	10	0.15	L 0.01	0.066	.044771	
NIT TOTL	114	MG/L	7501-7912	4	0.17	0.09	0.125	.033166	
PHOS ORT	119	MG/L	7001-7412 7501-7912	4	L 0.003	L 0.003	0.003	.0004579	1.1
PHOS TOT	119	MGZL	7001-7412 7501-7912	10	0.022	0.005	0.01025	-0080571	0.8
SILICA	120	MG/L	7501-7912	2	8.5	8.4	8.45	.070621	
SULPHATE	121	MG/L	7001-7412 7501-7912	43	9.	<u>L 5.</u>	7.5	1.8511	1.0
ARSENIC	2510	NGAL	7501-7912		L 0,005	L 0.005	0.005	0.0	
ARSENIC	2517	MGIL	7501-7912	6	L 0.005	L 0.005	0.005	0.0	
CADMIUM	2530	MG/L	7501-7912	4	L 0.0005	L 0.0005	0.0005	0.0	
CADMIUM	25.3T	MGZL	7501-7512	5	L 0.0005	L 0.0005	0.0005	0.0	_
CALCIUM	2540	467L	7001-7412 7501-7912	13	21:	9.0	16.35	5.3532	0.4

3089.5

TABLE 4.7 (continued)

IEC.

PARAMETE	TEST CODE	UNITS	DAT E PANGE	NO. OF	MAXIMU		MEAN	STANDARD DEVIATION	TEST	
DISSOLVE		MG/L	7001-7412 7501-7912	46	0.002	L 0.001	0.00125	0.0005	4.2	1
TOTAL	2561	MG/L	7501-7912	b	0.001	L 0.001	0.001	0.0		-
DISSOLVED	2570	4671	7281-7412	47	£ 8:1	L 8:04	0.055	0.03	0.4	
TOTAL	2571	MG/L	7001-7412 7501-7912	\$	0.49	0.07 L 0.1	0.1825	0.20549	0.6	
DISSOLVED	2580	MGZL	7001-7412 7501-7912	48	3.005	L 0.001	0.00275	-0017078	3.3	
TOTAL	2587	MG/L	7501-7912	8	0.001	L 0.001	0.001	0.0	-	
HENES IUM	2590	HG/L	7501-7412	13	2.3	1.03	1.7525	0.64814	0.6	
MANGNESE	2600	MG/L	7001-7412	4	D.01	L 9.01	0.01	0.0	0.0	
MERCURY	261T	467L	7501-7912	1.1	0.00005	L 0.00005	0.00005		-	1
POTASIUM	2640	MG/L	7001-7412 7501-7912	4 2	0.9	0.5	0.7	0.18257	0.7	-
SODIUM DISSOLVED	2650	467L	7001-7412 7501-7912	4 2	1:3	0.7	1,175	0.3594	0.3	
ZINC	2660	46/L	7001-7412 7501-7912	46	0.011	L 0.005	0.008	.0024495	1.3	
TOTAL	265T	MG/L	7501-7912	Б	0.02	L 0.005	0.0085	0.004928		1
COL .FECL	450	H.P.N.	7501-7912	1	23.	23.	23.			-
COL.TOTL	451	H.P.N.	7501-7912	1	33.	33.	33.			

3089.5

23

Page 501 EGM-2013-00163

#### Manthly Maan Discharges in Cubic Feet Per Sacand for Sheep Creek and Solmo River Tributaries (From Fisheries and Environment Canada, 1977)

Location	Yes	Jon	Feb	Mar	Apr	May	An	<u>.kd</u>	Aug	Sep	Oct	Nov	Dec	Lat (N)	Long (W)	Drainage Area (mi <sup>2</sup> )
Sheep Creek near Salmo	1930	•	•	÷	4	*	277	62.7	29.0	23.0	•	•	•	4990833*	117915111=	51.9
Nugget Creek	1938	•	э.		-		1			12	÷	•	σ.	49*09*04**	117008-62**	3,6
Sheep Creek	1939					33.8	17.6	9.5	4.7	A.1						
a state as state	Mean		+			33.8	17.6	9.5	4.7	7.7			10			
Aillings Creek	1938	-	21	÷.	4		-	-	-	0.20	÷	-	4	49 08 40"	117908'50"	1 <sub>2</sub> 3
Sheep Creek	1939	÷ .	1.1	100	14.1	8.0	4.2	1.6	0.45	0.40			22.			
	Mean			-		8.0	4.2	1.6	0,45	0.30			-			
Halfway Creek	1937	÷	•	2	÷	-	3.6	1.2	0.22	0,20	÷.	÷.	4	49010-20-	11791518*	2.8
Solmo	1938	-	4	n 11	18.0	23,1	10.2	1.4	0.54	0.40		÷.	2.1			
	1939	-		1.0	1.1	10.6	6.9	1,8	0.38	0,21	-201	20				
	Mean			12.7	18.0	15.9	6.7	1.5	0.38	0.27		100	2.1			

3089.5

IEC.

Page 502 EGM-2013-00163 IEC.

for the period of 1949 to 1976 are given in Table 4.9. Those for the period of 1977 to 1980 are given in Table 4.10.

It is evident from the tables that peak flows occur in May and decrease substantially between August and March.

The maximum instantaneous discharges and maximum daily discharges recorded for the Salmo River have generally occurred in May and June. The flow minima occurred during the fall and winter months.

### 4.5.4 Water Licences

On 1 March 1957, Cominco Ltd. was granted Water Licence No. 16532. This allowed the company to divert and use a maximum of 2727 m<sup>3</sup> (600,000 gallons) of water per day from Sheep Creek for the purpose of mining and milling.

In addition, on 1 March 1961, Cominco Ltd. obtained Licence No. 17622 to divert a maximum of 1282 m<sup>3</sup> (282,000 gallons) a day from Aspen Creek, a tributary of Sheep Creek (from the Water Rights Branch, Department of Lands and Forests, Province of B.C.). The breakdown of water uses are as follows: 1282 m<sup>2</sup> (250,000 gallons) a day for mining and milling, 100 m<sup>3</sup> (22,000 gallons) a day for industrial purposes (compressor) and 46 m<sup>2</sup> (10,000 gallons) a day for waterworks.

All of these licences have been transferred to David Minerals by the Water Rights Branch consistent with the transfer of title of the HB Mill.

### 4.5.5 Fisheries

There are no anadromous fish present in the Salmo River system. The Salmo River system is a tributary of the Columbia River, located 122 km above the Grand Coulee Dam. There are no known commercial or native food fisheries in the Salmo district. Very little information is available on the sport fishery patterns in the District.

Monthly and Annual Mean Discharges from 1949-1976 for Salmo River Near Salmo (From Fisheries and Environment Canada, 1976) Located 8 km S of Confluence with Sheep Creek

					SALHO HEV		ALHO - ST	ATION NO.						
			HONTHLY A		L NEAN DISS		. CUAIC FI					ORD		
YEAR			HAN	AFR	RAT.	HUL	JUL	AUG		DCT	NON	DEC	HEAM	783
			117	2340	5 \$70	1980	506	215	151	206	441	476		194
1950 1851 1952 1952 1954	274 447 284 194	236 935 112 364 276	401 521 252 264 647	1320 2110 2210 1120 1150	4080 5050 4620 4340 5800	**20 2710 2630 *320 *360	1310 953 885 1340 2040	383 235 251 385	183 150 278 355	795 561 112 269 342	003 175 107 456 696	871 875 105 328 875	1200 1238 1039 1130 1420	191 195 195
1955	318 355 152 175 340	247 313 165 102 246	177 349 234 423 249	920 2410 1320 1440 1790	1990 5510 6440 5350 4150	5032 3350 2170 1720 8660	2370 242 446 416 922	547 300 255 191 256	27 8 215 192 187 745	363 266 227 236 1000	659 215 211 249 688	121 191 759	1790 1180 1070 943	195 195 195
1960 1961 1962 1963 1963	233 757 147 147 143 224		422 558 209 483 200	2010 2015 1360	3#30 5100 1210 1850 1970	4210 4580 2866 2735 4960	841 663 801 1100	201 210 273 360 346	222 190 203 198 355	273 311 175	325 214 375 305 377	185 163 490 264 382	1120 5220 912 938 1110	
1965 1965 1967 1968 1969	232 208 267 238 295	231 176 233 386 286	381 358 402 961 352	2010 1770 865 888 2250	3626 5316 3970 3830 5160	2930 2970 5500 4310 3120	531 537 742 643	274 233 212 425 241	737 187 128 128 133	174	323 217 329 714	119 203 519 301	944 573 1110 1170 1200	196 196 196
1970	227 258 184 227 795	223 581 200 192 343	317 382 1180 412 620	760 1600 1590 1170 2110	1400 5510 6220 3850 4730	2920 3790 4700 2580 7220	357 1150 1760 525 1950	179 344 389 178	184 191 172 168 208	186 254 283 364 145	203 274 355 703 248	188 215 187 578 227	7#2 1250 1420 #25 1570	197 197 197 197
1975	31	157	330	790	\$070	*#50 3#50	1330	134	345	362	:::	1010	1210	157
NEAH	252	316	131	1190	+1+0	3000	1070	328	285	135	467	354	1150	HEAT
	LOCATION		17 12 33 5		DRAINAGE A		4 10 HILE	9						

SALHO BIVEN HEAR SALHO - STATION NO. OBHEDIA

	ANNUAL EXTREMES OF DISCHARG	E IN CFE AND ANNUAL TOTAL DISC	HADGE IN AC-FT FOR THE PERIOD	OF RECORD
TEAR	MAXIMUM INSTANTANEOUS DISCHARGE	MANIMUN DAILY DISCHARCE	HININUM DAILY DISCHARGE	TOTAL DESCHARGE TE
1949	11600 CPE AT 0300 PST DH HAY 14	10700 CFE ON HAT 13		13
1950 1951 1952 1953 1953	7430 CF8 AT 0630 PST OF MAY 13 9340 CF5 AT 0330 PST OF MAY 13 8400 CF5 AT 0513 PST OF MAY 12 8430 CF5 AT 1400 PST OF MAY 15 13000 CF5 AT 0400 PST OF MAY 15	6330 CFS OK RAY 13 8460 CFS ON RAY 12 7480 CFS ON RAY 12 8050 CFS ON RAY 15 1360 CFS ON RAY 15	152 CFE ON REF 24 145 CFE ON REF 21 58.0 CFE ON BEC 26 = 54.0 CFE ON JAN 7 248 CFE DN OCT 10	838000 AC-FT 18 886000 AC-FT 18 786000 AC-FT 18 815000 AC-FT 18 1030000 AC-FT 18
1955 1856 1957 1958 1957	10408. CFS AT 0330 FST ON JUN 13 13308 CFS AT 0448 FST ON MAT 21 12708 CFS AT 0468 FST ON MAT 26 10088 CFS AT 0308 FST ON MAT 22 48808 CFS AT 0330 FST ON JUN 6	9400 CFS DH JUH 13 10300 CFE DH MAT 31 10700 CFS DH MAT 5 6730 CFS DH MAT 22 8360 CF6 DH JUH 6	170 CFS ON RAP 38 151 CFS ON OCT 9 175 CFS ON OCT 9 146 CFS ON SEP 8 138 CFS ON SEP 8	935000 AC-FT 13 146000 AC-FT 13 734000 AC-FT 13 682000 AC-FT 13 132000 AC-FT 13
1960 1961 1962 1963	13100 CP3 AT 0130 P3T ON HAY 13 6610 CP4 AT 0300 P4T ON HAY 25 6310 CP4 AT 0115 P3T ON HAY 25 1670 CP4 AT 0316 P3T ON HAY 21	18208 CFS ON MAY 12 7120 CFS ON JUN 8 5628 CFS ON HAY 21 6150 CFS ON HAY 24 7778 CFS ON HAY 20	136 CFX ON OCT 5 111 CF6 DX OXC 11 112 CF3 OK JAN 10 136 CF3 OK DCT 17 141 CF4 OK DCT 16	817000 AC-FT 19 860050 AC-FT 19 660050 AC-FT 18 579009 AC-FT 19 809000 AC-FT 19
965 1965 1967 1968	4804 CFI AT 0140 FST OK HAY 30 7810 CFI AT 0330 FST DW HAY 3 9410 CFI AT 3330 FST DW JAY 3 16300 CFI AT 2120 FST OK JUH 2 8746 CFI AT 2120 FST OK HAY 13	8110 CPE OH HAY JY 7320 CPE OH HAY 7 8660 CP5 DH JUM 3 11400 CP5 OH JUH 2 8210 CP5 OH HAY 13	154 CPF ON DEC 15 118 CPF ON STP 24 164 0 CPF ON STP 24 154 0 CPF ON SAN 5 154 CPF ON JAN 5 154 CPF ON SPP 13	483000 AC-FT 136 705000 AC-FT 136 906000 AC-FT 136 954000 AC-FT 136 954000 AC-FT 136
970 971 973 973	6805 CF3 KT 0617 PAT OH HAY 76 11506 CF3 KT 1358 PAT OH HAY 13 11806 CF4 KT 2118 735 OH AAV 13 9260 CF4 KT 2128 735 OH AAV 14 13700 CF4 KT 2105 PAT OH AAV 14	5400 CFS ON NAY 25 10400 CFS ON NAY 13 10400 CFS ON NAY 13 5350 CFS ON NAY 17 13400 CFS ON JUN 15	114 CFE OM HOV 32 125 CFE OM JAM 1 93.3 CFS DM DEC 4 107 CFE OM SEP 14 136 CFS DM HOV 3	347000 AC-FT 197 907000 AC-FT 107 1010000 AC-FT 107 470000 AC-FT 197 110000 AC-FT 197
*75 *76	\$300 CFE AT 0300 PST DM MAY 16 8370 CFS AT 1616 PST D# MAY 11	1150 CFE ON MAY 16	153 CPS ON DEC 11	#15000 AC-FT 187
		EXTREME RECORDED FOR THE PERC	00 DF #2000	#32000 AC-PT

26

3089.5

IEC.

#### SALMO RIVER NEAR SALMO - STATION NO, 08NE074 MONTHLY AND ANNUAL MEAN DISCHARGE IN CURIC FEET PER SECOND FOR 1977-1980

YEAR	JAN	FEA	MAR	APR	MAY	<b>JUN</b>	M	AUG	ÆP	OCT	NOV	DEC	MEAN	YEAR	
1977	167	185	220	1240	2290	1530	363	212	296	286	379	337	676	1977	
1978	285	250	688	1990	4070	4220	1210	427	667	431	290	212	1230	1978	
1979	190	173	466	1042	4061	1763	597	219	207	211	177	344	771	1979	
	(5.09)	(4.90)	(13.7)	(29.5)	(115)	(50.1)	(16.9)	(5,17)	(5.86)	(5,97)	(5.0)	(9.73)	(224)		
1980	247	785	679	3407	4590	1532	\$33	379	364	281	459	614	1109	1980	
	(6.99)	(8.08)	(17.8)	(96.5)	(130)	(43.4)	(15.1)	(9,59)	(10.3)	(7.97)	(13.0)	(17.5)	(31,4)		
MEAN	220	223	501	1920	3753	2263	676	299	364	302	326	377	937	MEAN	

\* Brocketed figures report values in cubic metres per second (m<sup>3</sup>/sec) + cumers

IEC.

#### ANNUAL EXTREMES OF DISCHARGE IN OF'S AND ANNUAL YOTAL DISCHARGE IN AC-FT FOR 1977-1980

TEAH	MAXIMUM INSTANTANEOUS DISCHARCE	MAXIMUM DAILY DISCHARUE	MINIMUM DAILT DISCHARGE	TOTAL DISCHARCE	TEAN
1977	SEID CES AT 0258 PST ON JUN 8	4510 CES ON MAY 3	150 CFS ON JAN 2	454000 AC-FT	1977
1978	8670 CFS AT 2355 PST ON JUN 8	7450 CFS ON JUN 3	IRI CFS ON DEC 25	891000 AC-FT	1978
19.79	7168 CFS AT 0238 PST ON MAY 3 (203 m <sup>3</sup> /a)	6780 CFS ON MAY 5 (192 m <sup>3</sup> /s)	106 CF5 ON NOV 29 (1.01 m <sup>3</sup> /s)	574719 AC-FT (709000 doim <sup>3</sup> )	1579
1990	15501 CFS AT 1026 PST ON APR 29 (439 m)/11	13488 CF5 ON APR 29 (382 m <sup>2</sup> /s)	(5.16 m <sup>3</sup> /s)	B04121 AC+FT (992000 dam <sup>3</sup> )	19.80

3089.5

According to Mr. P.G. Stent, Conservation Officer for the Provincial Ministry of Environment, Fish and Wildlife Branch stationed at Trail, sportsfishing for rainbow trout (Salmo gairdneri) and Dolly Varden char (Salvelinus malma) take place on both Salmo River and Sheep Creek, but fishing intensity and catch statistics have never been collected. Most of the fish taken in Sheep Creek are usually less than 25 cm in length. Fishing for rainbow trout and Dolly Varden char occurs along the banks of the Salmo River. The favorite fishing location is 4 km south of Salmo near the old Highway 3-6 bridge which crosses Sheep Creek. Rainbow trout weighing up to 9 kg have been caught by anglers at this spot. Mr. Stent also reported that rainbow trout spawning has been observed in the lower reach of Sheep Creek, but details on their abundance are not available. A small number of Eastern brook trout (Salvelinus fontinalis) are found in Erie Lake and Erie Creek, which drain into the Salmo River.

Other fish found in the rivers and creeks of the Salmo district are: longnose sucker (Catostomus catostomus), largescale sucker (Catostomus macrocheilus), lake chub (Couesius plumbeus), redside shiner (Richardsonius balteatus), shorthead sculpin (Cottus confusus), mottled sculpin (Cottus bairdi), slimy sculpin (Cottus cognatus), longnose dace (Rhinichthys cataratae), and northern squawfish (Ptychocheilus oregonensis). According to a local angler and trapper, the number of squawfish is said to be increasing in the Salmo River.

#### 4.6 Groundwater

JEC\_

There are no known accounts of groundwater hydrology that are relevant to the HB Mine property. There is considerable evidence of groundwater present in the closed mine shaft. In 1979, Corninco Ltd. determined the mine groundwater flow rates and analyzed its quality.

### 4.6.1 Quantity

Table 4.3 shows the mine drainage flow rates. Between January and June, the flow rate was highest during the month of March. It was seven to nine times higher than monthly rates from April to June.

3089.5

### 4.6.2 Quality

IEC.

Water quality samples of the mine ground water were taken on 22 February, 10 April, 8 May and 5 June 1979. The results are given in Table 4.11. The drainage water was slightly alkaline with pH values remaining relatively constant for the period sampled. Total solid, total cyanide, dissolved iron and copper concentrations remained relatively constant. On the other hand, suspended solids, dissolved sulphate, lead and zinc concentrations varied on the four sampling dates.

### 4.7 Soils and Surficial Geology

According to Jungen (1980), Salmo soils are most frequent on the lower slopes of major valleys such as the Sheep Creek Valley. They occur on glacial till deposits that have long, smooth slopes. The topography is gently to steeply sloping and is broken by smooth linear gullies. The soils have developed in compact glacial (basal) till that is principally associated with coarse-grained bedrock. The deposits are generally over 1.5 m in depth and non-calcareous. The surface texture is moderately coarse (mainly sandy loam) and grades to very coarse with increasing depth. Typical soil development is Orthic Dystric Brunisol. Significant inclusions of Orthic Humo-Ferric Podzol are found in the cooler and moister transition zone at higher elevations, with Brunisolic Gray Luvisols occurring where the glacial till is of finer texture than usual. Orthic Eutric Brunisols are also present at lower elevations and where the parent material is slightly higher in calcareous content. Salmo soils are moderately acid, have low cation exchange capacities and are moderately base saturated. Salmo soils are well to rapidly drained.

#### 4.7.1 General Geology

The geology of the Salmo district has been described by Walker (1934) and more recently by Little (1950). Palaeozoic sedimentary rocks of the area rest on Proterozoic sediments, and are overlain by Mesozoic volcanic rocks. The Palaeozoic rocks are made up of quartzites, limestones and argillites and form a broad belt which extends northward from the Salmo area into the Kootenay Lake district. In the Salmo area, the most economically important group is the Lower Cambrian Laib group of

3089.5

29

Page 507 EGM-2013-00163

H B Mine Drainage Water Quality HB Mine Pollution Control Permit, P.E. - 1853 Monitoring Data - First and Second Quarter, 1979

## Mine Drainage

	Feb. 22	Apr. 10	May 8	June 5
pH	8.0	8.3	8.2	8.2
Total Solids	481.0	407.0	420.0	331.0
Suspended Solids	1.0	64.0	140.0	11.0
Dissolved SO4	200.0	119.0	64.0	93.0
Total CN	L0.01	L0.01	L0.01	L0.01
Dissolved Fe	0.11	L0.05	L0.05	L0.05
Dissolved Pb	0.04	0.05	0.08	0.07
Dissolved Zn	0.90	0.80	0.19	0.48
Dissolved Cu	0.005	0.005	0.005	L0.005

\*All measurements except pH are reported in milligrams per litre (mg/I = PPM).

3089.5

IEC.

Page 508 EGM-2013-00163 IEC

slates and limestones, in the calcareous members of which all the productive zinc-lead deposits of the area are found.

The Palaeozoic rocks are extensively folded and faulted, and have been intruded by a long narrow granitic tongue which extends south from the main Nelson batholith, following a line of regional faults. Also apparently associated with the post-Triassic intrusive period are numerous smaller granitic bodies which follow the same trend. Several of these smaller granitic stocks are in close proximity to the HB Mine, and it is probable that the ore is related to the granite.

### 4.7.2 Geology of the HB Mine

The HB Mine is located within the Kootenay Arc, which in the Salmo area consists of an assemblage ranging from quartzites through argillites to limestones and back into argillites. The HB ore bodies are localized within the dolomitized lower part of the Reeves Limestone.

In the mine vicinity, the Lower Laib is folded isoclinally, with axial planes striking north-south and inclined steeply east. The folds plunge 20 degrees to the south. The main ore bodies are confined to a syncline approximately 1067 m (3500 ft) in length and 61 to 122 m (200 to 400 ft) wide. The Garnet ore body 152 m (500 ft) to the west is in a smaller syncline. There are essentially two types of ore bodies, a steeply dipping variety of ore stringers and a flat lying type. Both types of ore zones conform to the 20 degree plunge of the fold.

The fine-grained dolomite host rocks for the ore are either described as crackled or as grey, massive. Crackle dolomite is a white dolomite containing dark carbonaceous material in lineations, patches and streaks. It represents a banded rock which has undergone tremendous stresses. The grey, massive dolomite is untextured and hosts only a small percentage of the total HB reserves. The mineralogy of the ore is simple with sphalerite, pyrite and galena with pyrchotite occurring locally. The larger steep zones have a Zn:Pb ratio of about 6:1 whereas the flat zones have a Zn:Pb ratio of 2.4:1.

3089.5

The boundaries of the HB ore bodies are determined by structure, lithology and topography. To the south, the ore zones pinch-out apparently caused by an upward refolding of the synclinal package. To the east and west the syncline and the dolomite host rock control the extent of mineralization. To the north, the ore zones plunge up to surface and are almost completely oxidized within 91 m (300 ft) of the surface. The chief economic constituents of the ore body were lead and zinc, occurring as marmatite and galena, in a gangue of talc, tremolite, limestone and dolomite. There were also considerable iron sulphides in the form of pyrite and pyrrhotite.

#### 4.7.3 Mining

IEC.

The ore bodies were mined by Cominco Ltd. from underground by both longhole and open stoping methods.

Access to the mine was through two main openings. The portal of the main entrance, and the 853 m (2800 ft) level haulageway, is situated about 91 m (300 ft) above Sheep Creek and provides access from the main surface buildings. Most of the personnel and supplies were carried underground on this level and all the ore and waste was trammed out.

The 1067 m (3500 ft) level portal is located about 122 m (200 ft) above Aspen Creek, and provides access to the upper reaches of the No.1 zone and to the hoist-room for the service shaft. Some material and a few personnel entered the mine through this opening. A third access of lesser importance, the 7006 m (3300 ft) portal, is located above the 1853 m (2800 ft) level portal and on the same slope.

Underground, the only ore tramming was on the 1853 m (2800 ft) level. This was done by a Ruston-Hornsby diesel locomotive pulling eleven 6-ton cars from various areas dumping at the coarse ore bin located on the surface about 103 m (340 ft) east of the portal. All other ore and waste movement underground was affected by 20 to 60 HP air or electric slushers and by gravity down to the 1853 m (2800 ft) level.

#### 4.8 Vegetation\*

IEC.

The Sheep Creek Valley is situated in the Western larch subzone of the Interior Hemlock biogeoclimatic zone, characterized by a total annual precipitation in the range of 56-89 cm (22-35") Krajina (1969).

Land on the south facing slope surrounding the mine complex includes areas of productive and non-productive woodland. Immature stands of quaking aspen, lodgepole pine and Douglas fir occupy medium quality productive sites (Forest cover map 82-F-3-g 1962). Paper birch is common and black cottonwood is dominant along the river bottoms. Fire destroyed the cover over part of this area in 1905 and in 1925. The tallings pond occupies a depression, bounded on the west by unproductive land (rock) and by productive woodland in other directions. Productive woodland has a cover of predominantly miniature western larch with minor Douglas fir, lodgepole pine and western white pine inclusions on medium quality sites. Fire also destroyed forest cover over part of the tailings pond area in 1925.

The regrowth of trees in the areas destroyed by forest fires is poor, primarily due to erosion of the thin topsoil layer after the fire. There is some harvestable timber in the area below the company houses, which was untouched by fire.

Other trees and shrubs found on the HB Mine property are: rose snowberry and dogwood. The species of grasses found include: red top alsike clover, red clover, sweet clover, timothy, bluebunch wheatgrass and field horsetail.

 $\star$  Common and scientific names of the vegetations found in the HB Mine site are listed in Appendix A

3089.5

33

Page 511 EGM-2013-00163

#### 77 C.

# 4.9 Wildlife

IEC

# 4.9.1 Ungulates

Good habitat for ungulates is found all along the Salmo River valley, extending up into the valleys of its tributaries. Sheep Creek valley, one of these tributaries, is part of this network of land classified as 3W (C.L.I. 1971). This classification indicates that the land has slight limitations to the production of ungulates, and provides good winter range for ungulates from the surrounding area. In the Sheep Creek valley area, excessive snow depth may limit ungulate production by reducing the mobility of ungulates and the availability of food plants.

There is a large area of class 2 W land (C.L.I. 1971) located in the Pend d'Oreille River valley approximately 15 km south east of the HB Mill area. Deer tagged on the Pend'Oreille winter range have been relocated more than 30 km north of their capture site to cal Biologist, Fish and Wildlife Branch, Nelson, pers. comm.). It is believed that most of the deer from the Salmo area migrate along the river valley bottoms to winter on this more favourable winter range, which has only very slight limitations for overwintering deer.

Mule deer (<u>Odocoileus hemionus</u>), whitetail deer (<u>Odocoileus virginanus</u>) and a few elk (<u>Cervus canadensis</u>) have been seen near the minesite and tailings pond during the winter months. In February 1982, 15 mule deer were seen in the vicinity of the tailings pond and the old highway (3-6) bridge at Sheep Creek. The deer appeared to be feeding on alfalfa planted in the borrowed area near the tailings pond as a part of the reclamation programs. Whitetail deer prefer the dense cover found in major valley bottoms and therefore are probably not numerous along the narrow, steep-sided valley of Sheep Creek.

Caribou (<u>Rangifer tarandus</u>) have not been seen in the study area. The Selkirk herd is centered in the Nelson Range east of the Sheep Creek valley. This herd utilizes high elevation ranges in northern Washington and Idaho and adjacent areas in British Columbia.

3089.5

#### 4.9.2 Carnivores

American black bear (<u>Ursus americanus</u>) are relatively common in the Sheep Creek valley, and grizzly bears (<u>Ursus arctos horribilis</u>) are sometimes sighted. One black bear was shot at the garbage dump site near the tailings pond in 1977. Cougar (<u>Felis concolor</u>) and coyote (<u>Canis latrans</u>) occur in the study area although no information is available concerning population levels.

# 4.9.3. Furbearers

Reclamation/revegetation procedures as well as extensive forest fires have resulted in a mixture of plant communities in the Sheep Creek valley. Riparian habitats, mature coniferous forests, second growth mixed woodlands and meadow lands support a variety of furbearing mammals. The furbearers occurring in the Salmo district are listed in Table 4.12.

Traplines in the Salmo District are licensed to Mr. Max Eberts of Salmo, who traps in the Erie Creek, Sheep Creek and Lost Creek areas, and to Mr. Harry Mueller of Salmo, who traps in the Hidden Creek, Porcupine Creek, and Wildhorse Creek areas up to Ymir. Mr. Derick Leduc has trap lines in the Salmo and Erie areas. Mr. Eberts reported catches of 10 beaver, 5 marten, 5 mink, 1 muskrat, and 3 weasel, to make a total of 24 pelts in 1982. It is not possible to extrapolate trapping records to give estimates of animal populations since trapping effort varies greatly and fluctuates with market prices for furs.

#### 4.9.4 Waterfowl

The HB Mine property is classified as having such severe limitations to waterfowl production that almost no waterfowl are produced. This is because so much of the Sheep Creek valley terrain is bounded by steep hillsides, and there are few suitable feeding areas for waterfowl. In addition, there are almost no permanent water bodies in the study area.

3089.5

# **TABLE 4.12**

# Species of Furbearers Occurring in the Salmo District Nomenclature after Cowan and Guiguet, 1956

Common Names Scientific Name		Occurrence		
Bobcat	Lynx rufus	Rare		
Lynx	Lynx canadensis	Rare	$\dot{\tau}$	
Beaver	Castor canadensis	Common		
Marten	Martes americana	Common		
Fisher	Martes pennanti	Common		
Weasel	Mustela spp.	Rare		
Mink	Mustela vison	Common		
Muskrat	Ondatra zibethica	Common		
Wolverine	Gulo luscus	Rare		

36

3089.5

IEC

Page 514 EGM-2013-00163

# 4.9.5 Birds

IEC

Ravens are plentiful in the area and congregate at the garbage dump. The open woodlands and denser conifer stands of Sheep Creek valley provide good summer and winter habitat for Ruffed grouse which is the most common upland game bird in the area. Great blue heron are occasionally sighted during the summer months on the HB Mine property. It is expected that the normal complement of passerines (small perching birds) occupy suitable habitats throughout the study area.

#### 4.10 Land Capability and Use

The physical capability of the land surrounding the mine and tailing pond has been classified for use in agriculture, forestry, recreation, ungulate and water fowl production (Canada Land Use Inventory). The classification was based on data from surveys conducted under the Canada Land Inventory Program and reported by Gardiner (1974). The following are physical capabilities of the land at the HB Mine for each use group:

#### 4.10.1 Agriculture

- (a) The Mine has severe limitations for agricultural use due to adverse topography, shallowness to bedrock and climate. Eighty percent of the land possesses no capability for agriculture or permanent pasture. Twenty percent is capable only of producing perennial forage crops.
- (b) The tailing pond land has severe limitations for agricultural use due to adverse topography, stoniness and climate. Forty percent of the land area possesses no capability for agriculture or permanent pasture while 60% is capable only of producing perennial forage crops. Improvement practices are considered feasible.

3089.5

4.10.2 Forestry

IEC.

- (a) The land at the mine site has moderate to severe limitations to the growth of commercial forest. Growth limiting factors include restriction of the rooting zone by bedrock and soil moisture deficiency. A small area has severe limitations which preclude growth of commercial forests.
- (b) The tailing pond land has slight (60%) to moderate (40%) limitations to growth of commercial forest. Growth may be limited by restriction of rooting zone by bedrock and soil moisture deficiency.

# 4.10.3 Recreation

a) Mine and tailings pond land lacks the natural capability and significant features to rate higher than low capability for outdoor recreation, but has natural capability to engender and sustain a low annual use based on such activities such as hiking, nature study or for aesthetic appreciation. The land possesses continuous flowing streams in upland areas,

# 4.10.4 Ungulates

(a) The mine and tailings pond land is classed as winter range of moderately high capability for deer and moose. Productivity may be reduced in some years due to excessive snow depth that reduces mobility of ungulates and availability of food plants.

# 4,10.5 Waterfowl

(a) Mine and tailing pond capability for the production of waterfowl is negligible or nonexistent due to adverse topography.

3089.5

\_\_\_IEC\_

4.10.6 Trapping

The trapping licence for the Sheep Creek Valley is issued to Messrs. Max and Melvin Eberts.

4.10.7 Guiding

There are no records of big game guiding ventures in the Salmo district.


4.11 Reclamation Work at the HB Mine Site

A reclamation program was carried out by Cominco. Ltd., in accordance with terms and conditions of Surface Work Permit M-85, issued by the Provincial Ministry of Energy, Mines and Petroleum Resources on 28 March 1973. The objectives of the reclamation program were to:

- improve growth conditions on the disturbed land areas and to encourage succession of native vegetation;
- accelerate soil formation and control erosion, by establishment and maintenance of an initial vegetative cover with grass and legume species;
- 3. provide forage for wildlife;
- 4. improve the aesthetic appearance of disturbed land surfaces.

The extent of the surface areas disturbed by the mining and milling operations during Cominco's ownership are given in Table 4.13 (Rusnell and Gardiner, 1982). The size of areas reclaimed and of those not yet reclaimed are also given. The locations of the reclaimed areas are shown in Figure 4.3. Of the 35.7 ha of surface area disturbed, Garnet Zone opening and tailings dam(2.4 ha), borrow pits (3.4 ha) and the waste rock dump at 1,067 m elevation (0.1 ha) were completely reclaimed. The waste rock dump at the 853 m elevation was not reclaimed because it remained in use as a storage area. Approximately 23% of the tailings impoundment was reclaimed.

3089.5



# Table 4.13

IEC\_

# The Nature and Extent of Land Disturbance and Reclamation at H.B. Operations (From Table 1, Rusnell and Gardiner 1981)

	Area of Disturbance		Area of Completed Reclamation			Non-vegetated Areas remaining		
	ac	ha	ac	ha	<u>%</u>	ac	ha	96
Waste rock dumps 853 m (2800 ft) level 1,067 m (3500 ft) level	2.2 0.2	0.9 0.1	0 0.2	0 0.1	0 100	2.2 0	0.9 0	100
Garnet Zone opening	6.0	2,4	6.0	2.4	100	0	0	0
Tailings impoundment	61.3	24.8	14.3	5.8	23	47.0	19.0	77
Tailings dam and borrow pits	8.4	3.4	8.4	3.4	100	o	0	o
Buildings and service area	4.0	1.6	٥	0	0	4.0	1.6	100
Roads	6.1	2.5	0	0	0	6.1	2.5	100
TOTAL	88.2	35.7	28.9	11.7		59.3	24.0	

3089.5 40

Page 519 EGM-2013-00163 A grass seed mixture composed of creeping red Iescue, Canada bluegrass, timothy, and red top, and legume seed mixture composed of rambler alfalfa, alsike clover and birdfoot trefoil, were used to seed the disturbed surfaces. Ponderosa pine, lodgepole pine, Douglas fir and paper birch seedlings were also planted.

The following is a summary of the results of reclamation efforts reported by Rusnell and Gardiner (1982) at the HB Mine site,

853 m (2800 ft) level waste rock dump:

IEC.

This area was used as a storage space so that the revegetation program was not initiated prior to the sale of the property.

1,067 m (3500 ft) level waste rock dump:

Cool, wet weather during May and June 1981 promoted satisfactory growth and cover at this site. Vegetation was dominated by creeping red fescue with significant timothy, red top, Canada blue grass and minor alsike clover distributed irregularly over the waste dump surface.

Lodgepole pine seedlings were planted on the waste dump in May, 1980 and were establishing satisfactorily. However, survival rates for other woody species was poor, as indicated by the following values: black cottonwood 25%, quaking aspen 4% and birch 3%.

Natural revegetation of the old housing site and around the Garnet Zone pit has progressed satisfactorily, with fertilizer applications enhancing growth and extent of coverage. Establishment of seeded legume and grass species near the Garnet Zone pit was variable, being poorest on the broken rock and best on the natural, undisturbed soil with its layer of organic matter on the surface.

### Tailings Dam and Borrow Pits

IEC.

#### a) Tailings Dam and West Borrow Area

A dense cover of alfalfa, timothy and creeping red fescue was growing on the tailings dam slopes and the west borrow area. Vegetative growth was excellent with no evidence of chlorosis. Maintenance fertilizer was not applied to either area in 1981.

Species composition varied somewhat on the compact top portion of the dam, however vegetative growth was very good. Canada bluegrass was the dominant species with significant amounts of red top, creeping red fescue and alfalfa also present. Minor amounts of birdsfoot trefoil were also present.

## b) 1974 and 1977 Borrow Areas

A satisfactory vegetative cover dominated by grasses was sustaining growth throughout both borrow areas without maintenance fertilizer. Species composition varied throughout the areas, being affected by soil composition, seepage, moisture accumulation and replacement of surface soil. Woody species, including willow and poplar, were invading the 1974 borrow area along east and west perimeters. All drainage ditches have been stabilized with vegetation.

Canada bluegrass was the dominant grass on the 1974 borrow pit floor with timothy and creeping red fescue becoming co-dominant within seepage areas and on the less compact slopes along either side of the pit. Alsike clover was present but distribution was irregular and overall cover minor.

Lodgepole pine establishment on the 1974 borrow area slopes appears to have been satisfactory. Trees were growing satisfactorily and emerging above the grass cover.

#### Tailings Pond

IEC.

The HB tailings pond occupies approximately 25 ha (Table 4.13). Water impounded behind the tailings dam covers approximately 25% of the pond area. The remaining area is covered by tailings and tailing slimes. Approximately one-third of this area has been revegetated.

Seed mixtures composed of a variety of agronomic grass and legume species were broadcast on untilled tailings surfaces during May, 1979 and October, 1980.

Fertilizer was broadcast prior to seeding to promote seedling establishment. Maintenance fertilizer was applied in June, 1980 and April, 1981 to sustain vegetative growth and promote seed production. 1981 maintenance fertilizer treatment was 46-0-0 applied at 109 kg/ha. The current year's vegetation was monitored in detail on June 29 and 30.

Broadcast application of seed and fertilizer on the untilled tailings surface has proven effective as a technique for revegetating the H.B. tailings pond. Due to the smooth tailings surface, seed and fertilizer were re-distributed by wind action, resulting in accumulation of high concentrations of both seed and fertilizer within cracks and microdepressions. For example, vegetation growing on tailings seeded in spring 1979 was characterized by large clumps of vigorously growing grasses, varying in basal area and irregularly distributed throughout the seeded area. Interspersed among the clumps, grass and legume plants established by self-seeding have increased plant density and overall vegetative cover. A thick carpet of moss covers most of the tailings surface between the clumps of grasses. Tall fescue and redtop were spreading onto unseeded tailings along surface drainage channels. Plant populations and vegetative cover continued to increase on coarse tailings within the main drainage channel.

3089.5

Quantitatively, biomass averaged 1971 kg/ha. The combined cover of grasses, legumes, mosses and litter averaged 88%. Only 12% of the tailings surface was bare of any plant cover. Seeded grasses and legumes contributed 53%, mosses 23%, with litter from previous years' growth amounting to 12%. Species composition was diverse, nine grass and legume species being identified. Tall fescue and red top were co-dominant, while all other grasses were minor to significant. Alsike clover was the only legume to provide significant cover.

A dense population of grass seedlings has been established throughout the area of tailings seeded in the fall of 1980. On areas of coarse textured tailings, large numbers of alsike clover seedlings emerged, but many were severely chlorotic and will likely die out. Others were healthy in appearance and growing satisfactorily. Alkaligrass was widely distributed. Mosses were providing ground cover, promoted by fertilizer applied at seeding and again early in the spring.

# 4.12 Historic and Archaeological Sites

The Salmo district has not been systematically inventoried for heritage resources. It appears that the site has a very low potential for the occurrence of historical or archaeologically significant sites within the mine property or the district.

#### 4.13 Existing Social Environment

#### 4.13.1 Setting

IEC.

The Village of Salmo is located in the Regional District of Central Kootenay in the south-east corner of the Province. It is known as the "Crossroads of the Kootenay's" and is a small town nestled in a valley of farm and timber lands. Salmo was incorporated in 1946 and expanded its municipal boundaries in the early 1970's so that it now occupies an area of 220.6 ha (545 ac.). The village is 42 km (26 mi) south of Nelson, 42 km (26 mi) east of Trail and 83 km (52 mi) west of Creston, with access by both the Southern Trans-Provincial Highway (Highway 3) and Highway 6.

3089.5

The economy of the Regional District is well-diversified. Trade and service industries play the dominant role with Nelson being the historical regional centre for those sectors. Also, the resource industries continue to contribute to the well-being of the Region's economy with forestry being the most important. Mining played a much larger role in the past but now is only significant at New Denver, Silverton and Salmo. Agriculture is not a large part of the economy, however, it does provide income on a part-time or subsistence basis. Tourism is becoming increasingly important with the main centre of attraction located in environs of the Nelson-Balfour strip along the west arm of Kootenay Lake. The area around Nelson lost a major part of the through traffic on the Southern Trans-Provincial route when the Salmo-Creston link was completed in 1964, but it remains a popular tourist destination (British Columbia Regional Index, 1978).

#### 4,13.2 Population

IEC

The population of the Regional District of Central Kootenay in 1981 was 51,505 (Statistics Canada Interim Report 1981). This represented a 5.2 percent increase over the 1976 population of 48,980. The age composition of the Region is comparable to the Provincial average with approximately 58 percent of the population being under 35 years of age. The population of Salmo was relatively stable between 1971 and 1976. During this time the village expanded its municipal boundaries which accounts for the increase in population from 870 in 1971 to 1090 in 1976. Between 1976 and 1981 the village increased its population by approximately 6 percent to 1154. Salmo's population represents only 2.2 percent of the Regional population. Table 4.14 illustrates the 1976 age and sex composition for both Salmo and the Regional District of Central Kootenay.

#### 4.13.3 Employment

The total labour force of the Regional District of Central Kootenay in 1971 was over 16,550. Recent figures compiled by the Regional District's Planning Department indicate that the greatest concentration of labour is found within the trade and financial services sector (37 percent) while primary industry accounts for only 15 percent of the labour force. In contrast, the village of Salmo's labour force is concentrated in the primary industry sector (37.5 percent). Table 4.15 compares the

3089.5

**TABLE 4.14** 

# POPULATION BY AGE GROUP AND SEX (1976)

46

Regional District of Central Kootenay	Male	<u>%</u>	Female	<u>%</u>	Total 1	<u>%</u>
0 - 19 20 - 34 35 - 64 65 +	8,720 5,830 7,790 <u>2,745</u> 25,080	$(17.8)(11.9)(15.9)\frac{5.6}{(51.2)}$	8,425 5,340 7,640 <u>2,645</u> 24,050	(17.2) (10.9) (15.6) (5.4) (49.1)	11,170 15,430 5,390	(35.0) (22.8) (31.5) (11.0) (00.0)
Salmo						
0 - 19 20 - 34 35 - 64 65 +	210 105 190 <u>50</u> 555	(19.3) (9.6) (17.9) (4.6) (51.4)	200 105 180 50 535	(18.3) (9.6) (16.5) (4.6) (49.0)	210 ( 370 ( 100	37.6) 19.2) 34.4) (9.2) 20.0)

 $^{1}\ \mathrm{Figures}\ \mathrm{may}\ \mathrm{not}\ \mathrm{total}\ \mathrm{due}\ \mathrm{to}\ \mathrm{rounding}$ 

IEC\_

Source: Regional District of Central Kootenay, Economic Profile, 1979.

3089.5

# TABLE 4,15

# EXPERIENCED LABOUR FORCE BY INDUSTRY (1976)

	Salmo	Regional District of Central Kootenay	British Columbia
Primary Industry Manufacturing Construction Transportation &	37.5 % 9.4 4.7	14.8 % 17.8 6.7	7.6 % 16.1 7.0
Communications	6.2	10.4	9.5
Trade & Financial Services	32.8	36.8	45.6
Public Administration and Defence	3.1	5.3	6.3
Other	6.3	8.3	7.9
	100.0	100.0	100.0

Source: F. Dykeman, Director of Planning, Regional District of Central Kootenay, pers. comm., 1982.

3089.5 47

IEC.

percentage of the labor force employed by sector for Salmo, the Regional District of Central Kootenay and British Columbia for 1976.

By far the largest employer of the Kootenay region, which includes the Salmo area, is the Cominco Ltd. operation in Trail. Cominco employs 6,300 persons with a monthly payroll of approximately \$7,000,000. Approximately 25 persons from Salmo work for Cominco Ltd. in Trail. The Cominco operation is scheduled for temporary shut down effective 30 June 1982 because of the general slowdown in the economy being experienced in B.C. and other parts of Canada. This event will significantly affect the economy of the region.

There are approximately 50 persons employed by various business establishments in the village of Salmo. The elementary and secondary schools employ a total of 22 teachers and staff. Louisiana Pacific Canada Ltd. operated a sawmill 5 km south of Salmo on old Highway 3-6. It employed 75 persons until September 1981 when the company shut down its operation. The company continues to employ nine persons as maintenance staff.

#### 4.13.4 Unemployment

Recent unemployment figures are available from the Canada Manpower Centre in Nelson which administers unemployment claims for the Salmo area. However, there are no detailed statistics concerning occupational groupings or accurate figures for monthly unemployment rates.

The current number of registered claimants at the Nelson Manpower office was 2,726 (1,946 male, 668 female) for the week ending 16 April 1982 Manager, Nelson Manpower office, pers. comm.). The mining and quarrying occupational group had a total of 65 registered claimants (63 male, 2 female) representing 3 percent of the total. The forestry and processing occupational groups exhibited a greater number of registered claimants, 234 (12 percent) and 417 (21 percent) respectively. The latest Statistics Canada estimated rate of unemployment for B.C. Economic Region No. 92, which includes the Nelson-Salmo area as well as the Kootenay-Columbia region, was 16.4 percent for the third week in March, 1982. This rate would be higher if the Kootenay-Columbia region was excluded from this estimate

# 4.13.5 Housing

150

As of 1982 there are approximately 430 single family homes, 4 duplex units, 8 apartments and 40 mobile homes within the Village of Salmo Municipal Clerk, Village of Salmo, pers. comm.). In addition, there are approximately 60 mobile homes in a trailer park located about 3 km (2 mi) south of the village.

The average price of a house in Salmo is \$40,000 with a range from \$10,000 to \$100,000. The monthly rental of a 2-bedroom apartment is estimated to be less than \$300 Municipal Clerk, Village of Salmo, pers. comm.). In 1981 there were 39 building permits issued for a total value of \$2,119,000, of which \$884,000 was for residential developments. There were 18 new homes built in 1981 and currently there is a 24-unit apartment complex under contruction.

# 4.13.6 Education

Educational services in the Salmo district are administered from Nelson (School District No.7). The Salmo Elementary School has an enrollment of 346 students, while the Salmo Secondary School has an enrollment of 183 students. The student teacher ratio is 15:1 including administration, library staff, and counsellors. These schools serve the areas between Ymir and Nelway and halfway to Fruitvale. There is an elementary school in Ymir with an enrollment of 50 students.

4.13.7 Commercial Services and Community Facilities

Though the village of Salmo has a relatively small population, it offers a wide range of commercial services and community facilities which are listed below:

#### Village of Salmo Facilities

RCMP Office Medical Clinic Fire Hall/Village Office Post Office Liquor Store Bus Depot - Greyhound Air Strip

3089.5

IEC\_

West Kootenay Power and Light Forest Ranger Station Department of Highways - Public Works Provincial Courthouse

#### **Community Halls**

Royal Canadian Legion #217 KP Hall Masonic Hall Guide and Scout Hall

### Banks

Canadian Imperial Bank of Commerce Kootenay Savings Credit Union

### Churches of the Community

Salmo Community Memorial Church Hillcrest Pentecostal Church Sacred Heart Parish Jehovah Witnesses Kingdom Hall

#### **Recreation Facilities**

Salmo Ski Hill - CSPS/CSIA Salmo Golf Course Swimming Pool Salmo Tennis Courts Curling Club Golden Age Activity Centre Salmo Public Library

### Schools

Salmo Elementary Salmo Secondary Selkirk Health Unit

#### Grocery Stores

Liberty Foods Valu-Mart Foods Riverside Service Salmo Corner Store

#### Food Restaurants

Birch's Burgers Dragon Inn Restaurant

3089.5

\_\_\_IEC\_

Ernie's Chicken & Ribs Trapper John's Restaurant The Last Straw Dining

#### Industries

HB Mill; David Minerals Ltd. Louisiana Pacific Can. Ltd. Sedy Cedar Sales Kootenay Stone Centre T.V. Views Publications Interior Paper Recycling Ltd. Norman Industries Goldbelt Mines Inc.

### Organizations

Legion Lions Kiwanis Chamber of Commerce Hospital Auxiliary Pythian Sisters Knights of Pythias Masons

#### Lodging - Hotels and Motels

Salmo Hotel Sharlyles Hotel Sal Crest Motel - 18 Units Selkirk Motel - 10 Units Reno Motel - 7 Units Pine Springs Motel - 16 Units

### Campgrounds and Trailer Parks

Hidden Creek Campground Wildwood Campground - Trailer Park Pine Springs Selkirk Trailer Park Evergreen Trailer Park Riverside Trailer Park Government Picnic Site -Eric Creek

#### Gas Stations and Repairs

Marathon Motors Salmo Texaco Riverside Service – Propane Whiteline Truck Stop

3089.5

Speedway Salvage Ltd, Mountain Auto Body

#### Auto Dealerships

\_IEC\_

Skyway Truck & Trailer Ltd. (International Dealership)

#### Other Businesses of Salmo

Salmo Drugs Salmo Building Supply Skyway Hardware Ltd. Salmo Sewing Basket Simpson Sears - Catalog Office West Kootenay Sound Services Hipwell Realty Ted Peil Agencies John's Insurance Agency Salmo Payless Store Taylor - Wilton Nel. Ltd. Alca Kennels G. & G. Trucking Salmo Transport Shell Can. Bulk Sales Hanson Sawmills Ltd. P. & B. Contracting Blackwood Electric Ltd. Solar House Laundromat

#### 4.13.8 Police and Fire Protection

A complement of four RCMP officers are permanently stationed in Salmo. The present staffing guideline is 1 officer for every 1,500 citizens. The fire protection of the Salmo district is provided by two fire trucks and two "fast attack units", manned by 30 volunteer firemen.

#### 4.13.9 Medical Service

Medical service in the Salmo District is provided by the Medical Associated Clinic which has a staff of two medical doctors and three office helpers. There is no dental care available at the present time. Nelson and Trail are the closest communities providing dental services.

3089.5

Salmo has recently acquired a new ambulance which is manned by the volunteer fire department. The nearest hospitals are located in both Nelson and Trail, equidistant from Salmo. The Selkirk Health Unit, operated by the Ministry of Human Resources, is also available to Salmo area residents on an on-call basis.

### 4.13.10 Transportation

Salmo is served by Highway 6 to the north and south and by Highway 3 to the west. Greyhound bus services are available for north and west bound passengers. Salmo is also served by Burlington Northern Railway, which carries freight only. There is also a small air strip which can accomodate small planes.

# 4.13.11 Recreational Opportunities

The Salmo area possesses the potential for a variety of outdoor recreation activities such as fishing, hunting, cross-country and downhill skiing, hiking and camping. The Salmo ski hill, located 3 km (2 mi) from the village, offers excellent skiing facilities. It is equipped with a 1235 m (4050 ft) long T-bar lift and with lighting equipment which allows night skiing. The vertical drop is 320 m (1050 ft).

In the village itself there is a curling club with three rinks, a golf course, swimming pool, tennis courts, and an ice rink is currently under construction.

#### 4.13.12 Water/Sanitation

Salmo is currently provided with water from three 60-ft wells. The extent of the water supply has not been determined, however, it is felt that the system is more than adequate to meet the needs of the community in the foreseeable future

The water from the wells is pumped uphill to a 100,000 gallon storage tank and from there is delivered to the community on a gravity feed system.

The sanitary sewer system consists of a collection network, a transfer main, two oxidation lagoons with chlorination at the outfall into Sheep Creek.

3089.5

JEC

The Regional District is responsible for garbage pick-up and disposal in the Salmo area. At present, private contractors carry out this service, transporting the garbage to the dump which is located on the south bank and uphill from Sheep Creek, approximately 9 km (5 mi) from Salmo and 3 km (2 mi) from the HB Mill.

# 4.13.13 Utilities

West Kootenay Power and Light Company Ltd. supplies electrical power to Salmo and the surrounding Region. Natural gas is piped to Salmo by Inland Natural Gas Co. while fuel oil and gasoline is supplied by Shell Canada Ltd., Imperial Oil Ltd. and Chevron Canada Ltd. Propane is also available and supplied by a Castlegar-based distributor.

# 4.13.14 Communications

The Salmo area is served by two newspapers, the Daily Nelson News and the Trail Times, Cable TV (4 channels), CBC, and two radio stations, CBUT and CJAT.

Telephone service is provided by B.C. Telephone Co.

### 4.13.15 Municipal Finance

The Village of Salmo's current financial situation is considered to be very healthy

Tax assessment for Salmo is based on the actual market value of the property less 10 percent. In 1981, residential property was taxed at a rate of 11.5 percent of the assessed value, businesses at 23 percent and industrial property at 27 percent. The approximate 1982 mill rates for Salmo are as follows: School - 60; the Regional District, Hospital, Municipal Finance Authority and B.C. Assessment Authority - 13; the General Municipality - 23; for a total of 96 mills.

3089.5

# 5.0 PROJECT DESCRIPTION

IEC.

David Minerals Ltd. is seeking an approval of Phase I of their project. This encompasses reactivation of the HB Mill for concentrating the gold bearing ore mined elsewhere in the Salmo district. No mining is planned within the HB Mine property.

### 5.1 Characteristics of Ore to be Processed

One source of the gold bearing ore is production from the Sheep Creek Mine, owned and operated by Goldbelt Mines Ltd. The mine is located approximately 10 km east of the HB Mine site. Table 5.1 shows the results of ore sampled and assayed on 15 June 1981 and 2 February 1982 by Kamloops Research and Assay Laboratory Ltd. of Kamloops, B.C.

#### TABLE 5.1

Head Assay of the Ore Sample from the Sheep Creek Mine, Goldbelt Mines Ltd.

	Au*	Ag*	Cu	РЬ	Zn	Fe	Ро
Jun 15 1981	0.52	0.70	0.02	0.54	0.27	3.4	ND
Feb 02 1982	0,47	0.41	0.03	0.25	0.31	3.18	1.96
* Troy ounce per d	ry short						
ND = not determin	ed						

Gold content of the ores delivered to the HB Mill from the Sheep Creek Mine were determined by the assaying laboratory located in the mill. The results are shown in

Table 5.2. It appears that the gold concentration varies a great deal from load to load. The primary reasons for this are:

- the mine is still in the exploration stage and
- 2) the gold concentrations in the vein fluctuate from place to place.

# TABLE 5.2

# Results of Gold Assays of Ore Delivered to the HB Mill from the Sheep Creek Mine

Delivery Date	Amount Delivered	Gold Concentration*
	(Dry Short tons)	
2/16/82	460.0	0.077
2/17/82	246.2	0.077 0.201
2/18/82	199.8	0.340
2/00/82	114.5	0.090
2/00/82	150.8	0.125

\* Troy ounce per dry short ton.

# 5.2 Milling Process

IEC\_


The flowsheet for concentrating gold and iron from the ore produced from the Sheep Creek Mine is given in Figure 5.1. The mill flowsheet and description of the processes used for concentrating lead and zinc from the ore produced at the HB Mine are given in Appendix B. Cominco Ltd. transported the concentrates to the smelter at Trail for refining. Gold bearing concentrate produced by the HB Mill will be transported to Helena, Montana for refining.

3089.5

# FIGURE 5.1

H.R. Mill Project, Mill Flowsheet for Processing the Gold Ore from the Sheep Creek Mine, Goldbelt Mines Inc.





57

3089.5


FIGURE 5.1 continued

IEC.

3089.5

Mill Flowsheet for Processing the Gold Ore from the Sheep Creek Mine, Goldbelt Mines Inc.






Page 537 EGM-2013-00163 FIGURE 5.1 continued

H.B. Mill Project, Mill Flowsheet for Processing the Gold Ore from the Sheep Creek Mine, Goldbelt Mines Inc.

# CONCENTRATOR FLOWSHEET



# Reagents:

IEC

	Sodium Isobutyl Xanthate		
	Aerofloat 208		
	Copper Sulphate		
	MIRC		
3089.5			
_		59	

#### 5.3 Transportation

IEC.

The gold bearing ore will be transported from the Sheep Creek Mine by trucks with an 8-ton capacity over a 19 km dirt road, approximately 8 m wide, which follows the path of Sheep Creek.

Gold concentrate will be placed in bins with canvas covers, and transported 322 km (200 ml) to Helena, Montana via paved Highway 3-6 to Creston and then to U.S. Highways in 25-ton trucks.

#### 5.4 Sewage and Garbage Disposal

Domestic sewage from the office, mill, and company houses will be treated in septic tanks of sufficient capacity to retain the maximum anticipated loads for at least 24 hours. Overflow will be discharged into the tailings line and then into the tailings pond.

Garbage will be dumped at a location near the tailings pond within the HB Mine site (Figure 5.2). This garbage dump is owned and operated by the Central Kootenay Regional District, and garbage from all over the region is dumped there.

#### 5.5 Utilities

Electrical power for the mill complex is supplied by West Kootenay Power and Light Company. The 60,000 volt, 3-phase main power line is strung along the strip of land between the public and private roads on the HB Mine property from Highway 3-6. A substation located in the vicinity of the mill reduces the voltage to 2300 or 550 volts to power the motors in the mill. Further reduction to 110 volts, single-phase for domestic use is made by transformers located at various sites.

Telephone service for the mill is provided by B.C. Telephone.

The water supplies for the mill, fire fighting and domestic use are obtained by diverting water from Aspen Creek. A 10,000 gallon covered wooden stave pen is used

3089,5

as the reservoir. David Minerals Ltd, also has a permit to pump water from Sheep Creek, but does not intend to use it because there are adequate supplies of water available throughout the year for the entire mill operation from the Aspen Creek diversion.

The office and houses in the mill complex are heated by oil.

#### 5.6 Employment

Since the purchase of the mine in September 1981, David Minerals Ltd. has employed 24 workers through a Vancouver contractor to overhaul one circuit for concentrating gold bearing ore. The contractor's employees have the following job classifications: pipe fitter, carpenter, electrician, equipment operator, welder, millwright, labourer and helper. Most of them have been recruited locally from the Nelson-Salmo area.

David Minerals Ltd. currently has a total of ten direct employees working at the mill site. They are: one each of mill manager, district geologist, geological helper-fieldman, metallurgist, assayer, surface foreman, temporary helper-draftsman and stenographer and two cooks. In addition, there are four shift workers temporarily working one circuit. Renovation of this circuit was completed on 8 March 1982.

Overhaul of the second circuit has been initiated and is expected to be completed by June 1982.

The number of additional shift workers which will be needed to man the proposed 3 shifts per day, 7 days per week mill operation will be approximately 12. Thus a total of 16 people will be needed for all the shifts (including a swing shift). In addition, a 4-man clean-up crew, a 4-man maintenance crew and a warehouseman will be needed to support the mill operations.

In the first instance, recruitment for all of these positions will be carried out locally.

The salaried staff which will be required for the operation include a mill manager, district geologist, metallurgist, junior metallurgist, mill superintendent, assayer, two

3089.5

laboratory technicians, time keeper and a secretary-stenographer. The total number of people employed at the mill will be approximately 37.

#### 5.7 Housing

There are seven company-owned houses on the mine premises. Some of the company's and the contractor's employees are housed there. With few exceptions, most of the persons staying in the company housing return to their homes for weekends. Some of the employees commute from Salmo and the surrounding communities. It is expected that the increase in the employment opportunities at the mill will not have an adverse effect on housing availability in the Salmo district, because of the weak housing market in the area.

#### 5.8 Development Schedule

Operation of the mill will be initiated immediately upon receiving the approval of the Metal Mines Steering Committee, Ministry of Energy, Mines and Petroleum Resources.

#### 5.9 Reclamation

No mining is planned in Phase I of the HB Mill project. Therefore, no new surface disturbances will be created. Moreover, the disturbed areas reclaimed by Cominco Ltd. on the mine property will be monitored to determine the need for further reclamation work.

#### 5.10 Effluent Control and Monitoring

The tailings pond used during the Cominco operation will be reused to dispose of tailings generated by the new operation. The original wooden flume used to carry the tailings from the mill to the tailings pond has been replaced by 8 in. plastic pipe in 1981. The layout of the tailing line is shown in Figure 5.2. A sagging and leaky flume sometimes allowed tailings to spill into Sheep Creek during the previous operation. Installation of the plastic pipe eliminates this problem. The tailings line was inspected by personnel of the Waste Management Branch, Nelson Regional office, on 3 and 9 March 1982.

3089.5


Klohn Leonoff Consulting Engineers were responsible for a detailed study of the feasibility of using the tailings pond. Results of the study and their recommendations are given in Appendix C. They concluded that the existing dam which was designed for a discharge of 80 cfs, can handle the 200 year flood estimated for the site, and has a capacity of approximately 790,000 tons. Depending on availability of ore, no substantial modifications to the dam height will be needed before mid-1984.

A constant flow of water is fed to the tailings pipe at the rate of  $1.45 \text{ m}^3$  per minute (320 gallons per minute) at the mill. The flow of water prevents sediment accumulation and freezing of the line during the winter.

A magnetic flow meter will be installed in the tailings pipe close to the tailings pond (Figure 5.2) to monitor the flow of tailings to the pond. An indicator will show flow rate and percentage composition of solid in the tailings. A totalizer will record total gallonage discharged each day up to one week period. These meters are connected to the office located in the mill complex and an alarm will be activiated if flowrate drops below a pre-set level. Water samples of the tailings pond overflow will be taken (Figure 5.2), and water quality will be determined.

63

3089.5



Page 543 EGM-2013-00163

### 6.0 ENVIRONMENTAL AND SOCIAL IMPACTS

The proposed reactivation of the HB Mill will treat high sulphide ore by crushing, grinding, flotation and thickening to produce a concentrate containing gold and iron. The concentrate will be transported to Helena, Montana by truck for refining.

Cominco Ltd. operated both the mine and mill for over 15 years with a minimum of environmental impact on the mine site, and with many beneficial social impacts on the communities of Salmo district. The mill's long history of successful operation suggests that if there were any adverse environmental impacts associated with the mill then they would have become evident long ago. Thus, it is espected that the reactiviation of the mill by David Minerals Ltd. will involve no significant adverse environmental impacts on the area surrounding the mine site.

### 6.1 Environmental Impacts

There will be some fugitive dust generated by transportation of ore and ore concentrate to and from the mill. Both public and private roads adjacent to and within the mine property are unpaved. Trucks are unable to travel over 10 km per hour because of the narrow road and steep grade of the hill. If excessive dust is generated by this traffic, a water truck will be used to wet the road during dry months. Dust emissions from unloading of the ore at the mill site and transporting the stockpile will be controlled by water spraying.

No significant change in the water quality of Sheep Creek or the Salmo River is anticipated from the tailings pond runoff. Overflow is discharged into the Salmo River, while surface runoff and mine drainage are discharged into Sheep Creek.

Tallings pond capacity is far greater than the amount of tailings to be discharged in the next two years.

No significant impact on the aquatic fauna and flora of Sheep Creek and the Salmo River is anticipated. During the previous Cominco operation no fish kill was ever reported.

3089.5

Although there are some ungulates present on the mine property, they are rarely encountered on the road. The speed limit for vehicles is 40 km per hour within the mine property, so that vehicle-ungulate collisions are most unlikely to occur. It was observed that deer fed on the alfalfa growing in reclaimed areas near the tailings pond during February 1982. Both Messrs. Graham Kenyon, President of the B.C. Wildlife Association, who resides in Trail, and Randy De Biasio, President of the Trail Wildlife Association, have stated that reactivation of the HB Mill will not adversely affect the wildlife of the Salmo district.

#### 6.2 Socio-Economic Impacts

#### 6.2.1 Employment

IEC\_

The information basis for the following employment estimates must be considered preliminary because:

- 1. Manpower estimates are not finalized.
- All estimates are best guesses based on previous experience. Each project is unique, therefore actual employment will probably vary somewhat from that predicted.

Despite these limitations the available employment estimates are valuable for planning purposes.

The mill operations will function year-round based on a 7-day week. Employees will work on an 8-hour shift basis, 3 shifts per day with a swing shift to permit a 5-day work week. Table 6.1 describes the workforce that will be required to operate and manage the mill. It is assumed that the main source of labor will be from the Nelson-Salmo area. Manpower officials in Nelson have indicated that local recruitment for the mill positions should not be a problem as there is presently a large number of unemployed people with mining and mill working experience in the area (AI Sabiskoss, Manager, Canada Manpower, pers. comm.).

3089.5

## TABLE 6.1

## OPERATING WORKFORCE REQUIREMENTS

	Job Description	Number of Employees
Salaried	Mill manager	1
Staff	Geologist	1
	Metallurgist	Î.
	Junior Metallurgist	1
	Mill Superintendent	1
	Chief Assayer	1
	Lab Technician (assay)	1
	Lab Technician (metallurgical)	1
	Timekeeper	1
	Cooks	2
	Secretary	1
Hourly-basis	Mill operators	12
Staff	Helpers	4
0.000	Clean-up crew (1 leader & 3 helpers)	4
	Maintenance crew	4
	Warehouseman/Storekeeper	1
	TOTAL	37

3089.5

IEC.

Page 546 EGM-2013-00163 Approximately 35 to 45 people will be employed during Phase I of the reactivation of the HB mill. Since September 1981 David Minerals Ltd. has employed 24 workers to overhaul one circuit for concentrating gold bearing ore. Direct and indirect/induced employment has already occurred as a result of Phase I and similar impacts are expected for Phase II and III.

The milling operations will create 16 basic jobs which in turn will generate about 5 non-basic jobs in the area to service the mill and the employees. The multiplier used to estimate the number of non-basic jobs is 0.35. Thus, for every job created at the mill, 0.35 non-basic jobs will be created in the Nelson-Salmo area. The multiplier is small because the Nelson and Trail areas already offer many goods and services which may be needed during the mill operations. Many businesses in the non-basic sector will require little or no expansion in terms of employment since many are not working at capacity as a result of the recent downturn in the region's economy precipitated by high interest rate, depressed lumber market and low metal prices.

#### 6.2.2 Population

IEC\_

The impact on the Salmo area population will be minimal since most employees will be recruited locally and will commute to work rather than relocate. Moreover, the scale of the operation is small so that the number of people possibly migrating to the area as a result of the mill will not be significant. There will be minimal impacts to community facilities and services in Salmo since most are not operating at full capacity.

### 6.2.3 Summary

David Minerals' H.B. Mill Reactivation Project is expected to create positive impacts on the local, regional and provincial economies. Its taxes will also contribute to the provincial and federal government revenues. In 1981, property taxes for the H.B. property were \$45,000.

David Minerals Ltd. is currently spending about \$115,000 to \$120,000 per month on payroll and equipment/supply purchases (\$95,000 and \$26,000-25,000 respectively).

IEC

When all three phases of the reactivation project are completed, it is estimated that operating costs will increase to approximately \$190,000 to \$200,000 per month with \$120,000 allocated to payroll and \$70,000-80,000 to equipment/supplies.

The number of jobs created by the mill reactivation, when all phases are complete, will be approximately 20-25. Twelve additional shift workers will be needed to keep the mill operating on a 24-hour per day basis, 6-8 people will be needed for clean-up and maintenance operations, while approximately 3-5 additional professional staff will be required. Five non-basic jobs are expected to generated in the Nelson-Salmo area as a result of the mill operations.

The project is expected to have minimal disruptive impacts on the Salmo community since the scale of the project is small and the communities in the immediate area have adequate facilities and services to accomodate any increased use by mill workers.

3089.5

## 7.0 REFERENCES

IEC.

- Canada Land Inventory. 1979, Land Capability Sector Maps for Salmo Area for Agriculture, Forestry, Recreation, Ungulates, Waterfowl and Present Land Use. Environmental Land Use Committee.
- Cowan, I.M. and C.J. Guiguet. 1978. The Mammals of British Columbia. British Columbia Provincial Museum Handbook No. 11: 414 p.
- Dykeman, F. 1982. Director of Planning, Regional District of Central Kootenay, pers. comm.
- Fisheries and Environment Canada. 1977. Historical Streamflow Summary, British Columbia. Inland Water Directorate, Water Resources Branch, Water Survey of Canada, 758 p.
- Forest Cover Map: Salmo PSYU. 1962. Survey Division B.C. Forest Service, Victoria, B.C.
- Gardiner R.T. 1974. Mined-Land Reclamation at Cominco Ltd., HB Operations Progress Report 1973. Submitted to Senior Inspector of Mines – Reclamation, Dept. of Energy, Mines and Petroleum Resources, Victoria, 10 p.
- Gardiner R.T. and J.E. Stathers. 1975. Mined-Land Reclamation at Cominco Ltd., HB
   Operations, Progress Report 1974. Submitted to Senior Inspector of Mines
   Reclamation, Dept. of Energy, Mines and Petroleum Resources, Victoria. 2 p.
- Holland, S.S. 1976. Landforms of British Columbia A Physiographic Outline. Dept. of Energy, Mines and Petroleum Resources Bulletin 48: 138 p.
- Jungen, J.R. 1980. Soil Resources of the Nelson Map Area (82 F) RAB Bulletin 20 Report No. 28 British Columbia Soil Survey, 217 p.

3089.5

Krajina, V.J. 1969. Ecology of Forest Trees in British Columbia. Ecology of Western North America 2(1): 1-146.

- Little H.W. 1950. Salmo Map-Area, British Columbia (Summary Account): Geological Survey, Canada, Paper 50-19.
- Rusnell, D.K. and R.T. Gardiner. 1980. Annual Reclamation Report for 1979 and Proposed Program for 1980, Cominco Ltd., H.B. Mine. Submitted to Senior Reclamation Inspector, Ministry of Energy, Mines and Petroleum Resources, Victoria, B.C. 8 p.
  - . 1981. Annual Reclamation Report for 1980 and Proposed Program for 1981, Cominco Ltd., H.B. Mine. Submitted to Senior Reclamation Inspector, Ministry of Energy, Mines and Petroleum Resources, Victoria, B.C. 7 p.

. 1982. Annual Reclamation Report for 1981, Cominco HB Operations Submitted to Senior Inspection of Mines, Reclamation, Dept. of Energy, Mines and Petroleum Resources, Parliament Bldg., Victoria, B.C., 8 p.

Russell, H. 1982. Municipal Clerk, Village of Salmo, pers. comm.

Sabiskoss, A. 1982. Manager, Canada Manpower, Nelson, pers. comm.

- Scott, W.B. and E.J. Crossman. 1973. Freshwater Fishes of Canada Fisheries Resources Board, Canada Bulletin 184, 966 p.
- Stathers, J.E. and R.T. Gardiner. 1976. Mined-Land Reclamation at Cominco Ltd., HB Operations, Progress Report 1975. Submitted to Senior Inspector of Mines - Reclamation, Dept. of Energy, Mines and Petroleum Resources, Victoria. 4 p.
  - . 1977. Mined-Land Reclamation at Cominco Ltd., HB Operations, Progress Report 1976. Submitted to Senior Inspector of Mines - Reclamation, Dept. of Mine and Petroleum Resources, Victoria. 6 p.

3089.5

IEC.

- IEC
  - \_. 1978. Mined-Land Reclamation at Cominco Ltd., HB Operations. Progress Report 1977. Submitted to Senior Reclamation Inspector, Ministry of Energy, Mines and Petroleum Resources, Victoria, B.C. 4 p.
- . 1979. Mined-Land Reclamation at Cominco Ltd. HB Operations. Progress Report 1977. Submitted to Senior Reclamation Inspector, Ministry of Energy, Mines and Petroleum Resources, Victoria, B.C. 10 p.
- Walker, J.F. 1934. Geology and Mineral Deposits of the Salmo Map-Area. British Columbia, Geological Survey Canada Mem. 172.
- Warning, G.F. 1960. Geology of the HB Mine. The Canadian Mining and Metallurgical Bulletin October 1960 p.
- Woods, G. 1982. Local Biologist, Fish and Wildlife Branch, Nelson Ministry of Environment, pers. comm.



APPENDIX A

Common and Scientific Names of the Vegetations Found in the HB Mine Site.

IEC

Appendix A Vegetations found in the HB Mine

### Common Name

Quaking aspen Black cottonwood Lodgepale pine Western white pine Ponderosa pine Douglas fir Paper birch Dogwood Western larch

Rose Snowberry


Red top Alsike clover Red clover Sweet clover Timothy Blue bunch wheatgrass Field horsetail Birdfoot trefoil Canada blue grass Creeping red fescue Tall fescue


## Scientific Name

Populus tremuloides Populus trichocarpa Pinus contorta Pinus monticola Pinus ponderosa Pseudotsuga menziesii Betula papyrifera Cornus stolonifera Larix occidentalis

Rosaceae Sympharicarpus albus

Agrostis alba Trifolium hybridum Trifolium incarnatum Trifolium melilotus alba Phleum pratense Agropyron spicatun Equisetuin telmateia Lotus corniculotus Poa compressa Festuca rutna Festuca arundinacea





#### A. Crushing Plant - (Cont'd)

The jaw crusher is a Traylor Blake type  $30^{\circ\prime} \times 42^{\circ\prime\prime}$  unit which has been in existence since 1914. It came to H.8. from Pinchi Lake where It was used in the first operation of that mine. The drive for the crusher is a 150 H.P. 2300 V. SED RPH motor through a set of Il V-beits to the main shaft sheave of the crusher. The set of the crusher is 6" close side.

- 2 -

Ore is discharged to #1 conveyor belt, a 36" belt and from there, over a tyrock 5" x 10" double deck screen. The top deck is punch plate 23" diameter holes and the lower deck is woven wire. Passing size is 1". Average from both decks is fed to a 1260 C.A.C. hydrocone crusher with the close side set at 3/4". Hydrocone drive is a 150 H.P. 2300 V, 900 R.P.H. motor to a V-belt drive. A flow switch prevents hydrocone start-op unless cooling water is flowing.

Screen undersize and hydrocone discharge are then joined on #Z belt, a 30" belt inclined at 19 $\frac{1}{2}$ . This belt goes to the top of the west fine ore bin.

A chute over the west F.0.8. can be used to direct muck directly to the west bin (under the head pulley of  $\ell/2$  belt) or via a cross conveyor ( $\ell/3$  belt) to the east bin. The F.0.8.'s are constructed of laminated  $2^{\prime\prime} = \{0^{\prime\prime}, 2^{\prime\prime} \times \delta^{\prime\prime}$  and  $2^{\prime\prime} \times \delta^{\prime\prime}$  with 1" sheathing on the inside face. Design capacity of all bins was 1,000 tons each, but dead space limits coarse ore capacity to approximately 500 tons and fine ore storage to approximately 550 tons per bin.

Controls for all equipment except the jaw crusher and cone crusher are located at the operator's pedestal located on the west side of Al conveyor. There is an emergency stop button for the hydrocone here as well-Controls for the jaw crusher are located on the west wall of the plant and for the hydrocone are at the south wall. There are also local controls for the air operated are gate and the hydraulic lift gate located above the jaw crusher.

An electrical interlock system exists between  $\frac{1}{2}$  conveyor, the screen and  $\frac{1}{2}$  conveyor. The jaw crusher has thermocouples installed to monitor temperatures of critical bearing areas and a chart recorder is located on the sait wall close to the operator's predestal to record these temperatures. An alarm is set at 45° C and will also activate a scam alarm in the concentrator. Power meters are also installed on the jaw, the bydrocome and  $\frac{1}{2}$  conveyor.

Plant throughput is designed at 200 tons per hour and this figure is easily attained unless muck conditions are particularly difficult – i.e.large muck requiring some blasting. Plant operation is one shift per day to fulfil milling requirements. There have been two operators in this plant from start-up but it is likely that one main is sufficient if the shift boss is available to help this man when blasting. Plant operation it scheduled in conjunction with tramming due to the coarse ore storage limitations.

in-plant dust is adequately controlled by a 10,000 C.F.H. services fan pulling air through a dust cyclone from under the crushers. The cyclone is a wet operation with underflow travelling by gravity to the classifier in the concentrator.

The plant Is serviced with a 10-ton capacity overhead trolley crane.

Operating problems arise when either very wet fine muck or very coarse muck is supplied to the cruthing plant. Feed control is inadequate to handle wet sloppy muck which leads to overloading of the conveyor belts (particularly #2). Coarse muck leads to blasting in the feed chute to the jaw crusher.

Continued . . . -

#### 8. Concentrator

IEC.

From the fine ore bins, muck is fed to the rod mill. Each bin is equipped with four chutes and four Hardinge type "C" constant weight feeders. The feeders under the east bin are driven through variable speed drives while those under the west bin are fixed speed.

-3-

Generally speaking ore is fed from one bin at a time. One  $24^{\prime\prime\prime}$  belt takes feed from under the west fine ore bin to the rod mill. Two  $18^{\prime\prime\prime}$  conveyors (No.5 and No.6) take feed from the east bin to #4 belt. There is no weightometer on these conveyors. Tonnage checks are carried out based on a two foot belt cut on #4 conveyor.

#### 8-1 Grinding Circuit

The main features of the grinding circuit are the 7'  $\times$  12' Dominion rod mill, the 66" Wemco Duplex spiral classifier and the 8'  $\times$  12' C.A.C. ball mill.

The rod mill requires a drum feeder in this installation. The feeder presently installed was overhauled in 1978 and was put into service on June 14, 1978. The mill is powered by a C.G.E. 300 H.P. 705 R.P.H. 2300 volt motor through a speed reducer with a ratio of 2.15 to 1. Hill speed is 24.0 R.P.M. or 83.6% of critical. All liners are NI-hard iron and can be cast in Trail Central Shops.

Hill discharge flows by gravity to the Vemco classifier. This unit is a duplex spiral with each spiral being 66" diameter by 33' 9" long. Usar shoes are cast iron and are also a Trail Central Shops item. Each spiral requires t14 shoes. Drive is supplied by a C.G.E. 15 H.P. motor through a 70:1 speed reducer. Speed of the spirals is 4 R.P.H.

Sands discharge from the classifier is laundered to the ball mill through a 54" scoop feeder. The ball mill is a 8" x 12" C.A.C. unit equipped with Ni Mard liners.

The ball mill drive is from a 400 H.P., 720 H.P.H., 2300 Valt C.G.E. motor through a V-belt drive. Hill speed is 22.7 R.P.H. which is 82.9% of critical.

Hill discharge is returned to the classifier by means of a discharge elevator scoop.

Classifier overflow flows via gravity to the talc machine in the flotation section.

The controlling factors in the grinding circult are densities in the mills and on the classifier overflow which are as follows:

Rod Hill Discharge	75% Solids
Ball Hill Discharge	72% Solids
Classifler Overflow	45% Sollds

Water is added at the following points.

Rod	8111	•	11)	Feed Discharge	

Ball Hill - 1) Feed Launder (1) Discharge Launder

Continued . . . .

Page 557 EGM-2013-00163 - 4 -

#### 8-1 Grinding Circult - (Cont'd)

Steel consumption in the mills is as follows:

Rod Hill 31" dla. x 11' Rods - 1977 Consumption - 0.217 #/T 1978 Consumption - 0.237 #/T

Ball Hill 2" dia, Balls - 1977 Consumption - 0.311 #/T 1978 Consumption - 0.380 #/T

Rods are usually charged weekly (6 Rods/Vk.) and balls are charged every two days (300 #/Charge).

8-11 Flotation

The sequence of flotation is a single stage talk flost followed by a lead roughing and a tink roughing float. The lead and tink rougher concentrates are each then cleaned twice before the final concentrates are sent on to thickening and flitering.

Hachine sizes are as follows and all are Denver units.

Float	No, of Banks	Size	No. of Cells
Tate	1	30's (100 c.f.)	в
Pb Achr,	2	24's (50 c.f.)	20
Fb Clean/Reclean	1	18 Specials	6
In Rohr	1	30's (100 c.F.)	12
In Clean/Reclean	1	30's (100 c.f.)	8

Supercharged air is supplied from a fan type blower rated at 1350 c.f.m.  $\emptyset$  12 ozs. pressure. This unit is located in the basement under the lead rougher teils.

The taic concentrate can either be combined with the lead concentrate at the thickener underflow stage or may be directed to talls as necessary. The taic talls pass through a splitter box to two banks of lead rougher cells. Lead rougher concentrate passes through a 2 x 2 S.R.L. pump to the claner/recleaner mathine. Cleaner talls join the taic talls as feed to the roughers. Lead rougher tails flow by gravity to the 8' x 8' Denver wood stave zinc conditioner and then on to the one bank of zinc rougher.

Zinc rougher concentrate is laundered to a splitter sump where a portion is split to the two regrind cyclones which are  $\delta^{\prime\prime}$  diameter Dorrclones. Overflow is carried back to the second side of the splitter box and then pumped via 1-1/4" Wifter pump to the cleaner/recleaner machine. Cyclone underflow is fed to the 5' x 10' C.A.C. regrind mill.

The regrind mill is driven from a 125 H.P. 1800 H.P.H., 2300 Volt English electric motor through a Farrell speed reducer with a ratio of 4,58:1. Final mill speed it 31 H.P.H., which is 88% of critical, Liners are all Hi-hard iron and can be fabricated in Trail Central Shops. Grinding media are 1-1/4" diameter balls and these are charged every second day in 200 Ib, lots Ball consumption is as follows:

1977 Consumption - .057 #/1.

1978 Consumption - .087 #/1.

Regrind discharge is pumped back to rejoin the cyclone overflow at the splitter box and on to the cleaner/recleaner machine.

The cleaner/recleaner machine can be set up to have any humber from one to five cells on recleaning service. Yalls from shis machine are recycled by gravity to the zinc conditioner.

Continued . . . .

8-11 Flotation - (Cont'd)

Reagents used in flotation are as follows:

	Consumption			
Respect	1977 W/T	1978 W/T		
Sadium Cyanide H.I.B.C. Frother Sadium Isopropil Xanthate Lime Dowfroth 250 Copper Sulphate	.052 .022 .305 .882 .057 .295	.052 .021 .255 .941 .062 .301		

- 5 +

Flotation control is achieved by density checks, monitoring of pH's in the circuits, quick assays and reagent addition. Density checks are made on the zinc cleaner feed and the zinc cleaner tails to ensure that this machine is being pulled correctly. Alkalinity of the lead cleaner and the zinc cleaners are checked to control from content in the concentrates. There is an automatic line addition made to the zinc cleaner feed based on a continuous monitoring probe in the cleaner machine. Other checks are performed manually and the time addition is reset using per cent of cycle timers, iron assays are carried out three times a shift on the final concentrates and a zinc colorimetric assay is made on the same frequency on the zinc raugher tails. Based on the above input, the operator can then make any required changes in reagent addition to the circuits.

Samples of classifier overflow, talc concentrate, lead rougher feed, lead recleaner concentrate, lead final concentrate, zine final concentrate, zine rougher tails and final talls are taken every two hours and are used to produce the daily assay report and the final daily metallurgy. Only the lead recleaner concentrate, the zine final concentrate and the final talls are reported on e shift basis. All other samples are combined to a 24 hour sample. Classifier overflow and final talls are to zuroted only calisher Auto-Samples every half hour. All other samples are cut manually every two hours.

Mechanically, the flotation circuit is quite flexible. The taic circuit can be bypassed for maintenance purposes. The lead roughing circuit can be cut to half production with one bank of cells down for maintenance. The tinc regrind circuit can be bypassed and when in operation, flows to the regrind circuit can be yarled at the splitter sump. Cleaning and recleaning capacity for both lead and time can be varied according to the conditions by adding or subtracting trays on the lip of the machines.

Vater addition to the flocation circuit is made as spray water in the concentrate launders and in some pump sumps.

#### 8-111 Thickening - Filtering and Concentrate Load Dut

Lead recleaner concentrate flows by gravity to a 15' x B' Dorrco (hickener which has a relatively high rake speed of I revolution every 45 seconds. The reason for this speed is to prevent excessive settling. The drive is a 1.5 H.9. 1800 R.P.M. C.C.E. gear motor with a '4.13 ratio. (hrough a chain drive. Lead thickener underflow at 40% tollds combines with the tale concentrate at the sump to the 1" Wilfley thickener underflow pump.

The combined flow travels to the Oliver 2 Disc American filter which produces concentrate at approximately 12-15% moisture.

Lead thickener overflow goes directly to the tallings disposel system and as a result of some noticeable losses of lead in this overflow, Separan was added on a trial basis with notly moderate success. No filter als have been tried on this circuit.

Continued . . . .

- 6 -

8-111 Thickening - filtering and Concentrate Load Out (Cont'd)

Zinc concentrate flows by gravity to a 30'  $\pm$  8' Dorr thickener with a rake speed of 1 revolution every 1-3/4 minutes. A 1" Wilfley pump delivers thickener underflow at 60% solids to a 6' diameter  $\pm$  6 disc Diiver American Filter which produces final concentrate at a molsture content of 10-11%. Aerodri 100 was being added to the filter feed but due to frothing problems on the tailings launder system which were thought to be partially associated with this reagent, it was discontinued and Separam was added to the thickener instead. The Separa addition was also to minimize thickener overflow losses of zinc as this overflow also was being system.

Vacuum to both filters is supplied from either of two 22" x 9" C.I.R. vacuum pungs located in the mill basement. A Roots Connerville No.67 A.F. rotary blower supplies blow air at ISO c.f.m. at S psi. The filtrate is handled by a 1-14" Oliver filtrate punp.

Dried concentrate is stored in two bins directly under the filter Boots and is loaded into trucks with a #50-D Hough payloader equipped with a 1-1/3 cu. yd, buckst.

Filter bags which were cotton have been changed in the last year to a nylon Neotex fabric made by Porrits and Spencer Ltd, as the cotton bag life was very poor. An improvement was notleed with the Neotex bag as usage dropped from an average 52 bags per month in 1977 down to 27 bags per month in 1978.

Personnel required to operate the entire concentrator are as follows for a seven day per week, 24 hour a day operation.

- 4 Hill Shift Bosses
- 4 Bill Operators
- 4 Utility Operators
- 1 Crushing Operators

In general the mill operator is occupied with the flotation circuit while the utility man controls the grinding circuit and carries out any required clean-oup duties. The utility operator can also fill in at required in the crushing plant should an operator be off sick. In this case the mill shift boss would control the flotation circuit and the mill operator operates the grinding circuit.

8-111-a Assay Lab.

There is a fully equipped bucking room and assay lab. located on the west side of the mill building. The assay lab. Is equipped to carry out analysis of mill samples using a wet chemical method. At the time of shurdown an Atomic Adsorption Unit was included in the lab. equipment but It was in bad working order and would require major repairs before use. There is also a smell testing lab. next to the assay lab. This area la equiped with bench style flotation machines, a filter press and ball mill. The equipment in this lab. Is to remain at the H.B. property while all assay supplies are to be shipped out as required at other properties (particularly trail Analytical Services).

This area of the operation employed a full time Bucker-Assayer and a (vi) time Staff Assayer, it was found that the routine daily assay run was all that could be accomplished in the lab, due to lack of hot plate prace and to lack of time. The method of analysis used was only suitable for lead, finc and iron assay. If the property is reopened, some consideration should be given to purchasing an A.A. unit or to fix the one presently in the lab, in order to make this area more adaptable.

Continued . . . .

#### 8-14 Tailings Disposal

IEC

Mill tailings during Phase I would be produced in the order of 500 tons per day when the mill is actually operating. A continuous program of operation is not anticipated until an adequate economic supply is forthcoming, possibly in Phase III when ores from the Rossland properties become available. The tailings product would leave the mill at 35% to 40% solids and travel through a Sclair piperline in the form of a U from one side of the Sheep Creek Valley to the bank on the other side. Also, at this point, the excess mine drainage water which is carried through a 6-inch diameter steel pipefrom the mine portal, enters the disposal system and the flow is then carried some 4,000 yards to the tailings impoundment area in an 8-inch diameter high density polyethylene pipe (Driscopipe, Series 1500).


- 7 -

As stated in the report by Klohn Leonoff, dated November 1981, Exhibit 'C' states that "the existing tailings structure has a capacity of approximately 790,000 tons."

Present plans for treatment of ores at the HB Hill are as follows:

1982	(first half)	35,000	tons
1982	(second half)	126,000	tons
1983	A CONTRACTOR OF A CONTRACT	252,000	tons
1984		252,000	tons
1985	(first half)	126,000	tons

It is evident that no major addition to the tailings facilities will be required until mid 1985 but, depending on company production and availability of ores for custom milling, no substantial modifications will commence, subject to your prior approval, before mid 1984.



DAVID MINERALS LTD.

IEC

# Tailings Disposal Scheme

HB Mill, Salmo, B.C.



Page 563 EGM-2013-00163

PROJECT:	HB Mill Tailings Disposal Scheme
LOCATION:	Salmo, B.C.
CLIENT:	David Minerals Ltd.
OUR FILE:	VA 2869 November 27, 1981

IEC\_

November 27, 1981

VA 2869

IEC.

-

2

## TABLE OF CONTENTS

PAGE

1.	INTRODUCTION AND SUMMARY	1
2.	DESCRIPTION OF EXISTING TAILINGS POND AND DAM	3
	2.1 Cominco's Operating History	3
	2.2 Geotechnical Aspects of Dam Construction	4
	2.3 Spillway	6
з.	TAILINGS DISPOSAL SITE	0
	3.1 Hydrological Setting	6
4.	TAILINGS DISPOSAL SCHEME	7
	4.1 Existing Capacity of the Pond	7
	4.2 Tailings Dam Raising	8
	4.3 Water Balance	8
	4.4 Permanent Spillway	9
5.	CONCLUSIONS AND RECOMMENDATIONS	9
	5.1 CODCIUSIONS	9
	5.2 Recommendations	9

## APPENDIX

I - LOGS OF BOREHOLES DRILLED BY GOLDER ASSOCIATES IN 1973

## LIST OF DRAWINGS

A-2869-1	÷.	SITE LOCATION
B-2869-2	÷.	LOCATION OF TAILINGS DISPOSAL POND
B-2869-3	-	PLAN OF EXISTING TAILINGS POND
D-2869-4	14	PLAN AND SECTION OF EXISTING DAM
B-2869-5	-	SCHEMATIC PROFILE OF TAILINGS POND
B-2869-6	1.57	STABILITY ANALYSIS OF DAM
A-2869-7	-	WATER BALANCE

November 27, 1981

#### INTRODUCTION AND SUMMARY

Klohn Leonoff Ltd. was requested by David Minerals Ltd. to investigate the feasibility of using the existing tailings pond at the HB Mill for the deposition of about one million tons of tailings. This report has been prepared for submission to the Nelson Branch of the B.C. Ministry of Energy, Mines and Petroleum Resources so that a permit can be obtained by David Minerals to operate the pond.

The HB Tailings Dam is located approximately four miles south of Salmo, B.C. (Drawings A-2869-1 and B-2869-2). The dam was originally built by Cominco in 1955 using a timber crib over which borrow materials from the west end of the pond were placed. The dam was raised in this manner to a height of about 40 ft. In 1964, a portion of the timber crib failed and moved about 10 to 15 ft. Drains were placed and toe protection was provided to stabilize the failure. Construction of the dam raising continued by the downstream method until operations were suspended in 1967. We understand that there was no independent geotechnical control of dam construction until 1973. In 1973, Golder Associates drilled three holes, one in the crest and two in the downstream portion of the dam. They encountered relatively soft material (as low as four blows per foot) in two holes. They recommended measures to reduce the phreatic surface within the dam, which were implemented. Subsequently, Golder Associates supervised the construction of dam raisings in 1975 and 1977. The operations at the HB Mill were suspended by Cominco in 1978.

The tailings dam is located at the southern end of a valley and has been constructed about 75 to 80 ft high using borrow materials. The tailings were deposited at the back of the pond, about 2900 ft from the crest of the dam and clarified water ponded against the upstream face of the dam (Drawing B-2869-3). Initially, two timber

VA 2869

VA 2869

40.8

November 27, 1981

decant towers were used in conjunction with two 24-inch diameter steel pipes to pass water from the upstream to the downstream side of the dam. In 1977, these decant towers were filled with concrete and replaced with a new spillway and drop manbole arrangement (Drawing D-2869-4).

Dr. Rajaram of Klohn Leonoff visited the damsite on September 23, 1981. Discussions were held with Mr. Newman of Cominco Engineering to obtain details of the tailings dam operation during the period 1955 to 1978. A profile of the tailings pond from the tailings flume to the dam crest was obtained from Mr. Newman and from Mr. Girdler of David Minerals. A schematic profile of the tailings pond is presented in Drawing B-2869-5. Assuming that tailings will be deposited uniformly on the existing tailings surface, a curve relating tons of tailings to elevation was developed. Approximately 790,000 tons of tailings can be deposited in the existing pond and dam. The dam will have to be raised by about 6 ft before the anticipated one million tons of tailings are deposited.

Klohn Leonoff will assess the condition of the existing dam by conducting a program of field investigation and laboratory analysis. Based on the results of this investigation, specifications for the dam raising will be provided.

The hydrology of the site was briefly analyzed to determine the water balance in the pond. It was concluded that the present spillway, which we understand is designed for a peak flow of 80 cu ft per second, is adequate to handle the runoff from a 200 year flood.

A seismic risk analysis of the site indicated that the acceleration amplitude with return periods of 100 years is 0.015 g (1.5 percent gravity). Since this figure indicates that the site has very low seismic risk, a static stability analysis was performed. The 2.

2.1

VA 2869

November 27, 1981

analysis indicates that the dam has a minimum factor of safety against a shearing type failure of 1.7.

- 3 -

This report details the condition of the existing dam and describes the physical and hydrologic setting of the tailings pond, the tailings disposal scheme, and final abandonment of the pond.

#### DESCRIPTION OF EXISTING TAILINGS POND AND DAM

The existing tailings pond is located approximately four miles south of Salmo, B.C. A plan of the pond area showing the contours of the tailings surface is presented on Drawing B-2869-3. The tailings dam is located at the southern end of a valley and has been constructed about 75 to 80 ft high using borrow material obtained from the abutment slopes. The dam is about 800 ft long and the pond occupies an area of about 67 acres. A plan and section through the dam are presented on Drawing D-2869-4.

#### Cominco's Operating History

Cominco operated the tailings pond during the period 1955 through 1978. The tailings pond was used during 1955 through 1967, and subsequently during the period 1974 through 1978. The crest of the dam was raised periodically during these years to accommodate the increasing volumes of tailings. These dam raisings were performed using the downstream method of construction, i.e., additional fill was placed on the crest and the downstream slope of the dam. It is our understanding that the dam construction during the years 1955 through 1967 was not performed under independent geotechnical control.

When the dam was initially constructed in 1955, a timber crib structure was used. This crib was covered with borrow material obtained from the west end of the pond. The dam was raised in this manner to a height of about 40 ft. In 1964, a portion of the

Se!

2.2

#### VA 2869

- 4 -

November 27, 1981

timber crib failed and moved about 10 to 15 ft. Drains were placed and toe protection was provided to stabilize this failure. Construction of the dam raising continued by the downstream method until operations were suspended in 1967.

Before Cominco re-opened the HB Mill in 1974, Golder Associates investigated the stability of the tailings dam in 1972 and 1973. They drilled three holes, one on the crest and two on the downstream portion of the dam. They encountered soft materials (as low as four blows per foot) in two of the three holes. They recommended that a filter blanket be placed on the downstream slope of the dam to reduce the phreatic surface and improve dam stability. This was implemented in 1974. Two subsequent dam raisings in 1975 and 1977 were supervised by Golder Associates (personal communication, Newman, 1981). Cominco has been monitoring the water levels in the dam since the installation of piezometers in 1973. These observations indicate that the phreatic surface within the dam has not changed since Cominco shut down their operation in 1978.

#### Geotechnical Aspects of Dam Construction

Cominco re-opened the HB Mine and Mill in 1973. In 1972 and 1973, Golder Associates of Vancouver investigated the stability of the tailings dam. In 1973, three boreholes were drilled to depths varying from 45 to 85 ft and extended approximately 20 ft into bedrock. One borehole was drilled from the crest and two boreholes from the downstream slope of the existing tailings dam. Logs of the boreholes obtained by Golder Associates are presented in Appendix I. Samples were obtained for laboratory testing, and perforated plastic standpipes were installed in the boreholes to monitor groundwater levels. A plan and section of the dam, showing the location of these boreholes, is presented on Drawing D-2869-4.

> Page 569 EGM-2013-00163

VA 2869

IEC.

A review of Golder Associates reports dated June 1972 and January 1974, and discussions with Mr. Newman of Cominco reveal the following about the tailings dam:

 The dam is generally comprised of brown sandy silt containing varying amounts of medium to coarse sand and fine gravel.

- 5 -

- There are zones of soft material in the fills placed before 1967 (as low as four blows per foot).
- A timber crib was used during the initial construction of the dam, and a portion of this crib failed in 1964 and moved about 10 to 15 ft.
- The foundation material under the fill consists of bedrock overlain by 6 to 8 ft of dense silty till with minor amounts of sand and gravel.
- The fill material has an angle of internal friction of approximately 35 1/2 degrees with zero cohesion, as determined by Golder Associates' laboratory tests.
- The factor of safety against a shearing type failure is of the order of 1.3. Since this analysis was completed by Golder Associates in 1973, the phreatic surface has been lowered and so the present factor of safety is considered to be greater than this figure.
- The dam has adequate protection against surface erosion.

Golder Associates recommended that if the ponded water level is raised, the dam should be raised using a filter blanket to maintain the phreatic surface below the level of the existing downstream fill slope. The specifications for the 1975 and 1977 dam raisings were prepared by Cominco on the basis of the Golder reports, and we VA 2869

6 -

November 27, 1981

understand that the construction was supervised by Golder Associates. A review of the piezometer readings through July 1981 indicates that the phreatic surface has been relatively constant, since Cominco shut down in 1978.

#### 2.3 Spillway

Prior to 1977, two timber decant towers were used in conjunction with two 24-inch diameter steel pipes to pass water from the upstream to the downstream side of the dam. Due to operating and maintenance problems with this system, Cominco filled these structures with concrete and installed a new spillway and drop manhole structure (Drawing D-2869-4). This structure is equipped with a 36-inch diameter steel pipe, and we understand was designed to pass a maximum flow of 80 cu ft per second (35,900 USGPM).

#### TAILINGS DISPOSAL SITE

The tailings disposal area is situated in a natural basin covering about 67 acres in the Salmo Provincial Forest. It is to the east of Provincial Highway 3 and the Salmo River, about four miles south of Salmo, B.C. (Drawing B-2869-2). To the east and west of the pond are heavily treed slopes consisting of B0 to 90% of evergreens. The dam is situated at the southern end of the basin.

#### 3.1 Hydrological Setting

Dr. McCreath of Klohn Leonoff, obtained data on snowcourse, streamflow, and precipitation from measuring stations at Creston, Nelson, Trail, and Edgren Creek. From analysis of the data, the average annual precipitation at the site is 31.5 inches, and the average annual evaporation is 16.7 inches. The average annual runoff from a catchment area of about 445 acres to the east of the tailings pond is about 14.5 inches. The water balance for the pond was calculated using these estimates for precipitation, evaporation, and runoff. IEC.

4.1

VA 2869

November 27, 1981

The peak 200 year flood inflow into the pond is estimated to be in the order of 120 to 150 cu ft per second (cfs). About 30 to 50% of this inflow can be temporarily stored in the pond since a flood surcharge of 2 ft has been assumed in computing the volume-elevation curve. Thus, the existing spillway, which we understand has been designed for a discharge of 80 cfs, can handle the 200 year flood estimated for the site.

- 7 -

#### TAILINGS DISPOSAL SCHEME 4.

## Existing Capacity of the Pond

The tailings pond has been operated since 1955 with the tailings being deposited at the upstream end of the tailings pond and the dam being raised as necessary by the downstream method of construction using borrow materials. Klohn Leonoff recommends that this method of tailings disposal be continued by David Minerals Ltd. In an effort to estimate the present capacity of the tailings pond, and the extent of dam raising necessary to store the anticipated 1,000,000 tons of tailings, a curve relating the tons of tailings to the elevation of the dam crest was developed (Drawing B-2869-5).

 $\lambda$  schematic profile of the existing tailings surface is presented on Drawing B-2869-5. The water level in the pond is 5 ft below the dam crest, and the depth of the ponded water on the upstream side of the dam is 9 ft. The tailings should be discharged in layers over the existing tailings surface. In June 1984, after about 790,000 tons of tailings have been deposited, the ponded water capacity and flood surcharge provision will be reduced to a minimum. At that point, the dam will have to be raised by about 6 ft before additional tailings can be deposited. During operation of the tailings pond, the elevations of the tailings should be monitored to ensure that the schematic profile presented on Drawing B-2869-5 is maintained. The depth from the creat of the slimes

IEC\_\_\_\_

November 27, 1981

surface on the upstream side of the dam should be maintained as depicted in the tons of tailings versus elevation curve.

- .8 -

#### 4.2 Tailings Dam Raising

VA 2869

The tons of tailings versus elevation curve indicates that the dam crest has to be raised prior to June 1984. Klohn Leonoff recommends that before the dam raising is undertaken, a program of field investigation should be conducted to assess the condition of the upstream portion of the dam. The upstream portion of the dam contains some soft zones, and also has a timber crib buried within it.

During the 1982 field season, two to three boreholes should be drilled to assess the condition of the upstream side. Soil samples should be obtained for conducting laboratory tests. Based on the results of the field and laboratory testing program, Klohn Leonoff will develop detailed specifications for the dam raising.

A stability analysis of the dam was performed using the parameters presented in Drawing B-2869-6. A preliminary profile of the dam raised by 6 ft was used to perform the analysis. A seismic risk analysis of the site indicated that the acceleration amplitude with return periods of 100 years is 0.015 g (1.5% gravity). Since this represents a very low seismic risk, a static stability analysis was performed. The minimum factor of safety for the dam was found to be 1.7.

4.3 Water Balance

Ret

The hydrological data given in Section 3.1 of this report was utilized to compute the water balance for the tailings pond (Drawing A-2869-7). Using a production rate of 900 tons per day, a tailings pulp density of 30%, and no recycling of the water, the tailings VA 2869

IEC.

November 27, 1981

transport water required is 350 USGPM. Of this amount about 50 USGPM remains within the voids of the tailings. The runoff and precipitation into the pond is estimated to be 335 USGPM. Assuming that 40 USGPM are lost due to evaporation and seepage, the average amount of daily flow out of the spillway is 595 USGPM. This represents an average dilution factor of about two for the tailings water. During periods of heavy runoff and precipitation, this factor could be much higher.

## 4.4 Permanent Spillway

On final abandonment of the pond, a permanent spillway should be constructed at the east abutment of the dam. This should be an open-channel spillway which will safely pass flood water from the upstream to the downstream side of the dam. The design of this spillway is beyond the scope of the present study.

## CONCLUSIONS AND RECOMMENDATIONS

#### 5.1 Conclusions

5.

2

- The existing tailings dam has a capacity of approximately 790,000 tons.
- The tailings should be discharged from the northern end of the pond, in layers over the 'existing tailings surface. The depth from the crest of the slimes surface on the upstream side of the dam should be maintained at a minimum of about 8 ft.
  - The dam crest should be raised by about 6 ft during the 1983 field season to accommodate the anticipated one million tons of tailings.

#### 5.2 Recommendations

 The condition of the existing dam, especially the upstream portion, should be investigated during the 1982 field season. Based on this investigation, plans and specifications for the 1983 dam raising should be prepared. VA 2869

IEC

- 10 -

November 27, 1981

 Piezometric levels in the dam should be monitored on a monthly basis.

3. The tailings surface elevation should be monitored to ensure that the schematic profile presented in this report is maintained. Any significant variations in this profile will affect the tailings storage capacity.

KLOHN LEONOFF LTD.

Regnam

V. RAJARAM, Ph.D., P.E. Senior Division Engineer

MARK T. OLSEN, P.Eng. Staff Consultant

VR/MTO/jas

2.90

## APPENDIX I

IEC

;16**\*** 

LOGS OF BOREHOLES DRILLED BY GOLDER ASSOCIATES IN 1973

Page 576 EGM-2013-00163

	-	•	
-	Ľ١	. نا	

RECORD OF BOREHOLE 2

PROJECT NO ....

IOCATION STE FIGHT / DORING DATE NOVEMBER 1, 1973 DATUM TONEN FROM COMMICO DRIMMING NO HO ZOS P BOREHOLE TYPE ROTARY TRICONE BOREHOLE DUMETER & M SAMALER HAUMER WEIGHT //O LE DROP 30 INCHES PEN. TEST HAUMER WEIGHT LE DROP INCHES

_	SOIL PROFILE	-	SA	HPL	25	SCALE	DYNAMIC PENCERATION RESISTANCE	CH. / SEC	14	1.1
	RESCRIPTION	STRAT PLOT	H JOHON	1445	BLOWS/FT.	ELEVATION S	SHEAR STRENGTH C., LB /SO.FT	WATER CONTENT, PERCENT	ADDITIONAL LAB. TESTING	STANOPIPE INSTALLATION
-	CA SURFACE.	_			1					hl
						1110	-			· .
	SOFTENDUN		-							WE 55' NOV 25,1973
	SANDY SILT WITH MED. 1 LOARSE SAND 1			00						-
	GRAVEL TO IS OW OF TEN TILL LIKE		3	; o a	4	1150.				
			4	100	-					
2		_	3	** 00	70	24.40				
	WOOD SOFT TO FIRM STRATIFIED BROWN Y GREY SILT WITH OCC. GRAVEL TO IN DA		6	* 00						1
000	SAND I GRAVEL					2430.			L.	
2			7	ws						111
	BEDROCK.		8	ws		2410			D.	
			7	ws						ilł
00			2.			410-				jU
0	END OF MOLE.									
				l.						
										İ.
									1	
_	(			L					0.84	WN RMO
	T AL SEALE						GOIDER, BHAWNER & ASS	DCIATES 2		C=ED

·•a				NOJECT No
10641104 San FJ Bonemole Sammler Hauner Weisht	THE ROTAR			
	SAMPLES	DYNAMIC PENETRATION HESISTANCE	COEFFICIENT OF PERMEABILITY I	· 1 - 2 - 2 - 2
TITA DESCRIPTION	TTPE TTPE BLOWS/FT BLOWS/FT	SHEAN STRENGTH CU. LB /50 FT	WATCH CONTENT, PERCENT	STANDFIPE
10 WOODEN CRUEN WARINGLE DENSITY ORDWN I GREV SILT WITH MED I CONTRACT AND I CONTRACT ADDAN US CONTRACT ADDAN				
THE AL SLATE		GIRTAN, HRAWHER B ASSOCIA	<u></u>	DHAMN


## LIST OF DRAWINGS


IEC


(0.5


1-38


A-2869-1	-	SITE LOCATION
B-2869-2	-	LOCATION OF TAILINGS DISPOSAL POND
B-2869-3	-	PLAN OF EXISTING TAILINGS POND
D-2869-4	-	PLAN AND SECTION OF EXISTING DAM
B-2869-5	-	SCHEMATIC PROFILE OF TAILINGS FOND
B-2869-6		STABILITY ANALYSIS OF DAM
A-2869-7	-	WATER BALANCE



















October 30, 1997 File: 18040-02-07/HB/01 x M-85

Mr. Walter Kuit Manager, Environmental Affairs Cominco Ltd. 200 Burrard Street Vancouver, BC V6C 3L7

Nu-Dawn Resources Inc. 102 Piper Crescent Nanaimo, BC V9T 3G3

Dear Sir/Madam(s):

## Re: HB Mine Tailings Impoundment, Salmo, B.C.

According to our records the HB Mine near Salmo, B.C. is permitted under Mines Act Permit M-85 to Cominco, while mineral title and fee simple land is owned by Nu-Dawn Resources. Geotechnical inspections of the tailings impoundment were performed by the Mines Branch in April 1993 and June 1997. Attached you will find copies of these inspection reports.

On July 22, 1977 the Acting Chief Inspector of Mines approved construction of a spillway at the dam by letter addressed to Mr. J.S. Newman, P.Eng., Civil Engineer for Cominco. The spillway was never installed.

In summary, site conditions at HB Mine tailings impoundment have deteriorated and pose public safety and environmental hazards. The main concerns are that the impoundment was never decommissioned with a permanent spillway on closure and the current decant structure is deteriorating; the intake channel and structure are filling with debris and the discharge flume and channel on the downstream face are in need of repair. The integrity of the dam itself appears to be satisfactory except that there should be more freeboard. Overtopping and breaching of the dam or regressive erosion at the decant outlet is considered a distinct possibility in the foreseeable future.

.../2

Ministry of Employment and Investment Regional Operations, Health and Safety Branch Energy and Minerals Division Mailing Address: PO Box 9320 Stn Prov Govt Victoria BC V8W 9N3 Telephone: (250) 952-0462 Facsimile: (250) 952-0481

Location: 5th Floor, 1810 Blanshard Street Victoria Page 587 EGM-2013-00163 While it is unusual to have different entities as Permittee and Owner, you both have obligations to make the tailings impoundment safe, remove the hazard(s) and decommission the tailings site so the Mines Branch can close its file on the tailings impoundment. I must add that there are other safety concerns at the mill building which our health and safety inspectors will review next year after another safety inspection. Ultimately, Mines Branch wants to close all its files on the site and you should proceed with this in mind.

If you have any questions please do not hesitate to call me at (250) 952-0485 in Victoria. I would appreciate a response from you on this matter before the end of January 1998, with a plan to take appropriate action in the summer of 1998.

Yours sincerely,

Lin, Esta

Tim Eaton, P.Eng. Manager, Geotechnical Engineering

TE/tl

cc: Ricci Berdusco Andrew Whale

Attachments

Ado - old timber arise in alars? - seepage around Anna old lower doort pipe in the or dam.

Page 588 EGM-2013-00163

			File:	18040-02-07/HB Bot Responsiv
To:	Fred Hermann, Chief	Inspector		
From:	Tim Eaton			
Date:	June 25, 1997			
Re:				
		S14		
		S14 S14		

File 18040-02-07/

#### FAX COVER SHEET

#### MINISTRY OF ENERGY AND MINES

#### **MINES BRANCH**

#### Street: 5th Floor, 1810 Blanshard Street, Victoria,

Mailing: PO Box 9320 Stn Prov Govt, Victoria British Columbia V8W 9N3

DATE SENT:

May 21

TO:

Raynerd Carson - Nu-Dawn Res.

FAX NUMBER:

250 - 756 -0298

FROM: Tim Eaton, P. Eng. Manager, Geotechnical Engineering Ph: (250) 952-0485 Fax: (250) 952-0481 Email: tim.eaton@gems2.gov.bc.ca

#### **COMMENTS:**

FYI - A geotechical inspection of HB tailings facility is scheduled for June 3 AM.

NUMBER OF PAGES INCLUDING COVER SHEET:



## Province of British Columbia Ministry of Employment and Investment

ENERGY AND MINERALS DIVISION

# **REPORT OF GEOTECHNICAL INSPECTOR**

(Issued pursuant to Section 15 of the Mines Act)

Name of Property:	HB Mine	File:	18040-02-07/HB/01
Location:	Salmo		
Mine Manager:	n/a		
Company: Address:	Cominco and Nu-Dawn as per cover letter		
Persons Contacted;	n/a		
Type of Mining:	Closed, u/g, base metal		
Date of Inspection:	June 10, 1997		

An inspection of the tailings impoundment was conducted in the company of Art O'Bryan. The previous geotechnical inspection was April 29, 1993. The following areas in particular were noted:

The upstream dam face (Photo 1) is in good condition with no evidence of effects from wave action. The dam crest and downstream slope (Photo 2) are also in good condition with no evidence of cracks, settlement, slumps or erosion. Vegetation cover (mainly grasses and legumes) is healthy and thick and an alder has started on the upstream face at waterline.

The downstream toe is wet in the same areas as observed in 1993 and the toe drains appear to be functioning satisfactorily. The grouted CMP (old decant outlet) near the central toe of the dam is dry and not showing any signs of leakage inside or outside of the pipe.

The operating decant or water control structure is structurally sound. However the inlet channel to the decant is completely full if cattails and the alders are much larger. Compare Photo 3 (April 29, 1993) and Photo 4 (June 10, 1997). The log at the entrance to the channel is still in place. However the concrete water level control beams have not been removed from inside the structure as ordered in my 1993 inspection, although I note that the wooden support posts for the upper beam appear to have been replaced with steel pipe. Note that the same number of concrete beams are resting on top of the control structure in both photos.

HB Mine Inspection Report Inspection of June 10, 1997 Page 2

A 900 mm CMP conducts water from the decant control structure to a drop structure (manhole) part way through the dam and another CMP from the drop structure to the downstream dam toe. The drop structure has had the steel cover secured so that we could not inspect inside and the steel plate has been removed from inside as ordered in my 1993 inspection.

The downstream outlet for the decant structure has had some minor improvements made to it, compare Photo 5 (April 29, 1993) and Photo 6 (June 10, 1997). The steel and fibreglass plume has been realigned and now carries the discharge water from the outlet CMP and discharges it into the drainage natural plunge pool, about seven metres away. However this outlet structure needs repair.

#### Discussion

The current arrangements at the dam require monitoring and maintenance to ensure satisfactory long term operation. The existing decant structure will eventually plug with debris with a potential dam breach the end result. The flume in the downstream outlet for the decant will topple out of place again in the near future. Discharge water will gradually erode and undermine the toe of the dam in this area.

As stated in my 1993 inspection report this tailings facility must be permanently decommissioned. An engineered spillway and outlet channel need to be designed and installed for the 1:200 year 24 hour flood or combination flood and freshet, whichever is determine to be the bigger event. Static stability must have a minimum factor of safety of 1.5 and seismic stability reviewed to satisfy the 1:475 year probabilistic event. In the event stability is inadequate the pond level should be further lowered by the new spillway to reduce risk and improve stability. If necessary the entire pond should be permanently drained from the impoundment by the spillway/outlet structure.

Tim Eaton, P.Eng. Manager Geotechnical Engineering


Date: October 30, 1997




РНОТО 1




РНОТО 2



рното з



рното 4



РНОТО 6

21 15

#### Province of British Columbia Ministry of Energy, Mines and Petroleum Resources

#### Report of Inspector of Mines (Issued pursuant to Section 15 of the Mines Act)

### **GEOTECHNICAL - EIM**

Name of Mine: HB Mine

Owner or Operator: Nor-Quest Resources Ltd.

Locality: Salmo, B.C.

Ignun

Address: 102 Piper Crescent Nanaimo, B.C. V9T 3G3

Manager: Mr. Raynerd Carson

Areas Inspected: Tailings Dam

Persons Contacted

Management:No one available.

The mine manager shall complete the right hand column noting specific corrective actions taken, or to be taken by a specified date, and return a copy to the inspector within 15 days of receiving the report.

### Inspection Report

Manager's Response of Action Taken

- 1. Crest good, no settlement.
- Upstream slope good, beach/ wave action/ erosion minimal.
- 3. Downstream slope covered with grass and alder, wet zones at toe and several seeps, but no seeps were obvious on downstream slope face. Stability looks good; no sloughs, settlements, toe drains operating.
- 4. Piezometer standpipe near toe at centre of dam is dry to a depth of approx. (plumbed with small stone) 45-50 feet. Check Fig. 1 from Golder Brawner 74 report (Feb. 12, 1979 Rep# E/74/124) assume it to be BH 2 which is drawn at about 50 foot depth on the section so assume piezo is dry.

Copies To:	1 D L
Tim Eaton, P. Eng.	Jim Calon
Geotechnical Manager	Signature - Inspector
105-525 Superior St. Victoria, B.C., V8V 1X4	
Address	Signature - Manager
Date of Inspection: April 29, 1993	Page 596 EGM-2013-00183

Report of Inspector of Mines Page 2 of 2

#### Inspection Report

Manager's Response of Action Taken

5. Decant structure at E end looks structurally sound, flow not impeded but bullrushes growing at inlet are being drawn into structure. Large log at entrance to outlet ditch is okay and prevents other debris from passing. Inside the decant well there are 2 concrete outlet water level control beams. One is raised approx. 18" and supported entirely by 2"x2"x4" on end which are rotting. This must be removed as soon as The lower beam sits on the possible. bottom and should be removed to create additional free board between dam crest to panel level. 6. Drop structure looks sound but water has flowed out of the MH as evidenced by recent erosion and flattened grass around the MH . A 1/4" steel plate inside the MH must be removed as soon possible. It is fastened by as rusting bolts to the concrete and will block the outlet when it falls. The downstream decant outlet requires 7. maintenance. A steel and fibreglass flume has partially collapsed and should be removed. There is some The channel below resulting erosion. the outlet should be armoured along a 15 m. stretch with rock larger than 300 m in diameter. Surface runoff shall be diverted from 8. the crest of the dam, E end. 9. For abandonment, this facility requires a geotechnical inspection (annual report) and assessment of long term stability and capacity to accommodate 1:200 year 24 hour flood through a spillway structure. Recommendations shall be made in this report by a registered B.C. geotechnical engineer. Flood precipitation data shall be reviewed at this time. Seismic stability shall be reviewed for the 1:475 year. event.

Date of Inspection:

Initials:

Inspector

Page 597 Manageo M-2013-00163 Province of British Columbia Ministry of Energy, Mines and Petroleum Resources

Parliament Buildings Victoria British Columbia V8V 1X4

Rm. 105 - 525 Superior Street, Victoria, B.C. V8V 1X4

October 16, 1987

File: 18040-02-07/HB/01

Nor-Quest Resources Ltd. Box 369 Salmo, B.C. VOG 120

### Attention: Mr. Greg Carriere, Project Manager

Dear Sir:

#### Re: H.B. Mill Project

Attached is my inspection report for the geotechnical inspection of the tailings dam conducted September 28th. Please post a copy in the usual, conspicuous location. You should also forward a copy to your corporation headquarters.

As I had said during my inspection the white plastic sleeve of the piezometer could not be located; it will be useful when you submit your engineering report for approval of recomissioning. You will also need to sound the pond and present the results of the sounding survey along with the engineering report in order to recomission this pond. You would be wise to undertake the sounding survey and the restoration of the piezometer as soon as possible.

The placing of the coarse material on the upstream face can probably be delayed until next year, for I am not likely to conduct my next inspection until Autumn of 1988.

Yours truly,

RTM:blh Attachments:

cc: A.W. Whale, Fernie R.A. Fyles, Victoria

R.T. Martin, P.Eng., Sr. Geotechnical Inspector



## Province of British Columbia

Ministry of Energy, Mines and Petroleum Resources

## REPORT OF INSPECTOR OF MINES

(Issued pursuant to section 4 of the Mines Act, 1980)

#### GEOTECHNICAL INSPECTION

Name of Mine H.B. MILL
District and Location District no.5, Nelson, near Salmo
Owner or Agent Nor-Quest Resources Limited
Designated Manager Greg Carriere
Date of Inspection September 28, 1987
Person(s) attending
T. Martin, Sr. Geotechncial Inspector )
G. Carriere, Manager
Part inspected

Remarks:

Sunny, warm, calm.

The usual springs at the junction of the downstream face and both the west abutment and the rock toe berm still exist, but they were severely reduced by the prolonged dry conditions this year. The piezometer on the toe berm seems to have been snapped off. Relocate and restore it if

Freeboard was adequate, but undercutting of the upstream face of the dam is becoming significant. Place coarse gravel and cobble-sized protection over the affected area before my next inspection.

Although no overflow was occurring at the time, the overflow had obviously been functioning this year. However, one stoplog was jammed in the guides. Remove the jammed log to allow free overflow. Check overflow occasionally during periods of high runoff.

R.T. Martin, P.Eng., Sr.Geotechnical Inspector MINISTRY OF ENERGY MINES AND PETROLEUM RESOURCES ENGINEERING & INSPECTION BRANCH 105 - 525 SUPERIOR STREET VICTORIA, B.C. VSVAddrestree

Date of inspection . report ..... October 16, ..... 19.87...




Page 599 EGM-2013-00163

HBMine 1997



## рното 1




рното 2

Page 600 EGM-2013-00163

Page 601 EGM-2013-00163

рното 4










PHOTO 5



PHOTO 6

Tailings P.nd EI/MT 105 Ų.) MINE Philo 23 - is many the port from the day the here is to the right the add of the port. R.T. Martas the high ! SACE water & a plugged the cast Laine of flower Mart of 12. 2 34 Len, Ele 0+ 4p - q - - the constitute in a super the last ground have. i.

Page 603 EGM-2013-00163

H.15 Minuc Tailonya Dam Sheet 2015 Mitte 22 - From the tare sport as prisent discharget into the concrete on the for and the note the high the plante the Philo 24 - and ofte selained borrow agains the incorporant heges the opicale. There is non-water ponding in occasion a ling in grant of the angent of the The file growing Page 604 stimical that she in


EGM-2013-00163




81/5

HE MINE

Sheet 3 of 3






# HB TAILINGS DAM

May 16, 1984.

Sheet 1 of 4



pond state beach area in the

Film Roll no. May B'84

Раде 606 by R.T. MEGM-2013-00163

## HB TAILINGS DAM

May 16, 1989

Sheet 2/4



Photo 8A

a view of the inlet structure. the year, and



Photo 16A

ister of the falland seems 1-5

Roll no. May B'84

Page 607 by R.T. Ma EGM-2013-00163

## HB DAM

May 16/84.



Photo 12A

previous decarting system ed from the protificating the real the tre of the de



Photo IBA aview looking your The cone quit.

Roll May B'84

Раде 608 R.T. Martff.-2013-00163



Photo 14A Several seepinges occur at the toe, Allis is the most promine tone.




a closer view of the seepage in 19A. The spring accuss right at the tog mear the pregometer stand-pipe,

Shec.


R.T. Martin.











Page 613 EGM-2013-00163

HB TAILINGS POND

SALMO, BC



R DOND DAM

PRIOR TO MILL

START- UP 1972



ON NAME.



October 30, 1997 File: 18040-02-07/HB/01 x M-85

Mr. Walter Kuit Manager, Environmental Affairs Cominco Ltd. 200 Burrard Street Vancouver, BC V6C 3L7

Nu-Dawn Resources Inc. 102 Piper Crescent Nanaimo, BC V9T 3G3

Dear Sir/Madam(s):

### Re: HB Mine Tailings Impoundment, Salmo, B.C.

According to our records the HB Mine near Salmo, B.C. is permitted under Mines Act Permit M-85 to Cominco, while mineral title and fee simple land is owned by Nu-Dawn Resources. Geotechnical inspections of the tailings impoundment were performed by the Mines Branch in April 1993 and June 1997. Attached you will find copies of these inspection reports.

On July 22, 1977 the Acting Chief Inspector of Mines approved construction of a spillway at the dam by letter addressed to Mr. J.S. Newman, P.Eng., Civil Engineer for Cominco. The spillway was never installed.

In summary, site conditions at HB Mine tailings impoundment have deteriorated and pose public safety and environmental hazards. The main concerns are that the impoundment was never decommissioned with a permanent spillway on closure and the current decant structure is deteriorating; the intake channel and structure are filling with debris and the discharge flume and channel on the downstream face are in need of repair. The integrity of the dam itself appears to be satisfactory except that there should be more freeboard. Overtopping and breaching of the dam or regressive erosion at the decant outlet is considered a distinct possibility in the foreseeable future.

.../2

Ministry of Employment and Investment Regional Operations, Health and Safety Branch Energy and Minerals Division Mailing Address: PO Box 9320 Stn Prov Govt Victoria BC V8W 9N3 Telephone: (250) 952-0462 Facsimile: (250) 952-0481

Location: 5th Floor, 1810 Blanshard Street Victoria Page 615 EGM-2013-00163 While it is unusual to have different entities as Permittee and Owner, you both have obligations to make the tailings impoundment safe, remove the hazard(s) and decommission the tailings site so the Mines Branch can close its file on the tailings impoundment. I must add that there are other safety concerns at the mill building which our health and safety inspectors will review next year after another safety inspection. Ultimately, Mines Branch wants to close all its files on the site and you should proceed with this in mind.

If you have any questions please do not hesitate to call me at (250) 952-0485 in Victoria. I would appreciate a response from you on this matter before the end of January 1998, with a plan to take appropriate action in the summer of 1998.

Yours sincerely,

Tim, Estor

Tim Eaton, P.Eng. Manager, Geotechnical Engineering

TE/tl

cc: Ricci Berdusco Andrew Whale

Attachments

. . .



Province of British Columbia Ministry of Employment and Investment

ð,

ENERGY AND MINERALS DIVISION

# **REPORT OF GEOTECHNICAL INSPECTOR**

(Issued pursuant to Section 15 of the Mines Act)

Name of Property:	HB Mine	File:	18040-02-07/HB/01
Location:	Salmo		
Mine Manager:	n/a		
Company: Address:	Cominco and Nu-Dawn as per cover letter		
Persons Contacted:	n/a		
Type of Mining:	Closed, u/g, base metal		
Date of Inspection:	June 10, 1997		

An inspection of the tailings impoundment was conducted in the company of Art O'Bryan. The previous geotechnical inspection was April 29, 1993. The following areas in particular were noted:

The upstream dam face (Photo 1) is in good condition with no evidence of effects from wave action. The dam crest and downstream slope (Photo 2) are also in good condition with no evidence of cracks, settlement, slumps or erosion. Vegetation cover (mainly grasses and legumes) is healthy and thick and an alder has started on the upstream face at waterline.

The downstream toe is wet in the same areas as observed in 1993 and the toe drains appear to be functioning satisfactorily. The grouted CMP (old decant outlet) near the central toe of the dam is dry and not showing any signs of leakage inside or outside of the pipe.

The operating decant or water control structure is structurally sound. However the inlet channel to the decant is completely full if cattails and the alders are much larger. Compare Photo 3 (April 29, 1993) and Photo 4 (June 10, 1997). The log at the entrance to the channel is still in place. However the concrete water level control beams have not been removed from inside the structure as ordered in my 1993 inspection, although I note that the wooden support posts for the upper beam appear to have been replaced with steel pipe. Note that the same number of concrete beams are resting on top of the control structure in both photos.

HB Mine Inspection Report Inspection of June 10, 1997 Page 2

A 900 mm CMP conducts water from the decant control structure to a drop structure (manhole) part way through the dam and another CMP from the drop structure to the downstream dam toe. The drop structure has had the steel cover secured so that we could not inspect inside and the steel plate has been removed from inside as ordered in my 1993 inspection.

The downstream outlet for the decant structure has had some minor improvements made to it, compare Photo 5 (April 29, 1993) and Photo 6 (June 10, 1997). The steel and fibreglass plume has been realigned and now carries the discharge water from the outlet CMP and discharges it into the drainage natural plunge pool, about seven metres away. However this outlet structure needs repair.

#### Discussion

The current arrangements at the dam require monitoring and maintenance to ensure satisfactory long term operation. The existing decant structure will eventually plug with debris with a potential dam breach the end result. The flume in the downstream outlet for the decant will topple out of place again in the near future. Discharge water will gradually erode and undermine the toe of the dam in this area.

As stated in my 1993 inspection report this tailings facility must be permanently decommissioned. An engineered spillway and outlet channel need to be designed and installed for the 1:200 year 24 hour flood or combination flood and freshet, whichever is determine to be the bigger event. Static stability must have a minimum factor of safety of 1.5 and seismic stability reviewed to satisfy the 1:475 year probabilistic event. In the event stability is inadequate the pond level should be further lowered by the new spillway to reduce risk and improve stability. If necessary the entire pond should be permanently drained from the impoundment by the spillway/outlet structure.

Tim Eaton, P.Eng. Manager Geotechnical Engineering

Date: October 30, 1997

Province of British Columbia Ministry of Energy, Mines and Petroleum Resources

> Report of Inspector of Mines (Issued pursuant to Section 15 of the Mines Act)

## **GEOTECHNICAL - EIM**

Name of Mine: HB Mine

Owner or Operator: Nor-Quest Resources Ltd.

Locality: Salmo, B.C.

Address: 102 Piper Crescent Nanaimo, B.C. V9T 3G3

IGNUN MANILIR

Manager: Mr. Raynerd Carson

Areas Inspected: Tailings Dam

Persons Contacted

Management:No one available.

The mine manager shall complete the right hand column noting specific corrective actions taken, or to be taken by a specified date, and return a copy to the inspector within 15 days of receiving the report.

Inspection Report

Manager's Response of Action Taken

- 1. Crest good, no settlement.
- Upstream slope good, beach/ wave action/ erosion minimal.
- 3. Downstream slope covered with grass and alder, wet zones at toe and several seeps, but no seeps were obvious on downstream slope face. Stability looks good; no sloughs, settlements, toe drains operating.
- 4. Piezometer standpipe near toe at centre of dam is dry to a depth of approx. (plumbed with small stone) 45-50 feet. Check Fig. 1 from Golder Brawner 74 report (Feb. 12, 1979 Rep# E/74/124) assume it to be BH 2 which is drawn at about 50 foot depth on the section so assume piezo is dry.

Copies To:	00	11
<u>Tim Eaton, P. Eng.</u> Geotechnical Manager	Signature - Inspector	DU.
105-525 Superior St. Victoria, B.C., V8V 1X4		
Address	Signature - Manager	
Date of Inspection: April 29, 1993	Dated:	Page 619

Report of Inspector of Mines r\_je 2 of 2

#### Inspection Report

Manager's Response of Action Taken

5. Decant structure at E end looks structurally sound, flow not impeded but bullrushes growing at inlet are being drawn into structure. Large log at entrance to outlet ditch is okay and prevents other debris from passing. Inside the decant well there are 2 concrete outlet water level control beams. One is raised approx. 18" and supported entirely by 2"x2"x4" on end which are rotting. This must be removed as soon as possible. The lower beam sits on the bottom and should be removed to create additional free board between dam crest to panel level. 6. Drop structure looks sound but water has flowed out of the MH as evidenced by recent erosion and flattened grass around the MH . A 1/4" steel plate inside the MH must be removed as soon possible. as It is fastened by rusting bolts to the concrete and will block the outlet when it falls. 7. The downstream decant outlet requires maintenance. A steel and fibreglass flume has partially collapsed and should be removed. There is some resulting erosion. The channel below the outlet should be armoured along a 15 m. stretch with rock larger than 300 m in diameter. Surface runoff shall be diverted from 8. the crest of the dam, E end.

9. For abandonment, this facility requires a geotechnical inspection (annual report) and assessment of long term stability and capacity to accommodate 1:200 year 24 hour flood through a spillway structure. Recommendations shall be made in this report by a registered B.C. geotechnical engineer. Flood precipitation data shall be reviewed at this time. Seismic stability shall be reviewed for the 1:475 year. event.

Date of inspection:

Initials:

Page 620 Manager EGM-2013-00163 Pages 621 through 623 redacted for the following reasons: s.3

HB Mine

RUN DATE: 04/04/97

RUN TIME: 14:41:12

-7 M-85

PAGE: 1 REPORT: RGEN0100

MINFILE / pc MASTER REPORT GEOLOGICAL SURVEY BRANCH ENERGY AND MINERALS DIVISION FE F

TIONAL MINERAL INVENTORY: 082F3 Zn2

MINFILE NUMBER	2: 082FSW004			AL MINERAL INVENTOR	
NAME (S)	<pre>Set (L.12672), ZINCTO HB MINE</pre>	N (L.10810), G	CARNET (L.10809),	INTERSTRATICS.	Northman Marpurces
REGIONS NTS MAP	: Past Producer : British Columbia : 082F03E : 49 09 08 N		Underground		N: Nelson 3: 11 (NAD 27) 3: 5444177
ELEVATION LOCATION ACCURACY	: 117 11 55 W : 1220 Metres : Within 500M : West of Aspen Creek a	and about 1.5	kilometres north of S		485516
COMMODITIES		linc Talc	Silver	Cadmium	Copper
MINERALS					
SIGNIFICANT		Sphalerite Spencerite	Galena	Pyrrhotite	Anglesite
ASSOCIATED		alc	Calcite		
ALTERATION COMMENTS ALTERATION TYPE MINERALIZATION AGE	: The northern area is : Carbonate S	ilica oxidized to a ilicific'n	Talc depth of 100 metres, Oxidation	Anglesite	Tremolite
DEPOSIT					
CLASSIFICATION: TYPE: E12 Missis J01 Polyme	: Sedimentary E ssippi Valley-type Pb-Z stallic manto Ag-Pb-Zn	assive xhalative n	Shear Industrial Min. E13 Irish	1-type carbonate-ho	sted Zn-Pb
MODIFIER: DIMENSION:	Contraction and a second	heared etres lso bladed. B	STRIKE/DIP: Strike: mineralization of	curs at	D/PLUNGE: 090/
HOST ROCK	the largest and most	easterly ore z	one.		
DOMINANT HOST ROCK:	Sedimentary				
STRATIGRAPHIC AGE	GROUP		ATION	IGNEOUS/METAN	IORPHIC/OTHER
ower Cambrian	Undefined Group	Laib			
LITHOLOGY:	Limestone Dolomite Siliceous Limestone Argillite Diabase Dike				
HOST ROCK COMMENTS:	The orebodies occur in ative with rocks of th			ich is correl-	
EOLOGICAL SETTING TECTONIC BELT: TERRANE:	Omineca Kootenay		PHYS	IOGRAPHIC AREA: Sel	kirk Mountains
NVENTORY					
ORE ZONE:	НВ				
	COMMODITY	7 Tonnes GRAF		78	
COMMENTS :	Lead Zinc Measured and indicated	4 ore.	.1000 Per cent .1000 Per cent		and the
REFERENCE :	Energy, Mines and Reso	urces Canada,	Mineral Bull. MR 198,	page 209	
APSULE GEOLOGY	Can tal		abauabé pa ba Massar	Ave. Free	12 - A. C.
	The HB orebodies carbonate hosted sedim orebodies are located Cambrian Laib Formation the Badshot Formation)	entary exhalat within dolomit n, Reeves Memb	ized limestone of the er (correlative with	The Lower limestone of	17.7.2
	in contact with argill: Formation, on a fault of	ites of the Lo	wer to Middle Ordovic	ian Active	C. C .

In contact with argillites of the Lower to Middle Ordovidian Active Formation, on a fault contact, with the Active rocks overthrust from the east over the Reeves rocks. Two distinct calcareous layers of the Reeves Member can be recognized in the area, an upper one about 110 metres thick separated from a lower 12 metre member by 15 to 30 metres of micaceous brown limey argillite. The HB orebodies occur within a hundred metres or

Page 624 MINFILEGM-2013-00482F5W004

#### CAPSULE GEOLOGY

so to the west of the thrust fault. It is thought that the mineralization is related to the intrusion of granitic stocks of the Middle to Late Jurassic Nelson Intrusions with the nearest outcrop about 1 kilometre away from the mine. The only intrusives present in the mine are post-ore diabase dykes up to 3 metres thick.

In the vicinity of the HB mine, the beds are folded into a broad synclinorium, and the limestone layers in the mine are on the west limb of this structure. There is evidence of much isoclinal folding within the trough of the synclinorium, with axial planes steeply inclined to the east and folds plunging 20 degrees to the south. There may be similar folding along the west limb within the mine area, but the portions of the folded beds revealed by the mine workings indicate that here the limestone has only formed thickened wrinkles. Within these wrinkles the beds are highly distorted by complex folding. In the central portion of the structures there is cleavage banding which strikes north and dips steeply. The primary folding is disturbed by major crossfolding in at least two places, one at the north end of the mine, the other just south of the main orebodies. The crossfolds plunge steeply to the north and resemble "S" type dragfolds.

The principal ore zones consist of three steeply dipping, parallel zones lying approximately side by side and extending as pencil-like shoots for about 900 metres along the gentle south plunge of the controlling structures. The largest and most easterly ore zone has a maximum height of about 140 metres and a maximum width of 30 metres. Within these zones are steeply dipping discontinuous ore stringers with a lead to zinc ratio of 1:5.

In addition to the steep stringer lodes there is a second type consisting of flat lying, slightly brecciated zones with a lead to zinc ratio of about 1:2.5. These zones plunge at 20 degrees to the south, in general agreement with the plunge of the other orebodies. There are several separate ore zones of the flat lying variety. The layers of ore range from a few metres to 12 metres in thickness, but are generally from 3 to 4.5 metres thick. The sulphide mineralization within these layers is fairly regular and resembles bedding.

There is evidence to indicate ore deposition was controlled by shear zones within the folded limestone; the best ore concentrations occurring at the junctions between steeply dipping shears (the pencil-like ore bodies) and flat lying shears (the flat-lying brecciated orebodies).

The mineralogy of the ore is relatively simple with pyrite, sphalerite and galena in order of abundance and minor pyrrhotite found locally. The northern portion of these bodies is exposed at surface, near the original HB claim, and are oxidized to a depth of about 100 metres at that point. Where the ore is protected by enclosing dolomite relatively little oxidation has occurred. Other secondary minerals include calamine, smithsonite, anglesite, and the rare zinc phosphate, spencerite.

Wallrock alteration is typical of lead-zinc deposits in the area. The ore zones are enveloped by a broad zone of dolomitization which is bordered along its contact with the limestone by a narrow zone in which limestone is replaced by fine-grained silica. Talc and tremolite alteration, thought to be pre-ore, is concentrated near the silica-rich zone resulting from the silicification of dolomite. An appreciable amount of talc is found locally within the ore zone.

A smaller zone, located to the southwest of the main HB mine, is known as the Garnet orebody (082FSW249). The Garnet zone was mined from the surface from a small open pit, whereas the main mine is entirely underground.

The HB mine produced a total of 6,656,101 tonnes of ore in 29 years between 1912 and 1978. Recovered from this ore were 29,425,521 grams of silver, 49,511,536 kilograms of lead, 260,431,646 kilograms of zinc, 2,019,586 kilograms of cadmium, 105,412 kilograms of copper and 6,159 grams of gold. Measured and indicated reserves published December 31, 1978 by Canadian Pacific Limited were given as approximately 36,287 tonnes grading 0.1 per cent lead and 4.1 per cent zinc (Energy, Mines and Resources Canada Mineral Bulletin MR 198, page 209).

#### BIBLIOGRAPHY

EMPR AR 1911-157,160,161; 1912-155,322; 1913-131,419; 1914-327, 510; 1915-135,160,445; 1916-K205; 1917-448; 1921-G347; 1925-A248; 1926-A278; 1927-C309; 1933-224; 1934-E5; 1948-134; 1949-168; 1950-124; 1951-A139; 1952-147; 1953-117,220; 1955-A48,52; 1956-A50, 83; 1957-A46; 1958-A45,39,63; 1959-A48,61; 1960-A54,68; 1961-A49,68; 1962-A49,74; 1963-A49,70; 1964-A55,116; 1965-181; 1966-213

EMPR PF (\*Warning, G.F. (1960): Geology of the HB Mine; Also see other reports, unidentified authors, on HB Mine; \*Irvine, W.T. (1957): The HB Mine; \*1:1200 Scale Map of General Mine and RUN DATE: 04/04/97 RUN TIME: 14:41:12 MINFILE / pc MASTER REPORT GEOLOGICAL SURVEY BRANCH ENERGY AND MINERALS DIVISION

BIBLIOGRAPHY	
--------------	--

Section, 1961; Miscellaneous sketches of Drill Core and Underground Faces) EMPR GEM 1972-48; 1973-57; 1974-67 EMPR MULL 41, p. 101 EMPR MINING Vol. I, 1975, p. 18 EMPR OF 1988-1; 1989-11; 1990-8; 1990-9; 1991-2 EMPR FIELDWORK 1987, pp. 19-30; 1988, pp. 33-43; 1989, pp. 11-27; 1990, pp. 9-31 EMPR BC METAL MM01014 GSC BULL \*29, p. 20 GSC MEM 94; \*172, p. 47; 308 GSC P 50-19 GSC MAP 3-1956, #18; 50-19A; 299A; 1090A EMR MF CORPFILE (Cons Mining & Smelting Co. of Canada Ltd.) EMR MIN BULL MR #166/Res.; \*198, p. 209 CIM Trans. Vol. 2, pp. 124-131 (\*Irvine, W.T., The H,B, Mine in Canadian Ore Deposits, 1957); Vol. LXIII, 1960, pp. 520-523 (\*Warning, G.F., Geology of the H.B. Mine) CIM Vol. LXIII, pp. 520-523 CMJ \*May, 1954, Ch. 14, p. 202 W MINER May, 1979, p. 60 GCNL #150, 1981; #171, 1983 \* 850724 CODED BY: GSB

DATE CODED: 850724 DATE REVISED: 910218

CODED BY: GSB REVISED BY: GJP FIELD CHECK: N FIELD CHECK: N RUN DATE: 04/04/97 RUN TIME: 14:42:16

IINFILE NUMBER:	082FSW004	NAME :	HB (L.12672)		STATUS: Pas	t Producer
Production <u>Year</u>	Tonnes <u>Mined</u>	Tonnes Milled		Commodity	Grams <u>Recovered</u>	Kilogram Recovere
1978	200,888	200,888		Silver Cadmium Lead Zinc	827,713	67,29 1,451,18 8,381,56
1977	357,256	357,256		Silver Cadmium Copper Lead Zinc	995,696	95,89 61 1,931,56 12,593,51
1976	374,163	374,163		Silver Gold Copper Lead Zinc	937,071 684	27, 2,036,929 12,796,512
1975	411,084	411,084		Silver Gold Lead Zinc	1,130, <b>314</b> 622	1,666,762 12,480,257
1974	232,348	232,348		Silver Gold Cadmium Lead Zinc	1,024,004 498	58,068 2,089,780 7,843,388
1973	319,039	319,039		Silver Gold Cadmium Lead Zinc	1,312,391 871	94,802 2,805,817 12,031,747
1965	352,804	352,804		Silver Cadmium Lead Zinc	i,344,427	113,539 3,139,705 14,781,827
1965	376,743	376,743		Silver Cadmium Lead Zinc	1,733,339	149,146 4,243,461 18,417,332
1964	433,451	433,451		Silver Cadmium Lead Zinc	2,115,533	156,051 2,855,168 18,996,984
1963	429,921	429,921		Silver Cadmium Lead Zinc	2,132,297	158,721 2,993,875 18,736,025
1962	425,448	425,448		Silver Cadmium Lead Zinc	1,866,273	147,567 3,291,149 18,410,012
1961	428,852	428,852		Silver Cadmium Lead Zinc	2,259,664	168,769 3,314,291 20,038,427
1960	421,302	421,302		Silver Cadmium Lead Zinc	2,244,330	149,015 3,591,335 17,562,315
1959	420,482	420,482		Silver Cadmium Lead Zinc	2,153,416	156,841 3,295,966 18,951,716
1958	415,682	415,682		Silver Cadmium Lead Zinc	2,582,295 Page 62 FGM-20	160,211 27 3,768,843 013-00163 <sup>0,324</sup>

RUN DATE: 04/04/97 RUN TIME: 14:42:16

FILE NUMBER:	082FSW004	NAME :	HB (L.12672)		STATUS: Past	Producer
Production <u>Year</u>	Tonnes <u>Mined</u>	Tonnes Milled		Commodity	Grams Recovered	Kilograms <u>Recovered</u>
1957	409,484	409,484		Silver Cadmium Lead Zinc	2,485,192	141,370 3,037,483 16,782,771
1956	394,900	394,900		Silver Cadmium Lead Zinc	2,312,508	126,691 2,565,979 14,484,983
1955	224,348	224,348		Silver Cadmium Lead Zinc	814,401	75,604 1,145,482 6,206,890
1950	2,610			Silver Lead Zinc	404,930	350,015 676,804
1949	8,083			Silver Lead Zinc	347,887	280,583 639,627
1927	595			Silver Gold Lead Zinc	49,205 187	137,876 20,275
1924	27			Silver Lead	2,084	6,571
1919	34			Silver Lead	4,230	13,043
1917	1,363			Zinc		445,566
1916	5,914			Lead Zinc		87,742 1,573,974
1915	4,706			Silver Lead Zinc	3,173	9,440 1,418,470
1914	2,193			Silver Lead Zinc	200,988	476,767 150,593
1913	1,708			Silver Lead	179,277	429,688
1912	673			Silver Lead	80,028	161,806

SUMMARY TOTALS: 082FSW004

NAME: HB (L.12672)

		Metric	Imperial	
	Mined:	6-656,101 tonnes	7,337,095	tons
	Milled:	6,628,195 tonnes	7,306,334	tons
Recovery:		and the second second second second second second second second second second second second second second second		
	Silver:	31,543,666 grams	1,014,151	ounces
	Gold:	2,862 grams	92	ounces
	Cadmium:	2,019,586 kilograms	4,452,424	pounds
	Copper:	889 kilograms	1,960	pounds
	Lead:	51,178,298 kilograms	112,828,802	pounds
	Zinc:	272,911,903 kilograms	601,667,585	pounds

Comments:

1978: Production ceased Aug. 17.

Page 628 EGM-2013-00163

CE	RITISH	Ministry of Environment, Lands and Parks	MINISTRY OF AND INVE Grown Land Register ServicesE P Office of the Surveyor General	
To:	Theresa Leona			Date: September 19, 1997
	Mines Branch Ministry of Er Victoria, Briti	mployment and Investm	eent	File: 10450-02-004 Job No. 151897

As discussed with Tim Eaton. September 19, 1997, enclosed please find cut sheets of official plans 18 Tray 17 and 7 Tray 6 along with copies of the survey plans for District Lots 966, 1221 and 1244, Kootenay District.

No charges were incurred in completing this order.

Q

for Brendan J. Feary Manager Registry Management Section

BAM:pd bcgeu

Enclosure

Page 629 EGM-2013-00163



# FAX COVER SHEET

# PROVINCE OF BRITISH COLUMBIA

#### MINISTRY OF EMPLOYMENT AND INVESTMENT

# ENERGY AND MINERALS DIVISION

#### MINES BRANCH

	Location: 5th Floor, 18 Address: PO Box 9320, Str Victoria,	. Prov. Gov't, V8W 9N3	
	Phone: (250) 952-0486	Fax: (250) 952-044	81
DATE SENT:	· Sept X, 1	997	
TO:	Ber Morton Crown Lond Regis	tig Bervices	
	387-1830		
FAX NUMBER:	Aheresa		
COMMENTS:	Ber, As discourses	<u>.</u>	T incuto
the fallo	now who ching of	and the real	<u>Area</u>
Lot 1244		ar. attached	
	V		
	e fossible to get a		2 aleas Nell? Page 630 EGM-2013-

Page 631 redacted for the following reason: Not Responsive Province of British Columbia Ministry of Employment and Investment Fifth Floor 1810 Blanshard Street Victoria British Columbia V8V 1X4 Fax: (250) 952-0481

Energy and Minerals Division

**Facsimile Cover Sheet** 

To:

Company:

Phone:

352-9300 Fax:

From: John Errington Ministry: Employment and Investment Energy and Minerals Division Phone: (250) 952-0470 Fax: (250) 952-0481

6/18/97 Date: Pages including this cover page: Original will be mailed: Yes \_\_\_ No

**Comments:** 

B. Mine

jce-fax



Ph: (250) 952-0475

June 17, 1997

File: M-85 14675-35-04

Mr. B. Baldigara Secretary, Assistant Administrator Regional District of Central Kootenay 601 Vernon Street Nelson, B.C. V1L 4E9

Dear Mr. Baldigara:

Re: H.B. Mine Tailings Impoundment

I have been asked to reply to your May 15, 1997 letter to Andrew Whale, Regional Manager, Ministry of Employment and Investment, regarding possible future liabilities associated with the H.B. tailings impoundment.

#### Status of Permits Covering the Tailings Impoundment

The mine is regulated under the Mines Act.

The mine, including the tailings impoundment, is covered by Permit M-85 issued to Cominco Ltd. (copy attached). However, they sold this property to David Minerals s.21

s.21 and the last record we have of an owner is Nu-Dawn Resources.

Over the years, in spite of numerous attempts to get the new owner to assume the responsibilities of the permit, Cominco still remains the permittee.

Cominco carried out considerable research in the early 1970's to determine the feasibility of establishing vegetation directly on the tailings material, and to determine the metal uptake in plants. That information is stored off-site and I do not have that information immediately available. I don't recall any major issues, however.

I could not find a closure plan and I don't believe that one was ever filed.

...2

Ministry of Employment and Investment Regional Operations, Health and Safety Branch Energy and Minerals Division Mailing Address: PO Box 9320 Stn Prov Govt Victoria BC V8W 9N3

Telephone: (250) 952-0462 Facsimile: (250) 952-0481 Location: 5th Floor, 1810 Blanshard Street Victoria

Page 633 EGM-2013-00163

#### Dam Safety

I have included Part 9 of our Health, Safety and Reclamation Code for Mines in British Columbia (Code). The owner and permittee have not satisified the requirements of part 9.2.4, 9.3.2 and 9.3.5 The obligations in this regard should be discussed with Tim Eaton, P.Eng., Manager, Geotechnical Engineering. At present there are no significiant dam safety issues, however some work is required.

Should the Regional District purchase this property, the tailings impoundment would still be regarded as part of a mine, albeit a closed mine, and regulated under the Mines Act. As such, there would still be requirements for maintenance, periodic inspections and monitoring. These requirements would likely not be onerous, however.

#### Contamination Level of the Liquid and Solid in the Tailings

This a potential concern especially in relation to the new Contaminated Sites Provisions of the Waste Management Act. Our own internal review several years ago made a preliminary assessment of acid rock drainage potential of these tailings and it was felt that the abundance of limestone which hosted this ore deposit was likely sufficient to prevent sulphide oxidation, and acid mine drainage from occurring. This needs to be confirmed through samples of tailings and seepage from the impoundment. If there is any metal release, it will be associated with neutral to alkaline drainage.

If you have any further questions or concerns, please do not hesitate to call either myself (250) 952-0470 or Tim Eaton (250) 952-0485.

Yours very truly,

Manager, Reclamation and Permitting

JCE:ch Encl.

cc: Andrew Whale, Cranbrook Tim Eaton Fred Hermann

let-hb

Pages 635 through 636 redacted for the following reasons: Not Responsive INTEROFFICE MEMORANDUM

Created:	03-Sep-1996 07:31am PDT
Sent:	03-Sep-1996 07:39am PDT
From:	Andrew Whale of EI
	AWHALE
Title.	Regional Manager, Kootenay
Dept:	Employment & Investment
Tel No:	426-1653

TO: John Errington of EI

( JERRINGTON )

CC: Tony Milligan of EI CC: Tim Eaton of EI ( TMILLIGAN ) ( TEATON )

Subject: RE: HB, mine

I've recently raised the HB issue with Bruce Donald who Cominco have tasked to look after all their old canadian properties. so let's hope that they take some action.

the tailings dam is a major liability. although it was well constructed and is currently in good shape [perhaps a little wave damage], it is not ready to be abandoned. spiggoting took place away from the dam and water level is controlled by a lareg decant . there is no spillway or other long term means of controlling the water level when the decant stops functioning [which it will do some day]

the major issue is, should we let cominco off the hook. if yes then any company can sell their exhausted mine and escape reclamation obligations. successive owners of the hb property have no money or security

andrew

M-85

Pages 638 through 639 redacted for the following reasons: Not Responsive

INTEROFFICE MEMORANDUM

Created:	29-Aug-1996 09:35am PDT
Sent:	29-Aug-1996 09:38am PDT
From:	John Errington of EI JERRINGTON
Title.	Reclamation Manager
Dept: Tel No:	Employment & Investment 952-0470
TET NO:	952-0470

( AWHALE ) ( TMILLIGAN )

TO: Andrew Whale of EI TO: Tony Milligan of EI Subject: HB, mine

Michael Mardin, lawyer for Cominco was here yesterday looking through the HB file (not the main purpose of the visit), and I let him know that they still were the permittee even though they sold the property many years ago.

They may write a letter saying they want out.

Our remedies with respect to Cominco are not clear. We still need to go after the present owner and try to get them to transfer the permit into their name.

#### INTEROFFICE MEMORANDUM

	Sent: 16-May-	1996 12:54pm PDT 1996 12:59pm PDT uschke of EI E
	Title: Dept: Employm Tel No: 426-165	ent & Investment 5
TO: Andrew Whale of EI	( AWHALE	)
CC: Tony Milligan of EI CC: John Errington of EI CC: Art O'Bryan of EI	( TMILLIG ( JERRING ( AOBRYAN	TON )
Subject: RE: (M-58) HB Mine HB Mill		

Just for the record I have inspected the mill (several yrs. ago) and I am concerned about the foundations for the leach tanks in the "new" expansion. I do not think that any permits should be let until an engineer inspects the tanks and thier foundations. My concern is that the foundations will not be able to bear the load and the tanks may quite possibly topple and spill cyanide laced leachate, with the possibility of serious injury and environmental damage.

Steve W.

INTEROFFICE MEMORANDUM Created: 16-May-1996 10:13am PDT 16-May-1996 10:22am PDT Sent: Andrew Whale of EI From: AWHALE Title: Regional Manager, Kootenay Dept: Employment & Investment Tel No: 426-1653 TO: Tony Milligan of EI ( TMILLIGAN ) CC: John Errington of EI ( JERRINGTON ) CC: Art O'Bryan of EI ( AOBRYAN ) CC: Steve Wuschke of EI ( SWUSCHKE ) Subject: RE: (M-58 HB Mine Tony, you should also discuss this with steve as he has intimate

knowledge of the site and problems

Page 642 EGM-2013-00163

BF June 30/96

INTEROFFICE MEMORANDUM

	Created:	15-May-1996 03:23pm PDT
	Sent:	15-May-1996 03:34pm PDT
	From:	John Errington of EI JERRINGTON
	Title:	Reclamation Manager
	Dept:	Employment & Investment
	Tel No:	952-0470
TO: Tony Milligan of EI	(	TMILLIGAN )
CC: Andrew Whale of EI	(	AWHALE )
CC: Art O'Bryan of EI m-85	1	AOBRYAN )
Subject: 4-58, HB Mine		

This mine has not operated for many years but is still on our books. Permit M-85 was last issued in November 1978 to Cominco Ltd. and not long after sold to David minerals who were given permission to work by S22 (unknown to us) and who subsequently went broke. The last thing in the file was an attempt to issue a permit to Nu-dawn Resources with an increase in security to \$110,000. I would really like to have this permit transferred into the new owner's name and some agreement on responsibility, then we can get Cominco out of it.

Under no circumstances should any work be allowed on the property either in rer val of assets or exploration, until we get the permit sorted out.

Suggest you discuss this file with Art as he has a long history with it.

FAX to Tony Milligan August 12/96 As we discussed, pla to the get to this by fill.

INTEROFFICE MEMORANDUM

		Created: Sent:	15-May-1996 03:23pm PDT 15-May-1996 03:34pm PDT
		From:	John Errington of EI JERRINGTON
		Title:	Reclamation Manager
		Dept: Tel No:	Employment & Investment 952-0470
TO:	Tony Milligan of EI	(	TMILLIGAN )
CC:	Andrew Whale of EI	(	AWHALE )

CC: Andrew Whale of EI CC: Art O'Bryan of EI

( AOBRYAN )

Subject: M-58, HB Mine

This mine has not operated for many years but is still on our books. Permit M-85 was last issued in November 1978 to Cominco Ltd. and not long after sold to David minerals who were given permission to work by S22 (unknown to us) and who subsequently went broke. The last thing in the file was an attempt to issue a permit to Nu-dawn Resources with an increase in security to \$110,000. I would really like to have this permit transferred into the new owner's name and some agreement on responsibility, then we can get Cominco out of it.

Under no circumstances should any work be allowed on the property either in removal of assets or exploration, until we get the permit sorted out.

Suggest you discuss this file with Art as he has a long history with it.

Pages 645 through 646 redacted for the following reasons: s.3

		NERAL RESOURCES DIVISION	For a tick
		. MERAL RESOURCES DIVISION	
		RESOURCE MANAGEMENT BRANCH	MINISTRY OF ENERGY, MINES & PETROLEUM RESOURCES.
		NOTICE OF WORK AND	- ETHOLEUM RESOURCES,
			A REC'D MAR 0 5 1993
		<b>RECLAMATION PROGRAM ON</b>	A
		MINERAL PROPERTY	NELSON, B.C.
r.	NAME OF DOODEDTV. NIL	-DAWN. RESOURCES. INC	
	NAME OF PROPERTY: 5.9	-URWIN. REDUCTINGO. LINU HA Be SLTE	••••••••••••••••••••
	Previous Annual Work Approv	al Number (applicable only to those properties previously worked	d)

10 2 2 3

· · ·

(ie. SMI91-0100500-123) ...... Reclamation Permit Number, if previously issued (may be several years old) ..... Name of Claims: ...ADA. #DL14388, Legal .Tender..MC..L10823/..Tailings.Pond..SL..36.DL1236.....

2.	LOCATION: Is any part of this Property in a Recreation Area or Park?YesNo
	Are any of the surface rights of this property privately owned?YesNo (Operator responsible for contacting owner)
	Name and address of private land owner:
	Mining division: .Nelson.District
	Latitude: <u>4.9</u> °. <u>08</u> . ' Longitude: <u>117</u> . °. <u>10</u> '. ' Minfile No. (if known)
	Access route (from nearest town to property): .From.Salmo,BCeaston.Airport.RdtoSheep.Creek.Rd.,
	North.on.Sheep.Creek.Rdto.Nu-Dawn.sign.then.up.bill.to.Mine

3.	OPERATOR/AGENT (Person or Company controlling property on behalf of the	he owner):
	Name:NU-DAWN RESOURCES INC.	
	Company contact person:Jim.Wadsworth	Fax No.:604-357-2516.
	AddressBox 369	CitySalmo
	Province British Columbia Postal Code: VOG 120	
	Signature of Operator/Agent: Mada ceron	Date:March.6, 1993

Address Province.	DAWN RESOURCES INC. Fax No: 604-756-0298 D2 Piper Crescent City Nanaimo ritish Columbia Postal Code: V9T 3G3 Date: March 6/93
Province.	itish Columbia Postal Code: V9T 3G3
Signature	human (an latter of Authorization from Denne)
	Owner (or letter of Authorization from Owner):
5. NAME O	ANAGER:J. Wadsworth
(Person re	sible for management and operation of property)

6. DURATION: Duration of work: From ...... March. 6, .. 1993.....

To. August 31, 1994

7.	EXPLORATION WORK (Brief Description, if applicable)				
	Blasting	Geophysical			
	Geochemical	Clearing Trees			
		Geological			
	Line cutting (distance, width, method)				
	Campsite: Length: m Width: m Are	a m <sup>2</sup>			
	If Blasting, give details of explosives, magazines, etc				
	Give number of existing explosives storage permit	Name of Blaster:			

Pump size: *	Capacityc.f.s.	Location of water intake (show on plan)

9. WASTE WATER TREATMENT (subject to approval under the *Waste Management Act*) including disposal of drilling mud and sludge. Describe treatment and disposal facilities (size of settling pond, recycling, distance to nearest stream, etc). Show on plan.

10. ESTIMATED NUMBER OF WORKERS ON SITE (including Contractors):......7.....

 $\lambda$ 

11. EQUIPMENT LIST			
Note: all motorized equipment to co	omply with the Mining Code		
Number and Type	Size/Capacity	Number and Type	Size/Capacity
a)		e)	
b)		f)	
c)		g)	
d)		h)	

12.	FIRST AID FACILITIES (Must comply with W.C.B. Regulations)
	Describe methods of communication, emergency transportation, and type of first aid kit. Phone, 12-Ton Pick-Up with
	Location of nearest hospital:Nelson, B. C. Travel time to hospital:

13. SURFACE	DISTURBANC	E OFF MINER	L CLAIMS			
Campsite:	# of people		Length:	m	Width:m	Area m
Road acces	s construction:	Total length:	m	Approxim	ate width: m	Area: m
	s construction:	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	m	Approxim	ate width: m	Area:

# 14. SURFACE DISTURBANCE ON MINERAL CLAIMS

(a)	Settling por	nds: #		Length m	Width:m	Area: m <sup>2</sup>
(b)	Road const	ruction:	Tot	al length m	Width:m	Area: m <sup>2</sup>
(c)	Drilling:	# of sites:	Depth:	Length: m	Width:m	Area: m <sup>2</sup>
(d)	Trenching	# of trenches:	Depth:	Length: m	Width:m	Area: m <sup>2</sup>
(e)	Test pits:	# of pits:	Depth:	Length: m	Width:m	Area: m <sup>2</sup>
(f)	Campsite:	# of people		Length: m	Width:m	Area m <sup>2</sup>
(g)	Undergrour	nd work: area of surface	disturbance	Length: m	Width:m	Area: m <sup>2</sup>
(h)	Rock dump	s: area of surface disturb	ance	Length: m	Width:m	Area: m <sup>2</sup>
(i)	Other: desc	ribe: Area:				m <sup>2</sup>
		TOTAL SU	RFACE AREA DIS	TURBED ON MINER	AL CLAIMS THIS YEA	AR: m <sup>2</sup>
PRIOR DISTURBANCE ON CLAIM					AR: m <sup>2</sup>	
	B	ALANCE OF UNRECL	AIMED DISTURBA	NCE AT THE END O	F PROJECT THIS YEA	AR: m <sup>2</sup>

# 15. PRESENT STATE OF LAND ON WHICH WORK IS PROPOSED

Present land use: Caretakers. for. Security. of. Plant	Type of vegetation:
Access roads (present use and condition) Roadsarein.good.condition,.	Access.for.Caretakers
Old workings (location, condition)N/AAdits.closed.with.doors.	

	RECLAMATION PROGRAM: Proposed use of land after reclamation: Recreation and Housing				
	Describe protective measures and proposed site reclamation methods with reference to the items listed below.				
	Topsoil handling (where applicable): Topsoilto.be.put.over.old.mill.bases.end.other.buildings				
	Camp sites: 7. Houses.to.be.left.for.new.owners.to.do.with.whatever.they.plan and sheds and office, warehouse. Trenches, drill sites, major excavations:Glory.Hole.above.mill.site, new.chain.link.fence to be put around complete opening. Roads:Boads.are.in.good.condition.				
	Revegetation of disturbed areas:				
	Waste dumps:				
	AditsBoth adits.to.be filled in with drill core and topsoil put over adits				
	Drill core storage Core. storage .building. to .be .taken .down,core .put. into .adits				
	Other:Concentrator,Leach.Plant,Refinery,Oil.Storage.Shed,Mine.Dry,CompressorShop,				
	Mine Shop, Machine Shop, All to be taken down, all machinery removed from property,				
	Tailings Damwe will place coarse material on the upstream face as rEagric/ed by Captachnical Inspactor P. T. Martin				

					4
17. URANIUM/THORIUM					
Is any part of this property designated as a Uranium/Thorium area? Yes X No					
If yes - has a survey been completed?	Yes	No			

Note: if underground exploration or development is contemplated, an additional 'Underground Exploration Work Application for Approval' form must be completed.

This application will be returned if it is not accompanied by a legible map showing location of claim posts, property boundaries, location of property, access to property, location of work areas, roads, watercourses, proposed grid layouts, camps and other surface facilities. Preferred maps are: a)1:50,000 topographic maps; b)claim maps; c)detailed map of area disturbed; or as required by the District Manager.

Page 651 redacted for the following reason: Not Responsive



Province of Ministry of Energy, Mines and Petroleum Resources

MEMORANDUM

: 354-6125 Fax: 354-6120

To: Art O'Bryan Inspector of Mines (Reclamation)

March 17, 1993

#### Re: Acid Generation Potential at the H.B. Mine Site

I do not have any personal familiarity with the current situation at the abandoned H.B. mine/mill site but have reviewed several geological descriptions of the orebodies and their setting.

All mineralization at the H.B. occurs within dolomite and limestone with minor zones of calcareous quartzite and calcareous argillite associated. All of these host rock types are carbonates or are carbonate-bearing. Pyrite is reported to be the most abundant sulphide in the ore zones but, on a mine scale, it is probably still much less abundant than the total of carbonate minerals. The No. 1 orebody is reported to have been weathered to a depth of about 100 metres meaning that the pyrite in that part of the mine would have been converted by oxidation to limonite prior to any mining. All of this information infers very strongly that any exposed rock within the mine workings or on surface will be acid-consuming due to the predominance of carbonate gangue and host rock. Likewise any waste rock or mill tailings can reasonably be expected to be acidconsuming. The only situation which might lead to possible acid generation on the site would be where sulphide concentrate containing the original high proportion of pyrite had been left behind. If no piles of sulphide concentrate are found, there should be no concern about significant acid generation on the site.

H. Paul Wilton, P. Eng. District Geologist Nelson



## PROVINCE OF BRITISH COLUMBIA MINISTRY OF ENERGY, MINES AND PETROLEUM RESOURCES

#### AMENDMENT TO RECLAMATION PERMIT (Issued pursuant to section 10(6) of the Mines Act S.B.C. 1989)

Permit

M-85

Issued to

NU-DAWN RESOURCES INC. 102 Piper Crescent Nanaimo, B.C. V9T 3G3

for reclamation of surface work located at the:

H.B. MINE, SALMO

is hereby revised subject to the appended conditions.

Amended at Victoria, British Columbia, this 6th day of April in the year 1993.

R.A. Fyles, P. Eng. Chief Inspector of Mines

> Page 653 EGM-2013-00163

Nu-Dawn Resources 1. . Page 2 of 7 Re. amation Permit M-85 Date: April 6, 1993

#### PREAMBLE



An application to amend Reclamation Permit M-85 dated March 5, 1993, from Dr. John C. Errington, an inspector appointed pursuant to section 5 of the Mines Act was filed with the Chief Inspector of Mines on April 6, 1993.

This permit contains the requirements of the Ministry of Energy, Mines and Petroleum Resources for reclamation. It also is compatible, to the extent possible, with the requirements of other provincial ministries for reclamation issues. The amount of security required by this permit and the manner to which this security may be applied, will also reflect the requirements of those ministries. However, nothing in this permit limits the authority of other provincial ministries to set other conditions, or to act independently, under their respective permits and legislation.

Decisions made by staff of the Ministry of Energy, Mines and Petroleum Resources will be made in consultation with other Ministries.

#### AMENDMENTS

The Chief Inspector of Mines (Chief Inspector) of Energy, Mines and Petroleum Resources hereby approves the amended program for protection and reclamation of the land surface and watercourses affected by the mine subject to compliance with the following terms and conditions:

- 1. <u>Reclamation Security</u>
  - (a) The owner, agent or manager (herein called the Permittee) shall cause to be deposited with the Minister of Finance and Corporate Relations within thirty (30) days of receipt of this amendment, an additional security in the amount of One Hundred Thousand dollars (\$100,000.00), bringing the total security for this permit to One Hundred and Ten Thousand dollars (\$110,000.00). The security will be held by the Minister of Finance and Corporate Relations for the proper performance of the approved program and all the conditions of this permit in a manner satisfactory to the Chief Inspector.
  - (b) Beginning on January 1, 1993, and annually thereafter, the security shall be increased at a rate equal to the previous year's annual increase in the British Columbia Consumer Price Index.

Recumation Permit M-85 Date: April 6, 1993

# DRAFT

# SPECIAL CONDITION

# 1. <u>Removal of Assets</u>

Until the security referred to in amended condition 1 above has been placed, there shall be no sale or removal of assets from the H.B. mine property.

# 2. <u>Annual Reclamation Report</u>

By March 31 of each year, an annual reclamation report shall be submitted in a form and containing the information required by the Chief Inspector.

# 3. Land Use

The surface of the land and watercourses shall be reclaimed to the following land use: Recreation and Housing.

# 4. <u>Productivity</u>

The level of land productivity to be achieved on reclaimed areas shall not be less than existed prior to mining on an average property basis unless the Permittee can provide evidence which demonstrates, to the satisfaction of the Chief Inspector, the impracticality of doing so.

# 5. Long-term Stability

Land and watercourses shall be left in a stable condition. To ensure longterm stability, engineered structures including waste dumps, major haul roads, and tailings impoundments shall be constructed and maintained in accordance with part 9 of the Health, Safety and Reclamation Code for Mines in British Columbia.

# 6. <u>Revegetation</u>

Land shall be revegetated to a self sustaining state using appropriate plant species.

np AFT

### 7. <u>Use of Suitable Growth Medium</u>

On all lands to be revegetated, the growth medium shall satisfy land use, productivity, and water quality objectives. All surficial soil material removed for mining purposes shall be saved for use in reclamation programs unless these objectives can be otherwise achieved.

#### 8. <u>Treatment of Structures and Equipment</u>

Prior to abandonment, and unless the Chief Inspector has made a ruling otherwise, such as heritage project consideration or industrial use,

- (a) all machinery, equipment and building superstructures shall be removed,
- (b) concrete foundations shall be covered and revegetated unless, because of demonstrated impracticality, they have been exempted by the Inspector, and
- (c) all scrap material shall be disposed of in a manner acceptable to the Inspector.

#### 9. <u>Waste Dumps</u>

Waste dumps shall be reclaimed to ensure

- (a) long-term stability,
- (b) long-term erosion control,
- (c) water quality released from waste rock dumps to the receiving environment is of a standard acceptable to the Chief Inspector, and
- (d) land use and productivity objectives are achieved.

#### 10. <u>Watercourses</u>

Watercourses shall be reclaimed to a condition that ensures

Nu-Dawn Resources 1.	
Page 5 of 7	

Re. \_mation Permit M-85 Date: April 6, 1993

DRAFT

- (a) long-term water quality is maintained to a standard acceptable to the Chief Inspector,
- (b) drainage is restored either to original watercourses or to new watercourses which will sustain themselves without maintenance, and
- (c) use and productivity objectives are achieved and the level of productivity shall not be less than existed prior to mining unless the Permittee can provide evidence which demonstrates, to the satisfaction of the Chief Inspector, the impracticality of doing so.
- 11. <u>Pits</u>
  - (a) Pit walls constructed in overburden shall be reclaimed in the same manner as waste dumps.
  - (b) Revegetation of pit walls constructed in rock, and/or on steeply sloping footwalls greater than 2:1, is not required. Pit wall seepage may require treatment to ensure that water is of a quality acceptable to the Chief Inspector.
  - (c) Where the pit floor is free from water, and safely accessible, vegetation shall be established.
  - (d) Where the pit floor will impound water and become a watercourse, provision must be made to create a body of water where use and productivity objectives are achieved.

### 12. Tailings Impoundments

- (a) All tailings ponds and impoundment structures shall be reclaimed to the approved land use.
- (b) Prior to mine closure, a report shall be submitted to the Chief Inspector outlining the post-operational state of the dams, dikes, related seepage control, spillway works, mine water deportment, and post-operational monitoring.

DRAFT

- (c) A permanent spillway shall be designed to a standard required by the Chief Inspector and installed prior to final decommissioning of any permanent impoundment structures.
- 13. Roads
  - (a) All roads shall be reclaimed in accordance with land use objectives unless permanent access is required to be maintained.
  - (b) Individual roads will be exempted from the requirement for total reclamation under condition 13(a) if either:
    - (1) the Permittee can demonstrate that an agency of the Crown has explicitly accepted responsibility for the operation, maintenance and ultimate deactivation and abandonment of the road, or
    - (2) the Permittee can demonstrate that another private party has explicitly agreed to accept responsibility for the operation, maintenance and ultimate deactivation and abandonment of the road and has, in this regard, agreed to comply with all the terms and conditions, including bonding provisions, of this reclamation permit, and to comply with all other relevant provincial government (and federal government) regulatory requirements.

# 14. <u>Metal Uptake in Vegetation</u>

- (a) Vegetation shall be monitored for metal uptake.
- (b) Where harmful metal levels are found, reclamation procedures shall ensure that levels are safe for plant and animal life.

# 15. Disposal of Fuels and Toxic Chemicals

Fuels, chemicals or reagents which cannot be returned to the manufacturer/supplier are to be disposed of as directed by the Chief Inspector in compliance with municipal, regional, provincial and federal statutes.

Nu-Dawn Resources Inc. Page 7 of 7 Recamation Permit M-85 Date: April 6, 1993

nn aft

#### 16. Acid Generating Material

All potential acid generating material shall be placed in a manner which minimizes the production and release of acid mine drainage to a level that assures protection of environmental quality.

#### 17. Monitoring

The Permittee shall undertake monitoring programs, as required by the Chief Inspector, to demonstrate that reclamation objectives including land use, productivity, water quality, and stability of structures are being achieved.

#### 18. Safety Provisions

All safety and other provisions of the **Mines Act** shall be complied with to the satisfaction of the Chief Inspector.

#### 19. Responsibility to Reclaim

Any reclamation that remains outstanding under the terms and conditions of Reclamation Permit(s) », at the time of issuance of this amended permit, shall become the responsibility of the Permittee under the terms and conditions of this permit.

#### 20. <u>Closure Plan</u>

The Permittee shall continually develop and evaluate closure options and on or before », shall prepare and submit a revised closure plan, and as soon as possible after that day, the Reclamation Advisory Committee may consider revisions to the permit. This provision shall not be construed as limiting the power of the Minister or the Chief Inspector to amend this permit at any time.

#### 21. Special Conditions:

TO 8-387 5985 P.01 MAR-05-1993 16:42 FROM EMPR-NELSON Province of Ministry of Office address: British Columbia Energy, Mines and Inon Street Petroleum Resources Telephone: (604) 354-6125 Mailing address: 310 Ward Street Nelson, B.C. VIL 554 From Fax No: (604) 354-6120 If there are any problems with the message please call (604) 354-6125 FAX TRANSMISSION COVER SHEET Date Sent: MARCH 5/93 Time: 3.30 Pro. Fax Number: \_\_\_\_\_ VICTORIA-PLEASE DELIVER THE FOLLOWING MESSAGE 7 A: 11 TO: M. MELLOM FROM: Resource Management Branch Ministry of Energy, Mines and Petroleum Resource 310 Ward Street Nelson, B.C. V1L 5S4 Telephone: (604) 354-6125 ptable Reclamation RE: /. This an acc 15 1415 Mine Fina recommend with reclamation Securit otherwise inform. me or be?? Should rect. deposit Sumber of pages sent \_\_\_\_ including cover sheet

MAR-05-1993 16:43	FROM EMPR-NELSON	то	8-387 5985 P.02
<i>*</i> •			1
	MINERAL RESOURC	ES DIVISION	
	RESOURCE MANAGEN		
		MENT DICANCH	MINISTRY OF ENERGY. MINES
	NOTICE OF WO	DV AND	& PETROLEUM RESOURCES.
			REC'D MAD D -
	RECLAMATION PRO		A
	MINERAL PR	OPERTY	NELSON, B.C.
1. NAME OF PROPERTY: NU-	DAWN. RESOURCES. INC H	3. STTR	
	al Number (applicable only to those prope		
(ie. 5//191-0100500-125)		·····	
Reclamation remnit Number, if	previously issued (may be several year	s old)	
Name of Claims; ADA. #ULI	4388, Legal. Tender. M. 1108	23/Tailings.Por	ndSL.36. DL1236
	·····		÷
2. LOCATION: Is any part of thi	s Property in a Recreation Area or Par	k? Yes	x No
			ator responsible for contacting own
	this property privately owner?		alor responsible for confacting during
Are any of the surface rights of			
Are any of the surface rights of Name and address of private land	l owner	*****	
Are any of the surface rights of the Name and address of private land Mining division: . Nolson . Div	lowner A)	l NTS map sheets (ie. )	
Are any of the surface rights of 1 Name and address of private land Mining division: . Nelson . Die Latitude: 49. °.08.	lowner strict	l NTS map sheets (ie. ) Minfile No.	094L/02E)
Are any of the surface rights of 1 Name and address of private land Mining division: . Nelson . Die Latitude: 49. °.08.	lowner strict	l NTS map sheets (ie. ) Minfile No.	094L/02E)
Are any of the surface rights of a Name and address of private land Mining division: . Nelson . Die Latitude: 4.9°08. Access route (from nearest town	to property): From. Salma,B. C.	l NTS map sheets (ie. ) Minfile No. easton.Airpor	094L/02E) (if known) t. Ed., to. Sheep. Creek. Ed.
Are any of the surface rights of a Name and address of private land Mining division: . Nelson . Die Latitude: 4.9°08. Access route (from nearest town	lowner strict	l NTS map sheets (ie. ) Minfile No. easton.Airpor	094L/02E) (if known) t. Ed., toSheep.Creek.Ed.
Are any of the surface rights of 1 Name and address of private land Mining division: . Nelson . Die Latitude: 4.9°08 Access route (from nearest town North, on . Sheep, Cree	l owner: atrict	l NTS map sheets (ie. ) Minfile No. east.on.Airpor 1.up.bill.to.Min	094L/02E) (if known) t. Ed., to. Sheep. Creek. Ed.
Are any of the surface rights of the Name and address of private land Mining division: . Nelson . Div Latitude: 49 ° 08 · Access route (from nearest town North.on, Sheep, Gree OPERATOR/AGENT (Person of	l owner atrict	I NTS map sheets (ie. ) Minfile No. easton.Airpor up.bill.to.Min half of the owner):	094L/02E) (if known) t. EdtoSheep.Creek.Ed.
Are any of the surface rights of 1 Name and address of private land Mining division: . Nelson . Die Latitude: 4.9	I owner atrict	I NTS map sheets (ie. ) Minfile No. 	094L/02E) (if known) t. EdtoSheep.Creek.Ed. e o.:.604-357-2222
Are any of the surface rights of a Name and address of private land Mining division: . Nelson . Die Latitude: 4.9°08 Access route (from nearest town North, on. Sheep, Gree OPERATOR/AGENT (Person of Name:NU-DAWN, RESOURCE Company contact person:Jim.	l owner atrict	I NTS map sheets (ie. ) Minfile No. 	094L/02E) (if known) t. EdtoSheep.Creek.Ed. e o.:.604-357-2222
Are any of the surface rights of a Name and address of private land Mining division: . Nelson . Die Latitude: 4.9	I owner atrict	l NTS map sheets (ie. ) Minfile No. 	094L/02E) (if known) t. RdtoSheep.Creek.Rd. e o604=357-2222 604=357-2516
Are any of the surface rights of 1 Name and address of private land Mining division: .Nelson.Did Latitude: 4.9 ° 08 · Access route (from nearest town North.on.Sheep.Cree OPERATOR/AGENT (Person of Name:NU-DAWN.RESOURCE Company contact person:Jim. Address	I owner strict	I NTS map sheets (ie. ) Minfile No. aast.on.Airpor hill.to.Min half of the owner): 	094L/02E) (if known) t. RdtoSheep.Creek.Rd. e o604=357-2222 604=357-2516
Are any of the surface rights of 1 Name and address of private land Mining division: . Nelson . Die Latitude: 4.9 ° 08 · Access route (from nearest town North . on . Sheep . Dree OPERATOR/AGENT (Person of Name:NU-DAWN . RESOURCE Company contact person:Jim. Address	I owner atrict	I NTS map sheets (ie. ) Minfile No. aast.on.Airpor hill.to.Min half of the owner): 	094L/02E) (if known) t. Ed to. Sheep. Creek. Ed. e. o.:. 604-357-2222 604-357-2516. Salmo
Are any of the surface rights of the Name and address of private land Mining division: . Nolson . Die Latitude: 49. °. 08. Access route (from nearest town North, on. Sheep, Cree OPERATOR/AGENT (Person of Name:NU-DAWN, RESOURCE Company contact person:Jim. Address	I owner strict	I NTS map sheets (ie. ) Minfile No. aast.on.Airpor hill.to.Min half of the owner): 	094L/02E) (if known) t. Edto. Sheep. Creek. Ed. e. o.:. 604-357-2222 604-357-2516. Salmo
Are any of the surface rights of a Name and address of private land Mining division: . Nelson . Div Latitude: 4.9 o.8. Access route (from nearest town North. on. Sheep. Cree OPERATOR/AGENT (Person of Name:NU-DAWN RESOURCE Company contact person:Jim. Address	I owner atrict	I NTS map sheets (ie. Minfile No. Minfile No. 	094L/02E) (if known) t. Edto. Sheep. Creek. Ed. e. o.:. 604-357-2222 604-357-2516. Salmo
Are any of the surface rights of a Name and address of private land Mining division: . Nelson . Div Latitude: 4.9 o.8. Access route (from nearest town North. on. Sheep. Cree OPERATOR/AGENT (Person of Name:NU-DAWN RESOURCE Company contact person:Jim. Address	I owner strict	I NTS map sheets (ie. Minfile No. Minfile No. 	094L/02E) (if known) t. Edto. Sheep. Creek. Ed. e. o.:. 604-357-2222 604-357-2516. Salmo
Are any of the surface rights of a Name and address of private land Mining division: . Nel son . Div Latitude: 4.9 'OB' Access route (from nearest town North, on, Sheep, Gree OPERATOR/AGENT (Person of Name:NU-DAWN, RESOURCE Company contact person:Jim. AddressBox, 369 Province. Brittish, Columbia Signature of Operator/Agent: OWNER: (Title Holder) Name:NU-DAWN, RESOURCES	I owner atrict	I NTS map sheets (ie. ) Minfile No. 	094L/02E) (if known) t. Ed. to. Sheep. Greek. Ed. e. 0604=357-2222 604=357-2516 Salmo roh.6, 1993
Are any of the surface rights of 1 Name and address of private land Mining division: .Nelson. Die Latitude: 4.9 ° 08 · Access route (from nearest town North.on.Sheep.Gree OPERATOR/AGENT (Person of Name:NU-DAWN. RESOURCE Company contact person:Jim. Address	l owner atrict	I NTS map sheets (ie. ) Minfile No. 	094L/02E) (if known) t. Ed to. Sheep. Creek. Ed. e. o.:. 604-357-2222 604-357-2516 Salmo rch. 6, . 1993
Are any of the surface rights of 1 Name and address of private land Mining division: .Nelson. Div Latitude: 4.9. °. 08. Access route (from nearest town North.on. Sheep. Bree OPERATOR/AGENT (Person of Name:NU-DAWN. RESOURCE Company contact person:Jim. Address	I owner atrict	I NTS map sheets (ie. ) Minfile No. 	094L/02E) (if known) t. Edto. Sheep. Creek. Ed. e. o.:.604-357-2222 604-357-2516 Salmo reh.6. 1993
Are any of the surface rights of 1 Name and address of private land Mining division: .Nelson. Div Latitude: 4.9 ° 08. Access route (from nearest town North.on. Sheep. Bree OPERATOR/AGENT (Person of Name:NU-DAWN. RESOURCE Company contact person:Jim. AddressBox. 369. Province. Brittish. Columbia Signature of Operator/Agent: Name:NU-DAWN. RESOURCES Address102. Piper. Creace ProvinceBritish.Columbia	l owner atrict	I NTS map sheets (ie. ) Minfile No. 	094L/02E) (if known) t. Ed to. Sheep. Creek. Ed. e. o.:.604-357-2222 604-357-2516 Salmo reh.6. 1993
Are any of the surface rights of 1 Name and address of private land Mining division: .Nelson. Div Latitude: 4.9 OB. Access route (from nearest town North.on.Sheep.Bree OPERATOR/AGENT (Person of Name:NU-DAWN. RESOURCE Company contact person:Jim. AddressJim. Address	I owner atrict	I NTS map sheets (ie. Minfile No. Minfile No. Minfile No. Minfile No. Maint half of the owner): Telephone N Fax No. City Date: Man City Nans Telephone No	094L/02E) (if known) t. Ed to. Sheep. Creek. Ed. e. o.:. 604-357-2222 604-357-2516 Salmo rch. 6, 1993 Direch. 6, 1993 Date: March. 6/93
Are any of the surface rights of 1 Name and address of private land Mining division: .Nelson. Div Latitude: 4.9 OB. Access route (from nearest town North.on.Sheep.Gree OPERATOR/AGENT (Person of Name:NU-DAWN RESOURCE Company contact person:Jim. Address	l owner: strict	I NTS map sheets (ie. Minfile No. Minfile No. Minfile No. Minfile No. Maint half of the owner): Telephone N Fax No. City Date: Man City Nans Telephone No	094L/02E) (if known) t. Edto. Sheep. Creek. Ed. e. o.:.604-357-2222 604-357-2516 Salmo rch.6, 1993

7.	<b>EXPLORATION WORK</b> (Brief Description, if	anplicable)		
	Blasting		Geophysical	
	Geochemical		Clearing Trees	
	Prospecting		Geological	and a second second second second second second second second second second second second second second second
	Line cutting (distance, width, method)			
	Campsite: Length: m Width:			
	If Blasting, give details of explosives, magazines,	etc		
_	Give number of existing explosives storage permit	t	Name of Blaster:	
8.	WATER SUPPLY (subject to approval under the	Water Act)		a i a e a construction a second a second a second a second a second a second a second a second a second a second
	Describe the source of water supply			
	Pump size:		ion of water intake (show on plan)	10 01 00 01 MIL A CHORES CADE 100 100 100 100 100 100 100 100 100 10
~ ~~				
».	Describe treatment and disposal facilities (size of s	ettling pond, recy		. Show on plan.
0.	Describe treatment and disposal facilities (size of s ESTIMATED NUMBER OF WORKERS ON S	ettling pond, recy	cling, distance to nearest stream, etc)	. Show on plan.
0.	Describe treatment and disposal facilities (size of s ESTIMATED NUMBER OF WORKERS ON S EQUIPMENT LIST	ettling pond, recy	cling, distance to nearest stream, etc)	. Show on plan.
0.	Describe treatment and disposal facilities (size of s ESTIMATED NUMBER OF WORKERS ON S EQUIPMENT LIST Note: all motorized equipment to comply with the l	ettling pond, recy ITE (including C Mining Code	cling, distance to nearest stream, etc)	. Show on plan.
0.	Describe treatment and disposal facilities (size of s ESTIMATED NUMBER OF WORKERS ON S EQUIPMENT LIST Note: all motorized equipment to comply with the l Number and Type Size	ettling pond, recy ITE (including C Mining Code (Capacity	ontractors):	. Show on plan.
0.	Describe treatment and disposal facilities (size of s ESTIMATED NUMBER OF WORKERS ON S EQUIPMENT LIST Note: all motorized equipment to comply with the l Number and Type Size a)	ettling pond, recy ITE (including C Mining Code (Capacity	cling, distance to nearest stream, etc)	. Show on plan.
0.	Describe treatment and disposal facilities (size of s ESTIMATED NUMBER OF WORKERS ON S EQUIPMENT LIST Note: all motorized equipment to comply with the l Number and Type Size a)	ettling pond, recy ITE (including C Mining Code (Capacity	<pre>cling, distance to nearest stream, etc)</pre>	. Show on plan.
0.	Describe treatment and disposal facilities (size of s ESTIMATED NUMBER OF WORKERS ON S EQUIPMENT LIST Note: all motorized equipment to comply with the l Number and Type Size a)	ettling pond, recy ITE (including C Mining Code (Capacity	cling, distance to nearest stream, etc)         ontractors):	Size/Capacity
0.	Describe treatment and disposal facilities (size of s ESTIMATED NUMBER OF WORKERS ON S EQUIPMENT LIST Note: all motorized equipment to comply with the l Number and Type Size a)	ettling pond, recy ITE (including C Mining Code (Capacity	<pre>cling, distance to nearest stream, etc)</pre>	Size/Capacity
0.	Describe treatment and disposal facilities (size of s ESTIMATED NUMBER OF WORKERS ON S EQUIPMENT LIST Note: all motorized equipment to comply with the l Number and Type Size a)	ettling pond, recy ITE (including C Mining Code /Capacity	cling, distance to nearest stream, etc)         contractors):	Size/Capacity

Page 662 EGM-2013-00163 ÷

.

TO

Mananaita.	# of parals		T		TT T' 3.1	
campsue.	# or people	**********	Length:	······ []]	Width:m	Area
Road access	s construction:	Total length:	m	Approxim	ate width: m	Area: m <sup>2</sup>

#### 14. SURFACE DISTURBANCE ON MINERAL CLAIMS

(a)	Scilling por	ada: #	1430	Leuglu m	Width:m	Area: m <sup>2</sup>
(b)	Road const	ruction:	Tot	tal length m	Width:m	Area: m <sup>2</sup>
(c)	Drilling:	# of sites:	Depth:	Leugth: m	Width:m	Area:
(d)	Trenching	# of trenches:	Depth:	Length: m	Width:m	Area:
(e)	Test pits:	# of pits:	Depth:	Length: m	Width:m	Area: m <sup>2</sup>
(f)	Campsite:	# of people		Length: m	Width:m	Area m <sup>2</sup>
(g)	Undergroun	id work: area of surface	disturbance	Length: m	Width:m	Area:
(h)	Rock dumps	s: area of surface disturb	ance	Length: m	Width:	Area:
(i)	Other: descr	ilæ. Area:				m <sup>2</sup>
		TOTAL SU	RFACE AREA DIS	TURBED ON MINER	AL CLAIMS THIS YE	AR:
PRI	OR DISTUR	BANCE ON CLAIM		PLANNED REC	LAMATION THIS YE	AR: m <sup>2</sup>
*****	BA	LANCE OF UNRECL	AIMED DISTURBA	NCE AT THE END O	F PROJECT THIS YE.	AR:m <sup>2</sup>

#### 15. PRESENT STATE OF LAND ON WHICH WORK IS PROPOSED

Present land use: Garatakars. for. Sacurity. of. Plant	Type of vegetation:
Access roads (present use and condition) Roadsare.in.good.condition,.	Access for Ceretakers
Old workings (location, condition) N/A Adits. closed. with doors.	*********

16.	RECLAMATION PROGRAM: Proposed use of land after reclamation: Recreation and Housing
	Describe protective measures and proposed site reclamation methods with reference to the items listed below.
	Topsoil handling (where applicable): Topsoil.to.be.put.over.old.mill.bases.and.other.buildings
	Camp sites: 7. Houses. to be left for new owners. to do with whatever they plan. And sheds and office, warehouse. Trenches, drill sites, major excavations:Glory. Hole above mill site, new chain link fence. to be put around complete opening. Roads: Boads. are in good condition.
	Revegetation of disturbed areas:
	Waste dumps:
	AdisBoth.adits.to.be.filled.in.with.drill.core.and.topsoil.put.ovar.adits
	Drill core storage . Core. storage . building. to . be . taken . down, . core put . into . adits
	Other:Concentrator, Leach. Plant, Refinery, Oil. Storage. Shed, Mine. Dry, Gompressor. Shop,
	.Mine Shop. Machine Shop. All to be taken down, all machinery removed from property.
	Tailings Damwe will place coarse material on the upstream face as required by Geotechnical Inspector, R. T. Martin. EGM-2013-00163

MARTOSTISSS IB:45 FRUM EMPRETSUM	10	0-307 3903 F.03
		r - N
parties and a second second second second second second second second second second second second second second		
17. IRANII/M/THORIJM		
Is any part of this property designated as a Uranium/Thorium area?	Yes X No	
If yes - has a survey been completed?YesNo		

EMOD HELDON

MOD DE

Note: if underground exploration or development is contemplated, an additional 'Underground Exploration Work Application for Approval' form must be completed.

This application will be returned if it is not accompanied by a legible map showing location of claim posts, property boundaries, location of property, access to property, location of work areas, roads, watercourses, proposed grid layouts, camps and other surface facilities. Preferred maps are: a)1:50,000 topographic maps; b)claim maps; c)detailed map of area disturbed; or as required by the District Manager.



TOTAL P.05

File Note: H.B. Mine

March 4, 1993

File: M-85 /

I talked to Red Mellor and Art O'Bryan.

Red will inform Nor-Quest that no work (including removal of assets) can take place until an application has been submitted under Section 10 of the Mines Act.

Once we have the application we can amend the existing permit, establish an appropriate security and get them working on the reclamation as they dissmantle the site.

We can set up an escrow account

Not Responsive if we need

to

Dr. J.C.Ervington, P. Ag. Manager, Reclamation and Permitting

cc Greg McKillop

111

Othre address:

Mailing address:

310 Ward Street Velson, B.C. V1L 5S4

File: H.B. MILL

ernon Street 10. JR. D.C. VIL 400

Telephone: (604) 354-6125

14675-



Province of British Columbia Ministry of Energy, Mines and Petroleum Resources



Wilmi tos Reig-Jeil Paper

Fax: 354-6120 Tel: 354-6131

March 3, 1993

Mr. Raynerd Carson, Pres. Nor-Quest Resources Ltd. 102 Piper Crescent Nanaimo B.C. V9T 3G3

Dear Mr. Carson:

#### Re: H.B. Mill and Tailings Pond, Nelson Mineral Division

This letter is written confirmation of the meeting in my office on March 2, 1993, where you requested information on Mines Act requirements for selling off the H.B. Mill machinery and milling equipment.

Prior to the sale and removal of any of the milling equipment and machinery on this mining property, and any other work, filing of a Notice of Work and Reclamation Plan, and a permit pursuant to the Mines Act, Section 10, is required.

Section 10(1) of the Mines Act states: "Before commendement of any work in, on, or about a mine, the owner, agent or manager shall apply for and obtain a permit from the Chief Inspector of Mines and shall, as part of the application, file with the District Inspector a plan outlining details of the proposed work and a program for the protection and reclamation of the land and watercourses affected by the mine, including the information, particulars, and maps established by the regulations or the Code".

At the present time, Nor-Quest Resources does not have any permit as required by the Mines Act to conduct any work on this property.

Also, pursuant to the Mines Act Section 10(8), a valid and subsisting permit shall be maintained and no work shall take place in or about a mine without one.

As well as a permit to proceed with work on a mineral property, supervisory requirements of actual work performed

..../2

Page 666 EGM-2013-00163 Page 2

must also be complied with. Work that will involve dismantling and removing equipment from the mine site, is subject to compliance with the Occupational Health & Safety Code Section 1.12.5., where the manager shall ensure that every worker is under the supervision of the holder of a Supervisors Certificate.

Pursuant to the OHS Code Section 1.12.6, the manager may designate in writing a qualified person to act as a supervisor for a period not exceeding six months. From mv experience your present n.p. Mill property caretaker/manager Mr. Jim Wadsworth would qualify for this supervisor requirement.

Any work to be conducted underground, such as rail removal from the Ymir Mine, will require the supervision of a certified Underground Shift Boss. This work will also require submission of a Notice of Work and Reclamation Program and approval or permitting pursuant to the Mines Act Section 10.

As you indicate no future mining work is planned, and the H.B. Mine property is to be sold for residential or recreation interests, final reclamation of the mine adits, any other mine openings, waste dumps, drill core storage, roads, mill buildings, and tailings pond and dyke will have to be addressed in the Reclamation Plan section of your Notice of Work submission. Use extra paper to provide essential details, if necessary for this report.

Part 10 of the OHS Code details standards and requirements for reclamation and closure. As discussed, sections 10,6.3 through to 10.6.7 will all be particular areas of concern.

Pursuant to the Mines Act Section 10(4), the Chief Inspector may, as a condition or issuing a permit require that the owner, agent, or manager give security in the amount, form, and subject to conditions specified by the Chief Inspector.

Final reclamation and long term stability of the tailings pond and dyke will be a prime concern. This area will be subject to inspections and regulating by Mr. T. Eaton, Manager of MEMPR Geotechnical Engineering section. Pursuant to the OHS Code Section 9.3.5, a report to the Chief Inspector of Mines for his acceptance, listing steps that will be taken to ensure structural stability and run-off control will be required.

..../3

Page 3

Final reclamation of the mine surface areas, dumps, major excavations, mill buildings, tailings area, roads etc.; (as detailed in the OHS Code Sections 10.5.3 to 10.5.6) will be subject to regulating and inspections by myself, Mr. S. Wuschke, District Manager/Engineer Occupational Health and Safety, and Mr. A. O'Bryan, Reclamation Inspector of Mines. Also Waste Management and Water licenses issued for the property through Ministry of Environment, will be subject to their reviews.

I am optimistic, as indicated by your co-operative reception to reclamation and closure requirements as discussed, that this work should proceed and be completed to the satisfaction of all.

s.22

Yours very truly,

Hellor

M.A. Mellor District Manager, EIM,

MAM/sb

c.c : J.Errington, Manager, Reclamation & Permitting

- T. Eaton , Manager, Geotechnical Engineering
  - S. Wuschke, District Manager/Engineer, OHS
- A. O'Bryan, Reclamation Inspector of Mines R. Crozier, Manager, Waste Management, MOELP

Page 668 EGM-2013-00163

TOTAL P.04

FEB-25-1993 16:59 FROM EMPR-NELSON TO 8-387 5985 P.01 Province of Ministry, Cree address; British Columbia Ener . and ernon Street Pet da Neison, B.C. VIL 4E6 i nources Telephone: (604) 354-6125 Mailing address: 310 Ward Street Nelson, B.C. VIL 504 From Fax No: (604) 354-6120 If there are any problems with the message please call (604) 354-6125 口清清 **V TRANSMISSION COVER SHEET** Jale Sent: Time: Fax Number: PLEASE DELIVER THE FOLLOWING MESSAGE YYAN Atera 1LLO TO: 1. MELLON M. FROM: **Resource Management Branch** Ministry of Energy, Mines and Petroleum Resources 310 Ward Street Nelson, B.C. V1L 5S4 Telephone: (604) 354-6125 MILL CLAMA RE: Number of pages sent 🔿 including cover sheet

Page 669 EGM-2013-00163

MEMORANDUM



Province of British Columbia

inistry of Energy, Mines and Petroleum Resources

February 25, 1993

Mr, G. McKillop Assistant Director Environmental Impact Management

Re: H.B. Mine, H.B. Mill, and H.B. Tailings Pond

It has come to my attention that Nor - Quest Resources Ltd. are in the process of selling off the H.B.concentrator equipment and machinery.

My source informs that a buyer from South America has been interested, but this may mean nothing at this time. The equipment was reported to be listed with Nelson Machinery for sale.

My telephone call to this firm, as a potentially interested party, confirmed this. The entire plant is for sale and is listed with Nelson Machinery. This includes the 1200 tpd grinding and flotation mill and also the 100 tpd cyanide gold circuit, installed new, by David Minerals and never used.

I was informed Nelson Machinery is currently drawing up a new catalogue that includes this entire mill, to be sold in pleces or as a unit.

Also it has been reported there has been some transferring of land ownership to another Nor - Quest Company, to Raynerd Resources, whatever this means. A Mr. Raynerd Carson, who lives or has an office in Nanaimo, is President of Nor -Quest Resources. Apparently there are back taxes owing on the property, that the equipment sale is intended to alleviate.

This news if true, concerns me knowing there are outstanding reclamation obligations on this property. This includes the Mill infrastructure, tailings pond, and very likely some mine openings, that could involve a glory hole to surface.

The last inspection report on file for the concentrator is one of mine, dated October 23, 1986, where mill reagents were ordered removed and the mine portal ordered sealed. Freeboard of the tailings pond was noted to be 10 feet, and the dam noted to appear stable. The mill chemicals etc. were removed at that time.



Province of Jir British Columbia Pat

inistry of Energy, Mines and Petroleum Resources TO

### MEMORANDUM

page 2,

The last recorded Geotechnical Inspection of the property by T. Martin, was September 28, 1987. Terry's one concern was undercutting of the upstream face of the dam becoming significant and requiring course gravel and cobble-sized protection being placed before his next inspection. There is no record in the file of this work being done. Mr. Greg. Carriere the Mine Engineer at the time, informs me this work was never done, as management avoided it.

I have discussed my concerns with Steve Wuschke. He has scheduled a property inspection tomorrow, to check out mine openings, and conditions in the mill. The tailings pond will still be snow covered.

I understand Ted Hall took action to ensure assets were guaranteed available for reclamation obligations that involved placing a lien on all of the mill equipment on a similar situation.

I recommend we take similar action with this property without delay.

ell

M.A.Meilor District Manager, EIM. Nelson.

> Page 671 EGM-2013-00163

> > TOTAL P.03



FEB-26-1993 10:18 FROM EMPR-NELSON TO 8-387 5985 Province of Ministry of C"" ?? address: British Columbia Energy, Mines and ernon Street Neison, B.C. VIL 4E6 Petroleum Resources Telephone: (604) 354:6125 Mailing address: 310 Ward Street Nelson, B.C. VIL 554 From Fax No: (604) 354-6120 If there are any problems with the message please call (604) 354-6125 FAX TRANSMISSION COVER SHEET 100 26/93 Time: 9.30 Am Date Sent: VICTORIA Fax Number: PLEASE DELIVER THE FOLLOWING MESSAGE Y.IST.IES hn TO: M. A. mellor elson FROM: Resource Management Branch Ministry of Energy, Mines and Petroleum Resources 310 Ward Street Nelson, B.C. V1L 5S4 Telephone: (604) 354-6125 how. I have Vecessary A RE: Timeson 3 Number of pages sent \_ including cover sheet

TO



Province of dia British Columbia

Ainistry of Energy, Mines and Petroleum Resources

## MEMORANDUM

February 25, 1993

Mr, G. McKillop Assistant Director Environmental Impact Management

Re: H.B. Mine, H.B. Mill, and H.B. Tailings Pond

It has come to my attention that Nor - Quest Resources Ltd. are in the process of selling off the H.B.concentrator equipment and machinery.

My source informs that a buyer from South America has been interested, but this may mean nothing at this time. The equipment was reported to be listed with Nelson Machinery for sale.

My telephone call to this firm, as a potentially interested party, confirmed this. The entire plant is for sale and is listed with Nelson Machinery. This includes the 1200 tpd grinding and flotation mill and also the 100 tpd cyanide gold circuit, installed new, by David Minerals and never used.

I was informed Nelson Machinery is currently drawing up a new catalogue that includes this entire mill, to be sold in pieces or as a unit.

Also it has been reported there has been some transferring of land ownership to another Nor - Quest Company, to Raynerd Resources, whatever this means. A Mr. Raynerd Carson, who lives or has an office in Nanaimo, is President of Nor -Quest Resources. Apparently there are back taxes owing on the property, that the equipment sale is intended to alleviate.

This news if true, concerns me knowing there are outstanding reclamation obligations on this property. This includes the Mill infrastructure, tailings pond, and very likely some mine openings, that could involve a glory hole to surface.

The last inspection report on file for the concentrator is one of mine, dated October 23, 1986, where mill reagents were ordered removed and the mine portal ordered sealed. Freeboard of the tailings pond was noted to be 10 feet, and the dam noted to appear stable. The mill chemicals etc. were removed at that time.

Province of

inistry of

British Columbia Energy, Mines and Petroleum Resources MEMORANDUM

TO

page 2,

The last recorded Geotechnical Inspection of the property by T. Martin, was September 28, 1987. Terry's one concern was undercutting of the upstream face of the dam becoming significant and requiring course gravel and cobble-sized protection being placed before his next inspection. There is no record in the file of this work being done. Mr. Greg. Carriere the Mine Engineer at the time, informs me this work was never done, as management avoided it.

I have discussed my concerns with Steve Wuschke. He has scheduled a property inspection tomorrow, to check out mine openings, and conditions in the mill. The tailings pond will still be snow covered.

I understand Ted Hall took action to ensure assets were guaranteed available for reclamation obligations that involved placing a lien on all of the mill equipment on a similar situation.

I recommend we take similar action with this property without delay.

Kellot M.A.Mellor

District Manager, EIM. Nelson.

CC. A. O'Bryon T. Eaton S. wuschke. J. Errington



Page 674 EGM-2013-00163

TOTOL D DT



HERET HALLAN

**Bank of Montreal** 

Corporate and Government Banking Group First Back Ticesta 595 Burrard Streat P O Bas 19400 Versionsa, ISC V7X, ICS

Lowpinse No. August 10, 1990

Ministry of Energy, Mines and Petroleum Resources Room 105, 525 Superior St., Victoria, B. C. V8V 1X4

Attn: Carol Howell

Dear Sirs

Letters of Credit No.

s.21

Further to our telephone conversation today, we enclose photocopies of the subject letters of credit. We also enclose copies of letters from your office addressed to Cominco, dated March 17, 1986 stating that the original letters of credit would be held in your office.

Yours truly. G. M. Fox,

Manager, Credit Administration

Page 676 redacted for the following reason: s.21 Province of British Columbia



Ministry of Energy, Mines and Petroleum Resources

Office address: 10<sup>i</sup> non Street Nusion, B.C. V1L 4E6 Phone: (604) 354-6125 Mailing address: 310 Ward Street Nelson, B.C. V1L 5S4

January 11, 1989

Our File: 14675-50/

Mr. M. Henningson Manager Cominco Ltd. P.O. Box 2000 Kimberley, B.C. VIA 2G3

Dear Sir:

Re: Annual Reclamation Report, Reclamation Permit M-85

The Annual Reclamation Report for the year 1988 and plans for the 1989 program are due March 31, 1989. Please use the enclosed report format as a checklist and modify the organization of the report to satisfy your particular program.

Document activities using a map or airphoto base at a convenient scale; a scale of 1:10,000 is suggested.

Ensure that the enclosed tables, which summarize surface disturbance and reclamation, are completed accurately.

Please submit three copies of your Reclamation Report, two to this office and one to Dr. J.C. Errington, Head of Reclamation, Rm. 105, 525 Superior St., Victoria, B.C. V8V 1X4.

Yours, very truly,

A.L. O'Bryan Inspector of Mines (Reclamation)


JCE/ALO/db Enclosure

cc: A. Whale, District Inspector & Resident Engineer J.C. Errington, Head of Reclamation

COMPANY <u>Cominco Ud</u> ADDRESS <u>Salma</u> , 3.C. <u>Vag</u> <u>3.C.</u> <u>Vag</u> <u>120</u> MANAGER <u>Ma</u> <u>R. Lyka</u> PERMIT NO. <u>M. 85</u> BONDINC <u>M. 85</u> BONDINC <u>M. 85</u> BONDINC <u>M. 85</u> BONDINC <u>M. 85</u> BONDINC <u>M. 85</u> BONDINC <u>M. 85</u> BONDINC <u>M. 85</u> BONDINC <u>M. 85</u> BONDINC <u>M. 85</u> BONDINC <u>M. 85</u> BONDINC <u>M. 85</u> BONDINC <u>M. 85</u> BONDINC <u>M. 85</u> BONDINC <u>M. 85</u> BONDINC <u>M. 85</u> BONDINC <u>M. 85</u> CAZETTED <u>May 1, 1978</u> <u>NEWSPAPER: May 1, 1978</u> 3. ADVISORY COMMITTEE APPROVAL <u>Torce 5, 9578</u> 4. MINISTER APPROVAL <u>Jure 30, 6478</u> 5. ORDER-IN-COUNCIL - DATE APPROVED <u>2411</u> <u>Sept 7 /78</u> 6. LETTER REQUESTING BONDING <u>STANS THE</u> 7. BONDING RECEIVED <u>SAME</u> 8. PERMIT SENT <u>May 1, 1978</u> 9. RENEWAL <u>PERZYACIOCANT</u> 10. REMARKS	MJ	INE <u>IJ. B. Mine</u>
MANAGER MR R. LAYKO MANAGER MR R. LAYKO PERMIT NO. M. 85 BONDING # 10,000.00 DATES: 1. REPORT SUBMITTED <u>Decarder 20 -777</u> 2. GAZETTED <u>May 1,1978</u> NEWSPAPER: <u>May 1,1978</u> 3. ADVISORY COMMITTEE APPROVAL <u>June 5,1978</u> 4. MINISTER APPROVAL <u>June 30, 6178</u> 5. ORDER-IN-COUNCIL - DATE APPROVED <u>2411</u> <u>Jeps 7/78</u> 6. LETTER REQUESTING BONDING <u>STIPUS THE</u> 7. BONDING RECEIVED <u>SAME</u> 8. PERMIT SENT <u>DOL ONDER</u> 14, 1978 9. RENEWAL <u>PERMADENT</u>	cc	MPANY Cominco Utd.
MANAGER Ma R Linko PERMIT NO. M-85 BONDING 10,000.00 DATES: 1. REPORT SUBMITTED <u>Decade 20, 777</u> 2. GAZETTED <u>May 1978</u> NEWSPAPER: <u>May 1978</u> 3. ADVISORY COMMITTEE APPROVAL <u>Tone 509.78</u> 4. MINISTER APPROVAL <u>June 30, 9178</u> 5. ORDER-IN-COUNCIL - DATE APPROVED <u>2411</u> <u>Jept 7/78</u> 6. LETTER REQUESTING BONDING <u>STIPUS THE</u> 7. BONDING RECEIVED <u>SAME</u> 8. PERMIT SENT <u>I ON ONDER</u> 14, 1978 9. RENEWAL <u>PERSMANCENT</u>	AD	DRESS <u>Salma, B.C.</u>
PERMIT NO. <u>M. 85</u> BONDING <u>A 10, 100, 000</u> DATES: 1. REPORT SUBMITTED <u>Decorder 21, 777</u> 2. GAZETTED <u>May 1, 1978</u> NEWSPAPER: <u>May 1, 1978</u> 3. ADVISORY COMMITTEE APPROVAL <u>Tone 5, 9, 778</u> 4. MINISTER APPROVAL <u>June 30, 6178</u> 5. ORDER-IN-COUNCIL - DATE APPROVED <u>24-11 Jept 7/78</u> 6. LETTER REQUESTING BONDING <u>STUDY S THE</u> 7. BONDING RECEIVED <u>SAME</u> 8. PERMIT SENT <u>May 1, 1978</u> 9. RENEWAL <u>PERMADENT</u>		_10G-1Z0
BONDING <u>10, 100, 000</u> DATES: 1. REPORT SUBMITTED <u>Decarcher 20, 777</u> 2. GAZETTED <u>May 1, 1978</u> NEWSPAPER: <u>May 1, 1978</u> 3. ADVISORY COMMITTEE APPROVAL <u>Troce 5, 9, 78</u> 4. MINISTER APPROVAL <u>Troce 5, 9, 78</u> 5. ORDER-IN-COUNCIL - DATE APPROVED <u>2411</u> <u>Dept 7/78</u> 6. LETTER REQUESTING BONDING <u>STAVS THE</u> 7. BONDING RECEIVED <u>SAME</u> 8. PERMIT SENT <u>IOUCOMER 14, 1978</u> 9. RENEWAL <u>PERSMANCENT</u>	MAI	NAGER MR R. Wykos
DATES: 1. REPORT SUBMITTED <u>Deconder 22 777</u> 2. GAZETTED <u>May 1, 1978</u> <u>NEWSPAPER: May 1, 1978</u> 3. ADVISORY COMMITTEE APPROVAL <u>Tone 5, 978</u> 4. MINISTER APPROVAL <u>Tone 30, 6178</u> 5. ORDER-IN-COUNCIL - DATE APPROVED <u>2411</u> <u>Dept 7/78</u> 6. LETTER REQUESTING BONDING <u>STRAVS THE</u> 7. BONDING RECEIVED <u>SAME</u> 8. PERMIT SENT <u>Outomber</u> 14, 1978 9. RENEWAL <u>PERSMANENT</u>	PEI	MIT NO. <u>M-85</u>
DATES: 1. REPORT SUBMITTED <u>Deconder 22 777</u> 2. GAZETTED <u>May 1, 1978</u> <u>NEWSPAPER: May 1, 1978</u> 3. ADVISORY COMMITTEE APPROVAL <u>Tone 5, 978</u> 4. MINISTER APPROVAL <u>Tone 30, 6178</u> 5. ORDER-IN-COUNCIL - DATE APPROVED <u>2411</u> <u>Dept 7/78</u> 6. LETTER REQUESTING BONDING <u>STRAVS THE</u> 7. BONDING RECEIVED <u>SAME</u> 8. PERMIT SENT <u>Outomber</u> 14, 1978 9. RENEWAL <u>PERSMANENT</u>	BON	$101NG \_ \ddagger 10, 1000, co$
<ol> <li>REPORT SUBMITTED <u>Decades 22 -777</u></li> <li>GAZETTED <u>May 1, 1978</u> <u>NEWSPAPER: May 1, 1978</u></li> <li>ADVISORY COMMITTEE APPROVAL <u>Torce 5, 978</u></li> <li>MINISTER APPROVAL <u>June 30, 9178</u></li> <li>MINISTER APPROVAL <u>June 30, 9178</u></li> <li>ORDER-IN-COUNCIL - DATE APPROVED <u>2411 June 1/28</u></li> <li>ORDER-IN-COUNCIL - DATE APPROVED <u>2411 June 7/78</u></li> <li>LETTER REQUESTING BONDING <u>STRAUS THE</u></li> <li>BONDING RECEIVED <u>SAME</u></li> <li>PERMIT SENT <u>ON Order 14, 1978</u></li> <li>RENEWAL <u>PERMIDIENT</u></li> </ol>		
<ol> <li>CAZETTED May 1978 NEWSPAPER: May 1978</li> <li>ADVISORY COMMITTEE APPROVAL Tone 50978</li> <li>MINISTER APPROVAL JUNE 30, 6178</li> <li>ORDER-IN-COUNCIL - DATE APPROVED 2411 Dept 7/78</li> <li>LETTER REQUESTING BONDING STRAVS THE</li> <li>LETTER REQUESTING BONDING STRAVS THE</li> <li>BONDING RECEIVED SAME</li> <li>PERMIT SENT (ON Oncomber 14, 1978)</li> <li>RENEWAL PERMADENT</li> </ol>		
<ul> <li>ADVISORY COMMITTEE APPROVAL</li></ul>		
5. ORDER-IN-COUNCIL - DATE APPROVED 2411 Sept 7/78 6. LETTER REQUESTING BONDING <u>STATUS THE</u> 7. BONDING RECEIVED <u>SAME</u> 8. PERMIT SENT <u>CONTEMPORALING</u> 14, 1978 9. RENEWAL <u>PERMANENT</u>		
6. LETTER REQUESTING BONDING <u>STRAVS</u> <u>THE</u> 7. BONDING RECEIVED <u>SAME</u> 8. PERMIT SENT <u>JOURNER</u> 14, 1978 9. RENEWAL <u>PERMICIPENT</u>	4.	MINISTER APPROVAL JUNE 30, 978
6. LETTER REQUESTING BONDING <u>STAVS</u> <u>THE</u> 7. BONDING RECEIVED <u>SAME</u> 8. PERMIT SENT <u>JOURNER 14 1978</u> 9. RENEWAL <u>PERMANENT</u>	5.	ORDER-IN-COUNCIL - DATE APPROVED 2411 Sept 7/78
8. PERMIT SENT <u>() ON ember 14, 1978</u> 9. RENEWAL <u>PERMADENT</u>		
9. RENEWAL PERMANENT	7.	BONDING RECEIVEDSAME
	8.	PERMIT SENT []OVER ben 14, 1978
0. REMARKS	9.	RENEWALPERMANENT
	.0.	REMARKS

: 11. 264-4109

Page 679 redacted for the following reason: Not Responsive



Receipt is acknowledged of your new security described as:

s.21

which will be retained in this office for safekeeping.

By copy of this letter, we are asking the Registrar of Securities to forward your old securities described as:

s.21


to you.


Yøurs very truly, J. G. Errington, P.Ag. Senvior Reclamation Inspector JCE:st

cc: Registrar of Securities, Ministry of Finance

Bank of	Montrea	1, Ir	iternatio	onal	Servio	ce Ce	entre	(B.C.)
Treasury	Group,	595	Burrard	St.	P.O.	Box	49350	)
Vancouve	r, B.C.	V72	C 1L5					


DATEP	0.0. 2.0.00	REGISTERED MAIL	NOTE:
	20, 1995 I RELEASED TO	NUMBER	- M65
			Besithan
	hr. G. H. So:		
	Co-Ordinator	, Banking	
	Comince Lfd 200 Granville	e Street	
	Vencouver, B. VGC 282	.C.	
] Please have signal.	s secondics index by It Bidgs - Vistoria, B ele of tratisferos gua vici on associationent 6	Inco. Kalana da anti-	g pink copy to Registrar of Securitos, Provincial
VALUE	DES	CRIPTION (RECEIVED)	REGISTRATION
		-	٨
			614
_			
17 We have transfer 19 We are releasing		e listed below by environg pink co. Performent Bidgs. Victoria B.C. V P1 reporting and are releasing the in ritids to your attest	
VALUE		DRIPTION (RELEASED)	REGISTRATION
			BEGISTRATION.
ð. 35. ¢€	1 - 3.9 55 Kr	ic of Locale 102 des Heros	
	14. Q. 1. 1973		
	COLUMN A REAL		
	ia in te	in in the second second	$z_{\mu} = \langle \overline{\chi}^{\prime} \overline{\chi}^{\prime} D \rangle \langle \psi^{\prime} U D \rangle \langle \overline{\chi}^{\prime} D \rangle \langle \overline{\chi}^{\prime} D \rangle$
TLAT MILLION	IVELSALE	SIGNATION HIM REGISTIN	For REContract Page 681






22. 21243-1249 186 Department No. 97 P.H.No. 22. W. KOOTENAY District Description land Grant For whom Surveyed L.1243 NELSON and FORT SHEPHERD -1-1244 R.R.Co. . 15. Surveyed by H. B. Smith P.L.S. Fely and March 1897 Plotted april 1897 By whom Hamford Survey Gazetted 22 a april 1897


Page 684 EGM-2013-00163



Page 685 EGM-2013-00163



Page 686 EGM-2013-00163



Page 687 EGM-2013-00163 Pages 688 through 690 redacted for the following reasons: Not Responsive

14795-40/HB

42

INTEROFFICE MEMORANDUM

Created:	15-Apr-1997 10:35am PDT
Sent:	15-Apr-1997 10:45am PDT
From:	Tim Eaton of EI
	TEATON
Title.	Manager - Geotechnical Engineeri
Dept:	Employment & Investment
Tel No:	952-0485

TO: John Errington of EL

( CHOWELL )

( JERRINGTON )

Subject: HB Mine M-85

CC: Carol Howell of EI

FYI and M-85 file.

Theresa checked the mineral title of the HB mine as per John's suggestion to me. Title ownership was confirmed by Ron Stewart of MTB.

Crown Grant Title is owned by:

Nu-Dawn resources Inc. 102 Piper Cres Nanaimo, BC V9T 3G3

Contact: Ray Carson 250-756-0291 or 756-0298

f am sending a minfile report to M-85.

Tim

Pennit still in Cominco's nome.



Province of British Columbia Petroleum Resources

Ministry of

# MEMORANDUM

To: J. B. C. Lang

11050-20114.13 To: J. B. C. Lang David Mingrals - MB minit Our File: H. B. Mine File . subject: <u>"Safe" storage level of tailings</u> Date: June 21, 1982

Further to my memo of March 1st on this matter, I have been trying to devise some sort of equation that would enable me to determine quickly the mean equivalent storage level of tailings. You may recall that I have recommended that the stacking of tailings above the crest of the dam was permissable provided that in the event of liquifaction the levelled tailings would still not reach a level any higher than the present overflow (2515 ft. g.m.s.l.). I am still committed to this condition -- at least until somebody can give me a good argument to the contrary.

Imperfect though they may be, I have settled upon the following six equations:

 $V_{s} \neq V_{n} \dots \dots (1),$ 

and

 $V_{s} \neq V_{f}$ .....(2)

wherein V is the volume of tailings stacked above the mean "safe" storage level,

 $V_{\rm p}$  is the volume of supernatant stored above that level but below the overflow level.

 $\boldsymbol{V}_{\rm f}$  is the volume of storage available in the original resand ervoir above the overflow but below the lowest point on the dam.

in which B is the distance from the dam to beachline at the time.

W is the mean width of the supernatant pond, and

D is the mean depth of water overlying the tailings against the dam.

in which S is the difference in elevation between the top of the stacked tailings and the overflow level,

U is the average width of the tailings stacked above

the overflow level,

and T = C - B.....(5)

with C being the distance from the dam to the point where the original contour of the overflow level reached farthest into the basin before tailings had been deposit in it.

 $V_{f} \stackrel{\circ}{=} C^{*}W^{*}F^{*}$  .....(6)

in which F is the depth of freeboard that could safely be filled with stored water without fear of overtopping the dam on a windy day.

The use of these equations is not easy and the problem is compounded when the information must be assumed or estimated. However, if substitution of the values shows that at any given time  $V_s$  equals, or exceeds, either  $V_p$  or  $V_f$ , then the safe storage level has been exceeded and operations should cease immediately.

You are welcome to try these equations. On the other hand, you may use your own formuli. The important thing is to have some convenient way of determining when the tailings are being stacked too high and the operator should be chedking his storage level several times each year. For your benefit I am attaching a calculation of the situation at the start of operations this year.

Martin Martin

R. T. Martin, P.Eng., Senior Geotechnical Inspector

RTM:kw attach.

c.c. A. J. Richardson 🧹

H. B. MINE (DAVID MINERALS) TAILINGS STORAGE STATUS AT ITSET OF 1982 R.T. Martin June 18, 1982, C=2,850' B=2,150' W=250 2530'el. 2520'el 50=9" In (5) T=C-B = 2,850'- 2,150' = 700' In (9) Vs = ± (S·U·T) = ± (15'×1000'×700')= 5,25×10 ft3  $(4ay) V_s = 5 \times 10^6 \text{ ft}^3 \blacktriangleleft$ Vp÷ 子(B·W·D)=子(2150'×950'×9')=12.25×10 ft3 In (3) (say) Vp= 12×106 ft3 Trying (1), Vs > Vp (Okay) In (6)  $V_{f} \doteq CWF = 2,850 \times 950' \times 3.5' = 9.48 \times 10^{6} \text{ ft}^{3}$ (any)  $V_{f} = 9 \times 10^{6} \text{ ft}^{3}$ Trying (2)  $V_s \neq V_f$  (Okay) CONCLUSION : At the outset there existed plenty of storage for the stacked tailings (twice as much as required). Therefore, the impoundment could not possibly be overtopped by either tailings or supernatoret fluid. Setting == 2 W=U in (1) Vs + Vp or by (4) and (3) SHIT + 2540 MAD (20) + 2 P By equin (5) (C-B) 7 3 B C+音B Yielding, 見大喜 And, if C= 2850 (as estimated above) B+ 1700 Thus, the beach, can shrink to about 1700 fee Egy 2013-90163 depending upon how valid my assumptions are. Top

1835 Fort Streat. Victoria, 3.C. VER 136.

July 22, 1977.

Mr. J. S. Newman, P.Eng., Civil Engineer, Géminco Ltd., TPAIL, B.C. VI 4L8.

Dear Mr. Newman:

Te: H.B. Nine Tailings Dam Spillway.

Further to our tolephone conversation of July 21st, place find attached a copy of a latter to Mr. John Brodie, Head of the Minine Section, Pollution Control Branch.

In regard to the proposed spilling this has been reviewed and the design considered to be adequate. Care should be taken to see that the spilling is level to the obstruct in the proper scenar.

Yours very truly,

J. E. Merrett, P.Eng., Acting Chief Inspector of Minas.

JEN: jau

copy: Mr. J. D. McDonald Mr. J. 3. C. Lang Mr. K. Mayars Mr. P. Wyka



Eu-E
· · · · · · · · · · · · · · · · · · ·
WHEN REPLYING PLEASE REFER TO

FILE NO

MINES AND PETROLEUM RESOURCES PARLIAMENT BUILDINGS, VICTORIA, BRITISH COLUMBIA VØV 1X4

MINERAL RESOURCES BRANCH

1835 Fort St	reet,
Victoria, B.	C- V8R-116.
	DEPT. OF MINES
May 5, 1977.	AND PETROLEUM RESOURCES
	Rec'd MAY 5 1977
	$\Delta A$
	4/11
1	· ·

Mr. John Brodie, Head, Mining Section, Pollution Control Board, Ministry of the Environment, Parliament Buildings, Victoria, B.C.

Dear Sir:

Re: H.B. Tailings Pond Extension 1977 - Stability of Dam

A meeting was held between representatives of the B.C. Ministry of Mines, Golder Brawner Associates and Cominco Ltd., at 1:30 p.m., April 20, 1977 in Trail to discuss the proposed extension of the H.B. Mine tailings pond.

A report has been submitted by Mr. McDonald and Mr. Lang along with their recommendations.

Permission to proceed with the extension of the H.B. tailings dam is granted subject to the following provisions:

- 1. Present lift to be 5 feet only.
- 2. A further extension of 10 feet is permissible as per Golder Brawner Report.
- No further extension over the 15 feet will be allowed without full review of the overall stability.
- Three prezometers to be installed in the dam, location to be determined by Golder Brawner & Associates.
- 5. The proposed spillway to be constructed and operating in 1977.

. . ./2

6. When the spillway is completed and operational the present decant system is to be sealed with concrete. Placing concrete in the decant pipes must be supervised by an appropriate staff member of the H.B. Mine.

Yours very truly,

U.E. Merrett, P.Eng., Acting Chief Inspector of Mines.

JEM: jau

copy: Mr. J.B.C. Lang, Mr. J.D. McDonald, Mr. K. Meyers, Mr. R. Wyka.

Page 697 EGM-2013-00163 1835 Fort Street, Victoria, B.G. V8R 1J6.

June 9, 1977.

Mr. J. S. Newman, P.Eng., Civil Engineer, Cominco Ltd., TRAIL, B.C. VIR 4L8.

Dear Sir:

#### Re: H.B. Mine Tailing Dam Spillway.

This will acknowledge receipt of your letter of June 1, 1977 enclosing copies of letter and attachments sent to Mr. J. Lang, in Nelson, concerning the above-mentioned subject.

In due course you will be contacted by Mr. J.E. Merrett, P.Eng., Acting Chief Inspector of Mines concerning your submission.

Thank you for your communication.

Yours very truly,

J.D. McDonald, P.Eng., Senior Reclamation Inspector.

JDM: jau

der -

Cominco Ltd./Trail, British Columbia, Canada V1R 4L8 Tel. (604) 364-4222 'Telex 041-4426

Engineering

	Cominco
Mr. J. D. McDonald Senior Reclamation Inspector Department of Mines and Petroleum 1837 Fort Street Victoria, B. C. V8R 1J6	DEPT. OF MA AND PETROLEUM RESOURCES Resources Rec'd JUN 6 1977

June 1, 1977

Dear Mr. McDonald:

Re: H. B. Mine Tailing Dam Spillway

I am enclosing two copies of a letter and attachments sent to-day to Mr. Lang in Nelson.

Yours truly,


J. S. Newman, P. Eng. Civil Engineer

JSN/af

Enclosures

1601= C- JEH ACINM.

#### Cominco Ltd./Trail, British Columbia, Canada



Engineering

Mr. J. B. C. Lang District Inspector of Mines Ministry of Mines and Petroleum Resources 310 Ward Street Nelson, B. C. VIL 554

June 1, 1977

Dear Mr. Lang:

#### Re: H. B. Mine Tailing Dam Spillway

I am enclosing a copy of the technical specification and drawings for the spillway for your perusal and approval.

The work will be constructed after the completion of the extension to the dyke, about September of this year.

Since the Construction Contract and order for pipe has to be placed, your early attention will be appreciated.

Yours truly,

J. S. Newman, P. Eng. Civil Engineer

JSN/af

Attachments: Technical Specification HB0.007-1, Rev. 2 Drawings: HB-298-1; HB-299-1; HB-300-1; HB-301-1; HB-302-0

cc: J. D. McDonald (2) KVSM RW GTJH MINISTRY OF MINES AND PETROLEUM RESOURCES Rec'd MAR 31 1977 310 Ward Street, Nelson. B.C. VIL 554. March 29th, 1977

Mr R.E. Jones, P. Eng., Mill Superintendent, Cominco Ltd., H.B. Mine, Salmo. B.C. VOG 1ZO

Dear Mr Jones,

Thank you for sending me copies of the H.B. Tailings Dike Extension proposal and specification No. HBO.010-1. I have gone over it with interest, and in the light of past proposals and future needs several questions come to mind.

First of all, the estimated life of the concentration operation is a major factor. The proposed 5 Foot Lift design will carry us through to 1979. At this time, however, a major change in the physical structure will have to be made to satisfy stability requirements acceptable to the Ministry of Mines. Should operations cease at this time which would mean the end of daily inspection and maintenance, area drainage and spillway modifications will be mandatory and extensive. Should the operations continue beyond 1979, a further dike extension will be required which shall also mean a new spillway for effluent, but area drainage will not be as vital.

fifteen feet of water on the upstream dike face is not a good situation and would indicate a rather high Phreatic water surface. This will be lowered by an efficient blanket drainage and toe drain system. The choice of material and subsequent deposition in place is therefore critical. It is suggested that standpipes, piezometers, be installed in the dam for monitoring future levels, and that an independent Geotechnical Engineer supervise the selection and placement of the blanket and toe drain material.

In 1976, Cominco did considerable planning on a new spillway system. This work indicated the entertainment of the shortcomings of the present method of decantation. Why was this plan abandoned? We also ask you to consider a system of cycloning the tails across the upstream dike surface, to keep the water away from the dike, and to effectively strengthen it. We would be pleased to have your comments on these items before considering your proposal.

- 2 -

Yours truly,

J.B.C.Lang, P. Eng., District Inspector of Mines and Resident Engineer.

c.c. J.W.Peck, P.Eng., Victoria.

JBCL/elg

Page 702 EGM-2013-00163

1835 Fort Street, Victoria, B.C. V8R 1J6.

March 25th, 1976.

Mr. F. Hodgson, Chief of Mining Division, Pollution Control Branch, Department of the Environment, Parliament Buildings, VICTORIA, British Columbia.

Dear Mr. Hodgson:

#### Re: P.C.B. File No. 0262100-PE-1853 Stability of Tailings Dam - H.B. Mine.

Further to a review of correspondence and reports

and a telephone discussion with your John Clarke, we confirm our approval of stability.

Yours very truly,

J:W. Peck, P.Eng., Chief Inspector of Mines.

JWP: jau

John Clark

MAKE I was not commend any stability problem with the HB tailings damy were you! pertinent comments you may have pertinent comments you may have Hooded appears that Goode Braume are satisfied with the contained work down (area)

Sugar agen of the disks inspiction open to which is all wall suit to all inspictors and with suite and the assessments of chines in their 16 16 1/K/2/

Page 704 EGM-2013-00163

		A CONTRACTOR OF A CONTRACT		RESOURCES	Comino	0
Departme	spector of Mine nt of Mines nt Buildings			<u>Îlli</u>		
February	25, 1976					
As reques	Reference P.( Application f <u>Permit No. PE</u> ted by Mr. J. F ranch, we are s	for Amendr 2-1853 Petrie, Ex	ment to	o H.B. Mi	ne  the Pollution	

Yours truly,

K.L

R.L. Brown Supervisor Waste Control

RLB:jf ENCLOSURES



## **Golder** Associates

CONSULTING GEOTECHNICAL ENGINEERS

October 6, 1975.

Cominco Ltd., Engineering Department, Trail, British Columbia.

Attention: Mr. S. Newman, P. Eng.

Dear Sirs:

#### Re: H.B. TAILINGS DYKE CONSTRUCTION

As requested, a visit was made to the above site in conjunction with Cominco personnel on September 18, 1975. The purpose of the visit was to review the completed dyke construction work. The following observations were made during the visit:

- i) The dyke fill had been placed according to specifications.
- ii) The coarse rock toe berm had been placed as required.
- iii) The borrow pit areas had been dressed and graded.
- iv) Surficial ditching had been carried out for run-off control.
- v) The pond water level was located at the approximate elevation of the original dyke crest.

It is our opinion that the work has been carried out satisfactorily but it is recommended that regular dyke inspections.

continued....2

GOLDER, BRAWNER & ASSOCIATES LTD., 785 TRANQUILLE ROAD, KAMLOOPS, B.C., CANADA V2B 3J3 . TELEPHONE: (604) 376-1206

Page 706 SOIL MECHANICS - FOUNDATIONS - GEOTECHNICAL SURVEYS - EARTH DAMS - LANDSLIDES - ROCK SLOPE STABLEDM-2013-00163 PAVEMENT EVALUATION - SOIL STABILIZATION - AIR PHOTO INTERPRETATION VANCOUVER - CALGARY - TORONTO - OTTAWA - WINDSOR - LONDON - BOSTON - MELBOURNE - SYDNEY be carried out. These inspections should ensure that the dyke is performing as designed and that no potential seepage problems are developing.

-2-

As requested, we have attached in point form, the areas which should be reviewed during these inspections. As discussed previously, a form could be prepared for the mine usage.

We trust that this is to your satisfaction.

Yours very truly, GOLDER, BRAWNER & ASSOCIATES LTD.,

Theren

H. HAWSON, P. Eng.

HH\*ah.

<u>V75095.</u>

cc. MM



Page 707 EGM-2013-00163

**Golder Associates** 

## H.B. TAILINGS DYKE INSPECTION

DATE OF INSPECTION	
WATER DEPTH IN PONDS	
WATER ELEVATION IN PONDS	

	ITEM	NO	YES	LOCATION
1.	Any cracks on dyke?			
2.	Any sloughs or failures on dyke?			
3.	Any erosion on downstream slope?		-	And the state of the state of the state of the state of the state of the state of the state of the state of the
4.	Any boiling at toe of the dyke?			
5.	Is surface run-off from abutments saturating the toe of the fill?	antana ana an		
	SEEPAGE		COLOUR 0	F SEEPAGE
		CLEAN	DIRTY	LOCATION IF DIRTY
$1_{1}$	Toe seepage.			
2.	East abutment seepage			
3.	West abutment seepage.			
4.	Downstream gully seepage.			·
5.	Seepagé around decant pipe.			·

.



Golder Associates

CONSULTING GEOTECHNICAL ENGINEERS

October 6, 1975.

Cominco Ltd., Engineering Department, Trail, British Columbia.

Attention: Mr. S. Newman, P. Eng.

Dear Sirs:

.

Re: H.B. TAILINGS DAM CONSTRUCTION

Please find enclosed our inspection report for the construction work carried out at the above site in September 1975.

Yours very truly,

GOLDER, BRAWNER & ASSOCIATES,

H. HAWSON, P. Eng.

HH\*ah.

V75095.

GOLDER, BRAWNER & ASSOCIATES LTD., 785 TRANQUILLE ROAD, KAMLOOPS, B.C., CANADA V2B 3J3 • TELEPHONE: (604) 376-1206

Page 709 SOIL MECHANICS - FOUNDATIONS - GEOTECHNICAL SURVEYS - EARTH DAMS - LANDSLIDES - ROCK SLOPE STATE GTV-2013-00163 PAVEMENT EVALUATION - SOIL STABILIZATION - AIR PHOTO INTERPRETATION VANCOUVER - CALGARY - TORONTO - OTTAWA - WINDSOR - LONDON - BOSTON - MELBOURNE - SYDNEY

#### SUMMARY OF FIELD INSPECTION

#### TAILINGS DAM INSPECTION, H.B. MINES, SALMO, B.C. (SEPTEMBER 10, 1975)

#### 1. DYKE CONSTRUCTION

44.

Some surface ponding had occurred on the dyke crest since the construction was suspended in December, 1974. The surface was scarified and the existing material was mixed with a thin lift of the new fill prior to recompaction. The dyke was brought up to a final elevation of 2,515 ft., using the borrow material from the east borrow pit. Bedrock was encountered at some locations in the pit and numerous boulders were present in the fill. The material in excess of 9 in. diameter was removed in the pit or discarded over the upstream slope during fill placement.

A sample of the material from the pit was sent to our laboratory and a Standard Proctor Dry Density test was carried out (Figure 1). These results were used for compaction control (Table 1).

Additional clearing was carried out on the western abutment to ensure a good bond between the fill and natural soil. On reaching the design dyke elevation, the crest was graded towards the tailings pond to ensure that no surface ponding could take place and that all run-off from the crest was directed towards the upstream slope.

#### 2. RE-GRADING OF THE DOWNSTREAM SLOPE

A number of erosion gulleys had developed on the downstream slope

### Golder Associates

the centre of the dam and tapered off towards the edge of the berm.

(c) A large gulley, washed out of the filter zone on the east abutment, was filled with the rock and the top of the filter blanket was re-graded.

#### 4. FINAL SITE GRADING

The slopes in the borrow pit were graded so that the area , could be re-seeded at a later date.

Numerous ditches and berms were constructed in the abutment areas to ensure that positive drainage was established which was directed away from the toe of the tailings dyke. Access roads to the downstream toe of the dyke were constructed on the western abutment in order to facilitate inspection and maintenance of the dam.

**Golder Associates** 



Page 711 EGM-2013-00163

## TABLE I

## RESULTS OF IN SITU DENSITY TESTS

(Impervious Till Material)

Date	11-9-75	12-9-75	13-9-75
Test Number	1	2	3
Location	Central	West End	W. Central
Elevation (approximate)	2,512	2,511	2,514
Moisture Content (%)	6.3 (1)	6.3 (1)	6.3 (!)
Dry Weight (lbs/cu.ft.)	127.1	134.5	131.2
Relative Compaction (Standard Proctor)	96.9%	102.5%	101.1%

#### NOTES:

1. Moisture content supplied by H.B. Mines. Samples 1 and 2 were destroyed so results are assumed the same as for Test No. 1.

Golder Associates

Page 712 EGM-2013-00163 since termination of the 1974 construction. A small bulldozer was used to re-grade the surface of the till fill in a relatively smooth slope. An attempt was made to fill the gulleys in the sand and gravel material using the same method, but due to trafficability problems, this work was eventually completed manually.

-2-

#### 3. ROCK TOE BERM


The material used for the rock toe berm consisted of 75 percent screened gravel from the B.C. Highways pit close to the tailings pond, and 25 percent waste rock from the old Can-Ex mine about 6 miles from the site. Material greater than 1 ft. diameter was rejected. Two gradation tests were performed on the B.C. Highways material and the resulting gradations, along with the approximate gradation of the mixed material, are given on Figure 2.


Prior to placement of the rock berm some of the existing wet material was removed. The rock material was placed in three areas, as follows:

> (a) A thin layer of the rock was placed over the wet area resulting from seepage from the western abutment area, and it was ensured the seepage was directed well away from the toe of the dyke.

(b) A 15 ft. wide rock berm was placed along the downstream toe of the dyke in the area where concentrated seepage was present. This berm was approximately 4 ft. thick close to the gulley at

#### **Golder Associates**





4

Project No Lite

Golder Associates

CONSULTING GEOTECHNICAL ENGINEERS

E/75/433 June 6, 1975,

Cominco Ltd., Trail, B. C.

ATTENTION: Mr. J. S. Newman, P. Eng.

Re: Site Inspection, H.B. Tailings Pond Dyke, Salmo, B. C.

Dear Sir,

5.

As requested we visited the above site along with Mr. J. S. Newman on May 29, 1975. The purpose of the visit was to inspect the H.B. Mine Tailings dyke and review the performance of the dyke since termination of construction in December 1974.

The following observations were made during the visit:

- 1. The pond water level at the time of the visit was located at the top of the original dyke crest (i.e., approximately elevation 2,505).
- Seepage was observed exiting at the downstream toe of the dyke and was estimated to be at approximately elevation 2,468 in the pit run sand and gravel toe filter.
- 3. Concentrated seepage zones which were present prior to construction at the dyke abutments are still evident. At the east abutment the seepage tends to saturate the ground surface at the toe of the dam.
- Concentrated seepage zones were observed in the downstream gully. These zones were present in this area prior to construction.

east

Runoff from the west abutment has developed erosion channels in the fill.

GOLDER BRAWNER & ASSOCIATES LTD., 224 WEST 8th AVE., VANCOUVER, B.C., V5Y 1N5 CANADA . PHONE: (604) 879-9266 TELEX: 04-508800

Page 716 FUR MECHANICS FUUNDATION: GEDTECHNICAL SUBVEYS - EARTH DAMS - LANDSLIDES BOCK SLOPE STABILIEGM-2013-00163 PAVEMENT EVALUATION SOL STABILIZATION AIR PHOTO INTERPRETATION

VARCEUVER CALGARY TREPORTO OUTAWA WINDSOR LONDON BOSTON MELBOURNE SYDNEY

- Surface ravelling has occurred on the downstream slope of the dyke due to ponding of surface water on the ungraded fill surface.
- 7. The seepage was observed to be clear.

6.

The construction work carried out in the fall of 1974 was terminated in December due to bad weather and working conditions. At this time the majority of the dyke fill had been placed and the dyke crest elevation varied from elevation 2,515 at the west end to 2,510 at the east end. Our letter of December 24, 1974 contains a summary of this construction. Additional work is scheduled to be carried out in the summer of 1975 to complete the dyke.

Examination of the pond area indicates that the dyke has performed satisfactorily during the last 6 months since termination of last year's construction. However, some local seepage is evident and as discussed at the site, it would be advantageous to provide a layer of coarser material at the toe to assist in controlling the seepage. As discussed, coarse mine waste rock would be suitable for this purpose and could be placed during this year's construction. The waste rock should be placed as a berm at the toe to cover the present seepage line. In addition, it is recommended that 2 to 3 feet of sand and gravel be spread over the relatively flat area at the toe of the west abutment. Further, the seepage flow at this abutment should be channelized out of the area. This will provide better trafficability in this area.

At the east abutment some additional sand and gravel fill should be placed to repair the erosion damage caused by the spring runoff. Also it is recommended that a diversion trench be excavated to prevent surface runoff water from the east borrow area, flowing around the toe of the dyke.

To reduce surface slope ravelling, the downstream face of the dyke should be graded and shaped to remove irregularities which tend to pond surface water. The final dyke crest should be graded towards the north so that surface water will be directed into the pond area.

It is understood that consideration is being given to sealing the existing timber decants and providing a spillway to control pond water level. In our opinion this type of water control is far superior to the present timber decant tower and as a result would recommend that this be carried out. To enable the spillway to be designed, runoff and survey data would be required. In addition the method of adequately sealing the present system should be reviewed.

Yours very truly,

GOLDER BRAWNER & ASSOCIATES LTD.

H. Hawson, P. Eng.

HH/jh V75095

> Page 717 EGM-2013-00163

**Golder Associates** 



Golder Associates CONSULTING GEOTECHNICAL AND MINING ENGINEERS

E/74/943

December 24, 1974

100

Cominco Ltd., Trail, B.C.

ATTENTION: Mr. M. S. Newman, P. Eng

Re: Field Inspection - Tailings Dam Extension H. B. Mines, Salmo, B.C.

Dear Sir,

Please find enclosed a summary of our field inspection carried out at the above project, during November 6 to December 9, 1974 inclusive.

The results of in situ density tests carried out during this period are presented on Tables 1 and 2. The results of the Standard Proctor compaction tests which were carried out on the materials used for construction are presented on Figures 1 and 2.

We trust that this is to your satisfaction.

Yours very truly,

GOLDER BRAWNER & ASSOCIATES LTD.

H. H. Hawson, P. Eng.

HHH/cc

V 74234

JAN 6 1975

J.S.N.

GOLDER, BRAWNER & ASSOCIATES LTD., 224 WEST 81h AVE., VANCOUVER, B.C., V5Y IN5 CANADA PHONE: (604) 879-9266 JELEX: 04-508800 Page 718

SON MECHANNES - FOUNDATIONS - GEOTECHNICAL SURVEYS - EARTH DAMS - LANDSLIDES - HOCK SLOPE STATEGM-2013-00163

PAVEMENT EVALUATION - SOIL STABILIZATION - AIR PHOTO INTERPHETATION

Summary of Field Inspection Tailings Dam Extension H.B. Mines Salmo, B.C.

#### 1. SEEPAGE

East Abutment Area

An area of seepage was encountered during the construction at the downstream toe of the existing dam near the east abutment. A small ditch had been previously excavated to channel the seepage flow away from the dam. The ground surface in this area was grass covered and soft due to the continued seepage. The area immediately east of this seepage had been covered by material pushed off the haul road.

An attempt was made to clear the disturbed material, however, the bulldozer used was unable to effectively clear the area. It was decided to place the required filter blanket in this area by pushing the disturbed material ahead of the sand and gravel blanket. In this manner the seepage area was covered with a filter blanket 4 to 5 feet thick and 16 to 20 feet wide.

#### West Abutment Area

Seepage was ecnountered at two locations on the west abutment. One area of seepage was located at the toe of the fill at approximately elevation 2461. This seepage appeared to be minor, but minor sloughing of the placed sand and gravel occurred in this area. To protect the toe of the dam a sand and gravel berm was placed to cover this seepage. The berm was constructed 2 to 6 feet thick and 12 to 16 feet wide. After placement of the berm there was no further indication of any movement or sloughing in the main dam section.

Seepage was also located further up the abutment slope at approximately elevation 2495. A small ditch had been excavated to channel the seepage away from the dam.

A small tracked bulldozer was used to clean out the majority of the soft material in the ditch. A sand and gravel filter blanket was then placed to cover the seepage. This filter blanket was constructed 3 to 5 feet thick and extended approximately 20 feet beyond the toe of the dam.

#### 2. SAND AMD GRAVEL - FILTER BLANKET

The sand and gravel used for the dam construction was obtained from a borrow pit located approximately 1 mile north of the dam site.

Several in situ density tests were carried out on this material. The results of the tests are presented on Table 1.

#### 3. DECANT CULVERT

14

The decant culvert under the eastern part of the existing dam was extended to enable construction of the dyke extension.

During the construction, water flowing through the culvert had not been completely stopped. The minor flow which continued was diverted to flow across the fill.

The sand and gravel fill beneath the culvert extension was placed in maximum lifts of 6 inches and compacted with a portable hand compactor. No

2.

density tests were performed but this material was well placed and compacted.

When the pipe was connected, two of the joints had minor leaks. Both leaks were eventually sealed using roofing tar and burlap. The joints were then backfilled and the pipe was buried.

#### 4. TILL FILL - IMPERVIOUS MATERIAL

The till fill or select fill material was supplied from a pit just east of the dam site.

The pit was worked in such a manner as to ensure that most of the run-off would drain towards the north or lower end of the pit. There were occasional pockets of fine sand in the pit. These pockets of sand were mixed in with the till which was taken from the pit. When the pit was initially opened, occasional roots were left from the cleaning operation. Any of the organic material which was found in the fill was removed. The pit also contained some large boulders. These boulders were also generally removed from the fill.

The results of in situ density tests performed on the till fill are presented on Table 2.

5.

#### PHREATIC SURFACE WITHIN DAM SECTION

The water level in the standpipe on the top of the old dyke. (BH //1) and at the toe of the new extension (BH //3) were checked on December 9, 1974. At that time the water level in the pond was at approximately elevation 2502. The water levels of the pond and in the standpipes were compared to those taken in December 1973 and referred to in our report of January 1974. (Refer V 73218) The comparison indicates with an increase in pond elevation of 2 feet, a 2 foot increase in the phreatic surface at BH #1 and a minor increase in the phreatic surface at BH #3 has occurred.

A third standpipe installed on December 1973 in BH #2 unfortunately had been destroyed during the construction.

#### 6. SUSPENSION OF OPERATION - DECEMBER 9, 1974

The continual warm wet weather had increased the moisture content of the till fill which was being placed. This increase in moisture content made trafficability on the top of the new dyke very difficult. It was also considered that this increase in moisture content would make handling and proper placement of the till fill difficult and impractical. Further it became apparent that continued operation would result in disturbance of the material already placed.

Therefore, it was recommended that the construction be suspended until such time as the fill could be properly placed.

At the suspension of operation the east end of the dyke had reached grade at elevation 2515 while the west end was generally 5 feet below grade at elevation 2510. The top of the dyke was graded prior to leaving the site to prevent ponding of precipitation on top of the dyke.

It is also recommended that the dam be periodically inspected over winter and spring.

Yours very truly, GOLDER BRAWNER & ASSOCIATES LTD.

J. A. Hul

Page 722 EGM-2013-00163

JAH/cc V. 74234

**Golder Associates** 

4.

## TABLE 1

RESULTS OF IN SITU DENSITY TESTS

	Sand and (	Gravel			
Date	14-11-74	14-11-74	15-11-74	28-11-74	30-11-74
Test No.	1	2	3	Lj	5
Location	West End	East End	Central	Central	Central
Elevation	2470	2470	2475	2490	2505
Moisture. Content(%)	3.18(1)		2.6(1)	3.5(1)	1,2(1)
Dry Weight (lbs./cu.ft.)	136	132	124	125	134
Relative Compaction (Standard Proctor)	111 59	100 5%	1000	100 50	
rioctorj	111.5%	108.5%	102%	102.5%	110%

Note (1) Moisture content supplied by H.B. Mines.

**Golder Associates** 

Page 723 EGM-2013-00163

## TABLE 2


## RESULTS OF IN SITU DENSITY TESTS

Silt Till (Select Fill Material)

Date	28-11-74	30-11-74	2-12-74	8-12-74
Test No.	1	2	3	4
Location	Central Area	Central Area	Central Area	Central Area
Elevation	2490	2500	2506	2510
Moisture Content(%)	2.1(1)	1.6(1)	1.2(1)	11.4(2)
Dry Weight (lbs./cu.ft.)	133.5	130.0	143.2	120.0
Relative Compaction (Standard Proctor)	, 109%	106%	118%	98%


Note (1) Moisture content supplied by H. B. Mines

(2) Moisture content supplied by Golder Brawner & Associates Ltd.



MAXIMUM DRY DENSITY 121.8 lb/cu.ft, OPTIMUM MOISTURE CONTENT 11.7 %

Golder Associates



MAXIMUM DRY DENSITY 122.8 lb/cu.ft. OPTIMUM MOISTURE CONTENT 12.2 %

Golder Associates



Engineering

Mr. J. W. Reck, P. Eng, Chief Inspector of Mines, Depointment of Mines and Petroleum Resources, Victoria, B.C. August 2, 1974. Deas Mr. Peck, Re: H.B. Mine, Solano - Tailings Dike Extension

The existing facility at the H.B. Mine is nearly full and to provide farther necessary storage we wish to increase the height of the dike by ten feet. This summer.

We have been in contact will own consultants, lyclass Braines and Associates and I am enclosing a latter received from them indicating Their agreement to the proposed construction.

I am also enclosing a copy of the specifications and a copy of drawing HB-289-P showing the proposed works. The first point mentioned in the latter is civeled in the last paragraph on page 37 [para 2-06(g)]. Points two and three are shown on the directing. Attangements will be made to carry out the field controls requested in the fauth point.

We would appreciate your approval at your earliest convenience to enciste us to proceed with the abase works.

yours very truly. - Cew

J.S. Neuman Dosigi Engineer.

Ence: Latter (lyelder-Brauner July 5/70) Drawnig HB-289-P Specifications HB0.005-1

CC. Mr. T. Waterens (Nolson) G.S. M.M.



#### Engineering

Mr. T. Waresland, Inspector of Mines, Court House, Nelson, B.C. August 2, 1974. Dear Mr. Waterland, Re: H.B. Mine, Salmo - Tailings Dike Extension. As requested this morning in our telephone Conversation, I have sent a letter to Mr. J.W. Peck Today with the information requested for approve to raise the duke by ten feer. I am enclosing a copy of the letter and enclosures for your use. your very truly and allow J.S. NEWMAN Dasign Ergeneer.

нды, сыная сонцярна, сызада

Page 729 EGM-2013-00163

 $c \in G.S.$ 

Erce.

# Golder Brawner Associates

CONSULTING GEOTECHNICAL ENGINEERS

Ulm. , I have not done drything about this H. Q. GOLDER C. O. BRAWNER V. MILLIGAN J. L. SEYCHUK N. R. MCCAMMON R. M. WILSON D. L. PENTZ D. B. CAMPBELL A. A. GASS H. G. GILCHHIST

E/74/492

July 5, 1974

Cominco Ltd., Engineering Department, Trail, B.C.

Attention: Mr. G. Shoblom

Dear Sirs:

Re: Dike Extension, H. B. Mine Tailings Pond, Salmo, B.C.

As requested, we have examined the proposed dam extension design and fill specifications at the H. B. Mine Tailings Pond as outlined in your letter of June 19, 1974 and as shown in your Drawing HB-289-P. We are in general accord with the specifications and design shown but would like to point out the following:

> The surface of the existing dike should be 1. scarified prior to placement of the select impervious fill and the common fill.

Ser pur 2 sistar

on por dury

The slopes of the dike extension, both up-2. stream and downstream, should not be constructed steeper than 2 horizontal to 1 vertical as shown on the drawing.

GOLDER, BRAWNER & ASSOCIATES LTD., 224 WEST 8th AVE., VANCOUVER, B.C., V5Y IN5 CANADA . PHONE: (604) 879-9266 . TELEX: 04-508800

SOU NU SHALLO'S FOULD ATTOMS GET TO MICAL SUBVEYS - EABTH DAMS TANG LEDES ROCK SLOPE STADE BAGE 730 EGM-2013-00163

PAVEMENT EVALUATION SOIL STABILIZATION AIR PHOTO INTERPRETATION

VARIABLE CALIFORY TORONIO ALIARA WINOSON TOMBON BOSTOD MATRODAY SYDNEY

3. The filter material should be placed on the existing dike slope to provide a continuous blanket no less than 2 ft. thick.

as per strug!

4. It is recommended that strict field control be exercised to insure that the fill materials excavated from the borrow pits are compatible with respect to filter requirements at all times.

We trust that this satisfies your present requirements. If we can be of further assistance, please contact us.

Yours very truly,

GOLDER BRAWNER & ASSOCIATES LTD.

Bier MA Dugleta

W. H. Highter

WHH/mm

V73218

## GOLDER BRAWNER & ASSOCIATES

Page 731 EGM-2013-00163



Engineering

1

Mr. H. H. Hawson Golder Brawner & Associates Ltd. 224 West 8th Avenue Vancouver, British Columbia V5Y 1N5

June 19, 1974

Dear Mr. Hawson:

RE: H.B. MINE TAILINGS POND

As a result of our recent discussions, I am enclosing two copies of our Drawing HB-289-P for your perusal.

To take advantage of the materials available onsite, we are specifying a zoned construction with a select impervious material on the upstream face, and a relaxed specification for the common fill.

The specification for the fills is as follows:

"Select fill shall be a glacial till, well graded with a maximum size of mine inches, and with at least 20% finer than the No. 200 U.S. Standard sieve size.

Common fill shall be a glacial till, well graded with a maximum size of nine inches."

For both zones we are specifying 12" maximum layers before compaction, and compacted to 95% of maximum dry density as determined for the Proctor compaction tests specified in ASTM D-698.

The samples we have taken from the west borrow area are coarser with 11 to 25% finer than No. 200, whereas the east borrow pit samples have 35 to 60% finer than No. 200.

For compaction equipment we are specifying a Hyster Model D gridroller with concrete ballast, which weighs 13 tons.

Continued .....

INTEROFFICE MEMORANDUM

Created:	29-Aug-1997 04:35pm PDT
Sent:	29-Aug-1997 04:40pm PDT
From:	Tim Eaton of EI TEATON
Title.	Manager - Geotechnical Engineeri
Dept:	Employment & Investment
Tel No:	952-0485

( FHERMANN )

( JERRINGTON ) ( AWHALE )

TO: Fred Hermann of EI TO: John Errington of EI TO: Andrew Whale of EI

Subject: HB

#### File: 14745-40/HB

FYI

Walter Kuit just called me. Cominco has rediscovered their liability at HB tailings dam. They are negotiating with NuDawn (apparently the ownership has chaged hands since my title searches in June and the owner is now based in Seattle but consists of the same people that were NuDawn) and the Regional District. The landfill environmental problems are complicating matters and Cominco will decide on a course of action soon. Cominco want to see a proper spillway installed.

Tim



14745-46/HI3 1. Al

Ph: (250) 952-0475

June 17, 1997

File: M-85 14675-35-04

Mr. B. Baldigara Secretary, Assistant Administrator Regional District of Central Kootenay 601 Vernon Street Nelson, B.C. V1L 4E9

Dear Mr. Baldigara:

#### Re: H.B. Mine Tailings Impoundment

I have been asked to reply to your May 15, 1997 letter to Andrew Whale, Regional Manager, Ministry of Employment and Investment, regarding possible future liabilities associated with the H.B. tailings impoundment.

# Status of Permits Covering the Tailings Impoundment

The mine is regulated under the Mines Act.

The mine, including the tailings impoundment, is covered by Permit M-85 issued to Cominco Ltd. (copy attached). However, they sold this property to David Minerals who subsequently went bankrupt, and the last record we have of an owner is Nu-Dawn Resources.

Over the years, in spite of numerous attempts to get the new owner to assume the responsibilities of the permit, Cominco still remains the permittee.

Cominco carried out considerable research in the early 1970's to determine the feasibility of establishing vegetation directly on the tailings material, and to determine the metal uptake in plants. That information is stored off-site and I do not have that information immediately available. I don't recall any major issues, however.

I could not find a closure plan and I don't believe that one was ever filed.

...2

Ministry of Employment and Investment Regional Operations, Health and Safety Branch Energy and Minerals Division Mailing Address: PO Box 9320 Stn Prov Govt Victoria BC V8W 9N3 Telephone: (250) 952-0462 Facsimile: (250) 952-0481 Location: 5th Floor, 1810 Blanshard Street Victoria

> Page 734 EGM-2013-00163

#### Dam Safety

I have included Part 9 of our Health, Safety and Reclamation Code for Mines in British Columbia (Code). The owner and permittee have not satisified the requirements of part 9.2.4, 9.3.2 and 9.3.5 The obligations in this regard should be discussed with Tim Eaton, P.Eng., Manager, Geotechnical Engineering. At present there are no significiant dam safety issues, however some work is required.

Should the Regional District purchase this property, the tailings impoundment would still be regarded as part of a mine, albeit a closed mine, and regulated under the Mines Act. As such, there would still be requirements for maintenance, periodic inspections and monitoring. These requirements would likely not be onerous, however.

#### Contamination Level of the Liquid and Solid in the Tailings

This a potential concern especially in relation to the new Contaminated Sites Provisions of the Waste Management Act. Our own internal review several years ago made a preliminary assessment of acid rock drainage potential of these tailings and it was felt that the abundance of limestone which hosted this ore deposit was likely sufficient to prevent sulphide oxidation, and acid mine drainage from occurring. This needs to be confirmed through samples of tailings and seepage from the impoundment. If there is any metal release, it will be associated with neutral to alkaline drainage.

If you have any further questions or concerns, please do not hesitate to call either myself (250) 952-0470 or Tim Eaton (250) 952-0485.

Yours very truly,

An John C. Errington, Ph.D., P.Ag. Manager, Reclamation and Permitting

JCE:ch Encl.

cc: Andrew Whale, Cranbrook Vim Eaton Fred Hermann

let-hb

Page 736 redacted for the following reason: Not Responsive

	O'Br jan		J.C. Errington				
SUBJECT:	B. Mine M-8:	S DATE:	Feb14/85				
For Your Information     Please Process	Please O.K. and Return Return With More Details	Please Discuss With Me Investigate and Report	Per Your Request Please Answer	For Your Signature			
	lease inspect	a advise this s	Smmer.	· · · · · · · · · · · · · · · · · · ·			
	lease inspect		νηηεΓ. 	· · · · · · · · · · · · · · · · · · ·			
· · · · · · · · · · · · · · · · · · ·	lease inspect		υηηε. 	· · · · · · · · · · · · · · · · · · ·			
EPLY:	lease inspect		Ummer.				

X

Page 737 EGM-2013-00163

Province of British Columbia MEMORANDUM FROM: TO: J.C. Erring Arto Brzan ang Desce SUBJECT: DATE: H.B. Dine JJ , 🔲 Please Discuss With Me Please O.K. and Return Per Your Request For Your Signature For Your Information For Your File Please Answer Please Process Return With More Details Investigate and Report \$10,000 pecnit and -85 and Cominco st wil David gut up althur the bon Cominco's perit to their name amendment of and 04 the 67 conditions of Fold Here for Window Envelope this permit Fold Here for Window Envelope No-one should allow this 51 work on. Until So permit is applied an a IF you bare SUSS 20 Th 7 REPLY: 5 (1)

TRUE VERTICES THEFT AND FORWARD BALANCE OF SET

David Koming H.R. Fic 1)ale M-85

Dec 8/2- table to inside from a , is shall be the man but the man for the function as Daid. and talk to Longe 26, and it is at in - should not be allowed to recome work with all perits are in place.



Page 739 EGM-2013-00163

				Landoren de l'atro, alters Aun trefe llem recordets
		THE PROVINCE OF BRITISH REGISTRAR OF SECU MINISTRY OF FINAN VICTORIA, B.C. V8V		
	RECEIVED FROM	Cominco Limited 2300 - 200 Granville Stree Vancouver, BC V6C 2R2	t	TRUST ACCOUNT: REG. MAIL INCOMING: 16449 VAULT INWARDS: YOUR FILE: OUR FILE:
				September 6, 1983
			YOUR REGIST	ERED LETTER
		2	NO. COURI	er DATED Aug. 31/83
		2		
	<u>Re: Mines</u>	Deposit		M-85
	S.	21		
	FULLY REGIS	TERED in the name of:	COMINCO I	LIMITED.
2.5M-4-81 · EVERGREEN F	RESS · VICTORIA	WE ACKNOWLEDGE RECEIPT OF THE E	NCLOSURES	
INITIALS		LISTED ABOVE.	*	
hsg N	<i>(</i> .)	x		
	; [	R REGISTRAR OF SECURITIES.	1	Recd. Maine For Registrar of Securities
		DEPARTMENT OF SECURITIES.		For Registrar of Securities

DEPARTMENT OF FINANCE

For Registrar of Securities

Page 740 EGM-2013-00163

Cominco Ltd.

RELEASED то: --

.

THE PROVINCE OF BRITISH COLUMBIA
REGISTRAR OF SECURITIES
MINISTRY OF FINANCE
VICTORIA, B.C. V8V 1X4

DATE

September 7


OUR FILE:

YOUR FILE:

1983

٠	200 Granville Steeet	
•	Vancouver, BC	
•	V6C 2R2	Attn: G. B. Soper
	WE HAVE FORWARDED TO YOU	THE FOLLOWING SECURITIES:
AMOUNT	PARTICULARS	REGISTRATION
		Central Star Verman
	Pot Marco Descata	, Recition (1993)
	Re: Mines Deposit	
	· ·	
		BEARER
	s.21	DEANER
		0.05
		$\wedge 1 - 2^{3-2}$


EVERGREEN PRESS · VICTORIA



Q.P. 31989

Tel. (604) 682-0611 / Telex 04-507730

 $\frac{1}{2}$ 




Finance

August 31, 1983


Registrar of Securities Ministry of Finance Parliament Buildings Victoria, British Columbia V8V 1X4

ATTE	
	s.22
Dear	

We enclose Performance Bonds in respect of Reclamation Permits registered in the name of Cominco Ltd. with Powers of Attorney attached as follows:



Please forward the following Bonds which are to be replaced by the above, as soon as possible, by registered mail.



Yours very truly,

COMINCO LITD.

Gratane R. Safer.

\_\*#

G. R. Soper Project Analyst Cash Management

GRS:st Encl.

Ministry of Energy, Mines and Petroleum Resources Parliament Buildings Victoria British Columbia V8V 1X4



Rm. 105, 525 Superior St., Victoria, B.C. V8V 1T7 387-3781

January 25, 1983

Our File: M-85

Mr. George Robbins Director of Environmental Affairs David Minerals Ltd. 4th Floor - 535 Howe Street Vancouver, B.C. V6C 2C2

Dear Mr. Robbins:

Re: Reclamation Permit M-85 H. B. Mine

In your letter of November 12, 1982, you stated that the completed Receipt and Agreement form would be forthcoming.

This form has not yet been received in this office. Please advise us as to its status.

Yours very truly,

J. D. McDonald, P. Eng., Senior Reclamation Inspector

J. G. Errington, P. Ag., Reclamation Inspector

JCE:sf

cc: J.B.C. Lang, Nelson A. O'Bryan, Nrldon



Ministry of Energy, Mines and Petroleum Resources Parliament Buildings Victoria British Columbia V8V 1X4

Rm. 105, 525 Superior St. Victoria, B.C. V8V 1T7

January 24, 1983

Our File: M-85

Mr. George Robbins David Minerals Ltd. 4th Floor 535 Howe St. Vancouver, B.C. V6C 2C2

Dear Sir:

#### Re: Annual Reclamation Report

The annual Reclamation report for the year 1982 and plans for the 1983 program are due March 1, 1983. Please use the attached report format as a checklist and modify the organization of the report to satisfy your particular program. Document activities using an airphoto base at a convenient scale. A scale of 1:10,000 is suggested.

Please submit three copies of the reclamation report to this office and we will forward copies to our district staff.

Yours very truly,

J.D. McDonald, P.Eng. Senior Reclamation Inspector

J.C. Errington, P.Ag. Reclamation Inspector

JCE/eaa



Ministry of Energy, Mines and Petroleum Resources Parnament buildings /ictoria British Columbia V8V 1X4

Our File: M-85

105-525 Superior Street, Victoria, B.C. V8V 1T7. Telephone: 387-3781 November 23 1982.

Mr. George Robbins, Director of Env. Affairs, David Minerals Limited, 4th Floor - 535 Howe Street, VANCOUVER, B.C. V6C 2C2

Dear Mr. Robbins:

#### Re: Reclamation Permit M-85 - H.B. Mine.


Receipt is acknowledged of your letter dated November 12, 1982 in which you agree to abide by the Terms and Conditions of Permit M-85.

Upon receipt of the completed Receipt and Agreement form, Reclamation Permit M-85 will be transferred into the name of David Minerals Ltd.

Yours very truly,

J.D. McDONALD, P.ENG., Senior Reclamation Inspector. J.¢ Errington, R.Ag. Redlamation Inspector.

JCE:NG



4th Floor - 535 Howe Street Vancouver, British Columbia, Canada V6C 2C2 Telephone: (604) 684-3333 Telex: 04-55346

i Part	1. 2° Q	_E.1763	RESOLAUS	23
	\$1.894.1	-1	1000	
Rec'd	出日寸	1 13	1982	
j		-1	· · · · · · · · · · · · · · · · · · ·	·

November 12, 1982

Mr. J. C. Errington, P.Ag., Reclamation Inspector, Ministry of Energy, Mines & Petroleum Resources, 105 - 525 Superior Street, Victoria, B.C. V8V 1T7

Dear Mr. Errington:

#### RE: Reclamation Permit for the H.B. Mine

Further to your letter to Mr. N. C. Croome of October 24, 1982, and to our subsequent telephone conversation, I am, by way of this letter, pleased to provide assurance that David Minerals Ltd. agrees to abide by the Terms and Conditions of Permit M-85. Receipt and Agreement documents establishing security in the amount of \$10,000.00 should be forthcoming from the Royal Bank of Canada. Accordingly, we ask that you transfer Permit M-85 into the name of David Minerals Ltd.

It is also our understanding that the above is an interim measure and that a formal reclamation plan must be submitted in support of an application for a permit authorizing surface work. We anticipate completion of a reclamation plan for the H.B. operation by March 1, 1983. It would be our intent to tailor this document to also serve the purposes of an annual reclamation report as required under Permit M-85. Please advise if this is satisfactory.

Yours truly,

DAVID MINERALS LTD.

A. Kobbins

George H. Robbins, Director - Environmental Affairs.

GHR:dep

cc: N.C. Croome C.P. Moore

Page 747 EGM-2013-00163



Ministry of Energy, Mines and Petroleum Resources <sup>p</sup>arliament Buildings ctoria British Columbia V8V 1X4

105-525 Superior Street, Victoria, B.C. V8V 1T7. Telephone: 387-3781 November 18 1982.

Mr. George Robbins, Director of Env. Affairs, David Minerals Limited, 5th Floor - 535 Howe Street, VANCOUVER, B.C. V6C 2C2.

Dear Sir:

#### Re: H.B. Property

I enclose a copy of Comminco's December 23, 1977 reclamation program, as requested.

Yours very truly,

J.D. McDONALD, P.ENG., Senior Reclamation Inspector.

J.1 Errington, P.Ag. Rechamation Inspector.

JCE:NG



Parliament Buildings Victoria British Columbia V8V 1X4

105-525 Superior Street, Victoria, B.C. V8V 1T7. Telephone: 387-3781 October 24, 1982.

Mr. N.C. Croome, P.Eng., Secretary - Treasurer, David Minerals Limited, 5th Floor - 535 Howe Street, VANCOUVER, B.C. V6C 2C2.

Dear Sir:

Our letter of March 15, 1982, described the procedure for making application for a reclamation permit for the H.B. property. The procedure of obtaining this reclamation permit will take approximately eight months from the time the application is received in this office, and to date we have not received your application.

As an interim measure you can assume responsibility for Cominco's Permit by agreeing to abide by the Terms and Conditions of the existing Permit (M-85, copy enclosed), and by placing a security of \$10,000 in the name of David Minerals Limited.

The security deposit, which should be submitted before work commences, must be in the form of cash, Government of Canada or Provincial direct or guaranteed securities having a maturity of not longer than three years, or Chartered banks', Trust companies', or Credit Unions' certificates of deposit where supported by an appropriate letter giving direction concerning payment of the funds to the Minister of Finance. Enclosed are Receipt and Agreement forms which should be completed by your bank with the original to be forwarded to this office.

Upon receipt of this security and upon a written assurance by David Minerals that it will agree to abide by the Terms and Conditions of Permit M-85, the Permit will be transferred into the name of David Minerals, and Cominco will be released from their obligations.

This interim measure will not remove the requirement for submitting an application for a reclamation permit as described in our letter of March 15, 1982.

I would remind you that failure to obtain a reclamation permit will be an offense under Section 10 of the Mining Regulation Act.

Yours very truly,

J.D. McDONALD, P.ENG., Serior Reclamation Inspector.  $\cdot$ 

J.C. Errington, R.Ag. Reclamation Inspector. Page 749 EGM-2013-00163

JCE:NG

nc: J.R.C. Tana Maleon



5th XXX Floor - 535 Howe Street Vancouver, British Columbia, Canada V6C 2C2 Telephone: (604) 684-3333 Telex: 04-55346

July 13, 1982

	IISTRY ( D FETRC			
	إلاز	1	 198	1
ec'd	0121. L	•	 	
M			 	·~

Mr. J.D. McDonald, P.Eng. Senior Reclamation Inspector Ministry of Energy, Mines and Petroleum Resources #105 - 525 Superior Street Victoria, B.C. V8V 1T7

Dear Sir:

#### Re: Reclamation - HB Tailings Pond

This is written with respect to the proposed reclamation procedure for the HB tailings pond.

As you are aware, this is not a new operation. The pond was developed by Cominco for its HB mine and no physical changes have been introduced. We are working on the assumption that the reclamation procedures introduced by Cominco and approved by your Department continue to apply.

However, we are now treating, and plan to continue to treat, ores which will vary in chemical composition from the HB ores and we will be using different reagents. Under these circumstances, it is possible that some change in reclamation procedure may become necessary. We wish to assure you that we will monitor the situation on an on-going basis and will be prepared to make any changes which are called for by the varying circumstances.

With this assurance, we trust that issuance of the necessary Reclamation Permit may proced.

Yours very truly,

DAVID MINERALS LTD.

H. Brodie Hicks, P.Eng., M.Eng. Consulting Engineer

HBH:jd

cc: Mr. J.B.C. Lang Mr. N.C. Croome Mr. C.P. Moore



Energy, Mines and Petroleum Resources

# MEMORANDUM

To: J.D. McDonald, P.Eng. Senior Reclamation Inspector Date: May 11, 1982 Our File: M-85

Re: H.B. Gold Project Stage I report dated March 1982

Review of Stage I

This document is of limited use and contains no statement on the reclamation of the tailings area.

## Current status of their application for a reclamation permit:

By letter dated March 15, 1982, David Minerals has been requested to apply for a reclamation permit. No response to date.

J.d. Errington, P.Ag. Reclamation Inspector

JCE/eaa

Page 751 EGM-2013-00163 J.D. McDonald, P.Eng. Senior Reclamation Inspector May 11, 1982

1-85

### Re: U.S. Gold Project Stage I report dated March 1982

Pevier of Stane T

This locument is of limited use and contains no statement on the reclamation of the tailings area.

# Current status of their apolication for a reclamation marrit:

By lotter when March 15, 1982, David Minorals has been requested to a vie for a reclamation permit. To response to date.

Ĩ.," 17.111 1943 lec1 tion. Ntor

.It w/apa

Our File: M-85

Rm. 105, 525 Superior St. Victoria, B.C. V8V 1T7 387-3781

March 15, 1982

Mr. N.C. Croome, P.Eng. Secretary-Treasurer David Minerals Ltd. 1016 - 475 Howe Street VANCOUVER, B.C. V6C 2B3

Dear Mr. Croome:

Thank you for your letter of February 2, 1982 advising of your purchase of the H.B. Mine. Our apology in the delay of reply.

In order to apply for a reclamation permit you must submit a reclamation plan. I have enclosed a format which may assist you in the preparation of this report and realize that much of this checklist will not apply to your proposed custom milling operation. Particular attention should be paid to describing the nature of the tailings material and its potential to support plant growth.

Once you have filed this report you are required to publish "Notice of Filing" pursuant to Section 10, subsection (4) of the Mining Regulation Act.in the B.C. Gazette and the local daily newsayper. (Form attached.) It is only necessary to publish the Notice once. Please provide us with the tear sheets and date "Notice of Filing" appeared in the Gazette and newspaper as the dates are required for inclusion in the necessary Order-in-Council. Instruction regarding security deposit will be following after approval by Order-in-Council.

If you require any additional information regarding the requests of this report please do not hesitate to call.


Yours very truly,

J.D. McDonald, P.Eng. Senior Reclamation Inspector

J.C. Errington, P.Ag. Reclamation Inspector

JCE/eass

Ministry of Energy, Mines and Petroleum Resources Parliament Buildings Victoria British Columbia V8V 1X4



387-3781

Room 105 525 Superior Street Victoria, B. C. V8V 1T7

March 10, 1982

Mr. R.T. Gardiner, P.Ag. Reclamation Agronomist Cominco Ltd. TRAIL, B.C. VIR 4L8

Dear Mr. Gardiner:

Re: Annual Report 1981 Permit: M-85 Property: H.B. Mine

This will acknowledge receipt of your Annual Reclamation Report for the above property.

Yours very truly,

J. D. McDONALD, P.ENG., Senior Reclamation Inspector

12 Lites

J. C. Errington, P.Ag., Reclamation Inspector

JCE: kw/eaa

c.c. J.B.C. Lang A. O'Bryan

> Page 754 EGM-2013-00163

Cominco Ltd./Trail, British Columbia, Canada V1R 4L8 Tel. (604) 364-4222/Telex 041-4426



Rec'd

Mr. J.D. McDonald Senior Reclamation Inspector Ministry of Energy, Mines & Petroleum Resources 525 Superior Street Victoria, B.C.

February 8, 1982

Dear Mr. McDonald:

Re: Cominco Ltd. H.B. Mine, Surface Work<sup>1</sup>Permit M-85

Respectfully submitted are three copies of the 1981 report on progress of reclamation at the H.B. Mine located near Salmo, B.C. Preparation of the report was completed prior to receiving a copy of the revised reporting format. We have taken the liberty of submitting the report as prepared since all requested information was included in the report. We trust the report is satisfactory.

During 1981, the mine-mill complex including equipment, surface structures, buildings and land were sold by Cominco Ltd. to David Minerals Ltd., 1004-595 Howe Street, Vancouver, B.C. V6C 2T5. Formal notification of this sale will be forthcoming following legal transfer of title to property to the new owners.

Yours sincerely,

Hardin

R.T. Gardiner, P. Ag. Reclamation Agronomist

RTG/jb

Enclosures

1016-475 Howe Street, Vancouver, B.C. V6C 2B3

Telephone (604) 684-3333



February 2, 1982

Mr. J.D. McDonald, P.Eng. Senior Reclamation Inspector Ministry of Energy, Mimes and Petroleum Resources #105 - 525 Superior Street Victoria, B.C. V8V 1T7

Dear Sir:

Please be advised that David Minerals Ltd. has purchased the assets of the HB Mine located five miles south of the Village of Salmo, British Columbia, consisting of surface rights, Crown Granted and recorded mineral claims, buildings, machinery and equipment.

David Minerals has agreed to assist and fully cooperate with Cominco Ltd. to enable Cominco to obtain refund of its Bond of \$10,000 presently filed with the Government of British Columbia under the Mines Regulation Act. It is in this regard that we wish to apply for a reclamation permit under the said Act. Would you please advise us of the necessary procedure to be followed in obtaining a reclamation permit to enable David Minerals Ltd. to renovate and re-open the HB Mill for treatment of ores, using the existing flotation system.

Thank you for your kind consideration in this matter.

Yours very truly,

DAVID MINERALS LTD.

N.C. Croome, P.Eng. Secretary-Treasurer

NCC: jd



### Ministry of Energy, Mines and Petroleum Resources

# MEMORANDUM

To: FILE NOTE - Cominco - H.B. Mine

Date: May 1, 1981 Our File: M-85

Ken Davies, Cominco telephoned

H.B. Property - \$10,000.00 Bond.

They are negotiating to sell the H.B. Property and enquired whether they would get the bond back upon the completion of sale.

I said that the bond would be returned on the condition that the new owner assumed the responsibility for reclamation and posted a separate bond.

J.C. Frrington, P.Ag. Inspector of Mines (Reclamation)

JCE/eas

cc: J.D. McDonald



To: FILE NOTE - Cominco - H.B. Mine

MELIORANDUM

Date: May 1, 1981 Our File: M-85

Ken Davies, Cominco telephoned

H.B. Property - \$10,000.00 Bond.

qui

They are negotiating to sell the H.B. Property and enquired whether they would get the bond back upon the completion of sale.

I said that the bond would be returned on the condition that the new owner assumed the responsibility for reclamation and posted a separate bond.

J.C. Errington, P.Ag.

J.C. Errington, P.Ag. Inspector of Mines (Reclamation)

JCE/eas

(/cc: J.D. McDonald

- File H.B Talked R. Causen.



Ministry of Energy, Mines and Petroleum Resources Parliament Buildings Victoria British Columbia V8V 1X4

Our File: M-85

387-3781

Room 105 525 Superior Street Victoria, B. C. V&V 1T7

April 10, 1981

Cominco Ltd. Trail, B. C. VIR 4L8

Attention: R. T. Gardiner Reclamation Agronomist

Dear Sir:

Re: Annual Report 1980 Permit: M-85 Property: H. B. Operations

This will acknowledge receipt of your Annual Reclamation Report for the above property.

Yours very truly,

J. D. McDONALD, P.ENG., Senior Reclamation Inspector C. C. J. C. Errington, P.Ag.,

Reclamation Inspector

JCE:kw

c.c. A. L. O'Bryan, Reclamation Inspector Technician - Nelson
J. B. C. Lang, District Inspector - Nelson



Cominco Ltd./Trail, British Columbia, Canada V1R 4L8 Tel. (604) 364-4222/Telex 041-4426



Mr. J.D. McDonald Senior Reclamation Inspector Ministry of Energy, Mines & Petroleum Resources

525 Superior Street Victoria, B.C.

April 2, 1981

AT THE REPORT OF 1400 141 ·······

Dear Mr. McDonald:

Re: Permit M-85: Cominco Ltd., H.B. Mine

Please find enclosed three copies of the Annual Reclamation Report for 1980 and Proposed Program for 1981 for the H.B. Mine.

Yours sincerely,


R.T. Gardiner, P.Ag. Reclamation Agronomist

RTG/jb

Enclosures



Page 760 EGM-2013-00163



# GOVERNMENT OF THE PROVINCE OF BRITIS, COLUMBIA REGISTRAR OF SECURITIES DEPARTMENT OF FINANCE VICTORIA, B.C. V8V 1X4

DATE September 5

1980

TO:- . Cominco Ltd.


INFLUCT

.200 Granville Street

- Vancouver, B. C.
- . V6C 2R2

File: 2112

WE HAVE TODAY FORWARDED TO YOU BY REGISTERED MAIL, THE FOLLOWING SECURITIES:



Our File: M-85

Room 105 525 Superior Street Victoria, B. C-V8V 1T7 March 21, 1980 Cominco Ltd. Trail, B. C. VIR 4L8 Attention: R. T. Gardiner, P.Ag., Reclamation Agronomist Dear Sir: Re: Annual Report, Permit M-85 Cominco Ltd., H. B. Mine This will acknowledge receipt of your letter dated March 14, 1980, enclosing your Annual Reclamation Report on the H.B. Mine. Yours very truly,

J. D. McDONALD, P.ENG., Senior Reclamation Inspector

.C.E

J. d. Errington, P.Ag., Reclamation Inspector

JCE:kw

c.c. A. O'Bryan B. Lang Cominco Ltd./Trail, British Columbia, Canada V1R 4L8 Tel. (604) 364-4222 'Telex 041-4426

**Environmental Control** 

EN Doyle Manager Tel (604) 364-4143

FJL Miller Assi. Manager Tel. (604) 364-4152

Mr. J.D. McDonald Senior Reclamation Inspector Ministry of Energy, Mines & Petroleum Resources 525 Superior Street Victoria, British Columbia mand **V8V IT7** 

March 14, 1980

Dear Mr. McDonald:

Re: Permit No. 85: Cominco Ltd. H.B. Mine

Please find enclosed three copies of the Annual Reclamation Report for 1979 and Proposed Program for 1980 for the H.B. Mine.

Roo'd

Wr. C

Con

nem. CP cities

ALD FEILGLEIM RELOURCES

HI

Yours sincerely,

R.T. Gardiner P. Ag. Reclamation Agronomist

RTG:sjs

Enclosure

Our File: M-85

1835 Fort Street Victoria, B. C. V8R 1J6 March 1, 1979 Cominco Ltd. Trail, B. C. V1R 4L8 <u>Attention:</u> R. T. Gardiner Reclamation Agronomist Dear Sir: This will acknowledge receipt of your letter of February 20, 1979 enclosing your Annual Reclamation Report for the H.B. Mine - Permit No. M-85. Thank you for forwarding same to this office. Yours very truly,

J. D. McDonald, P.Eng., Senior Reclamation Inspector

JCE:kw

Energy

Cominco Ltd./Trail, British Columbia, Canada V1R 4L8 Tel. (604) 364-4229/Telex 041-4426

	DEPT. OF MINES
Mr. J.D. McDonald Senior Reclamation Inspect	AND PETROLEUM RESOURCES
Ministry of Energy, Mines & Petroleum Resources 1835 Fort Street	Rec'd 7 7 8 6 1979
Victoria, B.C.	gpor c
February 20, 1979	

Dear Mr. McDonald:

Re: Cominco Ltd. HB Mines Annual Reclamation Report for 1978 and Proposed Program for 1979 Operation and Surface Work Permit M-85

Enclosed are three copies of the aforementioned report each containing an airphoto with transparent overlay documenting operational reclamation activities at the HB mine.

Yours sincerely,

Endurin

R.T. Gardiner Reclamation Agronomist

RTG/bf

Enclosure

Our File: M-85

1835 Fort Streat Victoria, B.C. V8R 1J6

November 10, 1978

Mr. L.M. McBride Solicitor Cominto Ltd. - H.B. Operations TRAIL, B.C. VIR 4L8

Dear Mr. McBride:

#### Re: Section 11, Mines Regulation Act.

Please find enclosed Permit No. M-85 issued to Cominco Ltd. -H.B. Operations authorizing surface work on the H.B. Operations, duly signed and sealed by the Honourable James R. Chabot, Minister of Mines and Petroleum Resources.

Yours very truly,

J.D. McDonald, P.Eng., Senior Reclamation Inspector

JDM/eas

cc: J.B.C. Lang, District Inspector

Encl.

m-85

October 31, 1978

Dr. J.T. Fyles Deputy Minister Ministry of Mines and Petroleum Resources

> Re: Signatures required for attached permits

Attached are two permits each for the following companies which require the Minister's signature and seal.

		t Respor			
ominco L	Ltd	H.B.	Mine	0.I.C.	2411
OMARCO L	1642 -	11.2.	HARE	0.1.0.	441
	ominco l			ominco Ltd H.B. Mine	

These permiss do not require further security deposits.

Please forward these permits to the Minister for his signature and return to Mr. J.D. McDonald, Senior Reclamation Inspector, for processing.

VED

W.C. Robinson, P.Eng., Chief Inspector of Mines

/eas



APPROVED AND ORDERED SEP. -7. 1978

10Bur Lieutenant-Governor

ENECUTIVE COUNCIL CHAMBERS, VICTORIA SEP. -7. 1978

Pursuant to the Section 11, Mines Regulation Act, and upon the recommendation of the undersigned, the Lieutenant-Governor, by and with the advice and consent of the Executive Council, orders that

the programme and report concerning the mining programme of Cominco Ltd. - H.B. Operations on property located near Salmon River south of Salmo, dated December 23, 1977, compiled in accordance with Section 11 of the Mines Regulation Act, is hereby approved for renewal of Permit Number M-85 on a permanent basis.

AND FURTHER ORDERS THAT the form and the amount of the security deposit for this renewal shall be the security deposit in the amount of \$10,000.00 presently held by the Minister of Finance.

Minister of Mines and Petroleum Resources

11.1

Presiding Member of the Executive Council

Page 769 EGM-2013-00163

Our File: M-85

1835 Fort Street Victoria, B. C. V8R 1J6

June 13, 1978

Cominco Ltd. Box 2000 Kimberley, B. C. VLA 2G3

Dear Sirs:

Re: Surface Work Permit No. M-85 H. B. Mine Project

The period of Surface Work Permits granted by the Minister of Mines and Petroleum Resources, is being changed from 3 years to permanent. Would you please, therefore, forward your copy of the Surface Work Permit, so that the appropriate change can be made, is you have not already done so.

An annual report of work and reclamation is still bequired and on the basis of this, and field inspections, bonding will be adjusted.

Yours very truly,

J. D. McDonald, P.Eng., Senior Reclamation Inspector

DMG: low

1835 Fort Street Victoria, B.C. V8R 1J6

May 24, 1978

Mr. R.E. Jones Mill Superintendent H.B. Operations Cominco Ltd, SALMO, B.C. VOG 120

Dear Sir:

### Re: Surface Work Permit #85

Thank you for submitting the extra copies of maps which we requested to accompany previously submitted 1977/1978 reclamation work report.

This material will be foviewed by the Advisory Committee on Reclamation and you will be notified as soon as it has been considered.

Renewal will be on a permanent basis.

Yours very truly,

J.D. McDonald, P.Eng., Senior Reclamation Inspector

DMG/bm

bcc: Bruce Lang Art O'Bryan

### ADVISORY COMMITTEE ON RECLAMATION

To: Mr. W.C. Robinson, Chairman, Ministry of Mines & Petroleum Resources Mr. D.M. Galbraith, Ministry of Mines & Petroleum Resources Dr. J.C. Errington, Ministry of Mines & Petroleum Resources Mr. A.S. Schori, Ministry of Agriculture Mr. T.A.J. Leach, Ministry of the Environment Mr. E. Smith, Ministry of Forests Mr. D. Zirul, Ministry of the Environment Mr. B. Pendergast, Ministry of Recreation & Conservation (Coal) Mr. G. Newcombe, Ministry of Recreation & Conservation (Mineral)

#### Re: Mines Regulation Act, Section 11

Information is attached for your review as noted below. A committee meeting will be called in the near future to discuss approval of Surface Work Permits. Please contact me if you have any questions.

M.R.A. Permit No. 85,

H.B. Mine, Cominco Ltd. 1977/78 Work/Reclamation Report

Yours very truiy,

J.D. McDonald, P.Eng., Senior Reclamation Inspector

DMG/bm

Cominco Ltd./H. B. Mine, Salmo, British Columbia, Canada, V0G 1Z0/Tel. (604) 357-2276



D. M. Galbraith Reclamation Inspector 1837 Fort St. Victoria, B.C.

May 3, 1978

Dear Sir:

Enclosed are six copies of the map sent into Mr. J.D. McDonald with our application for extension of Reclamation Permit No.85 as per your request.

Yours truly,

R. Wyka Acting Superintendent

RW:mfl

Enclosures (6)

ትሥባ	DEPT. OF MILLES
12010	PERSONEUR RESOURCES
	1579

Mines

1819

Canada

Envire ement Environment Canau

Protection de Environmental **I'Environnement** Protection

H.B. Mark 35

4th Floor, Kapilano 100, Park Royal, West Vancouver, B.C. V7T 1A2

April 20, 1978

Mr. R. Wyka, Mine Manager, Cominco Ltd., H.B. Mine, Salmo, B.C. VOC 120



Our file Notre reletence 4780-37/C685-2

Dear Mr. Wyka:

AA 1003 100 1751

Re: Effluent Quality Survey, October, 1977

As you are aware, during the period from October 4-6, 1977, the Environmental Protection Service conducted a study to determine the quality of the Cominco H.B. mine tailings pond decant. Samples were collected for chemical and bioassay analyses. We have enclosed for your information and records a copy of the results obtained.

A review of the data indicated that the decanted effluent is in compliance with the effluent quality requirements of our "Metal Mining Liquid Effluent Guidelines" for all parameters except fish toxicity. Based on the available data we are unable to determine the component or components of the effluent contributing to the toxicity.

Under normal circumstances, we would be concerned about the discharge of toxic effluent to the Salmo River and would be endeavouring to have this problem resolved. However, noting that the effluent is only marginally toxic and that your mine will be shutting down in September 1978, we are willing to live with the existing situation until the specified closure date.

With respect to site reclamation following mine closure, we have made arrangements with the Ministry of Mines and Petroleum Resources to obtain from that agency a copy of your plans for reclamation when submitted. Following our review of the plans, we will be providing comments as required to that Ministry for incorporation in their agreement with your Company.

..2

Page 774 EGM-2013-00163 If you have any questions or comments with respect to the enclosed data, please feel free to contact Mr. J. Villamere or Mr. G. Trasolini (telephone number 666-6711) of my staff.

Yours truly, ORIGINAL SIGNED BY B. A. HESKIN A SIGNE L'ORIGINAL

B. A. Heskin, P. Eng., Regional Director General, Pacific Region, Environmental Protection Service, Department of Fisheries and the Environment

Encl.

cc: Mr. W.N. Venables, P. Eng., Director, Pollution Control Branch, Water Resources Administration, Ministry of the Environment, Parliament Buildings, Victoria, B. C. V8V 4S5.

Mr. J. McDonald, Senior Reclamation Inspector, Ministry of Mines and Petroleum Resources, 1837 Fort Street, Victoria, B.C. V8R 1J6

Page 775 EGM-2013-00163

## COMINCO H.B. MINE

· .

## TAILINGS POND DECANT

### COMPOSITE SAMPLE RESULTS

October 4 - 6, 1977

•

### A. CHEMICAL ANALYSES

PARAMETER	DAY 1	DAY 2	DAY 3
As (T) mg	/1 0.004	0.004	0.005
Cd (T) mg	/1 <0.01	<0.01	<0.01
Cd (D) mg	/1 <0.01	<0.01	<0.01
Cu (T) mg	/1 0.02	0.02	0.01
Cu (D) mg	/1 <0.01	<0.01	<0.01
Нд (Т) μд	/1 <0.2	<0.2	<0.2
Ni (T) mg	/1 <0.05	<0.05	<0.05
Ni (D) mg	/1 <0.05	<0.05	<0.05
Pb (T) mg	/1 0.1	<0.1	0.1
Pb (D) mg	/1 0.03	0.04	0.04
Zn (T) mg	/1 0.09	0.08	0.08
Zn (D) mg	/1 0.05	0.07	0.07
N.F.R. mg	/1 <5	< 5	<5
рH	7.5	7.6	7.5

<u>B.</u>	TOXICITY DETERM	INATION	
	•	DAY 1	DAY
	LC <sub>50</sub> (96 hour)	56%	73%

# COMINCO H.B. MINE TAILINGS POND DECANT

GRAB SAMPLE RESULTS

October 5, 1977.

## PARAMETER

As	(T)	mg/l	0.004
Cđ	(T)	mg/l	<0.01
Cd	(D)	mg/l	<0.01
Cu	(T)	mg/l	0.01
Cu	(D)	mg/l	<0.01
Hg	(T)	µg/1	<0.2
Ni	(T)	mg/l	<0.05
Ni	(D)	mg/l	<0.05
Pb	(T)	mg/l	0.1
Pb	(D)	mg/l	0.03
Zn	(T)	mg/l	0.09
Zn	(D)	mg/l	0.04
N.F	.R.	mg/l	<5
pН			7.5

Page 777 EGM-2013-00163 Hon. J.R. Chabot

Minister of Mines & Petroleum Resources BUILDINGS

> Subject: Cominco Ltd. - Request for extension of Surface Work Permit, pursuant to Section 11. Mines Regulation Act.

Pursuant to Section 11, Mines Regulation Act, the reclamation programme of Cominco Ltd. is approved on a permanent basis with no increase of security bonding at this time. Cominco Ltd. has submitted a programme dated January 1978 which has been considered by all affected ministries of Government at an Advisory Committee Meeting on Reclamation held June 5, 1978, and approved by yourself, June 30, 1978.

The reclemation report has been filed and approved and Notice of Filing was published in the B.C. Gazette on May 1, 1978 and in the local daily newspaper May 1, 1978 and no representations have been made by others affected by the report.

> JAMES T. FYLES Deputy Minister

/eas

1-5 21

MEMORANDUM FROM W. C. Robinson, P.Eng., Chief Inspector TO The Honourable James R. Chabot Minister

Ministry of Mines and Petroleum Resources



DATE. June 30, 1978.

### Re: Surface Work Permit No. M-85 Cominco Ltd., HB Mine Pursuant to Mines Regulation Act

Cominco Ltd. has submitted to the Ministry of Mines and Petroleum Resources, their Reclamation Report, dated December 23, 1978. This has been reviewed by Mr. J. D. McDonald, Senior Reclamation Inspector and has been submitted to the Advisory Committee on Reclamation. It has been recommended that approval be granted on a permanent basis.

Work at the HB Mine will be terminated this fall. Field and laboratory research is underway to determine the most effective means for revegetation of both tailings and waste dumps. Level of bonding is considered to be adequate for the closing phase.

If you concur with these recommendations, please indicate so by signing this memorandum and returning to Mr. J. D. McDonald for processing.

W. C. Robinson, P.Eng., Chief Inspector of Mines

DMG:kw

c.c. Dr. J. T. Fyles

Our File: M-85

1835 Fort Street Victoria, B.C. V8R 1J6

June 30, 1978

Mr. R. Wyka Superintendent Cominco Ltd. H.B. Mine SALMO, B.C. VOG 120

Dear Sir:

## Re: Surface Work Permit No. M-85 Cominco Ltd, H.B. Mine

The Advisory Committee on Reclamation has recommended approval of renewal of your Surface Work Permit. This will be on a permanent basis, and no further applications need be made.

An Annual Report of work and reclamation will still be required and adjustment of bonding will be done on this basis.

If you have not already done so please advise this office when your report has been advertised. Forms attached.


Please also forward your copy of the permit so the change to permanent status can be made.

Yours very trugy,

J.D. McDonald, P.Eng., Senior Reclamation Inspector

DDG/eas

cc: J.B.C. Lang, District Inspector A. O'Bryan, District Reclamation Inspector Technician Cominco Ltd./Trail, British Columbia, Canada V1R 4L8 Tel. (604) 364-4222/Telex 041-4426



FHP Dewdney Regional Counsel Tel (604) 364-4114

LM McBride Solicitor Tel. 1604) 364-4106

TD Tutti Solicifor Tel (604) 364-4109 Mr. J.D. McDonald Senior Reclamation Inspector Ministry of Mines and Petroleum Resources 1835 Fort Street Victoria, B. C. V8R 1J6

June 27, 1978

re: Permit No. 85 - H.B. Mine

Dear Sir:

Pursuant to your letter dated June 13, 1978 addressed to our Kimberley Office, I enclose herewith Permit No. 85 to be amended as indicated in your letter.

After the permit has been amended to read "permanent" please return to the attention of L. M. McBride, Solicitor, Cominco Ltd., Trail, B. C. VIR 4L8


Yours very truly,

MMakrie

L. M. McBride

LMM:A Encl.

REGISTERED



M-85

Nelson Daily News 266 Baker St. Nelson, B.C.

April 19, 1978

Dear Sir or Madam:

Please insert the enclosed advertisement in your paper beginning with "Mines Regulation Act" in the form as shown.

We would like to have this advertisement placed in your paper on May 1st, 1978 for the one day only.

Please forward the bill for this advertisement to

Cominco Ltd. H.B. Operations Salmo, B.C. VOG IZO

Yours truly,

R. Wyka Acting Superintendent

RW:mfl

Enclosure

cc: Dept. Of Mines

## RE: SECTION 11, MINES REGULATION ACT

Notice of the filing of the report with the Minister, as required by Subsection 4 of Section 11, is to be in the form as follows:

## MINES REGULATION ACT

Notice pursuant to Section 11

Take notice that . Robert Wyka (owner, agent or manager)

of . . . . H.B. Mine, Cominco Ltd. (name(s) of mine(s) and/or company)



	AND	DEPT. OF MINES PETROLEUM RESOURCES
	Rac'd	APR 24 1978
à		

B. C. Gazette Victoria, B.C.

Alines

April 19, 1978

Dear Sir or Madam:

Please insert the enclosed advertisement in your paper beginning with "Mines Regulation Act" in the form as shown.

We would like to have this advertisement placed in your paper on May 1st, 1978 for the one day only.

Please forward the bill for this advertisement to

Cominco Ltd. H.B. Operations Salmo, B.C. VOG IZO

Yours truly,

R. Wyka Acting Superintendent

RW:mfl

Enclosure

cc: Dept. of Mines√

### RE: SECTION 11, MINES REGULATION ACT

Notice of the filing of the report with the Minister, as required by Subsection 4 of Section 11, is to be in the form as follows:

## MINES REGULATION ACT

Notice pursuant to Section 11

Take notice that . Robert Wyka (owner, agent or manager)

of .....H.B. Mine, Cominco Ltd. (name(s) of mine(s) and/or company)

has filed with the Minister of Mines and Petroleum Resources at Victoria a report made pursuant to Section 11 of the Act in respect to the surface mine(s) located at . Salmo, B.C.

> Page 785 EGM-2013-00163

1835 Fort Street Victoria, B.C. V8R 1J6

April 11, 1978

Mr. R. Wyka Superintendent Cominco Ltd, H.B. Mine SALMO, B.C. VOG 120

Dear Sir:

### Re: Section 11, Mines Regulation Act Permit No. 85 - H.B. Mine Operations Cominco Ltd.

This will acknowledge with thanks your letter of March 15, 1978 requesting renewal of Permit No. 85. This will be reviewed at the next Advisory Committee on Reclamation meeting.

Renewals require that the application be advertised. Attached is the appropriate form to be used. The advertisement is to be placed once only in the B.C. Gazette and once only in the Nelson Daily News. This office is to be advised as to the date of the advertisement along with a copy.

Yours very truly,

JDN

J.D. McDonald, P.Eng., Senior Reclamation Inspector

JDM/bm



Rec'd MAR 2 9 1978	AND	DEPT. OF MINES PETROLEUM RESOURCES

Mr. J.D. McDonald Senior Inspector of Mines - Reclamation Ministry of Mines and Petroleum Resources Parliament Buildings Victoria, B.C. V8V 2M2

March 15, 1978

Dear Sir: Re:

Please accept this letter as an application for extension of Reclamation Permit No. 85.

Reclamation Permit No. 85 H.B. Mine Operations.

Section II, Mines Regulation Act

Permit No. 85 was issued March 28, 1978, authorizing surface work at H.B. Operations for a period of 5 years.

In compliance with items 6, 7, 8 and 9 of the Terms and Conditions of this permit a program of research on land reclamation has been carried out since 1973. Progress of research has been recorded in the yearly reports previously submitted to the Senior Reclamation Inspector.

It is intended to terminate current mining operations as of September 1st, 1978 although the plant is to remain on the property for at least another year. Progress of the reclamation research program for 1978 will be submitted to the Senior Reclamation Inspector by January 31, 1979.

Land disturbance subsequent to March 28, 1978 will be very minimal or unchanged from the present time. The nature, extent and location of disturbed land at H.B. Operations is summarized in Table I and illustrated in Figure I.

Continued .....

The disposal of some buildings around the 3500 level area will begin in 1978 as well as the surface preparation of the 3500 level waste dump. The reclamation of the remaining waste rock dump, plant and service area, tailings pond and roads will be done subsequent to the removal of the mill and attendant buildings. This removal will be contingent upon a decision to do custom milling in the future.

We trust that our request for permit renewal will meet with your approval.

Yours truly,

R. Wyka Superintendent

RW/das

cc: E.N. Doyle K.V.S. Meyer R.T. Gardiner R.E. Jones

TABLE I.	TOTAL ACREAGE OF DISTURBED AND REVEGETATED LAND AT H.B. OPERATIONS.

	AREA (he	ctares)
NATURE OF DISTURBANCE	MARCH 28, 1973	MARCH 28, 1978
Waste Rock Dumps: 2800 Level 3500 Level	0.9 (2.2 acres) 0.1 (0.2 acres)	0.9 0.1
Open Pit	0	2.4
Tailings Impoundment	24.3 (60 acres)	24.8
Tailings Dam Construction and Borrow Pits	0	3.4
Buildings and Service Areas	4.0 (10 acres)	1.6
Roads	1.6 (4.0 acres)	2.5

1835 Fort Street, Victoria, B.C. V&R 1J6.

January 3rd, 1978.

Mr. F. E. Jones, Mill Superintendent, H.B. Operations, Cominco Ltd., Salmo, B.C. VOG 120

Dear Sir:

#### Re: Progress Report - 1977.

This will acknowledge receipt of your letter of December 23rd, 1977 enclosing "Mined Land Reclamation at Cominco Ltd., H.B. Operations, Salmo, B.C. Progress Report 1977".

Thank you for forwarding same to this office.

Yours very truly,

J. D. McDonald, P.Eng., Senior Reclamation Inspector.

JDM: jau

**DEPT. OF MINES** AND PETROLEUM RESOURCES Rec'd DEC 3 0 1977 Cam nen 68 Mines Mr. J.D. MacDonald Dale Senior Reclamation Inspector Mineral Resources Branch Ministry of Mines and Petroleum Resources Parliament Buildings Victoria, B.C.

December 23, 1977

Mr. MacDonald:

V8V-1X4

I am enclosing one copy of the "Mined Land Reclamation at Cominco Ltd., H.B. Operations, Salmo, B.C. Progress Report 1977" for your files.

The report explains the work which was carried out in 1977 on reclamation studies and also a brief idea as to the work planned for 1978.

Yours Truly

min

R.E. Jones Mill Superintendent H.B. Operations

RJ/das

1835 Fort Street, Victoria, B.C. V8R 1J6.

March 1, 1977.

Cominco Ltd., H.B. Mine, Salmo, British Columbia. VOG 120.

Attention: Mr. R. Wyka, Coting Superintendent.

Dear Sir:

Re: Progress Report - 1976.

This will acknowledge, with thanks, receipt of your letter of February 23, 1977 enclosing "Progress Report 1976" regarding Permit No. 85 submitted pursuant to Section 11 of the Mines Regulation Act.

Yours very truly,

J.D. McDonald, P.Eng,, Senior Reclamation Inspector.

JDM: jau



Page 792 EGM-2013-00163



Mr. J. D. McDonald Senior Reclamation Inspector Department of Mines and Petroleum Resources Parliament Buildings Victoria, B.C.

February 23, 1977

Dear Sir:

Enclosed is our report on reclamation research at H.B. Mine for the year 1976.

Yours sincerely,

R. Wyka Acting Superintendent

RW:mfl

Enclosure

Mines

1835 Fort Street, Victoria, B.C. V8R 1J6.

January 29th, 1976.

Mr. H.G. Barker, Superintendent, Cominco Ltd., H.B. Mine, SALMO, British Columbia. VOG 120.

Dear Sir:

This will acknowledge receipt of your letter dated January 27th, 1976 enclosing Progress Report on Land Reclamation at your H.B. Operations for the year 1975 which includes proposed 1976 programme.

Thank you for forwarding same to our office.

Yours very truly,

J.D. McDonald, P.Eng., Senior Reclamation Inspector.

JDM: jau



Rec'd

11

DEPT. OF MINES

AND PETROLEUM RESOURCES

JAN 2 9 1976

Mr. J. D. McDonald Senior Reclamation Inspector Department of Mines and Petroleum Resources 1835 Fort St. Victoria, B.C. V84 IJ6

January 27, 1976

Dear Mr. McDonald:

Enclosed is our Progress Report on Land Reclamation at our H.B. Operations.

Yours sincerely,

H. G. Barker Superintendent

HGB:mfl

Enclosure

Mines

Mined-Land Reclamation at Cominco Ltd.

H.B. Operations Salmo, B.C.

Progress Report 1975

R.T. Gardiner, P.Ag. Reclamation Agronomist

J.E. Stathers Assistant Reclamation Agronomist

Cominco Ltd. Trail, B.C.

> Page 796 EGM-2013-00163

## Table of Contents

Mined-Land Reclamation at Cominco Ltd. - H.B. Operations

Salmo, B.C.

## Progress Report 1975

		Page
1.	Introduction	1
2.	Mining Program	1
3.	Reclamation Research	
	3.1 Suitability of H.B. Tailings as a Liming Material	1
	3.2 Climatic Conditions During 1975	2
4.	Operational Reclamation	2
5.	Proposed Research and Operational Reclamation Programs for 1976	5
6.	References	2
7.	List of Tables	3

Mined-Land Reclamation at Cominco Ltd.

H.B. Operations Progress Report 1975

#### 1. Introduction

The general approach to reclamation of disturbed land surfaces at H.B. Operations is to improve growth conditions on waste disposal and other disturbed land areas and to encourage succession of native vegetation. Establishment and maintenance of an initial vegetative cover of grass and legume species will accelerate soil formation, control erosion, provide forage for wildlife, and improve the aesthetic appearance of disturbed land surfaces.

### 2. Mining Program

Land areas disturbed at H.B. Operations were described in "Application for Permit Authorizing Surface Work - Cominco Ltd., H.B. Operations, January, 1973", and the "Mined-Land Reclamation Research Report 1974"(1,2). Mining operations in 1975 conformed to the plans outlined in the original permit application. During 1975 construction of access roads to surface diamond drilling sites disturbed 0.7 acres. Land disturbed in construction of the lift to the tailings dam was inspected by Mr. Art O'Brien, Reclamation Inspector, on October 7, 1975. Improvement of drainage along the access road has been completed as suggested. Revegetation of the borrow pit will be carried out when more definite information related to future construction of the tailings dam and further disturbance to the borrow pit area is available.

The nature and extent of land surfaces disturbed to the end of 1975 are summarized in Table 1.

#### 3. Reclamation Research

#### 3.1 Suitability of H.B. Tailings as a Liming Material

The feasibility of using calcareous H.B. tailings as a liming material for neutralization of acidic mill waste at Sullivan Operations has been investigated since 1973(3). Mixing H.B. tailings at 25% by weight with oxidized iron and siliceous tailings reduced salt concentrations and maintained the pH within a range tolerated by most plant species for a period of 20 weeks in growth chamber studies.

The cost of commercial liming materials varies with purity (content of magnesium and heavy metals), degree of fineness or particle size, and calcium carbonate equivalence or neutralizing capacity. In 1975 a study was carried out to determine the suitability of calcareous tailings from three Cominco Ltd. operations as liming materials (unpublished report by Stathers and Gardiner, 1975). H.B. tailings has a particle size and calcium carbonate equivalence (the major factors affecting rate of neutralization in an acid medium) comparable to agricultural grade dolomitic limestone. The total lead and zinc content of H.B. tailings is high relative to agricultural grade dolomitic limestone (Table 2).

> Page 798 EGM-2013-00163

Page 2

## 3.2 Climatic Conditions During 1975

A summary of weather data recorded during 1975 at the B.C. Forest Service weather station located approximately 10 miles north-west of the H.B. mine is presented (Table 3). Precipitation during the 1975 growing season (May through September) was 283.2 mm. The period May through September 1975, had a mean monthly temperature of 13.9°C. The frost free period was 101 days, occurring between June 9 and September 18.

## 4. Operational Reclamation

In April 1974, approximately 2 hectares of road cut embankments were hydroseeded in an attempt to reduce surface creep and erosion(2). Maintenance fertilizer the equivalent of 66 Kgm/ha was applied to hydroseeded areas on April 29, 1975. Subjective evaluation of vegetative growth in September, 1975 indicated that where adequate plant populations had established plant growth was vigorous. Limitations to plant growth appeared to be caused by instability of steeply sloping embankments and soil moisture deficiency, rather than nutrient deficiency. On steeply sloping road cuts constructed through coarse-textured material vegetative cover was sparse. On gradually sloping embankments composed of finertextured material, and seepage sites, vegetative cover was satisfactory.

# 5. Proposed Research and Operational Reclamation Programs for 1976

Reclamation research investigations planned for H.B. Operations during 1976 will include:

- a) establishment of field experiments on shallow tailings deposited adjacent the tailings pipeline
- b) continuation of growth chamber studies to determine cultural techniques and plant species for revegetation of tailings and tailings slimes.

#### 6. References

- (1) Barker, H.G., 1973. Application for permit authorizing surface work -Cominco Ltd., H.B. Operations, Submitted to Senior Inspector of Mines, Reclamation, Dept. of Mines and Petroleum Resources, Parliament Buildings, Victoria.
- (2) Gardiner, R.T., 1975. Mined-Land Reclamation Research at H.B. Operations, Progress Report 1974, Submitted to Senior Reclamation Inspector, Dept. of Mines and Petroleum Resources, Parliament Buildings, Victoria, January 31, 1975.
- (3) Gardiner, R.T., 1975. Mined-Land Reclamation Research at Sullivan Operations, Progress Report 1974, Submitted to Senior Reclamation Inspector, Dept. of Mines and Petroleum Resources, Parliament Buildings, Victoria, January 31, 1975.

## Page 3

7. List of Tables

Table 1: Disturbed Land at H.B. Operations

Table 2: Characterization of H.B. Tailings as a Liming Material

Table 3: Weather Summary for 1975.











Page 800 EGM-2013-00163

Table 1:	Disturbed	Land at	H. B.	Operations

Nature of Disturbance	Area (Hectares)
Waste rock dumps: 2800 level	0.9
3500 level	0.1
Open pit	2.4
Tailings impoundment	24.8
Buildings and service area	1.6
Roads	2.3
	34

Table 2:	Characterization	of	H.B.	Tailings	as	a	Liming Materia	11
10 10 10 10 10 10 10 10 10 10 10 10 10 1		COLUMN TO A	CONCERNMENT OF THE OWNER	Contraction of the second second second second second second second second second second second second second s	and the second second	Married Woman	the second second second second second second second second second second second second second second second s	Citer Trees

Property	H.B. Tailings	Agricultural Dolomitic Limestone		
Particle Distribution (%)				
mesh size -4 -8 -20 -40 -60 -80 -100	100 100 99.4 98.3 98.0 96.7 94.6	100 100 87.5 80.5 62.5 42.3 26.8		
CaCO3 Equivalence (%)	84	87		
Total Pb content (ppm)	445	80		
Total Zn content (ppm)	3000	225		

Page 801 EGM-2013-00163

### Table 3:

## Weather Summary for the Year: 1975 Station: B.C. Forest Service, Salmo, B.C.

Month	Temperature °C			Precipitation				
	Means			Extremes		Rain	Snow	Total
	Max	Min	Mean	Max	Min	mm	cm	mm
Jan	-2.3	-11.3	-6.8	4.4	-23.3	5.59	111.51	117.09
Feb	1.4	-10.7	4.6	7.2	-23.3	25.40	86.61	112.01
Mar	5.3	-5.5	-0.1	8.3	-13.9	205.99	25.91	231.90
Apr	11.8	-3.3	4.2	20.0	-12.8	36.30	60	36.30
May	18.8	0.7	9.7	28.3	-7.2	38.10	-	38.10
Jun	21.1	6.0	13.5	28.9	0	71.88	6536	71.88
Jul	28.4	10.6	19.5	37.7	1.7	69.34	-	69.34
Aug	23.1	7.9	15.5	31.1	3.9	94.74	-	94.74
Sep	23.1	3.5	11.6	27.8	-0.6	9.14	-	9.14
Oct	9.6	1.5	5.6	25.0	-5.6	143.00	5.59	148.59
Nov	4.1	-5.4	-1.0	16.7	-13.3	83.30	-	83.30
Dec	n.a.	n.a.	n.a.	n.a.	n.a.	n.a,	n.a.	n.a.

1 In rainfall equivalents: 1 cm snow = 1 mm rain

Mean annual temperature: n.a. Mean monthly temperature: January -6.8°C Mean monthly temperature: July 19.5°C Months above 10°C: 4 Months below O°C: 4 Months above 4.5°C: 6 Frost free days (period): June 9 - Sept. 18 (101 days) Total annual precipitation: n.a. Annual snowfall: n.a. Season occurrence of ppt: Wet season n.a. Wettest month n.a. Dryest season n.a. Sept. (9.14 mm) Dryest month

> Page 802 EGM-2013-00163

1835 Fort Street, Victoria, B.C. V8P 1J6, May 7, 1974.

Mr. H.G. Barker, Superintendent, H.B. Mine, SALMO, British Columbia.

Dear Sir: Re: Exploration Programme.

This will acknowledge receipt of your "Notice of Opening of a Mine or Quarry or of Work on a Mineral Property".

The exploration work is within the boundaries of your production area and therefore is covered under your Permit 85.

For your information and guidance, enclosed is a copy of "Reclamation Guidelines for Exploration".

Yours very truly,

J.D. McDonald, P.Eng., Senior Reclamation Inspector.

JDM:s1

encl.

cc. - Mr. P.E. Olson, P.Eng., Inspector of Mines.

May, 1972

### NOTICE TO ALL FREE MINERS AND ALL PERSONS ENGAGED IN MINING EXPLORATION

#### **Forest Damage Abatement**

The Department of Forests has become seriously alarmed at the amount of unnecessary damage and waste of forest growth arising out of indiscrimination in the performance of mining exploration work. Included in its summary of areas where damage and waste are taking place are:-

Access roads.

(2) Bulldozed geophysical grid lines.

(3) Drilling-sites.

(4) Trenching.

(5) Mine-camp locations.

The main items of concern are: (1) Slash is not disposed of, leaving very severe hazards from both fire and disease; (2) in many cases access roads are not properly located and much waste takes place where the bulldozer operator makes several attempts to get through; (3) timber is destroyed because little or no care is taken to avoid waste.

Today's concept of forest growth and production is based on a perpetual-yield basis, and every effort must therefore be taken to minimize waste of standing timber as well as the destruction of surface capable of perpetual yield. It need not be construed that legitimate mining exploration work will be unnecessarily hampered by the need for sensible conservation of forest growth, but it is essential for all those in the mining exploration field to recognize that failure to co-operate in carrying out the requirements detailed herein will result in stringent official regulations to the probable detriment of the mining fraternity.

Section 10 of the Mines Regulation Act requires that whenever persons are employed in the opening-up, development, or proving of any mineral deposit, the appropriate District Inspector of Mines shall be notified. The reverse side of this notice is for that purpose.

The object is to establish where and what work is proposed so that the Inspector of Mines and the District Forester, in co-operation, can limit damage and waste.

Section 10 referred to above will be enforced to the point of penalties being imposed for its non-observance.

Section 115 of the Forest Act is quoted below for the benefit of those who may not be aware of the authority of the Forest Service to exercise control;-

115. (1) Where as the result of the carrying-on of any operation for the cutting or removal of trees or timber any slash, including in that expression any brush or debris, is occasioned or accumulated, the person carrying on the operation shall, on the demand of any officer authorized by the Minister, dispose of the slash by burning or otherwise to the satisfaction of the Minister.

(2) Where any person fails or neglects to dispose of any slash at the time and in the manner required under this section, the Minister may dispose of the slash, in which case all expenses incurred therein are forthwith due and payable to the Crown from that person.

The form of notice of exploration work to be done (see reverse side) should be completed in triplicate and one copy forwarded to the Inspector of Mines for the district in which the property lies and one to the District Ranger.

Free miners have rights and privileges! Free miners also have responsibilities and liabilities!

The accepted principles of multiple resource use require that free miners respect the rights of other natural-resource users-loggers, cattlemen, recreationists, water-users, and many others.

# NOTE.-The District Inspector and District Ranger should be notified every time work starts after any shutdown in addition to the original notification.

#### Use of Surface

All claim holders must reach agreement with the owner of the surface rights before commencing the work being reported on the other side of this form. If agreement cannot be reached the Gold Commissioner or Mining Recorder should be contacted as per section 12 (2) of the Mineral Act.

The H.L. Mare .




Please complete and forward one copy to the District Inspec-tor of Mines and one copy to District Forest Ranger.

N	otice of Openin Work of	ng of a Mine	or Quan	AND PETR	TE OF I	MINES RESOURCES
		n a Mineral I Section 10, Mines Reg	~ ~ /	Rec'd M	4Y 6	1974
			uuanon Act)	Ditter 1	1	19/4
. Name of property	H.B. Mi	ne		HILL M		
Location of propert			1			
. Owner's name and	address Cominco	Ltd.	******			
	Trail, f	B.C.				
		******			********	
Operator's name ar	ad address. Same as	above.			************	
. Estimated duration	of specified exploration	n or mine developmen	t programme	Drillin	g Pro	aram
From	May	19 74 to	October			10.74
	er of men to be employ					
		We preserve a surface to be used to prove an a surface week and a				
. Give approximate d	letails of any of the fall				- Product Products	
	letails of any of the foll		ose to do:			oad (12'-
(a) Road construc	tion (distance and widt	th of clearing*) 1000	ose to do: ' - 1200 ' ' of old r	of new oad to t	cat r be reh	abilitate
<ul><li>(a) Road construct</li><li>(b) Line-cutting (</li></ul>	tion (distance and widt distance, width, and m	th of clearing*) 1000 ethod)	ose to do: ' = 1200 / ' of old r	of new oad to t	cat r be reh	abilitate
<ul><li>(a) Road construct</li><li>(b) Line-cutting (</li></ul>	tion (distance and widt	th of clearing*) 1000 ethod)	ose to do: ' = 1200 / ' of old r	of new oad to t	cat r be reh	abilitate
<ul><li>(a) Road construct</li><li>(b) Line-cutting (</li></ul>	tion (distance and widt distance, width, and m learing other than abov	th of clearing*) 1000 ethod)	ose to do: ' = 1200 / ' of old r	of new oad to t	cat r be reh	abilitate
<ul> <li>(a) Road construct</li> <li>(b) Line-cutting (</li> <li>(c) Total area of c</li> <li>(d) Total area of:</li> </ul>	tion (distance and widt distance, width, and m learing other than abov	1000 th of clearing*)_1000 nethod)	ose to do: ' - 1200 / ' of old r	of new oad to l	cat r be reh	abilitate
<ul> <li>(a) Road construct</li> <li>(b) Line-cutting (</li> <li>(c) Total area of c</li> <li>(d) Total area of: Trenching (square)</li> </ul>	tion (distance and widt distance, width, and m learing other than abov mare feet)	1000 th of clearing*) 1000 tethod)	ose to do: ' - 1200 / ' of old r	of new oad to t	cat r be reh	abilitate
<ul> <li>(a) Road construct</li> <li>(b) Line-cutting (</li> <li>(c) Total area of c</li> <li>(d) Total area of: Trenching (sq Surface stripping)</li> </ul>	tion (distance and widt distance, width, and m learing other than abov pare feet)	h of clearing*)_1000 hethod)	ose to do: ' - 1200 / ' of old r	of new oad to t	cat r be reh	abilitate
<ul> <li>(a) Road construct</li> <li>(b) Line-cutting (</li> <li>(c) Total area of c</li> <li>(d) Total area of: Trenching (sq Surface stripping)</li> </ul>	tion (distance and widt distance, width, and m learing other than abov uare feet) ing (square feet)	h of clearing*)_1000 hethod)	ose to do: ' - 1200 / ' of old r	of new oad to t	cat r be reh	abilitate
<ul> <li>(a) Road construct</li> <li>(b) Line-cutting (</li> <li>(c) Total area of c</li> <li>(d) Total area of: Trenching (sq Surface strippi Test-pitting (s</li> <li>* Include sketch of location</li> </ul>	tion (distance and widt distance, width, and m learing other than abov quare feet) quare feet) quare feet)	1000 (h of clearing*)_1000 (ethod)	ose to do: ' - 1200 / ' of old r	of new oad to t	cat r be reh	abilitate
<ul> <li>(a) Road construct</li> <li>(b) Line-cutting (</li> <li>(c) Total area of c</li> <li>(d) Total area of: Trenching (sq Surface strippi Test-pitting (s</li> <li>* Include sketch of location</li> </ul>	tion (distance and widt distance, width, and m learing other than abov uare feet) ing (square feet)	1000 (h of clearing*)_1000 (ethod)	ose to do: ' - 1200 / ' of old r	of new oad to t	cat r be reh	abilitate
<ul> <li>(a) Road construct</li> <li>(b) Line-cutting (</li> <li>(c) Total area of c</li> <li>(d) Total area of: Trenching (sq Surface strippi Test-pitting (s</li> <li>* Include sketch of location</li> <li>Date Forest Service</li> </ul>	tion (distance and widt distance, width, and m learing other than abov quare feet)	1000 (h of clearing*) 1000 (ethod)	ose to do: ' - 1200 / <u>' of old r</u> 74	of new oad to t	cat r be reh	abi li tate
<ul> <li>(a) Road construct</li> <li>(b) Line-cutting (</li> <li>(c) Total area of c</li> <li>(d) Total area of: Trenching (sq Surface strippi Test-pitting (s</li> <li>* include sketch of location</li> <li>Date Forest Service</li> <li>. When work ceases of</li> </ul>	tion (distance and widt distance, width, and m dearing other than abov quare feet) quare feet) m where necessary. e advised by operator	h of clearing*).1000 ethod)	ose to do: ' - 1200 / <u>' of old r</u> 74	of new oad to t	cat r be reh	abi li tate
<ul> <li>(a) Road construct</li> <li>(b) Line-cutting (</li> <li>(c) Total area of c</li> <li>(d) Total area of: Trenching (sq Surface strippi Test-pitting (s</li> <li>* Include sketch of location</li> <li>Date Forest Service</li> <li>When work ceases of</li> </ul>	tion (distance and widt distance, width, and m learing other than abov quare feet)	h of clearing*).1000 ethod)	ose to do: ' - 1200 / <u>' of old r</u> 74	of new oad to t	cat r be reh	abi li tate
<ul> <li>(a) Road construct</li> <li>(b) Line-cutting (</li> <li>(c) Total area of c</li> <li>(d) Total area of: Trenching (sq Surface strippi Test-pitting (s</li> <li>* Include sketch of location</li> <li>Date Forest Service</li> <li>When work ceases of</li> </ul>	tion (distance and widt distance, width, and m dearing other than abov quare feet) quare feet) m where necessary. e advised by operator	h of clearing*) 1000 h of clearing* h o	ose to do: ' - 1200 / <u>' of old r</u> 74	of new oad to t	cat r be reh	abi li tate
<ul> <li>(a) Road construct</li> <li>(b) Line-cutting (</li> <li>(c) Total area of c</li> <li>(d) Total area of: Trenching (sq Surface strippi Test-pitting (s</li> <li>* Include sketch of location</li> <li>Date Forest Service</li> <li>When work ceases of</li> </ul>	tion (distance and widt distance, width, and m dearing other than abov quare feet) quare feet) m where necessary. e advised by operator	h of clearing*)_1000 h of clearing*)_1000 h of clearing*)_1000 he hold he owner, agent, or n hes (section 10, Mines Signature	ose to do: ' - 1200 ' ' of old r 74 Tanager shall, Regulation A AG	of new oad to t within one cr). Ba	cat r e reh	of cessation,
<ul> <li>(a) Road construct</li> <li>(b) Line-cutting (</li> <li>(c) Total area of c</li> <li>(d) Total area of: Trenching (sq Surface strippi Test-pitting (s</li> <li>* Include sketch of location</li> <li>Date Forest Service</li> <li>When work ceases of</li> </ul>	tion (distance and widt distance, width, and m dearing other than abov quare feet) quare feet) m where necessary. e advised by operator	h of clearing*)_1000 h of clearing*)_1000 h of clearing*)_1000 he hold he owner, agent, or n hes (section 10, Mines Signature	ose to do: ' - 1200 ' ' of old r 74 Tanager shall, Regulation A AG	of new oad to t within one cr). Ba	cat r e reh	of cessation,
<ul> <li>(a) Road construct</li> <li>(b) Line-cutting (</li> <li>(c) Total area of c</li> <li>(d) Total area of: Trenching (sq Surface strippi Test-pitting (s</li> <li>* Include sketch of location</li> <li>Date Forest Service</li> <li>When work ceases of</li> </ul>	tion (distance and widt distance, width, and m dearing other than abov quare feet) quare feet) m where necessary. e advised by operator	h of clearing*) 1000 h of clearing* h of c	ose to do: ' - 1200 / <u>' of old r</u> 74	of new oad to t within one cr). Ba	week	of cessation,

o

Page 805 EGM-2013-00163



Copy of Minute Approved 1 on 28, 1973 - Lieutenant-Gover.

1051.

#### report

THAT pursuent to Section 11 of the Mines Regulation Act, the mining company named herein has submitted a programme for the protection and reclamation of the surface of the land and watercourses to be afforted by its operations:

AND THAT there has been filed with the Minister of Mines and Petroleum Resources a report compilad in accordance with Section 11 of the Mines Regulation Act, that a motice of filing of the report has been published in the Gazette and that the report and the programme has been approved by the aforesaid Minister:

AND THAT after due consideration by all Departments of Government affected by or faterested in the programs submitted, the Minister of Mines and Petroleum Resources is prepared to approve the programmes

AND TO RECOMMEND THAT the Minister of Mines and Petroleum Resources be authorized to issue a permit for a pariod of five years commancing on the date of approval of this Order to the following company:

> Comince Ltd., H.B. Mine \$10,000.00

AND TO FERTHER RECOMMEND THAT the said permit be not issued watik security in the sum shown opposite the name of the company above is received by the Minister of Finance.

DATED THIS	26	DAY OF Mar	A.D. 1973

"Leo T. Nimsick"

Minister of Mines and Petroleum Resources 26 DAY OF Mar A.D. 1973

APPROVED THIS

#### "D. Barrott"

Presiding Member of the Executive Council.

#120 - 1006 Government St., Victoria, British Columbia, July 30, 1973.

Mr. L.M. McBride, Cominco Ltd., Trail, British Columbia.

Dear Sir: Re: Section 11, Mines Regulation Act, and H.B. Mine, Salmo, British Columbia.

Enclosed herewith Permit Authorizing Surface Work, duly signed and sealed by the Minister of Mines and Petroleum Resources, under authorization of Order-in-Council No. 1051.

In particular, your attention is drawn to the Terms and Conditions, which are a part of this permit.

Yours very truly,

J.D. McDonald, P.Eng., Senior Inspector of Mines - Reclamation.

JDM:s1

encl.

cc. - Mr. P.E. Olson, P.Eng., Inspector of Mines & Resident Engineer, Nelson, British Columbia.

THE DEPUTY MINISTER OF FINANCE OFFICE OF THE REGISTRAR PARLIAMENT BUILDINGS VICTORIA, B.C.

# RECORD OF INCOMING REGISTERED MAIL

RECEIVED FROM Corince Lt., Trail. Critich Columbia

strention: L. D. Tehrice

DATE RECEIVED JUNE 25, 1973


YOUR REGISTERED LETTER

3.04

NO. C 99

DATED JUNE 21, 1973

Sio,000.00 Sic: Lept. of Hines - Petroleur reposit Coninco inc. Sic. 000.00 Britich Columbia Ryero are Disar Actually Columbia Ryero are Disar (Se Fugat 35, 1977 No. Co-CR adv (1 x 510,600) Fully registored in the case of a COMMENDATION



INITIALS

Cominco
OEPT. OF MINES AND PETROLEUM RESOURCES
Rac'd JUN 85 1973

FHP Dewdney Regional Counsel Tel. (504) 354-4114

LM McBride

TD Tutti Solicitor Tel. (504) 364-4109 Registrar of Securities Department of Finance Parliament Buildings VICTORIA, B.C.

June 21, 1973

re: Section 11, Mines Regulation Act and security to be furnished -Cominco H. B. Operations -\$10,000.00 Order-in-Council No. 1051

## Dear Sir:

April 3, 1973 the Senior Inspector of Mines, Reclamation advised Cominco that a permit would issue authorizing surface work at its H. B. Operations (located at Salmo, B.C.) for a period of five years upon deposit of satisfactory security with the Minister of Finance. I now enclose 1 x \$10,000 British Columbia Hydro and Power Authority 6% Parity Development Bond due August 15, 1977 numbered CS-ER 669. The bond is registered as to principal and interest in the name of Cominco Limited and annexed to the bond is a stock Power of Attorney executed under seal by the Executive Vice-President and Secretary of the company whose signatures have been guaranteed by a chartered bank.

Upon receipt of the enclosed bond and power of attorney I understand you will so advise the Department of Mines and Petroleum Resources after which the Minister of Mines will sign Permit No. 85. We would request that when the permit is signed by the Minister the original & be forwarded to this office rather than to Mr. H. G. Barker, Superintendent, H. B. Mine. We will then forward Mr. Barker a copy for his information. Page 2/Registrar of Securities/June 21, 1973/ Cominco Ltd.

The bond is deposited for the duration of the permit or any extension thereof and we assume that if there is any breach or alleged breach of the Regulations or Act we will be notified and given the opportunity to remedy the same before the deposit is used.

Yours very truly,

I man a Ruide

L. M. McBride

LMM/mc Encls. <u>Registered Mail</u>

cc: Mr. J. D. McDonald, P. Eng. Senior Inspector of Mines, Reclamation Department of Mines and Petroleum Resources Parliament Buildings Victoria, B.C.

> Page 811 EGM-2013-00163

#120 - 1006 Government St., Victoria, British Columbia, April 3, 1973.

Mr. H.G. Barker, Superintendent, Cominco Ltd., H.B. Mine,

SALMO, BRITISH COLUMBIA.

Dear Sir: Re: Section 11, Mines Regulation Act.

By Order-in-Council No. 1051, approved by the Lieutenant-Covernor in Council on March 28, 1973, a copy of which is enclosed, the Minister of Mines and Petroleum Resources was authorized to issue to you a permit authorizing surface work, for a period of five years, upon deposit with the Minister of Finance of security in the amount as shown in the Order-in-Council.

The security deposit, which should be submitted forthwith, must be in the form of British Columbia parity bonds or cash. It must be deposited directly with the Minister of Finance, as outlined in subsections (6) and (7) of Section 11 of the Act, and the last paragraph of the Order-in-Council, or, alternately, the security deposit may be deposited with any Conadian chartered Bank, whereupon the Bank must complete the enclosed Receipt and Agreement form in duplicate, with the original to be forwarded to the Minister of Finance of the Province of British Columbia, and the copy os to be retained by the Bank for its files, as per condition (6) of the form.

A photocopy of the permit, listing the Terms and Conditions under which it is being issued, is enclosed for your information.

Upon receipt by this Department of advice from the Department of Finance that the security deposit has been received, the Minister of Mines will sign the permit, which will then be forwarded to you.

Yours very truly,

J.D. McDonald, P.Eng., Senior Inspector of Mines - Reclamation.

JDM:sl

Enclosures.

# MEMORANDUM

TO The Hon. L. Nimsick,

Minister,

FROM THE

# DEPARTMENT OF MINES AND PETROLEUM RESOURCES

VICTORIA, B.C., ...

March 5

Dept. of Mines & Petroleum Res.

WHEN REPLYING PLEASE REFER

., 19.73

Re: Section 11, Mines Regulation Act. Cominco Ltd., H.B. Mine, Salmo, B.C.

The Advisory Committee on Reclamation, consisting of three representatives of the Department of Lands, Forests, and Water Resources, one from the Department of Recreation and Conservation, (the representative of the Department of Agriculture was unable to attend but submitted a covering memorandum), the Inspector of Mines - Reclamation, and with myself as Chairman, has studied the report submitted by Cominco Ltd., H.B. Mine, as appended hereto. The Committee has approved the report, with the additions and amendments as listed below.

A notice of the filing of the Cominco Ltd. H.B. Mine reclamation report as required by subsection 4 of Section 11 of the Act was published, for one insertion only, in the B.C. Gazette on Thursday, February 8, 1973, and in the Nelson Daily News and the Trail Times on Thursday, February 8, 1973.

The report is submitted for your approval, under subsection 5 of Section 11 of the Act, with the following additions and amendments:

1. That topsoil and overburden soil stripped from the surface shall be conserved, as feasible, for possible useage in the reclamation of disturbed areas.

2. That investigations and research be carried out covering:(a) the location, stability, and erosion control of waste dumps, tailing ponds, and stockpiles;(b) the protection of watercourses, as applicable;

(c) the reclamation of disturbed areas;

Marona Aturn

all to the satisfaction of the Chief Inspector of Mines.

3. That upon completion of the programme in (2) above, a plan and report describing in detail the reclamation and protection of the disturbed areas be submitted to the Chief Inspector of Mines for approval.

4. That the permit be valid for a period of five (5) years, or until approval of the report in (3) above, whichever is the sooner: the permit to be renewable upon application and upon evidence of satisfactory performance.

5. The total acreage to be disturbed during the planned life of the operation is 76.4 acres. Cost of reclamation is estimated at \$100 per acre. A bond in the amount of \$10,000 is recommended.

J.W. Peck, P.Eng., Chief Inspector of Mines.

Page 813 EGM-2013-00163

JWP:s1 encl.

õ

COMINCO LTD.

H.B. MINE - SALMO, B.C.

Application for Permit Authorizing Surface Work

#### I. INTRODUCTION

The H.B. Mine and concentrator is situated about seven miles south-east of the village of Salmo, B.C. on the North side of the Sheep Creek valley.

The property which was originally staked by Horton and Benson (hence H.B.) about 1907 was purchased by Cominco Ltd. in 1927. Intermittent work was carried out until 1946. Later, an extensive diamond drilling program was undertaken followed by underground exploration.

With sufficient ore outlined, construction of a 1000 ton/day concentrator was started in April of 1952 and completed in the spring of 1953. Due to unfavourable metal prices, operation did not commence until May, 1955 and was suspended in 1966. The mine is scheduled to resume production in early 1973.

The current head office address of Cominco Ltd. is 1199 West Pender Street, Vancouver 1, B.C.

#### II. PRODUCTION PROGRAM

#### General

It is planned to treat up to 1200 tons of ore per day from an underground source, thereby producing separate lead and zinc concentrates which will be shipped to Cominco-owned smelters in Trail.

With current ore reserves it is expected that the mine will operate for 3 1/2 years.

## Nature of Mining and Milling Operations

(a) Geology

The main mineralization at the H.B. Mine consists of several zinc-lead sulphide ore bodies localized in the Reeves limestone member of the lower Hiab group of lower Cambrian age. The Reeves limestone has been thickened by folding to several times its original thickness. It has increased from an original thickness of 40' - 70' to a maximum of 700'. This bulge in the limestone member plunges 20° south and the ore bodies maintain their relative position in the lime band with a similar plunge. The main ore body, the No. 1 zone, is steeply dipping and varies from a depth of 400' in the northern section near 3500 level to about 10' at its southern tip where it reaches to within 200 ft. of the surface. Several other ore zones lie just to the west and below the crest of the No. 1 ore zone. The Garnet zone ore body, however, lies approximately 600' to the west of the main ore body and extends to the surface.

The chief economic constituents of the one body are lead and zinc occurring as marmatite and galena in a gangue of calc, tremolite, limestone and dolomite. There are also considerable iron sulphides in the form of pyrite and pyrrhotite.

(b) Mining

The ore bodies will be mined from underground by both longhole and open stoping methods with a minimum of pillars remaining. No disturbance of the surface area is expected except for the Garnet Zone which will be extracted through to the surface. The final dimensions of the breakthrough will be about 1000' long by 70' wide by a maximum of 200' deep.

Access to the mine is through two main openings. The portal of the main entrance, the 2800 level haulageway, is situated about 300' above Sheep Creek and provides access from the main surface buildings. Most of the personnel and supplies are carried underground on this level and all the ore and waste is trammed out.

The 3500 level portal is located about 200' above Aspen Creek and provides access to the upper reaches of the No. 1 zone and to the hoist-room for the service shaft. Some material and a few personnel enter the mine through this opening. A third access of lesser importance, the 3300 portal, is located about the 2800 level portal and on the same slope.

Underground, the only ore tramming that is done is on the 2800 level. This is done by a Ruston-Hornsby diesel locomotive pulling eleven 6-ton cars from various areas and dumping at the coarse ore bin located on surface about 340' east of the portal. All other ore and waste movement underground is effected by 20 to 60 H.P. air or electric slushers and by gravity through a system of ore passes down to the 2800 level.

The waste produced underground is generally a limestone or dolomite with sizes ranging from 1/2 inch to 24 inches. A portion of this waste is disposed of underground into accessible mined out stopes and the remainder is removed to surface via the 2800 level portal. On surface, a waste dump has been established east of the coarse ore bin, along the hillside and extending about 500 feet along the hill and 150 feet down the slope. The resulting talus slope rests at an angle of repose of about 40° and is about 200 ft. across, from the toe to the side of the hill.

There is also an established waste dump below the 3500 level portal that may be used in future to dispose of waste from planned development of an ore body north of the service shaft and extending above the 3500 level. The expected annual waste production is about 6000 tons.

## (c) Milling

Milling of the H.B. ore is straightforward with production of separate lead and zinc concentrates. Open-circuit primary and secondary crushing is followed by open-circuit rod milling and closed circuit ball milling. The talc and tremolite which are readily floatable are floated out first to avoid contamination of the lead concentrate. This is followed by lead rougher flotation and zinc rougher flotation. The final concentrates, about 100 tons/day, are thickened, filtered and then shipped to the smelters. The talc concentrate joins the zinc rougher tails and goes to waste.

The mill waste, about 1100 tons per day of solids, flows by gravity to a surge box, some 30 feet below the mill level, from where it crosses the Sheep Creek Valley through a "U-tube". The tailings drop 180 feet down the north arm of the "U-tube" to the creek level and go up the south arm some 120 feet where it discharges to a wooden flume. The "U-tube" is of 7" wood stave pipe and approximately 750 feet in length.

The wooden flume, of which 100% has been rebuilt, carries the tailings some 2 1/2 miles to the west to a settling pond. The tailings pond is a small depression about 1/2 mile wide by 3/4 mile long, ringed on three sides by steeply dipping hillsides and an earth fill dam on the fourth. Clear overflow is handled by a 30 inch culvert pipe through the dam with a vertical intake of 3 x 12 timber cribbing. The cribbing as well as the earth fill dam is raised as required. The clear decant water is discharged from the culvert into a ditch and flows by gravity to the Salmon River. It is estimated that the tailings area will increase in area from about 60 acres to 69 acres in the 3 1/2 years of project operation.

#### (d) Disturbed Land Area

Land area disturbed by mining and milling activity is summarized.

2800 level waste dump	2.2 acres
3500 level waste dump	0.2 acres
Tailings disposal pond	60.0 acres
Buildings and Service area	10.0 acres
Roads	4.0 acres
	76.1

## III. NATURE AND PRESENT USE OF LAND

The Sheep Creek valley is bounded on the north and south by steep mountain slopes. Relief in the area of the mine extends from 2500 to over 5500 feet. Elevation of the tailings pond is 2200 feet.

The valley is situated in the Western larch subzone of the Interior Western Hemlock biogeoclimatic zone which is characterized by total annual precipitation in the range  $22-35^{n(1)}$ . Zonal soils include orthic ferro-humic podzol developed on shallow glacial deposits over bedrock.

Land on the south facing mountain slope surrounding the mine complex includes areas of productive and non-productive woodland<sup>(2)</sup>. Immature stands of trembling aspen, lodgepole pine and Douglas fir occupy medium quality productive sites<sup>(3)</sup>. Fire destroyed forest cover over part of the area in 1905 and in 1925. The tailings pond occupies a depression bounded on the west by unproductive land (rock) and by productive woodland in other directions<sup>(2)</sup>. Productive woodland has a cover of immature western larch with minor Douglas fir, lodgepole pine and white pine on medium quality sites<sup>(3)</sup>. Fire destroyed forest cover on part of the area in 1925.

Land surrounding the mine and tailings poud has been classified with respect to physical capability for use by agriculture, forestry, recreation, big game and waterfowl(2). Classification was based on data from surveys conducted under the Canada Land Inventory program. Fhysical capability of land at the H.B. Mine for each use group listed is summarized.

- 1. Agriculture
  - (a) Mine: land has severe limitations for agricultural use due to adverse topography, shallowness to bedrock and climate.
     80% of land possesses no capability for arable culture or permanent pasture. 20% is capable only of producing perennial forage crops. Improvement practices are not feasible.
  - (b) Tailings pond: land has severe limitations for agricultural use due to adverse topography, stoniness and climate. 40% of land possesses no capability for arable culture or permanent pasture. 60% is capable only of producing perennial forage crops. Improvement practices are considered feasible.

# 2. Forestry

- (a) Mine: land has moderate to severe limitations to growth of commercial forest. Growth limiting factors include restriction of rooting zone by bedrock and soil moisture deficiency. A small area has severe limitations which preclude growth of commercial forests.
- (b) Tailings pond: land has slight (60%) to moderate (40%) limitations to growth of commercial forest. Growth may be limited by restriction of rooting zone by bedrock and soil moisture deficiency.

### 3. Recreation

(a) Mine and tailings pond: land lacks natural capability and significant features to rate higher than low capability for cutdoor recreation, but has natural capability to engender and sustain low annual use based on dispersed activities such as hiking, nature study or for aesthetic appreciation. Land possesses continuous streams in upland areas and vegetation possessing recreational value.

### 4. Ungulates

(a) Mine and tailings pond: land classed as winter range of moderately high capability for deer and moose. Productivity may be reduced in some years due to excessive snow depth that reduces mobility of ungulates and availability of food plants.

#### 5. Waterfowl

 (a) Mine and tailings pond: capability for production of waterfowl is negligible or nonexistent due to adverse topography.

# IV. RECLAMATION PROGRAM

Land disturbance at the H.B. Mine will be kept to a minimum by utilizing existing waste rock and tailings disposal areas. Upon completion of mining operations, disturbed areas will be reclaimed to an appearance and use compatible with surrounding areas.

Currently in British Columbia mined land reclamation practices are not well established nor are conditions limiting plant growth on mine and mill waste well defined. To provide basic information for preparation of a reclamation program for the H.B. Mine, a research program is proposed. The general research approach is summarized:

- 1. characterize the nature of mine and mill waste by field inspection, sampling and analysis of chemical and physical properties which influence growth,
- evaluate the suitability of mine and mill waste as a growth medium for plants using laboratory and growth chamber techniques.
  - 3. when areas of mine and mill waste become final, initiate field investigations to determine physical treatments, plant species, planting techniques, fertilizer requirements and soil amendments necessary to establish and maintain suitable plant cover on waste disposal areas.

## V. REFERENCES

(1) Krajina, V.J., 1969, Ecology of Forest Trees in British Columbia In Ecology of Western North America, Vol. 2, No. 1. Published by the Department of Botary, University of British Columbia.

 (2) Canada Land Inventory, Land capability analysis sector maps of Salmo area for agriculture, forestry, recreaction, ungulates, waterfowl and present land use.
 B.C. Map Librarian, B.C. Dept. of Agriculture, Victoria.

and Canada Land Inventory: Objectives, Scope and Organization: Report No. 1, 1970. Dept. of Regional Economic Expansion, Queen's Frinter, Ottawa.

(s) Forest Cover Map:

ap: Salmo PSYU, 1962. Surveys Division, E.C. Forest Service, Victoria, B.C. Cominco Ltd./Trail, British Columbia, Canada/Telex 041-4426

AND	PETROLEUM F	RESOURCE
Rec'd	FFD 1 F 1	070
nec u	FEB 151	313
<b>A</b>		1
la-	M	
	mmco-	-L

FHP Dewdney Regional Counsel Tet. (604) 368-9941

LM McBride Solicitor Tel. (604) 358-3456

TD Tutti Solicitor Tel. (504) 368-8341 Department of Mines and Petroleum Resources #120 - 1006 Government St. Victoria, B. C.

Attention: Mr. W. B. Montgomery Inspector of Mines - Reclamation

re: H. B. Mine

February 13, 1973

Dear Sir:

We have complied with your instructions of January 25th last. Notice of the filing of the Report was published for one insertion only, in the B.C. Gazette on Thursday, February 8th, 1973 and in the Nelson Daily News and the Trail Times on Thursday, February 8, 1973. I enclose a copy of the Notice which was mailed to the three publications. The Trail and Nelson papers printed it correctly but the Gazette omitted the last two words, "British Columbia." Is the Gazette notice satisfactory?

Yours very truly,

ride

L. M. McBride Solicitor

#### MINES REGULATION ACT

# Notice pursuant to Section 11

TAKE NOTICE that L.J. Nicholson, Agent of Cominco Ltd. (H.B. Mine), has filed with the Minister of Mines and Petroleum Resources at Victoria a report made pursuant to Section 11 of the Act in respect to the surface operations of the mine located at Sheep Creek, near Salmo, British Columbia.

> Page 820 EGM-2013-00163

#120 - 1006 Government St., Victoria, British Columbia, January 25, 1973.

Mr. H.G. Barker, Superintendent, Cominco Ltd./H.B. Mine,

SALMO, BRITTSH COLIMBIA.

Dear Mr. Barker: Re: Section 11, Mines Regulation Act.

This will acknowledge receipt of the reclamation report, with enclosures, of date January 19, 1973, addressed to the Honourable Minister of Mines and Petroleum Resources.

Subsection (4) of Section 11 of the Mines Regulation Act requires that you publish notice of the filing of the report. The notice should be in the form as per the attached. It is to be published, for one insertion only, in the B.C. Gazette on Thursday, February 8, 1973, and in the Nelson Daily News and the Trail Times on Thursday, February 8, 1973.

Following publication of the notice as above, please confirm in writing that it has been published, listing the date on which the notice appeared in each publication.

Yours very truly,

and -

(Mrs.) Sylvia I. Little, Secretary.

for W.B. Montgomery, P.Eng., Inspector of Mines - Reclamation.

:51

encl.

F.S. The B.C. Gazette is published by the Queen's Frinter, Victoria. The fee for this notice is \$6.50 (tax exempt) per issue, payment to be remitted with the order (cheque or money order in favour of the Minister of Finance). Cominco Ltd./H. B. Mine, Salmo, British Columbia, Canada/Tel. (604) 357-2276



The Honourable L. Nimsick Minister of Mines and Petroleum Resources Parliament Buildings

January 19, 1973

Victoria, B.C.

Dear Mr. Nimsick:

Enclosed are seven copies of our report "Application for Permit Authorizing Surface Work" at the H.B. Mine near Salmo, B.C.

Yours truly,

. 10. -JG

H. G. Barker Superintendent

/mfl

Enc. (7)

cc: LJN RPD

Mines

Pages 823 through 825 redacted for the following reasons: Not Responsive