Knight Piésold Ltd.

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

RESPONSE TO REVIEW COMMENTS ON TAILINGS EMBANKMENT DESIGN (REF. NO. 1625/6)

TABLE OF CONTENTS

PAGE

SECTION 1.0	INTRODUCTION	1
SECTION 2.0	RESPONSES	2
SECTION 3.0	CLOSING COMMENTS	13

FIGURES

Figure 1	Tailings Gradation
Figure 2	Relationship Between Compaction Energy and Moisture Content
	- Density
Figure 3	Tension Crack Stability Analyses

DRAWINGS

1623.103 Rev 0	Tailings Storage Facility - Geological Cross-Sections				
1625.111 Rev 1	Tailings Storage Facility - Tailings Embankment - Sections and				
	Details				
1625.202 Rev 2	Tailings Storage Facility - Foundation Preparation and Basin				
	Liner - Sections and Details				
1625.205 Rev 2	Tailings Storage Facility - Stage Ib Tailings Impoundment -				
	General Arrangement				



Association des Ingénieurs-Conseils du Canada 1625/6

January 25, 1996 INVESTIGATION KP 1-11 1 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

1625.212 Rev 0	Tailings Storage Facility - Material Specifications
1625.220 Rev 2	Tailings Storage Facility - Instrumentation Plan
1625.221 Rev 1	Tailings Storage Facility - Instrumentation Sections and Details

APPENDICES

Appendix A

Test Pit Logs From 1995 Supplementary Investigations



Association des Ingénieurs-Conseils du Canada

1625/6

January 25, 1996 INVESTIGATION KP 1-11 2 of 500 Knight Piésold Ltd.

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

RESPONSE TO REVIEW COMMENTS ON TAILINGS EMBANKMENT DESIGN (REF. NO. 1625/6)

SECTION 1.0 - INTRODUCTION

We are pleased to provide the following responses to the comments made by Mr. C.O. Brawner with respect to his review of the Mt. Polley Tailings Embankment design. Several of the points raised by Mr. Brawner have previously been discussed with Mr. G. Headley of the Ministry of Energy Mines and Petroleum Resources (MEMPR) - Geotechnical Division and have already been included in the detailed design drawings and technical specifications which may not have been made available for Mr. Brawner's review.



1625/6

January 25, 1996 INVESTIGATION KP 1-11 3 of 500 Knight Piésold Ltd.

CONSULTING ENGINEERS

SECTION 2.0 - RESPONSES

Mr. Brawner's comments are presented in *italics* and are discussed in the order of his presentation.

General

The plan is to develop three pits. From environmental, volume storage and tailings dam height considerations it is recommended that Imperial Metals be requested to review in detail the potential to mine the pit sequentially and place tailings in them on completion of Pit 1 followed by Pit 2. The stability and environmental benefits are significant. There may also be a cost saving.

The Mt. Polley deposit is a complicated ore body which requires mining from all three pits at various times in order to optimize grade and recovery. The mine plan is being developed by Imperial Metals Mine Engineering staff who are considering various development and waste storage options including in-pit storage of waste and possibly tailings. Knight Piésold consider in-pit tailings disposal to be a viable concept, but this should only be evaluated later on in the mine life, once the open pit development schedule is well defined. Therefore, in-pit tailings disposal is considered to be a possible opportunity for future mine development. We feel it is conservative to ignore this possible option at the present time and continue to plan for secure surface disposal of all tailings solids.

Site Investigation

Only one drill hole appears to have been drilled in the main embankment area. In B.C. valleys there is always the possibility of buried high permeability zones. It is recommended that 2 more boreholes to expand the geotechnical information be drilled and tested.

One hole has been drilled in the Main Embankment area (MP89-234), as noted by Mr. Brawner. It has previously been discussed with Mr. Headley (MEMPR) and it was agreed that three additional holes will be drilled, logged and sampled by a geotechnical engineer during the initial stages of construction as part of the embankment instrumentation and monitoring requirements. The holes are specified in



Association des Ingénieurs-Conseils du Canada

Knight Piésold Ltd.

the Technical Specifications and shown on Drawing Nos. 510-77-01-1625.220 and 1625.221. They will be drilled to about 15m depth and will be located in the bottom of the main valley, where significant overburden is known to be present. Lab testing will be conducted on the samples as required and vibrating wire piezometers will be installed in the embankment foundation for long term water pressure monitoring.

Glaciofluvial Sediments in the Tailings Basin

It is noted that obtaining good compaction and density of the till liner over the sediments will be difficult due to poor underlying support of the sediments.

Has removal of the sediments been considered so the liner is not required?

We do not consider total removal of the sediments to be a viable option, as these materials are suspected to underlie the dense low permeability glacial till within the basin. The glacial till materials were deposited when a glacier extended over the area, and it was this glaciation which caused the heavily over consolidated nature of the underlying sediments. Therefore, the basin liner is merely an extension of this natural low permeability glacial till cover and is only required in those areas where the natural glacial till deposit has been removed by recent surface erosion which has locally exposed the glaciolacustrine sequence in the vicinity of the proposed embankment and further downstream.

In early October, 1995, a total of 34 additional test pits were excavated and logged at the Main Embankment area. In addition, 6 test pits were excavated and logged at the Seepage Collection Pond area. This information has previously been submitted to Mr. Headley (MEMPR, Geotechnical Branch) and is included in Appendix A. The investigations are summarized below :

- The test pits were typically 6 m deep.
- Test pit excavations started in the centre of the valley and progressed toward the left (east) abutment at 25 m centres. These test pits encountered 2 to 3 m of dense, moist to wet till overlying stiff to very stiff, overconsolidated silt



Knight Piésold Ltd.

and silty sand (glaciolacustrine sediments). No sections of loose wet sediments were identified.

• Test pits were then excavated progressively toward the right (west) abutment at a 25 m spacing. Similar stratigraphy was encountered for approx. 125 m. At TPME-15 loose wet sand was encountered below the till. This material extended on the embankment centreline for approx. 125 m, to TPME-20. Over this area, the till cap varied from 1.7 m to 3 m thick, with loose glaciofluvial sediments underlying the till. At the upstream toe of the embankment this zone was approx. 100 m wide. It was approximately 130 m wide at the Stage Ib and Final downstream toe locations.

• The test pits excavated at the Seepage Collection Pond area were required to define the limits of the fine till and glaciolacustrine sediments in which the pond could easily be excavated. It was found that only the southwest corner was underlain by loose sediments. The rest of the pond has stiff silt and silty sand (glaciolacustrine sediments) below a till cap. Both of these materials are suitable for excavation of the pond. The pond will be relocated to avoid construction in any area with loose sediments.

Mr. Brawner has indicated that placement and compaction of the till basin liner will be difficult because of poor underlying support of the sediments and he has suggested that consideration should be given to removing the sediments. However, the test pit excavations have shown that the underlying highly overconsolidated sediments have sufficient strength characteristics to allow placement and compaction of the liner provided that all loose, wet topsoil and glacial till at the topsoil/till contact (a maximum of about 30 cm) is removed prior to fill placement. We feel that it will not be difficult to obtain good compaction and density of the basin liner and do not consider that total removal of the sediments will be necessary. In fact, the additional site investigations have indicated that the extent of the basin liner can be reduced in area due to the excellent low permeability foundation materials encountered throughout most of the tailings basin.



1625/6

January 25, 1996 INVESTIGATION KP 1-11 6 of 500

If the liner is placed it is suggested that a seepage cut-off be excavated and backfilled through the sediments near the upstream toe of the main embankment.

The nature and distribution of the geologic units, as described above and as shown on Drawing No. 1623.103, illustrate that it would be extremely difficult to construct a seepage cut-off at the upstream toe of the Main Embankment. In order for the cut-off wall to be effective, it must be extended to low permeability materials both vertically and laterally or else the seepage losses will merely be redirected to a different direction. Therefore, the seepage cut-off would have to be extended completely along the West Embankment. The seepage cut-off wall would be extremely difficult to construct and it is unlikely that it would provide any additional benefit and could actually result in a less efficient seepage control measures than the currently designed system.

Excavate all weak soil to at least 10 m upstream of the upstream toe of the main dam.

Any weak soils which could adversely affect construction activities, embankment stability or could compromise the efficiency of the seepage control measures will be removed and/or treated as specified in the Technical Specifications and as required by the Knight Piésold supervising engineers.

Underdrains

The design of all drain pipe must have sufficient strength to resist full earth load.

All drain lines that exit the dams must be designed so they can be cleaned for distances of about 100 m.

All culverts and drain lines must be designed or protected from icing up in the winter.

The design of the embankment drainage pipeworks is illustrated on Drawing No. 510-14-03-1625.202. The drainage pipeworks consist of CPE embankment foundation drains and DR17 HDPE pipework for the toe drains which pass through the



1625/6 January 25, 1996 INVESTIGATION KP 1-11 7 of 500

Knight Piésold Ltd.

abutments at the Main Embankment. The perforated CPE foundation drains are not required to resist full earth loads as the drains include a gravel surround which provides contingency flow capacity. The HDPE toe drains pass below the core zone and have been designed to withstand full earth loads from the ultimate embankment. The HDPE drains could be cleaned out as recommended by Mr Brawner, and additional toe drains can also be installed during future embankment raises, if necessary.

A series of perforated CPE drain pipes surrounded by gravel and filter fabric were previously included for control of groundwater during construction of the partial basin liner and for long term monitoring. However, the additional site investigation test pits described above and in Appendix A, indicate that the extent of the constructed basin liner will be reduced and the comprehensive drainage network will not be required. Therefore, the basin groundwater drains have been removed from the current Detailed Design Drawings.

All embankment drainage pipes will be covered by a minimum of 1 m of soil to prevent freezing. Buried pipeworks downstream of the embankment also include a cover berm, both for protection from icing and for easy identification and location of the pipes. The outlet pipeworks discharge to a covered drainage sump prior to discharge below the water (or ice) surface of the seepage collection pond.

Sediment control pipeworks, culverts and flow control structures associated with other components of the tailings storage facility also include standard provisions for cold weather operations.

Seepage Collection Pond

In the event that Imperial Metals may find more ore and tailings volume increases, the dam should only be increased in height by the downstream method. To allow for this the seepage collection pond should be located so such change will not encroach on the pond.

The design currently incorporates a buffer zone of approximately 35 m immediately downstream of the toe of the final embankment limits. The storage capacity of the



Association des Ingénieurs-Conseils du Canada 1625/6 January 25, 1996 INVESTIGATION KP 1-11 8 of 500

Knight Piésold Ltd.

tailings impoundment could be easily expanded to accommodate over 30 million additional tonnes of tailings by raising the final embankment crest by about 17 m using the centreline construction method. Furthermore, it would be a relatively simple exercise to relocate the seepage collection pond further downstream to provide additional space for further extension of the downstream toe of the embankment should this be necessary in the future.

Filter Design

Filter gradation is required to be shown. The design must be conservative.

Filter gradations for construction materials are shown on Drawing No. 510-14-03-1625.212, which is taken from part of the Technical Specifications. The gradation of the tailings is shown on Figure 1 (from Tailings Storage Facility Design Report, Ref. No. 1625/1, May 26, 1995).

The filter materials are considered to be 'non-critical' as defined by Sherard et al (Sherard, J.L., Dunnigan, L.P. and Talbot, J.R., 1984. "Filters For Silts and Clays", ASCE Journal of Geotechnical Engineering, Vol. 110, No. GT6), as they are situated upstream of the core zone. However, the specified filter gradations have been conservatively designed to meet the more rigorous criteria for 'critical' filters. Therefore, the specified filter gradations meet or exceed conventional filter requirements for both the glacial till core zone and for the tailings solids.

Index tests on the bulk tailings sample shown on Figure 1 indicate that the material is non-plastic and fine grained, with 6 percent clay, 64 percent silt and 30 percent fine sand. The operations of the tailings spigotting system will lead to some separation of the tailings adjacent to the embankment, whereby coarser materials will settle out rapidly and finer materials will be transported further out into the pond. The result is that additional filter relationships will be developed between the fine and coarse tailings as well as between the coarser tailings and embankment fill materials. In the event that cracks develop on the embankment from the upstream side, it is anticipated that the tailings will also function as a crack stopping filter medium.



Association ng des Ingénieurs-Conseils du Canada 1625/6 January 25, 1996 INVESTIGATION KP 1-11 9 of 500

Knight Piésold Ltd.

Random Fill

Provide the range of acceptable gradation.

Gradation envelopes for embankment fill materials are also included on Drawing No. 510-14-03-1625.212.

Compaction

Substantial direction is made to the use of vibrating compactors. This method usually develops a moisture profile in the lift and brings fines to the surface. Whenever vibrating compactors are used the surface must be scarified prior to placing the next lift.

Where soils to be compacted contain a moderate clay fraction it is better to use a heavy grid or club foot compactor. The grid roller is the most versatile, being suitable to all soil and gradations and can be pulled at a faster speed than other types for equivalent density.

We disagree with Mr. Brawner's comments about vibrating compactors and we have specified in the Technical Specifications that a self-propelled 10 ton (minimum) vibratory wedge foot roller be used to compact the glacial till. This compactor is excellent for glacial till as it combines the kneading properties of a sheepsfoot (or club foot) roller with the high compactive energy provided by a vibratory roller. The wedge foot compactor leaves a rough, pitted surface which does not require scarification. Vibratory rollers can produce a "moisture profile" when operating on materials that are significantly wet of the optimum moisture content. However, it is intended that any materials which are so wet as to interfere with proper compaction will not be permitted. The specified wedge foot roller could be operated in the static mode (no vibration) if wet materials were approved for placement in the embankment fill zones. Moisture Content - Density relationships for compaction equipment are discussed further under *Compaction Tests* below.



Association des Ingénieurs-Conseils du Canada 1625/6

January 25, 1996 INVESTIGATION KP 1-11 10 of 500

Knight Piésold Ltd.

Groundwater Monitoring Wells

Provide the location of these wells. Several must be downstream. List test requirements.

Three permanent groundwater quality monitoring wells have been specified in the detailed design of the Tailings Storage Facility. The locations are shown on Drawing No. 510-12-02-1625.205. Additional monitoring wells will be installed as required during operations and as outlined in "Groundwater Monitoring Design Document" (Knight Piésold Ltd. Ref. No. 1625/5, May 19,1995).

All monitoring wells will be installed in accordance with the industry standards and regulatory requirements, including proper well development and regular sampling and testing. The installation and monitoring requirements are also described in detail in "Groundwater Monitoring Design Document" (Knight Piésold Ltd. Ref. No. 1625/5, May 19,1995).

Compaction Tests

Why is Modified Proctor density used as the reference? Standard Proctor density is more common. A higher moisture content can be tolerated with Standard Proctor criteria. Over-compaction results in a brittle dam structure with limited flexibility to deal with differential settlement.

Mr. Brawner's statements reflect a common misconception within the earthworks construction industry. As indicated on Figure 1, there are different moisture-density relationships depending on the level of compactive effort applied. The Standard Proctor energy is lower than for the Modified Proctor test and, for the given example, the machine compaction energy is still higher.

It is evident from Figure 2 that if one only considers the individual test results, the 'maximum' density decreases as the compaction effort is reduced, and the 'optimum' moisture content also increases as the compactive effort is reduced. However, the theoretical moisture content - density relationship for a soil is defined by the zero air voids line, but we generally find that the 2% air voids line is usually the control in practice. Consequently, if the Standard Proctor moisture density criteria are



Knight Piésold Ltd.

specified, a lower density fill with a higher permeability and greater compressibility can result. Also, if the contractor attempts to place the fill at the standard proctor optimum moisture content with the heavier compaction equipment, he will sometimes find that excessive rutting, weaving and pore pressure development (or moisture profiles) can occur in fine grained soils. Knight Piésold have therefore used the Modified Proctor test as the reference as it provides a moisture - density relationship which is closer to the relationship expected from the specified compaction equipment.

The glacial till has a fairly low plasticity (PI = 10 to 14) and will be placed at near the optimum moisture content as defined by the Modified Proctor test. Placement at a higher moisture content and a lower density as suggested by Mr. Brawner would result in larger post construction fill settlements and would increase the likelihood of cracks forming in the fill.

<u>Seepage Collection Pond Dam</u> Consider a low permeability cut-off under the dam.

The seepage collection pond will be constructed by excavation into low permeability glacial till and overconsolidated sediments and does not include a dam. The level of the pond will be maintained below the natural groundwater level and, therefore surrounding groundwater migrates toward the pond creating a hydraulic sink. This will prevent seepage losses downgradient. The Bootjack-Morehead connector road includes a small amount of fill for road subgrade immediately below the seepage collection pond, but is not intended to be a dam. A low permeability cut-off would not provide any additional benefit as discussed previously in "*Glaciofluvial Sediments in the Tailings Basin*".

Stockpile Stabilisation Materials for Urgent Use

Develop stockpiles of artificial membranes, filter cloth, short horizontal drains, filter materials, sand bags etc., for use if unexpected events occur such as:

- dam overflow control if massive precipitation or runoff occurs;
- piping or seepage control from the dam slope, toe or valley floor develops;
- tension cracks develop in the dam.



1625/6

January 25, 1996 INVESTIGATION KP 1-11 12 of 500

The design basis for the tailings impoundment includes provisions for storage of the total runoff from the Probable Maximum Precipitation event. Also, the tailings facility will be carefully designed, constructed and closely monitored during initial construction and over its lifetime. If any problems are identified during the course of construction or ongoing monitoring, appropriate remedial actions, contingency plans and materials stockpiles will be implemented.

Modified Centreline Design

The design proposed entails some of the compacted main dam to be constructed over loose to medium dense tailings. With this design variability in consolidation characteristics would be expected. This could lead to tension cracks near the top of the main dam and generally parallel to C.L. Stability analysis should allow for 10 m deep tension cracks filled with water.

Vibratory compaction of the beach should also be considered for the beach zone in the zone downstream of the S.O.L. to ensure low compressibility results.

The modified centreline construction method is illustrated on Drawing 1625.111. As in the centreline construction method, the embankment fill zones extend onto the tailings beaches during each staged expansion. The tailings beaches will be comprised of sandy materials with a very high coefficient of consolidation. The compressibility of these materials will also be low and any settlements which result from on-going expansion of the embankment occur relatively rapidly and are complete during the construction period. In fact, one of the design requirements for each of the staged expansions on to the tailings beaches is for monitoring with vibrating wire piezometers in order to identify the development and dissipation of any excess pore pressures during construction. It has been our experience that any excess pore pressures which develop in the tailings tend to dissipate relatively quickly and the technical specifications include provisions for monitoring to ensure that the pore pressures have dissipated (and consolidation is therefore completed) prior to placement of each successive lift. Vibratory compaction of the first lift typically results in the largest pore pressure response in saturated tailings, after which successive lifts show progressively lower response to loading. The compressibility of the tailings decreases in response to the densification which results from loading and



Association des Ingénieurs-Conseils du Canada 1625/6

January 25, 1996 INVESTIGATION KP 1-11 13 of 500

Knight Piésold Ltd.

compaction so that compression of the tailings during future staged expansions will not be significant.

Based on our experience with similar construction methods and comparable tailings materials, it is highly unlikely that 10 m deep tension cracks can develop along the crest of the embankment. However, as suggested by Mr. Brawner, stability analyses have been conducted for a 10 m deep tension crack filled with water, as shown on Figure 3. The factor of safety for the water filled tension crack is higher than for the previously reported stability analyses. Therefore, the previously reported minimum factors of safety for the tailings embankment are unchanged even if a 10 m water filled tension crack occurs.

An upstream slip surface for a 10 m water filled tension crack was also evaluated. The results showed that this case is also not critical as the factor of safety is well in excess of 1.5.

Winter Operation

Describe winter operation for disposal.

The supernatant pond is expected to freeze and an ice cover of up to about 500 mm may result. This is a common occurrence for tailings impoundments situated in cold climates, and tailings sedimentation and process water reclaim will continue virtually unaffected by the ice cover. The primary consideration for winter operations is related to tailings deposition by spigotting during extreme cold conditions. The tailings discharge pipeworks will be managed in order to prevent low flows from freezing and glaciating which would result in large volumes of ice becoming entrapped within the tailings mass. Based on our experience at other cold regions tailings disposal operations, we do not feel that winter operations will be particularly difficult at the Mt. Polley site and the only modifications to the summer operating procedures would likely be the operation of fewer spigots in order to concentrate the tailings flows and thus prevent glaciation of the tailings discharge streams.



1625/6 January 25, 1996 INVESTIGATION KP 1-11 14 of 500

Knight Piésold Ltd.

SECTION 3.0 - CLOSING COMMENTS

In order to ensure that the above listed concerns and all other design objectives are met, all construction activities will be monitored by Knight Piésold geotechnical engineers. As part of the construction supervision program, a detailed Quality Assurance/Quality Control (QA/QC) program will be implemented. The QA/QC program will include Control Tests required for approval of construction materials and Record Tests on placed and compacted materials.

The tailings storage facility has been designed for staged construction over the life of the mine. This allows the on-going performance of the facility to be continually evaluated. The design has flexibility and can be revised as required based on monitoring records, operating experience and updated mine planning.



Association des Ingénieurs-Conseils du Canada 1625/6 January 25, 1996 INVESTIGATION KP 1-11 15 of 500





CAD FILE: \PROJECT 1625\FIG\A10 Plot scole 1=1 IMPERIAL METALS CORPORATION MT. POLLEY PROJECT Jan. 23, 1996 KNIGHT PIESOLD LTD CONSULTING ENGINEERS STATIC STABILITY 10 m Tension crack filled with water -Potential slip surface (drained tailings strength) Factor of Safety = 1.5 Potential tension crack slip surface Factor of Safety = 1.59 Tailings INVESTIGATION KP 1-11 18 PT TOURE Potential slip surface (undrained tailings strength) Factor of Safety = 1.43 625.A10 S















Knight Piésold Ltd. CONSULTING ENGINEERS

APPENDIX A

TEST PIT LOGS FROM 1995 SUPPLEMENTARY INVESTIGATIONS



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 26 of 500



KNIGHT AND PIESOLD LTD. CONSULTING ENGINEERS	SYMBOLS AND	TERMS USED IN	N THE REPORT
CLAY	SILT SA	ND GRAVEL	ORGANIC SOIL من عند مند عند مند عند dominant soil
RELATIVE P	ROPORTIONS	CLASSIFICATION B	Y PARTICLE SIZE
TERM	RANGE	Boulder	Over 8"
Trace	0 - 10%	Gravel –	3 - 8
Some	10 - 20%	Coarse Fine	3/4" - 3" #4 - 3/4"
"y" or "ey"	20 - 35%	Sand – Coarse Medium	#4 - #10 #10 - #40
and	35 - 50%	Fine	#40 - #200 #200 #0.002 mi
ie. CLAY - silty, tr	ace sand	Clay	Finer than 0.002 m
means : Clay soil w and OX to	ith 20% :o 35% silt 10% sand	<u>NOTE</u> Sieve sizes shown are	U.S. standard
DENSITY OF SANDS	AND GRAVELS	•	
DESCRIPTIVE TERM	RELATIVE DENSIT	Y STANDARD	PENETRATION TEST
Very loose	0 - 15%	0 - 4	Blows per foot
Loose	15 - 35%	4 - 10	Blows per foot
Medium dense	35 - 65%	10 - 30	Blows per foot
Dense	. 65 - 85%	30 - 50	Blows per foot
Very dense	85 - 100%	Over 50	Blows per foot

DESCRIPTIVE TERM	STRE	NGTH	N VALUE STANDAR PENETRATION TES	T REMARKS
Very soft	× 25	< 0.25	Less than 2	- Can penelrale with fist
Soft	25 - 50	0.25 - 0.5	.2 - 4	- Can indent with fist
Firm	50 - 100	0.5 - 1.0	4 - 8	- Can penetrate with thumb
SIIIT	100 - 200	10 - 20	8 - 15	- Can indent with thumb
Very stiff	200 - 400	2.0 - 4.0	15 - 30	- Can indent with thumb-nail
Hard	> 400	> 4.0	Greater Ihan 30	- Cannot indent with thumb-na

NOTES

I. Relative density determined by standard laboratory tests

2. N Value - blows/fl. of a 140/b. hammer falling 30 in. on a 2 in. O.D. split spoon

3. Unconfined compressive strength = 2 × Undrained shear strength, INVESTIGATION KP 1-11 28 of 500





KNIGHT PIESO	DLD LTD. GINEERS		TEST PIT LOC	TEST PIT No. TP95ME-4 SHEET / of /
PROJECT ME LOCATION OF TH DATE Oct. 3 /95	Polley EST PIT_A	Main Em	bankment &	PROJECT NO. <u>1625</u> GROUND EL. LOGGED BY <u>KOE</u>
NOTES Groundwater level difficulty in digging, equipment used, etc.	DEPTH (m)	GRAPHIC LOG	DESCRIPTION	AND CLASSIFICATION MATERIAL
Komatsu PCZOOLC Excavator Minorseep.		¥+ + + 0 + 0 + + + + + + + + + + + + + +	Topsoil - Disturbed Wet SILT and fi Glacial Till - Greyi SAND with some Moist to wet. M dense to 2.0m Of till unit Glacio lacustrine / fluv Greyish green brow and SILT. Silt is s Sand layers step	dark brown to black, ne SAND with ORGANICS. Sh green brown SILTY GRAVEL and COBBLES. Nedium dense to 1.25m, . Slight seep at bottom interbedded fire SAND tiff, overconsolidated. slightly, otherwise
Minor seep in Sand layers. Vertical trench Walls stable.	3 - 4 - - 5 - - - - - -		Moist. Glaciolacustine /fluvial Interbedded fin as above. Color and unit is sti clearly overcon. TD = 6.0m	sediments - r SAND and SILT, is greyish blue ffer, SILT layers solidated, Moist.
	7			
Photos 1-4,1-5	-		I	NVESTIGATION KP 1-11 32 of 500

-

KNIGHT PIESO	DLD LTD. GINEERS		TEST PIT LOC	>	TEST PIT NO. TP95ME-5 SHEET 1 of 1
PROJECT <u>Mt. Polley</u> LOCATION OF TEST PIT <u>Ma</u> DATE Oct 3 195			bankment ¢	PROJECT NO. 1625 GROUND EL. LOGGED BY KOE	
NOTES Groundwater level difficulty in digging, equipment used, etc.	DEPTH	GRAPHIC LOG	DESCRIPTION	AND CLASSIFICATI MATERIAL	ON
Komatsu PCZOOLC Excauator Minoi seep flom suifair runoff at top of till. Minoi seepin	부 - - - - - - - - - - - - - - - - - - -	+¥ + + + + + + + + + + + + + + + + + +	Topsoil - Disturbed, Wet, SILT and fin Glacial Till - Greenis, SAND with trace COBBLES, Moist at top (to 1.2m) to 1.8m. Slight S Glacio lacustrine / fil Greenish grey bro and fine SAND. Stiff. Silt is hard	dork brown esand with hgiey brown tosome bi towet. Mea idense toy eep at top wial Sedim won interbea Moist, stifi d, overconso	to black, OCGANICS n SILTY RAVEL and dium dense of Till. ents - lard SILT fo very lidated!
Vertical tiench Walls stable,	g 4		Glacio lacustrine / Fi Thterbedded SIL abour, Color is is very stiff top Overconsolidated. seep in Sand la	uvial Sedi Tand fine S greyish bl hard, silt Occasional yers	ments - SAND, as ue. Unit clearly minor
	7	<u>++++++</u>	10 - 6.3M		
Photos 1-6,1-7.	-		IN	VESTIGATION KP 1-11	33 of 500

-

Г

F

T

1

KNIGHT PIESO CONSULTING EN	DLD LTD.		TEST PIT LOC	3	TEST PIT NO. TP95ME-E SHEET 1 of
PROJECT <u>Mt</u> , LOCATION OF TH DATE <u>Oct</u> 3/95	Polley EST PIT	Main Ł	mbankment E	PROJECT NO GROUND EL LOGGED BY). 1625
NOTES Groundwater level difficulty in digging, equipment used, etc.	DEPTH	GRAPHIC LOG	DESCRIPTION	AND CLASSIFICATIO	N
Komutsu PC200LC Excavator Minorintion ofwater and Sand, "ranning Sand."	₽ 2- 3-	1 1 1 1 1 1 1 1 1 1 1 1 1 1	Topsoil- Disturbed Wet SILT and f Glacial Till-Greeni SAND with trace cobbles. moist dense to dense loose at topof Glaciofluvial Sedime brown, Very stiff Glaciofluvial Sedime medium grained S	dark biow ine SANDwith sh giey brow to some Gr to wet w (gt Z. om). till. ats - SILTY s overconsoli ents - Brown AND. Wet to ("Cunning	n to blac ORTANICS n SILTY AVEL and Medium Medium Medium
Vertical trench Walls stable.	4		Glaciof Luvial Sedin SILT and fine SA stiff to hard, o Occasional SAN Trace gravel at TD=6.0m	nents - Blu ND . Moist , over consolia DV layer.	ish grey very lated.
	7				
Photos 1-8,1-9,1-10.			I	NVESTIGATION KP 1-11	34 of 500

.



KNIGHT PIESO	KNIGHT PIESOLD LTD. TES			TEST PIT No. TP95ME-8 SHEET 1 of 1
PROJECT ME LOCATION OF TE DATE Oct. 3/95	Polley EST PIT_	bantment &	PROJECT NO. 1625 GROUND EL. LOGGED BY KDE	
NOTES Groundwater level difficulty in digging, equipment used, etc.	DEPTH (m)	GRAPHIC LOG	DESCRIPTION	AND CLASSIFICATION MATERIAL
Komatsu PCZOOLC Excavator	- - - 2-	4 0 + 0 + 0 + 0 + 0 + 0 + 0 + 0 + 0 + 0	Topsoil- Disturbed SILTand Fine SAND Glacial Till - Gre SILTY SAND with GRAVEL und COBB loose to 1.2m; d 2.5m. Till is c	dark brown to black, wet with OKEANICS: enish grey brown th trace to some LES. Moist, medium rense buery dense to overconso lidated.
Slight Seep.			Glacio fluvial Sed SILTY fine SANI Stiff tohard, overco Glacio lacustrine /	fuvial Sediments -
Vertical tiench walls stable:	4 - - - 5 -		Greyish brown v SILT with occas fine SAND, trace clay are over con	ery stiff to hard sional layer of SILTY e CLAY. Sill and hsolidated.
-	6			
Photo 1-11, 1-12			IN	VESTIGATION KP 1-11 36 of 500

Π

10




KNIGHT PIESO CONSULTING EN	OLD LTD.		TEST PIT LOC	3	TEST PIT No. TPASME - 11 SHEET 1 of 1
PROJECT Mt. LOCATION OF TH DATE Od.4 195	. Polley EST PIT_1 5	Main En	mbankment Q	PROJECT NO GROUND EL LOGGED BY	1625 KOE
NOTES Groundwater level difficulty in digging, equipment used, etc.	DEPTH (<i>m</i> \	GRAPHIC LOG	DESCRIPTION	AND CLASSIFICATIO MATERIAL	DN
Komatsy PCZOOLC Excavator Slightseepat topard bottom of dense till.	₽ 1- 2-	12 + 0 + 0 + 0	Topsoil-Disturbed dan and fine SAND W Glacial Till-Green With trace to some Moist to wet, med Glacial Till-As a appearance · Blue horizons · Dense t Over consolidated.	brown moist th ith ORGANIC ish giey brown GRAUEL and ium loose. bowe, with n c mottles are overy dens Slight seep	blue mottles SANDY at topard
Vertical trench Walls stable.	보 3 - - - - - - - - - - - - - - - - - -		bottom of unit. Glaciolacustrine/f Greyish blue SILT stiff to very sti Occasional wet san Glaciolacustrine/f Brownish green inte SAND. Silt layers Overconsolidated S brown color. Layer Moist (driver than a stiff. TD=6.2M	Cuvial Sedin , SILTY SAN ff. Overconse and seam to Fluvial Sea erlayered S are muddy b Sondy layers is typically apper unit	nents - ID - Moist, Nidated. ID cm . Iments - ILT and fine Iwn color, are green to 5mm .), Very
	7 -			-An	
Photo 1-20.			IN	VESTIGATION KP 1-11	39 of 500

[

Γ

KNIGHT PIESO CONSULTING EN	DLD LTD. GINEERS		TEST PIT LOC	3	TEST PIT NO. TPASME -12 SHEET 1 of 1
PROJECT <u>MH</u> . LOCATION OF TH DATE <u>Oct 4 /95</u>	Polley EST PIT	Main E	mbankment Q	PROJECT NO GROUND EL LOGGED BY). 1625 KPE
NOTES Groundwater level difficulty in digging, equipment used, etc.	DEPTH (m)	GRAPHIC LOG	DESCRIPTION OF	AND CLASSIFICATION	NC
Komatsy PC200LC Excavator.		+ + + + + + + + + + + + + + + + + + + +	Topsoil - Disturb roots for nea Topsoil not 1.6	ed topsoi rby burn m Thick o	l and pile riginally.
Slightseepat	Z. 3. 2.	0++++++++++++++++++++++++++++++++++++++	Glacial Till - Gr SILTY SAND I GRAVEL and Col to approx. 2.5 m 4.1m. Slight till unit.	with trace BBLES · Ma and very c seep at b	y brown to som oist, dens dense to sottom of
Vertical trench Walls stable.	5	+++++++++++++++++++++++++++++++++++++++	Glacio lacustine / Greyish blue + and SILTY Sr muddy SILT la thick; SILTY SAI Moist, Very stif	fluvial Se ogreen bri tND. Fine agers typic ND lagers a t to hard	diments - own SIL , brown rally 2cm 2 to 3 mm. Duer -
-	7-	<u>+.t.t.t</u>	consolidated TD = 6.3m		
Photo 1-21					

KNIGHT PIESO CONSULTING ENG	LD LTD. INEERS		TEST PIT LOC		TEST PIT NO. P.95ME-13 SHEET 1 of 1
PROJECT Mt. Polley LOCATION OF TEST PIT Main Embantment C DATE Oct. 4/95				PROJECT NO. GROUND EL. LOGGED BY	1625 KDE
NOTES Groundwater level difficulty in digging, equipment used, etc.	DEPTH (<i>m</i>)	GRAPHIC LOG	DESCRIPTION OF	AND CLASSIFICATION MATERIAL	
Komatsu PC200LC Excavator	l 2 3	X++ + 0 + 0 + 0 + + 0 + 0 + 0 + 0 + 0 +	Topsoil- Disturbed SILT and fines AN Glacial Till- Gr SILTY SAND W GRAVEL and C Very dense, ou	dark brown, i D with OKOMNI ernish grey ith trace to OBBLES . W Derronsolida	brown some hoist, ated.
No seeps evident. Ventical trenda walls stuble.	4 - 4 - 5 - 6 -		Glaciolacustrine /f Grey brown, moist SILT. Medium stir Asabove, but grey tohard. Moist, ou Asabove, Sedime pronounced interla SAN BY SILT. Very Over consolidated TD = 6.4 m	luvial Sedim SILT and S ff lostiff over blue color, ver er consolidate ents with mi ayering of SI stiff to har	ANDY icorsolidate y stiff d. Drc LTand a, moist,
	7-				
Pnoto 1-22,	-		Л	IVESTIGATION KP 1-11 41	of 500

KNIGHT PIESC CONSULTING END	DLD LTD. GINEERS	_	TEST PIT LOC	3	TEST PIT NO. TPOSME-14 SHEET 1 of 1
PROJECT <u>Mt . 1</u> LOCATION OF TE DATE <u>Od .4 (95</u>	est pit_	Main E	Embantment & PROJECT NO. GROUND EL. LOGGED BY). 1625 KDE
NOTES Groundwater level difficulty in digging, equipment used, etc.	DEPTH (m)	GRAPHIC LOG	DESCRIPTION OF	AND CLASSIFICATIO	N
Komatsy PC200LC Excavator, Slightseepat bottom of till.	<u>v</u> 2- 3-	++++++++++++++++++++++++++++++++++++++	Topsoil- Disturbed d SILT and fines AN Glacial Till- Greeniss NiTh truck to some moist to wet, mere at bottom of th Glacial Till- As abo appearance. Blue Sandy horizons. Ouciconsolidate horizons are thi	ark brown, m D with ORGA Agrey Brown S BAAUEL and dium dense 11. yee, with br grey Mottle Very dens d. Mottlea n (to 2 mm	oist towet INICS. ILTY SAND IOBBLES. STOP IND MOHING TS Are INDISt, Sandy), Wet.
14	4	0 + 0 + 0 + 0 + 0 + 0 + 0 + 0 + 0 + 0 +	Glacial Till-Asal medium denst, m Glaciolacustrine If Light brown, moi SILT. Stiff to very Mottled appearance TD=6.Zm	nearboltom	grey rolor, nents - r sandy st hura).
	7-		*. *		
Photo 1-23			I	VVESTIGATION KP 1-11	42 of 500

.....

KNIGHT PIESC	OLD LTD. GINEERS		TEST PIT LOC	TEST PIT NO. TP95ME-15 SHEET L OF
PROJECT Mt. 1 LOCATION OF TE DATE Oct. 4 /45	Pollay EST PIT N	lain Embl	antment &	PROJECT NO. 1625 GROUND EL. LOGGED BY KDE
NOTES Groundwater level difficulty in digging, equipment used, etc.	DEPTH	GRAPHIC LOG	DESCRIPTION	AND CLASSIFICATION MATERIAL
Komatsu	-	LEXT	Topsoil- Disturbed da and fine SAND wit	The brown, moist to wet SILT
PC200LC Excavator	1 -	+0+0+	Glacia Till - Greenish gr trace to some GRAVE loose, mo ist to we	Land COBBLES, Medium
	2-	0+0+0+++	Glacial Till-Asabe motiled appearance SAND, to 2mm. Very	mottled horizons are wrt gdense, moist overall.
	¥ 3- 		Glacio fluvial /lacus Highly irregular, in light brown fine t SILT. Unit is moisl, silt is overconso top of unit.	trine Sediments - termixed layers of o medium SAND and stiff toverystiff. lidated . Seep at
Some "Aunning send"	5		Glaciofluvial /lacust As above, with mon SAND). Sand is loc making water and top of unit. TD	rine Sediments - re SAND (SILTY ose, some pockets are running Seep al- = 6.1m
1.0		1		
	7-		1	
	-			
	-			
Photo 1-24, 1-25.				NVESTIGATION KP 1-11 43 of 500





KNIGHT PIESO	DLD LTD.		TEST PIT LOC	3	TEST PIT No. TP95ME- SHEET / of
PROJECT <u>M1</u> . LOCATION OF TE DATE <u>Oct 4 195</u>	Poll+9 ST PIT_/	Main En	bonkment &	PROJECT NO GROUND EL. LOGGED BY	
NOTES Groundwater level difficulty in digging, equipment used, etc.	DEPTH (м)	GRAPHIC LOG	DESCRIPTION	AND CLASSIFICATIO MATERIAL	N
Komaky PC 200 LC Excavator Tillquite wet, loose.	1-	++++++++++++++++++++++++++++++++++++++	Topsoil - Disturbra, SILT and fint SAN Glacial Till- Greenis SAND with trace Moist to wet, med Glacidl Till- As a bo mothled appearance loose offirm.	ark brown, mi D with OKGANI GRAUEL and C GRAUEL AND C GRA	ist towet is DBBLES ish grey rel, mediu or till
Seepatbascot till. "Running Sand "	₽3 - - - -	+.++ ++ +++++	Glaciofluvial Sedi wel, fine lo medi occasional irregu Overconsolidated	ium SAND lar layer of SILT. SAN	t biown, wim shiff, un is ins, wik
Trench walls collapsing .	5 -		"running sand", collapsing	Trench side	·s
	6 -		1 D-6.0M		
Photo 2-7.			ΙΝ	IVESTIGATION KP 1-11 4	46 of 500

TEST PIT No. KNIGHT PIESOLD LTD. TEST PIT LOG TP45 ME-19 CONSULTING ENGINEERS SHEET / of / PROJECT Ml. Polley PROJECT NO. 1625 LOCATION OF TEST PIT Main Embonkment E GROUND EL. DATE Oct 4/95 LOGGED BY KDE NOTES Groundwater level GRAPHIC DESCRIPTION AND CLASSIFICATION DEPTH LOG difficulty in digging, OF MATERIAL equipment used, etc. (m) Topsoil - Dark brown, moist lower SILT and fine SAND with ORGANICS. 2454 Komatsy PCZOOLC F.O.1 Glacial Till - Greenish grey brown SILTY SAND WITH trace to some GRAVEL and COBBLES. Wel, medium dense lloose. Excavator 1:01 Slightly drier, medium dense at 2.2m V Glaciofluvial Sediments - Brown, finc Seeping to medium SAND with occasional Throughout 3 thin layer (to2.5 cm) of shiff, over-consolidated SILT. Wet, loose, seeping throughout unit. SAND. "Running SAND" t++++ 4 FTT. Trench 5 collapsed. blacio la custrine Sediments - Light hown, moist, stiff toverystiff (almost hara) +++++++ SILT. TO=5.4m 6 No photo INVESTIGATION KP 1-11 47 of 500

KNIGHT PIESO	OLD LTD. GINEERS		TEST PIT LOC	3	TEST PIT NO TPASME-ZO SHEET I OF
PROJECT Me. LOCATION OF TO DATE Oct. 4 193	Polley EST PIT	Muin Em	bankment E	PROJECT NO GROUND EL LOGGED BY)
NOTES Groundwater level difficulty in digging, equipment used, etc.	DEPTH	GRAPHIC LOG	DESCRIPTION	AND CLASSIFICATIO	ON
Komatsy PC200LC Excavator		1 + 0 + + 0 + + 0 + + 0 + + 0 + + + + 0 + + +	Topsoil- Durk Biown fine SAND wi Glacial Till- Greeni SAND with tract COBBLES Medium	the order to we the order to some Grit to some Grit dense, mo,	n SILTAN VEL and St -
Random Seeps in Sang	Q 2- Q 3-	0 + 1	Glacio f luvial Sedin glained loost WC also random ly W	it SAND Se Thin unit	n, mediu ep at botto
-Strong seep at base of granily unit-		+++++++ 00000 00000 00000 00000 00000 00000 0000	Moist very stiff 00 occasional SAN blaciof willial Sedime bravel and cobble base of unit 2-39	nts - Wet, bro scan s, Verydinse pm.	NN SAND , Seepat
-vers hard to disin red till	- 5 -	+0+0+0 +++0+0 0++-+	Glacial Till - Ked Dron SILTY SAND with son Over ronsoliated. E TD = 5.7m	wn, verydense me GRAVEL Busul HII?	, moist and COI3BL
	6 - - 7 - - -				
Pho los Z-8, Z-9.					

1



KNIGHT PIESO	LD LTD.		TEST PIT LOC	SHEET / of
PROJECT Mt. Polley LOCATION OF TEST PIT U/S Toe DATE Oct. 4/95 Main Embontment			bantment	PROJECT NO. 1625 GROUND EL. LOGGED BY KDE
NOTES Groundwater level difficulty in digging, equipment used, etc.	DEPTH	GRAPHIC LOG	DESCRIPTION OF	AND CLASSIFICATION MATERIAL
Komatsu PC ZOOLC Excavalor		H B + 0 + 0 + 0	Glacial Till- Green SAND with O Glacial Till- Green SAND with tra and COBBLES- Moist to wet	nishgiey brown SILT, nishgiey brown SILT, c+ lu Some GRAVEL Medium denses
beep in sund.	2-	HTTT	Glaciof Guuial / la Biown, fine to wet SAND wi layer (to 1 cm stiff, overconso	instrine Sediments medium, 1005e, th occusional thin) of light brown, lidated SILT.
Holt collapsed	4-		Water seeping i TD = 4.6M	r SANDUNIT.
•	6			
No photo.			INV	/ESTIGATION KP 1-11 50 of 500

TEST PIT NO. TP95ALE-23 KNIGHT PIESOLD LTD. TEST PIT LOG CONSULTING ENGINEERS SHEET / of PROJECT Mt. Polley PROJECT NO. 1625 Uls Toe GROUND EL. LOCATION OF TEST PIT DATE Oct. 4 195 Main Embonkment LOGGED BY KOE NOTES GRAPHIC Groundwater level DESCRIPTION AND CLASSIFICATION DEPTH difficulty in digging, LOG OF MATERIAL (m) equipment used, etc. Topsoil- Blown, moist to wet SILTand fine Komalsy 0:5 PC200LC + 00 Glacial Till- Greenish grey brown SILJY SAND with trace bosome GRAVELARD COBBLES. Excavator Mediumdense, moist towet. Slight Seep slight Seepat base of till. 2 Glacial Till - As above with bluishgren moltled horizons, Very dense, moist to wet (rsp. on mottling). 3 blue color, very dense, moist. Ā . Glaciofluvial (blaciolacustrine Sedimonts -Brown, medium grained wet SAND with occasional Thin, very stiff over consolidated SILT layer, Random 4 titt Vertical trench 5 Seepsin NetSAND. walls stable. Glaciolacustine Sediments - Lightbrown, 6 moist, very stiff SILT with occasional SAND lager TO= 6.3m Photo 2-10 INVESTIGATION KP 1-11 51 of 500







KNIGHT PIESC	OLD LTD.		TEST PIT LOG	3	TEST PIT No. TOGEME-2 SHEET / of /
PROJECT M. I LOCATION OF TE DATE Oct. 5/95	Polley ST PIT <u>D</u>	IS Tor lage 16 M	ain Embantment	PROJECT NO GROUND EL LOGGED BY	KDE
NOTES Groundwater level difficulty in digging, equipment used, etc.	DEPTH	GRAPHIC LOG	DESCRIPTION	AND CLASSIFICATIO	N
Komatsu PC200 LC EXcavator	1	$ \begin{array}{c} x \\ x \\ 0 \\ 0 \\ 0 \\ 0 \\ 0 \\ 0 \\ 0 \\ 0 \\$	Topsoil- Distuibed of SILT and fine SAN Glacial Till- Green greyish mothled with trow to Som Medium Dense, n Glacial Till- As a towet, medium	nish qity bi horizons. S corrizons. S corrizons. S corre, bui bore, bui noist.	noist towet and with and with all ty sand a COBBLES Moist loose.
Seepin gravelly unit "Running Sard" Not asmuch water as embankment centre line.		+ + Ο° °°	Glaciof luvial Sedi SAND with some dense to loose, se Glaciof luvial Sedime loose, wet brown in, causing SAN Sand collapsing.	iments - B. GRAVEL . M. Sepin ground onts - Mediu SAND. Wat D to rollaps	rown, wet ledium 'g sections m grained, ter seeping and 'sun'
Trench collapsing	6	<u>1++++</u>	moist, stiff intern SANDY SILT. TD = 6.0m	layeral SILT	and
Photos Z-16, Z-17, Z-18.			IN	VESTIGATION KP 1-11	55 of 500





TEST PIT No. KNIGHT PIESOLD LTD. TEST PIT LOG TP95ME-30 CONSULTING ENGINEERS SHEET | of PROJECT Mt. Polley PROJECT NO. 1625 LOCATION OF TEST PIT DIS TOP GROUND EL. Final Main Embaniament LOGGED BY KDE DATE NOTES Groundwater level GRAPHIC DESCRIPTION AND CLASSIFICATION DEPTH difficulty in digging. LOG OF MATERIAL equipment used, etc. (m) Topsoil- Dark brown, moist lowed siltand finesAND with OKGANICS. Lots of Roots -Komatsu PC200LC Glacial Till- Greenish grey brown SILTY SAND with trace to Some GRAVEL and Excauator COBBLES. Moisi, medium dense Glacial Till - Asabove, but moist, dense toverydense. Occasional SAND LENS. Glaciofluvial Sediments - Green brown SILTY SAND with trace GRAVEL, Wel, medium dense to loose. 1. 5 Glaciof Unvial Sediments - Brown, loose wet Trench staying SAND with Water see ping, minor "running open SAND" TO > 5.9m 6 7 5 Photo Z-ZI INVESTIGATION KP 1-11 58 of 500



TEST PIT No. TRASME-32 KNIGHT PIESOLD LTD. TEST PIT LOG CONSULTING ENGINEERS SHEET / of / PROJECT Mt. Polley PROJECT NO. 1625 DIS Toe LOCATION OF TEST PIT GROUND EL. DATE Oct 5/95 Final Main Embankment KDE LOGGED BY NOTES GRAPHIC Groundwater level DESCRIPTION AND CLASSIFICATION DEPTH difficulty in digging, LOG OF MATERIAL equipment used, etc. (m) 1+ + + +. Topsoil-Dork blown, moist to wet SILT Komatsu PC 0.+ and fine SAND with ORGANICS. 200LC Excavator Glacial Till- Greenish grey brown SILTY SAND with trave to some 2 SlightSeep in GRAVEL and COBBLES. Moist to wet, medium dense to dense (at bo Hom). Slight seep in fill appiox 1.5m (densen) 3 Glacial Till - AS above, blue grey COlor, SANDY, +00+ wet, medium dense. 0.0 Glacial Till - Greenish grey brown color , as above SILTY SAND with trace GRAVEL, over-consolidated. (may be sediments), ٥. 5 Moist to wet, dense. Slight seep. + . . . + Seep in sand. 2 6 24-22:4---Glaciola custrine sediments - Interlayered light brown fine SILTY SAND and muddy brown operconsolidated SILT. Moist, stiff. TO=6.2m. Photo 2-23 INVESTIGATION KP 1-11 60 of 500

TEST PIT No. TP95ME-33 KNIGHT PIESOLD LTD. TEST PIT LOG CONSULTING ENGINEERS SHEET / of / PROJECT MH . Polley PROJECT NO. 1625 LOCATION OF TEST PIT 1/5 Tor GROUND EL. DATE Oct 5/95 LOGGED BY KDE Final Main Embankment NOTES GRAPHIC DESCRIPTION AND CLASSIFICATION Groundwater level DEPTH difficulty in digging, LOG OF MATERIAL (m) equipment used, etc. 1 + + + + + : Topsoil-Distuibed dark brown Mois towet SILT and fine SAND with ORGANICS Komatsa Oto: PC200LC Glacial Till - Greenish grey DIOWA SILTY SAND with trace to Some GRAVEL and 0:4 Excavator R COBBLES. Moist, dense. Minor Seep. Minor seepat Glacial Till- As above. Moist, have of looser very danse. till. 0. 3 Glaciolacustrine I fluxial Sediments-Interlayered, biown, moist SILT and SILTY SAND. Very Stiff. † たたたた T.t. +.++ Glacio fluvial / lacustring Sediments sitt to Brown, wet, medium grained StNDwith trace SILT. Medium dense to loose. 5 Water held in Sand, not seeping or running. ナナテト blaciolacustrine Sediments - Light brown, Moist SILT and SILTYSAND, SHIFF / very stiff. TO = 6.3m Photo Z-Z4 INVESTIGATION KP 1-11 61 of 500

TEST PIT No. KNIGHT PIESOLD LTD. TEST PIT LOG T095ME-34 CONSULTING ENGINEERS SHEET (of / PROJECT M. Polley PROJECT NO. 1625 LOCATION OF TEST PIT DIS Tor GROUND EL. DATE Oct 5/95 Final Main Embonement LOGGED BY KDE NOTES GRAPHIC Groundwater level DESCRIPTION AND CLASSIFICATION DEPTH difficulty in digging, LOG OF MATERIAL (m) equipment used, etc. Topsoil- Disturbed brown / black, moistb wet SILT and fine SAND with ORGANICS た、また、 Komatsy 0.1 PC200LC Glacial Till- Greenish greybown SILTYSAND with trace to some GRAVEL and COBBLES . Moist to Excavator wet, medium dense to dense at bottom. 0: blacidl Till- Asabore, with bluishgrey moHledhorizons, which are sandy coatings. Moist to wet, very dense. Glacial Till- as above, bluish grey with Some COBBLES and GRAVEZ. Moist, very dense. tat Slight Seep P Glacioflucuial / lacustrine sediments-4 Brown, wet, nedium grained SANDWith ++++ trage SILT. Occasional Sill pocket-Medium loose. +++ 5 Slight Seep. 2 HATTH Glaciolacustrine Sediments - Light biown, moist SILT and SILTY SAND Stift to ++++ TO=6.2m very stiff 6 7 1ho102-25 INVESTIGATION KP 1-11 62 of 500

PROJECT Mt. LOCATION OF TI DATE Sept 21/45	Polley EST PIT	See puge (5.0, P	PROJECT NO. 1625 GROUND EL. LOGGED BY KDE
NOTES Groundwater level difficulty in digging, equipment used, etc.	DEPTH	GRAPHIC LOG	DESCRIPTION AND CLASSIFICATION OF MATERIAL
JD-690DLC Excavator	P	Vi + + + + + + + + + + + + + + + + + + +	Darkbrown, wet, loose SILT and fine SAND with ORGANICS. (TOPSOIL). Bluishgrey bobrown, moist towet, dense tou dense SILTY SAND with some GRAVEL, o COBBLE. Over-consolidated, (GLACIAL TIL
Occ. seep,>>lgpm,	D 2 3 4	+ + + + + + + + + + + + + + + + + + + +	Grey-green to green brown, moist, Vary stiff 51LT with trace fine SA Uniform, glaciofluvial /glaciolacustri sediments. Occasional seep. Over consolidated
2	5	-	
		-	
		-	

TPSZO KNIGHT PIESOLD LTD. TEST PIT LOG CONSULTING ENGINEERS SHEET / of / PROJECT Mt. Polley PROJECT NO. 1625 LOCATION OF TEST PIT Seepage Collection Poro GROUND EL. LOGGED BY KDE DATE Od. 5/95 15m west of SZO NOTES Groundwater level GRAPHIC DESCRIPTION AND CLASSIFICATION DEPTH difficulty in digging, LOG OF MATERIAL (m) equipment used, etc. Topsoil- Disturbed darkbiown, black moist KHA. Komatsy towefsilt and fine SAND with ORGANICS. PCZOOLC Glacial Till - Orepaish grey brown Excavator Z GRAVEL and COBBLES. Has bluish Slight Seep. grey mottled horizons which are Net. Overall, moist towet, medium dense to 1.5m and modium dense to dense at bottom. Slight seepon mo Hled surfaces Holp almost Glaciolacustring/fluvial Sectiments -BIOWN, moist to wet SAND and dry. SILTY SAND. Stiff to firm. 5 Vertical trench Glaciolacustrine [Fluvial Sediments walls stable. Asabore, but greyish brown color, moist, stiff. TD=6.4M Photo 3-1 INVESTIGATION KP 1-11 64 of 500

TPSZO,5 KNIGHT PIESOLD LTD. TEST PIT LOG CONSULTING ENGINEERS SHEET 1 of PROJECT Mf. Polley PROJECT NO. 1625 LOCATION OF TEST PIT Seepage Collection Pond GROUND EL. DATE Oct 5/95 B+faven 520 /521. LOGGED BY KDE NOTES Groundwater level GRAPHIC DESCRIPTION AND CLASSIFICATION DEPTH difficulty in digging, equipment used, etc. LOG OF MATERIAL (m) and fine SAND with ORGANICS. 21 Komatsy PCZOOLC Glacial Till- Greenish give blowr SILTY SAND with from busome GRAVEL and Excavator COBBLES Moist, dense Glaciolacustrine / Fluvial Sediments -Minor seep or sundy crack Interlayered light brown SILT and SILTY SAND. Moist tower (at intill sandyhorizons). 5 blacio lacustrine / Fluvial Sediments -As above, greyishcolor. Unfical french ++++ wallss table +++++ TD=6.5m Photo 3-2 INVESTIGATION KP 1-11 65 of 500

KNIGHT PIESC	DLD LTD. GINEERS		TEST PIT LOC	2	TEST PIT NO. TP-S21 SHEET 1 OF 1
PROJECT <u>Mt. P</u> LOCATION OF TE DATE <u>Sept 21</u>	2011-y EST PIT <u>50</u> 95 (s	ераце Ро 5.0. Р.	SZI)	PROJECT NO GROUND EL LOGGED BY). <u>1625</u> ΚDΕ
NOTES Groundwater level difficulty in digging, equipment used, etc.	DEPTH (m)	GRAPHIC LOG	DESCRIPTION	AND CLASSIFICATIO	DN
JD 690 D-LC excavator Waterseeping in sandy sediments.		++++++++++++++++++++++++++++++++++++++	Brown, loose, ver grained SAND with together). Unstan collapsing. Water	and dense 5 (TOPSOL) and dense 5 ome GRAVEL, DER (GLAC Wef Medicu h Trace SIL ble, sides c seeping in	T(Birds
Entire trench collapsed, No samples, no photos.	3		Brown, mediumdens SILT and flpe SAN Consolidated. (Glac sediments).	, mois t tow D, trare CLA io fluvial/blad	et layered Y. Over- iolocustrire
	-			NVESTIGATION KP 1-11	66 of 500

TEST PIT No. TPSZIZ KNIGHT PIESOLD LTD. TEST PIT LOG CONSULTING ENGINEERS SHEET 1 of 1 PROJECT Mt. Polley PROJECT NO. 1625 LOCATION OF TEST PIT Suppoy Collection fond GROUND EL. DATE Oct 5/95 LOGGED BY KDE East at SZI NOTES GRAPHIC Groundwater level DESCRIPTION AND CLASSIFICATION DEPTH difficulty in digging. LOG OF MATERIAL (m) equipment used, etc. Topsoil- Distuibed darkbiown SILTura fine Komatsu PC SAND with ORGANICS WET RUMPIST Glacial Till- Greenish grey brown SILTYSANDNin 200 LC truce to some GRAVEL and COBBLES, moist tower, Excavator medium dense. Okecio lacustino I fluvial sodiments - biown, moist to wet fine SAND and SILT, Firm lostiff. blaciolacustring / fluvial Sediments -Blue givy interlayered SAND (fine) and SILT. Occasional seam of muddy brown 3 stiff orerronsolidated SILT / CLAY . Moist to wet, firm to stiff. 4 5 Glaciolacustrine Sediments - Light brown, ifit: Virtical trench Interlayered SILT and fine SAND. Moist, 6 walls stable. stiff TD = 6.0m Photo 3-3 INVESTIGATION KP 1-11 67 of 500

KNIGHT PIESO	DLD LTD.		TEST PIT LOC	S TEST TP- SHEE	PIT No. 522 T 1 of 1
PROJECT <u>M</u> E. LOCATION OF TH DATE <u>Sept 21</u>	Polley Est Pit_5	сераде (5.0.Р.	Pord, SEconner 522)	PROJECT NO. 14 GROUND EL LOGGED BYK	DE
NOTES Groundwater level difficulty in digging, equipment used, etc.	DEPTH	GRAPHIC LOG	DESCRIPTION	AND CLASSIFICATION MATERIAL	
JD 690D-LC Excavator	¥ -	+ 10+ 010 + + + + + + + +	Darkbrown, wet, 1005 with ORGANICS Greenish-gity to dense SILT/SI to some GRAVEL	e SILT and Fine (TOPSOIL). brown, moist, LTY SAND with CGLACIAL TIL	sand medium trace L).
Occ∙smallseep in bluish layer ≫lgpm	⊻ 2-	++++ +++ ++++ +++++ +++++	Mottled green grey SILTY fine SAN Mottled appearan of randomly orig of fine SILT ana	vo brown SIL vo. Very stiff ce duc to the p inted grey-blu ICLAY with tra	T and moist presence e layer, ce
	又 3- - - - - -	++++ +++++ +++++	SAND and GRAU a small a mount of consolidated GLAC LACUSTRINE SED	EL. Layers Se Hwater. Dense IOFLUVIAL 16LI IMENTS-	- p , over- 4010-
2	又 - 5 -	++++	Greyish Blue, mo and CLAY with consolidated. Min above glaciofluvia. sediments.	ist, very stiff s mace SAND. Ove nor seep. Simi gluciolacustrine	ILT Iar to

1.4

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT CONTRACT NO.

TAILINGS STORAGE FACILITY AND ANCILLARY WORKS (REF. NO. 1625/3)

PART 10 - TECHNICAL SPECIFICATIONS

MARCH 25, 1996

INVESTIGATION KP 1-11 69 of 500

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT CONTRACT NO.

TAILINGS STORAGE FACILITY AND ANCILLARY WORKS

PART 10 - TECHNICAL SPECIFICATION (REF. NO. 1625/3)

TABLE OF CONTENTS

PAGE

SECTION 1	GENERAL TECHNICAL REQUIREMENTS		1-1
	1.1	Scope	1-1
	1.2	Clearing, Stripping, Grubbing and Topsoil	1-1
		Removal	
	1.3	Open Excavation	1-3
	1.4	Embankments and Berms	1-12
	1.5	Plain and Reinforced Concrete	1-26
	1.6	Pipework	1-34
	1.7	Metalwork	1-54
	1.8	Painting	1-57
	1.9	Geosynthetics	1-58
	1.10	Contractor's Construction Schedule	1-59
	1.11	Contractor's Plant	1-60
	1.12	Availability and Use of the Site	1-62
	1.13	Spoil Disposal Area and Stockpile Areas	1-65
	1.14	Dewatering and Drainage	1-66
	1.15	Borrow Areas	1-67
	1.16	Setting Out the Work	1-68
	1.17	Drawings Submitted by Contractor	1-70

	1.18	Standard Specifications	1-71		
	1.19	Daily Reports	1-71		
	1.20	Provisional Sums	1-72		
	1.21	Payment - General	1-72		
SECTION 2	MOBILIZATION AND DEMOBILIZATION		2-1		
	2.1	Scope of Work	2-1		
	2.2	Use of Site	2-1		
SECTION 3 - TAILINGS BASIN			3-1		
	3.1	Scope of Work	3-1		
	3.2	Stripping, Grubbing and Topsoil Removal	3-1		
	3.3	Basin Groundwater Drains	3-2		
	3.4	Basin Liner	3-3		
	3.5	Borrow Areas, Spoil Areas and Topsoil Stockpile	3-6		
	3.6	Reclaim Barge Channel	3-7		
SECTION 4	EMBA	ANKMENTS AND SEEPAGE COLLECTION	4-1		
	PONDS				
	4.1	Scope of Work	4-1		
	4.2	Stripping, Grubbing and Topsoil Removal	4-1		
	4.3	Foundation Preparation and Excavation	4-2		
	4.4	Foundation Drains and Conveyance Pipework	4-4		
	4.5	Materials of Construction	4-5		
	4.6	Fill Placement	4-7		
	4.7	Seepage Collection Ponds	4-10		
	4.8	Construction Tolerances	4-11		
SECTION 5	SITE	ROADS AND DIVERSION DITCHES	5-1		
	5.1	Scope of Work	5-1		
	5.2	Sediment Control	5-2		
	5.3	Stripping, Grubbing and Topsoil Removal/	5-2		
		Replacement			
	5.4	Bootiack-Morehead Connector Relocation	5-3		

	5.5	Area B Runoff Collection Ditch	5-4	
	5.6	Tailings and Reclaim Access Roads	5-5	
	5.7	Tailings Area Diversion Ditch	5-7	
SECTION 6	NOT	USED		
SECTION 7	INSTRUMENTATION AND MONITORING		7-1	
	FACILITIES			
	7.1	Scope of Work	7-1	
	7.2	Grout Existing Boreholes	7-1	
	7.3	Piezometers	7-2	
	7.4	Terminal Station and Readout Box	7-4	
	7.5	Monitoring Hut	7-4	
	7.6	Flow Monitoring	7-4	
	7.7	Survey Monuments	7-5	
TECHNICAL SPECIFICATIONS

SECTION 1 - GENERAL TECHNICAL REQUIREMENTS

1.1 Scope

The general technical requirements specified in this Section shall, except as specifically excluded in the sections following, apply to all activities and operations relating to carrying out the Work as shown on the Drawings or as required by the Company Representative and/or the Engineer.

The Work to be carried out under the Contract shall consist of supply of all labour, Plant and materials and performing all things necessary to construct the entire Work as defined in these Technical Specifications, on the Drawings or required by the Company Representative and/or the Engineer.

A listing of the advance notice periods required of the Contractor is given on Table I, Page 1-73.

1.2 Clearing, Stripping, Grubbing and Topsoil Removal

The Contractor shall clear, strip, grub and remove topsoil from all ground surfaces prior to excavation in any area, in areas which are not excavated but in which fill is to be placed, and over remaining areas of the tailings basin to the limits shown on the Drawings.

In order to reduce erosion and contamination of the surface runoff to a minimum at all times, clearing, stripping, grubbing and topsoil removal shall be scheduled to be performed only as and when required to enable each portion of the Work to be carried out.

1.2.a Clearing

Clearing the areas of the Site so designated on the Drawings or in the Technical Specifications shall consist of the felling of all trees, shrubs and vegetation to within eighteen inches of the ground.

Felling of timber and removal from site of all merchantable timber will be carried out by Others under the direction of the Company Representative.

As Work of this Contract, all non-merchantable timber and vegetation shall be disposed of by burning to reduce it to ashes or as otherwise approved by the Company Representative. Care shall be taken in burning debris to prevent the fire from spreading. Prior to starting any fires the Contractor shall notify the Company Representative and the governmental authority having jurisdiction with regard to fires and shall obtain written permission to proceed.

General requirements regarding prevention and control of fires are covered in the General Conditions. At all times during which burning takes place, the Contractor shall have available in working order to control the fire, sufficient fire fighting equipment and personnel to operate such equipment.

Any clearing which the Contractor elects to perform for his own purposes shall be subject to the approval of the Company Representative and shall be performed in accordance with the requirements of this Clause. Prior to the clearing of any area which is not required for the Work, the Contractor shall submit to the Company Representative for approval, full details of the proposed clearing. Clearing in any such area shall not be commenced prior to receipt of written approval by the Company Representative.

1.2.b Stripping and Grubbing

Stripping and grubbing of the selected areas of the Site shown on the Drawings shall consist of the complete removal of all vegetation and organic matter and grubbing to remove all roots and stumps.

All vegetable matter, roots and stumps so produced shall be disposed of in the same manner as that specified for non-merchantable debris in (a) above. Muskeg or material which cannot be burned shall be stockpiled in the designated topsoil stockpile area.

1.2.c Removal of Topsoil

After an area has been cleared, stripped and grubbed and the debris removed, the Contractor shall remove the surface topsoil and stockpile this material in the areas shown on the Drawings. Organic matter shall be stockpiled separately from the oxidized rooting layer of mineral soil.

The material is to be stockpiled in a neat workmanlike manner approved by the Company Representative such that it will be stable and protected from erosion.

Areas of standing water and swampy ground which are of sufficient extent to prevent topsoil removal by normal construction methods will not require topsoil removal. These areas will be defined in the field by the Company Representative.

1.3 Open Excavation

1.3.a Classification

Material excavated in open cut for the Work will be classified as follows:

1.3.a.i Class 1 Excavation

Class 1 excavation shall be in material excavated within the specified excavation limits which can be removed by hand or accepted mechanical excavation methods up to and including removal by ripping and bulldozing using a track mounted tractor, at least equivalent to a Caterpillar D9L in weight and horsepower and equipped with a single tooth articulated ripping attachment or, in confined areas, by a mechanical hydraulic shovel at least equivalent to a Caterpillar 225 fitted with a rock bucket of 1 cubic yard capacity.

1.3.a.ii Class 2 Excavation

Class 2 excavation shall be in material excavated within the specified excavation limits which cannot be removed by the methods specified in Sub-clause (i) of this Clause, and which would normally require recognized quarrying methods such as drilling and blasting.

In the event of a dispute as to the classification of any excavated material, the decision of the Engineer will be final.

1.3.b General

The Contractor shall develop its excavation methods, techniques and procedures with due consideration of the nature of the materials to be excavated and shall take such precautions as are necessary to preserve in an undisturbed condition all materials outside the lines and grades shown on the Drawings. The Contractor will be permitted to carry out excavation, shaping etc. by whatever method it considers most suitable, providing it is consistent with producing an acceptable end result as determined by the Engineer. The Contractor shall be solely responsible for the safety and adequacy of the methods employed.

The Contractor shall also notify the Engineer after clearing, stripping and grubbing, and removing topsoil from an area, and obtain the Engineer's approval of the adequacy of the exposed surface prior to excavating below or placing material on the surface.

The Contractor, in its scheduling of the Work, shall allow sufficient time in its construction schedule for the Company Representative's proper consideration thereof prior to his authorization to proceed with excavation in any area.

Furthermore, in areas where the Contractor is excavating both Class 1 and Class 2 materials, as hereinbefore defined, the Contractor shall obtain the Company Representative's written authorization to proceed with excavation of each Class before excavation begins.

The Contractor shall not excavate beyond the lines and grades shown on the Drawings without the prior written approval of the Company Representative. Any additional excavation which is performed by the Contractor for any purpose or reason whatsoever, other than in compliance with a specific request from the Company Representative, shall be carried out at the expense of the Contractor. If such additional excavation, as defined herein, should in the opinion of the Company Representative, require backfilling in order to satisfactorily complete the Work, such backfilling shall be done by and at the expense of the Contractor to the satisfaction of the Company Representative and with material supplied by the Contractor at its own cost, and approved by the Company Representative.

Where pipe, drain or culvert trenches are to be excavated in fill, excavation shall not commence until the elevation of the compacted fill exceeds the nominal crown elevation of the conduit by at least 30 centimetres.

The Contractor shall provide, maintain and operate any temporary drainage and/or pumping facilities required to control ground and surface water in order to keep the excavations dry and in a stable condition. The Contractor's dewatering operations shall be accomplished in a manner that will not adversely affect the stability of the excavated slopes and will not cause erosion and softening of adjacent materials.

The discharge from any dewatering system shall be directed to sediment ponds.

When a section of excavation has been completed to the required lines and grades, the Contractor shall notify the Engineer who will inspect the Work. Excavated surfaces shall not be covered with pipe bedding, fill or concrete until the surface has been approved in writing by the Engineer. The Contractor shall uncover at its own expense, any excavated surface which has been covered prior to inspection and approval by the Engineer.

The Contractor shall protect and maintain all excavations until completion of the Work or until such time as the adjacent placement of material has been completed.

Material from the excavations, which meets, or can be processed to meet, the requirements for the construction materials specified in the Contract Documents, shall be either stockpiled for later use, or used directly for construction of the Work. In the event that the Contractor elects to stockpile fill material prior to placing it directly into the fill, the cost of double handling shall be at the Contractor's expense. Excavated materials not suitable for use in construction shall be disposed of in spoil disposal areas as shown on the Drawings and as approved by the Company Representative.

1.3.c Class 2 Excavation

If the Contractor proposes to perform open excavation of Class 2 materials using drill and blast techniques, the Contractor's methods, techniques and procedures shall be such that, by controlling the relationship among such factors as: the location, dimensions and sequence of excavation of various benches, lifts and rounds; the burden; the spacing and size of holes; the amount and type of explosive; the depth of charge and delay pattern; and by employing the most effective controlled blasting techniques, the peripheral surfaces of all completed excavations shall be smooth, sound and to the specified lines of excavation.

Not less than 7 days prior to commencing Class 2 excavation for each part of the Work, and at any time it proposes to alter his methods for such excavation, the Contractor shall submit to the Engineer for authorization to proceed with the Work, complete details of the proposed plan for such excavation. Such plans shall include drawings and statements on all of the factors noted in the first paragraph of this Sub-clause and such other relevant data as are required by the Engineer to permit the Engineer to review the Contractor's proposed method of producing sound, smooth, excavated rock surfaces.

If the methods, techniques and procedures of excavation adopted by the Contractor for any part of the Work are unsatisfactory in that they fail to conform to the Contractor's proposal as previously authorized by the Engineer or that they result in an excessive amount of excavation or overbreak beyond the specified lines or result in excavated rock surfaces which are not sound and smooth, then, notwithstanding the Engineer's prior authorization to proceed with the Work, the Contractor shall adopt at it's own expense such revised methods, techniques and procedures as are necessary to achieve the required results.

Except as otherwise specified, each bench of excavation in rock shall not exceed 6 m or such lesser height as may be directed by the Engineer in order to obtain satisfactory results.

Whenever there is danger of causing damage or injury by flying rock, the shots shall be suitably blanketed.

The Contractor will not be permitted to blast within 30 m of any concrete, grout or shotcrete which has been in place less than 2 days. Blasting within 30 m of concrete, grout or shotcrete that has been in place 2 days or more will be permitted only after submission by the Contractor and authorization to proceed with the Work has been granted by the Engineer of the Contractor's proposed blasting procedures together with an outline of precautions to be taken.

The Contractor shall use non-electric blasting methods when conditions so require.

Except as otherwise specified or directed by the Engineer, the Contractor shall use pre-shearing, cushion blasting or other smooth wall drilling and blasting techniques as approved by the Engineer to excavate rock surfaces in open excavation.

Pre-shearing shall consist of drilling a line of holes not less than 38 mm in diameter in the plane of the required rock excavation surface and charging them with the minimum amount of high velocity explosive which will shear the rock in a plane along the line of the drill holes without shattering the rock. The charging rate for these holes shall not exceed 360 gm of 75 percent Gelignite or equivalent per square metre of pre-sheared area. In the event that higher velocity powder is used the charging rate shall be decreased on a pro-rated basis. The distance between the drill holes for pre-shearing shall not

be greater than 0.6 m and such holes shall be drilled at closer spacings if the rock is being excessively shattered by the pre-shear blasting.

All holes in a pre-shear plane shall be drilled, charged and detonated simultaneously prior to drilling the production blast holes and at least 24 hours prior to detonating the production blast. The first row of production blast holes adjacent to the pre-sheared plane shall be lightly charged to ensure that the pre-sheared face will not be damaged when the main production blast is detonated.

The maximum practical amount of unexcavated burden shall be maintained between the pre-shear line and the open face. The bottoms of pre-shear holes shall not be positioned at a higher elevation than the bottoms of adjacent primary blast holes.

Where the unexcavated burden is considered to be insufficient for preshearing, "cushion blasting" shall be utilized. Cushion blasting is defined as the technique of carefully drilling a line of closely spaced holes, as for pre-shearing, in the plane of the minimum line of excavation, lightly loading the holes with well distributed, completely stemmed charges and firing them after the production blast in groups of not more than 25 holes per delay.

1.3.d Class 2 Surface Clean-Up

The Contractor shall completely remove all loose, shattered and disintegrated rock, gravel or other deleterious material preparatory to placement of any earthfill, concrete, shotcrete or against rock surfaces.

Such cleaning shall be done by the use of air and water jetting or by other methods approved by the Engineer for all surfaces beneath concrete, shotcrete or grout. Air and water jetting is defined as the use of such jets for the purpose of cleaning rock surfaces, removal of incompetent material and cleaning out of seams, cracks, fissures and other depressions.

Air and water jetting equipment shall be capable of delivering air and/or water jets at variable pressures up to 100 psi and shall be complete with a selection of nozzle sizes. Air and water jetting equipment shall be capable of delivering air, water or both air and water at the required pressure through one nozzle.

In all areas of open excavation of rock, other than those intended for the placement of concrete, shotcrete or grout, the rock surface shall be cleaned and scaled using regular excavating equipment to achieve a surface which is in compliance with the provisions of this Clause. The use of hand tools will not be required for such clean-up except in cases where hand scaling is necessary to provide safe working conditions.

1.3.e Tolerances in Class 2 Excavation

The Contractor will be permitted to leave projections of solid rock inside the required lines of excavation provided that such projections cover an area not greater than 0.5 square metres, occur at not less than 3 metre centres at the planes of the required lines of excavation and do not project more than 10 centimetres inside such plane.

1.3.f Revisions to Lines and Grades

In the event that the Company Representative should in his sole discretion require the Contractor to excavate any part of the Work to lines or grades other than specified, previously directed by the Company Representative, or shown on the Drawings then:

(i) if the Contractor is advised of such requirements before excavation to the lines and grades specified, previously directed by the Company Representative, or shown on the Drawings, such required excavation will be paid for as per the applicable L.S. price entered for the excavation in The Schedule of Estimated Quantities and Prices; or

(ii) if the Contractor is advised of such requirements after excavation to the lines and grades specified, previously directed by the Company Representative, or shown on the Drawings, all additional excavation so required will be paid for in accordance with "Changes in the Work" of the General Conditions.

1.3.g Stability and Protection of Excavated Surfaces

The Contractor shall be solely and completely responsible, until completion of the Work, for the safety, stability, maintenance, support and protection of all Class 1 and Class 2 excavated surfaces, the excavation of which is carried out under the Contract, and for the safety of his work force and the forces of Others while they are in the Contractor's working areas including areas in the immediate vicinity of the excavations. The Contractor shall supply and install rock reinforcement and provide all temporary supports, bulkheads, canopies, sheeting and bracing, divert surface water, remove water from the excavations, and shall provide and maintain such drainage and pumping facilities as are necessary to stabilize and protect the excavations. Except as otherwise approved by the Company Representative, such temporary support and facilities shall be removed by the Contractor on completion of the Work.

Immediately following each blast the Contractor shall scale and remove all loose or unstable material from surfaces exposed by the blast, including such material beyond the required line of excavation, and shall at all times maintain such surfaces free of loose, unstable and potentially dangerous materials. The Contractor shall, wherever necessary, remove by scaling or other means all loose, overhanging or otherwise dangerous material situated on existing slopes that are located above excavations to be performed under this Contract.

1.4 Embankments and Berms

1.4.a General

The words "embankment fill", "fill materials", "fill" and "rockfill" shall be regarded as being interchangeable when used in the context of referring to the various zones of material comprising embankments and road fills. Similarly the words "backfill" and "bedding" shall be regarded as interchangeable when used in the context of referring to the various zones of materials comprising trench fill.

At least 7 days prior to the scheduled commencement of fill placement the Contractor shall submit to the Engineer for authorization to proceed with the Work, complete details of the various stages, materials, equipment, methods and procedures he proposes to use for such operations. Notwithstanding that the Engineer has given the Contractor authorization to proceed with such procedures, the Contractor shall be completely responsible for the planning and execution of such procedures.

The Contractor shall be liable for any damage whatsoever to property, caused by or resulting from his operations in performing the Work, including dewatering and/or drainage of embankment foundations. Such damage shall be fully repaired by and at the expense of the Contractor.

The Contractor shall prepare the foundation for and construct the various zones of fill of embankments and berms to the lines and grades shown on the Drawings within the tolerances specified herein. Fill materials shall not be placed on any part of foundations until all

required excavation, dewatering and foundation preparation has been completed and written approval has been granted by the Engineer.

1.4.b Supply and Production of Fill Materials

Fill material for constructing the embankments and berms and for trenches shall be supplied by the Contractor and will be obtained from:

- excavations required for the Work
- borrow areas
- other sources which may be proposed by the Contractor and approved by the Company Representative and Engineer

The borrow areas and excavations contain sufficient material to complete the Work. However, the disposition of the material is random and heterogeneous in the borrow areas and excavations will require proper planning and operation to obtain suitable materials which meet the specified requirements for the various zones.

The Contractor shall be wholly responsible for supplying materials which conform to the specified requirements for each class of material and shall take whatever measures and precautions are necessary to achieve this objective. Such measures shall include, but not be limited to, planned operation, drainage and selective excavation in the borrow areas and excavations, sorting, blending, screening, etc.

In the event that the Contractor wishes to obtain any materials from sources other than those stipulated above, then it shall carry out, at it's own expense, investigations to show that the material contained in the alternate area are suitable for the intended purpose. Such investigations shall be sufficient, to establish that the material is suitable. Details of the investigations and the results thereof shall be submitted to the Company Representative and Engineer at least twenty-one (21) days before the Contractor intends to commence production in the alternate area. Approval by the Company Representative and Engineer for the Contractor to obtain construction materials from alternative sources shall not relieve the Contractor of it's responsibility to produce materials which conform with the specified requirements.

All borrow areas and excavations shall be cleared, stripped and grubbed prior to commencement of material production.

1.4.c Material Requirements

The Contractor shall provide all fill materials required for the Work and shall ensure that such materials meet the requirements specified herein or shown on the Drawings. The acceptability of such fill materials will be determined by the Engineer on the basis of quality control tests which will be made frequently on each material after it has been placed and spread in the embankments and berms.

Wherever the terms "rock", "rock fragments" or "rockfill" are used in this Section to denote a fill material, they shall mean rock obtained from Class 2 excavation or natural talus either directly from such sources or from stockpiles. The term "sand and gravel", when used in this Section includes naturally occurring cobble and boulder content in the sand and gravel where such material meets the gradation requirements shown on the Drawings.

Fill materials shall be durable, shall not, except as otherwise specified, contain more than a small proportion of thin, flat or elongated particles and shall be free from organic and other deleterious material. Except as otherwise specified, the particles shall be hard and resistant to breakdown during handling.

Fill materials shall be well graded within the specified gradation limits, that is, they shall contain a good distribution of all sizes of particles from the coarsest to the finest. The specified gradation limits shall apply to the materials when they are dumped and spread on embankments and berms or placed in trenches prior to any required compaction.

Drain gravel shall be free of organic materials and other deleterious substances. The materials shall be uniformly graded and the gradation shall fall entirely within the specified gradation limits for each class of filter materials. The drain gravel shall be placed to form the zones shown on the Drawings in a manner such that segregation is avoided. Drain gravel shall be compacted as directed by the Engineer. Moisture conditioning will not be required when placing drain gravel.

The required gradation envelopes for the various zones of fill and drain gravel are specified on the Drawings.

The Contractor shall, as and when necessary, process materials to produce fill materials which meet the requirements specified for the various zones. Such processing shall, where necessary, include, but not be limited to, separating material into various sizes, blending one material with another, scalping off oversize material, screening and/or washing to remove fines, crushing or selective excavation of the materials.

All oversize material shall be removed from the fill material either prior to its being placed in embankments, trenches or berms or after it is dumped and spread but before compaction operations are started. Material which is a by-product of the processing of materials for one zone may be incorporated in the fill for another zone provided that it satisfies the specifications for such latter zone either by itself or after it has been blended with other material.

Stockpile locations shall be as approved by the Company Representative. The Contractor shall stockpile fill material such that excessive segregation will not occur. Before any area is used for stockpiling, it shall be cleared and stripped as necessary to prevent contamination of the material. Stripping and topsoil removal shall be carried out in accordance with the provisions of Clause 1.2.

1.4.d Fill Placement

The Contractor's operations and procedures for placing fill shall be subject to the approval of the Engineer in accordance with the provisions of Clause 1.4.a. Furthermore, no fill materials shall be placed in embankments, berms or trenches until all foundation preparation in the fill area has been completed to the requirements of the appropriate section in this Technical Specification and has been approved in writing by the Engineer.

The Contractor shall construct the zones of the embankments and berms only with materials meeting the specified requirements for such zones. The fill in each zone shall be free from lenses, pockets and layers of materials which are substantially different in gradation from the surrounding material in the same zone.

Fill material shall be excavated, transported, placed and spread in such a manner that segregation is avoided. Any material placed which does not meet the specified requirements shall be removed or remixed, blended, disced, or otherwise reworked by and at the expense of the Contractor to produce a material which does satisfy the specified requirements of the zone, whether or not such material has been covered by other fill material. Except as otherwise specified, the Contractor shall construct each zone by placing spreading and levelling; and, where required, compacting the specified fill material in continuous lifts of the specified thickness. The surface of each lift shall be sloped only at such grades as are necessary to ensure at all times that adequate surface drainage is provided.

Fill shall not be placed against concrete until a minimum of seven (7) days have elapsed after concrete placement.

Except as otherwise specified in the Technical Specification fill shall be dumped and spread in such a manner that no gaps are left between adjacent dumped loads of materials. The fill shall be levelled prior to compaction using a motor grader to obtain a smooth surface free from depressions. Except in areas where space is limited or as otherwise specified, fill shall be placed by routing the hauling and spreading units approximately parallel to the axis of the embankment and, within practical limits, the hauling units shall be so routed that they do not follow in the same paths but spread their tracks evenly over the surface of the fill. The equipment used for placing fill shall be such that it does not cause segregation of the material.

For trench backfill or working around or near pipes, valves, instrumentation or structures, the Contractor shall exercise particular care in fill placement to avoid damage to the Work. Should the Engineer for any reason wish to reinspect components previously authorized for backfilling, the Contractor shall excavate and re-expose such Work to the satisfaction of the Engineer. If any fault in the Work is uncovered the Contractor shall make the fault good to the satisfaction of the Engineer and replace the backfill. Such excavation, repairs and backfilling shall be done at the expense of the Contractor.

The Contractor shall have available during all working hours, sufficient heavy rubber tired graders or other equipment, approved by the Engineer in accordance with Clause 1.4.a., to level, re-level and otherwise maintain the uncompacted fill surfaces in a smooth and workmanlike manner.

In earthfills which require moisture conditioning, the Contractor shall condition the material to the moisture content designated by the Engineer prior to placing the material on the fill zone. The Contractor shall adopt all measures necessary to achieve a moisture content within one percent of that designated, distributed uniformly throughout the layer of material being placed, immediately prior to compaction. The Contractor shall adopt whatever measures are necessary to ensure that the designated moisture content is preserved after compaction, until the succeeding layer is placed.

Wherever necessary, after a layer of fill has been placed, the moisture content of the fill material shall be modified to ensure that it is within the range specified.

If after placing, spreading and levelling any fill material which becomes too wet for proper compaction as determined by the Engineer, it shall be either removed from the embankment or berm or the moisture content reduced to a value acceptable to the Engineer by discing or other approved methods. Suitable disc harrows or other approved equipment shall be available during all working hours for use if required.

Equipment used by the Contractor to apply water to fill material shall be designed to apply water uniformly and at sufficient rates to achieve the designated moisture content. Water tank trucks shall be equipped with positive shut-off valves so that no leakage will result from the nozzles when the equipment is not operating. In the event that leaks do occur, they shall be repaired immediately.

Moisture conditioning shall be carried out in a manner that will avoid flow of water between zones.

All zones in the embankments and berms are to be constructed in near horizontal lifts with each lift being completed over the full length and breadth of the zone before material is placed in the next lift.

The maximum difference in elevation between adjacent zones in the embankments, permitted at any time during construction, shall be equal to the larger of the two lift thicknesses for the two adjacent zones. Except for this requirement, the Contractor will not be permitted to form any construction joints in the embankments without the approval of the Engineer.

1.4.e Compaction

All fill material, after placing, spreading and levelling to the appropriate layer thickness, shall be compacted in accordance with the requirements of this Sub-clause and to the requirements of the appropriate section in this Technical Specification.

Filter and drain materials shall be compacted with a minimum of 4 passes of the specified compaction equipment appropriate to the zone under construction. Core material, Zone S, and basin liner fill shall be compacted to at least 95% of Modified Proctor maximum dry density. Random fill, Zone B, shall be compacted to at least 90% of Modified Proctor maximum dry density.

Compaction of each lift of fill shall proceed in a systematic, orderly and continuous manner such as to ensure that all of each lift receives the compaction specified. The compaction shall be carried out by routing the compaction equipment parallel to the axis of the embankment or berm, except that where such routing is impracticable, such as in roller turning areas, in areas adjacent to the foundations or at the lower elevations of the fill, in areas adjacent to concrete, and in trenches, the compaction equipment may be routed in any direction provided that all of each lift receives the compaction specified.

Hand guided vibratory compactors shall be used to compact materials which cannot be compacted by the specified vibratory rollers because of location near pipes, valves, instrumentation, structures or accessibility.

The Contractor shall take every precaution, when operating compaction equipment, to avoid damage to adjacent structures and instrumentation devices and their leads, and to avoid disturbing the foundation. Any such damage or disturbance shall be repaired or remedied by the Contractor at its own expense.

The rolling pattern at all zone boundaries or construction joints shall be such that the full number of roller passes required in one of the adjacent zones or on one side of the construction joint extends completely across the boundary or joint.

Should the surface of the fill become rutted or uneven subsequent to compaction, it shall be regraded and recompacted, by and at the expense of the Contractor, before the next layer of fill is placed.

All particles of dimensions such that they interfere with compaction in the layer thicknesses specified, shall be removed from the zone in which they were placed, either prior to or during compaction.

The Contractor shall provide sufficient compaction equipment of the types and sizes specified herein as is necessary for compaction of the various fill materials. If the Contractor wishes to use alternative equipment, it shall submit to the Engineer for approval complete details of such equipment and the methods proposed for its use. The Engineer's approval of the use of alternative equipment will be dependent upon the Contractor's demonstrating, by constructing suitable test fills, to the satisfaction of the Engineer, that such alternative equipment will compact the fill materials to a density not less than that which would be produced by the equipment and number of coverages specified herein.

Compaction equipment shall have sufficient power for the most adverse conditions to be encountered during compaction of the fill and when the compaction equipment is ballasted to the maximum weight specified for compaction of the fill.

When vibratory rollers are operated in a multiple arrangement, all of the rollers shall be similar and similarly ballasted. Compaction equipment shall be maintained in good condition at all times to ensure that the amount of compaction obtained is a maximum for the equipment. The Contractor shall immediately make adjustments to the equipment to achieve this end whenever such are necessary.

The Contractor shall, prior to shipping compaction equipment to the Site, submit to the Engineer, manufacturer's data giving all dimensions, weights and complete technical data, including descriptions and calculations of applied forces.

Unless approved under the prior provisions of this clause all fill material shall be compacted using the following specified equipment:

1.4.e.i Smooth Drum and Wedge-Foot Drum Vibratory Rollers

Smooth drum and wedge-foot drum vibratory rollers shall be equipped with a suitable cleaning device to prevent the accumulation of material on the drum during rolling. Each roller shall have a total static weight of not less than 9 tonnes at the drum when the roller is standing on level ground. The drum shall be not less than 1.5 m in diameter and not more than 2 m in width. The vibration frequency of the roller drum during operations shall be between 1100 and 1500 vibrations per minute and the centrifugal force developed by the roller at 1250 vibrations per minute shall not be less than 17 tonnes.

The power of the motor driving the vibrator shall be sufficient to maintain the specified frequency and centrifugal force under the most adverse conditions which may be encountered during compaction of the fill. Propulsion equipment for the roller shall be adequate to propel the roller at speeds up to 6 km/h.

For compaction by the vibratory roller, 1 coverage shall consist of 1 pass of the roller. A minimum overlap of 12 inches shall be maintained between the surfaces traversed by adjacent passes of the roller drum. During compaction the roller shall be propelled at 3 km/h.

1.4.e.ii Hand-Guided Vibratory Compactors

The Contractor shall adopt special compaction measures consisting of hand guided vibratory compactors to compact fill in trenches, around structures and in other confined areas which are not accessible to the larger vibratory roller. Such compaction shall be capable of compacting the material to the same density as that achieved by the larger vibratory roller. The number of passes of the hand guided vibratory compactors shall be determined by the Engineer.

1.4.f Quality Control

The Engineer will take samples of fill materials and perform gradation and moisture content tests and will carry out field density tests on the compacted fill and any other tests that he considers necessary to ascertain that the fill being placed or already placed meets the Contract requirements. The results of the tests carried out by the Engineer will be final and conclusive in determining compliance with the Technical Specifications.

Samples for quality control will be excavated by the Engineer. Sample pits by the Engineer shall be backfilled by the Contractor using fill material similar to that excavated and compacted using special compactors.

The Contractor shall give the Engineer full co-operation in sample taking or making tests and shall render such assistance as is necessary to enable sampling and testing to be carried out expeditiously. Each lift of embankment fill will need to be approved by the Engineer prior to placement of further fill. The Contractor shall allow sufficient time for the Engineer to carry out the required test work in order to determine the acceptability of each lift. The making of such tests by the Engineer or the time taken to interpret their results shall not constitute grounds for a claim by the Contractor for additional compensation or an extension of time.

Tests carried out by the Engineer will be performed in accordance with the principles and methods prescribed by the American Society for Testing and Materials (ASTM) and other such recognized authorities, such methods being modified to the extent necessary to take into account local conditions and the large particle sizes of the materials specified.

Notwithstanding any quality control testing carried out by the Engineer, the Contractor shall be responsible for performing such tests as are necessary to control the quality of the materials prior to delivery to, and after incorporation in embankments and berms.

Separate payment will not be made to the Contractor for any work involved in carrying out the tests specified herein or for backfilling the test pits excavated by the Engineer.

Tests carried out by the Engineer for the purposes of quality control defined above will be as follows:

1.4.f.i Control Tests on Fill Materials Prior to Compaction

Tests for gradation, and for moisture content where applicable, will be made on samples of fill materials taken from test pits after spreading and prior to compaction, at frequencies sufficient to ensure that the fill materials adopted for use are in full compliance with the Technical Specifications.

The results of these tests will be made available to the Contractor on request as soon as the necessary computations have been completed and checked.

1.4.f.ii <u>Record Tests on Fill After Compaction</u>

Tests for density will be made on the fill compacted in place and samples of the fill will be obtained for related laboratory testing, at such frequency as the Engineer considers necessary for the proper evaluation of the properties of the fill materials after compaction.

1.4.g Suspension and Resumption of Operations

In planning and implementing suspension and resumption of fill placement operations, the Contractor shall take into account the requirements for foundation preparation.

The Contractor shall not place fill materials at such times that conditions for such operations are unsatisfactory due to excess rain, low temperatures or any other reason. The Contractor will be permitted to place fill at atmospheric temperatures less than 0°C only if it can be placed and compacted to densities equal to those which would be achieved in the same material if freezing conditions did not prevail. Free draining sand and gravel, cobbles and boulders, and rockfill may be placed during freezing weather and on frozen fill surfaces provided that the materials in such surfaces were compacted as required by the Engineer before they became frozen and that the surface is free of snow and ice.

If placement of fill is suspended because of precipitation or impending precipitation or for any other reason, the surface shall be graded and rolled smooth to seal the surface and to avoid unnecessary absorption of moisture. In order to achieve this, the Contractor may at his option, provide cross or crown slopes of up to 5 percent for drainage control. The runoff from fills in progress shall be directed to sediment control facilities to the satisfaction of the Company Representative.

Where operations have been suspended, the effects of rain or other adverse conditions will be assessed by the Engineer before approval is given to resume placing. Equipment shall not be allowed to travel on the fill until the fill has dried sufficiently to prevent excessive rutting and to allow the equipment to be operated satisfactorily.

1.4.h Protection and Maintenance

The Contractor shall maintain any placed fill in a neat and workmanlike condition until completion of the Work. The Contractor shall take such steps as are necessary to avoid ponding of water on the fill or contamination of the fill by traffic or other causes, and he shall at all times keep the surface and slopes of the embankment free from rubbish, rejected or unsuitable fill, or waste materials.

The Contractor shall do whatever is necessary to prevent surface runoff or water from any other source from eroding fill materials placed for the Work, and shall, at its own expense, immediately repair any damage resulting from such erosion. Any repairs shall be carried out using the same standards for quality and workmanship as defined in the Contract Documents for the portion of the Work being repaired. Should any slide, including all movements of earth, rock, debris, or other material occur within or onto any part of the embankments or berms, the Contractor shall remove such materials and all other materials affected as directed by the Engineer, and any portions of the embankments or berms so removed shall be rebuilt in accordance with the Contract Documents.

Unless shown otherwise on the Drawings buried pipework shall not be crossed by motorized vehicles until the specified backfill has been compacted to a depth of at least 30 cm above the crown of the pipe. In embankments or roadways subject to compacting equipment or high wheel loads the depth of cover shall be at least 60 cm above the crown of the pipe. Temporary crossings shall be adequately flagged.

.1.5 Plain and Reinforced Concrete

1.5.a Code Requirements

Concrete to be incorporated in the work shall conform in all respects with the requirements of ACI Standard 318, ACI 304R, ACI 211.1 and ACI 214, except in the case of conflict arising between the requirements of the Technical Specifications and those of ACI Standard, in which case the requirements of the Technical Specifications shall take precedence.

1.5.b Concrete Composition

1.5.b.i General

Concrete shall be composed of Portland cement, water, fine and coarse aggregate, water reducing agent and air entraining agent. Concrete shall be designed to give a practical combination of materials which will produce the required durability and strength in the hardened concrete.

The strength requirements of all concrete to be used in the Work shall be a minimum strength of 30 MPA at 28 days. Lean concrete for blinding ("mud-slab") shall attain a minimum strength of 20 MPS at 28 days.

1.5.b.ii <u>Concrete Workability</u>

Concrete delivered for placing shall, at the time of placing, have a maximum slump limit not exceeding 75 mm.

The Engineer reserves the right to require a lesser slump wherever it is practical for concrete of such lesser slump to be transported, placed and consolidated.

Where concrete is being placed by pump, the slump at the receiving hopper of the pump will be permitted to be 25 mm more than that specified above.

1.5.b.iii Mix Design

The responsibility for the design of all concrete mixes to be used in the work will rest entirely with the Contractor. The concrete supplied shall be in accordance with ASTM C94 Standard Specifications for Ready-Mixed Concrete.

The Contractor shall cooperate with, and provide assistance to the Engineer in obtaining samples of aggregates and concrete and in maintaining quality control of all aspects of concrete production at the batch plant and at the point of placement of concrete. The entrained air content of the mortar fraction of the concrete at the point of placement shall be maintained at six (6) percent and shall not vary by more than one (1) percent from this value.

1.5.c Materials

Except as specified otherwise or approved by the Engineer, Portland cement shall be Type IIA, conforming to ASTM Designation C150.

Fine aggregate shall be processed natural sand. Coarse aggregate may be natural gravel or a mixture of natural and crushed gravel. All concrete aggregates shall be sound, free of harmful materials and nonreactive with the alkali that may be contained in the cement. Aggregates shall be properly graded and shall comply with ASTM Specifications C33, C131 and C136. The Contractor shall be responsible for the quality of all such materials used in the Work.

Water used in mixing, clean-up and curing of concrete, as well as water used for spraying concrete aggregates, shall be fresh, clean and free from deleterious amounts of silt, organic matter, alkali, acids, salts and other impurities.

Unless otherwise specified herein or directed by the Engineer, the following admixtures shall be employed:

- An air-entraining agent, confirming to the requirements of ASTM Designation C260.
- (ii) A water reducing agent. The water reducing agent shall be "Pozolith 300N" manufactured by the Master Builders Company or equivalent conforming to ASTM C494.

1.5.d Sampling and Testing

During the concreting operations the Engineer will sample and test all classes of concrete in accordance with ACI Recommended Practice 311.4R-5.

Tests carried out by the Engineer for the purposes of quality control will be as follows:

(i) Coarse and fine aggregates properties

Grading ASTM C136, C117 Abrasion (coarse aggregate) ASTM C131 Specific gravity and absorption ASTM C127, C128 Friable particles ASTM C142

(ii) Field Tests of Concrete

Slump ASTM C143 Temperature Air content ASTM C231 Compression tests on cylinders ASTM C31, C39

The Contractor shall provide and maintain at no separate cost to the Owner sufficient testing of the above parameters for its own quality control to ensure the aggregates and concrete continue to meet the requirements of the Technical Specification and shall make the results of such tests available to the Engineer.

1.5.e Transport of Concrete

The time elapsed between completion of the mixing of the concrete at the batch plant and its discharge at the forms shall not exceed 90 minutes for concrete properly agitated while in transit. Under no circumstances shall water be added to concrete during transit where such concrete has previously been batched with mixing water at the batch plant.

If these basic limits cannot be met for concrete mixed at the batch plant consideration will be given to dry-mix batching with water and air-entraining admixture added in the transit mix truck prior to discharge. Extreme care shall be taken to ensure that only sufficient water and air-entraining admixture is added to provide the required slump and air content.

1.5.f Forms

All formwork shall be in accordance with ACI 347 - "Recommended Practice for Concrete Formwork".

A bond-breaking compound shall be used on all forms.

1.5.g Construction Tolerances

Except as specified elsewhere in this Clause formwork shall be erected and braced and the concrete placed such that the dimensions of the completed concrete structure fall within the following tolerances:

Elevation	6 mm maximum deviation
Variation in plumb	6 mm in 13 m
Variation in all structural	-6 mm to +12 mm
dimensions	
Variation in location of inserts	-6 mm to +6 mm
openings, embedded metalwork	

Concrete work and embedded metal that exceeds the specified tolerance limits shall be remedied or removed by and at the expense of the Contractor.

1.5.h Preparation for Placement of Concrete

1.5.h.i General

Before the beginning of any concrete placement, the Contractor shall prepare the place of deposit in accordance with all requirements specified herein and elsewhere in the Contract Documents and obtain authorization from the Engineer, at least 24 hours in advance, for placement of concrete.

1.5.h.ii Subgrade Preparation

Earth or granular foundations shall be thoroughly compacted and dampened prior to placing concrete.

All rock surfaces against which concrete is to be placed shall be clean and sound.

Construction joints, bedrock and earth subgrade against which concrete is to be placed shall be damp.

Wetting of hardened concrete or bedrock shall begin 24 hours prior to the placement of concrete unless otherwise directed by the Engineer.

Concrete shall not be placed on frozen surfaces or into pooled water.

1.5.h.iii Final Clean-Up and Check-Out Inspection

Final clean-up shall comprise the removal of all mud, grease, snow, debris, wire, paper and other foreign matter from the surfaces on and against which fresh concrete is to be placed, by means of air or water jets or hand retrieval. Free-standing water shall then be removed so as to leave the subgrade or joint in a saturated surface dry condition.

Final clean-up shall be completed before the Engineer will make his check-out inspection for authorization to place concrete.

1.5.i Placement of Concrete

1.5.i.i General

The Contractor shall provide the Engineer with 24 hours notice stating when and where concrete is to be placed. Final check-out inspection for approval of concrete placement will be undertaken by the Engineer only after the setting of forms, placement of reinforcement and embedded metal and final clean-up have been completed.

Concrete shall be placed only in the presence of the Engineer.

1.5.i.ii Placing Procedure

Concrete shall be deposited as closely as practicable in its final position in horizontal lifts not more than 50 mm deep. Lateral movement of the concrete by means of vibrators will not be permitted.

Concrete shall be dropped vertically without lateral movement into formwork and without interference. Unconfined free fall shall be limited to 1.5 metres unless otherwise required or approved by the Engineer.

Methods and equipment used for the concrete consolidation shall be in accordance with the report of ACI Committee 309 - "Consolidation of Concrete".

1.5.i.iii Supply of Concrete

Concrete for the work shall be supplied by the Contractor. It is the responsibility of the Contractor to ensure that the concrete meets all of the above requirements.

1.5.j Repairs to Concrete

Repair of imperfections in formed concrete shall be completed as soon as possible after removal of forms. The Contractor shall keep the Engineer advised as to when repairs of concrete will be performed, and repairs shall be performed in the presence of the Engineer unless inspection is waived in each specific case.

1.5.k Curing and Protection

During the period when concrete is protected by forms, the exposed surfaces of all concrete built up in lifts shall be initially water cured. After finishing operations have been completed, water curing shall be continued.

1.5.1 Edge Bevels

Exposed edges of finished concrete which will not be subsequently covered with fill shall be provided with 45 degree bevels in all directions. The bevels shall be constructed using bevel forming strips of 25 mm by 25 mm by 45 degree size.

1.5.m Steel Reinforcement

1.5.m.i General

All bars employed for the Work shall be deformed bars conforming to ASTM A615 grade 60 unless otherwise specified on the Drawings.

Reinforcement fabric shall be welded steel wire fabric complying with the provisions of ASTM A185.

At the time concrete is placed, reinforcement shall be free from loose rust, scale, oil, salt or other coating which could impair the bond to concrete.

Minimum concrete protective cover for reinforcement, unless otherwise shown on the Drawings, shall be 50 mm.

1.6 Pipework

1.6.a General

All materials furnished by the Contractor shall be new, suitable and the best of their respective kind and shall be subject to approval by the Engineer. They shall comply with the latest applicable standards for the American National Standard Institute (ANSI) American Society of Mechanical Engineers (ASME), American Society for Testing and Materials (ASTM), American Water Works Association (AWWA) and the American Association of State Highway and Transportation Officials (AASHTO). Any contradictions between standards shall be submitted to the Engineer for decision.

1.6.b Manufacturer's Information

When specified, 2 copies of manufacturer's catalogues shall be provided at least 14 days prior to installation of the pipework. For pipe fittings and related pipework components, catalogues shall include detailed information on material specifications, dimensions and pressure ratings, storage and handling requirements, installation and joining procedures, name and location of manufacturers representative, corrosion protective coatings. For valves, gates and accessories the required information shall include, in addition, a replacement parts lists by catalogue number, operating and maintenance instructions and warranty documentation.

1.6.c Pipe, Fittings and Couplings

1.6.c.i High Density Polyethylene (HDPE) Pipe

HDPE pipe and fittings shall be made from polyethylene resin compound qualified as Type III, Category 5, Class C, Grade P34 in accordance with ASTM D1248.

Approved HDPE pipe material includes but is not limited to:

- Driscopipe 8600, with cell classification PE355434C or Driscopipe 1000 with cell classification PE345434C by Phillips Driscopipe.
- Poly pipe, with cell classification PE345434C by Poly Pipe Industries.
- Sclairpipe with cell classification PE345434C by KWH Pipe (Canada) Ltd.
- Plexco PE3408 with cell classification PE345434C by Chevron.

Cell classification shall be as defined in ASTM D3350 for PE3408 materials.

Catalogues shall be provided in accordance with Clause 1.6.b.

Fabricated HDPE fittings shall have a pressure rating equal to the pipe in which they are installed. Pipe used to fabricate fittings shall have dimensions in accordance with ASTM F714.

1.6.c.ii <u>Corrugated Polyethylene (CPE) Drainage Tubing and</u> <u>Culvert Pipe</u>

Pipework shall be manufactured from virgin material Type III or IV, Class C, Category 5, Grade P33 in accordance with ASTM D1248. Pipework, including couplings and fittings, shall meet or exceed all requirements of AASHTO M-252.

Catalogues shall be provided in accordance with Clause 1.6.b.

Perforations for CPE tubing, where specified, shall be slotted and shall be in accordance with the requirements of AASHTO M-252 except that total inlet areas shall not be less than 85 cm²/linear metre for tubing of diameter 20 cm or less.

Couplings shall be split, snap-on or screw-on type, as supplied by the manufacturer of the pipework. Self coupling pipework may be supplied.

Pipework in diameters of 15 cm and under may be supplied in continuous coils.
Steel pipe shall be AWWA C200 manufactured to meet the requirements of ASTM A139 Grade A or B. Wall thickness shall be standard weight (Schedule 40) unless shown otherwise on the Drawings. Pipe ends shall be butted if couplings are required bevelled if to be welded, or grooved if Victaulic type couplings are required.

Steel pipe if indicated on the Drawings, shall be corrosion protected in accordance with Clause 1.6.c.xii or Clause 1.6.e.i for buried or exposed conditions, respectively or as otherwise indicated.

Steel pipe fitting dimensions for welding shall meet ANSI B16.9 or as otherwise approved. Fabricated fittings and specials shall be in accordance with ANSI/AWWA C208.

1.6.c.iv Plastic Discharge Hose

Plastic discharge hose shall be Kanaflex Series 170 R or approved equivalent. 150 mm diameter hose shall have a minimum 100 psi working pressure rating and 250 mm diameter hose a minimum 50 psi working pressure rating. The hose shall be provided with a standard weight steel, hose nipple, rubber lined and secured with two "King" Double Bolt Clamps or similar. The hose nipple shall be grooved for attachment to a Class 150 flange with a Victaulic Style 741 "Vic-Flange" or similar. Hose diameters and lengths shall be as shown on the Drawings or required by the Engineer. Catalogues shall be provided in accordance with Clause 1.6.b for hose specifications and dimensions only.

1.6.c.v Pipe Fittings and Couplings

Grooved pipe fittings and couplings shall be ASTM A536 ductile iron, or steel, as supplied or recommended by Victaulic Company of America, or approved equal. Gaskets and seals for grooved pipe where required shall be EPDM. All components including bolts and lubricants shall be provided by the coupling manufacturer. All units shall be shop prime painted.

Catalogues shall be provided in accordance with Clause 1.6.b.

"Dresser" type compression couplings shall consist of a cylindrical sleeve with conical inner surfaces at each end, two wedge shaped resilient gaskets, two ring shaped followers and a set of high strength, low alloy, track-head, oval-neck rolled-thread bolts with heavy hex nuts. Sleeve lengths shall be 100 mm for pipe under 127 mm IPS, 127 mm for pipe up to 355 mm IPS and 178 mm for pipe over 355 mm IPS. Couplings for pipe over 355 mm IPS shall accommodate a total angular deflection at the joint of not less than 4 degrees.

Flanged coupling adapters shall combine the features of a flexible compression coupling with a flange to create a compact flexible fitting to connect plain end pipe to flanged fittings.

Compression couplings and flanged coupling adapters shall be shop primed and rated for a working pressure of not less than 150 psi. Where indicated on the Drawings couplings shall be provided with a harness assembly, to prevent the pipe pulling out of the coupling, while maintaining full joint flexibility.

All components including harness assembly and bolts shall be supplied or approved by the fitting manufacturer.

Catalogues shall be provided in accordance with Clause 1.6.b.

1.6.c.vi Corrugated Steel Pipe (CSP) Culvert

CSP shall be fabricated with helical 68 x 13 mm corrugations from galvanized steel sheets meeting all requirements of ASTM A444 and shall conform to the requirements of AASHTO M-36.

Unless otherwise shown on the Drawings, wall thickness shall be 2 mm for culvert pipe of diameter 0.91 m or less and 2.77 mm for culvert pipe of larger diameter. Unless shorter lengths are required for installation, CSP shall be supplied in 6 m lengths.

Catalogues shall be provided in accordance with Clause 1.6.b.

Couplings for CSP shall be the hugger type (Armtec H500 or approved equivalent) with rubber O-ring gaskets as supplied by the pipe manufacturer. Couplers shall be galvanized, of similar gauge to or heavier than the pipe being joined and shall be supplied by the pipe manufacturer. Fittings and sections and specials for CSP shall be shop fabricated from galvanized CSP conduits of similar or heavier gauge or as otherwise shown on the Drawings or approved by the Engineer.

Seepage collars or diaphragms shall be galvanized corrugated steel sheet cut to fit snugly and symmetrically about CSP culvert. Collar dimension shall be at least 0.6 m greater than the culvert diameter on all sides.

All fasteners shall be galvanized, cadmium plated in accordance with ASTM B766, or stainless steel.

Half-round culvert shall be manufactured, nestable, flanged or nonflanged galvanized corrugated steel pipe. Field cut culvert will not be acceptable for permanent installations.

Half-round culvert shall be provided with sufficient 38 mm diameter x 1830 mm long sharpened galvanized pipe stakes complete with caps and clip brackets, or equal as approved by the Engineer, for anchoring of the half section at 3 m intervals both sides.

1.6.c.vii Precast Concrete Manholes

Pre-cast reinforced concrete sections including lids and bases for use as valve chambers, wet wells or manholes shall be in accordance with ASTM C789, ASTM C850 or ASTM C478 for the installed conditions shown on the Drawings. Joints between sections, lids and bases shall be rubber gasketed in accordance with ASTM C443 or mastic sealed tongue and groove. Cut-outs may be factory formed or field located. Cut-out location and diameter is the responsibility of the Contractor. Manhole step-iron rungs shall be 19 mm galvanized iron, or equal, 300 mm wide with a 50 mm drop, protruding 150 mm from the wall and spaced 300 mm vertically. Locations shall be as shown on the Drawings.

Manhole access frames shall be cast iron or ductile iron, 510 mm diameter minimum opening, H20 rated, for embedding in pre-cast lids c/w cast iron cover.

Access hatches shall be by Bilco as approved by the Engineer.

Vents, where required, shall be standard weight galvanized steel pipe with 180° goose neck and heavy duty galvanized bird screen. Vents shall be attached to a flanged or grooved standard weight galvanized steel section embedded in the pre-cast lid or as otherwise shown on the Drawings. Vent heights and diameters shall be as shown on the Drawings.

1.6.c.viii <u>Tapping Sleeves</u>

Tapping sleeves for installation on HDPE pipelines shall be shop modified, Style 6626 stainless steel tapping sleeves by Robar Industries or as otherwise approved. All metallic components including fasteners, shall be Type 304 stainless steel except the flange which may be ASTM A536 ductile iron. The branch shall be supplied without a test plug and shall be fully lined with rubber integrally bonded to the body gasket. The body gasket shall be a one piece rubber mat of grid pattern, fully lining the sleeve shell. The flange face shall be bare metal, flat faced, drilled to Class 150 pattern. Tapping sleeve and offtake sizes shall be as shown on the Drawings or specified elsewhere.

Tapping sleeves shall be rated for at least 75 psi.

1.6.c.ix Flanges, Gaskets and Bolts

Unless otherwise specified or shown on the Drawings, steel flanges shall be Class 150 in accordance with ANSI/ASME B16.5 and cast iron flanges shall be Class 125 in accordance with ANSI/ASME B16.1. Class 25 flanges shall be in accordance with AWWA C207. Flange gaskets shall be full face, 1/16 in, fabric reinforced rubber or compressed asbestos. Flange assembly bolts shall meet requirements of ASTM A307 Grade A or Grade B, for cast iron flanges. Bolts shall be square or hex head. Nuts shall be heavy hex in accordance with ASTM A307.

It shall be the Contractor's responsibility to ensure compatibility between flanges used for the work.

All bolts and fasteners for intermittent or total submergence, or buried service or for embedment in concrete shall be type 304 stainless steel. All other bolts and fasteners shall be galvanized in accordance with ASTM A394 or cadmium plated in accordance with ASTM B766 unless otherwise approved.

1.6.c.x Rubber Lining of Steel Pipe and Fittings

Where required, rubber lining of pipes and fittings, shall be Linatex natural rubber, Shore 40, Durometer A in accordance with ASTM D2240, of thickness 6.5 mm for pipe of 150 mm IPS or less and of thickness 9.5 mm for pipe of larger diameter unless otherwise shown on the Drawings.

1.6.c.xi Lining and Coating of Steel Pipe

If indicated on the Drawings buried steel pipework shall be externally protected with Shaw polyethylene "Yellow Jacket", Specification No. 1, in accordance with AWWA/ANSI C215. Joints and couplings in buried steel pipe or damaged protective coating shall be wrapped with "Canusa" heat shrink sleeves in accordance with AWWA/ANSI C216 or a petrolatum tape system (eg. Denso T-1), or as otherwise in accordance with AWWA C217 and approved by the Engineer.

Lining of steel pipe as required shall be in accordance with AWWA C210 or as otherwise approved by the Engineer.

Catalogues shall be provided in accordance with 1.6.b.

1.6.c.xii Pipeline Guide Posts

Unless otherwise indicated pipeline guide posts shall be vertical 2.4 m lengths of firmly embedded 64 mm diameter standard weight steel pipe c/w screw on cap, both hot dip galvanized. Posts shall either be concrete embedded to a depth of 1 m or sharpened and driven at least 1 m to firm embedment. At least a 1 m length of pipe shall remain above ground.

1.6.c.xiii Pipe and Valve Supports and Hangers

All pipes and valves shall be properly supported and anchored in accordance with normal practice and the Drawings. Standard above ground hangers shall be of the clevis or clamp type, Wyatt Figure 124 or Figure 133. Chain or strap hangers shall not be used. Saddles shall be the adjustable pipe stanchion type with u-bolt yoke, Grinnell Figure 259/264 or similar.

1.6.c.xiv PVC Pipe Well Screens and Casings

PVC pipe shall be Schedule 40 or Schedule 80 in accordance with ASTM D1785, pressure rated pipe (SDR Series) in accordance with ASTM D-2241, or Drain Waste and Vent (DWV) Pipe in accordance with ASTM D-2665 as shown on the Drawings. Fittings for PVC pipe shall be in accordance with ASTM D-2466 for Schedule 40 fittings, ASTM D-2467 for Schedule 80 fittings and ASTM D-2665 for DWV pipe.

Well casing pipe and couplings shall be Schedule 40 PVC in accordance with ASTM F-480. Threads shall be ACME type. Slots for well screens shall be sized as indicated on the Drawings and shall be 25 mm minimum in length, with 6 mm spacing between slots. Slots shall be aligned in five vertical rows for pipe of 12 mm OD.

Locking lids for wells shall be water tight PVC with 'O' ring compression seal and including pivot and hinge and hasp with snap latch. Lids shall be "Snap Cap" by Monitoring Wells Sale and Service or approved equivalent. Wells shall be complete with concrete collar surround, approved valve box or manhole c/w lid.

1.6.d Valves and Accessories

Valve types and accessories shall be as shown on the Drawings and as listed below. Catalogues shall be provided with all valves and accessories in accordance with Clause 1.6.b.

1.6.d.i Slide Gates

Slide gates shall be Armco Model 5-00 galvanized steel slide gate or approved equivalent, handwheel operated, with mounting frame, suitable for flush mounting on a concrete headwall. Frame extensions and stem extensions shall be as shown on the Drawings. Where required, stem extensions shall be encased in oil filled 50 mm or 62 mm diameter standard weight galvanized steel pipe with upper and lower oil seals, suitable for prolonged exposure to sub-zero conditions and of lengths as shown on the Drawings or required to suit actual lengths in the field. The length of stem that will move through the seal packings shall be Type 304 stainless steel. Stem sections shall be joined by welded and pinned couplings acting as guides inside the casing pipe. Stem couplings shall have well rounded edges and be free of protruding components and slide freely inside the casing pipe. Stem couplings shall be located clear of joints in the casing pipe. Casing pipe lengths shall be joined with threaded galvanized couplings.

1.6.d.ii Pinch Valves

Manually operated, full metal body c/w back-up flanges, working pressure to 75 psi, double acting pinch mechanism, port area 100 percent of full pipe area, reinforced pure gum rubber sleeve with integral flanges drilled to ANSI B16.5 Class 150 standard, hand wheel operated, 4:1 ratio bevel gears on valves 8 inch diameter and above. Suitable for service with mine tailings slurry. Red Valve Series 75, RKL Series LHW or approved equal.

1.6.d.iii Knife Gate Valves

Manually operated, full port flow, all wetted parts Type 304 stainless steel or ultrahigh molecular weight (UHMW) polymers, working pressure to 100 psi, heavy duty frame, UHMW body liner and replaceable wear seal rings, flanges drilled to ANSI B16.5 Class 150 standard, hand wheel operated, 4:1 ratio bevel gear on valves 8 inch diameter and above. Suitable for service with mine tailings slurry. Clarkson KGA valve, L&M M-100, Rovalve ARL17 or approved equal. Valves above 450 mm nominal size shall be provided with a hydraulic actuator. Valve supplier will provide one only portable power pack suitable for installation in a pick-up truck for operation of the hydraulic actuator.

1.6.d.iv Butterfly Valves

Manually operated, AWWA/ANSI C504 quality, wafer or lug type as shown on the Drawings for installation between ANSI Class 125/150 flanges. Suitable for buried or exposed outdoor application under sustained sub-zero conditions on pipelines carrying storm water drainage and mine tailings supernatant, which will contain suspended solids. Non-corroding bearings, heavy duty service. Butterfly valves will be required in the applications set out below and as shown on the Drawings. Where shown on Drawings valves shall include geared operator.

1.6.d.v <u>Vacuum Breaker</u>

Vacuum Breaker valves for tailings slurry pipeline shall be Tech-Taylor Style T1 F4R-A3.

1.6.d.vi Pressure Sensor Assembly

Pressure Sensor for installation in HDPE slurry pipeline shall be Red Valve Series 42S, 1" diameter c/w good quality 3 1/2" glycol filled pressure gauge with 1 to 200 psi range as approved by sensor supplier. Ball valves shall be supplied both above and below the gauge.

Sensor body shall be PGR. Valves, bushings, nipples, plug and sensor body shall be stainless steel.

1.6.d.vii <u>Plug Valves</u>

Plug valves shall be DeZurik Series 100 for water service or as approved by the Engineer. Valves shall be completed with electric actuator and manual override.

1.6.e Workmanship

1.6.e.i General

Wherever possible, pipelines shall be installed parallel to or at right angles to surface structures and roadways.

The Contractor shall set the grade for every pipe length and shall ensure that the bed on which piping is to be laid is solid, well compacted and free of any dips, hollows, boulders or hard and sharp protrusions. Installation of buried or ongrade pipework shall not commence until bedding conditions have been approved by the Engineer.

Pipe and couplings shall be laid in accordance with this specification and the manuals of instructions issued by the manufacturers of the pipe or coupling in accordance with Clause 1.6.b.

Pipe and fittings shall be checked before installation for defects or cracks that might prevent proper jointing or operation of the pipeline and shall be clean and free of foreign matter. All pipe, couplings and fittings etc., shall be lowered into place in such a manner as to prevent damage to the pipework. End hooks of any kind shall not be used.

Damaged or defective pipe components shall not be used in the work unless repairs or modifications have been carried out with the approval of and to the satisfaction of the Engineer.

Care shall be taken to ensure that no water, muck, silt, gravel or other foreign material enters the pipework at any time. Care shall be taken to properly align and support the pipe before joints are completed.

Pipe shall be adequately supported during construction and on completion to prevent abnormal stresses being imposed on items of equipment such as pumps, flanges, valves etc.

Whenever work is suspended for any reason all open ends of piping shall be plugged or otherwise suitably closed. Should any pipe become either partially or wholly clogged before final acceptance of the Work, it shall be cleaned out by the Contractor or it shall be replaced by the Contractor at the Contractor's expense.

1.6.e.ii HDPE Pipework

Joining of HDPE pipe lengths shall be by thermal butt fusion or by Victaulic type Hugger couplings or flanges as shown on the Drawings or where otherwise required.

Thermal butt fusion of HDPE shall be carried out by experienced technicians supplied by, or approved by, the pipe supplier or manufacturer and in general accordance with ASTM D2657 and the recommended procedures provided with the manufacturer's catalogue information. The Engineer may require fusion operators to perform test welds for destructive testing, prior to commencing work on any permanent component of the facility.

Butt fusion equipment shall be in good repair and of appropriate size for the job, complete with all necessary clamps, controls, gauges, supports, ancillary equipment and operation/maintenance manuals.

The Owner reserves the right to have non-destructive testing of all thermally butt fused HDPE pipe welds carried out at any time during the Work and to reject those that are unsatisfactory for any reason. Such joints shall be cut out and repaired at the Contractor's expense.

If the Contractor elects to drag HDPE pipework into place all stub ends, flanges or offtakes and other components must be supported above ground on suitable skids or as otherwise necessary to avoid damage. The Contractor shall provide all necessary temporary guide posts and equipment to ensure pipework is not dragged across areas of completed earthworks susceptible to damage. If damage occurs to pipeline components or to completed earthworks during pipeline installation, the damage shall be made good at the expense of the Contractor. Gouges, holes or abrasion of HDPE pipework such that the wall thickness is reduced to less than 80 percent of its manufactured thickness shall be sufficient grounds for rejecting the pipe. Damaged sections of HDPE may be cut out and the pipe rejoined by butt fusion at the expense of the Contractor.

Natural bends in HDPE pipelines shall not exceed 50 pipe diameters in radius. Pipelines shall not be bent to such radius until at least 6 hours after completion of any fused joints in the section of pipeline to be bent.

1.6.e.iii Flanged Joints

Flanged joints shall be made with gaskets accurately centred in the joint. Bolts, studs and nuts shall be lubricated with flange bolt lubricant so that the nuts can be run up by hand. Care shall be taken to prevent excessive initial tensioning of bolts and studs, and to ensure that tension is applied uniformly. Rust preventive compound applied to the faces of flanges before shipment shall be removed before installation. Acid or tools that may damage finished surfaces shall not be used for cleaning flanges.

1.6.e.iv <u>Welded Joints</u>

Welded joints in steel piping shall be made by the electric arc process in accordance with ASME/ANSI B31.1, Chapter V and AWWA C206. Welding shall be

1 - 50

performed only by welders holding current, valid, welding tickets issued by the relevant Alaska authority. Prior to assembly and welding operations, pipe ends and all welding fittings shall be thoroughly cleaned and be free of foreign matter. Special precautions, including the provision of adequate protective shelters shall be taken when welding in cold or wet weather to avoid undue chilling of weld metal within the zone of welding influence. No welding shall be done without adequate preheating when the temperature of the metal is below 50°F. Approved shop fabricated or butt welding fittings shall be used for all bends and connections. Stub-ins for branch connections will not be permitted without the prior approval of the Engineer.

1.6.e.v <u>Backfilling</u>

Before final acceptance of pipework and before backfilling is completed the Contractor shall clean and flush all pipework and carry out hydrostatic pressure testing as required in accordance with Clause 1.6.e.vi.

Pipe backfill materials and procedures shall be in accordance with Clause 1.4.d. and shall meet the gradation requirements shown on the Drawings. Movement of the pipe after the joint is made shall be minimized.

1.6.e.vi Hydrostatic Pressure Testing of Pipework

All steel and HDPE pipework and joints shall be pressure tested prior to backfilling or final acceptance. CSP corrugated polyethylene, PVC and Profile Wall HDPE will not require pressure testing. Before testing is performed, the Contractor shall place sufficient backfill, pipe anchors and thrust blocks at bends in underground pipework or as otherwise required to prevent displacement of the pipe during testing. Pipe anchors and thrust blocks at bends shall be left exposed during the test.

The Engineer shall be present during pressure testing of pipework and shall approve each length of pipe after it meets the requirements specified herein. Testing shall be performed on valved or capped sections of the pipeline so that each valve (except where specifically excluded) in the system is tested for leakage in the fully closed position. Unvalved sections of the pipeline shall be adequately plugged prior to pressure testing. The Contractor shall supply the test pump, pressure gauges and all equipment necessary for filling and draining the pipeline and for carrying out the pressure testing, including end caps and 12 mm or 19 mm valves for venting excess air and for filling the pipe.

Pinch valves, air release valves, check valves, gate valves, tapping sleeves and other items of pipework which in the opinion of the Engineer cannot be satisfactorily tested (eg. decant inlets) or could be damaged by testing shall be excluded from the test.

The procedure for testing shall be as follows. The section of pipework to be tested shall be slowly filled and all air expelled. The pressure at the lowest point in the pipe section shall then be raised to the required pressure listed below. The quantity of water pumped into the test section to maintain the specified pressure over the period of the test shall be considered to be the leakage. The duration of the test shall not be less than 2 hours after initial filling and stabilization.

Test pressure shall be as follows:

Steel Pipe	-	150 psi (minimum)			
	-	300 j	psi (maxi	imum)	
HDPE Pipe	-	1.5	times	the	rated
		pressure of the pipe			

Pipe shall be tested in lengths such that no section of steel pipe sees less than the minimum test pressure and that no section of HDPE pipe sees more than the test pressure or less than 75 percent of the test pressure. Particular care to avoid overpressure must be exercised when testing HDPE pipeline placed on steep grades.

No leakage will be allowed in steel pipework or HDPE pipework.

Air pressure testing of pipework will not be permitted.

In the event of leakage of the Contractor shall make good the faulty joint or coupling and re-test the pipe all at his own expense.

It is the responsibility of the Contractor to supply all water and equipment necessary for pipe flushing, cleaning and pressure testing and to dispose of the water after the completion of such work in a manner compatible with Clause 1.10.e.

1.6.e.vii Corrugated Polyethylene Drainage Tubing

Installation of corrugated polyethylene pipework shall be in general accordance with ASTM D2321 and the manufacturer's instructions, with specific requirements as shown on the Drawings.

Pipework shall be laid to the maximum extent, in long lengths to minimize the number of couplings required.

Jointing of corrugated polyethylene pipework to other pipework shall be carried out as shown on the Drawings.

1.6.e.viii Corrugated Steel Culvert Pipe (CSP)

Joining of CSP to other pipework shall be as shown on the Drawings.

Localized areas in which the zinc coating has been damaged by welding or other fabrication procedures shall be repaired by careful wire brushing followed by two applications of a zinc rich paint as specified in AASHTO M36, or approved equal. CSP or fittings with gross uncoated or damaged areas shall be removed from the Work and replaced at the Contractor's expense.

1.7 Miscellaneous Metalwork

1.7.a General

The Contractor is advised that all the items of metalwork are not detailed on the Tender Drawings. The Contractor shall prepare complete shop and erection drawings of all miscellaneous metalwork to be supplied by him, showing in detail the sizes of each component part, type and grade of metal, connection and welding details, method of assembly, hardware and anchorage or connections with other work. Each of such Drawings shall be submitted to the Engineer for review at least 30 days prior to fabrication or ordering of any item shown thereon.

Before commencing fabrication, the Contractor shall verify the location and obtain all necessary measurement of adjacent work and structures which might affect the work.

Design, fabrication and installation of miscellaneous metalwork shall be in accordance with the AISC Manual of Steel Construction, AISC Code of Standard Practice and ASTM A36, except as otherwise specified.

All work shall be equal to the best modern practice in the manufacture and fabrication of materials of the type described herein or shown on the Drawings. All metalwork shall be carefully assembled in the most substantial manner to carry out the design called for, and reinforced where required. Built-up work shall be completely assembled in the shop and match marked for correct field erection. All frames shall be suitably braced to maintain alignment during shipment and erection. All work shall be rigid and true to line and grade. Individual members shall not be spliced except where shown on the Drawings.

All embedded metalwork shall be accurately set in place before concrete is placed or, where shown on the Drawings, recesses shall be left in the concrete and the metalwork placed, anchored and mortared in place after the concrete has set.

Where it is impractical to place anchors or anchor bolts by either of the foregoing methods, holes shall be drilled in the concrete and anchors shall be installed by the Contractor as directed by the Engineer. Anchor bolts shall be installed within the following tolerances unless otherwise shown on the Drawings:

Variation of alignment	-1/8 inch \pm
Variation of bolt projection	-1/4 inch+

Exposed welds shall be ground smooth on all bearing surfaces where prominent welds would prevent proper seating or bearing of two members. Welding of galvanized steel will not be permitted except where shown on the Drawings.

Shop connections shall be welded. Field connections shall be welded or bolted. Bolted connections shall be made with either standard bolts or high strength bolts, as indicated on the Drawings.

Concrete stud anchors shall be welded to the steel as shown on the Drawings in accordance with the stud manufacturer's instructions.

1.7.b Materials

Except as otherwise specified or shown on the Drawings, materials shall conform to the following standard specifications:

1.	Structural steel shapes,	ASTM A36 and
	bar plates	ASTM A6
2.	Floor plates	ASTM A36
3.	Cast iron	ASTM A48, Class 25
4.	Steel pipe	ASTM A53 Grade A or
		B, Black, Schedule 40
5.	Bolts, nuts and washers	
	- High strength	ASTM A325 Type 1
	- Standard strength	ASTM A307 Grade A or
		Grade B
	- Threads	Coarse thread
	- Washers, hardened	ASTM A325

	- Washers, standard	Standard commercial
	strength	quality
	- Bevel washers	Malleable iron or steel
6.	High strength threaded studs	ASTM A449

All bolts and fasteners for total or intermittent submergence shall be stainless steel.

Unless otherwise shown on the Drawings, all exposed fastenings shall be of the same material, colour and finish as the metal to which they are attached.

1.8 Painting and Galvanizing

1.8.a Painting

All metal surfaces to be painted shall be free of sharp edges or protrusions, solvent cleaned to SSPC-SP1, blast cleaned to SSPC-SP6, vacuum cleaned and shall be prime painted in the shop with inorganic zinc primer, except for galvanized surfaces, surfaces to be encased in concrete. Shop painting shall be performed in accordance with the provisions of the Steel Structures Painting Council.

Finish coat shall be 2 part epoxy applied to miscellaneous metalwork in the field as specified on the Drawings or elsewhere herein.

Field Painting of Welded Areas of Primed Steelwork

The welded areas shall be cleaned of all rust, scale and weld flux by chipping and power wire brushing.

Immediately after surface preparation is completed, the area to be treated shall be coated with one coat of an approved primer applied by brush or spray. The primer shall be overlapped onto the previous coating to the extent of about 20 mm on each side of the weld.

1.8.b Galvanizing

All galvanizing shall conform to the following requirements:

- Galvanizing shall be hot dip in accordance with ASTM A385 and ASTM A153 unless otherwise specified.
- The coating shall be clean and smooth and free from defects. Repair of damaged hot dip galvanized coatings shall be in accordance with ASTM A780.
- Material shall be galvanized after all fabrication, machining and shop work is completed, except as otherwise specified herein.
- The galvanizing of bolts, nuts and washer shall be in accordance with ASTM A394. Nuts shall be tapped after being galvanized and the threads of nuts left bare.

1.9 Geosynthetics

1.9.a Filter Fabric

The filter fabric required to be incorporated into the Work shown on the Drawings shall be non-woven needle punched polyester geotextile fabric at least equal to the following specifications:

	Test	Filter Fabric
Property	Method	Type 1
Weight	ASTM D-3776	8 oz/sq.yd.
Grab strength	ASTM D-1682	255 lbs.
Elongation at break	ASTM D-1682	65 percent

DRAFT 1625/3 March 22, 1996 INVESTIGATION KP 1-11 130 of 500

Mullen burst strength	ASTM D-3786	450 psi
Permeability	Constant Head	0.25 cm/s
EOS	CW-02215	80 micron
Puncture	ASTM D-751	140 lbs.
Trapezoidal tear strength	ASTM D-1117	140 lbs.
UV Resistance		Not required

The filter fabric type shall be Supac 8 NP as manufactured by Phillips Fibers Corporation or approved equal.

1.9.a.i Shipment and Storage

Fabric shall be packaged and shipped in standard roll lengths and widths. The geotextile shall be kept dry and wrapped such that it is protected from the elements during shipping and storage. At no time shall the geotextile be exposed to ultraviolet light for a period exceeding fourteen days. The fabric shall be labelled as per ASTM D4873.

1.10 Contractor's Construction Schedule

The Contractor shall complete the various items of the Work within the mandatory time requirements and dates specified in the Contract Documents.

Key Dates

The Contractor's Construction Schedule submitted with the Tender shall be based on the times specified herein and shall be used by the Contractor for planning, organizing and directing the construction of the Work and for reporting progress. The Construction Schedule shall be a detailed critical path method (CPM) schedule showing all principal activities relating to construction of the Work. Such activities shall include the items of principal value in the Form of Tender.

In accordance with the provisions of the General Conditions and of the Special Conditions the Contractor shall upgrade its Construction Schedule as necessary after commencement of and throughout the Work to meet the requirements of those Clauses as specified.

1.11 Contractor's Plant

1.11.a General

Except as otherwise specifically provided for in the Tender Documents, the Contractor shall make all necessary arrangements for the provision, operation, security, maintenance and subsequent demolition, disposal or removal on completion of the Work of all Plant, including stationary construction facilities, of whatsoever nature required for the complete and satisfactory execution of the Work.

Omission in the Tender Documents of specific requirements for any particular items of Plant shall in no way be construed to relieve the Contractor from its obligations under the first paragraph of this Clause.

The Contractor shall give the Company Representative at least seven (7) days notice in writing of its intention to remove any particular item of Plant or any part thereof.

1.11.b Site Arrangement Plans

Within seven (7) days of award of the Contract the Contractor shall prepare and submit to the Company Representative and Engineer for authorization to proceed with the Work, detailed site arrangement plans showing the layout and details of all services and other construction facilities which it proposes to install in its working areas. These plans shall include, but shall not necessarily be limited to, the following:

- Construction access to the various work areas on the Site, including road connections to public roads.
- (ii) Contractor's administrative office, workshop, warehouse and storage facilities.
- (iii) Water supply, sewerage and waste disposal facilities.
- (iv) Borrow areas, spoil areas and stockpile areas.
- (v) Groundwater and/or surface water handling and sediment control facilities.

Acceptance by the Company Representative and Engineer of the site arrangement plans shall in no way be construed to relieve the Contractor of its duties and responsibilities for the provision, operation and maintenance of adequate and suitable Plant.

Whenever the Contractor proposes to make any additions or revisions to its roads and other stationary construction facilities, they shall be shown on relevant drawings and re-submitted to the Company Representative and Engineer for review before the additions or revisions are made.

In considering the proposed location of stationary construction facilities, the Company Representative will, amongst other things, make due allowance for the requirements of others who shall be working on the Site from time to time.

Site arrangement plans shall be kept up to date by the Contractor at all times.

1.12 Availability and Use of the Site

1.12.a General

The Contractor is advised that the construction equipment, materials and labour forces of Others may be present on the Site during the course of the Work. The Contractor shall not locate any portion of its Plant where it will interfere with the work of Others and shall remove and relocate any such plant, at the Contractor's cost, should it interfere with the work of Others at any time during the course of the work of Others. Therefore, the Contractor shall not be entitled to exclusive use of any portion of the Site and shall cooperate with the forces of others as may be required by the Company Representative. Should the Contractor desire to make use of or occupy any land which lies outside of the working areas, a proposal for use and occupancy of such land shall be submitted for acceptance by the Company Representative.

Without limiting the generality of any of the provisions contained elsewhere in the Contract Documents, the Contractor shall protect the property of the Owner and Others from damage as a result of its operations, to the satisfaction of the Company Representative. In the event of damage to the property of the Owner and Others resulting from the Contractor's operations, the Contractor shall immediately notify the Company Representative. The Company Representative may exercise an option to:

- (i) Either direct the Contractor to immediately repair such damage, or
- (ii) notify the Contractor that such damage will be repaired by the forces of others.

Any such repairs shall be made to the Owner's satisfaction and at the Contractor's expense and, if made by the forces of Others, the cost therefore shall be paid by the Contractor.

1.12.b Site Roads

The Contractor shall be responsible for constructing and maintaining all roads on and to the Site as required under the Contract as well as constructing and maintaining any additional construction roads as deemed necessary by it for the performance of the Work.

All roads on the Site, including those that may be constructed by the Contractor shall be available for use by the Owner, the Company Representative and the Engineer and by others having permission from the Company Representative to do so.

At the completion of the Work all site roads and culverts used by the Contractor shall be left in a safe condition, with a reasonably smooth, well drained surface.

1.12.c Contractor's Site Office

During the performance of the Work, the Contractor shall provide and maintain at the Site an office which shall be the headquarters of the Contractor's Project Manager.

1.12.d Landscape Preservation and Restoration

The Contractor shall preserve the natural landscape except where clearing and/or earthwork is required by the Contract or permitted by the Company Representative in writing, and shall so conduct the operations and equipment such that the destruction, scarring or defacing of trees, the native shrubbery and the natural surroundings are kept to a minimum. On completion of the Work, all working areas shall be smoothed and graded to conform to the natural appearance of the landscape. In the event that, in contravention of the requirements of this Clause, or for any other reason, the Contractor's operations result in destruction, scarring, damage, or defacing of trees, shrubbery, or landscape outside the limits of the Contractor's working areas, all trees or shrubbery so destroyed, scarred, damaged or defaced shall be removed as soon as possible thereafter and the landscape shall be restored and reseeded with the natural vegetation to the satisfaction of the Company Representative at no additional cost to the Owner.

1.12.e Prevention of Water Pollution

The Contractor shall comply with all Federal and Provincial laws and regulations with respect to disposal of pollutants and all additional requirements specified in the Contract Documents.

The Contractor's construction activities shall be performed in a manner such as to prevent solid matter, contaminants, debris and other objectionable pollutants and wastes from entering streams, flowing or dry water courses, lakes and underground water sources. Such pollutants and wastes include, but are not limited to, refuse, garbage, cement, concrete, sewage effluent, industrial waste, oil and other petroleum products, aggregate processing tailings, mineral salts and silty or muddy water. Sanitary wastes shall be disposed of by methods approved by the Company Representative.

The Contractor is expressly warned that the groundwater and/or surface water runoff from all areas disturbed by the Contractor's operations must be directed to sediment ponds. Accordingly, the Contractor shall construct intercepting ditches, sumps, bypass channels, barriers, and/or other means to direct all muddy water and eroded materials to such sediment ponds after it leaves his working areas and all roads on the Site and prior to its entry into existing streams or water courses or permanent installations. Except as otherwise specified, excavated materials shall not be deposited or stored in, or alongside of, water courses where they could be washed away by high water, storm or normal surface runoff.

Any waters discharged from the Site shall be essentially free of material in suspension. For the purpose of this Sub-clause, material in suspension in waters released to the environment shall not exceed 25 mg/l or as otherwise required by law.

1.12.f Construction Facilities of Others

The Contractor is advised that temporary construction facilities of others such as, but not limited to roads, power and water lines and communication lines have been or will be constructed by others during the course of the Work. The Contractor shall not disrupt the continuance of use of such facilities until the Contractor is advised by the Company Representative that they are no longer required. Should the Contractor at any time wish to relocate these temporary construction facilities to facilitate the Work, prior written approval shall be obtained from the Company Representative.

1.13 Spoil Disposal Area and Stockpile Areas

Except as otherwise specified, the Contractor shall dispose of unsuitable and surplus materials from the excavations in the spoil disposal area and stockpile areas as shown on the Drawings or as otherwise directed by the Company Representative. Spoil and topsoil shall be placed to the height and slopes as shown on the Drawings or as otherwise required by the Company Representative.

Each spoil fill and/or stockpile shall be developed in an orderly manner and in such a way that it does not interfere harmfully with the natural drainage in the area. The Company Representative reserves the right to limit the amount of material which can be placed in spoil disposal areas and/or stockpile areas and

to control the method of construction, height and slopes to which the material can be placed. Spoil fills and/or stockpiles shall be stable within themselves, shall not cause instability of adjacent natural slopes or any parts of the Work and shall be graded to provide free draining surfaces which do not detract from the general appearance of the area.

Stockpiles should be developed in such a manner as to limit segregation. All surface water runoff from spoil areas and stockpile areas shall be directed to sediment ponds.

1.14 Dewatering and Drainage

Except as otherwise provided for by the Contract Documents, the Contractor shall investigate, design, construct, operate, maintain and subsequently remove such temporary cofferdams, dikes, fills, surface and sub-surface dewatering and drainage facilities as are necessary for control and removal of all water entering the work areas including seepage and leakage water, precipitation and water resulting from the operations of the Contractor. Cofferdams, dikes, fills and dewatering and drainage facilities provided by the Contractor shall be safe and stable, and shall be such as to permit the Work to be performed in an orderly and efficient manner under dry conditions. Water removed from the excavations shall be disposed of in such a manner as will not endanger the environment, the stability of existing slopes, or the Work, and shall be directed to sediment ponds.

The Contractor will not be permitted to use the permanent drainage facilities installed for the Work without the prior approval of the Engineer.

Construction and maintenance of all groundwater and/or surface water facilities shall be subject to the approvals of the Company Representative and Engineer prior to construction and shall be carried out in accordance with the provisions of Clauses 1.9.b. and 1.10.e.

The Contractor shall obtain written approval from the Engineer before discontinuing the operation of any dewatering system.

1.15 Borrow Areas

The Contractor shall give the Company Representative and Engineer not less than 14 days notice of its intention to develop any potential borrow area.

Prior to developing any borrow area other than the borrow areas designated on the Drawings or in the Specifications, the Contractor shall carry out such sub-surface investigation and obtain and submit such samples as are required by the Engineer to enable the Engineer to assess the suitability of the materials in the area for the intended use.

The Contractor shall keep accurate exploration records of a type approved by the Engineer of any test pit, trench or drill hole which is excavated for the purpose of investigating construction materials, and a copy of such records shall be submitted to the Engineer within 7 days of the completion of the test pit, trench or drill hole. Samples recovered from test pits, test trenches and drill holes and submitted to the Engineer for approval will be tested by the Engineer.

The Contractor's borrow pit operations shall be such as to avoid waste of any suitable construction material therein. The Contractor shall clear, strip and grub borrow areas, windrow all topsoil or, as directed by the Engineer, stockpile all topsoil which, in the opinion of the Engineer, can be salvaged. Borrow areas shall be developed with due consideration for drainage and runoff from the excavated surfaces so as not to cause erosion of the adjacent terrain. Borrow areas shall be excavated in such a manner that water will not collect and stand therein. For materials sensitive to overwetting, the borrow areas shall be developed to minimize the exposure of the material to precipitation. In till borrow areas all excavated faces shall be vertical. Before being abandoned, the sides of any borrow areas outside the final limits of the tailings storage facility shall be brought to stable slopes with slope intersections rounded and shaped to provide a natural appearance. All rubbish, Contractor's equipment and structures shall be removed from these areas. Waste piles shall be levelled, trimmed and shaped to regular lines to prevent the occurrence of ponding or of concentrations of surface runoff and to provide a neat appearance. All surface water runoff shall be directed to sediment ponds.

Waste material from an excavation for the Work or from a processing operation in a borrow area shall be disposed of in a spoil area or in an area approved by the Company Representative and set aside for this purpose within the borrow area.

1.16 Setting Out the Work

1.16.a General

The Owner has established at the Site, survey reference points and a bench mark. The Contractor shall use such reference points and bench mark as the basis for setting out the Work and shall be responsible for their preservation insofar as they are affected by his operations.

The Contractor shall set out the Work efficiently and accurately and shall be solely responsible therefor. The Contractor shall provide, fix and be responsible for the maintenance of all monuments, stakes, templates, batter boards, bench marks and other reference marks, and shall take all necessary precautions to prevent their removal or disturbance and shall be responsible for the consequences of any such removal or disturbance and for the accurate reinstatement of all such marks. The Contractor shall provide the Company Representative with drawings showing the locations and details of his monuments and control bench marks immediately after establishing of such monuments and shall submit updated drawings after making any changes, additions or deletions.

The Work shall be set out to meet the requirements of the Drawings and tolerance limits specified in the Contract Documents in all respects. At the request of the Company Representative the Contractor shall at all times, without charge, provide qualified personnel, equipment, tools and materials to assist the Company Representative in checking the setting out of the Work. No payment will be made for any expense incurred by the Contractor as a result of any work performed in the establishment of lines and grades, or in the checking of these and the taking of any other surveys or measurements.

If at any time during the progress of the Work any error should become evident or occur in the location, grades, dimensions or alignment of any part of the work, the Contractor, upon such error occurring or becoming evident, shall forthwith inform the Company Representative and shall at the Contractor's own expense rectify such error to the satisfaction of the Company Representative, unless such error is based on incorrect data supplied in writing by the Company Representative, in which case the expense of rectifying the error will, as between the Contractor and the Owner, be borne by the Owner.

The Company Representative reserves the right to use the Contractor's setting out monuments to perform occasional check surveys at times agreeable to both parties.

1.16.b Survey Accuracy

The accuracy of control surveys shall be subject to the approval of the Engineer. The Contractor shall present data and calculations to establish the following standards of accuracy relative to the benchmark and reference points provided by the Owner.

 Points on the Setting Out Line (S.O.L.) and the Contractor's temporary control points for embankment construction shall be established to a horizontal standard deviation of less than 20 mm and a vertical standard deviation of less than 40 mm, both with a 95% confidence interval, taking into account the limits of accuracy of the survey instruments as provided by the manufacturer.

 As-Built locations of pipework and culverts shall be established to horizontal and vertical standard deviations of less than 100 mm with a confidence interval of 95%.

1.16.c Field Notes and Calculations

Field notes shall be recorded in securely bound field books of high quality with a table of contents and each page numbered sequentially. The field books shall be made available for inspection by the Engineer upon request. Traverse adjustments shall be clearly indicated in the notes. A log listing all field note books by number shall be maintained.

Calculations including computer printouts shall be maintained in binders and shall be neat, orderly, and cross referenced as applicable.

Cross-sections shall be plotted on approved translucent cross section drafting sheets and submitted to the Engineer together with the appropriate survey notes and calculations.

The original and one copy of all field notes and calculations shall be submitted upon completion of the work. Disk copies of computer calculations shall be submitted.

1.17 Drawings Submitted by Contractor

The Contractor shall submit to the Company Representative and Engineer for review, one (1) reproducible and two (2) print copies of such drawings as may be required by the Company Representative and Engineer. Such submissions shall give complete details and information and contain sufficient views and be to such suitable scales as will show clearly the work or item. Each

drawing shall be prepared on bordered D size sheets (56 mm x 86 mm), shall include north arrow and scale bars as appropriate and shall in every case include a title block in the lower right corner stating the subject of the drawings, a drawing number, the current revision and dates of all revisions. Each drawing shall be carefully checked and signed by the Contractor prior to submission. On completion of the Work the Contractor shall submit a drawing showing the as-built locations and elevations of all major components of the work.

The review by the Company Representative and Engineer of drawings and schedules submitted by the Contractor shall not be construed as indicating any checking of the drawings and schedules, and shall not relieve the Contractor of responsibility for adequacy and accuracy of detail of the work shown on such drawings and schedules or for any errors therein or of any other of the Contractor's responsibilities under the Contract.

1.18 Standard Specifications

Specific codes and standard specifications referred to in these Technical Specifications and the Drawings shall, to the extent of such reference only, form part of the Technical Specifications and Drawings. Where a particular standard is referred to, that standard shall, unless otherwise stated, be the edition in effect thirty (30) days prior to the closing date for submission of tenders.

Where no specific standards are referred to, material, equipment and articles furnished by the Contractor shall comply with the applicable provisions of the American Society for Testing and Materials (ASTM).

1.19 Daily Reports

The Engineer will maintain in detail a daily report to record progress of the Work, the number of personnel of all categories at the Site, the materials delivered to the Site, and all other items which he deems necessary to record.

This daily report will be kept in the Engineer's site office and the Contractor's representative shall be required to read and sign this document daily. In case of differences of opinion between the Engineer and the Contractor regarding the facts stated in the daily report, the Contractor shall, within twenty-four (24) hours, give notice in writing to the Engineer regarding any such difference.

1.20 Provisional Sums

Every provisional sum, if any, set out in the Schedule of Estimated Quantities and Prices for work to be executed by the Contractor, which has not been specified in detail when the Contract is entered into, shall be deducted from the Contract Price and in lieu thereof subject to the provisions below, there shall be added to the Contract Price the value of the work so executed, valued in accordance with the provisions of the General Conditions entitled "Changes in the Work".

Work under provisional sums shall be executed by the Contractor only at the discretion and written direction of the Company Representative.

The Owner at all times reserves the right to have any part, or all, of the work covered under provisional sum items in the Schedule of Estimated Quantities and Prices performed by Others without any reimbursement to the Contractor by reason thereof.

1.21 Payment - General

The provisions of this Clause shall apply to each and every other Section contained in the Technical Specifications as if such provisions were specifically contained in each such Section.

Payment for the Work required by the Contract Documents for which Items have been included in the Schedule of Estimated Quantities and Prices shall be made in accordance with the lump sum prices and provisional sums entered in the Schedule of Estimated Quantities and Prices. The work to be performed
by the Contractor for such prices and provisional sums shall include doing everything necessary to complete such Items in accordance with the Contract Documents.

Except as otherwise provided for elsewhere in the Tender Documents, the lump sum prices and provisional sums included in the Schedule of Estimated Quantities and Prices shall be deemed to include all of the cost of doing everything necessary to complete all work required, shown, enumerated or described in the Tender Documents and on the Drawings whether or not such work is specifically shown or described as part of the work of any specific item in the Schedule of Estimated Quantities and Prices.

TABLE 1

SUMMARY OF TECHNICAL AND SAFETY ADVANCE NOTICE PERIODS REQUIRED OF CONTRACTOR

Clause	Subject	Notice Period
1.3.c.	Class 2 excavation	7 days
1.4.a.	First fill placement	7 days
1.4.b.	Alternate borrow areas	21 days
1.4.d.	Fill placement against concrete	7 days
1.5.h.(i)	Concrete placement	24 hours
1.6.b.	Pipe and fittings catalogues	14 days
1.9.a.	Removal of plant	7 days
1.9.b.	Site arrangement and sediment control plans	7 days
1.13	Borrow area development	14 days
1.17	Daily reports	24 hours

SECTION 2 - MOBILIZATION AND DEMOBILIZATION

2.1 Scope of Work

The Work in this section comprises the establishment on the Site of all the temporary accommodation, Plant and equipment necessary for the successful performance and completion of the Work and shall include, but not be limited to:

- 2.1.a Assemble all necessary Plant and equipment and transport it to the Site.
- 2.1.b Establish all the Contractor's maintenance facilities, temporary workshops, office accommodation and sanitation facilities on the Site.
- 2.1.c Provide and maintain the Engineer's field office and testing laboratory on the Site.
- 2.1.d Maintain all Plant and services for the duration of the Work.
- 2.1.e On completion of the Work, remove all Plant, temporary facilities and the Engineer's field office and laboratory from the Site and clean up and leave the Site in a clean and tidy condition to the satisfaction of the Company Representative.

2.2 Use of Site

The area designated for the Contractor's temporary facilities is shown on the Drawings. The Tenderer shall submit with its Tender a sketch showing clearly how it would utilize this area and what temporary facilities would be constructed.

The Tenderer shall also submit with its Tender a detailed layout showing all temporary haul roads and any other areas which it may wish to utilize in performing the Work. The Contractor shall plan its operations in a manner such that there is minimum disturbance to the natural terrain outside the limits of the work areas shown on the Drawings.

SECTION 3 - TAILINGS BASIN

3.1 Scope of Work

The Work to be completed in this Section shall include, and not be limited to the following:

- 3.1.a Strip and grub all roots and stumps in the tailings basin as shown on the Drawings or as otherwise instructed.
- 3.1.b Burn all non-merchantable timber and dispose of material from the stripping and grubbing by burning. Dispose of material which cannot be burned in the designated spoil area.
- 3.1.c Remove and stockpile all topsoil from the areas which have been stripped and grubbed.
- 3.1.d Excavate exploratory trenches in the lower part of the tailing basin and install the basin groundwater drains.
- 3.1.e Develop, operate and maintain the borrow areas required to supply fill materials for the Work.
- 3.1.f Construct the basin liner in the lower part of the tailings basin.
- 3.1.g Excavate the reclaim barge channel.
- 3.2 Stripping, Grubbing and Topsoil Removal

Stripping, grubbing and topsoil removal shall be carried out as defined in Clause 1.2 within the tailings basin to the limits shown on the Drawings. Swampy and wet areas which are inaccessible to construction equipment will not require stripping. The limits of accessibility shall be agreed between the Company Representative and the Contractor in the field, with the objective of optimizing recovery of topsoil. The Contractor shall assume an average depth of stripping equal to 0.30 m.

Stripping, grubbing and topsoil removal shall be scheduled to work progressively uphill in the tailings basin to minimize the area requiring sediment control until the basin liner is completed and the Main Embankment has been constructed to El.918 metres.

In all areas which the Contractor is required to carry out further work, the stripped ground surface shall be established by survey in accordance with the General Technical Requirements.

3.3 Basin Groundwater Drains

The Contractor shall excavate exploratory trenches in the lower portion of the tailings basin at the locations shown on the Drawings for the purpose of determining the limits of the glacial till in place which is at least 2 m thickness after topsoil removal. These trenches shall be excavated under the direction of the Engineer.

The exploratory trenches shall be excavated in an uphill direction at 0.25% minimum grade from temporary dewatering sumps near the upstream toe of the main embankment. In all locations where the trenches exceed 1.0 m in depth the trenches shall be excavated with benches at 1.0 m from the base of the trench to facilitate installation of the basin groundwater drain geotextile surround.

The basin groundwater drains shall be constructed in each trench immediately upon completion of excavation. The Contractor shall clean out all material which has caved into the trench, extend the specified geotextile and perforated CPT and backfill with drain gravel to 1 m depth in 2 - 0.5 m lifts, each levelled and compacted with 2 passes of the hand-guided vibratory compactors. After closing the geotextile, the trench

shall be backfilled with glacial till compacted in 0.35 m maximum thickness lifts as shown on the Drawings.

The Contractor shall install the non-perforated HDPE connecting pipe between the two basin groundwater drains.

The Contractor shall maintain the basin groundwater drains in a dewatered condition by pumping temporary sump(s) until such time as gravity drainage is established through the permanent drain conveyance pipe to be constructed as part of the Main Embankment works.

3.4 Basin Liner

3.4.a General

After completion of basin groundwater drain construction in an area of the tailings basin, the Engineer will designate the limits of the basin liner, to be constructed of compacted glacial till, placed and compacted in 3 lifts and covered with a frost protection layer as shown on the Drawings.

3.4.b Subgrade Preparation

The Contractor shall regrade the stripped ground surface and compact using the smooth drum vibratory roller with a minimum of 2 passes to "proof-roll" the basin liner foundation. Areas which are pumping, rutting or weaving shall be subexcavated and replaced with glacial till backfill or scarified and recompacted. At the completion of subgrade preparation the basin liner subgrade shall be a smooth, firm surface without isolated low spots, draining to the upstream toe of the main embankment.

3.4.c Grade Control

The Contractor shall establish the limits of the prepared subgrade by survey and shall measure the elevations of a 10 m x 10 m grid of points to be progressively extended over the entire basin liner area as subgrade preparation and basin liner construction advance. The Contractor shall prepare a drawing showing the elevations of the grid points measured within the completed portion and along the limits of the prepared subgrade and shall submit a copy to the Engineer for approval. When signed and dated, the subgrade approval will form the basis for control of the thickness of basin liner placed and compacted in the permanent work.

The Contractor shall check the elevations at the grid points after compaction of the second of the three lifts of glacial till and shall direct placement of the final lift accordingly to achieve the required final thickness upon completion. The Contractor shall plot the measured elevations of the top of the compacted third lift of basin liner at each grid point to prove that there exists at each point the 450 mm minimum required thickness of compacted glacial till.

In case of a shortfall, the Contractor may elect to check the thickness of the basin liner by excavating small test pits at selected grid points to confirm the survey results. However, it is the responsibility of the Contractor to provide proof to the satisfaction of the Engineer, that the basin liner has been placed in all required areas to the minimum thickness shown on the Drawings.

After acceptance of each part of the basin liner by the Engineer, the Contractor shall place the frost protection layer.

3.4.d Basin Liner Construction

The glacial till basin liner shall be placed, levelled, moisture conditioned if required and compacted in 3 equal lifts of at least 150 mm compacted thickness to cover the lower portion of the tailings basin with a low permeability glacial till blanket which connects the compacted till core zone of the main embankment to the natural existing glacial till blanket in the upper portions of the tailings basin.

The Contractor shall supply glacial till meeting the gradation requirements specified on the Drawings and meeting the moisture content requirements designated by the Engineer.

The material shall be placed and spread and shall be levelled with a motor grader. Prior to compaction all rocks larger than 100 mm and all roots or sticks larger than 10 mm dia by 200 mm long shall be removed from the material.

Compaction of the individual lifts of the basin liner shall be carried out using the designated number of passes of the smooth drum vibratory roller operated as specified in Clause 1.4.

The upper edges of the basin liner shall be feathered out to meet the natural ground to prevent ponding of surface runoff. Temporary construction joints formed in the basin liner shall be stepped back by at least 2 m from lift to lift to allow good bonding of the material and to prevent penetration of more than one lift of the basin liner by vertical construction joints.

The Contractor shall protect and maintain the completed surfaces of each lift of the basin liner against disturbance by construction traffic and softening or erosion by runoff until such time as the Engineer accepts the work based on results of testing and instructs the Contractor to proceed. The Engineer will make every effort to expedite testing and to provide the results in a timely manner, however, it is the Contractor's responsibility to schedule the work to avoid delays.

When a portion of the basin liner has been accepted by the Engineer as completed, the Contractor shall cover the accepted area with the specified frost protection layer of glacial till and shall seal the surface thereof with the smooth drum vibratory roller. This upper surface shall be graded to shed runoff until such time as the embankment fill is raised above the level of the top of the basin liner.

3.5 Borrow Areas, Spoil Areas and Topsoil Stockpile

The primary borrow areas, spoil areas and topsoil stockpile for the Work are shown on the Drawings. Development of these facilities and any other borrow sources which the Contractor may choose to utilize shall in all respects conform to the requirements of the applicable Clauses of the General Technical Requirements.

Stripping of borrow areas shall in all cases be carried out progressively ahead of the excavation to minimize the area open to erosion and to minimize sediment loading in surface runoff. Borrow floors shall be sloped to drain, with runoff directed to sediment ponds.

Waste piles and sediment ponds may be located in worked out sections of the borrow areas upon presentation of evidence to the satisfaction of the Engineer to show that no further quantities of suitable material which might be required in the Work would become inaccessible as a result. The preferred spoil area is located in the swamp adjacent to the borrow area in the tailings basin. The development, maintenance, and operation of the borrow areas, haul roads and all sediment control ponds shall be the responsibility of the Contractor. The Contractor may employ methods and means of procedure of its own choosing, subject to compliance with the requirements of the General Technical Requirements. Approval by the Company Representative and/or Engineer of the Contractor's proposed methods shall in no way be construed to relieve the Contractor of his responsibility for the safety, adequacy or efficacy of his operations.

3.6 Reclaim Barge Channel

The reclaim barge channel shall be excavated to the lines and grades shown on the Drawings. The Contractor shall excavate test pits along the length of the reclaim barge channel for the purpose of classifying the soils in advance of excavation. The Engineer will designate the excavated material as suitable for use in basin liner or embankment fills or for haulage to spoil based on its gradation and moisture content characteristics. A 6 m wide access road shall be constructed parallel to the reclaim barge channel in native material as shown on the Drawings.

4.1 Scope of Work

The Work to be carried out under this Section shall include, and not necessarily be limited to, the following:

- 4.1.a Strip and grub and remove topsoil from the foundation area for the Main and Perimeter embankments and seepage collection ponds.
- 4.1.b Excavate and prepare the foundation areas for the embankments, including subexcavation and backfill as directed by the Engineer.
- 4.1.c Dewater and maintain the foundation excavations by employing any temporary measures as are necessary to keep the excavations properly dewatered.
- 4.1.d Install foundation and toe drains.
- 4.1.e Install drain conveyance pipework and monitoring sumps.
- 4.1.f Supply, place and compact all earthfill materials in the Main and Perimeter embankments and pond berms.
- 4.1.g Excavate the seepage collection ponds and install the seepage recycle sumps.

4.2 Stripping, Grubbing and Topsoil Removal

All stripping and grubbing, and removal of topsoil in the embankment foundation and seepage collection pond areas will be carried out as specified in Clause 1.2.

The Contractor shall assume an average depth of stripping equal to 0.3 m.

4.3 Foundation Preparation and Excavation

Embankment foundation preparation following the completion of topsoil removal will include shaping and compacting the exposed surface to ensure adequate drainage and suitable erosion protection as directed by the Engineer. Embankment foundation preparation will be carried out progressively, working up both abutments only enough to stay ahead of the fill.

Excavation in the embankment foundation areas to the lines and grades shown on Drawings will generally be carried out in silty sand or glacial till and will terminate at an elevation which exposes bedrock, competent silty sand or glacial till. It is not anticipated that excavation in bedrock will be required.

Any soft and saturated materials which are encountered in the embankment foundations and are not acceptable to the Engineer will require treatment. Treatment may include, but is not limited to, subexcavation and replacement with suitable coarse grained backfill, the extension of foundation drains, or the placement of extra fill to act as a buttress. The extent, including depth, of any required treatment will be determined by the Engineer. Any areas treated by subexcavation and replacement will require shaping and compaction, as above, prior to fill placement.

Materials excavated from the embankment foundation and seepage collection pond areas which satisfy the requirements for use as fill material will be used to construct the various zones of the embankment or pond berms. In order to implement this, the Contractor shall carry out the foundation excavation in a strictly selective manner such that the silty sands are not mixed with the glacial till.

The Contractor shall be responsible for maintaining and preserving the final excavated surfaces and shall keep them free of water to the maximum practical extent by constructing diversion drains, sumps, temporary berms etc. to divert and control surface runoff. The Contractor shall have adequate pumping capacity available at all times to ensure that the excavations are properly dewatered. The Contractor shall determine the actual locations of all

dewatering facilities in order to fulfil his responsibility for control of water in all excavations to the satisfaction of the Engineer. The Contractor must recognise that foundation preparation and dewatering may prove to be difficult and shall make any and all provisions necessary to ensure a satisfactory completion of the works as required by the Engineer.

The Contractor shall operate and maintain the dewatering facilities until the Main Embankment is raised to El. 918 metres (sufficient to store the 1 in 100 year 24 hour storm) and the Engineer gives approval to commence impounding water on the basin liner.

Particular attention shall be devoted to protecting the final excavated surfaces of the glacial till. The Contractor shall avoid tracking equipment over these surfaces as much as possible and shall place the first layer of glacial till fill over the final surfaces as soon as possible in order to protect them. In the event that any final excavated surface of the glacial till deteriorates due to the Contractor's failure to protect it, then the softened, saturated or deteriorated material shall be removed and replaced with competent material at the Contractor's expense.

Prior to placing any fill materials or concrete on excavated surfaces, the surfaces shall be prepared as follows:

- (i) Surfaces of excavations in glacial till, sloping at less than 4H:1V, shall be kept clean of any loose debris and compacted with 4 passes of a 10 ton vibratory roller. In the event that the moisture content of these surfaces is too high to permit 4 passes of a vibratory roller and the surface tends to rut and weave, then the compaction shall be reduced to 2 passes of a 10 ton static roller or as required by the Engineer.
- (ii) Surfaces of excavations in sands and gravels sloping at less than 4H:1V shall be trimmed to the required lines and grades and compacted with 4 passes of a 10 ton vibratory roller.

(iii) For excavated surfaces sloping at steeper than 4H:1V, the fill shall be keyed in to the native soil by cutting vertical steps into the slope equal in height to the lift thickness of fill being placed.

After completion of foundation preparation in any area the Contractor shall measure such area and delineate the area on a Drawing showing the embankment outlines and shall submit this Drawing to the Engineer for approval. When signed and dated by the Engineer the approved area shall be covered immediately with one lift of fill appropriate to the zones of the embankment and shall be compacted as specified.

All requirements for installing basin and foundation instrumentation shall be met prior to placing fill in or above the instrumented areas.

4.4 Foundation Drains and Conveyance Pipework

The Main Embankment foundation drains shall be installed after the foundation preparation has been completed and before the commencement of embankment fill placement. Drainage pipework, filter fabric and granular backfill shall be placed at the locations and to the lines and grades shown on the Drawings.

Conveyance pipework for the basin groundwater and embankment foundation drains at the Main Embankment shall also be installed after the foundation preparation has been completed and before the commencement of embankment fill placement. Conveyance pipework and glacial till backfill with bentonite enriched seepage cutoffs shall be placed at the locations and to the lines and grades shown on the Drawings.

Conveyance pipework for the toe drain at the Perimeter Embankment shall be installed after the foundation preparation has been completed and before the commencement of embankment fill placement. Conveyance pipework and glacial till backfill shall be placed at the locations and to the lines and grades shown on the Drawings. All pipework shall be supplied and the Contractor's installation methods shall be in conformance with the General Technical Requirements.

4.5 Materials of Construction

4.5.a General

The embankments shall be constructed by placing and compacting the material in the various zones in successive near horizontal layers which extend from one abutment to the other and do not contain any construction joints normal to the axis of the embankment.

All traffic on the embankment surface shall be routed to traverse the entire surface and avoid being concentrated on any particular route.

All zones of the embankment shall be constructed concurrently and no zone will be permitted to lag behind, or be constructed ahead of, its adjacent zone by more than one layer thickness, unless prior approval is given by the Engineer. In addition, the placing, spreading and compaction shall be scheduled in a manner such that all runoff from precipitation falling on the embankment shall drain towards the upstream face of the embankment. The purpose of this is to reduce the discharge of suspended solids and sediment downstream of the embankment.

4.5.b Material Requirements

Requirements for materials placed in the various zones of the embankment are as follows:

4.5.b.i Zone S - Core Zone Glacial Till

Glacial till required for Zone S shall conform to the gradation limits shown on the Drawings.

Excavation and handling of the glacial till shall be carried out in a manner such that it is well blended and well graded. Lenses of sand and gravel which may occur in or at the boundaries of the in-situ glacial till shall be removed unless the Contractor can demonstrate that it can be blended into the glacial till to produce a blend which conforms with the specified gradation limits for Zone S.

From time to time the Engineer shall designate the moisture content at which the glacial till is to be placed and compacted in the embankment. The Contractor will be required to moisture condition the material prior to delivering it to the embankment to obtain a moisture content which is within plus or minus one percent of the designated moisture content. In the event that the moisture content of the glacial till delivered to the embankment falls outside these prescribed limits then the Engineer may require that it be removed and replaced with material which complies with the prescribed limits. In some instances, the Engineer may permit the Contractor to adjust the moisture content on the embankment.

4.5.b.ii Zone B - Glacial Till

Glacial till required for Zone B shall conform to the gradation limits shown on the Drawings. The excavation, handling and moisture conditioning requirements are identical to those for Zone S.

4.5.b.iii <u>Toe Drain - Filter Sand</u>

Toe Drain pipework and filter sand shall be placed at the locations and to the lines and grades shown on the Drawings. The toe drain filter sand material shall meet the gradation requirements shown on the Drawings. The material shall be sound, durable and resistant to breakdown during handling.

4.5.b.iv Foundation Drains - Drain Gravel

Geotextile, CPT and HDPE pipework and drain gravel shall be installed or placed at the locations and to the lines and grades shown on the Drawings. The drain gravel shall meet the gradation requirements shown on the Drawings. The material shall be sound, durable and resistant to breakdown during handling.

4.6 Fill Placement

All material placed in the embankments shall be loaded, placed and spread in a manner such that segregation is avoided. All lenses of segregated material shall be removed or be reworked on the embankments to maintain the specified gradation in each zone.

The placing, spreading, and levelling of all material on the embankments shall generally be carried out with the equipment travelling parallel to the embankment axis. Spreading and compaction along abutments, or in confined areas, shall be carried out by routing the equipment in a manner best suited to the circumstances in accordance with the provisions of Clause 1.4.

After spreading, and prior to compaction, all material in Zones S and B shall be levelled with a motor grader to provide a regular surface free of oversize cobbles and segregated rock pockets. Requirements for placement of materials in the various zones in the embankments are shown on the Drawings and are described as follows:

4.6.a Zone S - Core Zone Glacial Till

The glacial till in the embankment core, Zone S, shall be placed and spread to form layers which will not exceed 300 millimetres after compaction, and compacted using the specified vibratory roller.

The moisture content immediately after levelling shall be within one percent of that designated by the Engineer. No fill shall be placed on dried out surfaces. If the moisture content is wetter than that designated by the Engineer, additional measures such as disking of the fill materials may be required prior to compaction.

4.6.b Zone B - Glacial Till

The glacial till in the Zone B, shall be placed and spread to form layers which will not exceed 600 millimetres after compaction, and compacted using the specified vibratory roller.

The moisture content immediately after levelling shall be within one percent of that designated by the Engineer. No fill shall be placed on dried out surfaces. If the moisture content is wetter than that designated by the Engineer, additional measures such as disking of the fill materials may be required prior to compaction.

4.6.c Foundation Drains and Toe Drains

All material in the foundation drains and toe drains shall be placed to the lines and grades shown on the Drawings. Drainage pipework shall be installed as shown on the Drawings. The Contractor shall submit the details of his proposed method of constructing the embankment toe drain to the Engineer for review 2 weeks prior to starting to work on the toe drain.

Compaction of drain gravel and outlet conveyance pipe backfill shall be carried out using 2 passes of the hand guided vibratory compacts. Compaction of the filter sand will not be required.

4.6.d Compaction

All compaction shall be carried out immediately after the material has been levelled using a motor grader.

All fill placed shall be compacted as specified in Clause 1.4.e. using the appropriate type of compaction equipment specified herein or on the Drawings.

The number of passes required shall at all times be determined by the Engineer and shall be varied to achieve the compaction objectives shown on the Drawings.

4.6.e Protection and Maintenance

The Contractor shall maintain any fill placed in the embankment in a condition which satisfies the requirements of Clause 1.4.e. until the completion of the Work. The Contractor shall take such steps as are necessary to avoid ponding of water on the fill, or contamination of the fill by traffic or other causes and shall at all times keep the surface and slopes of the embankment and foundations free from rubbish, rejected or unsuitable fill, waste materials and unnecessary equipment. Furthermore, the Contractor shall protect all buried pipework in accordance with Clause 1.6.e.

4.7 Seepage Collection Ponds

The seepage collection ponds are located downstream of the Main Embankment and Perimeter Embankment as shown on the Drawings.

The Contractor shall, after completion of topsoil removal and staking of the excavation limits, excavate test pits or trenches in the presence of the Engineer to determine the nature and extent of the soils within the excavation limits. The Engineer will carry out Control Tests on samples of the soil and will, through the Company Representative, issue an instruction to the Contractor designating the soils for use as fill or for removal to spoil.

The Main Embankment seepage collection pond excavation is expected to comprise predominantly saturated silty sands. The Perimeter Embankment seepage collection pond excavation is expected to comprise competent glacial till.

The Contractor, prior to commencing excavation in an area, shall submit his proposed excavation method complete with details of haul routes, dewatering measures and sediment control plan to the Company Representative for approval. The proposed excavation method shall in all cases be in conformance with the General Technical Requirements.

The seepage recycle sumps each comprise a cast-in-place concrete base slab, a vertical CSP sump riser and a CSP intake pipe as shown on the Drawings. The Contractor shall supply and place the base slab and shall supply and install the CSP riser and intake pipe. Materials supplied and methods of installation shall conform to the General Technical Requirements.

The seepage collection pond berms shall be constructed of fill placed, spread and compacted in 0.3 m lifts. The Engineer will select material from the seepage pond excavations for use in the pond berm at the perimeter embankment. The main embankment seepage collection pond berm will be constructed of glacial till from the borrow area in the tailings basin.

4.8 Construction Tolerances

The Contractor shall prepare the foundations for and construct the various zones of fill of the embankment to the lines and grades shown on the Drawings, within the tolerances specified below.

- 4.8.a The maximum permissible horizontal and vertical deviation of the boundaries between the zones of the embankments from the lines and grades shown on the Drawings, shall be plus or minus 600 millimetres.
- 4.8.b The maximum permissible horizontal and vertical deviation of the sloping outer faces of the embankments from the lines and grades shown on the Drawings shall be plus or minus 1000 millimetres provided that the average line of the final dressed slopes shall not fall inside the required slope line.
- 4.8.c The crest width of the embankments shall not be less than the dimensions shown on the Drawings at any station along the crest.
- 4.8.d The final surfaces of embankment crests shall be graded to and finished within plus or minus 100 millimetres of the elevations shown on the Drawings.

SECTION 5 - SITE ROADS AND DIVERSION DITCHES

5.1 Scope of Work

The Work to be completed in this Section shall include, and not be limited to, the following:

- 5.1.a Construct, operate and maintain all sediment control facilities for the Work.
- 5.1.b Strip, grub and burn all non merchantable timber, vegetation, stumps and roots in the areas designated on the Drawings or as otherwise instructed.
- 5.1.c Remove and windrow or stockpile all topsoil from the areas which have been stripped and grubbed.
- 5.1.d Construct the Bootjack-Morehead Connector Road relocation complete with drainage culverts and with a decant structure at Edney Creek tributary.
- 5.1.e Construct the Area B runoff collection ditch complete with flow control structures and overflow culverts.
- 5.1.f NOT USED
- 5.1.g NOT USED
- 5.1.h Construct the tailings area diversion ditch.
- 5.1.i Upgrade and connect the reclaim access road.
- 5.1.j Replace windrowed topsoil on fill slopes along roads and ditches.

5.2 <u>Sediment Control</u>

The Contractor shall schedule his construction activities to provide control of suspended sediment in surface runoff from areas disturbed by the Work in accordance with subclause 1.10.e of the General Technical Requirements.

The primary sediment control facility for the tailings area will be the sediment pond formed by the Bootjack-Morehead Connector relocation. Ditches, roads and other construction activities outside the tributary catchment of this primary sediment control facility will require care to limit sediment concentrations in receiving waters. Methods to be employed by the Contractor may include, but are not limited to, terracing, silt fences, hay bales and careful supervision of work near streamcourses.

5.3 Stripping, Grubbing and Topsoil Removal/Replacement

Stripping and grubbing shall be carried out as defined in Clause 1.2 within the limits of the Work shown on the Drawings.

For the Work of this Section 5, comprising site roads and diversion ditches, topsoil shall be windrowed along the downhill edges of the cleared, stripped and grubbed corridors for the Work. The Contractor shall remove the topsoil a minimum of 1 m past the line of fill stakes and shall take care not to push the windrow of topsoil into standing timber. In cases of conflict, the Contractor shall immediately notify the Company Representative of the requirement for additional clearing. In no case shall fill be placed on unstripped ground or supported on topsoil windrows.

Upon the completion of the site roads and diversion ditches in each area of the Work, the Contractor shall compact the fill slopes by track walking with a bulldozer and shall spread the windrow of topsoil onto the fill slope using bulldozer(s) and/or backhoe(s) distributing the available organic material to achieve an even coverage on the slope. Haulage of topsoil along roads and ditches will not be required.

5.4 Bootjack-Morehead Connector Relocation

The Bootjack-Morehead Connector Relocation shall be built in the location shown on the Drawings to provide a 6m wide roadway generally to B.C. Forest Service Class 4 standards.

Sidehill portions of the road shall be built in local cut to fill with drainage ditches and culverts to suit local conditions. The embankment section of the road located south east of the Main Embankment of the tailings area shall be built to El.911 as shown on the Drawings using glacial till from the designated borrow area in the S.E. corner of the tailings basin. The embankment fill shall be placed, spread and compacted in lifts of 0.30 m maximum thickness.

All culverts shall be supplied and installed in accordance with the requirements of the General Technical Specifications.

The outlet culvert and decant structure shall be supplied and installed as shown on the Drawings.

The Contractor shall place a wearing course of rockfill in a single lift of 200 mm minimum thickness to complete the Bootjack-Morehead Connector Relocation. The wearing course shall be loaded and hauled from the Owner's stockpile, located approximately 1 km distant from the millsite in the open pit area. The wearing course shall be graded and compacted to form a durable surface as shown on the Drawings.

The Contractor is advised that the Bootjack Morehead Connector is a public road. The Contractor shall at all times maintain access through or around the site on the existing or relocated portions of this road. Delays of not more than one half hour to traffic will be permitted. The Contractor shall provide suitably equipped flagpersons at any location where, and at all times when, construction activities require that public access along the road be temporarily restricted. A prominent sign stating CONSTRUCTION AHEAD, SLOW TO 30 km/h shall be erected and maintained by the Contractor, to the satisfaction of the Company Representative, at each end of the affected portion of the road.

5.5 Area B Runoff Collection Ditch

The Area B runoff collection ditch and the associated flow control structures shall be constructed above the Bootjack Morehead Connector Road at the locations shown on Drawing No. 1625.215. Sections and details are given on Drawing Nos. 1625.216 and 1625.217.

After windrowing of topsoil to the lower edge of the cleaned area, the contractor shall set out the ditch alignment and the locations of the flow control structures in conjunction with the Engineer to allow adjustment relative to existing topography and existing stream course locations. The Area B runoff collection ditch shall be located sufficiently distant from the existing road to allow construction of the ditch without closure of the road, and to avoid interference of the ditch cuts and fills with the existing road section.

The ditch shall be constructed entirely in cut, as shown on the Drawings and the excavated material shall be placed to form a maintenance access road along the ditch. All cut slopes shall be dressed and trimmed to stable, neat lines and grades. All fill slopes shall be dressed, trackwalked for compaction and covered with topsoil as specified in Clause 5.3.

The culverts, slide gates and concrete headwalls which comprise the flow control structures shall be supplied, constructed and installed in accordance with the General Technical Requirements.

Riprap shall be placed at culvert exits and at other locations designated by the Engineer for erosion protection. Riprap shall be mine waste rock from the Owners stockpile in the open pit area, selected during loading and placement to avoid pockets of fines and boulders of average dimension greater than 500 mm. The rip-rap shall be predominantly 75 mm to 300 mm in size, averaging 150 mm in size.

5.6 Tailings and Reclaim Access Roads

The tailings access road and pipe containment channel shall be constructed in the locations and to the lines, grades and dimensions shown on the Drawings or instructed by the Manager.

After windrowing of topsoil to the lower edge of the cleared, stripped and grubbed area, the Contractor shall set out the road by survey. The final location of the Bootjack Creek crossing will require the approval of the Manager. The Contractor shall not carry out any instream work at Bootjack Creek without the specific written approval of the Manager. The schedule key dates set forth in Clause 1.8 shall be used to plan this work.

The tailings access road shall be constructed by placement of material from required cuts in 0.5 m lifts compacted with 4 passes of the heavy vibratory roller. Fill slopes shall be staked and constructed at 2H:1V and shall be trackwalked for compaction upon completion to grade, followed by respreading of the windrowed topsoil onto the fill slopes. Cut slopes shall be dressed to remove loose and overhanging material.

The tailings and reclaim pipelines shall be supplied and installed as specified in Section 6.0 of this Technical Specification.

The Contractor shall supply and install drainage culverts in the locations shown on the Drawings or directed by the Engineer. The pipe arch culvert shall be supplied and installed in Bootjack Creek. Temporary diversion of the creek will be required to place and compact a sound, level bedding pad for the pipe arch culvert. Special care shall be used in compacting material into the haunches of the pipe arch culvert. An air actuated "pogo" compactor is the preferred method of compaction into the culvert corrugations. Manual compaction using shovel handles will be acceptable as directed by the Engineer.

The tailings access road earthworks are described and specified starting at the millsite and proceeding to the tailings area as follows:

5.6.a Millsite to Bootjack Creek

The Contractor shall excavate the pipeline trench as shown on the Drawings. In locations where the bottom of the pipeline trench is not in glacial till as determined by the Engineer, the Contractor shall subcut the trench and place glacial till to provide the required 0.3 m of select fine grained till as specified on the Drawings. The base of the completed pipeline trench shall be compacted with 2 passes of the heavy vibratory roller and shall be free of sharp projecting rocks, soft or pervious areas, and shall grade continuously without sharp changes in grade or isolated low spots. The Contractor shall protect and maintain the pipeline trench until the pipelines are installed and backfilled. Pipe backfill shall be select fine grained glacial till obtained from required road cuts, spread in 150 mm lifts and compacted with the hand guided vibratory compactor.

Riprap shall be placed and compacted with the bucket of an excavator to form interlocking erosion protection, well bedded in the pipe backfill. Riprap shall be obtained from the Owners waste rock stockpile in the open pit area.

The Contractor shall carefully consider his options for surface runoff control to prevent erosion damage to work in progress.

The tailings access road shall be completed with safety berms and road wearing course as shown on the Drawings.

5.6.b Bootjack Creek Crossing

The elevation of final road grade at the Bootjack Creek crossing will be determined based on the requirement for continuous free drainage grade on the pipelines. A 4 m wide bench for the pipe sleeves will be required at final road grade in addition to the 8 m wide roadway.

5.7 Tailings Area Diversion Ditch

The tailings area diversion ditch shall be excavated along the west side of the tailings area, graded to discharge into flow control structure #3 at the SW corner of the tailings area.

The ditch, for the most part, will follow an existing logging road and will be constructed in local cut to fill.

Cut slopes shall be trimmed to neat and stable lines and fill slopes shall be trackwalked and the available stripped and windrowed topsoil spread as specified in Clause 5.3. Riprap will not be required in this ditch.

7.1 Scope of Work

The Work to be carried out under this Section shall include, but not necessarily be limited to, the following:

- 7.1.a Grouting and decommissioning of existing boreholes and standpipes.
- 7.1.b Supplying and installing piezometers in the basin groundwater and embankment foundation drains, embankment foundation, fill zones and in the tailings upstream of the embankment. The piezometers will be located on two vertical planes, identified as planes A and B, as shown on the Drawings.
- 7.1.c Constructing a monitoring hut, supplying and installing a piezometer terminal station in the hut and connecting instrumentation to the terminal station.
- 7.1.d Supplying and installing a Parshall flume.
- 7.1.e Supplying and installing survey monuments.
- 7.1.f Drilling and geotechnical sampling for Main Embankment foundation piezometers.

7.2 Grout Existing Boreholes

The Contractor shall grout selected existing boreholes and standpipes shown on the Drawings prior to commencing work which might lead to crushing or burial of the collars of such existing boreholes and standpipes. The grout shall be an expanding cement grout as approved by the Engineer. Any drillholes which are lost due to construction disturbance prior to grouting shall be relocated by survey, dug out and grouted or backfilled at the Contractors expense.

7.3 Piezometers

7.3.1 Materials and Supplies

A total of eighteen (18) piezometers shall be installed during Stage Ia and Ib construction, as shown on Drawing No. 1625.220. The piezometers shall be RST Model VW-2100, or approved equivalent, electric vibrating wire type rated for 25 and 100 psi as shown on the Drawings. The piezometers shall be connected to a 24 channel Terminal Station located in a monitoring hut via RST Model VW-2323 standard heavy duty, PVC jacketed direct burial cable (non-vented). An RST Model VW-2102 manual readout box, or approved equivalent, shall be provided to facilitate the reading of the piezometric data directly from the terminal station.

A barometer shall be installed in the monitoring hut as the reading is necessary for barometric compensation. A summary of required materials and supplies and a schedule of the required piezometers and lead lengths for Planes A and B during Stage Ia and Ib construction are presented on Dwg. No. 1625.221.

7.3.2 Installation Procedures

Piezometers shall be installed in the basin groundwater drains, embankment foundation drains, embankment foundation, fill zones and in the tailings upstream of the embankment as shown on Drawing No. 1625.220 under the direct supervision of the Engineer. Installation details are shown on Drawing No. 1625.221. The location of each piezometer shall be accurately surveyed by the Contractor immediately upon installation.

Basin groundwater and embankment foundation drain piezometers shall be placed in the granular backfill adjacent to the perforated CPE pipework. The leads shall be extended through the embankment foundation in the conveyance pipework trenches and then to the terminal station at the monitoring hut in trenches along the route shown on the Drawings. They shall be carefully placed in a shallow trench which shall be bedded and backfilled with a fine uniform sand as shown on the Drawings.

Foundation piezometers shall be installed in boreholes drilled after the installation of the basin groundwater and embankment foundation drains piezometers. The boreholes shall be a minimum of 50 millimetres in diameter. Following installation of the foundation piezometers, each borehole shall be backfilled with uniformly graded sand, bentonite and native till free of +25mm diameter particles. The leads shall be carefully placed in a shallow trench which shall be bedded and backfilled with a fine uniform sand and extended to the terminal station at the monitoring hut as shown on the Drawings.

Embankment fill piezometers shall be placed in shallow trenches excavated in the compacted till fill and backfilled with native till. The till in the trenches shall be compacted by hand using a jumping jack or other approved compactor. Embankment piezometers located in the toe drain shall be placed in shallow trenches excavated in the compacted filter sand and compacted by hand, as above. The leads shall be carefully placed in a shallow trench which shall be bedded and backfilled with a fine uniform sand and extended to the terminal station at the monitoring hut as shown on the Drawings.

Tailings piezometers shall be installed in vertical 50 mm diameter perforated steel pipes set in concrete base blocks. The tailings piezometer leads shall be extended through the Zone S fill in narrow hand-dug trenches as shown on the Drawings and backfilled with select fine grained till and compacted as directed by the Engineer.

Each lead shall have the piezometer number securely affixed to it at intervals not exceeding 10 metres along the lead. Splice connections shall be made with field splice kits supplied by the cable/piezometer supplier.

Extreme care shall be taken to protect and maintain all piezometer leads. Prior to burial all piezometer lead trenches shall be adequately staked and flagged. All repairs and splices required as a result of damage attributable to the Contractor's operations shall be to the account of the Contractor, up to and including complete replacement of the piezometers.

7.4 Terminal Station and Readout Box

The terminal station shall be supplied and installed and the readout box shall be supplied as shown on the Drawings. Extreme care shall be taken to protect these facilities both during and after construction. Any repairs required as a result of damage attributable to the Contractor's operations shall be to the account of the Contractor, up to and including complete replacement of the facilities.

7.5 Monitoring Hut

A monitoring hut shall be supplied and erected adjacent to the drain monitoring sump at the seepage collection pond downstream of the Main Embankment to house the piezometer terminal station. The monitoring hut structure shall be Lumberland garden shed model #SWG 108C, code #SKU584060 (8 ft x 10 ft) or approved equivalent, as shown on the Drawings, and shall be positioned and erected to the satisfaction of the Engineer. Electric power for the monitoring hut will be provided by Others.

7.6 Flow Monitoring

The Contractor shall supply and install a Parshall flume for flow measurement in the location shown on the Drawings and shall provide such survey control as the Engineer may require from time to time. The Parshall flume shall be a "2 ft" model as supplied by ______, or approved equivalent.

7.7 Survey Monuments

The survey monuments shall comprise a steel rod grouted into a drilled or excavated hole and protected with a surface casing and cover, all as shown on the Drawings. Locations will be selected to provide long term settlement record points and control points for setting out of future work.

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

GROUNDWATER MONITORING PROGRAM (REF. NO. 1624/2)

JUNE 3, 1996

Suite 1400 750 West Pender Street Vancouver, British Columbia Canada V6C 2T8 Telephone (604) 685-0543 Telefax (604) 685-0147 CIS: 72360,477

Knight Piésold Ltd. CONSULTING ENGINEERS

INVESTIGATION KP 1-11 179 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

GROUNDWATER MONITORING PROGRAM (REF. NO.1624/2)

THIS REPORT HAS BEEN PREPARED EXCLUSIVELY FOR IMPERIAL METALS CORPORATION. NO THIRD PARTY SHALL BE ENTITLED TO RELY ON ANY OF THE INFORMATION, CONCLUSIONS, OPINIONS OR ANY OTHER MATTER CONTAINED IN THIS REPORT."



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 180 of 500
Knight Piésold Ltd. CONSULTING ENGINEERS

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

GROUNDWATER MONITORING PROGRAM (REF. NO. 1624/2)

TABLE OF CONTENTS

PAGE

SECTION 1.0	INTRODUCTION AND SCOPE OF WORK			1
	1.1	GENER	AL DESCRIPTION	1
	1.2	REFER	ENCE INFORMATION	3
SECTION 2.0	SITE	INFORM	ATION SUMMARY	4
	2.1	PREVIO	OUS INVESTIGATIONS	4
		2.1.1	General	4
		2.1.2	General Site Geology and Hydrogeology	4
		2.1.3	Open Pits	5
		2.1.4	Waste Dumps and Overburden Stockpiles	6
		2.1.5	Mill Site	7
		2.1.6	Tailings Storage Area	8
	2.2	1989 M	ONITORING WELL PROGRAM	9
	2.3	1995 M	ONITORING WELL PROGRAM	10
SECTION 3.0	GRO	UNDWAT	ER IMPACTS	12
	3.1	MILL S	ITE AREA	12
		3.1.1	Baseline	12
		3.1.2	Operational	13
		3.1.3	Post-Closure	14
	3.2	TAILIN	GS STORAGE AREA	15
		3.2.1	Baseline	15
		3.2.2	Operational	15
		3.2.3	Post-Closure	16



Association des Ingénieurs-Conseils du Canada 1624/2 June 3, 1996 INVESTIGATION KP 1-11 181 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

SECTION 4.0	GROUNDWATER MONITORING PROGRAM	17
SECTION 5.0	SUMMARY AND CONCLUSIONS	22
SECTION 6.0	REFERENCES	23

TABLES

Table 3.1	Estimated Baseline Groundwater Flows and Dilution Ratios
	Open Pits, Waste Dumps, Overburden Stockpile, Mill Site
Table 3.2	Projected Groundwater Production From 1995 Wells
Table 3.3	Estimated Baseline Groundwater Flows and Dilution Ratios
	Tailings Storage Area

FIGURES

Figure 1.1	Project Location Map
Figure 1.2	Groundwater Arrangement and Catchment Basins Map
Figure 1.3	Mine Site Drainage Plan
Figure 2.1	Geological Plan of Open Pit Area
Figure 2.2	Baseline Groundwater Contour Plan at Millsite
Figure 2.3	Baseline Groundwater Contour Plan at Tailings Storage Area
Figure 2.4	Groundwater Monitoring Wells Plan
Figure 3.1	Baseline Mine Site Hydrogeology
Figure 3.2	Operational Mine Site Hydrogeology
Figure 3.3	Post-Closure Mine Site Hydrogeology
Figure 4.1	Groundwater Monitoring Schedule



1624/2

June 3, 1996 INVESTIGATION KP 1-11 182 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

APPENDICES

Appendix A	Manual on Sampling and Handling Guidelines for		
	Determination of Groundwater Quality		
Appendix B	1989 and 1995 Monitoring Well Installations Logs		
Appendix C	Borehole Logs		
Appendix D	Baseline Groundwater Quality Data to the End of 1995		



1624/2

June 3, 1996 INVESTIGATION KP 1-11 183 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

GROUNDWATER MONITORING PROGRAM (REF. NO. 1624/2)

SECTION 1.0 - INTRODUCTION AND SCOPE OF WORK

1.1 GENERAL DESCRIPTION

The Mt. Polley Project is located approximately 56 kilometres northeast of Williams Lake, British Columbia (Figure 1.1). The project will include open pit mining of copper and gold bearing ore, storage of waste rock in dumps adjacent to the open pits, processing of the ore to produce mine concentrate and transport of tailings slurry via a gravity feed pipeline to the tailings storage facility. No discharge of process solutions is required or anticipated at any time.

Development of the Mt. Polley Project will comprise three interconnected open pits, waste dumps, overburden stockpiles and a mill site all located on the Mt. Polley ridge. The tailings storage area will be located in a relatively flat area south of the Mt. Polley ridge. The overall site plan is shown on Figure 1.2 and the proposed drainage plan of the mine site is shown on Figure 1.3.

The British Columbia Ministry of Environment, Lands and Parks (MELP), Environmental Protection Branch has requested that a Groundwater Monitoring Program be designed and implemented for the Mt. Polley Project. The Groundwater Monitoring Program will be used prior to the commencement of the site preparation construction program, during operations and after closure. This document has been prepared in response to the MELP request. Information provided in this report includes selection of the monitoring well locations, well construction procedures, monitoring protocols, and a summary of results to date. The specific goals of this report are as follows :



Association des Ingénieurs-Conseils du Canada -1-

1624/2

June 3, 1996 INVESTIGATION KP 1-11 184 of 500

Knight Piésold Ltd.

- To determine the direction and volume of groundwater flow from the mine site and other disturbed areas to receiving waters.
- To identify the locations of all surficial and deep groundwater aquifers underlying the mine site and their points of discharge to surface waters.
- To establish background groundwater quality in aquifers prior to mine development.
- To calculate seepage and groundwater contaminant dilution ratios in surface receiving waters in order to ensure no exceedances of the British Columbia environmental water quality criteria.
- To locate seepage collection ponds and recovery wells to ensure optimal recycling of seepage from the tailings pond during operations and to provide background data to evaluate the efficiency and integrity of the seepage recovery systems.

Other requirements of the Ground Water Monitoring Program, as requested by MELP, include:

- Groundwater Monitoring Program to be developed and evaluated by a qualified hydrogeologist.
- "... establish monitoring wells downgradient from the pit, waste rock piles, and tailings pond dams, and to sample aquifers in both surficial deposits and bedrock below. Establishment of control wells in appropriate locations will be required where feasible, as part of the hydrogeological study mentioned above."
- "General field and lab QA/QC requirements for blanks, determination of accuracy and precision and data acceptability are similar to that outlined for collection of surface water quality data. Additionally, the proponent is



Canada

HKS

June 3, 1996 INVESTIGATION KP 1-11 185 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

asked to submit a groundwater monitoring protocol incorporating procedural QA/QC concerns specific to groundwater quality monitoring for approval by Environmental Protection, Williams Lake prior to implementation."

"Dedicated samplers for each well are required. When measuring dissolved metals in groundwater it is desirable to use an "in-line" filter to prevent precipitation of dissolved metals, upon exposure to air. Well casings must be constructed of materials that will not leach metals and artificially contaminate the groundwater samples collected for metals analysis."

1.2 REFERENCE INFORMATION

The Mt. Polley Project groundwater regime has previously been studied by Knight Piésold Ltd., who have prepared a number of reports which contain information relevant to the Groundwater Monitoring Program. These documents include an evaluation of the groundwater regime as described in "Report on Geotechnical Investigations and Design of Open Pit, Waste Dumps and Tailings Storage Facility, February 19, 1990" and in "Mount Polley Project, Stage I Environmental and Socio-Economic Impact Assessment, January 1991". Additional information about surface water hydrology is also presented in "Report on Project Water Management (Ref. No. 1624/1), February 6, 1995" and "Tailings Storage Facility Design Report (Ref. No. 1625/1) May 26, 1995.". In addition, a groundwater sampling protocol is provided in "Manual on Sampling and Handling Guidelines for Determination of Groundwater Quality, (Ref. No. 1625/5)" which has been updated and is included in its entirety in Appendix A.



Association des Ingénieurs Conseils du Canada

June 3, 1996 INVESTIGATION KP 1-11 186 of 500

Knight Piésold Ltd.

SECTION 2.0 - SITE INFORMATION SUMMARY

2.1 PREVIOUS INVESTIGATIONS

2.1.1 General

Hydrogeological investigations at the Mt. Polley site were initiated in 1989 by Knight Piésold and Imperial Metals as part of the geotechnical evaluation of the open pits, waste dumps and tailings storage facility. Hydrogeologic investigations were conducted by advancing drill holes through overburden soils into the underlying bedrock. Bedrock permeabilities were evaluated using in-situ pump-in packer tests at the open pit site and the tailings storage area. Overburden permeabilities in the tailings storage area were evaluated using a combination of in-situ pump-in packer tests and falling head tests conducted in standpipes. Laboratory hydraulic conductivity testing was also conducted on representative samples of the overburden materials.

2.1.2 General Site Geology and Hydrogeology

The Mt. Polley project is located in an alkali intrusive complex in the Quesnel Trough, a 35 kilometre wide northwest trending regional volcanic - sedimentary belt. Rock units are segmented in blocks by several faults, including an inferred northwesterly trending normal fault which extends along Polley Lake. Geological structures of the region are predominately northwest trending, dipping steeply to the northeast as shown on Figure 2.1.

Topography is generally subdued and the area has been glaciated. Surficial deposits of well graded dense glacial till are common throughout the area and are typically present in greater thickness in topographic lows. Bedrock exposures are common at higher elevations.

The Mt. Polley ridge extends over parts of four watersheds. The two main watersheds are the Polley Lake watershed to the east and the Bootjack Lake



Association des Ingénieurs-Conseils du Canada 1624/2

June 3, 1996 INVESTIGATION KP 1-11 187 of 500

watershed to the west. The north side of the ridge drains into the 6K Creek watershed and the south side of the ridge drains into the Bootjack Creek watershed. The west and a portion of the north and central pits, several overburden stockpiles and part of the mill site will be located in the Bootjack Lake watershed. The remaining portion of the north and central pits, most of the north and southeast waste dumps, some overburden stockpiles and the remaining portion of the mill site will be located in the Polley Lake watershed. In addition to the two main watersheds there will be a small portion of the north waste dump located in the 6K Creek watershed and a small portion of the southeast waste dump located in the Bootjack Creek watershed (Figure 1.2).

The tailings storage area will be located in the Northeast Edney Creek Tributary. Due to construction of the embankment along the ridge tops and subsequent filling of the tailings facility, there is the potential for seepage into the two adjacent watersheds, Hazeltine Creek and Southwest Edney Creek Tributary.

Previous investigations have shown that the groundwater aquifers at the Mt. Polley Project site consist of unconfined fractured bedrock zones at the open pit, waste dump and mill site areas and a confined glaciofluvial/alluvial deposit at the tailings storage area. Static groundwater tables were determined to be relatively near surface for both areas, as shown on Figures 2.2 and 2.3.

2.1.3 Open Pits

The open pits are situated in an area of irregular topography with moderate to steep relief. Surface water ponding and stream flows in the pit area are ephemeral. Overburden, where present, in the open pit area consists of a thin veneer of colluvium, glacial till and forest litter. Bedrock consists of intrusion breccia, syenodiorite and monzonite with lesser occurrences of



Association des Ingénieurs Conseils du Canada 1624/2

June 3, 1996 INVESTIGATION KP 1-11 188 of 500

dyke rock. Several fault and fracture zones have been identified with occasional clayey or sandy fault gouge zones.

Geological structures trend in a north-south direction, parallel to the orientation of the Mt. Polley ridge. Several east-west oriented fault zones have been identified in the open pit areas, as shown on Figure 2.1. The rock quality is variable, with highly fractured zones up to 100 metres long encountered in several exploration and condemnation drill holes. Zones of very weak and highly altered rock up to 100 metres in thickness were also encountered. These zones are usually associated with geological contacts between rock units and faulting. The dominant joint set has a strike of 167 degrees and dips 74 degrees to the northeast. A weaker orthogonal joint set strikes 030 degrees and dips at 18 degrees to the northwest. Discontinuities are generally rough and often healed with calcite and chlorite.

The hydrogeology of the open pits was previously evaluated, with a summary provided in the Imperial Metals Corporation January 1991 document "Stage I Environmental and Socio-Economic Impact Assessment, Responses to Comments by the Agencies". The groundwater table was found to be near surface, running parallel to the surface topography. Groundwater flows originate from the Mt. Polley ridge and flow toward Polley and Bootjack Lakes, as shown on Figure 2.2. Piezometric measurements indicate that groundwater within the ridge is under hydrostatic conditions. In-situ hydraulic conductivity measurements obtained for the bedrock strata were generally low, less than 1 x 10⁻⁵ cm/s. In the fractured bedrock zones hydraulic conductivities were measured at 1 x 10^{-4} cm/s to 1 x 10^{-3} cm/s.

2.1.4 Waste Dumps and Overburden Stockpiles

Current mine plans include the development of two waste dumps and several overburden stockpiles, as shown on Figure 1.3. The Southeast waste dump provides storage for all waste rock generated from the Central



Association des Ingénieurs-Conseils du Canada 1624/2

June 3, 1996 INVESTIGATION KP 1-11 189 of 500 and West Pits. It will be activated at the start of mine development. The North Waste Dump may be developed later in the mine life in order to provide additional storage for waste rock generated from the North Pit.

Existing surface water ponding and stream flows in the waste dump and overburden stockpile areas are ephemeral. Overburden, where present, in the waste dump areas consists of a thin veneer of colluvium, glacial till and forest litter. Predominant bedrock types consist of monzonite porphyry, syenodiorite and various volcanic units including lapilli tuff and breccias. Geological structures are projected to be conformable with the open pit area.

The groundwater table is expected to be near surface, running parallel to the surface topography, with groundwater flows originating from the centre of the Mt. Polley ridge towards Polley and Bootjack Lakes, as for the open pit areas. Bedrock permeabilities are also expected to be similar to the open pit areas, generally less than 1×10^{-5} cm/s.

2.1.5 Mill Site

The mill site is located on a relatively flat and undulatory section of the topographic ridge between Polley and Bootjack Lakes. Surface water ponding and stream flows are ephemeral. Overburden at the mill site is generally similar to the open pit and waste dump areas. A swampy area with a thick organic horizon recharged by surface runoff and shallow groundwater flows has been excavated from the southern half of the mill site area. Bedrock types and geological features are also similar to the open pit and waste dump areas.

The hydrogeology of the mill site area was previously evaluated and a summary has been presented in the Imperial Metals Corporation document, "Stage I Environmental and Socio-Economic Impact Assessment, Responses to Comments by the Agencies, January, 1991". The groundwater table was



Association des Ingénieurs-Conseils du Canada 1624/2

June 3, 1996 INVESTIGATION KP 1-11 190 of 500

reported to be parallel to the surface topography, with groundwater flows migrating from the Mt. Polley ridge towards Polley and Bootjack Lakes, as shown on Figure 2.2. Piezometric measurements indicated that groundwater within the ridge was under hydrostatic pressure conditions.

In-situ hydraulic conductivity testing has not been conducted at the mill site. However, bedrock hydraulic conductivity is likely to be similar to that measured in the adjacent open pit area, typically less than 1×10^{-5} cm/s. Fractured high hydraulic conductivity bedrock zones identified in the open pit area are also likely to be present at the mill site.

2.1.6 Tailings Storage Area

The tailings storage area is located south of the Mt. Polley ridge, in a relatively flat topographic area located within the Northeast Edney Creek watershed. A small pond and two swampy areas exist within the tailings storage area. Surface discharges from these areas are ephemeral and are considered to be the result of groundwater discharges.

Subsurface stratum at the site consists of a 5 to 30 metre thick veneer of dense grey glacial till that is underlain by a glaciofluvial/alluvial deposit at the bottom of the catchment. The glacial till is locally overlain by wet organic rich deposits in localized topographic lows. Bedrock consists of a volcanic conglomerate which is heavily fractured and weathered. This unit becomes harder and more competent with depth and is underlain by a competent basalt. Some sedimentary sequences were identified in the conglomerates along the east ridge of the tailings basin.

The hydrogeology of the tailings storage area has been previously evaluated and it was determined that the tailings area groundwater table is sub-parallel to the surface topography, with groundwater flows directed northeast towards Northeast Edney Creek Tributary, as shown on Figure 2.3. Groundwater flows occurred predominantly in the sandy



Association g des Ingénieurs-Conseils du Canada - 8 -

1624/2

X

June 3, 1996 INVESTIGATION KP 1-11 191 of 500 glaciofluvial/alluvial deposit and at the bedrock contact. A slight upward gradient was encountered in the lower topographic areas.

In-situ hydraulic conductivity measurements have been obtained for both the overburden and bedrock strata. Bedrock hydraulic conductivities were found to range from 9 x 10^{-8} cm/s to 5 x 10^{-4} cm/s, with a geometric mean of 4 x 10^{-6} cm/s. The lower values were measured in competent bedrock, while the higher values were associated with highly fractured rock. In addition, hydraulic conductivities generally decreased with depth as weathering and fracturing diminish. Falling head hydraulic conductivities ranging from 1 x 10^{-6} to 2 x 10^{-5} cm/s were measured. A mean in-situ hydraulic conductivity of 9 x 10^{-6} cm/s was obtained for the grey surficial till. Samples of this material were also tested with an air entry permeameter, which produced a hydraulic conductivity of 2 x 10^{-8} cm/s.

2.2 1989 MONITORING WELL PROGRAM

A total of nine (9) groundwater monitoring wells were installed in selected NQ diamond drillholes during the 1989 investigations by Knight Piésold, as shown on Figure 2.4. Three of the wells (MP-89-107, MP-89-146 and MP-89-151) were installed in the open pit area and the remaining six wells (MP-89-231, MP-89-232, MP-89-233, MP-89-234, MP-89-235 and MP-89-236) were installed at the tailings area. The 1989 monitoring wells were not constructed in complete accordance to current industry procedures. The wells consisted of 40 mm PVC well pipe with screened sections constructed with a hacksaw that extend from approximately 3 metres below ground surface to the end of the well string. In the tailings storage area, the monitoring wells range in depth from 15 to 40 metres. Bentonite seals were installed below the well string and at the ground surface. Natural sand backfill was placed around the screened interval (Appendix B). The three open pit wells were extended the full length of the exploration drill holes, approximately 150 metres, and seals were not installed below the well string for these installations. The surface seals consist of a 1 metre concrete plug overlain by two metres of bentonite that was installed just below the bedrock surface.



Association des Ingénieurs-Conseils du Canada 1624/2

June 3, 1996 INVESTIGATION KP 1-11 192 of 500 One set of groundwater quality samples was collected in 1989 from all nine recently installed wells. In the spring of 1990, a second sample set was obtained from the three open pit wells. Sampling of the installations stopped in 1990 and resumed again in January, 1995. Deep snow cover and unmarked monitoring well locations limited the water quality sampling to only two wells (MP89-234, MP89-236) and water levels were limited to three locations (MP89-232, MP89-234, MP89-236). Wells MP89-234 and MP89-236 exhibited artesian conditions and had a static groundwater table of approximately 15 cm above the existing ground surface. The third well MP89-232 was found to have a water table located at the surface.

2.3 1995 MONITORING WELL PROGRAM

In August, 1995 seven additional groundwater wells (R-95-1 to R-95-7) were installed in the vicinity of the open pits and mill site (Figure 2.4). The wells were constructed with 110 mm PVC well pipe in 150 mm holes advanced with air rotary drilling methods. Well casings were installed over the full length of the holes, which ranged from 80 to 170 metres. Screened zones were installed at various levels, where high recharge was encountered during drilling (Appendix B). The well casings were sealed in accordance with standard BC water well practices.

During the Knight Piésold site inspection in September, 1995, water quality samples were collected from all 1995 wells (R-95-1 to R-95-7). The sampling was conducted in part to supply additional background groundwater data and in part to determine the sampling requirements that will be required for the Mt. Polley Project Groundwater Monitoring Program.

During the 1995 site visit, no existing users of either groundwater resource were identified with the exception of the anticipated future use of the fractured bedrock aquifers by the mine for make-up and potable water supply.

Drilling records produced by the well drillers for the open pit area (Appendix C) indicate fractured bedrock zones were encountered at various depths and that these



1624/2

June 3, 1996 INVESTIGATION KP 1-11 193 of 500

Knight Piésold Ltd.

CONSULTING ENGINEERS

zones were the primary sources of groundwater in each well. Groundwater levels measured in wells 95-R-1 and 95-R-7 in September, 1995, indicate the groundwater table is relatively shallow, occurring at depths of 12 to 19 metres. These depths are within several metres of the projected 1991 groundwater contour plan provided on Figure 2.3. The drilling information from the 1995 investigation has therefore reaffirmed the earlier work done in the report, "Mount Polley Project, Stage I Environmental and Socio-Economic Impact Assessment, January 1991".



Association des Ingénieurs-Conseils du Canada 1624/2

June 3, 1996 INVESTIGATION KP 1-11 194 of 500 Knight Piésold Ltd.

CONSULTING ENGINEERS

SECTION 3.0 - GROUNDWATER IMPACTS

3.1 MILL SITE AREA

3.1.1 Baseline

Mining hydrogeology is a complex process and is difficult to model since it has to deal with natural systems after they have been disturbed by mining processes. As a result, there will always be large uncertainties when reporting the results for mine hydrology studies. In general, the average volume of deep percolation to the groundwater table is a portion of the average annual precipitation (Brown, 1988). Recorded precipitation data for the site is limited and precipitation records for climatologically similar stations in the Mt. Polley area have therefore been used to estimate a mean annual site precipitation of 755 mm and a mean annual evaporation of 423 mm. Using these numbers it has been suggested by Brown that for medium precipitation (0.5-1.5 m/y) and low evaporation (0-0.5 m/y), a 25 percent portion be used to estimate the annual recharge contribution to the groundwater system.

As a result, 25 percent of the annual precipitation has been used to calculate baseline groundwater recharge rates at the proposed open pits, waste dumps, overburden stockpiles, and the mill site as shown on Table 3.1. Using this value, existing groundwater recharge at the proposed open pit area range from 0.0007 to 0.0034 m³/s with dilution ratios ranging from 22 to 273. Typical recharge rates at the proposed waste dump areas range from 0.0002 to 0.0075 m³/s with dilution ratios of 27 to 296. Typical recharge rates at the proposed mill site area range from 0.0005 to 0.0007 m³/s with dilution ratios of 106 to 392. Finally typical recharge rates at the proposed overburden stockpile areas range from 0.0004 to 0.0009 m³/s with dilution ratios ranging from 211 to 231.



Association des Ingénieurs-Conseils du Canada 1624/2

June 3, 1996 INVESTIGATION KP 1-11 195 of 500

Knight Piésold Ltd.

As shown on Figure 3.1, the groundwater table on the Mt Polley ridge is shallow and runs parallel to surface topography. The watershed/ groundwater divide is centred near the Mt Polley summit.

To date, baseline groundwater quality for wells 95-R-1 to 95-R-7 meet the 1994 BC Environmental Potable Water Criteria with the exception of iron in 95-R-5, 95-R-6 and 95-R-7 and manganese in 95-R-5, and 95-R-7 (shown in Appendix D). Baseline groundwater quality generally exceeds the 1994 British Columbia Environmental Aquatic Life Criteria for several total metals (aluminium, cadmium, chromium, copper, iron, lead, selenium, silver and zinc).

3.1.2 Operational

As shown on Figure 3.2, the groundwater seepage into the open pits will result in the establishment of a watershed/groundwater divide centred around the open pits. Precipitation infiltration and runoff occurring within this watershed will be collected as either groundwater seepage or surface runoff by the pit sump and added to the mill circuit process system. The divide will gradually increase in extent as the pits are developed to deeper depths and groundwater seepage gradients into the pits will be maximized. Groundwater flows to the various watersheds are expected to be reduced by an average flow of 15 l/s.

In addition, pumping water from the groundwater supply wells will also result in a reduction of groundwater flow into the Polley and Bootjack Lakes and will cause drawdown of the water table. The flow reduction resulting from the pumping has not been quantified, but Table 3.2 indicates the potential maximum rates and average annual recharge quantities. These maximum pumping rates are not safe yields, however, and pumping at these rates may result in depletion of stored water within the fractured unconfined aquifers. The net result will be a reduction in the groundwater table around



Association des Ingénieurs-Conseils du Canada 1624/2

June 3, 1996 INVESTIGATION KP 1-11 196 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

the mine site area. The maximum pumping rates may decrease with time until the pumping rate equals the recharge rate of the local system.

As a result, the overall impact to the Bootjack and Polley Lake watersheds due to mine development will be a slight decrease in groundwater flows relative to the baseline flows as groundwater will be collected in the open pit and in the recently installed groundwater pumping wells. Ongoing infiltration of precipitation during mine operations may result in slight modifications to groundwater chemistry, particularly for higher nitrogen levels due to flushing of blasting residues from the waste dumps. However, some of these infiltrating waters will be recovered in the open pit and pumping well systems. No adverse groundwater chemistry impacts are projected for the open pit development during operations as unaffected groundwater will flow into the excavation rather than affected groundwater flowing out of the excavation.

The downstream water quality impacts due to groundwater affected by the mine development are projected to be insignificant. Groundwater quality is not expected to be significantly degraded, and may actually be improved due to open pit dewatering practices. Also, the receiving water bodies will provide extensive dilution which is projected to be better than for the baseline conditions presented on Table 3.1 which are due to the interception and recycling of all the open pit infiltration and a significant proportion of the waste dumps infiltration.

3.1.3 Post-Closure

After mine closure, each pit will be permitted to flood. It is anticipated that the ultimate pit water level will be approximately 1090 metres, based upon the lowest pit wall elevation in the west corner of the West Pit and the existing shallow groundwater table. During spring runoff conditions and wet periods it is possible that surface water may runoff from the pits into Bootjack Lake watershed. Based upon average precipitation and



Association des Ingénieurs-Conseils du Canada 1624/2

June 3, 1996 INVESTIGATION KP 1-11 197 of 500

Knight Piésold Ltd.

groundwater recharge rates, it is estimated that this may commence about 50 years after closure. The post-closure flow paths to Bootjack and Polley Lakes are expected to return back to the baseline flow paths once pit flooding is complete (Figure 3.3). As flooding progresses, the groundwater divide formed around the pits will be reduced in size. The final configuration will be dependent upon localized geological conditions such as the hydraulic conductivity, heterogeneity, anisotropy and orientation of the fractured zones.

3.2 TAILINGS STORAGE AREA

3.2.1 Baseline

At the tailings area, the baseline groundwater quality is poor. Aluminium, arsenic, cadmium, chromium, copper, iron, lead, mercury, nickel, silver and zinc are generally not in compliance with the 1994 British Columbia Environmental Aquatic Life Criteria (Appendix D).

3.2.2 Operational

The construction of the tailings storage facility will modify the existing groundwater flow quantities and direction. The construction of the embankment will eventually result in the formation of hydraulic gradients and seepage flows into the Hazeltine Creek, Southwest Edney Creek and the Northeast Edney Creek watersheds. In addition to this, all surface water in the upper reaches of the Northeast Edney Creek watershed will be retained in the tailings storage facility instead of recharging the Northeast Edney Creek Tributary.

Groundwater seepage flows at the tailings storage facility have been calculated using a conventional Darcy seepage model. To calculate these groundwater seepage flows and their corresponding dilution ratios for the surrounding three watersheds three assumptions have been made. First, it



n Association ting des Ingénieurs-Conseils a du Canada 1624/2

June 3, 1996 INVESTIGATION KP 1-11 198 of 500

has been assumed that the seepage through the dam will remain constant throughout the year (steady state flow). Secondly, it assumes average monthly flow conditions in the surrounding creeks. Finally, it is assumed that no loss of solute will occur in the flow system (steady state solute transport). The dam seepage has been calculated using the SEEP/W finite element modelling program as part of the water balance analysis included in "Report on Project Water Management, Ref. No. 1624/1". As shown in Table 3.3, a conservative estimate of dilution ratios are presented and they range from 15 to 244 for the various watersheds.

3.2.3 Post-Closure

Groundwater conditions around the tailings storage facility will be permanently changed from the baseline conditions due to the new topographic high point of the tailings storage facility. Groundwater flow from the tailings storage facility will flow into all of the three adjacent watersheds. It is anticipated, however, that as tailings consolidation occurs, groundwater quality from the tailings impoundment will improve to levels from the tailings around the tailings impoundment will improve to levelsbetter than baseline values.

Surface water conditions will also be permanently changed. The surface water from the upper reaches of the Northeast Edney Creek watershed will be detained in the tailings storage facility and will be released by a spillway, installed at closure, into the Southwest Edney Creek Tributary. As a result, the flows along the Northeast Edney Creek Tributary will be permanently reduced and these surface flows will be redirected into the Southwest Edney Creek Tributary.



Association g des Ingénieurs Conseits du Canada 1624/2

June 3, 1996 INVESTIGATION KP 1-11 199 of 500

SECTION 4.0 - GROUNDWATER MONITORING PROGRAM

In response to MELP requests, a site inspection of the Mt. Polley Project was conducted by Mr. David Machin September 20 to 22, 1995. Mr. Machin is a registered Professional Engineer (Ontario) who specializes in hydrogeology, geology and environmental engineering. While on site, Mr. Machin reviewed the existing groundwater monitoring installations and collected water quality samples from all accessible installations.

The groundwater regime at the Mt. Polley site results from infiltration of precipitation through the ground surface into the underlying overburden and bedrock strata. Infiltration migrates through the pore spaces in the overburden and through joints/fractures in the bedrock and flows downgradient to topographic depressions. Infiltration at the site occurs predominately on the Mt. Polley ridge (the recharge zone) with discharge of the infiltrated water into Bootjack and Polley Lakes, as well as ephemeral stream courses. Hydrogeological impacts resulting from development of the Mt. Polley Project will likely consist of modification of the existing groundwater tables and infiltration rates. The potential exists for the modification of groundwater quality as either a direct result of mine activities or as a result of the modified infiltration rates.

The groundwater quality monitoring program will include sampling conducted by Imperial Metals Corporation on a quarterly basis during 1996 prior to the start of mining activities. The samples collected from the existing groundwater wells will be used to establish baseline water quality. During operations, quarterly sampling is recommended. Sampling will be conducted in mid-fall and mid-spring in order to obtain flows during high precipitation or recharge periods and in late summer and winter to obtain groundwater flow conditions during low precipitation or discharge periods. At closure the groundwater monitoring program will be continued on a quarterly basis for a minimum period of two years. At this point, the results of the two year monitoring period will be reviewed and the program will be modified as required. A proposed sampling schedule is provided on Figure 4.1.



Association g des Ingénieurs Conseils du Canada 1624/2

June 3, 1996 INVESTIGATION KP 1-11 200 of 500

Knight Piésold Ltd.

CONSULTING ENGINEERS

Current mine plans entail the development of only the southeast waste dump. The two proposed monitoring wells, P_6 and P_7 , will therefore not be constructed downgradient of the north waste dump until later in the mine life when the north waste dump is to be constructed. The monitoring wells will be constructed in accordance with the procedures outlined in the "Groundwater Quality Monitoring Manual" and equipped with dedicated inertia lift devices. The proposed location for each installation is shown on Figure 2.4.

A detailed description of the monitoring protocol that will be utilized during groundwater sampling and data collection is provided in Appendix A. The protocol provides a consistent methodology that permits the temporal comparison of data and helps to minimize the occurrence of erroneous data. Groundwater sampling and data collection will be conducted by an individual who has been trained in environmental procedures and the sample and preservation procedures will be strictly followed.

During mining operations and for 2 years after closure, groundwater conditions will be monitored in the mill site area from the groundwater sump located within the pit and from water supply wells 95-R-1, 95-R-4 and 95-R-7. Water well 95-R-3 was to be included in the monitoring program, but due to blockage in the completed well at a depth of 50 metres it has been omitted from the program. Wells MP89-107, MP89-146, and MP89-151 are being used for baseline groundwater monitoring but they will likely be destroyed during pit stripping operations. No replacement wells are proposed at the mill site area because it is believed that the 1995 water supply wells will provide adequate coverage of the three 1989 wells that will be lost in the open pit area.

During mining operations and for 2 years after closure, two background groundwater monitoring wells will exist in the mill site area (95-R-5 and 95-R-6). Well 95-R-5 is located on the east side of the Mt. Polley ridge in an area that is not downgradient of either the waste dumps or the open pits. Well 95-R-6 is located on the southwest corner of Mt. Polley in the projected Polley Lake groundwater recharge zone. This portion of the Polley Lake watershed will not be impacted by



Association des Ingénieurs-Conseils du Canada 1624/2

mining activities, except for the possibility of the shifting of the Polley and Bootjack Lake groundwater as a result of groundwater seepage into the open pits (Figure 3.2). Should the groundwater divide shift sufficiently that 95-R-6 is contained within the Bootjack Lake watershed, it will still remain upgradient of any impact zones. These two wells will therefore give additional information to the baseline groundwater quality established prior to construction in that they will help show the natural fluctuations of the baseline values throughout the operation of the mine life. Therefore during mining operations, baseline and background water quality data will be compared with values obtained from water wells 95-R-1, 95-R-4 and 95-R-7. If water quality levels indicate significant deviations from the baseline values and background wells 95-R-5 and 95-R-6 have remained constant over the time period in question, then further monitoring wells will be installed as appropriate to investigate any potential groundwater impacts.

During mining operations and for 2 years after closure, groundwater conditions will also be monitored in the tailings storage area. Monitoring will initially consist of the existing 1989 wells and three replacement wells, P_1 1996, P_2 1996, P_3 1996, which will be installed in 1996 as shown on Figure 2.4. (It is anticipated that MP89-232 and MP89-235 will be lost during the construction and early operations of the facility.) Wells MP89-231, MP89-233 and MP89-234 are located immediately outside the perimeter of the facility and every effort will be made to preserve them. In addition to all this, well P_4 will be installed at a later date when the tailings pond elevation will rise high enough to cause potential seepage into the Southwest Edney Creek Tributary.

During mining operations and for 2 years after closure, MP89-236 will be used as a background groundwater monitoring well. MP89-236 is located upgradient of the tailings storage facility, as evident by the artesian conditions observed during the September, 1995 site visit. This well intercepts groundwater flows from the recharge zone located near the watershed divide positioned to the north. MP89-236 will be lost during the later stages of the mine life due to the filling of the tailings storage facility. When this occurs, the well will be replaced with a new background well, P_5 , constructed further upgradient of the tailings storage facility



Association g des Ingénieurs Conseils du Canada 1624/2

June 3, 1996 INVESTIGATION KP 1-11 202 of 500

Knight Piésold Ltd.

as shown in Figure 2.4. As at the mill site area, the tailings storage area background well MP89-236 along with the established baseline values for the area will be used to detect any potential groundwater impacts. If water quality levels indicate significant deviations from the baseline values and the background well MP89-236 has remained constant over the time period in question, then further monitoring wells will be installed as appropriate to investigate any potential groundwater impacts.

During the September, 1995 site visit it was discovered that wells MP89-233 and MP89-234 had been damaged. The stick-up at MP89-233 was broken off below the ground surface with no visual indication of the well location. This site is considered to be lost for future data collection. The stick-up of MP89-234 was also broken off, apparently during clearing operations along the main embankment foundation. The well did however, retain a stick-up of approximately 15 cm, which will permit the repair of the installation for continued monitoring. Well MP89-236 will also require minor repair work. The stick-up, which is broken off several centimetres above the ground surface, must be extended and a steel protective casing must be installed. All of the above mentioned monitoring wells will be installed in accordance to the procedures provided by MELP and will be equipped with dedicated inertia lift devices.

To eliminate the possibility of cross-contamination between monitoring wells and to permit the use of in-line filtering systems during the collection of dissolved metal samples, all of the remaining 1989 wells will each be supplied with a dedicated inertia lift pump system. For each of the 1995 wells and 1996 proposed replacement wells, a dedicated submersible pump to preventing cross-contamination will be installed. For the submersible pumps, a sampling port will be provided at the well head to eliminate possible contamination by a water distribution pipe network.

When taking water samples the screened interval of the well will be significant but the method in which the wells were completed (more than one screened interval per well) will not be considered adverse since the purpose of the groundwater



Association des Ingénieurs-Conseils du Canada 1624/2

June 3, 1996 INVESTIGATION KP 1-11 203 of 500

Knight Piésold Ltd.

monitoring is to detect process impacts upon the environment. Due to the anticipated local depression of the groundwater table around the open pit, the long screen length will become beneficial because the impacted wells will continue to provide groundwater data at consistent reference points. If contaminants are detected or suspected in a well, it will be possible to determine which permeable bedrock aquifer is affected by using very low flow rate sampling, with the sampler intake set at the middle of the screened interval in question. This method will obtain a sample representative of the screened interval and not a composite sample of the entire well casing.



Association des Ingénieurs-Conseils du Canada 1624/2

June 3, 1996 INVESTIGATION KP 1-11 204 of 500

Knight Piésold Ltd.

SECTION 5.0 - SUMMARY AND CONCLUSIONS

This report presents the current understanding of the Mt. Polley Project site hydrogeological conditions and the anticipated impacts that will result from the project development. The Groundwater Monitoring Program has been designed on this basis and will fulfil the following objectives:

- Provide data for the establishing baseline groundwater quality levels.
- Detect groundwater contamination and identify the potential source.
- Estimate baseline groundwater flows and dilution ratios in receiving surface water bodies.

Existing monitoring facilities are adequate for the establishment of a baseline groundwater database and will be used to evaluate potential impacts on the groundwater system during mining operations. Additional monitoring installations will be required only at the tailings storage facility where three groundwater monitoring wells will be constructed in full accordance of the MELP groundwater monitoring procedures. If the North waste dump is constructed at a later date, downgradient wells will be installed by Imperial Metals Corporation at that later time.

Imperial Metals Corporation proposes to conduct a groundwater monitoring schedule as provided on Figure 4.1. This schedule can be adjusted as deemed necessary by both Imperial Metals Corporation and governing agencies. As indicated on the groundwater monitoring schedule, the data collected will be summarized and evaluated on an annual basis and a report will be submitted to the government agencies for review. The annual report will contain recommendations for the improvement of the Groundwater Monitoring Program, which will be adjusted to suit specific site conditions or to address any concerns that may be identified in the future.



Association des Ingénieurs-Conseils du Canada - 22 -

1624/2

June 3, 1996 INVESTIGATION KP 1-11 205 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

SECTION 6.0 - REFERENCES

Brown, A., "Groundwater Evaluation and Control for Gold Mining Projects," Second International Conference on Gold Mining, ed. C.O. Brawner (Littleton, Colorado: Society of Mining Engineers, 1988), pp. 219-233.



Association des Ingénieurs-Conseils du Canada 1624/2

June 3, 1996 INVESTIGATION KP 1-11 206 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

TABLE 3.1

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

ESTIMATED BASELINE GROUNDWATER FLOWS AND DILUTION RATIOS OPEN PITS, WASTE DUMPS, OVERBURDEN STOCKPILES AND MILL SITE

J:UOB\DATA\1624\WATERBAL\TABLE.XI	٤			Last Revision :	29-May-96
Precipitation (mm/yr) = Evaporation (mm/yr) = Infiltration as a % of Precipitation	755 432 0n = 25				
Watershed	Proposed Mining Component	Catchment Area (ha)	Watershed Average Annual Flows (m ³ /s)	Average Groundwater Flows (m ³ /s)	Dilution Ratio (1) (m ³ /s)
Polley Lake Watershed (Hazeltine Creek Weir)	North Waste Dump Area Southeast Waste Dump Area Overburden Stockpile Areas Open Pit Areas Mill Site Area	24.5 132.5 14.4 12.2 8.5	0.1995 0.1995 0.1995 0.1995 0.1995 0.1995	0.00147 0.00793 0.00086 0.00073 0.00051	136 25 231 273 392
Bootjack Lake Watershed (Morehead Creek Weir)	TOTAL Southeast Waste Dump Area Overburden Stockpile Areas Open Pit Areas Mill Site Area TOTAL	192.1 4.2 5.9 57 11.7 78.8	0.1995 0.0744 0.0744 0.0744 0.0744 0.0744 0.0744	0.01150 0.00025 0.00035 0.00341 0.00070 0.00472	17 296 211 22 106 16
6K Creek Watershed (6K Creek)	North Waste Dump Area	3.2	0.0493	0.00019	257

Notes:

1) Dilution Ratio = Watershed Average Annual Flow / Average Groundwater Flow; For existing (baseline) conditions.

2) Average Groundwater Flows = 25% Precipitation * Catchment Area / (31536000 sec/year)

Knight Piésold Ltd.

TABLE 3.2

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

PROJECTED GROUNDWATER PRODUCTION FROM 1995 WELLS

J:\JOB\DATA\1624\WATERBAL\TABLE.XLS

Last Revision : 17-May-96

		Well Identification No.				
		95-R-1	95-R-2 & 95-R-7	95-R-4	95-R-5	95-R-6
OUTFLOWS	Maximum Pump Rate, m ³ /hr	10.36	67.37	33.28	1.09	1.91
	Annual Volume Pumped, m ³	90,754	590,161	291,533	9,548	16,732
INFLOWS	Recharge Area, m ²	126000	283000	283000	80000	31500
	Annual Precipitation, mm	755	755	755	755	755
	Infiltration coefficient	25	25	25	25	25
	Annual Recharge, m ³	23,783	53,416	53,416	15,100	5,946
NET DIFFERENCE (1)	m ³	(66,971)	(536,745)	(238,117)	5,552	(10,786)

Note:

1) Net difference = Annual Volume Pumped - Annual Recharge.

Knight Piésold Ltd. CONSULTING ENGINEERS

TABLE 3.3

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

ESTIMATED BASELINE GROUNDWATER FLOWS AND DILUTION RATIOS TAILINGS STORAGE AREA

J:\JOB\DATA\1624\WATERBAL\TABLE.	XLS	Last Revision :	17-May-96
Watershed	Seepage Flow Through Dam Structure (1) (m ³ /s)	Average Annual Weir Flow (m ³ /s)	Dilution Ratio
Hazeltine Creek	0.00210	0.1995	95
Northeast Edney Creek	0.00218	0.0317	15
Southwest Edney Creek (2)	0.00013	0.0317	244

Notes:

- Seepage through Dam structures has been obtained from Case 2, Table 7.2 of the Knight Piesold Design Report 1625/1. Case 2 assumes the permeability of the foundation glacial till = 1x10⁻⁶ cm/sec.
- 2) Flows for the Southwest Edney Creek are unavailable. Dilution ratios have been calculated assuming similar flows to Northeast Edney Creek Tributary.















INVESTIGATION KP 1-11 216 of 500






IMPERIAL METALS CORPORATION MT. POLLEY PROJECT GROUNDWATER MONITORING SCHEDULE

nstallation	Monitoring	Pre- Establ	mining M ishment of	onitorin f Baselír	g for ne Data		Constructio	on									Min	ing)j	Post-m	ining M	onitoring			
No.	Sites		199	96			1997				19	998		-	1	999			2000	2007		20	08		1	2	909			20	10		2
		JIFM	AMJ	JAS	OND	JIM	AMJJ	AS	OND	JFN	I A M J	JAS	OND	J F M	A M J	JAS	OND	JFM	AMJJ	OND	JFN	AMJ	JAS	ONI	J FIM	AMJ	JAS	ONI	JFN	AMJ	JAS	0 N I	D 1
93-R-1	Mull Sile, Open Pits								100		E		-		111	1 100	-	100	100	REIL	100						600	-	100			103	
95-R-7	Mill Site, Waste Dump		圓		<u></u>	圓		圓	1	圓		1	圓		<u></u>	圓	圓		圓	圓	圓	圓		圓			目	目	<u> </u>	1		10	
95-R-4	Open Pits			圓			B	1									题	翻	調	100	100						圓	圓	圓	圖	1		
MP89-107	Open Pits			國	圓		Assumed I	ost															11									11	
MP89-146	Open Pits		1	目間	圓	100	Assumed I	teo																11									
MP89-151	Open Pits		1			圜	Assumed I	ost					1 k											3		11							
P ₆	Waste Dump							11												100							1	圓	1	1	100	團	T
Pγ	Waste Dump								1		6 5								1111	100								1	1			100	T
MP89-231	Tailogs Storage Area	11	100	M	10	100	Assumed 1	ost	T		111		11			HI	11	11	1111		11				1					T		T	T
MP89-232	Tailings Storage Area		1	100	100	155	Assumed 1	ost														111			-			-				-	T
MP89-234	Tailings Storage Area		8	1	8		M	100	10	100		100	1	-	100	100	100	100	80	EC.	-	HT21					100	1	100	100	100	1000	+
MP89-235	Tailings Storage Area		-		8	100	Assumed I	ost	100				1					-		100	-	E CON					100	1	100	-		1	+
P 1006	Tailings Storage Area			No.		1		THE OWNER	1909	100		100	1	100	100	NOT.	100	1 Martin		BIRE	-	100	-	Dest.		-	100	-				100	+
n 1004	Taillings Storage Area			- 6	-			-0	1000	100		200	100	-	-		ALC: NO	1000	88	-	803	-		- Hell	-		800	-				and a	
P1 1990	Tanings Storage Area			100	100		8	-	-			100	-	100	-		100	100	-	100	RIS	BER		100	1 =	-	103	-			80	89	-
P ₃ 1990	Tailings Storage Area				100		- B	1	<u> </u>		-	B	-		102	<u>B</u>	100	100	1	22	322	101		- E				-8	日間	間	 	1	-
05.12.5	Packground	1 2 1	100	No.	100	100	100	100	100	101		100	1		80		100	TOD	1	100	ALC: NO	- Mart -		100	100		100			100	100	and a	+
06.0.4	Dackground		-	100	100	101			-	-8-	-	100	-	100	200		-	1	101		100			-				-	18	-		105	
93-R-0	Background	41	8	100	-			8	-	8			2		1020		-		101	100	88	圖	開	-	83	-	100	-	1	開	-	102	
MP89-236	Background		-	1	-	555		-				100	-	-		間	题		圓							11							-
P ₅	Background	44									1.1										101		1	B	圆				圓	目	100		1
	Review of yearly data							14	200																		13						
5	annoal report																						13	0	80 I								
																								011				1.1					
	Review of post- mining									11	DI II		11												10.0								
	data and monitoring									1 8	1 8 1																					TT	T
	program adjustment													11												3		11					100

17

Knight Piésold Ltd. CONSULTING ENGINEERS

APPENDIX A

MANUAL ON SAMPLING AND HANDLING GUIDELINES FOR DETERMINATION OF GROUNDWATER QUALITY



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 221 of 500

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

MANUAL ON SAMPLING AND HANDLING GUIDELINES FOR DETERMINATION OF GROUNDWATER QUALITY (REF. NO. 1625/5)

MAY 19, 1995

Suite 1400 750 West Pender Street Vancouver, British Columbia Canada V6C 2T8 Telephone (604) 685-0543 Telefax (604) 685-0147 CIS: 72360,477

Knight Piésold Ltd. CONSULTING ENGINEERS

INVESTIGATION KP 1-11 222 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

MANUAL ON SAMPLING AND HANDLING GUIDELINES FOR DETERMINATION OF GROUNDWATER QUALITY (REF. NO. 1625/5)

TABLE OF CONTENTS

PAGE

SECTION 1.0	INTR	ODUCTIO	ON	1
SECTION 2.0	EQU	IPMENT		2
	2.1	LIST		2
		2.1.1	Sample Collection	2
		2.1.2	Sample Preparation	3
			and Preservation	
		2.1.3	Sample Shipment	3
	2.2	MAINT	ENANCE AND STORAGE	3
SECTION 3.0	SAM	PLE COL	LECTION	4
	3.1	STEP 1	- PREPARE FOR SAMPLING	4
	3.2	STEP 2	- DETERMINE GROUNDWATER	4
		LEVEL	AND WELL VOLUME	
	3.3	STEP 3	- PURGE WELL	5
	3.4	STEP 4	- MEASURE FIELD PARAMETERS	5
	3.5	STEP 5	- COLLECT SAMPLES	6
	3.6	STEP 6	- FILTRATION OF SAMPLES	6
	3.7	STEP 7	- PRESERVE SAMPLES	7



Association des Ingénieurs-Conseils du Canada - i -

1625/5

May 19, 1995

Knight Piésold Ltd.

SECTION 4.0

CONSULTING ENGINEERS

3.8	STEP 8	- SHIP SAMPLES TO	8				
	LABOR	ATORY					
	3.8.1	Sample Labels	8				
	3.8.2	Packing	8				
	3.8.3	Chain-of-Custody Record	8				
QUA	LITY CO	NTROL AND DATA REVIEW	10				
4.1	INTRODUCTION						
4.2	FIELD PARAMETERS						
4.3	PRELIMINARY DATA REVIEW						
4.4	ANNUA	AL WELL EVALUATION	10				

TABLES

Table 3.1 Sampling and Preservation Procedures for Groundwater Monitoring

APPENDICES

Appendix A Record Sheets

Association of Consulting Engineers of Canada

Association des Ingénieurs-Conseils du Canada - ii -

1625/5

May 19, 1995

INVESTIGATION KP 1-11 224 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

MANUAL ON SAMPLING AND HANDLING GUIDELINES FOR DETERMINATION OF GROUNDWATER QUALITY (REF. NO. 1625/5)

SECTION 1.0 - INTRODUCTION

This document presents the groundwater sampling procedures recommended for the monitoring wells at the Mt. Polley Project. The plan sets out numerous guidelines, but specific procedures, data sheets and management techniques may be refined by the staff members responsible for sampling. The objective is to standardize procedures and techniques for sample collection, preservation and shipment, thereby ensuring that incidental errors are not introduced and allowing for continued comparison of results with on-going sampling.



Association des Ingénieurs-Conseils du Canada - 1 -

Knight Piésold Ltd. CONSULTING ENGINEERS

SECTION 2.0 - EQUIPMENT

2.1 <u>LIST</u>

Equipment required for sampling, preparation and preservation of samples and shipment to laboratory is outlined below:

- 2.1.1 Sample Collection
 - Tarp to lay down around well, used to keep all equipment clean.
 - Plastic coated water level probe with incremental depth markings.
 - Measuring tape.
 - Wash bath of about 2 3 l size for decontaminating the water level probe.
 - Disposable latex gloves.
 - Deionized water (2 3 | for each well).
 - Well log with monitoring well completion diagram.
 - Data forms for documenting the sampling details.
 - Appropriate sampling bottles (2 1 l, 1 500 ml, 2 250 ml for each well).
 - Commercially purchased bailer for 2 inch monitoring wells, which can be disassembled for decontamination, or disposable bailers to be dedicated to each well.
 - Non-contaminating bailer line (e.g. fishing line, stainless steel or teflon-coated stainless steel) of sufficient strength to prevent breakage.
 - Bailer retrieval system such as fishing reel or down rigger.
 - Volumetric measurement devices (e.g. 20 l bucket and 1 l graduated cylinder).
 - Indelible marker.
 - Wash bottle.
 - Large brush for cleaning inside and outside of bailer.
 - Clean rags.



Knight	Piéso	old	Ltd.
CONS	SULTING	ENG	INEERS

-

- Paper towels.

Clipboard or binder for sampling forms.



Knight Piésold Ltd. CONSULTING ENGINEERS

2.1.2 Sample Preparation and Preservation

- Deionized water.
- Spare sample bottles.
- Wash bottles.
- Paper towels.
- Disposable latex gloves.
- Protective eye glasses.
- Vacuum filtration apparatus.
- 0.45 micron filter papers.
- Tweezers.
- Nitric acid (HNO₃) and pipettes (2 ml required in each of three bottles per well). Concentration is 15 normal.
- NaOH pellets (provided by laboratory in total cyanide sample bottle).

2.1.3 Sample Shipment

- Cooler for shipping samples.
- Tape for sealing sample bottles and cooler.
- Indelible marker and address labels.
- Max-min thermometer.

2.2 MAINTENANCE AND STORAGE

Procedures for handling and storage of sampling equipment should be consistent with those for analytical laboratories. For example:

- Equipment should be stored in sealed containers in a clean room dedicated to sampling.
- Equipment should be repaired or replaced if it is malfunctioning.

1625/5 May 19, 1995



Association des Ingénieurs-Conseils du Canada

Knight Piésold Ltd. CONSULTING ENGINEERS

-

- Equipment should be transported to the sampling site in sealed containers.
- Equipment should be cleaned with deionized water between collecting each sample.



Association des Ingénieurs-Conseils du Canada - 5 -

1625/5 May 19, 1995

÷.

Knight Piésold Ltd. CONSULTING ENGINEERS

SECTION 3.0 - SAMPLE COLLECTION

3.1 STEP 1 - PREPARE FOR SAMPLING

Wear a fresh pair of disposable latex gloves throughout the sampling process.

Prior to taking any measurements or samples, sample bottles and identification labels should be prepared. The bailer should be checked for any leaks or weaknesses. Equipment such as the water level probe and field parameter metres should be tested. Also, all pertinent information must be documented in the upper portion of the field sampling record sheet, an example of which is included in Appendix A.

Table 3.1 gives details of the groundwater samples to be collected from each well, including the sample size and preservative required. The procedures involved are described in Steps 2 and 8 below.

3.2 <u>STEP 2 - DETERMINE GROUNDWATER LEVEL AND WELL</u> <u>VOLUME</u>

- Immerse tip of the water level probe in water to confirm that it is operating.
- Check that the tape length is correct.
- Decontaminate the water level probe by rinsing it in a deionized water bath.
- Measure the depth to water from the top of the PVC to within at least 0.01 m.
- Measure the total depth of the well from the top of the PVC to within at least 0.01 m.
- Calculate the volume of the water column in the well.
- Fill in section on sampling record sheet titled "Groundwater Level and Well Volume".



Knight Piésold Ltd. CONSULTING ENGINEERS

3.3 STEP 3 - PURGE WELL

The water standing in a well prior to sampling is not representative of in-situ groundwater quality and must be removed (the well purged), so that formation water can replace the stagnant water.

The steps for purging the well include:

- Rinse tubes, bailer line and anything else lowered into the well with deionized water to prevent cross-contamination.
- Gently bail three well volumes from the well.
- Dispose of the purged water in an environmentally acceptable manner.
- Fill in section on sampling sheet titled "Well Purging".

3.4 STEP 4 - MEASURE FIELD PARAMETERS

Near the end of the well purging, the field parameters (temperature, conductivity and pH) should be measured because they are subject to change once the groundwater is removed from the well. To measure:

- Rinse the metres with deionized water and blot dry with clean paper towels.
- Rinse the field parameter sample container (1 l vol.) and blot dry with clean paper towels.
- Calibrate the field parameter metres in the standard solutions (the standard solutions should be comparable to the values expected in the field).
- Fill the field sample container immediately after the well has been purged.
- Immediately measure the parameters in order:
 - temperature
 - conductivity
 - pH
- Fill in section on sampling record sheet titled "Field Parameters".



Knight Piésold Ltd. CONSULTING ENGINEERS

3.5 STEP 5 - COLLECT SAMPLES

Since purging of the well will assist in "pre-cleaning" the equipment, the same equipment should be utilized for sampling. The sampling should be carried out in the following order using the correct bottles:

- Field parameters (Bottle No. 1) 11
- Total metals (T.M.) (Bottle No. 2) 250 ml
- Total mercury (T.Hg) (Bottle No. 3) 500 ml
- Dissolved metals (D.M.) (Bottle No. 4) 250 ml
- Total cyanide (T.CN) (Bottle No. 5) 11

The sampling procedure should comprise the following:

- Take precautions to prevent dirt and dust from contaminating the samples.
- Before filling the sample bottles, rinse out twice using water being collected from the well, except for total cyanide bottle (No. 5). In this bottle, add 7 to 10 NaOH pellets, if not already added.
- Fill the containers almost full, but in bottles No. 2, 3 and 4 leave room to add the HNO₃ (2 ml) preservative and allow for shaking.
- Cap the sample containers tightly.
- Complete the sample label before moving to the next sampling site.
- Store the samples in a protective container for protection during transportation to camp.

3.6 STEP 6 - FILTRATION OF SAMPLES

Upon returning to camp, the dissolved metals and total mercury samples must be filtered before the preservative is added. Consequently, these samples have the greatest potential for becoming contaminated and care must be taken to avoid touching the filter or sample. Filtering procedures are as follows:

- 8 -



Association des Ingénieurs Conseils du Canada

Knight Piésold Ltd. CONSULTING ENGINEERS

Rinse the inside of the vacuum filter apparatus (base and funnel) with deionized water and shake out excess water.

With the tweezers, place a filter on the base of the filter funnel. Handle the filter only on the edges. Screw the top portion of the vacuum filter apparatus on carefully so as to avoid wrinkling the filter paper.

- Pour the sample into the top of the filter apparatus and secure the lid.
 Attach the bottom section and hand held suction pump, making sure the airline is properly secured.
- Using the hand held pump, filter the sample into the bottom of the apparatus. (Note: If the sample is silty, this procedure may take some time).
- Rinse the original sample bottle with deionized water before returning the sample. Return sample and fasten cap on bottle.
- After each sample, rinse filter apparatus with deionized water and be sure to replace filter.

3.7 STEP 7 - PRESERVE SAMPLES

Many of the chemical constituents and physicochemical parameters that are to be measured or evaluated in groundwater monitoring programs are not chemically stable so preservation is required to prevent sample degradation.

Preservation methods are generally limited to pH control, chemical addition, refrigeration and protection from light and are intended to retard biological action and hydrolysis and to reduce sorption effects.

Table 3.1 summarizes the sample preservation methods required for each bottle. All bottles should be kept at 4° C. In bottles 2, 3 and 4, add 2 ml of HNO₃. In bottle 5, NaOH pellets were added prior to sampling.



Association des Ingénieurs Conseils du Canada

Knight Piésold Ltd. CONSULTING ENGINEERS

1

Complete the section on the sampling record sheet titled "Sampling, Filtration and Preservation".



Association des Ingénieurs-Conseils du Canada - 10 -



3.8 STEP 8 - SHIP SAMPLES TO LABORATORY

3.8.1 Sample Labels

The labels should be sufficiently durable to remain legible even when wet and should include:

- Sample identification number (Well No. and Bottle No.)
- Name of collector
- Date and time of collection
- Place of collection
- Parameter(s) requested, i.e. Total Metals, Total Mercury, Dissolved Metals, Total Cyanide or Field Parameters

3.8.2 Packing

- Seal and carefully pack the sample bottles in an upright position to ensure that they are not disturbed during shipping.
- Pack ice in properly sealed, water-tight plastic bags around the sample bottles.
- Position the shipping (max-min) thermometer so that it is not against the ice.
- Use newspaper or equivalent as a packing material. Styrofoam chips should not be used.
- Seal the shipping container.

3.8.3 Chain-of-Custody Record

A chain-of-custody record should be filled out and should accompany every shipping container sent to the laboratory. The record should include:



Knight Piésold Ltd. CONSULTING ENGINEERS

- Sample number
- Signature of collector
- Date and time of collection
- Sample type
- Identification of well
- Number of sample bottles
- Signature of person(s) involved in the chain of possession
- Inclusive dates of possession
- Internal temperature of shipping container when samples were sealed into the shipping container
- Maximum temperature recorded during shipment
- Minimum temperature recorded during shipment; and
- Internal temperature of shipping (refrigerated) container upon opening in the laboratory.

The chain-of-custody record sheet is included in Appendix A.



Knight Piésold Ltd. CONSULTING ENGINEERS

SECTION 4.0 - QUALITY CONTROL AND DATA REVIEW

4.1 INTRODUCTION

In order to document the condition of the well and verify the accuracy of the sampling and handling program, some quality control measures must be taken. Quality control includes the following categories:

- Field parameters
- Preliminary data review
- Annual well evaluation

If quality control locates a source of error, the source should be identified and documented. Corrective action, including re-sampling, should then be initiated.

4.2 FIELD PARAMETERS

Quality control for determination of field parameters simply includes calibration of all field measurement equipment prior to use and re-calibration in the field before measuring each sample.

4.3 PRELIMINARY DATA REVIEW

On receipt of the laboratory data, the results should be compared with previous data from the well and with data from any adjacent wells. Should anomalous data be present, the possible reasons should be assessed and resampling initiated to verify or discount any anomalies.



Association des Ingénieurs-Conseils du Canada

CONSULTING ENGINEERS

Knight Piésold Ltd.

4.4 ANNUAL WELL EVALUATION

Annual evaluation of the wells provides documentation of the well condition and, therefore, the quality of the data. Complete records of the tests should be filed. These include:

(i) Sedimentation

The quantity of sediment in each well should be documented by measuring the total depth of the monitoring well. Any sediment should be removed from the well, described (sand, silt, organic matter, etc.), and documented.

(ii) Rising Head Test

An annual rising head test is required to verify the performance of each well. Following a similar procedure every year, data should be collected from 5 percent recovery to 95 percent recovery. Thirty to forty reading should be taken, where possible. The rising head test data collection form included in Appendix A should be completed in full. The time data should be measured to the second for wells which recover 95 percent in less than an hour. The data should be analyzed by qualified personnel and compared to earlier results to determine whether or not the well response has changed.



Association des Ingénieurs-Conseils du Canada

Knight Piésold Ltd.

TABLE 3.1 CONSULTING ENGINEERS IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

SAMPLE AND PRESERVATION PROCEDURES FOR GROUNDWATER MONITORING⁽¹⁾

Bottle No.	Bottle Parameter Specific Analysis No. Group		Bottle Type	Preservative	Maximum Holding Time
1	Field Parameters	ield Parameters Conductivity, pH, Colour, Dissolved Solids, Hardness		4°C	Conductivity and pH are field determined but sample should be shipped ASAP to minimize pH shift ⁽³⁾
	Major Ions	Bicarbonate, Sulphate, Chloride, Fluoride			28 days
	Nutrients	O-Phosphate, D- Phosphorus, T-Phosphorous, Nitrate, Nitrite, Ammonia			48 hours
2	Total Metals	Al, Sb, As, Ba, Be, Bi, Bo, Cd, Ca, Cr, Co, Cu, Fe, Pb, Mg, Mn, Mo, Ni, Se, Si, Ag, Sr, U, V, Zn	250 ml plastic	2 ml HNO ₃ 4°C	6 months
3	Total Mercury		500 ml plastic	2 ml HNO ₃ 4°C	6 months
4	Dissolved Metals	Al, Sb, As, Ba, Be, Bi, Bo, Cd, Ca, Cr, Co, Cu, Fe, Pb, Mg, Mn, Mo, Ni, K, Se, Si, Ag, Na, Sr, U, V, Zn	250 ml plastic	Field filtration (0.45 micron), 2 ml HNO ₃ 4°C	6 months
5	Total Cyanide		1 1 plastic	7 to 10 NaOH pellets, sodium arsenite if oxidizing agents are present, 4°C	14 days, 24 hours if sulphide is present

1. References: Test Methods for Evaluation Solid Waste - Physical/Chemical Methods, U.S. EPA SW-846 (2nd Edition, 1982).

Methods for Chemical Analysis of Water and Wastes, U.S. EPA-600/4-79-020.

Standard Methods for the Examination of Water and Wastewater, 16th Edition (1985).

Collection and Preservation of Environmental Samples, Analytical Service Laboratories, December, 1986. 2. Plastic Polyethylene

Conductivity and pH field measurements are not always required but should be carried out whenever equipment is available on site



3.

Knight Piésold Ltd. CONSULTING ENGINEERS

APPENDIX A

RECORD SHEETS



.

Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 240 of 500

10

Knight Piesold Ltd.

CONSULTING ENGINEERS

MT. POLLEY PROJECT GROUNDWATER SAMPLING QUALITY CONTROL CHAIN OF CUSTODY RECORD

PROJECT NO.:

(ONE PER	SHIPPING	CONTAINER)
----------	----------	------------

Month and Year of Sampling Round

DESCRIPTION OF CONTENTS

Page _____ of _____

SAMPLE NO. SAMPLING METHOD

SAMPLE NO.		SAMPLING METHOD	SAMPLING DATE	INITIALS	
Well No.	Bottle No.			· · · · · · · · · · · · · · · · · · ·	
				_	
	-			_	

BOTTLE NO.	VOLUME	PARAMETER
1	1000 ml	Field Parameters (F.P.)
2	250 ml	Total Metals (T.M.)
3	500 ml	Total Mercury (T.Hg)
4	250 ml	Dissolved Metals (D.M.)
5	1000 ml	Total Cyanide (T.CN)

Temperature:

Initial _____ Max. ____ Min. _____

Final

CHAIN OF CUSTODY

Date		Location	Signature
From	То		
			J:JJOB\DATA\0019\GWATER3.XLS

INVESTIGATION KP 1-11 241 of 500

CONSULT	t Piesold Ltd ring engineer	l. RS C	GROUNDW	MT. POLLEY PROJECT ATER SAMPLING QUALITY RISING HEAD TEST	CONTROL
PROJECT NO).:			WELL NO.: DATE:	
'RE-TEST W - Day Be - Day Te	ATER LEVE	LS Date Date		Depth to Water	
URGING	otoa.			Well Inner Diameter	
- Purgini	g Method			DVC Stickup	
- Time P	burging Started	(hemes)		Total Dapth	
- Time P	urging Ended ((II.III.5)			
- Total V	Volume Durged	u.m.s)		Droho Sorial No	
- Total +	olume Furged	-		Probe Senar No.	
- Comm	ents	d7		Теме Ву	
VELL COND	DITION				
ECOVERY	DATA:				
T	Time	Depth to war	er	C	
Date	(firmes)	From Tup of r	ve	Comments	

INVESTIGATION KP 1-11 242 of 500

22

CONSULTING ENG	d Ltd. FINEERS	GRO	DUNDWA	MT. PO ATER SAN REC	LLEY PR APLING (ORD SHI	OJECT QUALI EET	TY CONTROL
PROJECT NO.:				WELL NO	D.:		
	1	5		DATE SAL	MPLED:		
WEATHER:				COMMEN			
GROUNDWATER LE	VEL AND WE	LL VOLU	ME				
F		1.1.5	Time	Depth		Con	nments
a) Depth to Water from	top of PVC						
b) Depth to bottom of T	est Zone from to	op of PVC					
c) Length of Standing W	Vater Column, I	L (b-a)					
Volume of Standing Wa	ter Column (0.	$8 \times L \times D^2$					
- where $D =$	inner diameter	of PVC pipe					
ELL PURGING							
Volume to purge (3 x vo	olume of standin	g water col	umn) =				
Purging Duration:	from	l		to)		
				91	-		-
	Durge Well a	with Dailar			Durgo	Wall with	
Bailer Volume	Purge Well w	vith Bailer	Container	Volume	Purge	Well wit	n Grundros Pump
Bailer Volume	Purge Well w	vith Bailer	Container	Volume	Purge	Well wit	n Grundros Pump
Bailer Volume Number of Bails Volume Bailed Well Yield (high, me	Purge Well w	vith Bailer	Container Number o Volume P	Volume of Containers Pumped	(high = 1	Well wit	as fast as purging)
Bailer Volume Number of Bails Volume Bailed Well Yield (high, me Comments:	Purge Well w	vith Bailer	Container Number o Volume P	Volume of Containers Pumped	Purge	Well wit recharge a >24 hrs to	as fast as purging) o recover from purg
Bailer Volume Number of Bails Volume Bailed Well Yield (high, me Comments:	Purge Well w	vith Bailer	Container Number o Volume P	Volume of Containers Pumped	Purge	Well wit recharge a >24 hrs to	as fast as purging) o recover from purg
Bailer Volume Number of Bails Volume Bailed Well Yield (high, me Comments:	Purge Well w dium, low)	Time	Container Number o Volume P	Volume of Containers Pumped	Purge	Well wit recharge a > 24 hrs to Groundwa	as fast as purging) o recover from purg
Bailer Volume Number of Bails Volume Bailed Well Yield (high, me Comments:	Purge Well w	Time	Container Number o Volume P Calibrati Stated	Volume of Containers Pumped ion Standard Measured	Purge	Well wit recharge a > 24 hrs to Groundwa	as fast as purging) o recover from purg
Bailer Volume Number of Bails Volume Bailed Well Yield (high, me Comments:	Purge Well w	Time	Container Number o Volume P Calibrati Stated	Volume of Containers Pumped ion Standard Measured	Purge(high = 1(low = 2)	Well wit recharge a > 24 hrs to Groundwa	as fast as purging) to recover from purg
Bailer Volume Number of Bails Volume Bailed Well Yield (high, me Comments:	Purge Well w	Time	Calibrati Stated	Volume of Containers Pumped ion Standard Measured	Purge(high = 1(low = 2)	Well wit recharge a > 24 hrs to Groundwa	as fast as purging) to recover from purg
Bailer Volume Number of Bails Volume Bailed Well Yield (high, me Comments:	Purge Well w	Time	Container Number o Volume P Calibrati Stated	Volume of Containers Pumped ion Standard Measured	Purge	Well wit recharge a > 24 hrs to Groundwa	as fast as purging) o recover from purg
Bailer Volume Number of Bails Volume Bailed Well Yield (high, me Comments:	Purge Well w dium, low) S	Time	Container Number of Volume P Calibrati Stated	Volume of Containers Pumped ion Standard Measured	Purge	Well wit	as fast as purging) o recover from purg ater Sample
Bailer Volume Number of Bails Volume Bailed Well Yield (high, me Comments:	Purge Well w dium, low) S	Time ESERVAT	Calibrati Stated	Volume of Containers Pumped ion Standard Measured Itration	Purge Purge (high = 1 (low = 2) Preser (Y / N)	Well wit recharge a > 24 hrs to Groundwa vation	as fast as purging) to recover from purg tater Sample Container No.
Bailer Volume Number of Bails Volume Bailed Well Yield (high, me Comments:	Purge Well w dium, Iow) S	Time ESERVAT	Calibrati Stated ION Fil (Y / N)	Volume of Containers Pumped ion Standard Measured tration Method	Purge Purge (high = 1 (low = 2 Preser (Y / N)	Well wit recharge a > 24 hrs to Groundwa Groundwa vation Type	as fast as purging) o recover from purg ater Sample Container No. and Volume
Bailer Volume Number of Bails Volume Bailed Well Yield (high, me Comments:	Purge Well w dium, low) S	Time ESERVAT	Calibrati Stated (Yolume P Calibrati Stated (Y / N)	Volume of Containers Pumped ion Standard Measured	Purge (high = 1 (low = 2 Preser (Y / N)	Well wit recharge a > 24 hrs to Groundwa vation Type	as fast as purging) o recover from purg ater Sample Container No. and Volume 1 (1000 ml) 2 (250 ml)
Bailer Volume Number of Bails Volume Bailed Well Yield (high, me Comments:	Purge Well w dium, low) S	Time ESERVAT	Calibrati Stated ION Fil (Y / N)	Volume of Containers Pumped	Purge Purge (high = 1 (low = 2 Preser (Y / N)	Vell wit	as fast as purging) o recover from purg ater Sample Container No. and Volume 1 (1000 ml) 2 (250 ml) 3 (500 ml)
Bailer Volume Number of Bails Volume Bailed Well Yield (high, me Comments:	Purge Well w dium, Iow) S TION AND PR	Time ESERVAT	Calibrati Stated ION Fil (Y / N)	Volume of Containers Pumped	Purge Purge (high = 1 (low = 2 Preser (Y / N)	Well wit recharge a > 24 hrs to Groundwa vation Type	as fast as purging) o recover from purg ater Sample Container No. and Volume 1 (1000 ml) 2 (250 ml) 3 (500 ml) 4 (250 ml)

 $\hat{\boldsymbol{A}}$

.



APPENDIX B

1989 AND 1995 MONITORING WELL INSTALLATIONS LOGS



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 244 of 500

Intert of the second of the s	KNIGHT AND PIESOLD CONSULTING ENGINEERS	LTD.	TEST HOLE I	LOG
NOTES Water loss, type and size of hole, drilling method, 	PROJECT <u>MI. Polle</u> LOCATION OF TEST H DATE BEGUN <u>O.T. 31</u>	V OLE <u>Tailings</u> 1989 DATE FIN	1100 B IISHED Nov. 1,1989	PROJECT No GROUND ELEVATION LOGGED BY KMK + KM.N
$\begin{array}{c c c c c c c c c c c c c c c c c c c $	NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	DEFECT SPACING (cm) PERMEABILITY (* 10°cm/s) (* 10°cm/s)		ON AND CLASSIFICATION OF MATERIAL
$\begin{array}{c c} \begin{array}{c} 1 \\ e \\ e \\ zometer \end{array} \end{array} = \begin{array}{c} 1 \\ 1 \\ 1 \\ 1 \\ 1 \\ 1 \\ 1 \\ 1 \\ 1 \\ 1 $	Pneumatic leads water table nt sersec 12" Ø PUC staid: /e staid: /e	$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	$ \begin{array}{c} & & & \\ & & \\ \hline \\ \hline \\ \hline \\ \hline \\ \hline \\ \hline \\ \hline$	sursoce y, silty till with ounded pettles own course sond and growel K-spar proch intrusive) is and with minor clay binder win course sond and growel K-spar rich intrusive) thend volcaric complumines and planer joints in Silled ag, hereatile, or calcite ing weathering down hole) strained to sondy clay gouge

KNIGHT AND	PIESOLD I	TD.		-	TES	T HOLE	LOG	TEST HOLE No MP89-232 SHEET) of 1
PROJECT LOCATION OF DATE BEGUN	M1. Polle; TEST H Nov, I ,	0LE 1989		: /:. , : E FINISH	<u>л</u> . нер <u>1</u>	.]: lov. 4, 198	- PROJECT No GROUND ELEVA LOGGED BY <u>RN</u>	1621 TION 919.4 K + K McN
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	DEFECT SPACING (cm)	PERMEABILITY (* IO ⁶ cm/s)	HELLA (Seet)	GRAPHIC LOG	DESCRIP	TION AND CLASSIF OF MATERIAL	ICATION
I'z" & PVC standpipe piezonster hole sloughed in at 50'	- 15 30 - 40 0 - 40 0 - 40 0 - 5 - 0 0 - 40 0 - 5 - 0 0 0 - 15 - 0 0 0 0 0 - 15 - 0 0 0 0 0 - 15 - 0 0 0 0 0 - 15 - 0 0 0 - 15 - 100 - 20 0 - 20 - 25 - 25 - 20 - 25 - 20 - 25 - 20 - 25 - 25 - 20 - 25 - 25 - 20 - 25 - 25 - 40 - 25 - 25 - 25 - 40 - 25 - 25 - 40 - 25 - 25 - 25 - 40 - 25 - 20 - 20 - 20 - 25 - 20 - 20 - 25 - 20 - 20 - 25 - 20 - 20 - 25 - 20 - 20 - 25 - 20 - 20 - 25 - 20 - 20 - 20 - 25 - 20 - 20 - 25 - 20 - 20 - 25 - 20 - 20 - 20 - 20 - 20 - 20 - 20 - 25 - 20 - 20 - 20 - 20 - 20 - 25 - 20 - 20 - 25 - 20 - 20 - 20 	7. 3 10 3 10 3 10 3 10 3 10 3 10 3 10 3 10 3 10 3 10 3 10 10 10 10 10 10 10 10 10 10	.7[.2[50 - 4 100 - 4 150 - 4 200 - 4 250 - 4 300 - 4 350 - 4 350 - 4		- water to - dense, group - clay rich is down Hole - lay cred is and silts - purple worth with obunder - sound ord (dominant to core with obunder - sound ord (dominant to core with core - well stra with co - well stra with co - wolcanic	ble at T' silty glacial int, becoming coor lay rich very ind, sost, clay by vo t cobbles and gre clay rich volcomic srectures at a caris, tight, roug calcite instilling) lay gougo raised purple re late instilled ro is of purple son lay motrix corglomerate	till sergraind Sine souds Ironic congliment wel mud 70° and 115° h and planer h and planer ds tone (os above)
l	1 16			-	A	EOH	INVESTIGATION KP 1-11_24	6 of 500

ă,

KNIGHT AND consulting	PIESOLD	D LTD.	TEST HOLE LOG							
PROJECT LOCATION OF DATE BEGUN	MI. Poli TEST Nov. 5,	<i>ley</i> HOLE _ <i>1989</i>	T .	: 1: 43 TE FINI	A	Nov. 6, 1989	- PROJECT No. 1621 GROUND ELEVATION 933.			
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	DEFECT DEFECT SPACING (cm)	PERMEABILITY (* IO ⁶ cm/s)	HELDE (feet)	GRAPHIC LOG	DESCRIPTI	ON AND CLASSI	FICATION		
1 ¹ / ₂ PVC stordyipe pipzameter bentonite seal 2 cm hole sloughed in at 100	- 5 - 5 - 15 - 0 - 10 - 5 - 5 - 70 - 75 - 70 - 70 - 75 - 70 - 70 - 75 - 70 - 70 - 75 - 70 -	2 4 3 4 000 00 00 00 00 00 00 00 00 00 00 00 0	II [222 16 17 [50 100 100 150 150 150 150 150 1	TO T	- dense, grey with abure and silty c I water tobl - grey san , some peb	silling q lacial de at 56' dy glacial to bles (necessing m rathered volca to, with ma to trave sand	I till up mestly pables ill with ostly pables and gravel		

KNIGHT AND	TD.	TEST HOLE LOG									
PROJECT LOCATION OF DATE BEGUN	MI. PO TEST Nov	<i>оШеу</i> т но 7,19	DLE_ 189	7' DAT	TE FINI	H SHED	NOV.],]	1989	- PROJECT No 1621 GROUND ELEVATION 909. LOGGED BY RNK + K M. N		
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	ROD	DEFECT SPACING (cm)	PERMEABILITY (* IO ⁶ cm/s)	(Seet)	GRAPHIC LOG	DES	SCRIPTIO	N AND CLASSI	FICATION	
Pheumatic leads 11" & PVC 2 tordaile 2 istonater	- 50 - 1 - 20 - 0			14 [+ o +	- water - dense - s p.b) - g.sy	table at grey thes, and cloye	scirsoce clay.and silt .rare 5cm back	with a track ds of chan so	
bentonite sed	100 	35 40 65 85 70 20 50 0	10 30 30 30 30 30 30 30 30 30 30 30 30 30	,32 [3.3 [100 - - - 150 - -	4	- Usa la de to	thored po ltened sects core	uiple volceni to sond and primited 60 axis	c co-glomma grovel) and 90°	
sand backs:11	90 100 90 95 70	70 90 15 25 0	30		2 <i>00 -</i> - -	4	- dec wra	reasing thering	degree 10 with dep	s oth .	
and seal 2 and seal 2 an a		40 40 60 80 10	10 10 10 23		- 2 <i>50 -</i> - -	4					
n at 270'		10 0 0 15 40	10		3 <i>0</i> 0 - - -	4	×				
		30 80 60 70	30		350 - - - -	• • •	EC)H	χ.		

\$

KNIGHT AND PI	ESOLD L	TD.			TE	ST HOLE L	_OG	TEST HOLE NO. MAR 1- 235
PROJECT M	I. Polley	,					ODO ISCT N	SHEET of /
OCATION OF	TEST H	OLE	To	iling	H,	sr K	GROUND ELEVAT	1021
ATE BEGUN	100.91	789	DAT	E FINI	SHED	Nov. 10, 1989	LOGGED BY RNA	+ K Me N
NOTES /ater loss, type and size of hole, drilling method, roundwater level, tc.	RECOVERY %	DEFECT SPACING (cm)	PERMEABILITY (× 10 ⁶ cm/s)	(Seet)	GRAPHIC LOG	DESCRIPTIO	ON AND CLASSIFI OF MATERIAL	CATION
oneumatic "ds "d PVC standpile reks:// benton/te scal 	80 20 100 40 70 90 70 85 95 70 60 60 50 65 65 85 90 70 30 70	<3 10 30 10 30 10 30 10 10 30 10 10 30	510 .086 .40	50		- very weath conglomerate thin clay.	hered purple e with rough filled frontung	volconic , woug,
bocksill z	10 85 70	V 10 30 10 30 10 30 10 20 10 20 10		200		с hoolod 5. - purple Ja EDH	lear zone salt INVESTIGATION KP 1-11 24	9 of 500

Г	KNIGHT AND	PIESO	LD L	.TD.		Т	EST	HOLE	LOG	TEST HOLE NO
ſ	PROJECT LOCATION OF DATE BEGUN	MI. P TES Nov,	<i>olle)</i> Т Но 10,	OLE _		oilings TE FINISH	Hren HED Nou	K. 11, 1989	PROJECT No	1621 10N 944.4 K + K 11LN
	NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	ROD	DEFECT SPACING (cm)	PERMEABILITY (x IO ⁶ cm/s)	(Seet)	GRAPHIC LOG	DESCRIPTI	ON AND CLASSIF	ICATION
	pneumatic leads 1 ¹ O PK standpyre 2 pirsometer sand backs: 11 bentonile Sral 2 becks: 11 bentonile seal backfill onematic pig 20-rinr tip ot 380	5 10 10 40 40 70 70 70 70 70 70 70 70 70 70 70 70 70	000100200055000055000000000000000000000	23 VII V30 V330 VIII VIII VIIIII VIIIII VIIIII VIIIII VIIIII VIIIII VIIIII VIIIIIIII	2.7 [2.7 [2.0]	50 - × 100 - ×	y -w y -w y x x x x x x x x x	0 H	At Surgere. et silty till of syamite with and chlorite sill orth Sricture. and 70° to NVESTIGATION KP 1-11 2500	with some h thin led tryht lesects cone aris

KNIGHT AND PIESOLD LTD.

100

TEST HOLE No.

CONSULTING	ENGINE	ERS				IE	SI HOLE	LUG	95.R.I
PROJECT LOCATION OF	T. P.	<u>Пец</u> Т Н	OLE _					PROJECT No. 16 GROUND ELEVAT	10N
DATE BEGUN				DA	TE FI	NISHED	<u>.</u>	LOGGED BY	
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	BLOWS / FOOT	MOISTURE CONTENT %	MONITIORING	DEPTH	CRAPHIC LOG	DESCRIPTI	ON AND CLASSIF OF MATERIAL	ICATION
90-100' 1 gpm 150'-180' 20+ gpm 175' fractured		B			100		0-3' overburder 3-20' syenodiori 3-20' syenodiori 20-50' monzonite 50-70' syenodiori 70-80' 50/50 syen 80-100' 50/50 syen 100-110' 70% monz 110-130' syenodiori 130-150' dk. green b 150-160' monzonite 170-190' dk. green b 190-290' syenodiori 290-330' monzonite 330-350' syenodiori	h ite, green chloritic, minor porphyry porphyry, pink, K-spar ri- ite, grey, prophyritic odiorite and monzonite por porphyry, pink, K-spar ri- conite porphyry, 30% syen te, light grey, prophyritic basaltic volcanics e porphyry, 30% basaltic v e porphyry, buff, K-spar ri- basaltic volcanics, minor e porphyry rite, light grey, prophyritic e porphyry, buff, K-spar ri- ite	to some ch orphyry ch odiorite rolcanics ch to some
							350-360' monzonite 360-460' 50/50 sye possible in	e porphyry, pink, K-spar r nodiorite and monzonite p ntrusive breccia	ich orphyry,
	-				HOD		II	NVESTIGATION KP 1-11 251	of 500

KNIGHT AND A	PIESO	LD L	.TD.			TE	ST HOLE L	OG	45. R.I
PROJECT MT	D II							ODO IF CT No. 1	SHEET 2
LOCATION OF	TEC	T U						CROUELI NO. 1	7/01/
DATE BEGUN	163			041		SHED		LOCCED BY	
NOTES			-	UAI				200020 81	
Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	BLOWS / FOOT	MOISTURE CONTENT %	MONTALLATION	DEPTH	GRAPHIC LOG	DESCRIPTIO	ON AND CLASSII OF MATERIAL	FICATION
405-440' 20+ gpm - 415-440' fractured - -				11111		× + + + + + + + + + + + + + + + + + + +	360-460' 50/50 syeno possible intr E.O.H. = 460'	diorite and monzonite p usive breccia	orphyry,
	-				500 -	-			
~						-			
						-		,	
						-			
	-								
	-								
						-			
	-								
KNIGHT AND F	PIESOLO	D LTD.		TE	ST HOLE L	LOG	TEST HOLE N 95. R. 2 SHEET 1 of		
--	--------------------	---------------------------------------	----------------------------	--------------	---	--	---------------------------------------		
PROJECT	T. Polle	ey				PROJECT No. 1	624		
LOCATION OF	TEST	HOLE _		- Continue -		GROUND ELEVA	TION		
DATE BEGUN			DAT	E FINISHED)	LOGGED BY			
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	BLOWS / FOOT MOISTURE CONTENT %	NOLLYTTYLSNI DNINOLINOW	DEPTH	DESCRIPTIO	ON AND CLASSIF OF MATERIAL	TICATION		
122-138' 80 gpm 122-138' fractured					0-4' overburden 4-20' syenodiorite 20-40' syenodiorite 40-70' syenodiorite 100-110' sy	e, weathered beige to ligit e, lightly weathered beig e, light grey e, dk. grey, highly pyritic e, light grey, oxidized e, light grey, oxidized e, light grey, limonite co e, light grey te, light grey, fractured e, light grey, fractured	ht brown e to light brown		
	-					NVESTIGATION KP 1-11 25	i3 of 500		

ľ

KNIGHT AND A	PIESOL	D LTD.			TE	ST HO	LE L	.OG	95. R.3
BBO IECT 00	- 72 11	4						DDO IECT No. 1	SHEET I
PROJECT	1. 1-011	ey						PROJECT No.	019
LOCATION OF	TEST	HOLE						GROUND ELEVAT	ION
DATE BEGUN			DA1	TE FINI	SHED			LOGGED BY	
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	BLOWS / FOOT MOISTURE	MONTTORING	DEPTH	GRAPHIC LOG	DES	CRIPTIC	ON AND CLASSIF	ICATION
	1 1 2 1 1 1					0-2' 0 2-30' s 30-50' s 50-60' m 60-70' 5 70-110' s	verburden yenodiorite yenodiorite xidized nonzonite p 0/50 syeno yenodiorite	, grey-green, weathered , rusty limonite coated fr orphyry, pink diorite and monzonite po , light brown minor pink	actures, highl orphyry a monzonite
140-190' 2 gpm 140-190' fractured				100'	· · · · · · · · · · · · · · · · · · ·	F 110-140' 6 140-160' 4 160-190' n 190-210' s 210-280' s	orphyry 0% monzor 0% monzor nonzonite p nyenodiorite	nite porphyry, 40% syen nite porphyry, 60% syen orphyry, beige , grey-green , light brown, oxidized p	odiorite odiorite
				- - - - - - - - - - - - - - - - - - -		280-310* 3	syenodiorite	rite	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
310-370' 7 gpm 310-370' fractured			11111111	-		310-340' s 340-350' 5 350-360' 7 360-370' 5 370-420' s	yenodiorite 0/50 syeno 0% monzo 0/50 syeno yenodiorite	, light brown diorite and monzonite po nite porphyry, 30% syend diorite and monzonite po , grey-green	rphyry xdiorite rphyry
					1.				
*			11 1	line!	N 1		15.1		-1 500

PROJECT Mī. Polles PROJE LOCATION OF TEST HOLE DATE FINISHED LOGGE NOTES OATE FINISHED LOGGE NOTES Water loss, type Water loss, type Use of hole, of the second size of the second size of hole, of the second size of the sec	CT No. <u>1624</u> D ELEVATION <u></u> D BY <u></u> CLASSIFICATION TERIAL
LOCATION OF TEST HOLE GROUN DATE BEGUN DATE FINISHED LOGGE NOTES Water toss, type and size of hole, groundwater level, etc T_	D ELEVATION D BY CLASSIFICATION TERIAL
DATE BEGUN DATE FINISHED LOGGE NOTES Water less, type and size of hole, drilling method, groundwater tevel, etc. 	CLASSIFICATION TERIAL
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CLASSIFICATION TERIAL
$\frac{1}{2}$ $\frac{1}$	n :
$\frac{1}{2}$ $\frac{1}$	
E.O.H. = SCO'	
500' -'' 	
E = 500' = -1' $E = 500'$ $E = 500'$	
[-]	

KNIGHT AND P	PIESO	LD L	.TD,			TE	ST HOLE I	LOG	95.A.L
PROJECT	T. P	alley						PROJECT No	1624
LOCATION OF	TES	тн	DLE_					GROUND ELEVA	TION
DATE BEGUN				DAT	E FINI	SHED		LOGGED BY	
NOTES	2	-		7		0			
Water loss, type	ы. т	FOO	JAE 7 %	DNI	x	LG	DESCOIDTI	ON AND CLASSI	TICATION
drilling method,	VER	1 s	ISTU TEN	ET B	EPT	HIC	DESCRIPTIN	ON AND CLASSIF	TCATION
groundwater level,	ECO	MOT	WO	NONI NST/	٥	RAF		OF MATERIAL	
erc.	8	8		A K		0			
	-			88	-	0:.	0-20' overburder	n, glacial till	
						Y	20-90' monzonite p	porphyry, reddish maroo	n
	Į –	P		Ξ		*			
	-				-	. *			
	-				5	T 1			
	-					+ ×			
85-105' 10 mm	-			E		+			
65-105 10 Bpm				Ξ.	100' -	×	90-140' monzonite	porphyry, reddish marc	on, oxidized
	-					×			
	-					× +			
						+ +			
140-170' 12 gpm				Ξ	-		140-160' syenodiori	te, grey-green	
	-			E		11.			
	-					1	160-190° syenodion	te, grey-green, slightly o	
	-					1.			
					200'		190-200' syenodiorit	e, grey-green	
10.0001 100.	-			11		1.1	200-230' syenodiorit	e, grey-green, slightly or	xidized
10-222' 100+ gpm 210-222' fractured	-			11				6	
	E I			-		11	230-240' svenodiorit	te, grey-green	
	-					~ *	240-270' mafic tuff		
	-					1 1	2		
	-				· · ·	×	000 000		
	-					1	270-320 monzonite	porphyry, grey and pink	
	-				300'	T X			
313-320'	_					× ,			
possible water	Į			11		4			
312-320' fractured	-					74	320-330' dk. green b	asaltic volcanic, minor n	nonzonite porp
	-					1	550-500 syenodiorit	e, grey and plink	
350-380'	-				-	1.			
possible water	Ē			E		1.1	360-380' syenodiorit	e, grey and pink, trace m	nafic volcanic
350-380' fractured				-		11:			
	-			F		1:1	380-400' syenodiorit	e, grey and pink	
					400'	1 1	E.O.H. = 400 IN	VESTIGATION KP 1-11 256	6 of 500

Γ

ſ

Г

T

Г

T

Ľ

1

L

KNIGHT AND PIESOLD LTD

TEST HOLE No

CONSULTING	ENGINE	ERS				TE	ST HOLE I	LOG	95. A.5 SHEET I of I
PROJECT_m	T. Pol	ley						PROJECT No	1624
LOCATION OF	TES	тн	OLE _					GROUND ELEVA	TION
DATE BEGUN		100		DAT	TE FIN	ISHED		LOGGED BY	
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	BLOWS / FOOT	MOISTURE CONTENT %	MONTORING INSTALLATION	DEPTH	GRAPHIC LOG	DESCRIPTI	ON AND CLASSI OF MATERIAL	FICATION
150-170' 1 gpm 160-170' fractured 197-210' 3 gpm 197-210' fractured							0-14' overburder 14-23' broken roc 23-40' syenodiori 40-50' syenodiorit 50-60' 50/50 syen 60-70' 30% monzo 70-90' monzonite 90-130' mafic tuff 130-140' mafic tuff 130-140' mafic tuff 140-150' 80% monzonite 160-170' 80% monzonite 160-170' 80% monzonite 210-230' monzonite 230-260' mafic tuff E.O.H. = 260'	n, glacial till k te, light grey and beige, e, grey-green odiorite and monzonite onite porphyry, 70% sys porphyry, brick red 5-10% pink monzonite j onite porphyry, 20% ma porphyry, pink onite porphyry, 20% ma	weathered porphyry modiorite porphyry fic tuff fic tuff

KNIGHT AND	PIESOL	D LTD.			TE	ST HOLE	LOG	95. R. C
PROJECT	T Pol	HOLE .	0.03	55 5 M			PROJECT No.	624
DATE BEGUN				E FIN	ISHED		LOGGED BY	
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	BLOWS / FOOT MOISTURE CONTENT %	MONITORING	DEPTH	GRAPHIC LOG	DESCRIPTI	ON AND CLASSIF OF MATERIAL	ICATION
9-88' 3 gpm 9-88' fractured				-	90° - × × + + × × × × ×	0-9' overburder 9-20' syenodiori 20-80' fine graine	n te, light grey, weathered ed monzonite, pink	
				100	· · × · · · × + ×	80-90' syenodiorit 90-100' fine graine 100-110' syenodiorit 110-130' fine graine 130-180' syenodiorit	te, light grey d monzonite, pink te, light grey d monzonite, pink, 10% e, grey-green, minor mor	syenodiorite uzonite
150-175' 2 gpm 150-175' fractured						180-200' fine grained	d monzonite, pink, minor	syenodiorite
					* *	200-210' Augite por 210-300' fine graine	phyry dike, dk. grey d monzonite, pink	
			11	-	* × × × * *			
300-310' 1 gpm 300-310' fractured				300	× *	300-390' fine graine	ed monzonite, pink	
			11	-	* × + +	3		
					*			

.

TEST HOLE No. 95.R.6

KNIGHT AND PIESOLD LTD. TEST HOLE LOG CONSULTING ENGINEERS SHEET 2 of 2 PROJECT No. 1624 PROJECT _____ Polley GROUND ELEVATION _____ LOCATION OF TEST HOLE ____ DATE BEGUN _ LOGGED BY ____ DATE FINISHED ____ NOTES % MOISTURE CONTENT % MONTORING LOG BLOWS / FOOT Water loss, type CORE RECOVERY DEPTH DESCRIPTION AND CLASSIFICATION and size of hole, GRAPHIC drilling method, OF MATERIAL groundwater level, etc. *'* × 400-410' 80% monzonite porphyry, 20% syenodiorite 1 410-417' 1 gpm 410-420' syenodiorite, grey-green, minor monzonite porphyry 410-417' fractured 420-430' Augite porphyry dike, dk. grey 4 4 430-570' monzonite porphyry, pink, minor grey syenodiorite 74 7 × × + 7 500 ÷ 505-570' some fractures t x × 11. 570-580' fractured 570-584' syenodiorite, grey-green ~ . -E.O.H. = 584' 600

INVESTIGATION KP 1-11 259 of 500

CONSULTING	ENGINE	ERS								SHEET
PROJECT	T. Pol	ley							PROJECT No.	1624
LOCATION OF	TES	тно	DLE_						GROUND ELE	VATION
DATE BEGUN	_			DAT	E FIN	ISHED			LOGGED BY_	
NOTES	%	01		5NO		90				
and size of hole,	RY	/ FO	TUR	LATIN	TH	CL	DE	SCRIPTI	ON AND CLASS	SIFICATION
drilling method,	COVE	SMO	NUTE	NITIC	DEP	APHI			OF MATERIAL	÷
erc.	RE(вго	~ 8	MO		GR				
	-					1	0-3' 3-10'	overburden	1 te, light brown, oxidi:	zes, fractured
				XX		/	10-400'	syenodiori	te, grey-green	
	[1,1				
	-					!				
				-		1'.				
70-85' 2 gpm				E		1.				
70-85' fractured	-			-	1	1.				
				1	100 .					
						1				
	-									
	Ľ					1-1				8
100	-									
160-200' 15 gpm	-					- '				
160-200° fractured	Ľ			Ē		11			-	
				F	200	1.1				
	-					-1'-				
	Ē](;)				
	-									
250-310' 50 mm						5.1				
250-310' fractured				-		-, ,				
	-			-		,				
	Ē			-	300	,				
	-			-						
	-			-		- 7.				
	E			-		1:1				
	-			=		11				18
340-455' fractured	-					-				
						1:1				
						1				

*

CONSULTING	ENGINE	ERS					ST HOLL I	_00	SHEET 2
PROJECT	TPO	lley			-			PROJECT No. 16	24
LOCATION OF	TES	THO	DLE _		-			GROUND ELEVA	
DATE BEGUN				DAT	E FIN	SHED		LOGGED BY	
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	BLOWS / FOOT	MOISTURE CONTENT %	MONITORING	DEPTH	GRAPHIC LOG	DESCRIPTIO	ON AND CLASSIF OF MATERIAL	ICATION
340-455' fractured					600		400-430' Augite por 430-560' syenodiori E: O. H. = 560'	rphyry dike, dk. grey ite, light grey-green	
						-			

Knight Piésold Ltd. CONSULTING ENGINEERS

APPENDIX C

BOREHOLE LOGS



.

Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 262 of 500

125

69

5

- 1

-

IMPERIAL METALS CORPORATION

	Property	Mount Polley		Location			1	Correct Din:	-90*	1		-
	Hole No .:	95R-1		Equipment				True Bre.				0
	Commenced:	July 8,1995		Flevetion	1137. 24 m.		-	Survey at				
1	Completed	July 14, 1995		Size	6"			A Parovaria	-	1		
	Coordinates	1550.61 M	22/2.35E	Com Stored				Langth	1600	11.1		
	Date	July 14 1995		Logad Bu	Dad Devall			The seal Feats	400IL			
From	Ta	10417 14 1575	and the second	Loverd By	Kad r esan			Cadsoar Peac:			0.11.0	D
Fact	19	Sub	Description	Sample	From	10	Lgu	Kec.	Au	lotal Cu	Unde Cu	Ratio
Fees	10	SVD	Description	No.	Feet			70	02/1	ppm	ppm	76
10	10		sychodionite, green chilontic, abundant epitdole, mmor monzorute porphyry #1				1-1-1-1-1		0,003	887		
10	20		10% syenodiorite, 30% monzonite porphyry #1,			1			0.004	1320		
20	30		monzonite porphyry, pink, K-spar rich, magnetic						0.001	179		
30	40		visible py						<001	75	_	
40	50					A		6 A	0.002	112		
50	60		svenodiorite, grey, porphyritic						0.004	584		
60	70	1					1		0.002	420	-	
70	80	1	50/50 syenodiorite and monzonite porphyry, magnetic		A CONTRACT OF A				0.002	722		
80	90		monzonite porphyry #1 as above at 20 fL, magnetic	1	Sector and the sector of the s	()	Line and	in the second second	<001	225		
90	100		· · · · · · · · · · · · · · · · · · ·						<00]	330		
100	110	1	70% monzonite porphyry #1, 30% syenodiorite	in a start of the					< 001	158		
110	120		svenodiorite, light grey, porphyritic, white plagioclase phenos						<001	34	1	
120	130								<001	140		
130	140		dark green besaltic volcanic, local epidote + magnetite						<001	195		
140	150			1					<001	90	and the second	
150	160	4	80% monzonite porphyry, 30% basaltic volcanic as at 130 ft.						<001	127		
160	170		monzonite porphyry # 1, buff, white plagioclase phenos 2-3 mm.				1		<001	295		
170	180		90% basaltic volc as above @ 130'; 10% mpp#1		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1				< 001	144		
190	190		90% basaltic volc as above @ 130; 30% mpp#1						<001	26	1	
190	200		sydr, it grey matrix, whit plag phenos 2-3mm.	A					<001	25		
200	210	1							< 001	94		
210	220								<001	79		
220	230								< 001	54		
230	240		sydr. It grey matrix, white plag phenos 2-3mm				1		< 001	57		
240	250	1					-		< 001	124		-
250	260						1		< 001	270		
260	270								< 001	210		
270	280						-		< 001	126		
280	290								0.007	\$79		
290	300		90% ok mon#1: 10 % sydt as above at 190' noss by						0.005	1120		
300	310		few malachite amine						0.003	1515		
310	320		for malachite grains						0.014	1690		
320	330		i i i i i i i i i i i i i i i i i i i						0.001	872		
330	340		10% nk mon#) as above 90% grey north syde						< 001	122		
340	350		a source of the second se		1				0.001	572	-	-
350	360		montel ale addite alege address						0.001	450		
360	370	A Printer and	SO/SO be month) and gree and poss intr bearing						0.000	202		
370	380		and a participant and boy stat, possible, orong the						< 001	419		
380	390			-		-			0.000	513		
390	400								0.007	482		
400	410						-		0.001	879		-
410	420		* visible on						0.008	1375		
420	430		* visible en						0.004	253		
430	440		* *						0.007	1605		
440	450						-		0.000	912		
450	460								0.003	1160		
	1000						1		0.000	11001		1
		-	-END OF HOLE-				-		-			
			- MATTER AT ALL MADE				-		-			

PAGE 1

1	2 A		<u> </u>			-			-			
h	1. Aug		ALC ALC ALC ALC ALC A									
		*		95R-	-2		*					
	Property:	Mount Polley		Location:	1		Correct Dip:	-90		1		
	Hole No .:	95R-2		Equipment:			True Brg.:					
	Commenced:	14-Jul-95		Elevation:	1100 m.		Survey at:					1.000
	Completed:	31-Jul-95		Size:	6		% Recovery:					1
	Coordinates:	2/85N/2850E		Core Stored:			Length:	, 295 FL				
	Date:	10-Aug-95		Logged by:	R. Pesalj		Unusual Feat.:					
From	To			Sample	From	To	Lgth.	Rec.	Au	Total Cu	Oxide Cu	Ratio
Feet	1.1.1	Syb	Description	No.				%	Oz/T	ppm	ppm	%
0	10		syenodiorite, limonite coated cuttings, weathered beige to light brown						<.001	179		
10	20								0.001	295		
20	30		syenodlorite, grey disseminated pyrite visible, minor weathered syenodlorite as above						0.001	566		
30	40			1966 - 1966 - 1966 - 1966 - 1966 - 1966 - 1966 - 1966 - 1966 - 1966 - 1966 - 1966 - 1966 - 1966 - 1966 - 1966 -					<.001	277		
40	50		syenodiorite, light grey, slightly bleached, minor epidote and pyrite						<.001	292		
50	60		•						<.001	160		
60	70		•						0.001	257		
70	80		syenodiorite, dark grey, highly pyritic; pyrite 8-10%						<.001	368		
80	90		•						<.001	651		
90	100	6							<.001	363		
100	110		syenodiorite, light grey, 10% of oxidized cuttings						<.001	353		
110	120		as above, no oxidation, slightly bleached						<.001	231		
120	130	r	 limonite coated, disseminated magnetite and pyrite abundant 						<.001	119		
130	140		syenodiorite, light grey, fresh, disseminated pyrite, epidote, minor disseminated magnetite						<.001	200		
140	150		•						<.001	319		
150 Z	160								<.001	231		
160 1	170		•						<.001	165		
170	180		 Fragments, 2-3 cm fault 						<.001	88		
180 ≥	190		 Fragments, 2-3 cm fault 						<.001	188		
190 0	200		 Fragments, 2-3 cm fault 		1.1				<.001	165		
200 2	210		 Fragments, 2-3 cm fault 	1 1 1					<.001	149		
210	220		 Fragments, 2-3 cm fault 	faul					<.001	241		
220	230		 Fragments, 2-3 cm fault 	1					<.001	192		
230 230	240		syenodiorite, light grey, fresh, disseminated pyrite abundant, minor magnetite						<.001	198		
240	250		* Fragments, 2-3 cm fault						<.001	183		
250 8	260		* Fragments, 2-3 cm fault						<.001	118		
260	270		* Fragments, 2-3 cm fault						<.001	139		
270	280		Fragments, 2-3 cm fault						<.001	207		

Page 1

٠,

ŝ.

						-	1.1		1			
	3. S.			95R-	2							
	Property:	Mount Polley		Location:			Correct Dip:	-90				
	Hole No .:	95R-2		Equipment			True Brg.:					
· · · · ·	Commenced:	14-Jul-95		Elevation:			Survey at:					
	Completed:	31-Jul-95		Size:	6"		% Recovery:					
14	Coordinates:	4		Core Stored:			Length:	, 295 FL				
	Date:	10-Aug-95		Logged by:	R. Pesal]		Unusual Feat.:					
From	To			Sample	From	To	Lgth.	Rec.	Au	Total Cu	Oxide Cu	Ratio
Feet		Syb	Description	No.				%	Oz/T	ppm	ppm	%
280	290		* Fragments, 2-3 cm fault						<.001	291		
290	295		" Fragments, 2-3 cm fault	-					<.001	454		
			End of Hole	-								

1

 $_{\lambda}^{uv}$

a y

1

.....

*

Page 2

.

.

٠

1

1....

z.

...

1.3

	Property:	Mt. Polley		Location:			Correct Dip:	-90				
	Hole No .:	95R-3		Equipment:			True Brg.:					
	Commenced:	01-Aug-95		Elevation:	1121.69 4		Survey at: ,					
9	Completed:	02-Aug-95		Size:	6"	1	% Recovery:		-			
	Coordinates:	2416.59N/24	60.16E	Core Stored:		1	Length:	505 FL				1
	Date:	11-Aug-95		Logged by:	R. Pesal		Unusual Feat.:					1
From	To			Sample	From	To	Lgth.	Rec.	Au	Total Cu	Oxide Cu	l
Feet		Syb	Description	No.				%	Oz/T	ppm	ppm	1
0	10		syenodiorite, grey-green, weathered, trace Ilmonite on fractures						<.001	483		
10	20								<.001	433		1
20	30								<.001	450		1
30	40		syenodiorite, rusty limonite coated fractures, highly oxidized						<.001	243		
40	50								<.001	330	1	•
50	60		monzonite porphyry #1, salmon pink, iron oxides on fractures						<.001	581		
60	70		50/50 syenodiorite and monzonite porphyry #1 rwsfycoloured cuttings						<.001	588		
70	80		syenodiorite, light brown, minor pink monzonite porphyry #1						<.001	433		
80	90		•						<.001	141		
90	100		•			· · · · ·			<.001	195		
100	110								<.001	178		
110	120		60% monzonite porphyry #1; 40% syenodiorite, light brown and pink						<.001	517		
120	130								<.001	224		1
130	140		•	1					<.001	272		1
140	150		40% monzonite porphyry #1, 60% syenodlorite, limonite coating on fracture						<.001	160		1
150	160								<.001	176		-
160	170		monzonite porphyry #1, beige fine grained matrix, white plagiocase laths 2-3 mm long						<.001	192		
170	180								<.001	14		1
180	190								<.001	89		Î
190	200	43	syenodiorite, grey-green, chloritic, some epidote, trace disseminated pyrite						<.001	257		-
200	210								<.001	638		Î
210	220		syenodiorite, light brown, oxidised disseminated pyrite 2-3%, abundant limonite						<.001	284		
	Property:	Mt. Polley		Location:			Correct Dio:	-90			-	1

-

_ _ _ _ _ _ _ _ _ _ _ _

•

20

•

	Hole No .:	95R-3		Equipment:			True Brg.:					Ī
	Commenced:	01-Aug-95		Elevation:			Survey at:					Γ
	Completed:	02-Aug-95		Size:	6		% Recovery;					Γ
	Coordinates:	2440N/2700E		Core Stored:			Length:	505 FL				T
	Date:	11-Aug-95		Logged by:	R. Pesal]		Unusual Feat.:					Г
From	To			Sample	From	To	Lgth.	Rec.	Au	Total Cu	Oxide Cu	T
Feet		. Syb	Description	No.				%	Oz/T	ppm	ppm	Γ
· 220	230								<:001	213		T
230	240								<.001	298		T
240	250		•						<.001	257		T
250	260								<.001	161		I
260	270		•						<.001	238		L
270	280		•						.001	748		
280	290		syenodiorite, green, chloritic, non-oxidised disseminated pyrite 5-6%						.001	818		
290	300					10000			<.001	381		Г
300	310					(0.002	479		T
. 310	320		syenodiorite, light grey and pink, slightly oxidised, disseminated pyrite 1%						<.001	185		Ī
320	330		•				1		.001	281		Г
330	340		•						<.001	446		Γ
340	350	:	50/50 syenodiorite and monzonite porphyry #1, slightly oxidised, disseminated pyrite 3%						<,001	423		
350	360		70/30 monzonite porphyry #1 and syenodiorite, slightly oxidised, disseminated pyrite <1%		-				.001	251		
360	370		50/50						0.003	259		
370	380		syenodiorite grey-green, non-oxidised, chloritic, disseminated pyrite 5%						0.001	369		
380	390								<.001	370		Г
390	400								0.001	348		ſ
400	410								0.001	348		ſ
410	420								<.001	665		
420	430	5 15	syenodiorite grey and pink, feldspathised, abundant epidote, <1%pyrite						<.001	328		
430	440							1	<.001	220		ſ
440	450					1.0.01			<.001	295		Γ
	460		•						<.001	226		ſ

ㅋㅋ?ㅋㅋ

p a c a c c c

	Hole No.:	95R-3		Equipment:			True Brg.:					
	Commenced:	01-Aug-95		Elevation:			Survey at:					
	Completed:	02-Aug-95		Size:	6"	2	% Recovery:					
	Coordinates:	· . 1		Core Stored:			Length:	505 FL				
	Date:	11-Aug-95		Logged by:	R. Pesalj		Unusual Feat.:					
From	To			Sample	From	To	Lgth.	Rec.	Au	Total Cu	Oxide Cu	Ratio
Feet		Syb	Description	No.				%	Oz/T	ppm	ppm	%
460	470		syenodiorite grey-pink, feldspathised, abundant epidote, disseminated <1%pyrite						<.001	327		н
470	480								<.001	212		
480	490							1	<.001	266		
490	500								<.001	254		
			End of Hole									

...

1.1

311. |41.2

41.04

 $^{*}r$

-

1.12

1.1

÷

T

	Property:	Mount Polley		Location:			Correct Dip:	-90				
	Hole No .:	95R-4		Equipment:			True Brg.:					
	Commenced:	03-Aug-95		Elevation:	1050.43.	1.	Survey at:					
	Completed:	05-Aug-95		Size:	6*		% Recovery:					
	Coordinates:	3250.26 M/13	04.90E	Core Stored:			Length:	405FL				
	Date:			Logged by:	R. Pesalj		Unusual Feat.:					•
From	To		-	Sample	From	To	Lgth.	Rec.	Au	Total Cu	Oxide Cu	1
Feet		Syb	Description	No.				%	Oz/T	ppm	ppm	
0	10		brown glacial till, minor fragments of monzonite						0.003	247		•
			monzonite porphyry #1 reddish-maroon ground mass,									
10	20		white plaglocase phenos						<.001	261		
20	30		•						<.001	242		
30	40		•			1			<.001	343		1
40	50		•						<.001	292		
50	60								<.001	383		
60	70		•						<.001	56		
70	80		•						<.001	33		1
80	90								<.001	40		
90	100		monzonite porphyry #1 as above, abundant limonite, well oxidised						<.001	50		
100	110		monzonite porphyry #1 as above but less oxidised, reddish-maroon						<.001	35		-
110	120		•						<.001	70		1
120	130								<.001	87		-
130	140		•						<.001	118		
140	150		syenodiorite, grey-green, chloritic, disseminated pyrite 5-6%, unoxidised						<.001	105		
150	160								0.002	138		
160	170		syenodiorite as above but slightly oxidised, minor monzonite porphyry #1						<.001	55		
170	180		•						<.001	112		j
180	190								<.001	158		1
190	200		syenodiorite grey-green, chloritic, unoxidised, disseminated pyrite 2-3%						<.001	113		1
200	210	5	 slightly oxidised 						<.001	158		1
210	220		•				18		<.001	155		1
220	230		•						<.001	162		1
230	240		syenodiorite, green-grey, chloritic, unoxidised, disseminated pyrite 3-5%						0.019	255		

'e No.

95R

9 St

95R-4

- 1

COLI

.

p. 1

	Property:	Mount Polley		Location:			Correct Dip:	-90				
	Hole No .:	95R-4		Equipment:			True Brg.:					
	Commenced:	03-Aug-95		Elevation:			Survey at:		-			
	Completed:	05-Aug-95		Size:	6"		% Recovery:					
	Coordinates:	3		Core Stored:			Length:	405FL				
	Date:			Logged by:	R. Pesal		Unusual Feat.:					
From	To		-	Sample	From	To	Lgth.	Rec.	Au	Total Cu	Oxide Cu	Ratic
Feet		Syb	Description	No.				%	Oz/T	ppm	ppm	%
240	250		mafic tuff, green, chlorite and epidote alteration, disseminated pyrite 3-5%						<.001	160		
250	260								<.001	162		
260	270		•						0.001	171		
270	280		monzonite porphyry #1, plnk and grey, unoxidised, disseminated pyrite 2-3%						<.001	574		
280	290		•						0.001	699		
290	300		•			1			0.002	720		
300	310		•				1		0.001	557		
310	320		•						0.002	514	1	
320	330		dark green very fine grain basaltic voicanic, minor monzonite porphyry #1						0.002	650		
330	340		syenodiorite grey and pink, feldspathlsed, trace disseminated pyrite						0.001	306		
340	350								0.001	451		
350	360								<.001	415		
360	370		syenodiorite as above, trace fragments of mafic volcanic						0.002	766		
370	380		•						0.001	474		
380	390		syenodiorite pink and grey, highly feldspathised, trace pyrite						0.002	536		
390	400								0.003	649		
_			End of Hole									

INVESTIGATION KP 1-11 270 of 500

Page 2

.

-

.

.`

×i.

•

. .

	Hole No .:	95R-5		Equipment:			True Brg.:					
	Commenced:	08-Aug-95		Elevation:			Survey at:					
	Completed:	09-Aug-95		Size:	6"		% Recovery:					
	Coordinates:	9 N.		Core Stored:			Length:	260FL				
4	Date:	11-Aug-95		Logged by:	R. Pesalj		Unusual Feat.:					
From	To			Sample	From	To	Lgth.	Rec.	Au	Total Cu	Oxide Cu	Ratio
Feet		Syb	Description	No.				%	Oz/T	ppm	ppm	%
230	240		mafic tuff, green, chloritic, abundant epidote, disseminated pyrite 5%						<.001	62		
240	250		•						<.001	68		
250	250 260								<.001	96		
			End of Hole									

.

.

• •

	25		12	95R-6								
	1											
	Property:	Mount Polley		Location:			Correct Dip:	-90				
	Hole No .:	95R-6		Equipment:			True Brg.:					
	Commenced:	10-Aug-95		Elevation:	1190m.		Survey at:					
	Completed:	13-Aug-95		Size:	6°		% Recovery:					ĺ
	Coordinates:	3640N/2360E		Core Stored:		_	Length:	584FL				1
	Date:	02-Oct-95		Logged by:	R. Pesalj		Unusual Feat.:					1
From	To	1	-	Sample	From	To	Lgth.	Rec.	Au	Total Cu	Oxide Cu	î
Feet		Syb	Description	No.				%	Oz/T	ppm	ppm	1
0	10		syenodiorite, light grey, weathered, slightly oxidised surfaces						0.002	729		1
10	20								0.003	1175		-
20	30		pink fine grain monzonite, 1-2%fine grain disseminated pyrite						0.001	891		Ī
30	40								<.001	540		1
40	50								<.001	505		-
50	60								<.001	351		-
60	70					-			<.001	348		-
70	80								<.001	589		-
			svenodiorite light grey upoxidised porphyritic									i
80	90		minor monzonite						<.001	485		
90	100		nink fine grained monzonite as above at 20'						<.001	392		-
100	110		syenodiorite, light grey, unoxidised, porphyritic,						< 001	352		
110	120		monzonite , pink, fine grain 10% syenodiorite as						<.001	403		-
120	130								<.001	419		-
130	140		syenodlorite, grey-green, chloritic, minor monzonite as above						<.001	249		-
140	150		•	1					<.001	378		1
150	160								<.001	386		1
160	170								<.001	404		Í
170	180								<.001	477		1
180	190		monzonite, pink, fine grain minor grey syenodiorite, 2-3% pyrite						<.001	433		-
190	200		•						<.001	659		1
200	210	-	Augite porphyry dyke, dark grey, unoxidised		-				0,003	557		1
210	220		monzonite porphyry, pink, fine grain, 3-5%						0.002	670		-
220	230		*						0.001	833		-
												-
-												1
-	Property	Maunt Dellars		Locations			Correct Die:					1
	Property:	Mount Polley		Location:			Correct Dip:	-90				ļ

.

1

1

1.

14 64

14

1.

1

	Hole No .:	95R-6		Equipment:			True Brg.:					
	Commenced:	10-Aug-95		Elevation:			Survey at:					
	Completed:	13-Aug-95		Size:	6"		% Recovery:					
	Coordinates:			Core Stored:			Length:	584FL				
-	Date:	02-Oct-95		Logged by:	R. Pesal		Unusual Feat.:					
From	To			Sample	From	To	Lgth.	Rec.	Au	Total Cu	Oxide Cu	Ratio
Feet		Syb	Description	No.				%	Oz/T	ppm	ppm	%
230	240		monzonite porphyry, pink, fine grain 3-5% disseminated pyrite						<.001	767		
240	250					-			0.001	942		
250	260								0.004	1185		
260	270								0.005	1360		
270	280								0.005	2020		
280	290					-			0.003	1350		
290	300		syenodiorite, green-grey, chloritic, disseminated pyrite 2-4%						0.002	909		
300	310		monzonite porphyry, plnk fine grain, 3-5% disseminated pyrite						0.002	1400		
310	320		·						0.001	3320		
320	330					-			0.003	1200		
330	340								0.002	1470		
340	350						1		<.001	1025		
350	360								0.003	1950		
360	370				1				0.002	1240		
370	380								0.003	1700		
380	390								<.001	1455		
390	400		50/50 syenodiorite and monzonite porphyry						0.001	1980		
400	410		20/80 syenodiorite and monzonite porphyry						0.005	1765		
410	420		syenodiorite grey-green, minor monzonite porphyry						0.003	1725		
420	430		augite porphyry dyke, dark green, unaltered						0.002	579		
430	440		monzonite porphyry, pink, minor arey svenodiarite						<.001	636		
440	450					-			0.001	718		
450	460								<.001	707		
460	470	-				-			0.002	804		
470	480					-			0.001	651		
480	490								<.001	777		
490	500		•			-			0.002	1160		
500	510								0.003	1250		
	Property	Mount Polley		Location'			Correct Din	-90				

히 하 다

٠

.

	Hole No .:	95R-6		Equipment:			True Brg.:					
	Commenced:	10-Aug-95		Elevation:			Survey at:		[
2	Completed:	13-Aug-95		Size:	6"		% Recovery:				1	
	Coordinates:			Core Stored:			Length:	584Ft				
	Date:	02-Oct-95		Logged by:	R. Pesalj		Unusual Feat.:					
From	To			Sample	From	To	Lgth.	Rec.	Au	Total Cu	Oxide Cu	Ratio
Feet		Syb	Description	No.				%	Oz/T	ppm	ppm	%
510	520		monzonite porphyry, pink, minor grey syenodiorite						0.002	624		
520	530		*						0.005	1110		
530	540		•						0.008	1860		
540	550								0.006	1435		
550	560								0.006	1285		
560	570								0.008	1475		
570	580		syenodiorite, grey-green, chloritic, disseminated pyrite 1-2%						0.012	2330		
580	584		•						0.009	4280		
-			End of Hole									

1

×.

14

 $e^{2k+i\phi}$

•

.

*

h n n n

 $\mathbb{R}^{N_{1}}$

•

-

1

2

*

Parts.

a the second second second

Property:	Mount Polley		Location:		1	Correct Dip:	-90				
Hole No .:	95R-7		Equipment:			True Brg.:					
Commenced:	14-Aug-95		Elevation:	1113.89		Survey at:					
Completed:	19-Aug-95		Size:	6		% Recovery:					
Coordinates:	2189.20H/29.	64.25 E	Core Stored:			Length:	560FL				
Date:	02-Oct-95		Logged by:	R. Pesal		Unusual Feat.:					
To			Sample	From	То	Lgth.	Rec.	Au	Total Cu	Oxide Cu	Ratio
	Syb	Description	No.				%	Oz/T	ppm	ppm	%
10		syenodiorite, light brown, oxidised						0.002	326		
20		syenodlorite, grey-green, chloritic, disseminated pyrite 3-5%						<.001	360		
30								<.001	411		
40								<.001	579		
50		•						<.001	561		
60								<.001	270		
70					1			0.004	335		
80								0.01	199		
90								0.005	402		
100								<.001	208		
110	and the second second						_	<.001	144		
120								0.002	187		
130						1000 C 1000		0.001	210		
140		-						<.001	241		
150								<.001	731		
160								<.001	150		
170		-						<.001	489		
180							1	<.001	156		
190	1000000		1					< 001	358		
200							_	< 001	294		
210								< 001	545		
220								< 001	208		
230							1-	< 001	215		
240					-			< 001	260		
250								< 001	287		
260							1	< 001	251		
270	10-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-							<.001	374		
280		•						<.001	-265		
200								1.001	200		
	Property: Hole No.: Commenced: Coordinates: Date: To 10 20 30 40 50 60 70 80 90 100 100 110 120 130 100 110 110 120 130 140 150 100 110 120 130 140 150 100 110 200 210 220 230 240 220 230 240 220 230 240 220 230	Property: Mount Polley Hole No.: 95R-7 Commenced: 14-Aug-95 Coordinates: 2/89. 20/M/29. Date: 02-Oct-95 To Syb 10	Property: Mount Polley Hole No.: 95R-7 Commenced: 14-Aug-95 Coordinates: 2/89, 30 // 292 // 2.5 E Date: 02-Oct-95 To	Property: Mount Polley Location: Hole No.: 95R-7 Equipment: Commenced: 14-Aug-95 Size: Coordinates: 2/39. 20 // 29.6 // 25 E Core Stored: Date: 02-Oct-95 Logged by: To	Property: Mount Polley Location: Hole No.: 95R-7 Equipment: Commenced: 14-Aug-95 Elevation: ///3.84.without polley Commenced: 19-Aug-95 Size: 6" Coordinates: 2189.80.1/129.64.42.5.5 Core Stored: Loggeb by: R. Pesaij To Sample From Sample From 10 syenodiorite, light brown, oxidised Image: polytic 3-5% Image: polytic 3-5% 30 - - Image: polytic 3-5% Image: polytic 3-5% 30 - - Image: polytic 3-5% Image: polytic 3-5% 30 - - Image: polytic 3-5% Image: polytic 3-5% 30 - - Image: polytic 3-5% Image: polytic 3-5% 30 - - Image: polytic 3-5% Image: polytic 3-5% 30 - - Image: polytic 3-5% Image: polytic 3-5% 30 - - Image: polytic 3-5% Image: polytic 3-5% 30 -	Property: Mount Policy Location: Hole No.: 95R-7 Equipment:	Property: Mount Polley Location: Correct Dip: Hole No.: 95R-7 Equipment: $V73.894m$, Survey at; Commerced: 14-Aug-95 Size: 6* 95 Recovery: Coordinates: 2/84.80//286/4286 Core Stored: Unusual Feat: Unusual Feat: To 02-Oct-95 Logged Dy: R. Pesaj Unusual Feat: To 02-Oct-95 Sample From To Length: 02-Oct-95 Symoutorite, light brown, oxidised No. Commerced: Comerced: Unusual Feat: To symoutorite, grey-green, chloritic, disseminated No. Comerced: Comerced:	Property: Mount Polacy Location: Control [p: -90 Hole No.: 95R.7 Equipation: ///3.87 \pm . Surveys: Completed: 194.40g-95 Size: 6" % Recovery: Completed: 194.40g-95 Size: 6" % Recovery: Corest Logged by: R.Pesal Unusual Feat: Source: Legght: Source: Source: Legght: Source: No. Legght: Source: No. Rec. % 10 Syenoclicite, Ight brown, oxidised No. Image: Source: Image: Source: Image: Source: Image: Source: Image: Source: Image: Source: Monte: Source: Image: Source: I	Property: Mount Polley Location: Correct Dip: -90 Hole No:: 958-7 Equipment: Image: Survey at: Image: Image:	Property: Mount Polaty Correct Dip: 90 \sim Hale No: 95R.7 Equipment: I Tors Big:. \sim \sim Commenced: 14.4ug-95 Survey at: Survey at: \sim Survey at: \sim \sim Completed: 19.4ug-956 Corre Stored: \sim No \sim No \sim \sim Date: 02-0C+55 Corre Stored: \sim No \sim </td <td>Property: Hola No:Mount Polary Equipment:Correct Dip: FU-90Correct Dip: Tow BSR.7-90Correct Dip: Correct Dip: Tow BSR.7-90-90-90-90Complated: Coordinates: Data:02-06-05Coord Stored: Data: SyllCoord Stored: DescriptionReATotal Coordinates: Tow BSR.7Total Dip: Total Dip: Dip: SyllReATotal Coordinate: Total Dip:<br <="" td=""/></br></br></br></br></br></br></br></br></td>	Property: Hola No:Mount Polary Equipment:Correct Dip: FU-90Correct Dip: Tow BSR.7-90Correct Dip: Correct Dip: Tow BSR.7-90-90-90-90Complated: Coordinates: Data:02-06-05Coord Stored: Data: SyllCoord Stored: DescriptionReATotal Coordinates: Tow BSR.7Total Dip: Total Dip: Dip: SyllReATotal Coordinate: Total Dip:

-	-	-	-
	5		1
- 23	- 1	T T	
	-		

.

.

-

1

٩.

÷

290	300								<.001	365		
300	310		•	1					<.001	217		
310	320								<.001	392		
	Property:	Mount Polley		Location:	1		Correct Dip:	-90				
	Hole No.:	95R-7		Equipment:			True Brg.:					
	Commenced:	14-Aug-95		Elevation:			Survey at:					
	Completed:	19-Aug-95		Size:	6		% Recovery:					
	Coordinates:	· · · · · · · ·		Core Stored:			Length:	560Ft				
-	Date:	02-Oct-95		Logged by:	R. Pesalj		Unusual Feat.:					
From	To			Sample	From	To	Lgth.	Rec.	Au	Total Cu	Oxide Cu	Ratk
Feet		Syb	Description	No.				%	Oz/T	ppm	ppm	%
320	330		syenodiorite, grey-green, chloritic, disseminated pyrite 3-5%						<.001	308		
330	340								<.001	214		
340	350			-					<.001	284		
350	360								<.001	275		
360	370								<.001	462		
370	380								<.001	213		
380	390								<.001	212		
390	400		•						<.001	277		
400	410		Augite porphyry dyke, dark grey and black, unaitered						<.001	252		
410	420		-						<.001	229		
420	430				-				<.001	115		
430	440		syenodiorite, pale grey-green, disseminated pyrite						< 001	119		
440	450					-			< 001	514		-
450	460							-	< 001	805		
450	470								< 001	405		
470	480								< 001	331		
490	400						The second s		< 001	173		
400	450								< 001	404		
430	500								<.001	210		
510	510								< 001	262		
510	520								1001	202		
520	530								4,001	209		
530	540								<.001	197		
540	550		•						<.001	224		
550	560								<.001	270		[

Knight Piésold Ltd. CONSULTING ENGINEERS

APPENDIX D

BASELINE GROUNDWATER QUALITY DATA TO THE END OF 1995



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 277 of 500

•

Knight Piésold Ltd.

CONSULTING ENGINEERS

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

OPEN PIT/MILLSITE BASELINE GROUNDWATER QUALITY

FORMDATA/IASHWOGALITY/APPE	SIR XLS													Lass Update:	7 May 96
		1994 BC Er Water Qual	nvironment ity Criteria	MP89-107	MP89-107	MP89-146	MP80-146	MP89-151	MP89-15/	Q5.R.1	R-95-4	8.05.41	R.95.5	8.95.6	R-95-7
		Freshwater Aquatic Life	Drinking Water	Nov 25/89	Apr 5/90	Nov 25/89	Apr 5/90	Nov 25/89	Apr 5/90	Sept 20/95	Sept 21/95	Sept 21/95	Sept 21/95	Sept 20/95	Sept 22/95
Physical Tests											-		-		
Conductivity (umhos/cm)				380	153	81	70.9	150	335	207	206	206	331	322	191
Total Dissolved Solids										144	146	148	241	236	133
Hardness	CaCO3		in the second	167	78.7	30.6	27.0	71.2	73.0	102	72	70.6	171	167	87.8
pH		1224	6	7.83	7.26	6.97	6.92	7.50	7.25	7,79	7.89	8.07	8.23	7.67	7,42
Total Suspended Solids				interest	100 V.	10000	(TOUR DESIGNATION OF THE OWNER OF			8	13	11	28	44	5
Turbidity (NTU)										1	5,3	5,8	9,8	11.7	3.7
Dissolved Anions														-	1
Alkalinity	Total CaCO3					100				124	99.3	101	155	145	60.4
Chloride	CI									< 0.5	<0.5	< 0.5	< 0.5	0.5	<0.5
Fluoride	F	1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1								0.19	0.21	0.2	0.41	0.99	0.6
Sulphate	SO4			1000					2112	2	18.2	18.3	36.4	42.2	38.3
Nutrients															
Ammonia Nitrogen	N	222	222							< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005
Nitrate Nitrogen	N								-	0.014	< 0.005	< 0.005	< 0.005	0.008	< 0.005
Nitrite Nitrogen	N		2000		-	32221	-		Serie:	0.001	< 0.001	0.001	0.001	0.007	0.002
Dissolved ortho-Phosphate	P									0.021	0.01	0.01	0.004	0.001	0,18
Total Dissolved Phosphate	P			****		-				0.021	0.01	0.01	0.004	0,001	0.18
Total Phosphorus	P									0,027	0.021	0.022	0.021	0,013	0,279
Cyanides															
Total Cyanide	CN		0,2			-				< 0.001	<0,001	< 0,001	<0.001	< 0.001	< 0.001
Total Metals															
Aluminum	T-AI	0.005-0.1	2000	0.14	0.50	0.37	1.57	0.74	0.66	0.029	0.308	0.244	0.502	1.31	0.05
Antimony	T-Sh	12000	++++							< 0.0001	< 0.0001	0,0002	0.0001	0.0001	0.0008
Arsenic	T-As	0.05	0.025	0.0004	0.0014	0.0015	0,0018	0.0013	0.0010	8000.0	0.0048	0.0049	0.0021	0.0049	0.0047
Barium	T-8a		1							0.02	< 0.010	< 0.010	0.012	0.027	< 0.010
Berythum	T-Be					++++				< 0,005	< 0.005	< 0.005	< 0,005	< 0,005	< 0,005
Bismuth	T-Bi						****			< 0.10	<0.10	< 0.10	<0,10	<0.10	< 0.10
Boron	T-8		5			****	****	****	++++	< 0.10	0,27	0.26	<0,10	<0.10	< 0.10
Cadmium	T-Cd	0.0002-0.0018	0,005	<0.0002	0.0012	0.0002	0.0005	< 0.0002	0.0003	< 0.0002	< 0.0002	< 0,0002	< 0.0002	< 0.0002	0.001
Calcium	T-Ca								****	32,3	25,7	24.7	6t.2	45	21.7
Chromium	T-Cr	0.002-0.02	0.05	0.001	0.002	0.001	0.006	0.003	0.002	< 0.001	< 0.001	< 0.001	0.001	< 0:001	< 0.001
Cohalt	T-Co			< 0.001	0.001	< 0.001	0.001	< 0.001	< 0,001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	0,002
Copper	T-Cu	0.002-0.004	1	0.018	0.050	0.26	0.41	0.13	0.072	0.002	0.002	0.002	0.002	0.009	< 0.001
Iron	T-Fe	0.3	0.3	< 0,03	0.07	0.28	1.33	1.80	0.37	< 0.030	0,234	0,201	0.627	0.785	0.529
Lead	T-Pb	0,001-0.007	0,01	< 0,001	0.002	0.003	0.009	0.010	0.004	< 0.001	< 0,001	< 0.001	< 0,001	0.001	< 0.001
Magnesium	T-Mg					****	****		****	5.5	3.14	3.03	8,58	14.1	8,78
Manganese	T-Mn		0.05	1.24	1.67	0.011	0.025	0.038	0.030	0.013	0.043	0.041	0.1	0.027	0,64
Mercury	T-Hg	0.0001	0.001	0,00005	0.00006	0.00005	<0.00005	0,00007	< 0,00005	< 0.00001	< 0,00001	<0,00001	< 0,00001	0.00002	<0.00001
Molybdenum	T-Mo		-	0.005	0.002	0.010	0.002	0,009	0.009	0,01	0,038	0.039	0.031	0.028	0.004
Nickel	T-Ni	0.025-0.15	****	< 0.001	< 0.001	0.001	0.003	0.004	< 0.001	< 0.001	0.001	< 0.001	0.002	0.004	0,002
Selenium	T-Se	0.001	0,01		****				1000 C	< 0.0005	0.0007	0.0006	< 0.0005	< 0.0005	0.0018
Siticon	T-Si	12012				1111			1250	8.43	9.27	9.02	10.9	16.5	23.2

Notes 1) Results are expressed as milligrams per litre except for pH, Conductivity (unihos/cm), and Turhidity (NTU).

2) halk-bold shaded values indicate excedance of the BC Environmental freshwater aquatic life criteria. (Approved and Working Criteria for Water Quality - 1994, BC Environment, Victoria)

3) The letter d after the monitoring well identification mane means that it is a duplicate sample, eg R-95-4d

4) A < sign mean that the value is less than the detection limit stated.

Knight Piésold Ltd. CONSULTING ENGINEERS

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

OPEN PIT/MILLSITE BASELINE GROUNDWATER OUALITY (con't)

LUNKDATAIN24WQUALITYAP	ENDC.XLS													Last Update:	7 May 96
Contraction of the second s	Concerning to the second second	1994 BC E	1994 BC Environment			I				1			-	I	T
		Water Qual	Water Quality Criteria		MP89-107	9-107 MP89-146	MP89-146	MP89-151	MP89-151	95-R-1	R-95-4	R-95-4d	R-95-5	R-95-6	R-95-7
		Freshwater	Drinking	Nov 25/89	Apr 5/90	Nov 25/89	Apr 5/90	Nov 25/89	Apr 5/90	Sept 20/95	Sept 21/95	Sept 21/95	Sept 21/95	Sept 20/95	Sept 22/95
Total Metals		Aquatic Life	Water		-										
Lotal Metals															
Silver	T-Ag	0.0001	****	0.0002	<0.0001	< 0.0001	0.0001	<0,0001	0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0,0001	< 0.0001
Strantium	T-Sr	alter.			****			****	****	0,117	0.066	0.065	0,186	0,466	0,043
Titanium	T-TI					****				<0,010	0.013	0.012	0,024	0.011	< 0,010
Uranium	T-U		0.1							0,00054	0_00031	0,00031	0,00046	0,00089	0,00007
Vanadium	T-V	-			****		****			< 0.030	<0_030	< 0.030	< 0,030	< 0.030	< 0.030
Zinc	T-2n	0,03	5	< 0.005	< 0,005	<0.005	0,015	< 0.005	< 0.005	< 0.005	<0,005	< 0.005	0.007	< 0.005	0.066
Dissolved Metals															
Aluminum	D-AI			0,010	0.018	0.065	0.22	0,058	0,096	0.019	0.016	0.027	0,043	0,03	0.01
Antimony	D-Sb							****		< 0.0001	0,0001	0.0001	0,0002	< 0.0001	0.0006
Arsenic	D-As			0.0002	0,0012	0.0010	0.0012	0.0003	0.0009	0,001	0.0044	0.0045	0.0015	0,0041	0,0047
Barium	D-Ba	4000			-	-	****			0.02	< 0.010	< 0.010	< 0,010	0.023	<0,010
Beryllium	D-Be				****					< 0.005	< 0.005	< 0.005	< 0,005	< 0.005	< 0,005
Bismuth	D-BI	(ashe);						****		<0.10	<0,10	< 0.10	< 0.10	< 0.10	< 0.10
Boron	D-8					-				<0.10	0.27	0,26	< 0.10	< 0,10	< 0.10
Calmium	D-CJ			< 0.0002	0.0010	< 0.0002	< 0.0002	< 0.0002	< 0.0002	< 0.0002	< 0.0002	< 0.0002	< 0.0002	< 0.0002	0.0009
Calcium	D-Ca			54.8	26.0	10.4	9.05	23.9	24.3	31.9	23.8	23.3	55.7	44.1	21.1
Chromium	D-Cr			< 0.001	< 0.001	<0.001	< 0.001	0.001	0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001
Cobalt	D-Co			< 0.001	< 0.001	<0.001	< 0.001	< 0.001	< 0.001	<0.001	< 0.001	<0.001	< 0.001	< 0.001	0.002
Conper	D-Cu	-	0.000	0.013	0.018	0.21	0.24	0.025	0.021	0.002	< 0.001	< 0.001	< 0.001	0.004	< 0.001
Iron	D-Fe			<0.03	< 0.03	< 0.03	<0.03	0.03	< 0.03	< 0.030	< 0.030	< 0.030	0.051	< 0.030	0.407
Lead	D-Pb		1111	< 0.001	< 0.001	0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001
Magnesium	D-Mg			7.08	3.26	1.10	1.05	2.73	2.91	5.44	3.03	3	7.83	13.8	8.56
Manganese	D-Mn			1.17	1.17	0.007	0.015	<0.005	0.030	0.012	0.036	0.035	0.069	0.023	0.617
Mercury	D-He			< 0.00005	< 0.00005	<0.00005	< 0.00005	< 0.00005	< 0.00005						
Molyhdenum	D-Mo			0.007	0.007	0.003	0.002	0.006	0.008	0.011	0.038	0.038	6.031	0.028	0.004
Nickel	D-Ni	1	1000	<0.001	< 0.001	<0.001	0.003	<0.001	<0.001	<0.001	< 0.001	< 0.001	<0.001	<0.001	0.001
Porassium	D-K			0.60	0.70	0.50	0.61	0.42	0.56	0.51	0.33	0.1	1.10	0.38	0.75
Selenium	D-S-			0.00	0.70	0.55	0,01	V, 14	0.00	<0.0005	0.0008	0.0008	<0.0005	<0.0005	0.002
Silicon	D-Si					2000		1000	STR.	61	0.0000	0.0005	0.73	17.4	22.6
Silve	D-Ar	2000	5354	0.0001	<0.0001	<0.0001	<0.0001	<0.0001	< 0.0001	<0.0001	<0.00	<0.0001	<0.0001	<0.0001	<0.0001
Section	D-Na			2.44	215	4.64	3.51	2.34	2.000/1	4.61	16.0	16.0	5.09	7.10	1 69
Struction	DS	200		2.99	6.13	4,04	3.35	2.24	4,40	4,01	10,9	10.9	0.120	1.10	3.30
Suonuum	D-SI	1000 P			****				****	0.115	0.003	0,062	0,179	0,462	0,042
1 tanium	0.11	222.)			1110	1000	100	100	100	< 0.010	< 0,010	< 0,010	< 0.010	<0.010	<0,010
Venetium	D-0									0,00052	0.00017	0.00029	0.0004	0.00044	0.00005
vanadium	D-V					****				< 0.030	<0,030	< 0.030	<0,030	< 0.030	<0.030
Zinc December 10	D-Zn	200		< 0.005	<0,005	< 0.005	< 0.005	<0,005	<0.005	< 0,005	< 0,005	< 0,005	< 0,005	< 0.005	0.057
Organic Parameters															
Total Organic Carbon	C			****	inerest (****			1.2	< 0.5	< 0.5	0.9	1	0.9

Notes 1) Results are expressed as milligrams per line except for pH, Conductivity (umhos/cm), and Turbidity (NTU).

2) Italic hold shaded values indicate excedance of the BC Environmental freshwater aquatic life criteria. (Approved and Working Criteria for Water Quality - 1994, BC Environment, Victoria)

3) The letter d after the monitoring well identification name means that it is a duplicate sample, eg R-95-4d

4) A < sign mean that the value is less than the detection limit stated.

Knight Piésold Ltd.

CONSULTING ENGINEERS

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

TAILINGS STORAGE FACILITY BASELINE GROUNDWATER QUALITY

UU08/DATADS4WQ/ALITYAPPEN	DC318								_			Lass Update:	7 May, 96
			1994 BC Environment						1000 005	14000 012	14000 000	1000 334	14700 2761
		Erschwater Drinking		MP89-231	MP89-232	MP89-233 Nov. 25/80	MP89-234	MP89-234 Supt 22/05	MP89-235	MP89-230	MP89-236	MP89-236 Sent 72/05	MP89-236d
			Water	1459 23769	PARK 2,0/07	007.23(69	1808 43/07	ochr 22130	NOV 25/89	14114 2,3/03	240 11234	acht 22/33	acht weise
Physical Tests			1										
Conductivity (umbos/cm)				1226	289	393	422	399	4280	574	511	460	473
Total Dissolved Solids		-						330			323	336	335
Hardness	CaCO3	-	-	182	96.7	197	80.2	154	432	177	187	227	229
pH	Contraction of the second		-	7.73	7,40	7.65	8.0	7.89	7,28	8.24	7,87	7.71	7,74
Total Suspended Solids							dana.	548			373	240	74
Turbidity (NTU)								113			250	105	23,8
Dissolved Anions													
Alkalinity	Total CaCO3		-	-	-		-	250			284	301	298
Chloride	CI		1000		1444		4444	1,3			2,0	1.2	0,6
Fluoride	F							0.13			0,13	0.11	0,11
Sulphate	SO4		-			****		14.4		(Line (12,3	3.8	4.5
Nutrients													
Ammonia Nitrogen	N			-	2012-	12.17	100	0.014	1000	100	< 0.005	< 0.005	<0,005
Nitrate Nitrogen	N					****		< 0,005	-		0,007	0,028	0,028
Nitrite Nitrogen	N					****		0.001			0,005	0.001	0,001
Dissolved ortho-Phosphate	p		1944			****		0.022	2110	1111	0.003	0.002	0,002
Total Dissolved Phosphate	P			-	-			0,022			0,003	0,002	0,002
Total Phosphorus	р							0,553	****		0,500	0,333	0,070
Cyanides													
Total Cyanide	CN		0.2		-			< 0,001			< 0.001	< 0.001	<0,001
Total Metals													
Atuminum	T-AI	0.005-0,1		7.88	34.1	15.4	4.77	13.1	5.84	9.80	4.49	1.23	0.619
Antimony	T-Sb								0,0001		0.0024	0.0003	0,0006
Arsenic	T-As	0.05	0.025	0.0085	0.0004	0.0088	0.073	0.0079	0.0346	0.014	0.0068	0.0042	0.0039
Barium	T-Ba		L.		1000		-	1.000	0.292		0,114	0.023	0.02
Beryllium	T-Be					****			< 0.005		< 0.005	< 0,005	< 0.005
Bismuth	Т-Ві					****		****	< 0.10	*****	< 0,10	< 0,10	< 0.10
Boron	T-8		5	and .				(arm)	0, 2.5		< 0.10	< 0,10	< 0.10
Cadmium	T-CJ	0.0002-0.0018	0.005	< 0,0002	0.015	0.0003	< 0.0002	0.0003	0.0008	0.0003	0.0002	<0,0002	< 0.0002
Calcium	T-Ca				-	-			63.6		57.6	56.2	55.4
Chromium	'T-Cr	0.002-0.02	0,05	0.005	0.047	0.040	0.007	0.029	0.012	0.012	0.007	0.001	0.001
Cobalt	T-Co		mand	0.006	0.013	0.009	0.002	0.010	0.008	0.007	0.006	0.001	0.001
Copper	T-Cu	0,002-0.004	L.	0.030	0.069	0.048	0.019	0.052	6.068	0.075	0.129	0.061	0.133
tron	T-Fe	0.3	0.3	11.9	29.3	20.9	4.47	14.0	6.63	15.3	9.95	4.86	5.26
Lead	T-Pb	0.001-0.007	10.0	0.003	0.013	0.009	0.004	0.006	0.013	0.011	0.008	0.001	0.002
Magnesium	T-Mg	1.000							22.2		23.7	23.9	23.7
Manganese	T-Mn		0.05	0.99	0.72	0.45	0,14	0.66	0.590	0,45	0,670	0.182	0,200
Mercury	T-Hg	0.0001	0,001	0.00008	0.00020	0.00012	0.00013	0.00012	< 0.00001	0.00013	0.00009	< 0.00001	< 0.00001
Molybdenum	T-Mo	375		0,005	0.002	0,012	0.003	0,010	< 0.001	0.005	0.003	0.001	< 0,001
Nickel	T-Ni	0.025-0.15		0,015	0.062	0.036	0.005	0,023	0,019	0.011	0.007	100.0	0,002
Selenium	T-Se	0.001	0,01						< 0.0005		0,0009	< 0.0005	< 0.0005
Silicon	T-Si								17.7		14.5	10.4	9.55

Notes 1] Results are expressed as milligrams per litre except for pH, Conductivity (umbos/cm), and Turbidity (NTU).

2) Italic bold shaded values indicate extedance of the BC Environmental freshwater squatic life criteria.

(Approved and Working Criteria for Water Quality - 1994, BC Environment, Victoria)

3) The letter d after the monitoring well identification none means that it is a duplicate sample, vg.R-95-44

4) A < sign mean that the value is less than the detection limit stated,



CONSULTING ENGINEERS

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

TAILINGS STORAGE FACILITY BASELINE GROUNDWATER QUALITY (con't)

LUDIEDATA/IESEWQUALITY/APPEN	dicixia											Last Update:	7 May, 96
		1994 BC Environment Water Quality Criteria		MP89-231	MP89-232	MP89-233	MP89-234	MP89-234	MP89-235	MP89-236	MP89-236	MP89-236	MP89-236d
		Freshwater Aquatic Life	Drinking Water	Nov 25/89	Nov 25/89	Nov 25/89	Nov 25/89	Sept 22/95	Nov 25/89	Nov 25/89	Jan 17/95	Sept 22/95	Sept 22/95
Total Metals							-						
Silver	T-Ag	0,0001		0.0003	0.0003	0.0005	< 0.0001	< 0.0001	0.0004	0.0002	0.0020	< 0.0001	< 0.0001
Strontium	T-Sr			-		****		0.841		-	2.06	2,07	2.03
Titarium	T-TI	325		100.000	-	100	111	0.07	-	2.5	0.031	0,011	<0,010
Uranium	T-U	-	0.1				_	0.00122			0,00106	0.00103	0.00104
Vanadium	T-V					-		0.031			< 0.030	< 0.030	< 0,030
Zine	T-Zn	0.03	5	0.044	0.066	0.078	0,024	0.026	0.064	0.039	0.049	0.01	0.008
Dissolved Metals													
Aluminum	D-AI		1000	0.045	0.13	0.027	0.029	0.024	0.015	0.014	0.035	0.023	0.015
Antimony	D-Sh							< 0.0001			0.0017	0.0003	0.0003
Arsenic	D-As			0.0018	0.0024	0.0015	0.066	0.0231	0.0008	0.0008	0.0006	0.0002	0.0001
Barium	D-Ba							0.069			0.023	< 0.010	<0.010
Beryllium	D-Be							< 0.005			< 0.005	< 0.005	< 0.005
Bismuth	D-Bi		121128	-		1111		< 0.10		-	<0,10	< 0.10	< 0.10
Borog	D-B			-	-			0.25	_		<0.10	<0,10	<0,10
Calmium	D-C4			< 0.0002	<0.0002	< 0.0002	<0.0002	< 0.0002	< 0.0002	< 0,0002	< 0,0002	< 0.0002	< 0,0002
Calcium	D-Ca		-		33.4	46.6	16.1	32,9	128	39.7	43.0	53.1	53,5
Chromium	D-Cr			0.002	0.002	0.001	< 0.001	< 0.001	0,001	0,001	< 0.001	< 0.001	< 0,001
Cobalt	D-Co	-		< 0.001	<0.001	< 0.001	< 0.001	< 0,001	0.002	< 0.001	< 0.001	< 0.001	< 0,001
Copper	D-Cu			0,006	0.007	0.001	< 0.001	< 0.001	0.009	< 0.001	< 0.001	0.004	< 0,001
Iron	D-Fe			2.08	0.35	< 0.03	< 0.03	0.037	< 0.03	< 0.03	< 0.030	0.068	< 0.030
Lead	D-Pb			0.001	0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001
Magnesium	D-Mg	_	-	14.0	3.15	19.2	9.50	17.4	26.6	18.6	19.2	23	23.1
Manganese	D-Mn			0,78	0.21	0.13	0.036	0,037	0.43	0,066	0,011	< 0.005	< 0.005
Mercury	D-Hg			< 0,00005	< 0.00005	< 0.00005	< 0.00005		< 0.00005	0.00005		-	
Molybdenum	D-Ma	-	-	0.005	0.002	0.009	0.003	< 0.001	0.006	0.003	0.003	0,003	< 0,001
Nickel	D-NI			D,006	0,013	0.007	< 0.001	< 0.001	0,004	<0,001	< 0.001	< 0.001	< 0.001
Potassium	D-K			4.00	1,13	1.10	1,78	2,21	4,27	2,05	1.97	2.55	2.63
Selenium	D-Se							< 0.0005			0.0009	< 0.0005	< 0.0005
Silicon	D-Si		1000 C		1.000			8,77		-	6.60	7.73	7.8
Silve	D-Ag		ا مستو	< 0.0001	< 0,0001	<0.0001	< 0.0001	< 0,0001	0.0001	< 0.0001	< 0.0001	<0.0001	< 0,0001
Sodium	D-Na			180	7.97	8.30	66.0	32.4	686	42.9	44,0	14.0	14,7
Strontium	D-Sr							0.651			1.68	1.96	1.98
Titanium	D-Ti		1	-	1000	1225		<0.010	-		< 0.010	< 0.010	<0.010
Uranium	D-U	-						0,00069			0,00078	0,00092	0.00098
Vanadium	D-V	-		-				< 0.030			< 0.030	< 0.030	< 0,030
Zinc	D-Zn			0.025	0.011	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005
Organic Parameters							1						
Total Organic Carbon	c	200		-	-				1.0		1.1	1.0	0.8

Notes 1) Results are expressed as milligrams per line except for pH, Conductivity (unhos/cm), and Turbidity (NTU).

2) Italic hold shaded values indicate excedance of the BC Environmental freshwater squatic life criteria,

(Approved and Working Criteria for Water Quality - 1994, BC Environment, Victoria)

3) The letter d after the monitoring well identification nume means that it is a duplicate sample, ug R-95-4d

4) A < sign mean that the value is less than the detection limit stated,

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

REPORT ON GEOTECHNICAL INVESTIGATIONS AND DESIGN OF OPEN PITS AND WASTE DUMPS (REF. NO. 1628/1)

JULY 5, 1996

Suite 1400 750 West Pender Street Vancouver, British Columbia Canada V6C 2T8 Telephone (604) 685-0543 Telefax (604) 685-0147 CIS: 72360,477

Knight Piésold Ltd. CONSULTING ENGINEERS

Knight Piésold Ltd. CONSULTING ENGINEERS

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

REPORT ON GEOTECHNICAL INVESTIGATIONS AND DESIGN OF OPEN PITS AND WASTE DUMPS (REF. NO. 1628/1)

This report was prepared by Knight Piésold Ltd. for the account of Imperial Metals Corporation. The material in it reflects Knight Piésold's best judgement in light of the information available to it at the time of preparation. Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. Knight Piésold accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report.



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 283 of 500

Knight Piésold Ltd.

CONSULTING ENGINEERS

IMPERIAL METALS CORPORATION <u>MT. POLLEY PROJECT</u>

REPORT ON

GEOTECHNICAL INVESTIGATIONS AND DESIGN OF OPEN PITS AND WASTE DUMPS

TABLE OF CONTENTS

SECTION 1.0	INTR	ODUCTIO	DN				
	1.1	1					
	1.2	2					
		ACKNO	DWLEDGEMENTS				
SECTION 2.0	SITE	4					
	2.1	4					
	2.2	REGIO	5				
	2.3	SEISMI	CITY	5			
SECTION 3.0	GEO'	7					
	AND TESTING						
	3.1	GENER	7				
	3.2	OPEN I	PIT				
		3.2.1	General Description	8			
		3.2.2	Geotechnical Drilling	8			
		3.2.3	Permeability Testing	11			
		3.2.4	Groundwater Monitoring	11			
		3.2.5	Pit Dewatering	12			



1628/1 July 5, 1996

PAGE

Knight Piésold Ltd.

CONSULTING ENGINEERS 3.3		WASTE	14				
		3.3.1	Waste Characterization	14			
		3.3.2	Surficial Materials	14			
SECTION 4.0	OPEN	N PIT SLO	PE DESIGN	16			
	4.1	GENER	AL	16			
	4.2	FACTO	RS WHICH INFLUENCE PIT	16			
		SLOPE	STABILITY AND SLOPE ANGLE				
	4.3	STRUC	TURAL GEOLOGY	17			
	4.4	EVALU	JATION AND CONTROL OF	18			
		GROUN	NDWATER				
	4.5	PIT SLO	OPE AND BENCH DESIGN	18			
SECTION 5.0	WAS	TE DUMP	LAYOUTS	19			
	5.1	WASTI	E DUMP LOCATIONS AND	19			
		CONST	RUCTION				
	5.2	STABI	LITY ANALYSES	20			
	5.3	RECLA	MATION	21			
SECTION 6.0	WAT	TER MANA	AGEMENT PLAN	22			
SECTION 7.0	REFI	REFERENCES					



Knight Piésold Ltd. CONSULTING ENGINEERS

TABLES

Table 2.1	Mean Monthly and Annual Precipitation
Table 2.2	Probable Maximum Precipitation
Table 2.3	Estimated Pan Evaporation at Site
Table 2.4	Seismic Risk Calculation
Table 3.1	Summary of Permeability Testing in Open Pit
Table 3.2	Groundwater Levels in Proposed Open Pit Area
Table 4.1	Preliminary Pit Slope Design

FIGURES

Figure 1.1	Project Location Plan
Figure 2.1	Location of Weather Stations
Figure 2.2	Short Duration Rainfall Intensity-Duration-Frequency Data for Mine
	Site
Figure 3.1	Plan of Geotechnical Drill Hole Locations and Open Pit Design
	sectors
Figure 3.2	Summary of Joint Data for MP89-152
Figure 3.3	Summary of Joint Data for MP89-153
Figure 3.4	Summary of Joint Data for MP89-154
Figure 3.5	Summary of Joint Data
Figure 4.1	Open Pit Typical Failure Modes
Figure 4.2	Open Pit Slope Angles and Bench Designs
Figure 5.1	Waste Dump Typical Static Wedge Failure Analysis
Figure 5.2	Waste Dumps Shear Strength of Rockfill
Figure 5.3	Waste Dumps Stability Chart



Association des Ingénieurs-Conseils du Canada

- iii -

1628/1 July 5, 1996

Knight Piésold Ltd. CONSULTING ENGINEERS

DRAWINGS

1628.100	Overall Site Plan Geotechnical Investigations Programs
1628.101	Geologic Plan of Open Pit Area
1625.230	Drainage Plan - Mine Site

APPENDICES

- Appendix A Review of Open Pit design by C.O. Brawner, P.Eng.
- Appendix B Drill hole data and point load test results
- Appendix C Test pit logs - 1995



1628/1 July 5, 1996 Knight Piésold Ltd.

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

REPORT ON GEOTECHNICAL INVESTIGATIONS AND DESIGN OF OPEN PIT AND WASTE DUMPS

SECTION 1.0 - INTRODUCTION

1.1 <u>GENERAL OVERVIEW</u>

The Mt. Polley Project is located in central British Columbia approximately 56 kilometres north-east of Williams Lake, as shown on Figure 1.1. The nearest settlement is the community of Likely, which is located on the northern tip of Quesnel Lake.

The project derives its name from Mt. Polley, a low mountain with a peak elevation of 1260 metres, approximately 300 metres above the surrounding terrain. Mt. Polley is situated between Polley Lake to the east, and Bootjack Lake to the south-west. The site is accessible by paved road from Williams Lake to Morehead Lake, near Likely, and then by gravel forestry road for the final 10 kilometres to the site.

The project involves open pit mining of an estimated 82.3 million tonnes of copper and gold ore contained in three adjacent orebodies, at a nominal rate of 17,800 tonnes per day. Approximately 92.6 million tonnes of waste rock will be stored in waste rock dumps adjacent to the open pit.

After processing of the ore to produce a copper/gold concentrate, the tailings will be discharged as a slurry into a tailings storage facility designed to provide environmentally secure storage of the solids waste, with collection and recycling of all process solutions. No discharge of process solutions from the site is required.



Association g des Ingénieurs-Conseils du Canada 1628/1

July 5, 1996 INVESTIGATION KP 1-11 288 of 500
Knight Piésold Ltd.

This report is an updated version of the 1990 Knight Piésold report "Geotechnical Investigations and Design of Open Pit, Waste Dumps and Tailings Storage Facility" prepared for Imperial Metals Corporation. Details related to the tailings storage facility have been omitted. New information concerning modified waste rock dump sites, geotechnical investigations throughout the site, project water management plans, proposed reclamation program, pit bench design, and proposed pit dewatering plans have been incorporated in this report. All new or revised information has been derived from the following documents by Knight Piésold Ltd:

- March 1995 "Report on Geotechnical Investigations for Mill Site and Tailings Storage Facility" (Ref. No. 1623/1).
- February 1995 "Report on Project Water Management" (Ref. No. 1624/1).
- March 1996 "Hallam Knight Piésold Reclamation Plan Report"
- June 1996 "Groundwater Monitoring Program" (Ref. No. 1624/2).

1.2 SCOPE OF REPORT AND ACKNOWLEDGEMENTS

This report summarizes the design for the open pit and waste dumps with a brief discussion on the project water management plans. It is based on the results of field investigations and laboratory testwork. Specific design items which are addressed in the report are:

- Site characteristics including hydrometeorology, regional geology and seismicity.
- The results of geotechnical investigations carried out in the open pit and waste dump areas.
- Assessment of open pit geology, rock mass characteristics, hydrogeology, and dewatering requirements.



July 5, 1996 INVESTIGATION KP 1-11 289 of 500

- New layout of the waste rock dumps and an assessment of the hydrogeologic impacts.
- Water management plans.

These items are discussed in the following sections of the report and are intended to provide input towards a Work Systems Approval.

All field geotechnical work was carried out under the direction of Knight Piésold Ltd. personnel with active involvement of Imperial Metals Corporation field personnel.

A comprehensive review of geotechnical data pertaining to the open pit design was carried out by Mr. C.O. Brawner, P. Eng. Results of this review with recommendations for open pit slope design are summarized in Section 4.0 of the 1990 Knight Piésold "Report on Geotechnical Investigations and Design of Open Pit, Waste Dumps and Tailings Storage Facility, Ref. No. 1621/1", and are included in this report as Appendix A.



July 5, 1996 INVESTIGATION KP 1-11 290 of 500

CONSULTING ENGINEERS

SECTION 2.0 - SITE CHARACTERISTICS

2.1 HYDROMETEOROLOGY

Long and short term climate records are available for a number of locations in the area, as shown on Figure 2.1. Two recently established stations (Likely with 12 years of record and Horsefly with 17 years) are located within 40 km of the site in similar terrain. The project area is subjected to a relatively temperate climate with warm summers and cool winters. The precipitation is well distributed throughout the year.

Detailed climatological summaries from 1984 to 1990 for weather stations from within the project area are included in Appendix A of the 1990 Knight Piésold report, Ref. No. 1621/1. Site specific data collected from July 1995 to January 1996 is available in the 1996 Hallam Knight Piésold "Reclamation Plan" report.

The mean annual temperature at Likely, the nearest station to the site, is 4.0°C with an extreme maximum of 33.9°C and an extreme minimum of -37°C. At Quesnel, with approximately 76 years of record, extremes are 40.6°C and -46.7°C. Frost free days in the area range from 199 at Horsefly Lake (elevation 788 m) to 244 at Barkerville (elevation 1244 m).

A preliminary estimate of the total annual and monthly distribution of precipitation for the site has been made using data from a number of stations in the area. The mean annual precipitation at Likely is 699.7 mm and at Barkerville (with over 76 years of record) is 1043.9 mm. Precipitation for the site can be expected to fall within this range. The 1996 Knight Piésold "Groundwater Monitoring Program" report gives a mean annual site precipitation of 755mm. Data for Likely, Barkerville and the site are presented in Table 2.1.

Short term storm intensity, duration, and return period curves have been plotted using data obtained from the rainfall frequency atlas for Canada, and are shown on Figure 2.2. Probable maximum precipitation for the site has also been calculated from data contained in this atlas and is shown on Table 2.2.



Association g des Ingénieurs Conseils du Canada -4-

1628/1

July 5, 1996 INVESTIGATION KP 1-11 291 of 500

Evaporation data and estimated evaporation for the site have been computed using potential evapotranspiration by AES using the Thornwaite model and available data for Quesnel and Williams Lake. This data is shown in Table 2.3. Canadian Climate Normals, Volume 9 contains lake evaporation data for Mica Creek and Blue River which are at similar latitude to the mine site but are judged to be too distant to be relevant.

2.2 REGIONAL GEOLOGY

The Mt. Polley site is located in an alkalic intrusive complex in the Quesnel Trough, a 35 km wide north-west trending volcanic sedimentary belt.

The rock units are segmented into blocks by several faults, including an inferred north-westerly trending normal fault which extends along Polley Lake. The predominant structural orientation of the region is north-west trending and dipping steeply to the north-east. Localized geology in the vicinity of the open pit is shown on Drawing 1628.101.

The topography is generally subdued and has been glaciated. Surficial deposits of well graded, dense glacial till material are common throughout the region and are typically present in greater thicknesses in topographic lows. Bedrock exposures are common at high elevations.

2.3 SEISMICITY

The Mt. Polley site is situated within an area of very low seismic activity. A seismic risk calculation based on a Cornell type probabilistic model has been developed by the Pacific Geoscience Centre. The results for the Mt. Polley site are included as Table 2.4 and are summarized as follows:



Association des Ingénieurs Conseils du Canada 1628/1

July 5, 1996 INVESTIGATION KP 1-11 292 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

Return Period (yrs)	Probability of Exceedence in 50 years (%)	Peak Ground Acceleration (g)	Peak Ground Velocity (m/s)
100	40	.021	.043
475	10	.037	.077
1000	5	.046	.094

The project is located in a NBCC Acceleration Zone 0, and Velocity Zone 1 for structural design requirements.



1628/1

July 5, 1996 INVESTIGATION KP 1-11 293 of 500

Knight Piésold Ltd.

SECTION 3.0 - GEOTECHNICAL INVESTIGATIONS AND TESTING

3.1 <u>GENERAL</u>

Geotechnical investigations have been carried out to provide design criteria for the proposed open pit and waste dumps facilities. Investigative work consisted of field mapping, test pit excavations, installation of ground water monitoring wells, and diamond drilling with permeability testing. The following provides a summary of the investigation work:

- <u>1989</u> A diamond drilling program and hydrogeologic investigation was conducted by Imperial Metals Corporation, in conjunction with exploration drilling. A total of thirty-nine geotechnical drill holes, including three holes with oriented drill core, were completed in the open pit areas, as shown on Figure 3.1. Details from the oriented drill holes are included as Appendix B. Nine groundwater monitoring wells were also completed, as shown on Figure 3.1.
- <u>1995</u> A geotechnical investigation program consisting of thirty-nine test pits was completed by Knight Piésold throughout the project area. Test pit logs are included as Appendix C. Seven groundwater monitoring wells were completed in the vicinity of the open pits and mill site.

Evaluation of site conditions and geotechnical design criteria were based on the following:

- (i) Open Pit
- Detailed logging of rock mass discontinuity data in oriented drill core from angled drill holes, and non-oriented drill core from vertical exploration holes (1989).
- Selected laboratory testing of fault gouge material (1990).



July 5, 1996 INVESTIGATION KP 1-11 294 of 500

CONSULTING ENGINEERS

- Permeability testing in vertical drill holes (1989)
- Installation of three pneumatic and standpipe piezometers (1989), and installation of groundwater wells monitoring flow from the pit to Bootjack Lake (1995).
- (ii) Waste Dumps
- Laboratory studies on the acid generation potential of waste rock (1990).
- Condemnation drilling in the vicinity of the proposed waste dumps (1989).
- Groundwater well monitoring flow from the south-east dump to Polley Lake (1995).

3.2 <u>OPEN PIT</u>

3.2.1 General Description

The open pit will consist of three interconnecting pits, namely the Central, North and West Pits as shown on Drawing 1625.230. The Central and North Pits will extend approximately 1,100m in a north-south direction and the Central and West pits approximately 1,100m in an east-west direction. The total area of the open pits at the conclusion of the operation will be approximately 70 ha. Mining is scheduled to commence in the Central Pit. Development of the North and West Pits will follow.

3.2.2 Geotechnical Drilling

The exploration program conducted by Imperial Metals Corporation in 1989 was expanded to provide additional information on the rock structure within the proposed open pit areas. Geotechnical drill logs were developed in



1628/1

July 5, 1996 INVESTIGATION KP 1-11 295 of 500

Knight Piésold Ltd.

addition to the geologic logs for 39 drill holes. The drill hole locations are shown on Figure 3.1. The following parameters were routinely recorded:

- RQD (rock quality designation)
- Discontinuity spacing and description of surface conditions
- Discontinuity orientation with respect to the core axis
- Discontinuity infilling materials
- Point load test results

Three inclined geotechnical drill holes, MP89-152, MP89-153 and MP89-154 were drilled in 1989 to provide true orientation of the rock discontinuities.

Stereonet plots of the joint and fracture orientations measured in each of the three inclined holes have been developed by the Schmidt contouring method and are presented in Figures 3.2, 3.3 and 3.4. A combined plot of all discontinuity data is included in Figure 3.5. A summary of rock types, RQD, fracture index and unconfined compressive strength data for the three inclined geotechnical drill holes is included as Appendix B.

The predominant rock types encountered were intrusion breccia, syenodiorite and monzonite, with minor occurrence of mafic dykes. Several fracture zones were identified and occasional clayey to sandy zones of fault gouge were encountered in the drill core. Two samples of fault gouge were analyzed in the laboratory as follows:



July 5, 1996 INVESTIGATION KP 1-11 296 of 500

CONSULTING ENGINEERS

Drill Hole	MP89-143	MP89-152
Depth	38 m (125 ft)	90 m (245 ft)
Gradation		
Gravel	6 percent	7 percent
Sand	28 percent	16 percent
Silt	46 percent	23 percent
Clay	20 percent	54 percent
Atterberg Limits		
L.L.	57 percent	86 percent
P.L.	26 percent	36 percent
P.I.	31 percent	50 percent
Pocket Penetrometer	disturbed	4.5 tons/ft ²
Natural Moisture Content	23.5 percent	26.5 percent

In general, the rock mass quality comprising the proposed open pit walls was found to have variable conditions, ranging from strong and fresh to weak and altered rock. The uniaxial compressive strength of intact core samples ranged from very high (>200 MPa) to very low (<5 Mpa). Zones of very weak and highly altered rock were identified at localized intervals in most drill holes. Highly fractured zones up to 100 metres in thickness were encountered in several drill holes. Zones of increased fracturing, more intense alteration and lower rock mass quality are recognized to be generally associated with large scale structural features such as faults and contacts between the intrusive geologic units.

Discontinuities in the rock mass generally reflect the regional structural trend, as the dominant joint set was observed to strike 170 degrees and dip 75 degrees to the north-east. A secondary joint set was found to be approximately orthogonal to the main set, striking 30 degrees and dipping 20 degrees to the north-west. Discontinuities observed in the core were generally rough, and contained calcite and chlorite cementation. However, smooth, polished and slickensided joints were also identified. It should be



Association des Ingénieurs Conseils du Canada 1628/1

July 5, 1996 INVESTIGATION KP 1-11 297 of 500

noted that these orientations are based on the results of oriented core from three drill holes. Information on rock mass structure from the other cored drill holes supports these general orientations, however a more comprehensive model of the rock mass structure will be established with the initial development of the open pit.

3.2.3 Permeability Testing

Permeability testing was completed in five vertical exploration holes in 1989 as shown on Figure 3.1. The test apparatus consisted of an NQ double packer wireline system with a flow meter and pressure gauge for accurate monitoring of test conditions.

The test results are included in Table 3.1. In general, the measured rock formation permeabilities were less than about 1×10^{-5} cm/s, but occasional higher permeability zones (approximately 10^{-4} cm/s to 10^{-3} cm/s) were encountered, often associated with zones of intensely fractured bedrock. The geometric mean of all the permeability tests is 8.4 x 10^{-6} cm/s.

3.2.4 Groundwater Monitoring

Groundwater instrumentation installed in 1989 in the open pit area included three 40 mm diameter standpipe piezometers for water level measurement and groundwater sampling. These wells are still operational. Two multiple port pneumatic piezometers were installed for measurement of water levels and hydraulic gradients, but their status is unknown. Water level measurements were also obtained in open drill holes at the site. In August 1995, three groundwater monitoring wells were installed in the vicinity of Bootjack Lake to monitor the groundwater flow from the open pit and the mill site. An additional monitoring well was installed to monitor the groundwater flow from the east waste dump to Polley Lake. These are discussed in the 1996 Knight Piésold groundwater monitoring report, Ref.



Association des Ingénieurs Conseils du Canada -11-

1628/1

July 5, 1996 INVESTIGATION KP 1-11 298 of 500

No. 1624/2. This report reviews past well monitoring programs and presents the results of the 1995 wells. It serves as a compilation of the current understanding of the site's hydrogeological conditions and the anticipated impacts that will result from the project development.

In general, groundwater levels around the project area were measured at depths in the order of 30 metres at higher elevations, and 3 to 10 metres at lower elevations, as summarised in Table 3.2. Hydraulic gradients measured in the multiple port installations appeared to be approximately hydrostatic, however, temporary artesian flows were encountered in a few holes during drilling.

3.2.5 Pit Dewatering

Water inflow into the open pits results from groundwater seepage and surface runoff. While groundwater seepage is assumed to be relatively constant over the life of the mine, surface water inflows can be more variable depending on open pit area, precipitation levels and surface water diversions surrounding the pit perimeters. Groundwater flow is difficult to predict accurately, but experience at other mines suggests that the inflow will be in the order of 0.005 m³/s to 0.025 m³/s. These rates may be temporarily higher if permeable fracture systems are intersected, but short term dewatering of these fracture zones should occur.

Surface water inflow due to direct precipitation will vary according to rainfall intensity, and is expected to average about 0.01 m^3 /s to 0.02 m^3 /s on an average annual basis depending on the undiverted catchment area of the pit(s). These values are based on an average annual precipitation of 755 mm/yr (as discussed in Section 2.1), a runoff coefficient of 75% and initial and final pit areas of 41 ha and 90 ha respectively.

Water accumulating in the pit bottom will be transferred to an in-pit sump located on the East side of the Central Pit, about 60 metres above the ultimate base. From there, it will be pumped to the mill for use as process water or



Association des Ingénieurs-Conseils du Canada 1628/1

July 5, 1996 INVESTIGATION KP 1-11 299 of 500

discharged into the tailings basin. However, during storm events considerable water will accumulate in the pit bottom where it will be temporarily stored in a bottom sump until it is transferred to the higher sump. Pumping requirements will be determined during initial operations and the pumping capacity will be selected to accommodate increased pumping requirements during and after storm events.

If additional water storage capacity is required, a separate external pit sump may be installed during later mine operations.

Perimeter dewatering wells, and/or horizontal drains may be installed in and around the pits to draw down groundwater levels should it be necessary to control seepage and enhance pit slope stability. These requirements will be progressively determined during mine development.

In the later years of mine operation, the Central Pit may be used for waste rock disposal while the West Pit is mined. Groundwater and surface runoff could then accumulate in the Central Pit and may result in increased lateral seepage rates into the West and North Pits. The West Pit is about 50 metres deeper than the Central Pit and seepage would occur through a bench approximately 150 m high which separates the two pits. The permeability of the bedrock throughout the pit area has been determined to be less than approximately 1 x 10^{-5} cm/s, but may range from 1 x 10^{-4} cm/s to 1 x 10^{-3} cm/s in zones of fractured bedrock (natural geologic fracture zones and/or blast damaged zones). There are three geologic contacts in the vicinity of the bench which have been identified as zones of weak and highly altered rock. These discontinuities could serve as relatively high permeability seepage paths into the West Pit and will be evaluated during initial and ongoing pit development.

The North and Central Pits are separated by a larger bench, approximately 100 m high. Both pits are of the same depth. A north-south trending fault has been found which cuts the west side of the bench and could be a zone of high permeability which will be evaluated during future pit development. It



n Association ing des Ingénieurs Conseils du Canada 1628/1 July 5, 1996 INVESTIGATION KP 1-11 300 of 500

Knight Piésold Ltd.

is unlikely that seepage from the Central to North Pits will be a significant consideration due to long seepage path lengths and low seepage gradients.

3.3 WASTE DUMPS

Waste Characterisation 3.3.1

A detailed program of acid/base accounting was completed in 1989 and 1990 on potential waste rock materials from the open pit. This program involved the collection of random samples of drill core and subsequent analyses for:

- total sulphur
- neutralization potential
- total acid generation potential (calculated on the basis of total sulphur)

These tests were carried out by Envirochem Services Ltd. and Coastech Research, both of North Vancouver, B.C. The results of the waste characterization tests for the 94 samples tested are included in Appendix C of the 1990 Knight Piésold report, Ref. No. 1621/1. The testwork indicates that the waste rock will not be acid generating. ARD tests are discussed extensively in the 1996 Hallam Knight Piésold "Reclamation Plan Report".

3.3.2 Surficial Materials

The revised waste dump sites are shown on Drawing No. 1625.230. In general, the sites are characterized by gently undulating topography. The Central pit may be used for waste rock disposal when development of the west pit proceeds during the later stages of operation.



neers

1628/1

Knight Piésold Ltd.

The North dump is situated on a relatively flat area with bedrock knobs and ridges. Colluvium, glacial till and forest litter were encountered along the flat area to a maximum thickness of approximately 20 metres. The North dump has a capacity for 16 million tonnes and will likely be used during the mining of the North Pit later on in the mine life.

The South-East dump is situated along the crest of a broad ridge. The topography is relatively flat and undulating. A veneer of colluvium, glacial till and forest litter is present over most of the area. Bedrock was encountered in drill holes at depths ranging from approximately 3 to 7.6 metres.

Groundwater in the vicinity of the waste dumps is generally shallow with flow directions governed by the surface topography.



Association des Ingénieurs Conseils du Canada 1628/1

July 5, 1996 INVESTIGATION KP 1-11 302 of 500

CONSULTING ENGINEERS

SECTION 4.0 - OPEN PIT SLOPE DESIGN

4.1 GENERAL

This section provides a revised summary of Section 4.0 of the 1990 Knight Piésold "Report on Geotechnical Investigations and Design of Open Pit, Waste Dumps and Tailings Storage Facility" authored by Mr. C.O. Brawner. A proposed blasting program and details of anticipated groundwater inflow and pumping requirements can be found in the original report, which is included as Appendix A.

4.2 <u>FACTORS WHICH INFLUENCE PIT SLOPE STABILITY AND SLOPE</u> <u>ANGLE</u>

Factors which influence rock slope stability of open pit mines include geologic structure, groundwater conditions and dynamic acceleration forces generated during blasting.

The potential for pit slope instability is generally related to the presence of adversely oriented geologic discontinuities in the pit slopes. Typical slope failure mechanisms include circular, planar, block, wedge, and toppling modes as shown in Figure 4.1.

The presence of groundwater in the pit slopes influences stability by reducing rock mass shear strength due to reduced effective stress, creating seepage forces towards the pit slopes, creating hydrostatic forces in tension cracks, and increasing hydrodynamic shock due to blasting below the water table. Consequently, it is important that low water levels and groundwater pressures be maintained in the pit slopes. The most effective way to develop this control is with the installation of horizontal drains. Drainage requirements can most effectively be determined during initial development of the open pit by inspection of bench faces for seepage, and through the drilling of exploratory drain holes.

Dynamic acceleration forces due to blasting must be reduced at the final pit face to allow the steepest practical slopes to be developed, thereby minimizing the waste to



Association des Ingénieurs Conseils du Canada 1628/1

July 5, 1996 INVESTIGATION KP 1-11 303 of 500

Knight Piésold Ltd.

ore ratio. This requires controlled blasting techniques to maintain the design pit slope angles.

Slope movements, reflecting instability of the pit slopes, are typically indicated by the development of tension cracks along the pit or bench crests. Periodic inspections along the pit crest and bench locations will identify areas which may require further scaling and/or monitoring.

4.3 STRUCTURAL GEOLOGY

Three inclined boreholes, MP89-152 to MP89-154 were drilled using the clay imprint procedure to orient the rock mass structure. Stereographic plots are shown in Figures 3.2 to 3.5. The overall plots indicate a predominant joint set with an average strike of 170 degrees and an average dip of 75 degrees east. A secondary joint set was revealed striking on average 30 degrees and dipping 20 degrees north west. These geologic structures are the features which will influence slope stability throughout the pit walls, and potentially lead to certain types of instability in each pit face depending on the face orientation. The pit slope design must accommodate these potential failure mechanisms.

Generally, the rock strength is moderate to high so that stability will be controlled by the geologic structures. In addition to the joint sets described above, several localized zones featuring very closely spaced fractures, development of clayey gouge material and low compressive strength were noted. These localized zones may require additional design requirements, such as reduction of bench face angles, or installation of steel mesh and/or shotcrete to control bench face stability, which will be evaluated during development of the pit.

Details of the rock mass discontinuity data (R.Q.D. and joint frequency), together with unconfined compressive strength data, are provided in Appendix B.



n Association ing des Ingénieurs-Conseils du Canada 1628/1

July 5, 1996 INVESTIGATION KP 1-11 304 of 500

4.4 EVALUATION AND CONTROL OF GROUNDWATER

The groundwater table is generally close to the ground surface, ranging from 30 metres depth in topographically higher areas, to 3 metres depth in lower elevations around the project area. In some cases, artesian conditions were encountered in exploration drill holes. Drainage measures will be developed in the pit allowing for pit walls to be excavated at the steepest slopes possible and to prevent potential bottom heaving of the pit floor. Drainage measures to control seepage into the pit and improve stability of the pit walls will include the installation of horizontal drain holes, as determined from observed conditions in the initial pit development.

4.5 PIT SLOPE AND BENCH DESIGN

Design of initial pit slopes is based on a relatively steep bench face of 70 degrees, with inter-ramp slope angles of 52 degrees, shown as Design I in Figure 4.2. This design is based on the available structural information, and assumes drained conditions in the pit slopes. Where favourable interaction of rock mass structure and pit wall geometry are revealed during initial pit development, Design II will be utilized to optimize pit slope angles. These two pit slope designs are included to accommodate the different combinations of geologic conditions and pit slope orientations. A summary of the proposed design geometry for pit slopes is presented in Table 4.1. It should be highlighted that pit slope design will be modified based on updated geology and on additional geotechnical information obtained during early pit development.

For final pit design, controlled blasting will be used to develop the relatively steep bench face angles. Bench faces will be scaled to reduce ravelling and reduce width requirements for catch berms. The most recent pit design was completed using Mintec's MEDSYSTEM software.



ssociation Association Consulting des Ingénieursngineers Conseils Canada du Canada 1628/1

July 5, 1996 INVESTIGATION KP 1-11 305 of 500

CONSULTING ENGINEERS

SECTION 5.0 - WASTE DUMP LAYOUTS

5.1 WASTE DUMP LOCATIONS AND CONSTRUCTION

Waste dump sites are shown on Drawing No. 1625.230. Selection of waste dump sites has included consideration of environmental and economic factors, in addition to optimization of waste rock haulage.

The waste dumps are generally situated on relatively flat topography and will be underlain by glacial till and bedrock. Sufficient quantities of suitable topsoil and glacial till will be stripped and stockpiled for reclamation of the dumps. The ultimate waste dumps, as shown on Drawing No. 1625.230 include final reclaimed slopes of 2h:1v. During operations, the waste rock will be placed in individual benches as required to control surface erosion.

Drainage ditches will be used to control surface runoff from the North and South-East waste dumps. The dumps will be graded to direct runoff from the tops of the dumps into the open pit areas. The ditches will collect runoff from the dump slopes and will transfer the water to sediment control ponds as shown on Drawing No. 1625.230. The water will then be discharged into the tailings basin. There will be three main perimeter drainage ditches, as follows:

- The first drainage ditch will run north to south along the eastern end of the South East waste dump.
- The second drainage ditch will run west to east along the southern end of the final limit of the South-East dump.
- The third drainage ditch will run south between the South-East waste dump and . the mill site. It is then directed east and will connect to the first drainage ditch. This ditch will cut across the southern end of the South-East waste dump, to be used later in the mine life. As the dump advances, the ditch will be converted to a rock drain so that drainage can continue as the dump is developed. It is anticipated that natural segregation of coarser material will occur during waste



Association des Ingénieurs-Conseils du Canada

shane

1628/1

July 5, 1996 INVESTIGATION KP 1-11 306 of 500

rock placement. The coarser material will fall to the base of the advancing dump and the ditch will be filled with durable, coarse material. In the event that coarse, durable material is not available to fill the ditch, suitable material will be selected and placed in the ditch prior to covering it with the waste dump. This requirement will be evaluated as the waste dump develops.

Existing groundwater levels at the waste dump sites have been observed to be within a few metres of the ground surface, with a phreatic surface similar to the general topographical features. Due to the segregation of waste rock during placement, coarser particles will collect along the base of the dump providing free draining conditions within the waste dump materials.

5.2 STABILITY ANALYSES

Stability analyses of the waste dump have been carried out for a range of natural ground conditions and maximum dump height. A typical stability analysis is shown on Figure 5.1.

Strength parameters for the rockfill have been assumed from published information on the shear strength of rockfill by Leps (1970), and recommended values from the US Forest Service Intermountaine Region, Dump Stability Performance Objectives and Evaluation Criteria. These are summarized in Figure 5.2. Strength parameters for the foundation material are based on an in-situ layer of till, as stripping of topsoil and organic debris will be implemented.

The stability analyses were carried out for base translational failure along the waste rock/foundation contact using a non-circular analysis. The analyses were completed for the final reclaimed slopes of 2h:1v, using a maximum dump elevation of 1170 metres, as shown in Figure 5.1. The calculations take into account the maximum natural slope of the terrain in the waste dump area which does not exceed 38°. Previous stability analyses, outlined in the 1990 "Report on Geotechnical Investigations and Design of Open Pit, Waste Dumps and Tailings Storage Facility" (ref 1621/1) indicated that for the final reclaimed dump slopes, a minimum factor of safety of 1.3 can be achieved for all terrain on site, regardless if topsoil is stripped.



Association g dés Ingénieurs Conseils du Canada

Knight Piésold Ltd.

However, topsoil stripping will be implemented in the waste dump locations, creating a factor of safety against failure greater than 1.5 on all terrain, as indicated in Figure 5.3. The topsoil will be used for reclamation, as discussed below.

5.3 <u>RECLAMATION</u>

Areas designated for waste rock storage will be logged, grubbed and cleared prior to mining. Topsoil, overburden and coarse woody debris will be removed and stockpiled. These materials will be removed in a staged manner so that material removed from each succeeding raise is replaced on the previously completed raise. This leapfrog pattern will reduce the need for large soil stockpiles, will minimize haul costs, and will accelerate the recolonization of reclaimed areas by native materials from soil seed banks, bud banks, and rooted offsets. Most importantly, reclamation of completed raises of the waste dumps will commence almost immediately instead of being deferred until the end of mining.

Waste rock dumps will be constructed by end dumping, re-contoured to an ultimate slope of 2h:1v, covered with a layer of overburden/topsoil and re-vegetated. Individual dumps will not exceed 50 m in height. The top surfaces of the stockpiles will drain toward the open pits, but will be designed to have ridges and depressions, to blend in with the surrounding topography and to create habitat diversity. The final surfaces will be covered with a layer of overburden and topsoil, then re-vegetated. Final reclamation of the waste dumps will involve spreading of topsoil and glacial till and seeding or planting as required.

For further discussion on proposed reclamation plans, refer to the 1996 Hallam Knight Piésold "Reclamation Plan Report".



n Association ng des Ingénieurs-Conseils du Canada 1628/1

July 5, 1996 INVESTIGATION KP 1-11 308 of 500

CONSULTING ENGINEERS

SECTION 6.0 - WATER MANAGEMENT PLAN

An overview of all water associated with the Mt. Polley Project is provided in the 1995 Knight Piésold "Report on Project Water Management". An overall project water balance was completed by integrating the water balances for the mine site, including the open pits, waste dumps and mill site with the tailings facility and the undisturbed catchment areas immediately upgradient from it. The @RISK Analysis and Modelling program was used to describe the effects of the statistical nature of precipitation over the entire life of the project.

The report demonstrated that the tailings facility and open pit can and will be operated so that no surface discharge of excess water will be required and that make-up water requirements from Polley Lake will be minimized by addition and use of surface runoff from waste dumps and undisturbed catchment areas. Included in the report is the most recent hydrometeorological information obtained, including precipitation, snowmelt, evaporation and runoff. The report discusses assumptions made and presents conclusions and recommendations concerning make-up water supply and the project water management plan.



Association des Ingénieurs-Conseils du Canada 1628/1

July 5, 1996 INVESTIGATION KP 1-11 309 of 500

SECTION 7.0 - REFERENCES

Brown, Adrian., 1988. "Groundwater Evaluation and Control for gold Mining Projects," Second International Conference on Gold Mining, ed. C.O. Brawner (Littleton, Colorado: Society of Mining Engineers), pp. 219-233

Hallam Knight Piésold Ltd., 1996. "Mt. Polley Reclamation Plan, Ref. No.H1221".

Imperial Metals Corporation, 1990. "Stage I Environmental and Socioeconomic Impact Assessment, Volume I of II".

Knight and Piésold Ltd., 1990. "Report on Geotechnical Investigations and Design of Open Pit, Waste Dumps and Tailings Storage Facility, Ref. No. 1621/1".

Knight Piésold Ltd., 1995. "Mt. Polley Project, Report on Project Water Management, Ref. No. 1624/1".

Knight Piésold Ltd., 1996 "Groundwater Monitoring Program, Ref. No. 1624/2"



1628/1

July 5, 1996 INVESTIGATION KP 1-11 310 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

TABLE 2.1

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

MEAN MONTHLY AND ANNUAL PRECIPITATION

Location:	Likely, B.C.		Mir	ne Site	Barkerville		
Elevation:	724 m		1000 m		1265		
Location:	52° 121°	36'N 32'W	52° 30'N 121° 35'W		53° 4'N 121° 31'W		
Ian	<u>Mean</u> (mm)	<u>Std. Dev.</u> (mm)	<u>Mean</u> (mm)	<u>Std. Dev.</u> (mm)	<u>Mean</u> (mm)	Std. Dev. (mm)	
Fab	60.2	27.0	59 1	27.0	25.6	44.4	
Mar	37.8	13.5	44.5	13.5	85.3	29.1	
Apr	42.2	20.9	43.1	20.9	61.8	24.5	
May	36.6	15.4	50.6	15.4	65.9	28.9	
June	66.3	29.7	81.5	29.7	89.2	28.8	
July	47.0	27.4	65.7	27.4	81.7	31.0	
Aug	82.0	35.7	83.1	35.7	102.3	53.0	
Sept	50.4	27.1	60.4	27.1	85.4	39.9	
Oct	61.6	42.3	60.4	42.3	88.4	37.4	
Nov	58.4	18.8	57.3	18.8	86.6	28.2	
Dec	83.0	36.9	74.8	36.9	108.7	42.5	
Annual	699.7	116.4	755	116.4	1043.9	112.7	

Source :

Canadian Climate Normals, 1951-1980, Temperature and Precipitation Atmospheric Environment Service, Environment Canada.



Association des Ingénieurs-Conseils du Canada

Knight Piésold Ltd. CONSULTING ENGINEERS

TABLE 2.2

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

PROBABLE MAXIMUM PRECIPITATION

.

1 hour PMP 6 hour PMP 24 hour PMP

= 88 mm = 163.3 mm

= 78 mm

= 78 mm/hour = 14.6 mm/hour = 6.8 mm/hour

Source :

Rainfall Frequency Atlas for Canada, W.D. Hogg, D.A. Carr, Supply and Services Canada 1985.



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 312 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

TABLE 2.3

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

ESTIMATED PAN EVAPORATION AT SITE

	Quesnel	Williams Lake	Site
May	98	88	93
June	. 130	124	127
July	151	144	148
August	131	129	130
September	81	77	79
October	39	38	38
Total	630	600	615

Source:

Based on computed potential evapotranspiration data by AES using Thornthwaite model, increased by an empirical factor of 1.25 to bring into line with pan evaporation data.



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 313 of 500

CONSULTING ENGINEERS

TABLE 2.4

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

SEISMIC RISK CALCULATION

52.55 NORTH/NORD

ENERGY, MINES AND RESOURCES CANADA GEOLOGICAL SURVEY OF CANADA ENERGIE, MINES ET RESSOURCES CANADA COMMISSION GEOLOGIQUE DU CANADA

SEISMIC RISK CALCULATION *

REQUESTED BY/ DEMANDE PAR

CALCUL DE RISQUE SEISMIQUE *

Mt. Polley, B.C.

121. 63 WEST/OUEST

Jeremy Haile / Knight & Piesold Ltd.

SITE

LOCATED AT/ SITUE AU

PROBABILITY OF EXCEEDENCE PER ANNUM/ PRODABILITE DE DEPASSEMENT PAR ANNEE	0.010	0.005	0. 0021	0. 001
PROBABILITY OF EXCEEDENCE IN 50 YEARS/ PROBABILITE DE DEPASSEMENT EN 50 ANS	40 %	55 X	10 %	5%
PEAK HURIZONTAL GROUND ACCELERATION (G)	! ! ! 0.021	0. 028	0. 037	0. 046
ACCELERATION HORIZONTALE MAXIMALE DU SOL (G)	1		$\frac{1}{2} \sum_{i=1}^{n} \sum_{j=1}^{n} \sum_{i=1}^{n} \sum_{i=1}^{n} \sum_{i=1}^{n} \sum_{j=1}^{n} \sum_{i=1}^{n} \sum_{i=1}^{n} \sum_{i=1}^{n} \sum_{i=1}^$	
PEAK HORIZONTAL GROUND VELOCITY (M/SEC)	1 0 012	0.054	0.077	0.084
VITESSE HORIZONTALE MAXIMALE DU SOL (M/SEC)	! ! !	0, 056	0.077	0, 074

* REFERENCES

 NEW PRODABILISTIC STRONG SEISMIC GROUND MOTION MAPS OF CANADA: A COMPILATION OF EARTHQUAKE SOURCE ZONES, METHODS AND RESULTS. P.W. BASHAM, D.H. WEICHERT, F.M. ANGLIN, AND M.J. BERRY EARTH PHYSICS BRANCH OPEN FILE NUMBER 82-33, OTTAWA, CANADA 1982.

- ENGINEERING APPLICATIONS OF NEW PROBABILISTIC SEISMIC GROUND-MOTION MAPS OF CANADA.
 A. C. HEIDEBRECHT, P.W. BASHAM, J.H. RAIMER, AND M.J. BERRY CANADIAN JOURNAL OF CIVIL ENGINEERING, VOL. 10, NO. 4, P. 670-680, 1983.
- 3. NEW PROBABILISTIC STRONG GROUND NOTION MAPS OF CANADA. P.W. BASHAN, D.H. WEICHERT, F.M. ANGLIN, AND M.J. BERRY, BULLETIN OF THE SEISMOLOGICAL SOCIETY OF AMERICA, VOL. 75, NO. 2, P. 563-595, 1985.

4A. SUPPLEMENT TO THE NATIONAL BUILDING CODE OF CANADA 1985, NRCC NO. 23178. CHAPTER 1: CLIMATIC INFORMATION FOR BUILDING DESIGN IN CANADA. CHAPTER 4: CUMPENTARY J: EFFECTS OF EARTHQUAKES. Association des ingénieurs des ingénieurs

CHAPITRE 4: COMMENTAIRE J: EFFETS DES SEISMES.

23-DCT-89 20:17:40

mj

Knight Piésold Ltd. CONSULTING ENGINEERS

TABLE 2.4 (Continued)

SEISMIC RISK CALCULATION

SITE

Mt. Polley, B.C.

ZONING FOR ADOVE SITE/ ZONAGE DU SITE CI-DESSUS

1985 NECC/CNEC: ZA = 0; ZV = 1; V = 0.05 M/S

ACCELERATION ZONE/ ZONE D'ACCELERATION ZA=O ZONAL ACCELERATION/ ACCELERATION ZONALE 0.00 G

VELOCITY	ZONE/	ZONE DE \	/ITESSE	Z∨=1
ZONAL VE	LOCITY/	VITESSE	ZUNALE	0.05 M/S

1985 NBCC/CNBC ** SEISMIC ZONING MAPS/ CARTES DU ZONAGE SEISMIQUE

* PROBABILITY LEVEL: 10% IN 50 YEARS NIVEAU DE PROBABILITE: 10% EN 50 ANNEES

G OR M/S	ZONE	ZONAL VALUE
0.00		
	0	0.00
0.04		
	1	0.05
0.08		
	5	0.10
0.11		
0 1/	Э	0.15
0, 16	0	0 70
0 23		0.20
0. 60	5	0.30
0.32	3	
	6*	0.40

- * ZONE 6: NOMINAL VALUE/ VALEUR NOMINALE 0.40; SITE-SPECIFIC STUDIES SUGGESTED FOR IMPORTANT PROJECTS/ ETUDES COMPLEMENTAIRES SUGGEREES POUR DES PROJETS D'IMPORTANCE.
- ** FOR NDCC APPLICATIONS, CALCULATED ZONE VALUES AT A SITE SHOULD BE REPLACED BY EFFECTIVE ZONE VALUES [ZA(EFF) OR ZV(EFF)] AS SHOWN BELOW/ POUR APPLICATIONS SELON LE CNBC, ON DOIT REMPLACER LES VALEURS ZONALES CALCULEES POUR UN SITE PAR LES VALEURS EFFECTIVES [ZA(EFF) OU ZV(EFF)] COMME MONTRE CI-DESSOUS;

	1.	IF/SI	(ZA -	ZV) >	1.	DEN>	ZA(EFF)	5	ZV + 1.
OR/O	U								
	2.	IF/SI	(ZA -	ZV) C	1,	mmu>	ZA(EFF)	=	ZV - 1.
08/0	U								
()	Associat	E/SL	ssociation o	ANI)/E	T ZA > 0,	====>	ZV(EFF)	13	1.
	Enginee of Casa		onseils	2 CIT	ED ABOVE,	PAGE	677)		INVESTIGATION KP 1-11 315 of 500
	(10	DIR PA	GE 677	DE LA	REFERENC	E 2 CI	-DESSUS)		
									23-DCT-89 20:17:40

Knight Piésold Ltd. CONSULTING ENGINEERS

TABLE 3.1

X

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

SUMMARY OF PERMEABILITY TESTING IN OPEN PIT

Hole No.	Depth Interval	Measured Permeability
	(ft)	(cm/s)
MP89-145	40-60	1.0×10^{-6}
	70-90	4.6 x 10 ⁻⁶
	100-120	5.0 x 10 ⁻⁷
	130-150	3.5×10^{-6}
	160-180	1.3 x 10 ⁻⁵
	190-210	$< 3.0 \times 10^{-6}$
	220-240	8.7 x 10 ⁻⁷
MP89-146	60-80	8.8 x 10 ⁻⁶
	90-110	5.0 x 10- ⁷
	120-140	$6.9 \ge 10^{-7}$
	150-170	3.1×10^{-6}
	180-200	1.5×10^{-5}
	210-230	5.7 x 10 ⁻⁶
	240-260	2.2 x 10 ⁻⁶
	270-290	3.7 x 10 ⁻⁶
	300-320	1.1 x 10 ⁻⁵
	330-350	$1.6 \ge 10^{-4}$
	360-380	1,5 x 10 ⁻⁶
	390-410	$< 1.5 \times 10^{-6}$
	420-440	6.9 x 10 ⁻⁷



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 316 of 500

.

Knight Piésold Ltd. CONSULTING ENGINEERS

2

TABLE 3.1 (Continued)

Hole No.	Depth Interval	Measured Permeability
	(ft)	(cm/s)
MP89-146 (Con't)	460-480	9.8 x 10 ⁻⁷
	480-520	1.0×10^{-6}
	520-560	2.5×10^{-6}
	600-640	4.8 x 10 ⁻⁶
	640-700	2.0×10^{-6}
MP89-147	20-50	3.2×10^{-4}
	50-80	6.8×10^{-6}
	80-120	2.6×10^{-6}
	120-160	4.0×10^{-5}
	160-200	$1.4 \ge 10^{-4}$
	200-240	1.8×10^{-5}
	240-280	6.2 x 10 ⁻⁶
	280-320	1.8 x 10 ⁻⁵
	320-360	7.5×10^{-7}
	360-400	7.5×10^{-7}
MD90 149	20.60	10 - 10-4
WIP89-148	20-60	1.0×10^{-4}
	60-100	6.6 x 10 ⁴
	100-140	3.0 x 10 ⁻⁶
	140-180	4.2 x 10 ⁻⁴
	180-220	4.8 x 10 ⁻⁵
	220-260	3.0 x 10 ⁻⁵
	260-300	7.2 x 10 ⁻⁶
	300-340	4.9×10^{-4}



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 317 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

3

TABLE 3.1 (Continued)

Hole No.	Depth Interval	Measured Permeability
	(ft)	(cm/s)
MP89-155	20-50	2.8×10^{-5}
	50-90	1.6 x 10 ⁻⁵
	90-130	3.4×10^{-4}
	130-170	4.7 x 10 ⁻⁶
	170-210	$< 1.0 \times 10^{-7}$
	210-250	$< 1.0 \times 10^{-7}$
	250-290	1.0×10^{-7}
	290-330	1.7 x 10 ⁻⁶
	330-370	9.4 x 10 ⁻⁷
	370-410	4.5×10^{-6}
	410-450	1.5 x 10 ⁻⁷
	450-490	6.8 x 10 ⁻³
	490-530	1.4×10^{-4}
	530-570	3.6 x 10 ⁻⁵
	570-610	2.7×10^{-4}
	610-650	$< 1.0 \times 10^{-7}$
	650-700	$< 1.0 \times 10^{-7}$
Geometric Mean	n of all tests:	8.4 x 10 ⁻⁶ cm/s



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 318 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

TABLE 3.2

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT GROUNDWATER LEVELS IN PROPOSED OPEN PIT AREA

DEPTH TO GROUNDWATER TABLE (m) IN MONITORING WELLS

Date	<u>MP89-107</u>	<u>MP89-146</u>	<u>MP89-151</u>
August 16, 1989	28.0	14.7	35.5
November 8, 1989	10.0	10.5	31.0

DEPTH TO PHREATIC SURFACE (m) IN MULTIPLE PNEUMATIC PIEZOMETERS

	MP89-147A	-147B	-147C	MP89-155A	-155B
Tip Depth (m)	27.6	59.0	88.8	7.8	157.7
Date					
August 2, 1989	3.2	2.6	4.5	-	
August 15, 1989	3.5	2.4	4.6	-	-
November 12, 1989	2.2	1.6	9.2	2.7	*

Reading beyond capacity of read-out box.



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 319 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

TABLE 4.1

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

PRELIMINARY SLOPE DESIGN

DESIGN SECTOR	PIT SLOPE ORIENTATION	BENCH FACE ANGLE	BENCH HEIGHT (m)	BENCH WIDTH (m)	INTER- SLOPE ANGLE
Ţ	All slopes	70°	20	8.5	52°
II	Favourable conditions	75°	20	8.5	55°

Notes: 1. Pit slope design based on fully drained slope conditions.

 Pit slope design to be reviewed during initial development of pit, as actual conditions are encountered.



Association des Ingénieurs-Conseils du Canada


















IMPERIAL METALS CORPORATION MT. POLLEY PROJECT OPEN PIT – PRELIMINARY DESIGN SLOPE ANGLES AND BENCH DESIGN







ī

Plot

FILE: \1628\FIC\A4

3

DESIGN II – FAVOURABLE CONDITIONS ENCOUNTERED DURING PIT EXCAVATION



1628.A4



MT. POLLEY PROJECT WASTE DUMPS SHEAR STRENGTH OF ROCKFILL

IMPERIAL METALS CORPORATION



Information taken from : REVIEW OF SHEARING STRENGTH OF ROCKFILL By Thomas M. Leps, F. ASCE July , 1970

June 6, 1996 KNIGHT PIESOLD LTD. consulting engineers

CIL7733

FIGURE 5.2









Knight Piésold Ltd. CONSULTING ENGINEERS

APPENDIX A

REVIEW OF OPEN PIT DESIGN BY C.O.BRAWNER, P.ENG.



Association des Ingénieurs-Conseils du Canada 1628/1 July 5, 1996 INVESTIGATION KP 1-11 337 of 500

Knight and Piesold Ltd. CONSULTING ENGINEERS

SECTION 4.0 - OPEN PIT SLOPE DESIGN

4.1 FACTORS WHICH INFLUENCE PIT SLOPE STABILITY AND SLOPE ANGLE

The most important factors which influence rock slope stability of open pit mines are geologic structure, groundwater conditions and seismic acceleration forces due to blasting.

Where geologic discontinuities, (joints, bedding planes, foliation, shears, faults, etc.) singly or in combination dip out of the slope at angles near or in excess of the angle of friction of the discontinuities, a potential for failure exists. It is essential that the geologic model of discontinuities around the pit be determined and the kinematic potential for failure evaluated. Typical failure models are shown in Figure 4.1. They include circular, planar, wedge, block and toppling modes.

Where multiple bench failures can occur along discontinuities, it is normally necessary to obtain samples to perform direct shear tests along these discontinuities. The surface roughness and waviness along the discontinuity must be evaluated in the direction of sliding. This may increase the effective angle of friction by ten degrees or more. Both conditions require assessment in order to evaluate the safety factor for that portion of the slope.

The presence of groundwater in the slopes may influence stability in a number of ways:

a. Reduction in the frictional shear strength due to buoyancy.

Reduction in cohesion of clay gouge or clayey rock with increasing moisture content.



Knight and Piesold Std.

c. Development of seepage forces during drainage towards the pit slope.

 Creation of hydrostatic forces in tension cracks during heavy rainfall or snow melt (this pressure increases as the square of the depth).

e. An increase in hydrodynamic shock due to blasting below the water table.

As a result, it is important that the water table and groundwater pressures be maintained low in the pit slopes. The most effective way to develop this control is with the installation of horizontal drains. Any tension cracks that develop should be monitored and filled in to prevent the build up of water pressures.

Seismic acceleration forces due to blasting must be reduced at the final pit face to allow the steepest practical slopes to be used to minimize the waste to ore ratio. This will usually comprise using controlled blasting for the line holes, angled line holes, buffer holes adjacent to the line holes, numerous delays and blasting to a free face. Photographs of representative conditions are enclosed in Figure 4.2. The relationship between distance from the blast, pounds per delay and particle velocity (related to damage) is given in Figure 4.3.

4.2 STRUCTURAL GEOLOGY

Three boreholes, MP89-152 to MP89-154 were drilled on an inclination and the core was oriented using the clay imprint procedure as discussed in Section 3. Stereographic plots are shown in Figures 3.2 to 3.5. The overall plots indicate the major joint set has an average strike of 167 degrees and an average dip of 75 degrees E. The strike variation is about \pm 20 degrees and the dip variation about \pm 10 degrees. A second set of joints strikes 30 degrees \pm 20 degrees and dips 18 degrees W \pm 10 degrees. These geological structures are the major features which will influence pit slope stability for all walls.



Association Association of Consulting des Ingénieurs-Engineers Conseils of Canada du Canada

Knight and Presold Ltd. CONSULTING ENGINEERS

CONSULTING ENGINEERS

27

This structure will lead to certain types of potential instability in each pit face depending on the face direction. The pit slope design must accommodate this potential.

East facing slopes	-	planar failure along shears, faults and
		contacts
North facing slopes	-	shallow wedges along joint intersections
		or fault contacts
South facing slopes	-	local wedges adjacent to fault contacts
West facing slopes	-	toppling
South facing slopes West facing slopes	-	or fault contacts local wedges adjacent to fault contacts toppling

Rock joint continuity data (R.Q.D. and Joint Frequency) is shown in Appendix B, together with unconfined compressive strength data. Generally the rock strength is moderate to high so that stability will be controlled by the geologic structure. Several local zones of high fracturing and low strength were noted, i.e. - hole MP89-152, depth 180-350 feet. When the preliminary pit design has been developed, it will be necessary to evaluate rock strength data where drill holes intersect the pit walls to determine if any special design modification would be required. The west facing slopes must be evaluated in particular. If weak zones dip into these slopes, stress relief and high stress could cause subsidence and over stress the overlying rock to initiate toppling movement.

4.3 EVALUATION AND CONTROL OF GROUNDWATER

Groundwater is generally reasonably shallow below the ground surface. In some drill holes it was artesian. Consideration must be given to developing drainage of the pit walls to allow steep slopes and drainage in the pit floor to prevent pit bottom heaving. Wet blast holes will also require the use of more expensive explosives than the standard ANFO.



Association Association of Consulting des Ingénieurs-Engineers Conseils of Canada du Canada

Knight and Presold Ltd. CONSULTING ENGINEERS

The projected open pit dewatering requirements have been estimated from the permeability test results and by a general water balance incorporating climatic data and hydrogeologic information. The volume of recoverable groundwater stored in the bedrock fractures and fissures has been estimated by assuming a specific yield of 0.005. Open pit dewatering systems will be required to remove this water from storage. Additional open pit inflows will include direct precipitation and groundwater er recharge from the area of influence. The hydrometeorologic data presented in Section 2.1 has been adjusted for runoff and transpiration losses to enable a prediction of annual recharge to the groundwater system.

The rate of groundwater inflow is controlled by the permeability of the bedrock. The bedrock permeability is expected to be anisotropic due to structural features. Rock structure provides a barrier to groundwater movement across relatively intact formations and low permeability clay gouge but also results in preferential flow parallel to fractured rock zones. The site investigation program outlined in Section 3.2 identified zones with a broad range of permeabilities.

It is anticipated that the principal directions of groundwater inflow will be parallel to the dominant structural features which trend roughly north and south. This groundwater flow trend is advantageous in the later years of operation, when the ultimate depth of the west pit is below the surface elevation for Bootjack Lake. In general, the rock structure provides a natural barrier to flow from Bootjack Lake into the bottom of the ultimate pit. However the approximately east-west trending fault structure in the west zone, as shown on Figure 2.3, may provide a high permeability conduit for groundwater flow. On-going evaluation of pit geology during operations will enable accurate predictions to be made prior to final development.

It is estimated that the average, steady state pumping requirements for open pit groundwater control over the life of the project will be approximately 15 L/s (200



Knight and Piesold Std. CONSULTING ENGINEER

Igpm). This estimate does not include for removal of direct precipitation which will average approximately 13 L/s (175 Igpm) annually. The actual pit dewatering rate will be higher in the early stages of the operation when groundwater is removed from storage, and during periods of high rainfall.

Generally the most effective ways of controlling seepage into the pit is to install horizontal drain holes. They should be 20 to 30 metres (60 to 100 ft) long, drilled at a +2 to +3 degree slope and spaced about 12 metres (40 ft) apart at the toe of each double bench where seepage is encountered. In order to locate seepage zones, all blast holes which have water in them along the line holes and buffer holes should be plotted on blasting plans. The horizontal drain holes are only installed in areas where seepage is indicated.

If wet holes become a problem, a program to drill every tenth to twelfth blast hole an additional 6 to 9 metres (20 to 30 ft) deep and blast to that lower depth will provide a groundwater sink and help to lower the water table in the blast area. If this procedure is not successful, pumping wells at a number of locations around the pit may be required.

In order to continue to monitor the groundwater level conditions, a percentage of future drill holes should have piezometers installed to monitor the water table.

4.4 BLASTING CONTROL NEAR THE FINAL WALLS

Where the pit slope design angle will not be controlled by the structural geology the use of controlled blasting at the final face will normally allow an increase of 5 to 7 degrees in the slope angle. This involves the use of controlled blasting, with reasonably small diameter blast holes detonated as a pre-shear line in the harder massive rock or as a cushion or post shear line in weak or heavily fractured rock. The line holes should not be larger than 15 cm (6 inches) in diameter and spaced



Association Association of Consulting des Ingénieurs-Engineers Conseils of Canada du Canada

Knight and Piesold Ltd. CONSULTING ENGINEERS

1.5 to 2 m (5 to 6 ft) apart. It is preferable if this pre-shear line is drilled at an angle of 70-75 degrees below the horizontal rather than vertical. It is also desirable to drill the line holes double bench depth to do away with a small bench lip which could develop half way up a double benched slope. To minimize wall damage it is preferable that the explosive in the line holes be decoupled laterally and/or air decked to spread the explosive more throughout the length of the hole. Rock excavation should be to the line holes and not beyond.

Two or three lines of buffer holes are recommended, drilled in front of the line holes with the spacing equal to about one-half that between the production holes. The first line of buffer holes should be angled. The others may be vertical. They should use the same diameter as the line holes. In order to drill the angle holes, it will be necessary to purchase or lease a drill which drills this size of hole and can be angled at angles up to about 25 degrees. Tamrock have drills with angled capacity. The amount of explosives per buffer hole will be approximately one-quarter that in the production holes. All buffer holes should be delayed.

Production holes may use larger diameter drills. Every hole of a production blast within one hundred feet of the final wall must be delayed singly.

Blasting should be developed towards a free face with that free face perpendicular to the wall. A typical trial blast pattern is shown in Figure 4.4. Figure 4.2 shows an excellent blast control program at Gortrum Mines in Ireland. Figure 4.3 is a plot of damage to rock, related to the weight of charge per delay, and the blast distance to the final wall. This graph emphasizes the utmost importance of using delays to reduce seismic acceleration forces to minimize wall damage.

The best blast design will result from trial test blast patterns in the field. The most beneficial program will develop where the open pit will be developed initially as a small pit and a subsequent set back will be developed. This initial pit can be



Knight and Presold Std. CONSULTING ENGINEERS

developed with variable test slopes and test blast patterns to develop the best blast design for the final wall. Test trial blasts will be required wherever the rock conditions change substantially.

It is recommended that double benching be used at the final wall. In order for this procedure to be successful, the upper bench face must be scaled prior to drilling the buffer holes on the next lower bench elevation. It is also important that blast holes be staggered so the bottom of the hole does not intercept the crest of the bench below. Otherwise, very fragmented bench crests will develop leading to considerable ravelling and a greater berm width.

It is recommended that the operators of front-end loaders or shovel loaders who excavate this final face be given a seminar on structural geology, particularly the identification of small planar blocks and small wedges which could fail. By recognizing these in advance, they can dig them out so that ravelling at a later date will be reduced. By minimizing this ravelling the bench width can be narrowed to increase the overall slope angle.

Do not place piles of loose rock at the outer side of berms to catch ravelling rock. This requires an excessive bench width and results in overall flatter slope angles. Berms are to catch ravelled rock. They are not intended for later access.

4.5 MONITORING

The development of slope movement will be indicated by the development of a tension crack or cracks. It is most important that periodic inspections along the crest and bench locations be performed periodically to locate such cracks.

When tension cracks are observed the initial monitoring program requires the installation of surface movement hubs or gages which will allow measurement of



Association Association of Consulting des Ingénieura-Engineers Conseils of Canada du Canada

Knight and Piesold Ltd. CONSULTING ENGINEERS

both vertical and horizontal displacement. This is required to evaluate the type of movement that is occurring - circular, planar, toppling etc.

If larger scale movements appear to be developing, an electronic distance measuring (EDM) prism monitoring system should be developed. Three or four prisms should be installed on a line down the center of the slide with readings taken daily from a fixed station across the pit. Movement records should be plotted daily to determine if there is an acceleration of the movement. Plots should be made of a total movement vs time. At this point in time a decision as to whether the slide will be stabilized or whether it will simply be monitored and allowed to fail will then be made. If it is to be allowed to fail, continued monitoring of the acceleration will allow the date of failure to be predicted several days in advance. Mining would be discontinued at this time.

From a practical standpoint, where failure volumes involve 500,000 cubic yards or more, experience is that a failure will not occur within the next 24 hours if the amount of daily movement is less than about three inches.

Any failures involving one or more benches should be back analyzed. The location, structural geology, face failure geometry, failure surface roughness, seepage and blasting details etc. should be recorded. This allows the most accurate evaluation of the shear strength along the failure surface to be determined, to be used in redesign. Photographs should be taken and described.

4.6 BENCH DESIGN

For final pit wall bench design it is proposed that controlled blasting be used to develop a relatively steep bench face (70 to 75 degrees) which should be scaled with excavating equipment and a drag chain or equivalent from the top. Double benching is recommended. The scaling will reduce subsequent ravelling and reduce



Association Association of Consulting des Ingénieurs-Engineers Conseils of Canada du Canada

Knight and Piesold Ltd. CONSULTING ENGINEERS

the catch width required for berms. Where the rock face stands up well, a 6 metre (20 foot) wide bench is suggested. If the rock is very fractured and considerable ravelling occurs the bench will have to be widened to about 8 metres (25 feet).

If areas of heavily fractured rock or faulted rock are encountered in the final slopes, more stable bench faces can frequently be developed using bulldozers and rippers rather than blasting along the final line holes. By utilizing this procedure the slope angles at Bougainville, in Papua New Guinea, for example, were steepened some 8 degrees.

4.7 PRELIMINARY PIT SLOPE DESIGN

East Facing Slope - A revised geological interpretation provided by Imperial Metals Corporation indicates the geologic structure is reasonably uniform over all three pits. Planar failures will occur locally where the structure dip is flatter than the bench face angle.

The slope angle can be developed with bench face angles of 70 degrees. The overall angle will depend on berm width, bench height and whether single or double benching will be used. See Table 4.1 and Figures 4.5 and 4.6.

<u>West Facing Slopes</u> - Based on existing structural geologic data the structure dips into the west facing slopes at about 45 to 75 degrees. Where the structure dip is less than about 60 degrees and does not cross major faults the bench faces can be developed at 75 degrees. The overall angle will depend on berm width, bench height and single or double benching. Where the dip angle is steeper than about 60 degrees the potential for toppling failure exists. The bench faces should be flattened to 70 degrees and berm widths should be increased by 2.0 metres.



Association Association of Consulting des Ingénieurs-Engineers Conseils of Canada du Canada

Knight and Piesold Ltd. ONSULTING ENGINEERS

The overall slope angles for various conditions are shown in Table 4.1 and Figures 4.5 and 4.6.

It is very important that these slopes be drained.

<u>South Facing Walls</u> - The fault structures generally dip N-S and will not materially influence slope stability. The joints dip into the slope which is a stable condition. Accordingly bench faces can be developed at 75 degrees with minimum berms widths. The overall slope angle will depend on the use of single or double benches. See Table 4.1 and Figures 4.5 and 4.6.

<u>North Facing Walls</u> - The fault structures will have similar influence as in the south facing walls. The two joint sets prevalent at the site will intersect to form shallow wedges. Some local bench size failures can be expected. Bench faces should be developed at 70 degrees with wider catch berms. The overall slope angles for various conditions are given in Table 4.1 and Figures 4.5 and 4.6.

Note that the slope angles recommended do not include haul roads.

<u>Pit Noses</u> - The preliminary design of the west pit and central pit has created a north and a south nose. Such noses usually suffer from excessive ravelling and instability. It is recommended the overall slopes in any such area be flattened 10 degrees by using wider catch benches.

<u>Ramps</u> - It is desirable to locate haul roads on the most stable pit wall - in this instance along the west facing slopes.

<u>Fault Intersections</u> - Where faults intersect the walls at shallow angles (<30 degrees) local wedge failures will occur. Extra scaling will be required.



Ássociation Association of Consulting des Ingénieurs-Engineers Conseils of Canada du Canada

Knight Piésold Ltd. CONSULTING ENGINEERS

APPENDIX B

DISCONTINUITY DATA AND POINT LOAD TEST RESULTS



Association des Ingénieurs-Conseils du Canada 1628/1

July 5, 1996 INVESTIGATION KP 1-11 348 of 500 Knight Piésold Ltd.

CONSULTING ENGINEERS

APPENDIX B

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

DISCONTINUITY DATA AND POINT LOAD TEST RESULTS

DRILLHOLE MP89-152 (285/55)

D	EPTH	ROCK	R.Q.D.	FRACTURE	GAUGE	COMP.S	TRENGTH
from	to	TYPE		INDEX (jt/ft)	(psi)	(psi)	(MPa)
10	20	DIORITE	60	2.0	3200	36188	250
20	30		82	2.0	3200	36188	250
30	40		83	1.0	3500	39581	273
					2900	32796	226
40	50		68	1.5	3500	39581	273
					2800	31665	218
50	60		95	1.2			15
60	70		80	2.0	1000	11309	78
70	80		88	1.0	2000	22618	156
					4000	45235	312
80	90		93	1.5	2900	32796	226
90	100		68	3.0	2000	22618	156
100	110		93	1.0	1000	11309	78
110	120		100	1.2	2200	24879	172
120	130		65	2.7			
130	140		80	1.0	2800	31665	218
140	150		80	1.2	3000	33926	234
150	160		75	1.3	3000	33926	234
160	170		97	1.7	1900	21487	148
170	180		75	1.7	2600	29403	203
180	190		80	High	400	4524	31
190	200		20	High			
200	210		40	High	1800	20356	140
220	230		20	V.High			
220	230	SYENO	40	High	400	4524	31
230	240		60	2.5	1500	16963	117
240	250		35	3.0	1000	11309	78
250	260		18	High			
260	270		35	High	200	2262	16
270	280		25	High	200	2262	16
280	290		10	High	900	10178	70
290	300		7		100	1131	8
300	310		5	High			
310	320		3	High	700	7916	55



2

APPENDIX B (Continued)

DRILLHOLE MP89-152 (285/55)

	DEPTH ROCK	<u>R.Q.D.</u>	FRACTURE	GAUGE	COMP.STRENGTH	
from	to <u>TYPE</u>		INDEX (jt/ft)	(psi)	(psi)	(MPa)
320	330	0	High			
330	340	15	High	700	7916	55
340	350	-	1.5	600	6785	47
				800	9047	62
350	360	85	1.8	1700	19225	133
				2200	24879	172
360	370	99	0.7	1100	12440	86
370	380	95	1.5	2700	30534	211
380	390	95	1.2	2600	29403	203
390	400	80	4.0	1200	13571	94
				2000	22618	156
400	410	80	1.0	2100	23748	164
410	420	80	3.3	1800	20356	140
				2600	29403	203
420	430	65	3.3	1200	13571	94
430	440	70	3.0	700	7916	55
440	450	15	High	1200	13571	94
450	460	83	1.7	1200	13571	94
				1000	11309	78
460	470	94	1.4	1600	18094	125
470	480	90	1.0	1000	10051	100
480	490	85	1.1	2800	31665	218
				400	4524	31
490	500	80	2.0	100		
500	510	65	1.0	700	7916	55
510	520	40	3.0	900	10178	70
520	530	70	1.6	1800	20356	140
530	540	75	0.8	1000	20000	2.10
540	550	85	0.8	700	7916	55
		00	010	1200	13571	94
550	560	45	High	900	10178	70
560	570	45	High	600	6785	47
570	580	25	High	400	4524	31
510	200	35	High	600	6785	17
580	590	30	High	2800	31665	218
590	600	15	High	2000	7016	55
550	000	15	ILEU	1500	16063	117
600	610	02	0.4	2100	23749	164
610	620	00	0.5	1000	21/197	148
620	630	72	1.6	1900	2140/	140
A	Association of Consulting Engineers of Canada du Canada	21	1.0	INVESTIGATIO	ON KP 1-11 350) of 500

APPENDIX B (Continued)

3

DRILLHOLE MP89-152 (285/55)

DI	EPTH	ROCK	<u>R.Q.D.</u>	FRACTURE	GAUGE	COMP.S	TRENGTH	
from	to	TYPE ·		INDEX (jt/ft)	(psi)	(psi)	(MPa)	
630	640		92	1.0	2000	22618	156	
640	650		92	0.8	800	904	762 7	
650	660		35	1.2	300	3393	23	
660	670		98	0.5	200	2262	16	
					900	10178	70	
670	680	IB	95	0.8	1700	19225	133	
					1600	18094	125	
680	690		95	0.7	400	4524	31	
					1000	11309	78	
690	700		87	1.3	3000	33926	234	
					2000	22618	156	
					1700	1922	133	
700	710	DYKE	95	1.2	1200	13571	94	
		IB			1000	11309	78	
710	720		100	0.6	2800	31665	218	
720	730		85	1.1	600	6785	47	
730	740		90	1.0	1900	21487	148	
740	750		50	1.0	300	3393	23	
					100	1131	8	
750	760		100	0.4	1300	14701	101	
					1200	13571	94	
760	770		90	0.6	300	3393	23	
					700	7916	55	
770	780		40	High	50	565	4	
780	790		35	1.5	1900	21487	148	
790	800		25	High	1500	16963	117	
800	810		-	0.9	3200	36188	250	
810	820		92	0.9	1100	12440	86	
					3200	36188	250	
820	830		87	1.1	2500	28272	195	
830	840		80	1.1	900	10178	70	
0.10	0.50				2100	23748	164	
840	850		50	High	600	6785	47	
0.50	0.00		00		1600	18094	125	
850	860		90	1.1	2300	26010	179	
0.40	070		0.5		1500	16963	117	
860	870		95	1.1	1100	12440	86	
870	880		25	1.2	800	9047	62	
880	890		96	0.5	200	2262	16	
(Association	Association			500	5654	39	



of Consulting Engineers of Canada des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 351 of 500

APPENDIX B (Continued)

4

DRILLHOLE MP89-152 (285/55)

DI	EPTH	ROCK	<u>R.Q.D.</u>	FRACTURE	GAUGE	COMP.S	TRENGTH
from	to	TYPE		INDEX (jt/ft)	(psi)	(psi)	(MPa)
890	900		94	0.7	300	3393	23
900	910		90	1.7	800	9047	62
910	920		55	3.0	300	3393	23
920	930		45	2.0	200	2262	16
					400	4524	31
930	940		30	High	100	1131	8
940	950		87	1.4	3500	39581	273
950	960		70	2.0	1200	13571	94
960	970		90	1.5	1500	16963	117
970	980		93	1.4	2500	28272	195
×					200	2262	16
980	990		85	1.3	1500	16963	117
990	1000			1.5	2300	26010	179
DRILL	HOLE MP	89-153 (253/50))				
30	40		25	High	1000	11309	78
40	50		15	High			
50	60		35	High	500	5654	39
60	70		70	High	1000	11309	78
70	80	DYKE	35	High	2500	28272	195
		IB		0	600	6785	47
80	90		15	High	100	1131	8
90	100		35	High	100	1131	8
100	110		18	3.0	800	9047	62
110	120		50	2.2	2300	26010	179
120	130		15	3.0	1700	19225	133
130	140		12	4.0	1200	13571	94
140	150		95	1.1	400	4524	31
150	160		95	0.9	1300	14701	101
160	170		91	1.0	2000	22618	156
170	180		35	26	1200	13571	94
180	190		65	2.0	100	1131	8
100	170		05	2.4	300	3303	23
190	200		87	13	2700	30534	211
200	210		00	0.8	3600	40712	. 281
210	220		04	1.2	1800	20356	140
210	220		74	1.4	2500	20330	195
220	220		07	07	3800	120272	296
230	230	725 17	02	11	2900	32706	226
A	Association of Consulting Engineers of Canada	Association des Ingénieurs- Conseils du Canada	74	1.1	INVESTIGATIC	DN KP 1-11 352	of 500

1

APPENDIX B (Continued)

5

DRILLHOLE MP89-153 (253/50)

DI	EPTH	ROCK	<u>R.Q.D.</u>	FRACTURE	GAUGE	COMP.S	TRENGTH
from	to	TYPE		INDEX (jt/ft)	(psi)	(psi)	(MPa)
0.40	050	x	100				
240	250		100	0.6	2500	28272	195
250	260	(<u>+</u>)	80	1.4	1100	12440	86
260	270		100	0.4	1000	11309	78
			100	0.4	1400	15832	109
270	280		100	0.4	3000	33926	234
			100	0.4	1500	16963	117
280	290		80	1.2	2600	29403	203
290	300		96	0.7	1700	19225	133
300	310		89	1.1	1400	15832	109
310	320		96	0.9	2400	27141	187
320	330		50	2.7	1300	14701	101
330	340	DYKE	80	1.2	600	6785	47
		IB			400	4524	31
340	355		83	1.0	2200	24879	172
350	360		98	0.6	1500	16963	117
360	370		100	0.6	1400	15832	109
370	380		80	1.6	1000	11309	78
380	390		100	0.4	1600	18094	125
390	400		98	0.9	2200	24879	172
400	410		100	0.3	2000	22618	156
410	420		100	0.5			
420	430		100	1.0	1300	14701	101
430	440		100	0.5	2000	22618	156
					1200	13571	94
440	450		91	0.4	1900	21487	148
450	460		96	0.6	1800	20356	140
460	470		100	0.5			
470	480		100	0.7	1200	13571	94
480	490		100	0.3	1200	13571	94
490	500		100	0.0	1200	13571	94
					1000	11309	78
					4000	45235	312
500	510		100	0.4	2500	28272	195
510	520		98	0.7	1500	16963	117
520	530		97	0.7	3000	33926	234
530	540		90	0.8	2200	24879	172
540	550		100	0.3	2200	24879	172
550	560		100	0.7	2300	26010	179
560	570		65	1.8	800	9047	62
570	×. 580	Accordiation	50	2.6	300	3393	23
(A	of Consulting Engineers of Canada	des Ingénieurs- Conseils du Canada			INVESTIGATI	ON KP 1-11 35	3 of 500

12

6

 $\hat{k}^{(i)}$

APPENDIX B (Continued)

DRILLHOLE MP89-153 (253/50)

DI	EPTH	ROCK R.Q.D	R.Q.D.	FRACTURE	GAUGE	COMP.STRENGTH	
from	to	TYPE		INDEX (jt/ft)	(psi)	(psi)	(MPa)
		~			700	7916	55
580	590		20	2.0	500	5654	39
					2800	31665	218
590	600		75	1.5	1100	12440	86
600	610		40	3.0	50	565	4
					100	1131	8
610	620		82	1.3	800	9047	62
620	630		97	0.6	1000	11309	78
630	640		95	0.3	2400	27141	187
640	650		80	1.2	2000	22618	156
650	660		100	0.3	2800	31665	218
660	670		100	0.1	500	5654	39
					1000	11309	78
670	680		98	0.4	2700	30534	211
					700	7916	55
680	690		95	1.1	100	1131	8
				1.1	700	7916	55
690	700		96	0.8	1000	11309	78
700	710		89	0.9	2200	24879	172
710	720		92	0.7	900	10178	70
720	730	DYKE	70	1.4	1000	11309	78
730	740		75	0.8	1500	16963	117
DRILLI	HOLE MP	89-154 (245/50))				
10	20	IB	20	2.5	2000	22618	156
					2800	31665	218
20	30		30	2.5	1400	15832	109
. 30	40		50	1.8	400	4524	31
40	50		30	1.8			
50	60	DYKE	70	1.7	100	1131	8
		IB			300	3393	23
60	70		25	3.0	1100	12440	86
70	80		95	High	400	4524	31
80	90		45	High	400	4524	31
90	100		7	High	1100	12440	86
100	110		45	1.9	600	6785	47
110	120		55	1.9	2600	29403	203
120	130	DYKE	55	2.1	600	6785	47
130	1. 1. ADiation		30	High	350	3958	27
(A	of Consultin Engineers of Canada	g des Ingénieurs- Conseils du Canada			INVESTIGATI	ON KP 1-11 35	54 of 500

7

APPENDIX B (Continued)

DRILLHOLE MP89-154 (245/50)

DI	EPTH	ROCK	<u>R.Q.D.</u>	FRACTURE	GAUGE	COMP.S	TRENGTH
from	to	TYPE		INDEX (jt/ft)	(psi)	(psi)	(MPa)
140	150		25	3.0	350	3958	27
150	160		55	1.7	150	1696	12
160	170		55	1.0	300	3393	23
170	180		35	High			
180	190		30	High	300	3393	23
190	200		60	High			
200	210	DYKE	12	High	300	3393	23
210	220	IB	3	High	250	2827	19
220	230		3	High	50	565	4
230	240		15	High			
240	250		40	High	1100	12440	86
250	260		30	High			
260	270		45	High			
270	280		14	High			
280	290			High			
290	300	DYKE	18	High	500	5654	39
300	310	IB	5	High			
310	320		18	High	300	3393	23
320	330		45	7.5	700	7916	55
					900	10178	70
330	340		75	1.5	4100	46366	320
340	350		95	1.2	5000	56544	390
350	360		85	1.6			
360	370		94	0.9	3000	33926	234
370	380		91	1.1	2600	29403	203
380	390		40	2.2	3400	38450	265
390	400		97	1.2	4100	46366	320
					3600	40712	281
400	410		93	1.3	3000	33926	234
410	420		93	1.2	1400	15832	109
420	430		92	1.4	3500	39581	273
430	440		83	2.3			
440	450	SYENO	85	1.6	2900	32796	226
450	460		90	1.1	2800	31665	218
460	470		95	0.8			
470	480		87	1.0			
480	490		95	1.1			
490	500		94	1.2			
500	510		96	1.2			
510	520 ation	Association	91	1.0			
K	of Consulti Engineers of Canada	ng des Ingénieurs- Conseils du Canada			INVESTIGAT	ION KP 1-11 3	55 of 500

8

APPENDIX B (Continued)

DRILLHOLE MP89-154 (245/50)

DI	EPTH	ROCK	R.Q.D.	FRACTURE	GAUGE	GAUGE COMP.S	
from	to	TYPE		<u>INDEX</u> (jt/ft)	(psi)	(psi)	(MPa)
520	530		92	1.4			
530	540		100	0.4			
540	550		98	0.7			
550	560		92	0.9			
560	570	IB	87	1.3	2400	27141	187
570	580		95	1.1	2000	22618	156
580	590	DYKE	82	0.8	3400	38450	265
				25	High		
600	610	SYENO	100	0.1	3600	40712	281
610	620	IB	97	1.2	1400	15832	109
620	630	DYKE	95	0.7	1600	18094	125
630	640	SYENO	90	0.9	900	10178	70
640	650		92	1.3	3700	41843	289
650	660		85	1.4	1600	18094	125
660	670		90	1.3	1700	19225	133
670	680		96	0.7			
680	690		99	1.0	1400	15832	109
690	700		95	1.0	3500	39581	273
700	710	IB	87	1.0	500	5654	39
710	720		80	1.3	100	1131	8
					1500	16963	117
720	730		30	2.0	900	10178	70
730	740		40	2.0	500	5654	39
740	750		30	High	500	5654	39
750	760		20	High	0	0	0
760	770		25	V.High			
770	780		10	V.High	0	0	0
780	790		18	V.High	50	565	4
790	800		15	V.High			
800	810		34	High	50	565	4
810	820		23	High	300	3393	23
					0	0	0
820	830		6	V.High	150	1696	12
830	840		40	High			
840	850	IB	68	1.4	600	6785	47
850	860		53	1.4	1300	14701	101
860	870		50	1.2	2000		
870	880		85	1.1	150	1696	12
880	890		70	1.3	800	9047	62
890	> 900	Association	100	1.0	300	3393	23
X	of Consulting Engineers of Canada	g des Ingénieurs- Conseils du Canada			INVESTIGAT	ION KP 1-11 3	56 of 500

9

APPENDIX B (Continued)

DRILLHOLE MP89-154 (245/50)

	DEPTH	ROCK	R.Q.D.	FRACTURE	GAUGE	COMP.S	TRENGTH
, from	n to	TYPE		INDEX (jt/ft)	(psi)	(psi)	(MPa)
900	910		100	0.4	800	9047	62
910	920		97	0.7	400	4524	31
920	930		65	1.0	1200	13571	94
930	940		100	0.6	800	9047	62
940	950		89	0.8	500	5654	39
950	960		98	0.7	1400	15832	109
960	970		90	1.4	200	2262	16
970	980		18	1.5	400	4524	31
980	990		70	1.2	2000	22618	156
990	1000		93	1.6	300	3393	23
100	0 1010		15	High	100	1131	8
101	0 1020		15	High			
102	0 1030		85	1.5	1100	12440	86
103	0 1040		85	1.5	1500	16963	117



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 357 of 500

1

Knight Piésold Ltd. CONSULTING ENGINEERS

APPENDIX C

TEST PIT LOGS



Association des Ingénieurs-Conseils du Canada 1628/1 July 5, 1996 INVESTIGATION KP 1-11 358 of 500

		TEST PIT No.
KNIGHT AND PIESOLD LTD. CONSULTING ENGINEERS	TEST PIT L	_OG TP35-1 SHEET / of /
PROJECT Mt Polley		PROJECT No. 1623
LOCATION OF TEST PIT A	000x 5,822,550N, 592,610E	GROUND ELEVATION ~ 1112 m
DATE Jan 11/95	- Fine are stockpile	LOGGED BY KGB
NOTES Groundwater level, difficulty in digg- ing, equipment used, etc. DEPTH (metres)	GRAPHIC LOG DESCRIPTION OF	AND CLASSIFICATION MATERIAL
Hitachi 200 hoc.	* * * Cark brown / black ORGAN	JICS
Maderate digging conditions.	Brown, dense, slightly SILT with some clay. Well graded, Becomes denser at chunks are ripped Sandy Silt Gle	moist, fine-grained sandy fine-grained gravel and poorly sorted. depth (dense, cohesive from in-site material). <u>acial Till</u>
from 4 to s.s.m		
	+0, +	
Seep encantered5 at 5.2 m depth	saturated till below	5.2 m.
6-	ED.P Ho excavate any	at 5.5m. Too deep further.
7-		
		INVESTIGATION KP 1-11 359 of 500

KNIGHT AND F	PIESOLD LTD.		TEST PIT	LOG	TEST PIT NO. TP95-2 SHEET 1 OF 1
PROJECT LOCATION OF DATEJan	M+ Polley TEST PIT 11 /95	<u>Арргох 5,8;</u> Сс	22,560 N 592,730 E	PROJECT No GROUND ELEVAT LOGGED BY	1623 ION <u>~ 11 10 m</u> LGB
NOTES Groundwater level, difficulty in digg- ing, equipment used, etc.	DEPTH (Metres)	GRAPHIC LOG	DESCRIPTION	AND CLASSIFICAT	ION
Hitachi 200 hoe Water table encountered at 1.2 m No scorples taken.		× ± ± + 0, + + 0, + 0, + 0, E. 0, P	<u>Dark brown / black, eaturat</u> Orange brown / brown, dense sandy SILT with Organics sometimes cocour Sandy SILT Glau Bedrock encountered at fragments, typically I water table.	ed, ORGANICS. c, moist to very moi the same gravel a stored to Im depth cial Till I. Zm depth. Ar Dem dia. Wet de	ist, fine-grained nd clay. h. ngular ve to
			Note: This trench was long: 1-6m-1 4m 1 • The north-south po of organize, a -the bedrock. • The east west port • Both limbs encounted	excavated appro A A A A A A A A A A A A A	x. 10m 2 Im 1 ovorlying above. 110w depths.
۶.	-			INVESTIGATION KP 1-11 3	360 of 500
PROJECT MH. Polley PROJECT No. 1623 LOCATION OF TEST PIT Approx 5,872,56 E GROUND ELEVATION ~ II DATE In 1625 Concentrator DATE In 1625 Concentrator IDATE In 1625 Concentrator BEDTH GRAPHIC LOG Ing. equipment DEPTH GRAPHIC Used, etc. Indexter DESCRIPTION AND CLASSIFICATION Moderate Indexter Indexter Moderate Indexter Description Moderate Indexter Brown, dense, fine-grained sandy SILT with som Indexter Indexter Gravel and clay. Stightly moist to moist. Moderate Indexter Similar to material encountered in TP35-1 No samples Indexter Indexter Indexter Indexter Indexter Waler table Indexter Indexter Internation Indexter Indexter Indexter Indexter Indexter Indexter Indexter Indexter Indexter Indexter Indexter Indexter Indexter	CONSULTING	PIESOLD LTD.	TEST PIT	LOG	TEST PIT NO TP95-3
--	--	--	---	--	---
NOTES Groundwater level, difficulty in digg- ing, equipment used, etc. DEPTH (metres) GRAPHIC LOG DESCRIPTION AND CLASSIFICATION OF MATERIAL Hitachi 200 hoc + 0 + 1 + + 00 digging conditions 0 + 0 + 1 + + 00 gravel a.d clay. Slightly moist to moist. Similer to material encountered in TP35-1 Similer to material encountered in TP35-1 Similer to material encountered in TP35-1 Similer to material encountered in TP35-1 Sordy Silt Glackal Trill Water table encountered. at 2.1 m V 2 + + + 0 - + + + 0 - + + + + 0 - + + + + 0 - + + + + + + + + + + + + + + + + + + +	PROJECT LOCATION OF DATE	Mt. Polley F TEST PIT Approx 11/85	5,872,560 N, 592,745 E Concentrator	PROJECT No GROUND ELEVAT LOGGED BYK	1623 10N <u>~ 1110 m</u> GB
Hitachi 200 hoe Moderate digging conditions I 0++ No samples taken. Walcr table at 2.1 m bater pended in pit to 2m digth after 18hrs. 4 Hitachi 200 hoe T 0++ Brown, dense, fine-grained sandy SILT with som gravel a.d clay. Slightly moist to moist. Similar to material encountered in TP95-1 Sandy SILT Glacial Till Bedrock encountered at 2.1 m. Angular fragment. Bedrock encountered at 2.1 m. Angular fragment. I to 20 cm dia. typically. Very broken at surt and becomes more competant with depth. Eaclehoe rips through Im et bedrock, and I s very fractored. 4	NOTES Groundwater level, difficulty in digg- ing, equipment used, etc.	DEPTH GRA (metres)	DESCRIPTI	ON AND CLASSIFICAT	ION
	Hitachi 200 hoe Moderate digging conditions No samples taken. Water table encountered. at 2.1 m buter fonded in pit to 2m depth after iBhrs.	$ \frac{1}{2} = 1$	t: Brown, dense, fine-g gravel a.d clay. Similar to material Sandy Silt Bedrock encountered 10 to 20 cm dia. typ and becomes more Backhoe rips ti- could continue. Is very fracture	zined sandy SILT w Slightly moist to m encountered in TPg Glacial Till at 2.1 m. Angular t ically. Very broken competant with a righ Im et bedroc indicating the cou s.	ith some oist. 5-1 Gragments at surface Lepth.

Г

ſ

ľ

1

Ľ

KNIGHT AND E	PIESOLD LTD.		TEST	PIT	LOG	TEST PIT NO. TP95-4 SHEET 1 OF 1
PROJECT LOCATION OF DATEJAN	Mt. Poller TEST PIT _1 11/95	1 Approx 5,8 51	822, 510N, 532. outh end of Con	765 E centrator	_ PROJECT No _ GROUND ELEVAT LOGGED BY	1623 FION <u>~ 1109 m</u> KGB .
NOTES Groundwater level, difficulty in digg- ing, equipment used, etc.	DEPTH (metres)	GRAPHIC LOG	DES	CRIPTION	AND CLASSIFICAT	TION
Hitachi 200 hoe Moderate diyying conditions Sample TP95-4 taken 2 to 36m Water table encountered at 3.6m. water panded to approx 2 to 2.5m depth after 18 his		$\begin{array}{c} \cdot \cdot$	Crange-brown grained san Clay (sim Cohesive in-si Chuncs of m medicate-on S Basal till Bedrock er c fragments en	(new surfl idy SILT ilar -ts - itus repared andy SILT andy SILT	are) to brown, der with some grave TPSS-1). slightly rin "in at depth is ripped from p ravel. Glarial Till at 3.6 m depth. d.	nse fine- I and y moist. where it. Fine to Argukur 362 of 500

Г

1

Γ

Г

Π

Γ

1

1

L

L

KNIGHT AND P CONSULTING I	PIESOLD LTD.		TEST PIT	LOG	TEST PIT NO. TP95-S SHEET 1 of 1
PROJECT	M+ Polley			PROJECT No.	1623
DATE Jan	TEST PIT 4	<u>-</u>	720 N , 592,600 E Crusher	GROUND ELEVAT	10N <u>~ 1120 m</u> KGB
NOTES Groundwater level, difficulty in digg- ing, equipment used, etc.	DEPTH (Metres)	GRAPHIC LOG	DESCRIPTION	AND CLASSIFICAT MATERIAL	ION
Hitachi 200 hoe.	0		Oxidized sitty 54100 with Coarser grained than to Lite of roots through Sitty Sand G	- some gravel, tr. !ls in TP35-1.3 a nout. Hacial Till]	ale clay.
No seeps encountered.		<u>λ</u> ι` Ε.Ο. Ρ.	Bedrack encountered as Oridized (iron stained.	t o.sm. Lapilli -) on exposed ou	tuff (volkuizs +crop.
No samples talken.	2 -		trationed ,		
			1):4c: Test fit is 10 n =f to 1.4m.	long, and varia	is in sight
	-				
	-				
	-				
	-				
۰.	-				
				INVESTIGATION KP 1-11 3	363 of 500

KNIGHT AND PIESOLD LTD. CONSULTING ENGINEERS	TEST PIT L	_OG TEST PIT NO. TP95-6 SHEET 1 of 1						
PROJECT M+ Polle	PROJECT M+ Polley PROJECT No 1623							
LOCATION OF TEST PIT	TOTOX 5,822, 20 N; 592, 240 E	GROUND ELEVATION ~1117 m.						
DATE Jan 12/35 '	Course are stackpile.	LOGGED BY KGB.						
NOTES DEPTH Groundwater level, difficulty in digg- ing, equipment used, etc.	GRAPHIC LOG DESCRIPTION OF	AND CLASSIFICATION MATERIAL						
Hitachi 200 hoe	DRGANICS							
Moderate digging conditions tample TP95-6 from 0 to 4m Digging recense rivore diffrentt. No sceps	++++ Brown, dense, fine-grained fine-grained gravel, ++++ Slightly moist. Economics very drose (1) ++++ be backnoe rife critic wes be gravely and sile. Frobbidy Sandy Silt +++ +++ +++ +++ +++ +++ +++ +	ed sandy SILT with some trare to some clay. wed) near battom of pit riss if the come cand a cosal will come cand a cosal will layer). Glacial Till						
encountered. 5	Dridized coarse-grain. E.D.P. rock fragments coroun fragments or visible	ed Land and argular tered. No large rock outerop encountered.						
6-								
		×						
		INVESTIGATION KP 1-11 364 of 500						

KNIGHT AND PIESOLD LTD. CONSULTING ENGINEERS	TEST PIT LO	G TEST PIT NO. TP35-7 SHEET 1 of 1
PROJECT Mt Polley	PR	OJECT No
LOCATION OF TEST PIT A	Concentrator GR. Concentrator GR.	COUND ELEVATION <u>~ 1112 ~</u>
NOTES DEPTH (Groundwater level, difficulty in digg- ing, equipment used, etc.	DESCRIPTION AND OF MA	CLASSIFICATION
Ultrain instrue.	w = Organiks	
Moderate digging conditions, 2	+ + Brown, dense, slightly me slitt with some gravel + + Hard, gray coloured -ill e Hard, gray coloured -ill e Hard, gray coloured -ill e (marding). Figs in every table from pit. Gravel is ro sized. Typically, J.e. the in creative - the in creative - -	hist, fine-grained sandy 1, clay. Similar to a surrounding test pite. 1 reprinted at multi- tering erice r, as a multi- tering erice r, as a multi- tering and fire to medium procedure fill c hill / bedrock and act
Seep enrountered at 4.4m. Semple TF35-7 (A.4 to 5.8m) Difficult digging conditions 6		<u>veial-111</u>
	INV	VESTIGATION KP 1-11 365 of 500

к	NIGHT AND F	PIESOLD LTD.		TEST F	PIT	LOG	TEST PIT NO. TP95-8 SHEET 1 of 1	
P	ROJECT	Mt. Polle	1			PROJECT No	1623	
L	OCATION OF	TEST PIT	ADDER 5,82	2,560 N ; 592,690 B	E.	GROUND ELEVAT	TION ~ 1110 m	
D	ATE Jan	12/55	Co	ncentrator		LOGGED BY	ЦВ.	
Gi di in u:	NOTES roundwater level, fficulty in digg- ig, equipment sed, etc.	DEPTH (metres)	GRAPHIC LOG	GRAPHIC LOG DESCRIPTION AND CLASSIFICATION OF MATERIAL				
F	lituchi 200 hoe.	0	غلا يلا لمذ	Orgentes, plack	+ brzw	n colour.		
(di	Noderate. gging conditions.	1 -	° + + + + + + + + + + + + + + + + + + +	Dense, brown, A Fire-grained g Ereavented. sim No hard basal Sance	ravel ravel ilar t till dy silt	ined sandy SILT and claus. Loose ill as majority of encountered. Glacial Till	with come . once Mill site pits.	
la Fi b	bter quickly ording at ottem of hole.	¥? 2 -	<u> </u>	Sedrock encounte Argular fragment through approx	cred at s up t 1.1m	1 3 m. Lapilli Ti o 30 cm dia. Bai with diffrculty	off (volunities), cluboe tears Secomes	
۲ ۲	10 samples raken.	3 -	E.0.P	extremely diffre	wlt to	excavate at 2.	Em depth.	
		-						
		-						
1		4						
						INVESTIGATION KP 1-11	366 of 500	

KNIGHT AND PIE CONSULTING EN	ESOLD LTD.		TEST F	PIT	LOG	TEST PIT NO. TP95-9 SHEET 1 of 1
PROJECT	Mt. Polley				PROJECT No.	1623
LOCATION OF T	TEST PIT	mar 5,82	3.280 N; 591, 300 E		GROUND ELEVAT	ION ~ 1052m
DATE Jan 12	/95	- Ea	st side Bootjack 1	Lake	LOGGED BY	43.
NOTES Groundwater level, difficulty in digg- ing, equipment used, etc.	DEPTH (metres)	GRAPHIC LOG	DESCF		AND CLASSIFICAT MATERIAL	ION
Hitachi 200 hoe.	0	L W W	Organics.			
Moderate digging conditions	1		Brown, dense, trace to some Poorly sorted, till at mill	woist, clay, well of site,	sandy gravelly 51 Medium Eized g graded. coarser-	LT with gravel. than
Sample TP95-9A =	2 - 0	+ + + + + + + + + + + + + + + + + + +	Sandy Gray slight to	Gracell	y Silt Glacial Till (firm)	
50mple 7795-98 - (2.5 +0 5.0m)	4 − 3]]	0+++++0 +++++0 +++++++++++++++++++++++	(sticky and c clay - and c coboles Tro	cohesive to sea) sanning silt wi no g nist, -inc -b scarce g	He serve Lease gravelie.
Seep @ 4m.	<u>▼</u> 4	D+0++++	Very plastre resis Very plastre. excavating 1 material !	rance u Baclehi natoria	be creates such 1. This is very	wit
	5	E.D.P.		iondy si	It Glacial Till	
	-					
	1					
	-				INVESTIGATION KP 1-11	367 of 500

KNIGHT AND P	PIESOLD LTD.		TEST	PIT	LOG	TEST PIT NO. TP95-10 SHEET 1 of 1
PROJECT	Mt. Pollay	1			PROJECT No.	1623
LOCATION OF DATE Jan	TEST PIT _A	1077 5,823 (EC	2,850 N: 551 480 ist side Bootjack L) E lake)	_ GROUND ELEVAT	10N <u>~1048m</u> KGB.
NOTES Groundwater level, difficulty in digg- ing, equipment used, etc.	DEPTH (metres)	GRAPHIC LOG	DESC	RIPTION	AND CLASSIFICAT F MATERIAL	ION
Hitachi 200 hoc.	0	<u><u>v</u> <u>v</u> <u>v</u></u>	Organics.			
Moderate diyong conditions.	1 2	+0 $+$ $+$ $+0$ $+$ $+$ $+$ $+$ $+$ $+$ $+$ $+$ $+$ $+$	Oxidized dense clay. Slightle encountered [Sande	sandy j motst at mi j <u>si</u> H c	SILT with some g . Some material Ill site. Loose one <u>Flacial Till</u>	gravel and as e excavated.
Sanple 7985-10	3-		Brown, dense traic robbles once excavi Denser materiz Crocker Hico	, moist, s and ated. 1 al at	silty gravelly clay. Non-plast inoderate to cours bottom of pit.	SAND with rz. Loose e gravel. S-9
More diffrault digging (due to course racks)	5-	ф+ + - - - - - - - - - - - - - - - - - -	Silly	Gravelly	Send Glacial Till]
No seeps ervountored.	6 -	D. + D. + D. + D. D E. O. P.	Rock fragments base of pit	en 1001	ted (up to 20 cm sible bedrock ?	dia.) at
	7-					(A)
~	-	*			INVESTIGATION KP 1-11	368 of 500

TEST PIT No. KNIGHT AND PIESOLD LTD. TEST PIT LOG TP 55-11 CONSULTING ENGINEERS SHEET / of / 1623 PROJECT _____Mt. Polley PROJECT No._ LOCATION OF TEST PIT APPROX 5,822,500 N; GROUND ELEVATION ~ 1040 m 591,800 E (East side of Bodjock Lake) LOGGED BY _____K4B. Jan 12/95 DATE NOTES DEPTH GRAPHIC LOG Groundwater level, (metres) DESCRIPTION AND CLASSIFICATION difficulty in digging, equipment OF MATERIAL used, etc. 0 Hitachi 200 hoe. 00: Brown, dense, slightly moist (new surface) to very Moist (to 2.8m depth), gravely SAND with some silt. Non-plastic. Poorly sorted, moderately Moderate digging conditions graded. chighty oxidized near surface. Gravelly Send Glacial Till Sample TP95-11 2 Seep encountered @ 2.8m. 3 saturated sandy GRAVEZ with some cobbles, D trace to some silt. Modurately dense. Argular cobbles and gravel. Very comic material. Diffrault 0.0° Noticable water in material when excavated. digging due to 4 coarse material 00:0 Sandy Gravel Glavial Till 5 .0 E. O. P. 6 INVESTIGATION KP 1-11 369 of 500

	KNIGHT AND F	PIESOLD LTD.		TEST	PIT	LOG	TEST PIT NO. TP95-12 SHEET 1 of 1
ī	PROJECT	Mt. Polley				_ PROJECT No	1623
	LOCATION OF	TEST PIT	porr 5 BZZ	2 250N; 5921	40 E	_ GROUND ELEVA	TION ~ 1050m
	DATE Jan	13/95	_ (Eas	st side of Bootsa	cle Lake)	LOGGED BY	KGB.
	NOTES Groundwater level, difficulty in digg- ing, equipment used, etc.	DEPTH (metres)	GRAPHIC LOG	DE	SCRIPTION	AND CLASSIFICA F MATERIAL	TION
F	titachi 200 hoe.	0	¥ ¥ ¥	Organics			
	litachi 200 hoe. Sample TP95-12 Modurate digging to 2m.	- 1 - - - - - - - - - - - - - - - - - -		Brown, moder Moderately e some fine - Poorly sorte Eedrock e -upically contact.	ately oxid lense, fir grained g d, modur Sandy Sil neountered 20 cm die	lized, moist to ve re-grained sandy ravel and clays ately graded. SI t Glacial Till at 13m appth. a 51305. Slightly	ry moist, sILT with trace organics. ightly plastic. Fractured, wet at
		-				INVESTIGATION KP 1-17	1 370 of 500

TEST PIT No. KNIGHT AND PIESOLD LTD. TEST PIT LOG TP95-13 CONSULTING ENGINEERS SHEET | of / M+ Polley 1623 PROJECT ____ PROJECT No.___ LOCATION OF TEST PIT ADATON 5 822 170 N; 592 470 E GROUND ELEVATION ~ 1076 m (East side of Boofjack Lake) Jan 13/95 LOGGED BY _____KAB. DATE _ DEPTH NOTES GRAPHIC Groundwater level, LOG (metres) DESCRIPTION AND CLASSIFICATION difficulty in digging, equipment OF MATERIAL used, etc. 0 Hitachi 200 hoe. +0." + 0 Brown, dense, moist, sith SAND with some gravel, trace to some clay. Gravel is typically medium sized. Well graded, poorly sorted. Slightly 0 plastic. Courser than material encountered Moderate + digging conditions at millsite. Good construction material. Ô silty said Glacial Till 1 2 Sample TPy5-13 -(0+0 3.5m) 3 -ill becomes denser and more difficult to execusive. Diffrent Grey-brown, hard, slightly moist sandy SILT digging conditions 00with some gravel and clay. Rounded gravel; 010variable sizes. Extremely cohesive (rips in E.O.P. chunks from pit). Looks like a basal till. No seeps. 5 Sandy Silt Basal Till 6 INVESTIGATION KP 1-11 371 of 500

1

KNIGHT AND F	PIESOLD LTD. ENGINEERS		TEST PIT L	LOG	TEST PIT NO. TP95-14 SHEET 1 of 1
PROJECT	Mt. Polley			PROJECT No.	1623
LOCATION OF	TEST PIT	1000x 582	25 000 N; 589 230 E	GROUND ELEVAT	ION ~ 575m
DATE Jen	13/95	_ (7.1	km along Main Azicos Koad)	LOGGED BY	(4/3.
NOTES Groundwater level, difficulty in digg- ing, equipment used, etc.	DEPTH (metres)	GRAPHIC LOG	DESCRIPTION	AND CLASSIFICAT MATERIAL	ION
Hitachi 200 hoe	0	ल गर म	Organics		
Moderate digging conditions Sample TPOS-14. No sceps. Diffrolt digging with digging with dippin.	2-	$\begin{array}{c} + & - & - & - & - & - & - & - & - & - &$	Dxidized - brown near sur coloured with depth), sandy SILT and CLAY trace cobbles, Grave Material cecomes drive Hard, elightly moist, some gravel and clay poorly sorted. Plastic Good construction M Sandy Silt	face (buoming gr dense, slightly i with some grav I and cobbles are and cobbles are cr sciew 2m: sondy SILT Moderate to u c when wet. aterFal. Glacial Till	rey-brown moist, vel and e rounded, with vell graded,
	5.				
	5				
	-				
	1				
			2		
	-				
<u>.</u>	-			INVESTIGATION KP 1-11 3	372 of 500

Г

ſ

[

Γ

KNIGHT AND F	PIESOLD LTD.		TEST F	эιт	LOG	TEST PIT NO. TP95-15 SHEET 1 OF 1
PROJECT	Mt. Polle	4			PROJECT No	1623
LOCATION OF	TEST PIT A	may 58	6 300 N; 587 500	E	_ GROUND ELEVA	TION ~ 530 m
DATE	13/95	(4.35	kin along Main Azles	is Road) LOGGED BY	KGB.
NOTES Groundwater level, difficulty in digg- ing , equipment used , etc .	DEPTH (metres)	GRAPHIC LOG	DESCR	RIPTION	AND CLASSIFICA	TION
Hitachi 200 hoc	0	++::++ >++::+0 >::+0+:::	No organics (o	n top .	of clear-cut hill).	ll -
Moderate	-	0.0	Brown, dense	, sligt	itly moist, sandy	gravelly
digging conditions.	1	-++	SILT with tri	are to	some clays train	e cobbles.
		·*0	Poorly sorted	, well	graded. Rounde	d cobbles
Sample TP95-15	← 2	·	and gravel.	Dine	e basal-till like	approvance
		++0	When excave-c	d ir	i hard chunks,	although
No seeps.		···· 0	majority of n	nateria	l is loose once	excavated.
	3	++ 0	Good construct	tion n	naternal.	
		++++	(Similar till a	as TPS	13-14, only coarse	er.)
	-	U.	5000	- Ca	welly silf clarical	7711
	1	+	Louine	y Gia	very stit graciect	(III)
	4 - 2	+				
	-	. +				
	-	FAR				
	-	L. U. F.				
	5 -					
	-					
	1					
	1 21					
	-					
۶.	-					
	1				INVESTIGATION KP 1-11	373 of 500
				-	the second s	

ſ

Γ

Γ

PROJECT Mt. Bolley PROJECT No. 1623 LOCATION OF TEST PIT Approx 5 820 580N; 594 370 E GROUND ELEVATION -98 DATE Jen 15/95 (TSF Prices Read) NOTES DEPTH GRAPHIC Considering a conjument DEPTH GRAPHIC used, etc. DEPTH GRAPHIC LOG DESCRIPTION AND CLASSIFICATION OF MATERIAL Used I + i + i In a conjument I + i + i used, etc. I - i + i + i In a conjument I - i + i + i Used attack I + i + i In a conjument I - i + i + i Used attack I + i + i I + i + i I - i + i + i I + i + i I + i + i - i + i + i I + i + i I + i + i - i + i I + i + i I + i + i - i + i I + i + i I + i + i - i + i I + i + i I + i + i - i + i I + i + i I + i + i - i + i I + i + i I + i + i - i	KNIGHT AND F	PIESOLD LTD.	TEST PIT LOG				
LOCATION OF TEST PIT Append 5200 580N; 534 3TDE GROUND ELEVATION -380 DATE Groundwate teven, difficult used, etc. Hitachi 200 kae. 1 + + Q 1 + + Q 2 + + + Q 3 - + + + + + + + + + + + + + + + + + +	PROJECT Mt. Polley PROJECT No. 1623						
NOTES DEPTH (metzs) GRAPHIC LOG Broundwater level, ing, equipment used, etc. DEPTH (metzs) GRAPHIC LOG Used, etc. DEPTH (metzs) DEPTH (metzs) DEPTH LOG Hitachi 200 kee. 0 0 0 Hitachi 200 kee. 0 0 0 Hitachi 200 kee. 0 0 0 1 ++ 0 0 ++ 0 ++'+ 0 Easy to moderate 1 1 ++'+ 2 ++ 0 1 ++ 0 1 ++ 0 1 ++ 1 ++ 2 ++ 0 ++ 2 ++ 0 +- 2 ++ 2 ++ 2 ++ 2 ++ 2 ++ 2 ++ 2 ++ 2 ++ 2 ++ 2 ++ </td <td>LOCATION OF DATE</td> <td>TEST PIT Approx 13/35 (</td> <td>5 B20 580N; 594 37DE GROUND ELEVATION ~ 980 T3F Access Road) LOGGED BYKAB.</td>	LOCATION OF DATE	TEST PIT Approx 13/35 (5 B20 580N; 594 37DE GROUND ELEVATION ~ 980 T3F Access Road) LOGGED BYKAB.				
Hitachi 200 kee. Hitachi 200 kee. Easy to moderate 1 + + Q Hitachi 200 kee. Easy to moderate 1 + + Q Hitachi 200 kee. 1 + + Q 1 + + Q 2 + + Q 1 + Q	NOTES Groundwater level, difficulty in digg- ing, equipment used, etc.	DEPTH GRA (Metres)	DESCRIPTION AND CLASSIFICATION OF MATERIAL				
Easy to moderate Less to moderate 1 + + Q Here to some gravel and clay. Occasional rounded cobble or boolder. Moderately grad poorly sorted. Plastic. No oxidation eviden 1 + + Q + + + + + + + + + + + + + + + + + + +	Hitachi 200 koe.	0 +	Drganics				
Lep at S.Dm. 4 0 + + + + + + + + + + + + + + + + + +	Easy to moderate digging conditions. Sample TP95-16 (0 to Sm)	2 + · · · · · · · · · · · · · · · · · ·	H. Brown, dense, slightly moist, sandy SILT with trace to some gravel and clay. Occasional t rounded cobble or boulder. Moderately graded poorly sorted. Plastic. No oxidation evident. In-situ material is very stiff! Sandy Silt Glacial Till tt				
7-	Sep at S.Dm. Very difficult digging conditions.	4 + + + + + + + + + + + + + + + + + + +	+ + + Grey, hard, slightly morst sandy SILT with some get - - - - - - - - - - - - -				

Γ

Γ

Ľ

Γ

Γ

ľ

ſ

KNIGHT AND I CONSULTING	PIESOLD LTD. ENGINEERS		TEST PIT	LOG	TEST PIT NO. TP95-16 SHEET 1 of 1
PROJECT LOCATION OF DATE	Mt. Polley TEST PIT A 13/95	pprox 5820 (TSF Ard	2 580N: 594 370 E ress Road)	_ PROJECT No GROUND ELEVAT	1623 FION <u>~ 980m</u> KGB .
NOTES Groundwater level, difficulty in digg- ing, equipment used, etc.	DEPTH (Metres)	GRAPHIC LOG	DESCRIPTION	AND CLASSIFICAT	TION
Hitachi 200 koe.	0	<u>x v</u>	Organics		
Easy to moderate digging canditizes. Sample TP95-16 (0 to Sm)	2-		Brown, dense, slight, trace to some grad rounded cobble or l poorly sorted. Plas In-situ reaterial is [Sandy Sil	ly moist, sandy sel and clay. C boolder. Moderat strc. No oxidatic. 'very stiff' T Glacial Till	SILT with Occasional ely graded n evident.
Sep at s.om. Very difficult digging conditions.	4 	C_{0}^{+} + + + + + + + + + + + + + + + + + +	Grey, hard, slightly n ad clay, trace cobble: ground in extremely moist. Note: Some local co sand exist an	wrst sandy SILT a s. Material is rip cohesive chunks asse oreas of g d water seqos t INVESTIGATION KP 1-11	ped from ped from Slightly ravel and through. 375 of 500

ſ

[]

Γ

Γ

+2

			IESI	PIT	LOG	TPS5-17 SHEET 1 of 1
PROJECT	Mt. Polley EST PIT A	(175) (175)	21 110 N; 594 23 F Arress Pard)	DE	GROUND ELEVATI	1623 ON ~ 880 m 4B.
NOTES Groundwater level, difficulty in digg- ing , equipment used , etc .	DEPTH (Metres)	GRAPHIC LOG	DESC	CRIPTION	AND CLASSIFICATI	ION
Hitachi 200 hoe. Moderate digging conditions. Sample TPOS-17 Water level rises to 3m depth after 15 hirs. Water table encountered at 4.3 m.		0 + 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Brown, moderal with some fit moderately gra gravel and Gra Material is	tely dens ne cobbl aded. N cobbles. wel and	e, moist, GRAVEZ es and silt. Ree on plastic. sub-a Sand Glacial Till d below 4.3 m.	and SAND rly sorted, ingular

Γ

F

Γ

[

KNIGHT AND PIESOLD LTD CONSULTING ENGINEERS	TEST PIT LOG	TEST PIT NO. TP95-18 SHEET 1 OF 1
PROJECT M+ P	PROJECT No.	1623
LOCATION OF TEST PIT_	Approx 5821 100 N: 593 285 E GROUND ELEV	ATION ~ 992~
DATE Jan 14/95	_ (Along tailings /reclaim pipeline route) LOGGED BY	KGB.
NOTES DEPTH Groundwater level, difficulty in digg- ing, equipment used, etc.	GRAPHIC LOG DESCRIPTION AND CLASSIFIC OF MATERIAL	ATION
Hitachi 200 hoe.	U U U Organics	
Modurate digging conditions. 1 Sample TPOS-18 2	brown, dense, slightly moist sandy SILT ++ i gravel and trace clay. Occasional ++ i Plastic. Poorly sorted, moderately gravel ++ i top 20cm is oxidized; the remain Sandy SILT Glacial Till ++ + +	with some rounded cobble. aded. Apprex. der is fresh.
Diffrolt digging conditions, No sceps incontrered. 4	+ + + + + Gray-brown, hard, slightly moist sandy gravel and clay, and there cobbles. + + - + + cohesive (rips out of pit in chunks t - 0. + sorted, well graded. Gravel and cob E. D. P. round to sub-rounded.	SILT with some Very dense and). Poorly bles are
	INVESTIGATION KP 1-	11 377 of 500

	KNIGHT AND F	PIESOLD LTD.		TEST PIT L	_OG	TEST PIT NO. TP95-19
	PROJECT	Mt. Pollay TEST PIT_	Approx :	5821 600 N; 592 980 E	PROJECT No	1623 ON ~1042m
	NOTES Groundwater level, difficulty in digg- ing, equipment used, etc.	DEPTH (Metros)	GRAPHIC LOG	DESCRIPTION OF	AND CLASSIFICATI	ION -
the second of the second second	Hitachi 200 hoe. *Seepare from 0.2 to 0.8m only.	V* 0 1	× + · · + · · · · · · · · · · · · · · ·	Organics. Brown, dense, moist grave cobbles and clay. Oxidi Very well graded, poord sub-rounded particles.	lly SAND and SILT ized near surface. Is sorted, sub-an Ursible seepage.	with trace Plastre, goks to
	Moderate digging conditions	2 -	+++ ++ ++ ++ ++ ++ ++ ++ ++ ++ ++ ++ ++	(Note: This may be a la from road cons Brown, dense, slightly SAND with some grav Plaster Poorly contail	moist, silty fine	grained (with cepth).
	Sample TP95-19 (0.8 to 6.0m)	4	+ + 0 + + + + 0 + + + + 0 + + + + 0 + + + + 0 + + + + 0 + + + + + 0 + + + + + 0 + + + + + + 0 + + + + + 0 + + + + + + 0 + + + + + + 0 +	Ecromes moister with scridy SILT with som cobbles. All gravel is a Silty send/sand	depth. Material depth. Material are gravel and cla evb-round to sub-ar dy Silt Glacial Til	berones 2y, trace gular.
	Difficult digging conditions.	5		Becomes grey and have	I. Rounded grave	I and cobbles.
	۵.	7 -	C. U, T *	Note: Argular rock fragments Fine-grained, matric with (Possible bedrock contr	encountered at both HNVESTHICTATION REMARK) 3'	tan of hole. fillefitsoo

KNIGHT AND F	PIESOLD LTD.		TEST PIT LOG TEST PIT No. TP95-20 SHEET 1 of 1
PROJECT	Mt. Polley		PROJECT No
LOCATION OF	TEST PIT A	TYPY 5 B2	20 800 N; 565 670 E GROUND ELEVATION ~ 922 ~
DATE Jan	4/95	_ (South	h-cust corner of Polley Lake) LOGGED BY KGB.
NOTES Groundwater level, difficulty in digg- ing, equipment used, etc.	DEPTH (metres)	GRAPHIC LOG	DESCRIPTION AND CLASSIFICATION OF MATERIAL
Hitachi 200 hoe. * Perclued water- table above dense till.		▲ 本 本 本 本 本 本 本 本 本 本 本 本 本	Black / brown ORGANICS. Completely seturated. Side walls continuously slough into pit. Very smelly! Very soft. Water continuously seeps into pit.
Very easy digginy (0-2.5m)	2	+:	Gen was shift > hard shirt the worst sind shit with
More diffizult disging conditions.	3		some gravel and clay. Plastic. Poorly sorted inclusively graded. Very cohesive. Looks like basal +111 encountered in local pits, only more in-situ moisture.
Sample 1195-20	4 - 4 -	+++ +++ FOD	Sandy Silt Basal Till
	5	Е.О.Р.	Aproximate depth. Diffriult to riensure due to pit constantly collapsing and filling with water.
	-		INVESTIGATION KP 1-11 379 of 500

KNIGHT AND P CONSULTING	PIESOLD LTD.		TEST PIT	LOG	TEST PIT NO. TP95-21 SHEET 1 OF 1		
PROJECT	Mt Polley			PROJECT No.	1623		
LOCATION OF	TEST PIT _	forex 5 C	20 340N; 595 340E	GROUND ELEVA	TION <u>~ 522 m</u> KB		
NOTES	DEPTH	GRAPHIC					
Groundwater level, difficulty in digg- ing , equipment used , etc .	(metres) ▽	LOG	DESCRIPTION AND CLASSIFICATION OF MATERIAL				
Hitachi 200 hoe.	× 0_	ж ж ж					
Visible seeps from peat from 0 to 1m depth. Pit is saturated.	1 -	+++ +++ +++	Black/brown, sctura Very strong odour.	ted, very soft ore Minimal strength	GANICS.		
Very solf digging throughout.	2		- 2 Layer of gray, saturated, very soft, silty fine grained SAND. Varues of gray and brown colours. Easily indented with finger.				
No samples talen.	3 -	51 51 21 51 51 21 51 51 21					
	4 - - -	+ 					
	5 -	6 0 + + + + + + + + + + + + + + + + + +	ORGANICS. Varued Gellow grass and :	silt layers. Tan small (up to lon	layers contain ; ave 0.5cm		
	6 -	+ 8 + + + + + + + + + + + + + + + + + +	poorly graded. Ver	y plastic and cohes T and ORGANKS	ive. strongodour.		
	7 - - -	E.D.P.					
	-		Note: Depths are approx collapsing and	incutives martialities the tai	Bit of 500stantly		

KNIGHT AND A	PIESOLD LTD.		TEST	PIT	LC	OG	TEST PIT NO. TP95-22 SHEET 1 of 1
PROJECT	Mt Polley				_ P	ROJECT No.	1623
LOCATION OF	TEST PIT	Approx 5B2	20 890 N: 565 54	DE	_ G	ROUND ELEVATI	ON ~ 522m
DATE Jan	14/95	_ (Sour	th end of folley L	ake)	L	OGGED BY KG	3
NOTES Groundwater level, difficulty in digg- ing, equipment used, etc.	DEPTH (metres)	GRAPHIC LOG	DESCRIPTION AND CLASSIFICATION OF MATERIAL				ION
Hitlachi 200 koe		K K K K					
from peat large. Pit is saturated	2	가 가 가 가 가 가	Black/brown, saturated, very soft ORGANKS. Side walls continuously collapse into pit. Very strong odour. Minimal strength.				
bigging throughout test pit.		二下下					
No samples taken.		14 14 14 14 14					
	4 -	₩ ₩ ₩ ₩ ₩ ₩ ₩	Teo lacou s	sturated	()/*	TI FOR SUF CON	1 OPEANING
	5	⊕+ 5+ + 5+ 3+ 2++ + + + +	Varued layers, Some material as encountered in TP95-21.				countered
	6 -	E.O.P.					
					,		.,
*.	-		Noter Depths are continuously	apprexima 1 collaps	ing of	INVESTIGATIONIKP (11)	with water. 381 of 500

KNIGHT AND P CONSULTING E	PIESOLD LTD.		TEST PIT	LOG	TEST PIT NO. TP95-23 SHEET 1 of 1	
PROJECT	Mt Polley			_ PROJECT No	1623	
LOCATION OF DATE Jan	TEST PIT A	prox 582 (South	West corner of Polley Lake)	_ GROUND ELEVAT	10N <u>~ 922 m</u> KGB,	
NOTES Groundwater level, difficulty in digg- ing, equipment used, etc.	DEPTH (Metres)	GRAPHIC LOG	DESCRIPTION AND CLASSIFICATION OF MATERIAL			
Hitachi 200 hoe.	3 0 -	¥ ¥ ⊻ ¥	Black/brown, saturated,	very soff ORGANICS.		
Soff digging conditions. Pit is saturated.	1	+ 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Gray, saturated, very sorted, poorly grade strong odour. Very	y soft CLAY and SI id. Varived. Very f cohesive.	LT. Well Dlastrc.	
No samples taken.	3-		Layers of darkgrey/ fine-grained SAND a course grained and [LACUSTRIN	black, saturated, nd SILT. Some sa of quartz confros DE LAVERS	uery soff nd is itian. Cohesix.	
		E. D. P.	Note: Depths are appres continuously colle water,	points only due to p points and the pit	lit walls filling with	
۰.	-			INVESTIGATION KP 1-11	382 of 500	

KNIGHT AND P CONSULTING E	IESOLD LTD.		TEST	PIT	LOG	TEST PIT NO TP95-24 SHEET 1 of 1
PROJECT	Mt. Polley				_ PROJECT No	1623
LOCATION OF	TEST PIT A	porox 5	820 800N; 595	360 E	_ GROUND ELEVAT	TION _~ 922 ~
DATE Jan 1	4/95	_ (500	th-west corner of	Polley Lak	e) LOGGED BY	KGB.
NOTES Groundwater level, difficulty in digg- ing, equipment used, etc.	DEPTH (Metres)	GRAPHIC LOG	DES	CRIPTION	AND CLASSIFICAT	TION
litachi 200 hoe.	3 0	¥ <u>w</u> ¥	Slach orown,	saturated,	very soft ORGANICS	
Very soff digging conditions. Dil walls are hore competent than in earlier test pits (TPOS-20 to 23)	1-	$\begin{array}{c} + \cdot \cdot \cdot \\ + \cdot \\$	Lacustrine se Dark gray, v some organ Dark gray, SAND. Both are f Strong ode	very soft, res. Var very soft plastrz di our. LACUSTRIN	of the following: saturated CLAY an ued. Well sorted t, saturated sulty we to high sult/cl	d SILT with poorly grad fine-graine ky content.
taken.	4	$\begin{array}{c} \begin{array}{c} + & + & + & + & + & + & + & + & + \\ + & + &$	Tan/grey, s Varued laye shells and graded, U	a-vra-ed rs conto yellow lory plass	aining white fresh grass. Well sort biz and cohesive.	nd Oegawics -water- ted, poorly Strong odo
	7-					
]				1	
÷.	-				INVESTIGATION KP 1-11	1 383 of 500

Γ

ſ

ſ

Γ

Γ

KNIGHT AND PIESOLD LTD.		TEST PIT	LOG	TEST PIT NO. TP95-25		
CONSULTING ENGINEERS				SHEET / of /		
PROJECT Mt. Polley		PROJECT No. 1623				
LOCATION OF TEST PIT	Approx 5	BZO 930 N; 595 250 E	GROUND ELEVAT	ION ~ 922		
DATE Jan 14 /95	_ (a	access road to Polley Lake)	LOGGED BY	43.		
NOTES DEPTH Groundwater level, difficulty in digg- ing, equipment used, etc.	Ievel, (Metres) GRAPHIC LOG DESCRIPTION AND CLASSIFICATION OF MATERIAL					
Hitachi 200 hoe 30-	M M M	Black/orown; saturated,	very soft CREANICS.			
Very soft 1 digging conditions.	+ (1)	Dark grey, saturated, CLAY and SILT with depth to sandy CLAY	very soft (and stick some sand, coar 1 and SILT with -	kg) sentry with trace		
2-	· + + +	Gravel. Very plastic, well sorted, poorly	Strong odour. 1 graded. Layes	Nodurate to s of sound		
Jample 1703-23	+	- and gravel at local intervals.				
(04 to 5m) 3	···+ (-···++	LACUSTRINE	LAYERS			
4	+1++++++++++++++++++++++++++++++++++++	-				
Difficult digging carditions at sto s.8m 6	$\frac{1}{1} + \frac{1}{1} + \frac{1}{1} + \frac{1}{1} + \frac{1}{1} + \frac{1}{1} = \frac{1}{1} + \frac{1}{1} = \frac{1}{1} = \frac{1}{1} = \frac{1}{1} + \frac{1}{1} = \frac{1}$	Brown, hard slight some gravel and clay dense chunks are rip well graded. Plastic to basal till encount in colour. Sandy Silt	ly moist, sandy s y, trace cobbles ped from pit. Pool (when wet). Look tered locally, chile Basal Till	ILT with Very orly sorted, is simileo- y brown		
			INVESTIGATION KP 1-11	384 of 500		

KNIGHT AND PIESOLD LTD. CONSULTING ENGINEERS		TEST PIT	LOG	TEST PIT NO. TP95-26 SHEET 1 of 1
PROJECT Mt. Polley			PROJECT No	1623
LOCATION OF TEST PIT	Approx 581	9 150 N; 594 645 E	GROUND ELEVAT	ION - 938m
DATE 15/95	- (Tai	lings Basin)	LOGGED BY	KGB.
NOTES DEPTH Groundwater level, difficulty in digg- ing, equipment used, etc.	GRAPHIC LOG	DESCRIPTION	AND CLASSIFICAT	ION
Hitachi 200 hoe.	× × ×	ORGANICS		
Moderate diviging conditions 2	+ $+$ $+$ $+$ $+$ $+$ $+$ $+$ $+$ $+$	Brown, dense, slightly n some fine gravel and Very plastic. Poorly s With depth, material increases in gravel a like a typical basal Very cohesive, hard ripped out of pit.	noist = moist, sand d clay, trace co corted, well grade becomes grey colou content. Looks very till. chunks of material This material is	y SILT with obbles. i.d. red and Nuch Nuch il is more
No seeps encountered, 3	++ -+++++++++++++++++++++++++++++++++++	moist then usually	Encountered.	
Sar-ple TP35.26				
5	+ + + = +	Material at approx 5.5	on becomes very	plastic due
6 -	+ 00 + 00 E.O.P.	to higher moisture a when removided). In well graded nature,	intert (behaves) aftertal remains 11. only more moist	ila plasticera La scora
7-				
			INVESTIGATION KP 1-11	385 of 500

KNIGHT AND F	PIESOLD LTD.		TEST PIT I	LOG	TEST PIT NO. TP35-27
0.15.07	ML Dollar	1		ODO ISOT N	IL22
	TECT OF A	5 01	A WAN. ERS SEAF	CROUND ELEVA	TION WERD
DATE TO	OCATION OF TEST PIT HIM SOID HON, COS SOLL GROUND ELEVATION -				
NOTES	0,00				- <u>k</u> - ·
roundwater level, difficulty in digg- ing , equipment sed , etc .	(metres)	LOG	DESCRIPTION	AND CLASSIFICA	TION
- Juli 200 hos	0	2 4 4	ORGANICS		
* richt 200 the * richt seeps · 2.7m and Am only. The meinder of the pit is dry. i inderate to i 'trout digging Londitions.	2 * * * * * * * * *	A 1 4 4 1 0 0 1 4 1 0 0 0 4 4 1 0 0 0 1 4 1 4	Brown (gray at depth), SILT with some gra Poorly sorted, well g in ocnse chunks from are sub-rounded. Co depth to "some co material is oxidized Sandy Silt	hard, slightly n wel and clay, + raded. Very co m fit). Gravel beles content in beles." Top D ed. Plastre who t Basal Till	noist sandy race cobbles. husive (rips and cobbles creases with ism of en wetted.
	×			INVESTIGATION K	(P 1-11 386 of 500

		1		And the second s	TEST PIT No.
CONSULTING	ENGINEERS		TEST PIT I	_OG	TP95-28
	Mt Polle	1	No. 1	DROUSOT No	1423
OCATION OF	TEST DIT	Amor 58	19 3KD N . 595 285 F	GROUND FLEVAT	FION~ 923.4m
DATE Jar	15/95	(Ta	ailings Basin)	LOGGED BY	KGB.
NOTES	DEPTH	GRAPHIC	0		
iroundwater level, difficulty in digg- ing , equipment sed , etc .	(metros)	DESCRIPTION	AND CLASSIFICA MATERIAL	FION	
Hitachi 200 hoe	30	ж Ж	Brown, soll, saturated	ORGANKS.	
Ponded water it surface. Fasy digging protitions	1		Grey-green, soft, very and silty SAND. We Clay and silt are very Sand layer is visibly c	most layers of 11 sorted, poorly g plastic due to hij wet on pit walls	CLAY and SILT graded layers. gh nuoistore.
	2.	-+-=+			
inciderate to hidficult dicging inditions (1.5 to 6.2m),	3 -	\mathcal{J}_{0}^{*} + 1 , \mathcal{D}_{0}^{*} + 1 , \mathcal{D}_{0	Brown-gray, hard, slig some gravel and Very cohesive, dense cu when wet. Poorly so Sandy silt	htly moist, san clay, trace a unks of materi orted, well grade Glacial Till	dy 51LT with obbles. al. Plastrc d.
Sample 7795-28 (5.40 b.2m)	- 5 6	1 + + + - + 0 0 - + + 0 0 + + + + + + + +	Material iceremes moist matrix materials berg removided (like plastic water table nearby.	at Sm dipth. C ne etricy and ene). Bedrock a	lay and silt are cash, ind possible
	7-				
	× :			INVESTIGATION K	(P 1-11 387 of 500

KNIGHT AND F	PIESOLD LTD		TEST PIT L	LOG TEST PIT NO. TP95-29 SHEET 1 of 1
DATE Jan 15/85			318 745 N: 596 270E Hal East Ridge Borrow Area)	PROJECT No. 1623 GROUND ELEVATION ~ 336m LOGGED BY
NOTES roundwater level, difficulty in digg- ing, equipment sed, etc.	DEPTH (metres)	GRAPHIC	DESCRIPTION	AND CLASSIFICATION MATERIAL
Hitachi 200 hoe. Ury soil to I'm dupth? Moderate Jging conditions lo sceps. Sumple TP95-29		$\begin{array}{c} 1 \\ 1 \\ 1 \\ 1 \\ 1 \\ 1 \\ 1 \\ 1 \\ 1 \\ 1 $	Brown, dense (firm to the Sandy SILT with som cobbles. Material is encruntered. Poorly so when wet, otherwise ratural moisture con- with depth, and exca Good construction mate [Sandy Silt G	hard), dry to slightly moist, me gravel, trace clay and drier than usually orted, well graded. Plastric at plastric limit with tent. Becomes very hard wates in dense, colusive chunks. terial. <u>Placial Till</u>
11				INVESTIGATION KP 1-11 388 of 500

KNIGHT AND F	PIESOLD LTD		TEST PIT I	_OG	TEST PIT NO. TP95-30
DATE	<u>MH. Polley</u> TEST PIT_ 5/95	Apprex 58 (Potentin	al East Ridge Borrow Area)	PROJECT No GROUND ELEVA LOGGED BY	1623 TION <u>~ 538m</u> <i>K41</i> 3.
NOTES)roundwater level, difficulty in digg- ing, equipment sed, etc.	DEPTH (metres)	GRAPHIC LOG	DESCRIPTION	AND CLASSIFICA MATERIAL	TION
Hitachi 200 hoe. No seeps neountered. Modurate igging conditions Sample TP95-30	0 1 2 3 4 5	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	Brown, dense (firm to Savdy SILT with som cobbles. Peorly sort-co cohesive, grey coloured and k is ripped out of pit cobbles are sob-round Good construction made <u>Sardy SIH Glar</u>	hard), slightly e gravel, train i well graded hard with depth in chunks. Gra ed to roord. etal (cimilar to hal TI!!	moist, c clay and , Becomes more as Material well and o TP85-28).
	*.			INVESTIGATION K	P 1-11 389 of 500

÷

-		T			TEST PIT No.
CONSULTING	PIESOLD LTD. ENGINEERS		TEST PIT I	LOG	TP95-31 SHEET 1 of 1
PROJECT	Mt. Bllen			PROJECT No.	1623
.OCATION OF	TEST PIT	mar 5618	955N; 596 470 E	GROUND ELEVAT	10N ~ 239m.
DATE Jan	15/95	_ Clotert	ial East Ridge Borrow Area)	LOGGED BY	4B.
NOTES Groundwater level, difficulty in digg- 'ng, equipment used, etc.	DEPTH (metros)	H GRAPHIC LOG DESCRIPTION AND CLASSIFICATION OF MATERIAL			
Hitachi 200 hoe	0	M M M	ORGANICS.		
No sceps incountored. lodurate ungging ronditions anaple 7795-31		$\begin{array}{c} +++\\ ++\\ ++\\ ++\\ ++\\ ++\\ ++\\ ++\\ ++\\ +$	Brown, dense (firm to SILT with some gra coldbles. Decasional sorted, well graded countered in TPSE moisture content as Good construction Sandy SILT G	rard), slightly n wel, trave day boulder at depth Same materia 5-25 and 30 (se 795-30). material.	wist, sondy and i. Poorly il as some natural
	-			INVESTIGATION KP	1-11 390 of 500

-					
KNIGHT AND F	PIESOLD LTD.		TEST PIT	LOG	TEST PIT NO TPG5-32 SHEET 1 OF 1
PROJECT OCATION OF DATE	MH. Polle TEST PIT 16/35	y Approx 5 81 _ (East-	9 140 N; 585 780E Tailings Basın)	PROJECT No GROUND ELEV LOGGED BY	1623 VATION <u>~ 932m</u> KGB.
NOTES roundwater level, difficulty in digg- g, equipment sed, etc.	DEPTH (metres)	GRAPHIC LOG	DESCRIPTIO	ON AND CLASSIFIC	ATION
l'tachi 200 hoe durate to difficult digging. NO seeps phicunfored	2-	0+:0+:+:+:+::+:+:+:0++:0++++++++++++++	ORGANICS, black/brown Brown, dense (very with some gravel Becomes grey in ro to hard with de No oxidized zone cobbles are sub-ro based like with [Sardy Sil	stiff), slightly mois and clay, trace blour and increases oth. Poorly sorted near surface. G und to round. B depth. Very low p t Glacial Till	st, sandy slut cobbles. in density , well graded. fravel and comes very ermeability.

4

5

6

٠.

00

E.O.P.

INVESTIGATION KP 1-11 391 of 500

KNIGHT AND PIESOLD LTD. CONSULTING ENGINEERS			TEST PIT I	_OG	TEST PIT NO. TP95-33 SHEET (of 1	
PROJECT	Mt. Polley			PROJECT No.	1673	
DATE Jan	TEST PIT 1 16/95	<u>4000× 58</u> (5W	18750 N: 594 820 E 1 Tailings Bash)	GROUND ELEVAT	ION <u>~ 932m</u> KGB.	
NOTES .oundwater level, difficulty in digg- J, equipment ed, etc.	DEPTH (motres)	GRAPHIC LOG	DESCRIPTION	AND CLASSIFICAT	ION	
achi 200 hoe	10	¥_¥ ¥	Black, soft, saturated ORGANK	s. Swemp. Willows +	swamp spruce.	
2 ded water 2 sorface perched water ble).	1-	$\begin{array}{c} \vdots \vdots$	Gray-black, oxidized, stiff some organics (grass and sorted, poorly graded. SILT and	t, moist SILT and I roots). Very plas Low permeability CLAY	clay with tic. well	
5 toth, easy tigging (0to 0.5m) scrate tigging (0.9to 41m)	2 -	++++0 +++++++0 +++++++++++++++++++++++	Brown, durse (U. stiff), slightly most sandy SILT with some gravel and clay, trave cobbles. Poorly sorted, well graded. Oxidized at contract with overlying SIH + clay. Slightly plastic. Low permeability			
	4 -	+++++++++++++++++++++++++++++++++++++++	Sandy SILT a	Glacial Till		
Smooth, easy inging (4.1 fo 7.7m)	5 -		Grey, stiff to very stiff, SAND. Very then lam can be carefully peele Well sorted, poorly gr	Moist, SILT and inated layers (« d apart by hand raded. No varies	fine-grained (Imm) which d. Plastic. evident.	
5 .ple TP95-33 (4:1407.7m)	6	++++++++++++++++++++++++++++++++++++++	Low permenbility. Com	esive. d SAND		
	7	+++++++++++++++++++++++++++++++++++++++			0 1 11 200 of 500	
	8	E.O.P.		INVESTIGATION KE	1-11 392 OF 500	

KNIGHT AND PIESOLD LTD.

TEST PIT No. LOG TEST PIT TP95-34 CONSULTING ENGINEERS SHEET / of I 1623 Mt. Polley PROJECT No.__ PROJECT ____ OCATION OF TEST PIT Approx 5818 730 N; 595 250 E GROUND ELEVATION ~ 824 m. LOGGED BY ______ KGB Jan 16/95 (South Basin) DATE ____ DEPTH GRAPHIC NOTES LOG oroundwater level, (metres) DESCRIPTION AND CLASSIFICATION difficulty in diggg, equipment OF MATERIAL ed, etc. D 世世世 BLACK, SOLT ORGANKS. Achi 200 hoe Brown, dense (hard), slightly moist, sandy SILT with " ocerate diciging iditions. some gravel and clay, trave cobbles. Top 30cm 1 is oxidized. Rounded gravel and cobbles. Material is just below plastic limit. Poorly sorted, well Friple TPSS-34A graded. Similar material as encourtered in TPSS-33. 2 2 to 4.1m) Low permeability. Sandy Silt Glacial Till. · Only local, 3) Flow seeps sible at intact. Dark grey / black, stift > very stiff, slightly moist, rooth easil SILT and fine-grained SAND. Well sorted, pourly 3hg (4,155,4m graded. Does not have layering like TP55-33 did. 5 At plastic limit. Cohesive. Low permeability. 2 p'e TPOS-348-Drier than TP95-33 sittend sand layers. 4.1 to 6.4m) SILT and SAND 6 E.D.P. 7 INVESTIGATION KP 1-11 393 of 500

KNIGHT AND PIESOLD LTD. CONSULTING ENGINEERS			TEST PIT	LOG	TEST PIT NO. TP95-35 SHEET 1 of 1
PROJECT	Mt. Polley			PROJECT No.	1623
OCATION OF	TEST PIT	ADDOX 50	318 690 N; 595 535 E.	GROUND ELEVAT	10N ~ 517m
DATE Jan	16/95	" (:	South Basin).	LOGGED BY	KGB
NOTES	DEPTH	GRAPHIC	allest		
Groundwater level, difficulty in digg- ig, equipment sed, etc.	(metres)	LOG	DESCRIPTION	AND CLASSIFICAT MATERIAL	ION
itachi 200 hoe	0	+01.1.0	ORGANICS, black / brange.		
: derate digging lunditrans. (0,2 to 4.0m).	1 - - - - - - -	1 + 1 + 1 + 1 + 1 + 1 + 1 + 1 + 1 + 1 +	Brown, dense (u. stiff + SILT with some grave Poorly sorted, well grave Rounded gravel + rebb Chuncis of matorial e	p hard), slightly m I and clay, trail aded. slightly pl ples. Dense, very mountored with	oist sandy e cobbles. lastrc (at P.1 cohesive depth when
* Seep at contact.	3 -	+++++++++++++++++++++++++++++++++++++++	ripped out of pit. depth. Very low perm [Sandy silt	Becomes grey-ri eability. Glacial Till	your with
outh, casy	√* 4 - 	+ + + + 0 <u>+</u> + + + + + + + + + +	Darte grey, slightly r SAND Sand 3 USIN	noist, stiff, SILTO	nd Ane-grain
-ple 7895-35 b to 6.6m)	5-	++ + ++ + + + + + + + + + + + + +	silt. Well sorted, pa limit. Cohesive chunks cohesive overall. Low	thy graded. Below when excavated permeability. 3	w plastic d, and forme materia
	6 -	+++++++++++++++++++++++++++++++++++++++	Silt a	d Sand.	
	7-	E. D.P.			
				INVESTIGATION KF	9 1-11 394 of 500

KNIGHT AND P CONSULTING E	IESOLD LTD		TEST PIT	LOG	TEST PIT NO. TP95-36 SHEET 1 of 1
PROJECT Mt. Polley			0 50 11 535 075 5	PROJECT No	1623
DATE Jan 1	TEST PIT _ 16/95	<u>Hport 50</u>	South Basin)	LOGGED BY	KGB.
NOTES DEPTH GRAPHIC Loundwater level, difficulty in digg- g, equipment ied, etc.			DESCRIPTION	AND CLASSIFICA F MATERIAL	ATION
"tachi 200 hae.	D	₩ +++ +++	ORGANICS.		
i odurate dicging, des slough into pit.	1	0 + + + 0	with trave to some gravel or cobbles moderately graded.	gravel and clau in this material. Moister than m	silty SAND y. No coarse Poorly sorted, wast tills
Sample 795-36.4 .2 to 3.2m)	a 2	+ + + + 0 -	Rounded gravel. Ce also. Silly Sa	nd Glacial Till	then most -: 11s,
l :durate flow from sand l yer.		+++ +++ ++++ +++++++++++++++++++++++++	Black, medium to coars (to none) of silt.) graded. Saturated.	e-granued SAND Not cohesive. We Approx 60 cm the	with trace Ill sorted, poorly ick.
S ooth digging 3.2-06.3m)		++++	Creamy brown, Very sti	$\frac{ND}{H} \Rightarrow hard, slightly$	moist SILT
Scomple TP95-36 B- (B to 6.3 m)	⊴	+++	and CLAY. No coar sorted, poorly grade	ze meterial. La d. Very cohesive Tand ELAY]	yered. Well . Low perneability
	6	- +-+ - + - + -+ E.D.P.	Brown, soft, moist . grained SAND. Wel slightly cohesive (pr	to very motst sill I sorted, poorly is shally due to his	st and fine- graded. gh moisture
	7	-	Content). Sides of Diffrent to tell when Instability of test	pit continuously re this large ex pit wells.	cave -in, fists due to
		-	L SILT		N KP 1-11 395 of 500

KNIGHT AND PIESOLD LTD. CONSULTING ENGINEERS PROJECT <u>MH. Pollay</u> DCATION OF TEST PIT <u>Aprox 58</u> DATE Jan 16/05 (Su			TEST PIT	LOG	TEST PIT NO. TP95-37 SHEET 1 of 1
			18 345 N; 595 260 E Taillings Bash),	_ PROJECT No _ GROUND ELEVA LOGGED BY	1623 TION <u>- 938</u> КЦВ,
NOTES oundwater level, difficulty in digg- i, equipment ed, etc.	DEPTH (Metres)	GRAPHIC LOG	DESCRIPTION	I AND CLASSIFICA F MATERIAL	TION
Moderate digging to 1.sm Sample TPgs-37 of below trill/ bedrock contact. Diffrzolt digging Dele.		$\frac{1}{2} + \frac{1}{2} + \frac{1}$	ORGANICS. Brown, very stiff, moiss and clay. Poorly so Contains more moistur close proximily to su Sundy 5 Bedrock encountered as purple volconic conglo are typically 30 cm s	t sondy SILT with ted, well graduce than usual (rfare and bectood ilt Glacial Till t lism depth. Very merate (friable) ize. and very ang	- some gravel J. Plastic. probably due to k). fractured, Fragments vlar.

۶.

INVESTIGATION KP 1-11 396 of 500

i
KNIGHT AND F	PIESOLD LTD.		TEST PIT	LOG	TEST PIT No. TP35-38							
FROJECT	MH, Polley		and the second secon	PROJECT No	1623							
DCATION OF	TEST PIT_ 16/85	Approx 58	A8 460 N; 585 485E	GROUND ELEVA	TION <u>~915m</u> KGB,							
NOTES oundwater level, difficulty in digg- g, equipment ed, etc.	DEPTH (metres)	GRAPHIC LOG	DESCRIPTION AND CLASSIFICATION OF MATERIAL									
Flachi 200 hoe.	0	N N U	ORGANICS.									
1">durate dicging (U to 4.7m)	- - 1 - - -	+++++++++++++++++++++++++++++++++++++++	Brown to gray, hard, slig some gravel and c Rown ded gravel. Ven out of pit. Plastic."	htly moist sand by. Poorly sorte duse, cohesive Grey colour on	SILT with d, well graded. chunks ripped face of some							
encountered.	2 -	+++++++++++++++++++++++++++++++++++++++	near surface and b depth. Low permabili Sandy sil	ty: + Glacial Till	bbles " with							
	4 -	++++++++++++++++++++++++++++++++++++++	Durk gray, stiff to vere clay, trace to some plastic. Lodes like al material is layered (Probable transition w with underlying laye	stiff, morst SILi sand, trace gr bove till, althout land peels aport here till has been rs)	T with some avel. Very ugh some on layers). in mixed							
Modurate, get in oth digging (4.5 to 6.7m) zimple 7795-38	5 	++++++++++++++++++++++++++++++++++++	Creany brown to grey, SILT WITH some clay Well sorted, poorly g SIIt. Till-like feet fe Similar to SIIt/clay Low permeability. SILT an	ley stift > hud, . Very cohesive raded. Obvious x density of this encountered in - d CLAY	slightly moist and dense. layers in gray 3 material. TPSS-36.							
				INVESTIGATION	KP 1-11 397 of 500							

NIGHT AND F	PIESOLD LTD.		TEST PIT I	LOG	TEST PIT NO. TP95-39
	mt Polle			PROJECT No	1623
OCATION OF	TEST PIT	ADDDY 51	RIS 405 N: 595 405 E	GROUND FLEVAT	10N ~918m
DATE JOA	16/95	(5	with tailing basin)	LOGGED BY	KGB.
NOTES	DEDTH	CRADUIC			
Groundwater level, difficulty in digg- g, equipment ied, etc.	(metres)	LOG	DESCRIPTION	AND CLASSIFICAT MATERIAL	ION
itachi 200 hoe.	0	¥	Black, schurated, soft ORG+	ANICS,	
"oderate gging (oto 2.5m)	1-	+ + + + + + + + + + + + + + + + + + +	Brown to grey, hard, slig SILT with some grave well graded. More n cohesive chanks of 4 Typical till.	ghtly moist -> moi el and clay. Pou moist on surface rill (from surface ilt Glacial Till	ist, sandy orly sorted, of duse, icc inflew?).
act. Fisy digging Sto 7.5m Sides of pit Hinuously Swoogh.	3		Brown, soft, saturated No colusion (pit walls well corted, peorly dense with depth. Sond	d, fine-grained continuously can graded. Eccom and silt	SAND. and SILT. Ne-in). Very es more
	5				
Ú.	6 -				
	-				
2 de TP35-39 (cor bottom of 01t).	 ↓ ↓	E.D.P.	Note: Bottom of pit is sloughing of sic measurements in	estimated only te walls made possiblevestigation Ki	as continuous accurate P 1-11 398 of 500
	8				

.

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

RESPONSE TO REVIEW COMMENTS ON GROUNDWATER MONITORING PROGRAM

(REF. NO. 1625/7)

SEPTEMBER 12, 1996

IMPERIAL METALS CORP. MT. POLLEY PROJECT

RESPONSE TO REVIEW COMMENTS ON GROUNDWATER MONITORING PROGRAM (REF. NO. 1625/7)

This report was prepared by Knight Piésold Ltd. for the account of Imperial Metals Corporation. The material in it reflects Knight Piésold's best judgement in light of the information available to it at the time of preparation. Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. Knight Piésold accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report.

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

RESPONSE TO REVIEW COMMENTS ON GROUNDWATER MONITORING PROGRAM (REF. NO. 1625/7)

TABLE OF CONTENTS

PAGE

SECTION 1.0	GENERAL	1
SECTION 2.0	RESPONSES TO REVIEW COMMENTS	2

FIGURES

Figure 1	Groundwa	ter Mo	nitoring Wells	Plan		
Figure 2	Proposed	1996	Groundwater	Monitoring	Wells	Schematic
	Diagram					

i

1625/7

September 12, 1996

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

RESPONSE TO REVIEW COMMENTS ON GROUNDWATER MONITORING PROGRAM (REF. NO. 1625/7)

SECTION 1.0 - GENERAL

The following is a response to the review comments submitted by Mr. Joe Negraeff of the Ministry of Environment on July 22, 1996, with respect to the Environmental Baseline Report 1995 and related Groundwater Monitoring Documents. This document specifically contains only the relevant responses to the review comments pertaining to the groundwater monitoring program as originally documented in the following:

- "Imperial Metals Corporation Mount Polley Project Environmental Baseline Report 1995", by Hallam Knight Piesold Ltd. (Section 7.0 only);
- "Manual on Sampling and Handling Guidelines for Determination of Groundwater Quality (Ref. No. 1625/5)", dated May 19, 1995, by Knight Piesold Ltd.; and
- "Groundwater Monitoring Program (Ref. No. 1624/2)", dated June 3, 1996, by Knight Piesold Ltd.

This document is organized in a manner whereby the review comment is listed followed by the response. Reference numbers are provided as per the original Environmental Baseline Report (1995) submitted for review. In some instances the response may take the form of a reference or clarification of information originally submitted for agency review.

The groundwater wells installed at the proposed minesite in 1995 were installed by Imperial Metals Corporation (IMC) for the primary purpose of investigating open pit dewatering and water supply for mill process requirements. The 1995 wells were installed without the direction or supervision of Knight Piesold Ltd. The details of installation were provided to Knight Piesold Ltd. by IMC and were included in the Report Ref. No. 1624/2.

IMC has recently provided further details on the 1995 installations. Specifically, the wells comprise 5 inch diameter, flush jointed PVC pipe which were grouted inside 6 inch diameter steel casings to a minimum depth of 5 m or to bedrock. The PVC included slotted sections in the aquifers to maximize water recovery. The use of the 1995 wells as groundwater monitoring wells was considered to be a secondary objective and will be decommissioned in early 1997 once the new 1996 monitoring wells have been installed and sampling has commenced.

Subsequent to the review comments and consideration of the importance of groundwater quality sampling and associated monitoring of potential hydrogeologic impacts on surrounding surface drainages, the 1996 groundwater monitoring program has been revised. Provisions have been included for the installation of a total of eight (8) additional wells (three new wells in the minesite area in addition to the five wells proposed for the tailings facility area, originally proposed in Report Ref. No. 1624/2) dedicated for the purpose of monitoring groundwater quality. The 1996 groundwater monitoring wells will be used to collect baseline groundwater quality and for monitoring groundwater quality during operations and at closure. Details on the proposed groundwater monitoring wells are included in the "Requirements and Specifications for the 1996 Groundwater Monitoring Program (Ref. No. 1625/8)" which accompanies this document.

SECTION 2.0 - RESPONSES TO REVIEW COMMENTS

The following are responses to review comments made by the Ministry of Environment, as documented on July 22, 1996, specifically relating to the groundwater monitoring program.

A. Imperial Metals Corporation Mount Polley Project Environmental Baseline Report 1995.

Section 7.0 Groundwater Sampling

Section 7.1 Introduction

Comment: "Please note that the Guidelines for Minimum Standards in Water Well Construction for the Province of B.C. are directed at production wells i.e. for development of water supplies. Optimal construction of monitoring wells differs somewhat from production wells in choice of well drilling machinery, well casing diameter, materials, and well development prior to sampling".

Response: Additional groundwater monitoring wells will be installed in 1996 in accordance with accepted standard practice for groundwater monitoring wells, as per EPA, CCME and ASTM criteria (see accompanying Report Ref. No. 1625/8 for details).

Section 7.2 Methods and Materials

Comment: "Are joins in the PVC well casings in the 1995 wells welded or threaded? Weld materials can contribute to metals contamination. PVC casing and screens should be threaded not welded to avoid potential for contamination from the weld compounds".

Response: The 1995 wells included 5 inch diameter Schedule 40 flush jointed, threaded PVC casing and screens, as per recent information

September 12, 1996

provided by Imperial Metals Corporation. All PVC casing and screens for the 1996 wells will also to be flush jointed and threaded.

Comment: "Groundwater samples should be free of particulates and kept anaerobic as they would be in-situ in the ground (i.e. no air or head space in the sample container). It is desirable to collect dissolved metals samples in groundwater without exposure to air by using "in-line" filtration methods to ensure no oxidation of iron etc. to ferric iron, which in turn precipitates as particulate ferric hydroxide or oxyhydroxides scavenging other dissolved metals species such as arsenic, cadmium, lead and vanadium with it in the process. This will lead to underestimation of the dissolved concentration of any metal".

Response: Agree that groundwater samples should be kept free of particulates and kept anaerobic. In-line filtration will be adopted in the future for the collection of dissolved metals samples.

Comment: "If there are lots of suspended solids in a groundwater sample as is the case of the '89 series wells around the tailings pond, this means either the well has not been properly developed prior to sampling i.e. (a) the fines present after well development were not flushed or cleaned out of the well, (b) that regular maintenance is not performed prior to sampling or (c) that precipitates (particulate matter) have formed in the sample due to exposure to air during the sampling process".

Response: Agree. All proposed 1996 monitoring wells will be developed following installation to remove all fine-grained sediment that may cause clogging. The wells will be re-developed if sediment is observed during operations. All remaining (1989 and 1995) wells which are scheduled to be re-sampled for a period of time in later 1996 and early 1997 will be re-developed if necessary prior to sampling.

Comment: "We insist that the monitoring wells to be constructed in 1996 around the tailings pond and elsewhere as described below, meet acceptable monitoring well specifications as detailed in numerous EPA and CCME publications on groundwater sampling methodology e.g. EPA/625/6-87/016, EPA/625/6-90/016b, EPA/625/R-93/003a; and CCME EPC-NCSRP-48/e (March 1994) etc.".

Response: The specifications for the 1996 groundwater monitoring wells will meet the necessary EPA and CCME criteria and shall be consistent with ASTM D5092 for groundwater monitoring wells. Details of the proposed 1996 installations are included in the accompanying Report Ref. No. 1625/8. This revised installation procedure will mean that the wells cannot be converted to groundwater pumpback wells as originally intended for the tailings impoundment.

Comment: "It would be worthwhile contacting some industry experts with practical field experience in groundwater sampling for metals, to gain from their experience with pumps, well maintenance, sampling equipment, in-line filtration etc. for the objective of obtaining good quality groundwater chemistry result especially for dissolved metals".

Response: Knight Piesold Ltd. has experience in groundwater monitoring well installation, groundwater sampling and well development. The monitoring well locations, installation methodology and sampling procedures have also been reviewed by Mr. Leslie Smith, Ph.D. of the University of British Columbia (see attached letter report).

Section 7.3.1 Open Pit / Mill Site

Comment: "Please note in this and subsequent sections i.e. 7.3.2 etc., that there is no B.C. Water Quality Criteria (BCWQC) for "total aluminum for aquatic life. The only BCWQA for aluminum for aquatic life is for the "dissolved" form of aluminum.

Response: Comment noted. Response under separate cover by Mr. Dan Royea of Hallam Knight Piesold Ltd.

1625/7

September 12, 1996

B. Imperial Metals Corporation Mt. Polley Project Groundwater Monitoring Program (Ref. No. 1624/2), June 3, 1996.

Section 2.1.6 Tailings Storage Area

Comment: "At the bottom of the page it says the groundwater flows northeast towards NE Edney Creek Tributary. From the contours shown in Figure 2.3, it would seem that the groundwater flows would be to the eastsoutheast. Please clarify".

Response: Correction noted. Groundwater flows do indeed flow eastsoutheast toward NE Edney Creek Tributary (as suggested) and not northeast as initially reported.

Section 2.3 1995 Monitoring Well Program

Comment: "The 110 mm diameter PVC well installations sited around the pit area are ideal for production i.e. dewatering, but not necessarily for monitoring. They will take considerable effort to purge prior to collection of water quality samples when they are not in use for dewatering. By having multiple screened zones in one casing or borehole, there will be a lot of mixing and diluting of groundwater from the different aquifer zones intercepted by the one casing. The drill logs indicate there are very significant aquifers at different levels in the same boreholes. Multiple small diameter casings each sealed in the different aquifers in each borehole would give more valuable information as to groundwater quality, its source and potential problem in the discharge area if known".

Response: The 1995 wells installed around the minesite area are suitable for dewatering as this was the primary intent with these wells. Although the use of these wells for groundwater monitoring is not ideal as mixing and dilution of groundwater from the different aquifers may occur, they may still function as monitoring wells to identify any changes in groundwater quality. Notwithstanding this, it has been decided by IMC that only the new (1996) wells will be used to monitor initial baseline and long-term groundwater quality. Some of the 1989 and 1995 wells will continue to be monitored in late 1996 and early 1997 to provide overlap with the 1996 wells. In addition, IMC reserves the option of continuing to monitor wells 95-R-5 and 95-R-6 to provide additional long-term monitoring of background water quality in the minesite area. The proposed schedule for monitoring is shown on Table 1 of Report Ref. No. 1625/8.

The proposed 1996 monitoring wells in the minesite area will be located below the groundwater table in relatively pervious fracture zones in bedrock to provide initial baseline and on-going groundwater quality information during operations. During drilling the hole will be water tested to determine the most permeable zone for the installation of the well. If a significant fracture zone is encountered at a shallower depth during the installation of the first well, then a separate hole will be drilled to enable a second monitoring well to be installed. The installation of multiple wells in one hole is not practical since the diameter of the hole must be very large to facilitate multiple installations of the minimum 50 mm diameter wells complete with the necessary filter pack and seal backfill materials. All attempts will be made during the 1996 groundwater monitoring program to locate the completion zones in the most permeable fracture systems, based on the geologic information and the conditions encountered during drilling. Additional details on the 1996 program are discussed in the accompanying Report Ref. No. 1625/8.

Comment: "Again please explain the rationale for the siting of two groundwater monitoring wells almost side by side (95-R-2 and 95-R-7) as indicated in Figure 2.4. It is assumed that these wells are situated and constructed primarily for dewatering purposes, with monitoring a secondary consideration. We would like to see installation of an additional well designed strictly for monitoring purposes, to be located between the central pit and Bootjack Lake, possibly off the main road below the most southwesterly corner of the central pit in the "draw" that is apparent from the contours in Fig. 1.3. The siting of this well should be done in consultation with a qualified hydrogeologist to ensure it is optimally located for detection of contaminated groundwater migrating from the pit area to Bootjack Lake. This should be done as soon as possible so that baseline data may be collected prior to mining".

Response: Groundwater wells 95-R-2 and 95-R-7 were constructed primarily for dewatering purposes, as suggested. Well 95-R-7 was drilled as a second well since 95-R-2 was lost during drilling. One additional groundwater monitoring well, designated P_8 , will be installed between the central pit and Bootjack Lake as part of the 1996 program, as suggested. This well will be located in the draw and adjacent to the access road, as shown on the attached Figure 1.

Comment: "We are also concerned that only one monitoring well (95-R-5) was installed along the entire basal perimeter of the southeast waste rock dump (which is some 2.5 km in length) and that it is located at the extreme north end of the dump. We will require the installation of 2-3 additional wells designed specifically for monitoring purposes to monitor contaminant migration in groundwater flow down-gradient from the waste rock dump towards Polley Lake and Bootjack Creek. Again the siting of these wells should be done in consultation with a qualified hydrogeologist to ensure they are optimally located for the above mentioned purpose".

Response: Two additional monitoring wells, designated P_6 and P_7 , will be installed east and south of the southeast waste dump between the dump and Polley Lake as part of the 1996 program. The approximate locations of the proposed wells are shown on the attached Figure 1.

Comment: "What was the groundwater level in the '95 series wells at the time of completion? This is not indicated in the Appendix B well log or the Appendix C borehole information. Please provide this information in writing to this office".

1625/7 September 12, 1996 INVESTIGATION KP 1-11 409 of 500 Response: Static groundwater levels for the 1995 wells, measured inside the well following completion and prior to sampling are as follows: 95-R-1, 20.1m; 95-R-4, 10.7m; 95-R-5, 1.3m; 95-R-6, 3.9m; 95-R-7, 12.2m. This information was collected by Knight Piésold Ltd. during groundwater sampling.

Section 3.2 Tailings Storage Area

Section 3.2.1 Baseline

Comment: "This section states that the tailings area baseline groundwater quality is poor, however the poor quality of the groundwater in this area may be exaggerated by poor well construction and development technique, as recognized in Section 2.2 of this report and as documented by Marc Zubel, Senior Groundwater Engineer, Water Management Branch, Victoria, B.C., in his Feb. 4, 1991 comments to A.P. Kohut on the Mt. Polley Copper/Gold Project Stage I Addendum Report (Oct. 1990)".

Response: Some of the 1989 wells at the tailings area will be plugged and abandoned during construction of the tailings facility. The remaining wells will be decommissioned in early 1997 following a period of overlap with the new 1996 monitoring wells. The proposed 1996 wells will be installed in accordance with accepted standards for monitoring well installation and will be developed prior to sampling.

Section 3.2.2 Operational

Comment: "One of the objectives of the Mt. Polley groundwater monitoring program as required by BCMELP and identified on page 2 of this report was to locate the seepage collection pond and recovery wells to ensure optimal recycling of seepage from the tailings pond during operations. This objective does not appear to be addressed in this report. Please respond as to whether the seepage pond has been optimally located for tailings pond seepage recovery? Does it capture all of the potential "discharge" in the sandy area in the vicinity of the main tailings embankment, identified during the initial drilling in the tailings pond area"?

Response: The seepage collection pond at the main tailings embankment has been located at the low point in the valley to intercept runoff and near surface seepage from the embankment. A system of embankment foundation drains, which are also interconnected with foundation pressure relief holes, drain by gravity into the seepage collection pond. The primary function of the seepage collection pond is to provide a reservoir for seepage monitoring and containment prior to recycling to the tailings embankment as necessary. The geological sequence of glaciofluvial and glaciolacustrine sediments which underlie the glacial till materials in the valley are complex and it is highly unlikely that all groundwater will report directly to the seepage collection pond. However, an extensive groundwater recovery well system has not been incorporated into the design since the tailings water is projected to be of good quality and no adverse water quality impacts are anticipated.

IMC had previously intended that all new groundwater monitoring wells downgradient of the tailings impoundment comprise 5 inch diameter wells which could be converted to pump back wells if required to supplement any requirements for make-up water for the milling operation. However, the current groundwater monitoring program has been modified to be consistent with MOE requirements for monitoring well installations only. Therefore, any provisions for seepage recovery by pump-back wells will be addressed during operations. Pump-back wells will be installed if additional make-up water is required or if on-going groundwater quality monitoring indicates that groundwater chemistry is being adversely affected by excessive seepage from the tailings impoundment.

Comment: "I do not have a copy of the Report referred to in this section i.e. Report on Project Water Management, Ref. No. 1624/1. Could you please provide me with a copy".

Response: Copy of "Report on Project Water Management (Ref. No. 1624/1)" included with this document, as requested.

Section 3.2.3 Post-Closure

Comment: "What is the basis for stating that the groundwater quality from the tailings impoundment will improve to levels better than baseline values? Is this due to a reduction in recharge for the drainage area due to change in permeability of surface material compared to pre-tailings pond conditions? or to better monitoring well installations, where the suspended sediment content, will be reduced or eliminated and therefore enhance the quality of the groundwater samples collected"?

Response: This statement should be modified from "improve to levels better than baseline values" to "return to levels similar to baseline values". During operations and for a period of time after closure, seepage from the impoundment will comprise process water which originates from the supernatant pond and from consolidation of the tailings mass. In the longterm, the closure pond will contain surface runoff water. Once consolidation of the tailings mass is complete and the seepage from the surface water pond reaches steady state conditions all groundwater impacts due to process water will cease. On-going seepage to the groundwater system would then be of similar water quality to the final surface runoff pond.

Section 4.0 Groundwater Monitoring Program

Comment: "The person who collects the groundwater samples, should not only be trained in environmental procedures, but be trained in and very familiar with proper groundwater quality monitoring procedures".

Response: Agree. IMC are currently relying on Hallam Knight Piesold Ltd., who have suitably qualified personnel trained in proper procedures in groundwater quality monitoring and sampling. Also, IMC are presently in the process of identifying a suitably qualified individual to assist with environmental monitoring, including on-going water quality monitoring and sampling during operations. The procedures and protocol for groundwater sampling and handling are included in Report Ref. No. 1625/5.

Figure 1.2

Comment: "How will the spring in the southwest corner of the tailings pond be capped off"?

Response: The spring, located in the southwest corner of the tailings facility, will be capped with a 50 mm diameter PVC pipe at surface to provide an additional permanent installation for groundwater quality monitoring. The pipe will be installed by excavating a shallow hole and installing a slotted PVC screen section complete with a filter sand pack and a bentonite seal at surface in order to facilitate regular water quality sampling of the spring. The spring in designated S_1 and is shown on the attached Figure 1.

C. Imperial Metals Corporation Mt. Polley Project: Manual on Sampling and Handling Guidelines for Determination of Groundwater Quality (Ref. No. 1625/5), May 19, 1995.

Note: Responses to other comments in Section C are addressed by Mr. Dan Royea of Hallam Knight Piesold Ltd. under separate cover.

Section 2.1.2 Sample Preparation and Preservation

Comment: "In-line filtration methods such as the Gelman high capacity filter should be employed for filtration of dissolved metals samples to ensure there is no exposure to air which oxidizes iron in the samples which in turn scavenges dissolved metals, thereby underestimating the dissolved portion of the metals. In groundwater situations there should be very little to no particulate in the water samples unless the well has not been properly developed or if oxidation occurs allowing precipitates to form on the inside of the well casing and immediate aquifer material around the well casing. Wells susceptible to such precipitate formation or sediment accumulation should be cleaned and pumped 2 to 3 weeks prior to sampling to remove the precipitates/sediment from the well prior to actually collecting samples".

Response: In-line filtration methods will be used in the future to collect the dissolved metals samples. All wells will be developed following installation and at least 2 to 3 weeks prior to sampling to remove any sediment or precipitates, as suggested.

Appendix D: Baseline Groundwater Quality Data to the End of 1995

Note: Details on the results of the baseline groundwater quality program are included by Mr. Dan Royea of Hallam Knight Piesold Ltd. under separate cover.

INVESTIGATION KP 1-11 414 of 500





IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

REQUIREMENTS AND SPECIFICATIONS FOR THE 1996 GROUNDWATER MONITORING PROGRAM (REF. NO. 1625/8)

SEPTEMBER 12, 1996

Suite 1400 750 West Pender Street Vancouver, British Columbia Canada V6C 2T8 Telephone (604) 685-0543 Telefax (604) 685-0147 CIS: 72360,477

Knight Piésold Ltd.

CONSULTING ENGINEERS

Knight Piésold Ltd. CONSULTING ENGINEERS

IMPERIAL METALS CORP. MT. POLLEY PROJECT

REQUIREMENTS AND SPECIFICATIONS FOR THE 1996 GROUNDWATER MONITORING PROGRAM (REF. NO. 1625/8)

This report was prepared by Knight Piésold Ltd. for the account of Imperial Metals Corporation. The material in it reflects Knight Piésold's best judgement in light of the information available to it at the time of preparation. Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. Knight Piésold accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report.



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 418 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

REQUIREMENTS AND SPECIFICATIONS FOR THE 1996 GROUNDWATER MONITORING PROGRAM (REF. NO. 1625/8)

TABLE OF CONTENTS

SECTION 1.0	GENERAL	1
SECTION 2.0	WELL LOCATIONS	2
SECTION 3.0	COMPLETION ZONES	4
SECTION 4.0	DRILLING METHODS	6
SECTION 5.0	INSTALLATION DETAILS	7
SECTION 6.0	WELL DEVELOPMENT	9
SECTION 7.0	SAMPLING PROCEDURES	10

TABLES

Table 1 Groundwater Monitoring Schedule

FIGURES

Figure 1	Groundwa	ter Mo	nitoring Wells	Plan		
Figure 2	Proposed	1996	Groundwater	Monitoring	Wells	Schematic
	Diagram					

i

Association of Consulting Association des Ingénieurs-Engineers of Canada Conseils du Canada

1625/8

PAGE

Knight Piésold Ltd.

CONSULTING ENGINEERS

<u>IMPERIAL METALS CORPORATION</u> <u>MT. POLLEY PROJECT</u>

<u>REQUIREMENTS AND SPECIFICATIONS FOR THE 1996</u> <u>GROUNDWATER MONITORING PROGRAM</u> <u>(REF. NO. 1625/8)</u>

SECTION 1.0 - GENERAL

The following is a summary of the recommendations and requirements for the installation of additional (1996) groundwater monitoring wells for the Mt. Polley Project. The objective of the wells is to provide high quality installations for the collection of groundwater samples for the evaluation of initial baseline conditions and groundwater quality during operations and at closure. The monitoring wells will also be used to monitor fluctuations in groundwater levels resulting from seasonal effects as well as to monitor any influences resulting from mine development. It is the intent to install the new 1996 groundwater monitoring wells sometime in September, 1996 to allow for the collection of the initial set of (baseline) samples as soon as possible.

Specific details on the monitoring well supplies, installation procedures and drilling methods are provided along with recommendations for well development and sampling procedures. The locations of the proposed 1996 groundwater monitoring wells in addition to the existing wells are shown on the attached Figure 1. This figure is revised from the original Figure 2.4 previously submitted in the "Groundwater Monitoring Program (Ref. No. 1624/2)". The completion details and requirements for the 1996 groundwater monitoring wells are also shown on the attached Figure 2. The proposed schedule for groundwater monitoring is shown on Table 1.

The proposed groundwater monitoring program has been reviewed by Mr. Leslie Smith, Ph.D. of the University of British Columbia. His review comments and suggestions are presented in his attached letter report "Re: Mt. Polley Project -



Association des Ingénieurs Conseils du Canada 1625/8 September 12, 1996 INVESTIGATION KP 1-11 420 of 500

1

Knight Piésold Ltd.

CONSULTING ENGINEERS

Groundwater Monitoring Program". Mr. Smith's recommendations have been included in this document and are supported by Imperial Metals Corporation.

This document should be read in conjunction with the "Response to Review Comments on Groundwater Monitoring Program (Ref. No. 1625/7)", dated September 11, 1996 which also accompanies this document.



Association des Ingénieurs-Conseils du Canada 1625/8

September 12, 1996 INVESTIGATION KP 1-11 421 of 500

Knight Piésold Ltd.

CONSULTING ENGINEERS

SECTION 2.0 - WELL LOCATIONS

The 1996 groundwater monitoring wells will be installed in selected intervals and geologic units to characterize the groundwater quality at the minesite and tailings facility areas. The wells will be installed as dedicated wells for the sole purpose of groundwater quality sampling. The wells will be installed and developed as per standard practice and as outlined herein and will be maintained over the life of the project.

it is planned to installa

A total of eight (8) monitoring wells will be installed during the 1996 program, including five (5) at the tailings facility area, designated P_1 to P_5 , and three (3) at the minesite area, designated P_6 to P_8 . The monitoring wells will be located outside the various development areas to provide initial baseline and background groundwater quality as well as for long-term groundwater quality monitoring. The locations of the proposed monitoring wells are shown on Figure 1.



1625/8

September 12, 1996 INVESTIGATION KP 1-11 422 of 500 Knight Piésold Ltd.

CONSULTING ENGINEERS

SECTION 3.0 - COMPLETION ZONES

The completion zones for the monitoring wells will be located in the saturated zone below the groundwater table and below the groundwater surface predicted during operations. This will ensure that groundwater samples may be collected at any time during the year and at any time during operations and at closure. The wells will be installed in relatively pervious zones in overburden and bedrock, as these zones will provide the preferential paths for groundwater flow in addition to providing greater recoveries for well development and sampling.

The monitoring wells in the tailings facility area will be completed in the relatively permeable glaciofluvial sandy unit which underlies the glacial till, and in the heavily fractured bedrock (conglomerate) at the base of the overburden. Two holes will be drilled at each site for the installation of one well per hole in each of the relatively pervious overburden, and fractured bedrock zones.

The monitoring wells in the minesite area will be installed in relatively permeable fracture zones within bedrock. The actual locations of the completion zones (screened intervals) will be assessed based on the geologic conditions intersected during drilling. Specifically, zones of high water take or flow will be targeted as completion zones for the wells. A target depth of approximately 30 to 40 metres will be selected for each hole. Water tests will be carried out progressively during drilling to determine the most permeable zone for the completion zone. Specifically, the location of the most permeable intervals in each borehole will be selected by observations of changes in water production rates and water levels as the borehole is drilled. The most permeable zone, consisting of either a small fracture zone, or a highly fractured zone within a fractured interval will then be selected for the monitoring interval. An air rotary system will be used to drill the borehole. If it is determined that the most permeable zone is at some depth above the bottom of the borehole, then either a local sand and gravel or a thick grout mixture will be installed as backfill prior to the installation of the well. In addition, if a second significant fracture zone is intersected at a shallower depth, then an additional well will be installed (in a separate hole) at the same site.



Association des Ingénieurs Conseils du Canada 1625/8 September 12, 1996 INVESTIGATION KP 1-11 423 of 500

Knight Piésold Ltd.

CONSULTING ENGINEERS

The thickness of the completion zone will depend largely on the permeability and water production rate of the fracture zone. In general, approximately 3 metre thick completion zones will be used for the high permeability zones, while approximately 6 metre thick completion zones will be used for the less permeable zones. The larger completion zones are preferred in low permeability zones to allow for more flow into the well during well development and purging, and to provide a more representative sample for the low yield producing zones. In no case will the completion zone exceed 6 metres.

Completion details for the proposed 1996 groundwater monitoring wells is shown on Figure 2.



Knight Piésold Ltd.

CONSULTING ENGINEERS

SECTION 4.0 - DRILLING METHODS

Appropriate drilling methods will be utilized to prevent contamination of the surrounding formation water and to allow for the collection of representative groundwater samples. No drilling fluids or additives will be used for the drilling of the monitoring well holes as the fluids may affect the groundwater samples. Dry methods will be utilized for the drilling of all boreholes.

Potential drilling methods for the monitoring well holes in overburden in the tailings facility area include hollow stem auger, air-rotary with casing advancer, or dual-wall (reverse circulation) air rotary. Samples may be retrieved from auger flights, or from split-spoon or thin-walled sampling methods to identify permeable water-bearing zones for the selection of the screened intervals for the wells. No mud-rotary drilling will be permitted nor air-rotary utilizing the down-hole hammer as this method requires lubricating oil which may contaminate the hole.

Drilling methods for the monitoring well holes in bedrock in the minesite area include air-rotary or reverse circulation (air only). The completion zones for these wells will be determined by observation of water production rates and water levels measured progressively at select intervals during drilling. No mud-rotary or downhole hammer methods shall be used for the monitoring well holes at the minesite.



Association des Ingénieurs-Consells du Canada 1625/8 September 12, 1996 INVESTIGATION KP 1-11 425 of 500 Knight Piésold Ltd.

CONSULTING ENGINEERS

SECTION 5.0 - INSTALLATION DETAILS

The groundwater monitoring wells will be installed in pre-drilled holes with a minimum diameter of 150-mm (6-inches). Dry drilling methods only (i.e. no drilling fluids) will be used for the drilling of the monitoring well holes. Details of the well installations are described below. A schematic diagram showing the typical completion details for the groundwater monitoring wells and record information required for installation are shown on Figure 2.

The groundwater monitoring wells will comprise decontaminated 50.8 mm (2 inch) diameter, flush jointed, threaded Schedule 40 PVC tubing. This will facilitate the installation of submersible pumps for groundwater sampling and pump systems for the development of the wells. Centralizers will be installed at designated spacings (approximately 6 metres) along the PVC to help centre the casing inside the borehole. Well screens will be installed at the bottom of the well and will be 3.05 or 6.10 metres (10 or 20 feet) long with #20 (0.020 in. or 0.25 mm wide) slots. The screens will also be decontaminated, flush jointed, threaded Schedule 40 PVC as per the solid riser. Suitable slip caps, slip couplers and end plugs are also required, as shown on Figure 2.

Backfill materials will include a uniform silica sand, such as #16 (0.40 mm diameter) required as the filter pack around the well screens. Such sand shall be no coarser than #10 mesh and no finer than #40 mesh. The sand will be bounded by a low permeability seal zone comprised of approximately 1 metre minimum of fine (3/8" diameter or less) bentonite chips. The materials will be backfilled from the bottom up with a delivery (tremmie) pipe to prevent any bridging of backfill materials during installation. A sand and gravel or cement-bentonite grout backfill may be required, particularly for the minesite wells, in order to isolate the completion zone and support the groundwater well installation above the bottom of the borehole.

Following the installation of the top bentonite seal, the holes will be backfilled with a cement-bentonite grout mixture around the annulus between the PVC casing and the wall of the borehole. The grout will be mixed to a thick consistency and



Association g des Ingénieurs-Conseits du Canada 1625/8 September 12, 1996 INVESTIGATION KP 1-11 426 of 500

Knight Piésold Ltd.

CONSULTING ENGINEERS

pumped down the hole with a delivery pipe from the bottom up to ensure a proper seal. The grout seal is required to prevent surface water from entering the well. Under no circumstances will the boreholes be grouted by pouring grout into the open hole from surface to a depth greater than 3 metres inside the hole.

Following grouting, a surface bentonite seal and protective steel casing, complete with locking cap will be set in concrete around the PVC casing for protection and ease of sampling.

These methods are consistent with EPA, CCME and ASTM D5092 requirements and specifications.



Association des Ingénieurs-Conseils du Canada September 12, 1996 INVESTIGATION KP 1-11 427 of 500 Knight Piésold Ltd.

CONSULTING ENGINEERS

SECTION 6.0 - WELL DEVELOPMENT

The groundwater monitoring wells will be developed following installation to remove fine particulate matter, including fine silts and clays which may originate from the geologic formation or from cuttings generated during drilling. Well development techniques include pumping water down the well under positive and negative (suction) pressures to remove foreign matter and particulates from the filter sand pack around the screen. The result is clear and non-turbid water which is more representative of the in-situ groundwater conditions. This also makes it easier to filter the water samples (by in-line filtration methods) for the dissolved metals samples. Air-surging methods will not be permitted as this may disturb and significantly reduce the effectiveness of the filter sand pack.

Subsequent well development will also be carried out if the water is found to be turbid or contain foreign matter.



Association des Ingénieurs-Conseils du Canada 1625/8 September 12, 1996 INVESTIGATION KP 1-11 428 of 500 <u>Knight Piésold Ltd.</u>

CONSULTING ENGINEERS

SECTION 7.0 - SAMPLING PROCEDURES

Groundwater samples will be recovered by the use of submersible pump systems. The pump system is advantageous in decreasing the sampling time, minimizing labour costs and allowing for direct sampling from the screened interval and therefore is strongly recommended.

Bailers will also be available in the event that the pump system breaks down or is not available. Only one bailer will be dedicated to each well for sampling purposes. Bailers will not be utilized for more than one well as this will result in potential contamination of the samples.

Sampling procedures generally involve the removal of stagnant water from the well prior to collecting the sample. It is recommended that the equivalent of three borehole volumes of water be removed from the well prior to collecting the sample. This is achieved by measuring the static water level inside the well and calculating the volume of water inside the well and borehole, then pumping (or bailing) three times this volume from the well prior to sampling. This ensures that the sample is representative of the in-situ baseline groundwater within the formation. In addition, during the purging of the wells (prior to sampling), chemical, or field, parameters such as pH and/or electrical conductivity will also be checked to ensure these values are stable (within acceptable limits) prior to collecting the groundwater sample. In the event that the recovery of the well is very slow and three borehole volumes cannot practically be removed from the well then the well should be pumped once and allowed to recover prior to collecting the sample.

The groundwater sampling program previously prescribed in the "Groundwater Monitoring Program (Ref. No. 1624/2)" indicates that groundwater samples will be collected on a quarterly basis (i.e. once every 3 months). This will allow any natural variations in the baseline or background water quality to be assessed. Rising head type slug tests will also be performed in each well, once at the completion of well development, and once per year thereafter in order to assess the on-going performance of the well and to provide information on the hydraulic



Association des Ingénieurs-Conseils du Canada 1625/8 September 12, 1996 INVESTIGATION KP 1-11 429 of 500

Knight Piésold Ltd.

CONSULTING ENGINEERS

conductivity and response of the geologic formation. The proposed schedule for groundwater monitoring is included in Table 1.

Details on the groundwater sampling methods and protocol, including sampling and chain of custody forms for sample collection as well as forms for rising head tests, are included in the "Manual on Sampling and Handling Guidelines for Determination of Groundwater Quality (Ref. No. 1625/5)" previously issued on May 19, 1995. A revised copy of this manual will be prepared prior to continuing with the groundwater sampling program in the fall of 1996.



Association des Ingénieurs-Conseils du Canada 1625/8

September 12, 1996 INVESTIGATION KP 1-11 430 of 500

TABLE 1

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT GROUNDWATER MONITORING SCHEDULE

nstallation	Monitorine	Pre- Establ	mining M ishment of	onitoring for f Baseline Data		C	onstruc	struction Mining															Post-mining Monitoring												
No.	Sites		195	16			199	7		1998					1999					2000	1	2007		20	08		2009					2	010		201
	100 C	JF3	AMJ	JASONI	DIF	M, A	MJ.	JAS	0 N 1	D J F 3	M. A. M	11/	A \$ 0	D N D	JFM	AMJ	JAS	0 N D	1 F 1	CAM JJ	0	ND	J.F.M	A.M.J	1 4 8	OND	JEM	A M J	JAS	0.N.I	D J. F.I	A M J	JAS	SON	DJF
92-8-1	Mult Site, Open Pits				+-5		8	++			++-	1	++		++				+++	++++	-		++		-	-	++-		11-						
95-R-7	Mill Site, Wasie Dump		10	10 M	- 8	-					-			-	-		-		+++		-		11	14	11				1.1.	1	+++		-+	_	
95-R-4	Open Pits							1.				44		1				11			-		41		-	24	1.	1	-	-	11			-	444
MP89-107	Open Pits			100 100	E		Assume	d lest				1	1								-				-		1	1.					31		111
MP89-146	Open Pits				10		Assume	ed lost					1.	11									1		1.01				11					_	
MP89-151	Open Pits		IIII :		10		Assume	ed lost					1					14							111		11		11					11	
Pg (1996)	Open Pits			日間	1			屋	圓	間			飅	圓	飅	题	目目	1	圓	III		圓	目	10 A	篇	肩	圖			圖	篇				1
P _s (1996)	Waste Dump				1		题	1	日間	日間		6		圓	圓		. III	1	躢	圓		圓	圖		10	圓	篇	篇	1	圜	1	100	1.9		1
P ₁ (1996)	Waste Dump			III III	調			1	國	圓		F	100	圖	圓	麗	1	1 801	闘	圖			圜		100	10	1		100	爴	圜	100			4
MP89-231	Tailogs Storage Area	-	圖	職職	1		Assume	ed lest																1.11	E.							1	11		
MP89-232	Tailings Storage Area		8	間間	目	1	Аззити	d lest					1.1								-														TT
MP89-234	Tailings Storage Area	1	10	100 100	1		101	TT													-										1 i l		11		
MP89-235	Tailings Storage Area			111 125	1	1	Assume	ed lost						T							-				1								100		
P ₁ (1996)	Tailings Storage Area				1			1	1 61	1			101	1	圓	1	E	1 10	100	m		151	101				圓		1	10	1	10	1		i
P3 (1996)	Tailings Storage Area				1		1	1		1			100		圓			10	100				1					EI .	1	100	111	III	T		1
P ₂ (1996)	Tailings Storage Area		1117		1		HI I	1			1		100	1	10	10			1	101		1	10			85		=	1 18	100	83	-	T		
P4 (1996)	Tallings Storage Area		111	100 100			1	1	810	193			100	-	1	1		1 101	1	1	-	8	10	105		-	8	10	1	bit	100	-	T		TT
P ₅ (1996)	Tailings Storage Area	1		100 100	1		100	1		16	100		Real Property lies			1	1		100				10	10	10	10	1		1		1	100	1		
S, (1996)	Tailings Storage Area		HU.		1 6			1 1			1		100		8		6	1	1	10			10						1	100	1	-			
95-R-5	Background	1	1		1			1	T	10	1		7	ħ	-A	- A	H F	T	IT	171		71	T	Th.					T	T	11		-11		
95-R-6	Background	F		10 10	16								11	T							-						11					T	-11		111
MP89-236	Background							tt					tt	tt									11			11			11			117			
1	Review of yearly data	11	111	106	tf	tt	11	1	TT		11		TT	T									11			11	11		11			111	11	TT	11
	annual report				1	tt					1		++	+													100		11						100
5					1	++		++-		F +			++	+					<u>_</u>				7+						1				111	++	1
	Review of post- mining		111	1111	+	++		++	+++		++		++	++					11				++				1		++-	11	11	+++	+++	++	+++
	data and maniform	-			++	1		++-	+++		-	+++	++	++									++-						++			11	-	++	+++
2	program adjustment	-			+	-		+			++	+++	+	++-									++-						+			11	111	++	100
Btes:	1. P ₁ = Groundwater mo 2. S ₁ = Monitoring well	mitoring to be inc	wells to be i	installed during fi	all of 15	196. Juring 6	all of 19	96.			-lash-		1.1.				-						LaL a				-				1.1.1	111		-	

P₁ = Groundwater monitoring wells to be installed during fall of 1996.
 S₁ = Monitoring well to be installed at groundwater seep location during fall of 1996.
 Groundwater quality monitoring data will be reviewed as soon as practical following each sampling round. The results will also be reviewed and documented in an annual report to be issued each January.

\$/7/96 EVOBIDATAV634\SCHED3.XLS




IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

SPECIFICATION FOR DRILLING, MONITORING WELL INSTALLATIONS AND RELATED SERVICES (REF. NO. 1628/3)

SEPTEMBER 18, 1996

Suite 1400 750 West Pender Street Vancouver, British Columbia Canada V6C 2T8 Telephone (604) 685-0543 Telefax (604) 685-0147 CIS: 72360,477

Knight Piésold Ltd. CONSULTING ENGINEERS

INVESTIGATION KP 1-11 434 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

3

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

SPECIFICATION FOR DRILLING, MONITORING WELL INSTALLATIONS AND RELATED SERVICES (REF. NO. 1628/3)

This report was prepared by Knight Piésold Ltd. for the account of Imperial Metals Corporation. The material in it reflects Knight Piésold's best judgement in light of the information available to it at the time of preparation. Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. Knight Piésold accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report.



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 435 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

CONSULTING ENGINEERS

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

4

SPECIFICATION FOR DRILLING, MONITORING WELL INSTALLATIONS AND RELATED SERVICES (REF. NO. 1628/3)

TECHNICAL SPECIFICATION

TABLE OF CONTENTS

PAGE

DEVELOPMENT

SECTION 1.0	GENERAL			
	1.1	SCOPE OF WORK	1	
	1.2	COMPLETION TIME	2	
	1.3	QUALITY OF WORK	2	
	1.4	CONTRACT ADMINISTRATION	3	
	1.5	PROVISIONAL SUMS	3	
	1.6	TERMINATION	3	
SECTION 2.0	MOB	ILIZATION/DEMOBILIZATION	4	
	AND	SITE PROVISIONS		
	2.1	MOBILIZATION	4	
	2.2	DEMOBILIZATION	4	
	2.3	STAGING AREA	4	
	2.4	DRILLING SITE ACCESS AND	4	
		PREPARATIONS		
SECTION 3.0	MON	ITORING WELL DRILLING STRATEGY	6	
SECTION 4.0	EQU	IPMENT, MATERIALS AND LABOUR	8	
	4.1	GENERAL	8	
	4.2	DRILLING AND SAMPLING EQUIPMENT	8	
	4.3	MONITORING WELL INSTALLATION	9	



CONSULTING ENGINEERS

SECTION 5,0	REC	ORD KEEPING	11
SECTION 6.0	MEA	SUREMENT AND PAYMENT	12
	6.1	MOBILIZATION/DEMOBILIZATION	12
	6.2	SITE PREPARATION AND DRILL MOVES	12
	6.3	DRILLING AND TESTING PAYABLE ON AN HOURLY BASIS	12
	6.4	STANDBY FOR UNANTICIPATED WORK STOPPAGES	13
	6.5	CONSUMABLE ITEMS	13

TABLES

Table 1	Summary of Drilling Program
Table 2	Monitoring Well Supplies

FIGURES

Figure 1	Groundwater Monitoring Wells Plan
Figure 2	Proposed 1996 Groundwater Monitoring Wells - Schematic
	Diagram

 $M_{2}^{1/2} \in \mathbb{R}^{3/2} \times \mathbb{R}^{1/2}$





Association Association of Consulting des Ingénieurs-Engineers Conseits of Canada du Canada - ii -

1628/3 September 18, 1996 INVESTIGATION KP 1-11 437 of 500

Knight Piésold Ltd.

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

SPECIFICATION FOR DRILLING, MONITORING WELL INSTALLATIONS AND RELATED SERVICES (REF. NO. 1628/3)

TECHNICAL SPECIFICATION

SECTION 1.0 - GENERAL

1.1 SCOPE OF WORK

The Work of this Contract includes the supply of all personnel, equipment and materials and the performance of all things required in connection with the installation of groundwater monitoring wells for the Mt. Polley Project, as described in this Specification, including the following major items of work:

- 1. Mobilizing and setting up one drill rig and any necessary support equipment.
- 2. Drilling through overburden using a dry drilling method, casing, and recovering soil samples in selected holes.
- 3. Drilling through bedrock using a dry drilling method.
- 4. Monitoring changes in down-hole water production and measuring standing water levels during drilling operation.
- 5. Providing monitoring well materials and installing monitoring wells.
- 6. Providing specified backfill materials and backfilling holes using these materials.
- 7. Cleaning up the drill sites and the temporary staging area.



Canada

The following work and services will be provided by Imperial Metals Corporation (the Owner) or by Knight Piésold (the Engineer) at the site:

- 1. Establishing and marking all monitoring well sites.
- 2. Assisting in the preparation of all monitoring well sites including clearing where necessary.
- 3. Maintaining site access routes.
- 4. Supervising all drilling activities and monitoring well installations.
- 5. Surveying locations and reference elevations of all monitoring well holes.

1.2 COMPLETION TIME

The Tender shall be returned to the Owner on or before September 25, 1996. The Contractor shall commence mobilization immediately upon written notification to the designated staging area and shall be prepared to commence drilling on or before October 1, 1996.

1.3 QUALITY OF WORK

In order to ensure efficient and satisfactory performance of the work in accordance with the requirements of this Contract, the Contractor shall employ competent and experienced foremen and drillers at all times.

The Engineer can, if in his opinion the work is not being carried out to acceptable standards, order the Contractor to stop work. The work will start again when, in the Engineer's opinion, the fault has been corrected. All payment for that work will stop while the fault is being corrected. No payment shall be made for work improperly performed.



Canada

Knight Piésold Ltd.

1.4 CONTRACT ADMINISTRATION

Upon award of the Contract, a Purchase Order will be issued to the Contractor by the Owner. Technical direction of the work, including site supervision, and contract administration will be carried out by Knight Piésold's Resident Engineer (the Engineer).

The Contractor shall assign, and make available for the duration of the Work, a designated representative (Contractor's Representative) authorized to carry out the work in all respects and authorized to agree upon and sign for the quantities of the Work on a daily basis.

The Contractor's Representative shall present the daily quantities each day to the Engineer for agreement and signature by Noon of the following day. The signed daily time and quantity sheets, when summarized in a monthly invoice, shall form the sole basis for payment under the Contract.

1.5 PROVISIONAL SUMS

Provisional sums have been established for various items of Work to be carried out and for materials to be supplied by the Contractor. Written authorization from the Engineer is required <u>prior</u> to any expenditure, purchase or work under Provisional Sum items.

1.6 TERMINATION

The Engineer reserves the right to terminate the Work on any hole or for the entire site upon providing at any time reasonable advance notice to the Contractor. In the event of such termination, the Owner's sole obligation to the Contractor shall be limited to payment for Contractor services performed to that time in accordance with the payment items in the Schedule.



DNSULTING ENGINEERS

SECTION 2.0 - MOBILIZATION/DEMOBILIZATION AND SITE PROVISIONS

2.1 MOBILIZATION

The Contractor shall mobilize one drill rig, plus all down-hole accessories, consumable down-hole supplies, tools and testing equipment to the Mt. Polley Project. Mobilization shall include setting up at the staging area and preparation of the drill rigs, tools and accessories at the first drill site.

Mobilization shall commence immediately upon written notification by the Engineer.

Additional drill rigs, tools, etc. shall be mobilized when and as required by the Engineer.

2.2 DEMOBILIZATION

Demobilization of any drill rig shall proceed only upon written notification of the Engineer.

2.3 STAGING AREA

A staging area will be designated by the Owner for the Contractor's temporary use during the course of the work. The Contractor shall comply with all requirements regarding proper disposal of waste oils, rubbish, sewage, etc. to the Owner's satisfaction and as directed by the Engineer. During the course of the work, the staging area shall be maintained in an orderly condition. Upon final demobilization, the Contractor shall leave the staging area in an orderly and clean condition, to the Owner's satisfaction, as directed by the Engineer.

2.4 DRILLING SITE ACCESS AND PREPARATIONS

The Owner will be responsible for providing access to the drill sites for a truckmounted drill rig and for clearing the drill sites where necessary. The Owner will provide the necessary personnel and equipment for preparing the drill sites. The



Association des Ingénieurs Conseits du Canada 1628/3 September 18, 1996 INVESTIGATION KP 1-11 441 of 500

Knight Piésold Ltd.

Contractor shall be responsible for the timely and efficient completion of the Work including the provision of any staging and/or other supports for the rig and its equipment. The Owner shall assist the Contractor in constructing staging/supports using available equipment, where necessary. After removal of the drill rig, each site shall be cleaned up to the satisfaction of the Owner, as directed by the Engineer.



SECTION 3.0 - MONITORING WELL DRILLING STRATEGY

In general, one deep and one shallow monitoring well will be installed at each of the eight (8) drill sites at the Mt. Polley Project. The locations of the drill sites, designated P_1 to P_8 , are shown on the attached Figure 1. Monitoring wells will be installed at five (5) sites, designated P_1 to P_5 , at the tailings facility area and at three (3) sites, designated P_6 to P_8 , at the minesite area.

(15 inch)

Each monitoring well will consist of 50.8 mm (2 inch) diameter PVC tubing (screens and risers) installed in a pre-drilled borehole. The monitoring well holes should be 150 mm (6 inch) in diameter since it is generally recommended that a minimum annular space of 2 inches be maintained between the inside diameter of the borehole and the outside diameter of the monitoring well (ref. ASTM Standard D5092, subsection 6.6.2). The holes may be drilled to a minimum diameter of 125 mm (5 inches) provided that there will be sufficient annular space between the outside of the monitoring well and the inside of the borehole/casing for the insertion of a tremmie pipe large enough to deliver the backfill materials to the required depth.

At the minesite area, both deep and shallow monitoring well holes will be terminated within bedrock as the overburden in the area is generally very thin. The holes for the deep monitoring wells will be advanced to a target depth of between 30 and 40 metres, to be determined by the Engineer at the time of drilling. For costing purposes, a target depth of 40 m can be assumed for each of the deep minesite holes, as indicated in Table 1. After completion of the deep monitoring well, a shallow well may also be installed at the drill site, at the discretion of the Engineer. For costing purposes, it can be assumed that a second monitoring well hole will be drilled to a maximum depth of 10 m at each of the three minesite locations.

At the tailings facility area, the deep monitoring well holes will be terminated at a distance of 10 to 15 metres into bedrock. At Locations P_1 to P_3 , the expected thickness of the overburden ranges from approximately 30 m to 35 m, through which soil sampling will be conducted using standard penetration testing (SPT) methods and split spoon equipment. Sampling will be generally carried out at 3 m (10 ft) intervals for the first 15 m (50 ft) and at 6 m (20 ft) intervals thereafter. At Locations P_4 and P_5 the expected overburden thickness is expected to be much less and, therefore, no



n Association ng des Ingénieurs Conseils du Canada 1628/3 September 18, 1996 INVESTIGATION KP 1-11 443 of 500

Knight Piésold Ltd.

soil sampling will be required. After completion of the deep monitoring well at each location, a shallower hole will be drilled and terminated within the overburden at a depth determined by the Engineer at the time of drilling. For costing purposes, the maximum depth of the shallower monitoring well holes can be assumed to be the depth of the bedrock surface, as indicated in Table 1.

The monitoring wells shall be installed in a manner similar to that shown on Figure 2. For the monitoring well holes in the minesite area, the depth of the completion zone for each well will be determined based on cuttings retrieved from the hole; down-hole groundwater inflow rates, to be estimated during drilling at approximate 3 m (10 ft) intervals; and periodic water level readings. In all cases, the completion zones will target the most permeable zones encountered during drilling and will be determined on site by the Engineer.

For the monitoring well holes in the tailings area, the depth of the well completion zones will be determined based on the results of SPT testing and overburden sampling as well as cuttings samples retrieved from the bedrock, down-hole groundwater inflow rate estimates and periodic water level readings. In general, one well will be installed in the most permeable soil unit and one in the fractured bedrock near the overburden-bedrock contact.



SECTION 4.0 - EOUIPMENT, MATERIALS AND LABOUR

4.1 GENERAL

The Owner will provide a bulldozer, backhoe and any miscellaneous support equipment which is currently on site, as necessary. The Contractor may obtain water necessary for mixing grout and concrete at the Mt. Polley plant site. The Contractor must have a means of retrieving and storing sufficient water for use at each monitoring well site.

The Contractor shall supply all other equipment, materials, supervision and facilities required for the performance of the work. The Contractor shall also maintain a good supply of spare parts, casing, rods and consumables. Subject to the approval of the Engineer, the Contractor may use equipment and materials of his own preference, except for items which are specifically required in this Specification. Items of equipment or materials which, in the opinion of the Engineer, do not meet the specified requirements shall be replaced by the Contractor, at his own expense, with equipment and materials meeting the specified requirements.

4.2 DRILLING AND SAMPLING EQUIPMENT

The Contractor shall mobilize and have in operation one drill rig capable of penetrating overburden and bedrock until the work is complete. The Contractor shall employ a dry drilling method as described below and shall have available split spoon sampling equipment. A method of estimating down-hole groundwater inflow rates shall be provided by the Contractor and shall be submitted to the Engineer for approval prior to carrying out the Work. The Contractor shall supply a means of periodically measuring down-hole water levels during drilling unless provisions are made for the Engineer to supply such equipment.

Dry drilling methods must be used for the drilling of all monitoring well boreholes. Drilling fluids or additives are strictly prohibited as they could contaminate the groundwater samples. For the monitoring well holes in overburden (in the tailings facility area), acceptable drilling methods include hollow-stem auger, air-rotary with casing advancer, or dual-wall (reverse circulation) air-rotary. The drilling method



Association des Ingénieurs-Conseils du Canada

nada

selected should allow for temporary support of the borehole walls both during drilling and during backfilling operations since cohesionless alluvial deposits may be encountered at the tailings facility area. For the monitoring well holes in bedrock (in the minesite area), acceptable drilling methods include air-rotary or reverse circulation. No mud-rotary drilling or air-rotary drilling using a down-hole hammer will be permitted.

4.3 MONITORING WELL INSTALLATION

Monitoring wells will be installed as shown on Figure 2. An estimation of the quantities of supplies and materials required for the monitoring wells, which the Contractor must supply, is provided in Table 2. Since the actual monitoring well completion zone depths will not be determined until the drilling of each hole is complete, the estimates given in Table 2 are based on maximum quantities expected.

The monitoring wells should consist of 50.8 mm (2 inch) diameter, decontaminated, flush-jointed and threaded Schedule 40 PVC tubing (includes both riser pipe and screen). For each well, the Engineer will select either a 3.05 m or 6.10 m (10 ft or 20 ft) long well screen, depending on the relative permeability of the surrounding geologic zone. The screen shall comprise #20 (0.020 in. or 0.25 mm wide) slot, or similar, section of PVC. The Contractor shall have available sufficient screen lengths to install 6.10 m of screens at each monitoring well. The Contractor shall also supply sufficient centralizers to attach to the tubing at 6 m spacings as well as end plugs, top caps and slip couplers for all wells.

A uniform sand, such as #16 silica sand (or 0.40 mm min. diameter), will be required for the filter pack around the well screens. Such sand shall be no coarser than #10 mesh and no finer than #40 mesh. The sand will be bounded by a low permeability seal zone comprised of at least 1 m of fine (3/8" dia or less) bentonite chips. Above the top seal, the annulus between the PVC casing and the wall of the hole will be backfilled with a cement-bentonite grout mixture. Below the lower bentonite seal, where necessary, the hole will be backfilled using either a cement-bentonite grout mixture or a clean sand and gravel, to be approved by the Engineer. A surface bentonite seal will also be installed along with a protective steel casing complete with locking cap set in concrete around the top of the PVC casing for protection.



Association g des Ingénieurs Conseils du Canada 1628/3 September 18, 1996 INVESTIGATION KP 1-11 446 of 500

Knight Piésold Ltd. CONSULTING ENGINEERS

The grout shall consist of water, Normal Portland Cement and high-yield milled bentonite (unaltered), mixed to a thick consistency. The recommended mixing ratio is 30 USgal water : 3 bags cement : 1/2 to 1/3 bag bentonite.

All backfill materials placed to a depth greater than 3 m below the ground surface must be installed from the bottom up using a delivery (e.g. tremmie) pipe to prevent bridging of the backfill materials inside the hole during installation.



CONSULTING ENGINEERS

SECTION 5.0 - RECORD KEEPING

During the drilling, the Contractor shall keep a running log of the drilling operation. This log shall be signed by the driller and foreman and the original copy given to the Engineer at the end of each shift. The log shall include a general description of the overburden and bedrock, measured groundwater inflow rates, water level readings, and general comments on drilling conditions and unusual rises or drops in the water levels during drilling. The locations of the water inflow tests and water level readings will be determined by the Engineer.

All the time spent drilling versus testing shall be recorded whether to the account of the Engineer or to the Contractor.

The Contractor's Representative and the Engineer shall agree on quantities for payment on a daily basis. The signed daily quantity forms, when summarized in a monthly invoice, shall form the sole basis for payment for the Work.



1628/3 September 18, 1996 INVESTIGATION KP 1-11 448 of 500

CONSULTING ENGINEERS

SECTION 6.0 - MEASUREMENT AND PAYMENT

6.1 <u>MOBILIZATION/DEMOBILIZATION</u>

Payment for mobilization shall include for all costs of mobilizing and establishing the Contractor's presence at the designated staging area. Mobilization will be considered complete when the drill is fully functional and actively drilling its first hole. Payment for demobilization shall include for all costs of final cleanup and removal from the site of the work of all equipment, materials and waste as directed by the Engineer.

Payment for mobilization and demobilization will be made at the lump sum rates negotiated between the Owner and the Contractor.

6.2 SITE PREPARATION AND DRILL MOVES

Measurement for payment of drill moves will be made on the basis of an hourly rate for the drill moves and shall include tear down, move and rig set-ups required for the work.

Payment for drill moves will be made at the rate negotiated between the Owner and the Contractor.

6.3 DRILLING AND TESTING PAYABLE ON AN HOURLY BASIS

Drilling operations shall be carried out at the locations and to the depths directed by the Engineer. Measurement for payment for drilling will be made on the basis of the actual time taken to drill the holes and perform the tests, as prescribed by the Engineer. Payment will be made at the rates negotiated between the Owner and the Contractor and shall include for all costs of the drilling operations required to advance the hole. Payment for the installation of the monitoring wells will be made at a separate rate to be negotiated between the Owner and the Contractor.



6.4 STANDBY FOR UNANTICIPATED WORK STOPPAGES

Standby time shall be deemed to occur when, in the opinion of the Engineer, the Contractor is delayed for short periods through no fault of the Contractor.

Payment for standby time, up to a maximum of 8 hours per shift, will be made at the rate negotiated between the Owner and the Contractor.

6.5 CONSUMABLE ITEMS

Unit rates for the consumable items shall be established based on the values included in the attached Table 2, to be completed by the Contractor.

Consumable items required by the Engineer and not included on Table 2 will be made at the actual and necessary net cost, including handling and freight, for delivery of the materials to the site. All items and materials to be claimed as consumables must be approved by the Engineer prior to being used in the Work.



Knight Piésold Ltd. CONSULTING ENGINEERS

à

TABLE 1

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

1996 GROUNDWATER MONITORING PROGRAM SUMMARY OF DRILLING PROGRAM

	Approximate	Deep We	ell Hole	Shallow W	Vell Hole
Well Site	Expected Overburden Thickness (m)	Maximum Expected Hole Depth (m)	Split Spoon Sampling	Maximum Expected Hole Depth (m)	Split Spoon Sampling
1. <u>Tailin</u>	gs Arca				
\mathbf{P}_1	30	45	Yes	30	No
P ₂	35	50	Yes	35	No
P ₃	30	40	Yes	30	No
P ₄	5	20	No	5	No
P ₅	10	20	No	10	No
2. Mines	ite Area				
P ₆	Minimal	40	No	10 (Optional)	No
P ₇	Minimal	40	No	10 (Optional)	No
P ₈	Minimal	40	No	10 (Optional)	No



Association des Ingénieurs-Conseils du Canada

Knight Piésold Ltd.

TABLE 2

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

1996 GROUNDWATER MONITORING PROGRAM MONITORING WELL SUPPLIES

Item	Quantity	Unit	Unit Rate (\$CDN)	Total Cost (\$CDN)
 2 in. dia. Schedule 40 PVC solid riser (flush jointed, threaded, decontaminated, c/w centralizers at 6 m spacings). 	1270	ft.		
 2 in. dia. shedule 40 PVC screen (#20 slot, flush jointed, threaded, decontaminated). 	320	ft.		
3. Bentonite chips ("Enviroplug" or similar).	50	50 lb. bags		
4. Portland normal cement (Type 1)	110	88 lb bags		
5. High yield unaltered bentonite drill mud	25	50 lb bags		
6. Silica sand (#16 or similar)	130	50 lb. bags		
7. Silica sand (#20/#30 or similar)	25	50 lb. bags		
8. Concrete stone mix	15	55 lb. bags		
 2 in. dia. PVC slip couplers, bottom plugs and J-type top caps. 	16	each		
10. Steel protective casings	16	each		
TOTAL COST				

Notes:

- Quantities of materials were estimated assuming that all wells will be installed at the maximum target depth

- Quantities of cement and high-yield bentonite were calculated based on a mix ratio of 30 USgal of water : 3 bags cement : 1/2 bag bentonite.

- If unit sizes of materials supplied by the Contractor differ from those indicated above, quantities should be adjusted accordingly.



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 452 of 500





MOUNT POLLEY MINING CORPORATION MOUNT POLLEY PROJECT

1996 GROUNDWATER MONITORING WELL INSTALLATION PROGRAM (REF. NO. 1628/4)

FEBRUARY 7, 1997

Suite 1400 750 West Pender Street Vancouver, British Columbia Canada V6C 2T8 Telephone (604) 685-0543 Telefax (604) 685-0147 CIS: 72360,477

Knight Piésold Ltd.

CONSULTING ENGINEERS

Knight Piésold Ltd. CONSULTING ENGINEERS

IMPERIAL METALS CORPORATION MT. POLLEY PROJECT

<u>1996 GROUNDWATER MONITORING</u> <u>WELL INVESTIGATION PROGRAM</u> (REF. NO. 1628/4)

This report was prepared by Knight Piésold Ltd. for the account of Imperial Metals Corporation. The material in it reflects Knight Piésold's best judgement in light of the information available to it at the time of preparation. Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. Knight Piésold accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report.



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 456 of 500

CONSULTING ENGINEERS

MOUNT POLLEY MINING CORPORATION MOUNT POLLEY PROJECT

1996 GROUNDWATER MONITORING WELL INSTALLATION PROGRAM (REF. NO. 1628/4)

TABLE OF CONTENTS

PAGE

SECTION 1.0	INTRODUCTION		
	1.1	PROJECT DESCRIPTION	1
	1.2	PREVIOUS WORK	2
	1.3	REFERENCE INFORMATION	3
	1.4	SCOPE OF WORK	5
SECTION 2.0	1996	MONITORING WELL INSTALLATIONS	6
	2.1	GENERAL	6
	2.2	DRILLING	6
	2.3	GROUNDWATER MONITORING WELL	8
		INSTALLATIONS	
	2.4	IN-SITU TESTING	9
	2.5	LABORATORY TESTING	9
SECTION 3.0	SUM	MARY AND CONCLUSIONS	10

TABLES

Table 2.1 Summary of 1996 Monitoring Well Installations



Association des Ingénieurs-Conseils du Canada

Knight Piésold Ltd. CONSULTING ENGINEERS

FIGURES

Figure I Groundwater Monitoring Wel	Figure 1	Groundwater Monitoring Wells Pla	in
-------------------------------------	----------	----------------------------------	----

APPENDICES

Appendix A	Drillhole Logs
Appendix B	Groundwater Monitoring Well Completion Details



CONSULTING ENGINEERS

MOUNT POLLEY MINING CORPORATION MOUNT POLLEY PROJECT

1996 GROUNDWATER MONITORING WELL INSTALLATION PROGRAM (REF. NO. 1628/4)

SECTION 1.0 INTRODUCTION

1.1 PROJECT DESCRIPTION

The Mount Polley Project is located in central British Columbia approximately 56 kilometres north-east of Williams Lake, as shown on Figure 1.1. The nearest settlement is the community of Likely, on the northern tip of Quesnel Lake.

The Mount Polley Mine has reserves of 82.3 million tonnes of copper and gold ore contained in three ore bodies. Ore will be hauled to the crusher and then it will be processed in the mill by selective flotation to produce a copper-gold concentrate at a production rate of approximately 17,800 tonnes per day (6.5 million tonnes per year). Approximately 92.6 million tonnes of waste rock will be stored in waste rock dumps adjacent to the open pit.

After processing the ore to produce the copper/gold concentrate, the tailings will be discharged as a slurry into the tailings storage facility which will provide environmentally secure storage of the tailings solids. As the solids settle out of the slurry, process fluids are collected and recycled back to the mill for re-use in the milling process. No surface discharge of any process solution from the tailings facility is required or anticipated.

In 1996, the British Columbia Ministry of Environment, Lands and Parks (MELP), Environmental Protection Branch requested that a Groundwater Monitoring Program be designed and implemented for the Mount Polley Project. One of the requirements of the program was to "... establish monitoring wells down-gradient from the pit, waste rock piles, and tailings pond dams, and to sample aquifers in



Association des Ingénieurs-Conseils du Canada 1628/4 February 7, 1997 INVESTIGATION KP 1-11 459 of 500

both surficial deposits and bedrock ...", including the establishment of background wells up-gradient of any potential impacts by mining activities. The 1996 Groundwater Monitoring Well Installation Program was undertaken to fulfil this requirement. This report presents the details of the 1996 Groundwater Monitoring Well Installation Program, procedures followed during the work and results of the program.

1.2 PREVIOUS WORK

In 1989 Knight Piésold Ltd. was retained by Imperial Metals Corporation to conduct a geotechnical evaluation of the open pits, waste dumps and tailings storage facility for the proposed development of the Mount Polley Project. Monitoring wells were installed as part of this program. The 1989 Monitoring Well Program is summarized as follows:

1989 MONITORING WELL PROGRAM

- A total of nine (9) groundwater monitoring wells were installed in selected NQ diamond drillholes during the 1989 investigations by Knight Piésold, as shown on Figure 1. The 1989 monitoring wells were not installed in complete accordance to current industry practices. They were constructed using 38 mm diameter PVC well pipe with screened sections extending from approximately 3 metres below ground surface to the end of the well string. The screened sections were made using a hacksaw to cut the slots in the PVC pipe.
- Three wells (MP-89-107, MP-89-146 and MP-89-151) were installed in the open pit area. These wells were extended the full length of the exploration drill holes, approximately 150 metres. Bentonite seals were not installed below the well string. The surface seals consisted of a 1 metre concrete plug covered by two metres of bentonite that was installed just below the bedrock surface.



Association des Ingénieurs-Conseils du Canada

CONSULTING ENGINEERS

Six wells (MP-89-231, MP-89-232, MP-89-233, MP-89-234, MP-89-235 and MP-89-236) were installed at the tailings facility. These monitoring wells varied from 15 to 40 metres in depth. Bentonite seals were installed below the well string and at the ground surface. Natural sand backfill was placed around the screened interval.

Additional groundwater wells were completed in the vicinity of the open pits and mill site with an air rotary water well drill rig in 1995. The program was coordinated and supervised by Imperial Metals Corporation. The 1995 Monitoring Well Program is summarized as follows:

1995 MONITORING WELL PROGRAM

 In August, 1995 seven groundwater wells (R-95-1 to R-95-7) were installed in the vicinity of the open pits and mill site, as shown on Figure 1. The wells were primarily for groundwater supply and were constructed with 110 mm PVC well pipe in 150 mm holes advanced with air rotary drilling methods. Well casings were installed over the full length of the holes, which ranged from 80 to 170 metres. Screened zones were installed at various levels, where high recharge was encountered during drilling. The well casings were sealed in accordance with standard BC water well practices.

1.3 <u>REFERENCE INFORMATION</u>

Prior to starting the 1996 Groundwater Monitoring Well Installation Program, a report containing detailed specifications for the drill program was issued, "Imperial Metals Corporation, Specification for Drilling, Monitoring Well Installations and Related Services, (Ref. No. 1628/3), September 18, 1996".

A summary of previous work on groundwater monitoring wells is presented in the Knight Piésold report "Imperial Metals Corporation, Groundwater Monitoring Program, Ref. No. 1624/2, June 3, 1996". This report is a compilation of the



Association des Ingénieurs-Conseits du Canada 1628/4 February 7, 1997 INVESTIGATION KP 1-11 461 of 500

hydrogeological conditions at the site and the anticipated impacts that will result from the project development.

Knight Piésold Ltd. has prepared a number of reports which contain information relevant to the Groundwater Monitoring Program, as summarized below:

- i) Imperial Metals Corporation, Report on Geotechnical Investigations and Design of Open Pit, Waste Dumps and Tailings Storage Facility, February 19, 1990.
- ii) Imperial Metals Corporation, Mount Polley Project, Stage I Environmental and Socio-Economic Impact Assessment, January 1991.
- iii) Imperial Metals Corporation, Report on Project Water Management (Ref. No. 1624/1), February 6, 1995.
- iv) Imperial Metals Corporation, Tailings Storage Facility Design Report (Ref. No. 1625/1), May 26, 1995.
- v) Imperial Metals Corporation, Manual on Sampling and Handling Guidelines for Determination of Groundwater Quality, (Ref. No. 1625/5), May 19, 1995.

A number of geotechnical investigations were conducted during construction of the Stage Ia tailings embankment in 1996. Detailed geologic and hydrogeologic information obtained from these investigations and the 1996 Groundwater Monitoring Well Installation Program will be presented in the report, "Mount Polley Mining Corporation, Mount Polley Project, Updated Design Report, Ref. No. 1627/2".

- 4 -



Association des Ingénieurs Conseils du Canada

Knight Piésold Ltd.

1.4 SCOPE OF WORK

The 1996 Groundwater Monitoring Well Installation Program was conducted between October 30 and December 6, 1996. The drill Contractor (Drillwell Enterprises Ltd.) was responsible for the following:

- Mobilization of one drill rig (air rotary) and support equipment.
- Overburden drilling, using a dry drilling method.
- Standard penetration testing (SPT) and associated sampling in overburden.
- Bedrock drilling, using a dry drilling method.
- Monitoring changes in down hole water production and measuring water levels during drilling operations.
- Installation of groundwater monitoring wells in permeable zones and backfilling of drill holes. (Well pipe and supplies were provided by Mount Polley Mining Corporation.)
- Well development.
- Clean up of drill sites.

Access to the drill sites and drill site construction were the responsibility of Mount Polley Mining Corporation. The monitoring well locations were surveyed by the Mount Polley Mining Corporation survey crew.

The following services were provided by Knight Piésold for the 1996 Groundwater Monitoring Well Installation Program:

- Selection of location for drill sites.
- Supervision of drill activities and monitoring well installations.
- Logging of the drill holes, including SPT samples and drill cuttings. Detailed drill logs are included in this report.
- Laboratory testing of selected samples.
- Selection of completion zones for the groundwater monitoring wells. The monitoring well completion details are included in this report.
- Supervision of well development.
- Training and supervision of monitoring well sampling.



anada

CONSULTING ENGINEERS

SECTION 2 - 1996 MONITORING WELL INSTALLATIONS

2.1 GENERAL

The 1996 groundwater monitoring well installation program was conducted between October 30 and December 6, 1996. The 1996 groundwater monitoring wells were designed to serve as permanent groundwater monitoring points for the project. They will be utilized prior to operations, during the life of the mine and after mine closure.

A total of nine sites were selected for well installations, as follows:

- Six sites around the perimeter of the tailings storage facility (GW96-1, GW96-2, GW96-3, GW96-4, GW96-5, GW96-9).
- Three sites around the perimeter of the mine (GW96-6, GW96-7, GW96-8).

The locations of the drill sites are shown on Figure 1.

A total of 15 monitoring wells were installed at the nine locations. Most sites were targeted for one deep and one shallow well. Only GW96-6, GW96-7 and GW96-9 had a single well completed. If two wells were targeted for a site, the geologic formations and hydrogeologic conditions observed during drilling of the first (deep) hole were used to select the well completion zone for the second (shallow) hole. The completion zones of the monitoring wells were selected to target preferential groundwater flow pathways near surface and at depth.

A summary of the monitoring wells, their locations and completion zone details is provided on Table 2.1.

2.2 DRILLING

The drilling was conducted with an air-rotary rig, provided by Drillwell Enterprises Ltd., of Duncan B.C. The holes were advanced with a 149.2 mm (5 7/8 inch) O.D.



Geologic descriptions and observations of moisture conditions, in-hole water levels and down-hole water production rates are provided on the drillhole logs in Appendix A.

2.3 GROUNDWATER MONITORING WELL INSTALLATIONS

After drilling and logging of the first (deep) drillhole was completed at each site, the zones of greatest groundwater yield within each of the overburden and bedrock units were selected for completion of the monitoring wells. If two wells were required, a second hole was then drilled for installation of the shallow well. At GW96-6 and GW96-7, bedrock was encountered at surface or beneath a very thin veneer of overburden and the bedrock permeability was relatively consistent. Therefore, only one well was installed at these locations. GW96-9 was a supplemental well specifically targeted for a near surface aquifer in the vicinity of GW96-3 and GW96-4 and only one well was considered necessary.

Each monitoring well consists of 50.8 mm (2 inch) diameter, decontaminated, flushjointed, threaded Schedule 40 PVC tubing (screens and risers) installed within a hole approximately 150 mm (6 inch) in diameter. Screen lengths from 1.8 m (6 ft) to 6.1 m (20 ft) were selected in the field, as required to capture the extent of the target zone. The screens were provided with #20 (0.020 inch or 0.25mm) slots. The screens were surrounded by a filter pack of uniformly graded #16 silica sand. The well completion zone was hydraulically isolated by an upper and, where necessary, lower bentonite chip seal. In most cases, the upper seal was separated from the #16 filter sand pack by a layer of fine-grained (#20-#30) silica sand in order to prevent downward migration of gelled bentonite into the primary filter pack. Above the upper seal, the hole was backfilled with a combination of bentonite chips and/or cement-bentonite grout (installed using a tremmie pipe) and/or washed gravel (19 mm to 37 mm). Each well installation was completed with a bentonite chip surface seal and a steel protective casing with locking cap at surface.

Monitoring well completion details are provided in Appendix B.



Association des Ingénieurs Conseils du Canada 1628/4 February 7, 1997 INVESTIGATION KP 1-11 465 of 500

CONSULTING ENGINEERS

2.4 IN-SITU TESTING

In-situ testing was limited to Standard Penetration Tests (SPT's) within the overburden in GW96-1A, GW96-2A and GW96-3A for the purpose of collecting further information on foundation conditions at the tailings embankments. Uncorrected SPT blow counts are included on the drillhole logs in Appendix A.

2.5 LABORATORY TESTING

Soil samples collected during Standard Penetration Testing in the 1996 groundwater monitoring well drillholes were sealed up and are in storage at the Mount Polley site. To date, no laboratory testing has been carried out on these samples.



1628/4 February 7, 1997 INVESTIGATION KP 1-11 466 of 500

SECTION 3 - SUMMARY AND CONCLUSIONS

During the 1996 Groundwater Monitoring Well Installation Program, a total of 15 monitoring wells were installed at 9 different sites, 6 of which were located around the perimeter of the tailings storage facility and 3 of which were located around the perimeter of the mine. Monitoring wells were completed in overburden and in bedrock.

Groundwater quality sampling from the monitoring wells is required on a quarterly basis. Monitoring will be conducted prior to commencement of mining operations, in order to establish baseline water quality, during mining operations and for a period of at least 2 years after mine closure. The groundwater monitoring program will be administered and conducted by Mount Polley Mining Corporation.



Association des Ingénieurs-Conseils du Canada 1628/4 February 7, 1997 INVESTIGATION KP 1-11 467 of 500 Knight Piésold Ltd. CONSULTING ENGINEERS

TABLE 2.1

MOUNT POLLEY MINING CORPORATION MOUNT POLLEY PROJECT

SUMMARY OF 1996 MONITORING WELL INSTALLATIONS

LUOR REPORT 1628 (AubL-21 stelShout)

6-Feb-97

Monitoring General		Coordinates		Ground	Completion Zone	Geologic Unit
Well No.	Location	Northing	Easting	El. (m)	(m below ground surface)	
GW96-1A	Tailings Facility	5 819 939.06	595 415.82	927.89	52.4 - 60.1	Bedrock
GW96-1B	Tailings Facility	5 819 935.22	595 416.16	927.81	32.6 - 39.0	Overburden
GW96-2A	Tailings Facility	5 819 449.92	596 065.40	931.42	50.9 - 55.2	Bedrock
GW96-2B	Tailings Facility	5 819 447.08	596 074.73	931.42	29.7 - 35.7	Overburden
GW96-3A	Tailings Facility	5 818 308.97	595 768.75	912.06	47.0 - 53.0	Bedrock
GW96-3B	Tailings Facility	5 818 306.52	595 765.16	912.06	15.4 - 20.0	Overburden
GW96-4A	Tailings Facility	5 818 164.58	595 147.94	940.56	19.2 - 25.0	Bedrock
GW96-4B	Tailings Facility	5 818 162.87	595 151.26	940.46	2.7 - 7.3	Overburden
GW96-5A	Tailings Facility	5 819 626.68	594 330.34	973.55	13.8 - 19.7	Bedrock
GW96-5B	Tailings Facility	5 819 629.64	594 329.79	973.44	3.0 - 7.1	Overburden
GW96-6	Minesite Area	5 822 851.66	593 659.21	1058.53	34.4 - 43.0	Bedrock
GW96-7	Minesite Area	5 821 520.53	592 983.23	1021.32	9.9 - 14.3	Bedrock
GW96-8A	Minesite Area	5 822 468.46	591 861.59	1050.10	35.2 - 40.1	Bedrock
GW96-8B	Minesite Area	5 822 469.40	591 859.31	1050.09	11.0 - 15.7	Overburden/Bedrock
GW96-9	Tailings Facility	5 818 277.14	595 503.89	916.18	3.4 - 6.1	Overburden


Knight Piésold Ltd. CONSULTING ENGINEERS

r

APPENDIX A

DRILLHOLE LOGS



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 470 of 500

KNIGHT PIE	ESOL	D LTC).		TI	FST	HOLE	106	TEST HOLE NO.
PROJECT LOCATION OI DATE BEGUN	M F TES	t: Po ST HC 29/96	//ey DLE 7 D.	- H SF	Vdro 10 14 N5012 15 N5012 FINISH	9161 339.06 135.22 ED_[Investigat E595415.82 E595416.16 DEC 6/96	PROJECT GROUND	SHEET 1 of 4 NO. <u>/627.300</u> EL. <u>18: 927.87</u> BY <u>PJP</u>
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	BLOWS/FOOT			DЕРТН (т)	GRAPHIC LOG	DESC	CRIPTION AND CLAS	SSIFICATION
DRILLWELL - AIR ROTARY W/O WATER -57/8 & tricone bit -6" steel casing		-							
Nore: * Gw's A+B Installed in separate drill holes. (3m appart)	-	Tqe			- 5.1	· + · + · + · + · · +	SILT (TILL) clay, rare c graded, low brown, m. brown, m. very m	- sandy, some g obbles, very stiff permeativy, vi asive. very stiff to bist.	ravel (20%) and tostiff, well any moist to wet, hard and
GEOLOGY inferred from cuttings and SPT symples.	- ¹⁶ /24 =67%	9 19]n= 16535 14			3.9 -	++++++++++++++++++++++++++++++++++++++	- peroning moist t	some gravel to a very moist.	gravelly and
~	-24/24	5PT 2 230=			5.1 - - 6.0 -	1 +++ ++++++++++++++++++++++++++++++++	CLAY and S poor recover softer - se CLAY and s lesser silt	y from cuttings spt @ 6.0m. ILT (GLACIOLAC and fn silty s	strine) - as wet and ostrine) - and laminations
1×1 1×20 3001 1×1		456	¢		-	1 ++ · · · · · · · · · · · · · · · · · ·	bedded, loo only low 20 to 100 texture non plost soturated	pomm thick, fil monotions observations observations observations me thick we revers high to m ic coarse silt grey.	is no sand used. Contains Ill gridal fill-like nod plasticity to layers, wet to
CO 111: 100/100					85 - - -		- hit 0.3m of glaci	ø boubler beli el till unit-se	eved to be tap e SPT @ 8.8m
Litely pushed gravel in	-4"/24" 	571 577= 15726 13			8.8 -	+ · · · · · · · · · · · · · · · · · · ·	SILT and s gravelly, tri med dense moist to u	ace clay and n to dense, massi on moist, brow	me gravel to are cobbles, we, low permability wn.
	_				9.5 -	+ 0	- possibly - becoming	investigation ke dense to very d	+ill > softer 1-11 471 of 500 ense

KNIGHT PIE CONSULTING	ESOLD	LTD. Ers		TI	EST	HOLE L	OG	TEST HOLE NO GW96-14/ SHEET 2 of 4
PROJECT LOCATION OF DATE BEGUN	Mt. TEST	<u>B//e</u> HOLE	DATE	FINISH	gical ED_1	Investigation	PROJECT NO GROUND EL LOGGED BY	
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	BLÖWS/FOOT		DEPTH (m)	GRAPHIC LOG	DESCRIF	PTION AND CLASSIF OF MATERIAL	TICATION
DRILLWELL - AIR ROTARY W/O WATER - 57/8" of tricone bit - 6" steel casing		1						
Nore: * Gw's A+B Installed in separate drill hotes.	 	5PT 2 102n= 1979		10.7 - - 12.1 - - - - - - - - - - - - - - - - - - -	+ · · + · · · · · · · · · · · · · · · ·	- becoming vo brown - E Coarser SAND (TILL) (30%+035%) well graded, moist, grey last 1"	- si Hy (25% to: trace clay, very massive, low p to grey - brow	t and grey slightly dense, ermeability, n.
				/2.8 - /3.7 - 	· + · + · + · + · + · + · + · + · + · +	Sand (thin - cont'd gra - becoming fin w some fine grav- low perm	liver of glacin welly silly si ne grained to sind (20%) el "Fine Till", nea bility, moi	silt (TILL) and till SILT (TILL) and some very stiff, st, grey-gree
			¢	17.3 - 17.3 -	++++++++++++++++++++++++++++++++++++++	SAND (TILL) clay, very low porm, brown of brown of - beroming g sitt.	dense, well, and . dense, well, groo moist brow, times puelly and or	si Hy, trace led, mossive, + to ornge - ly some
	6"/10" 2 _60% 5	21 50 (4") =>100	i.	18.0 -	+ + + + + + + + + + + + + + + + + + +	SILT and SAND Clay, very sti low permeabing red - brown	D (TILL) - grav ff to hard, well lity, moist,	elly, trace graded, mass brown to
		-		27.7	+ 0,0+	SAND (TILL) - clay and co graded, mass dimp to me	grovelly, some soles, very d nivestightion pering pist, bionn	silt, trace

1										
	KNIGHT PIE CONSULTING	ESOL	D LT	D.		TE	EST	HOLE L	OG	TEST HOLE NO. GW96-1A/18 SHEET 3 of 4
	PROJECT LOCATION OF DATE BEGUN	M TES	<u>†. P</u> ST H 1.29/	OLE_	- ' <i>H</i> ATE	FINISHI	<i>qical</i> ED	Investigation DEC6/96	PROJECT NO GROUND EL LOGGED BY	
11.00 F	NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	BLOWS/FOOT	L		DEPTH (m)	GRAPHIC LOG	DESCRIF	PTION AND CLASSI OF MATERIAL	FICATION
	DRILLWELL - AIR ROTARY W/O WATER -57/8 of tricone bit -6" steel casing									
	Nore: * Gw's A+B Installed in separate drill holes.		45 437 n= 62 570	a		27.7		SILT (GLACIO Sond (10%) Coarse si H Permerbilit Mossive?, -may be per betty girde SAND (GLACIO fine grained, thin, Very de	LACUSTRINE) - and chy (5-10 wery stiff, y unit, non moist, grey iodic fine gra d layers. FLUVIAL) - track silt brination. ASE, DOORLY gr	trace fine %), mostly likely low plastic, to grey-green. vel and e coarse silt, s me and aded by ered.
COD REF. CUD/REF.I Pist scale 1=1	Note: Upon Start-up in Am, Watr at 60' below grade inside casing. Note: Begins making watr -31.9m -2 gall/nin -32.6m - 5gall/nin -36.6m - 15gall/nin -38.1m - 50gall/nin -41.1m - 2gall/nin -41.1m - 2gall/nin -42.4m - 0gall/nin -42.4m - 0gall/nin -42.4m - 0gall/nin					30.7		Saturated, g SILT (TILL) - s well groded, tr lower permes SAND (GLACIC Silt (3-10°/c dense, period SILT (Tine) & w sondar o - unit grou between Sond with gravel w - clern wote, SILT and SAN traie cley, ve mossive, low to red - bowly	rey. Sandy, some gra site chy (10%) bility, moist of LUVIAL) - gra bic thin layors for thin layors fo	tel, very stift, mossive, 19 rey velly, troce dirty water, of silt/ rght up touth se grained to sandy as dirty. t gravel re gravel re gravel re gravel vell gravec

.

L

L

	KNIGHT PIE		D LT[Э.		TE	EST	HOLE L	OG	TEST HOLE NO. GW96-14/18
	PROJECT LOCATION OF DATE BEGUN	<u>†. В</u> st но	//ey DLED	<u>- '</u> Н АТЕ	<u>ydro log</u> FINISHI	gical ED	Investigation	PROJECT NO GROUND EL LOGGED BY	0. <u>/627.300</u> . <u></u> 	
Wr or dr gr et	NOTES oter loss, type nd size of hole, rilling method, roundwater level, ic.	CORE RECOVERY %	BLOWS/FOOT			DEPTH (m)	GRAPHIC LOG	DESCRIP	PTION AND CLASSI OF MATERIAL	FICATION
CO MC (COLNCIA POLICIA POLICIA POLICIA)	RILLWELL - AIR ROTARY MO WATER 57/8" & tricone bit 6" steel casing TTE: * GW'S A+B Installed in separate drill holes.					47.6 		Vokanic Cong "fingments" werthered se of volcrnic - poriodic density : priminily - no fiult Zonos	Nomerate (BEL of hematitic diment comp clasts. moist rock co and moisture constant. facture, w. inproposed.	DROCK) - olly altered, osed priminity hips but contat ok terning
						-		*	NVESTIGATION KP 1-1	1 474 of 500

KNIGHT PIE CONSULTING	ESOLI	D LT	D.	Т	EST	HOLE	LOG	TEST HOLE No. GW96-74/78 SHEET 1 of 4
PROJECT LOCATION OF DATE BEGUN	M- TES	t. Po ST HO 10/9.	//ey - DLE(TSF 6DA	Hydro 10)28: N5819)28: N5819 TE FINISH	9ica/ 449.92, 447.08; HED M	Investiga 552665.30	GROUND EL	0. <u>/627.300</u> <u>2A: 931.42</u> <u>26: 931.42</u> <u>PJP</u>
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	SPT BLOWS/FOOT		DEPTH (m)	GRAPHIC LOG	DES	CRIPTION AND CLASS OF MATERIAL	IFICATION
DRILLWELL - AIR ROTARY W/O WATER - 57/8" of tricone bit - 6" steel casing								
Nore: * Gw's A+B Installed in separate drill holes.	-				+ +	0-5.5m - 0-3n 3-5.5 5.56m - 50	GLACIAL TILL - SCET, WET 5 m - VERY RE. 5 SS. 2"O.D.	use, Moist
GEOLOGY INFARED FROM CUTTINGS AND SPT SAMPLE		1= 250	- PUSAIOD RECIS		+ + + + + + + + + + + + + + + + + + +	4" RECOU SILT/S VERY TRACE 5.5 m - 7.0 Moi	ERY - PUSHED R AND TILL - GRE DENSE, WELL = CLRY, GRAVE NM - TILL ST GRAVELLY C	V-BROWN, G-RADED, MOIST CEY, MASSIN
				-	- + 0 - + + 0 - +	F.01 - 8.9 SILT, DCC M	Sm - TILL ISAND, BROKEN SIONAL COBSCI	UP GRAUEL
*			¢		- + - + - + - + - + - + - + - + - + - +			
-SPT @ 11.8M	- 24"	15 25 32	JN=58	(1/m) - (36') -		GLACIO LA SIL- SAND VER - M	CUSTRINE T, GREY- GREEN 25%, SOME C MOIST AY CONTAIN TH	IN FINE SAN
		28	-		- + _ - + . + + +	NERY MINER STOP	MOIST TO W MATER BUIL INVESTIGATION KP 1-1 DRICCINC	ET AND DS UP WHEN 1 475 of 500

KNIGHT PIE CONSULTING	ESOL) LT[eers).		TE	EST	HOLE LOG TEST HOLE No. GW96-24/28 SHEET Z OF 4
PROJECT LOCATION OF DATE BEGUN	<u>M</u> TES N <u>Nou</u>	<u>t. B</u> St Ha . <i>10/</i>	1/ey DLE_ 196 D.	<u>- ' H</u> ATE	<i>Idro log</i> FINISHI	gical	Investigation PROJECT NO. 1627.300 GROUND EL. Now.17/96 LOGGED BY PJP
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	BLOWS/FOOT			DEPTH (m)	GRAPHIC LOG	DESCRIPTION AND CLASSIFICATION OF MATERIAL
DRILLWELL - AIR ROTARY W/O WATER -57/8 & tricone bit -6" steel casing					11.7		
Nore: * Gw's A+B Installed in separate drill holes.		-				↓ ↓ ↓	SPT- S.S. 2" O.D @ 11.8 m (38'9") SGLACIOCACUSTRINE SILT - VERY STIFF, OLIVE GREEN - LINNE BROWN, THINCY TO IRREGULAR LAMINATED (2-10 mm THICK), FINE SANA LAYERS, CONTAINS ONE BOMM THICK FINE- MED. GRAINED SAND LAYER - DAMP, VARIABLE SILT CONTENT (PRIMARILY MO-CS GRAINED) LOW VERTICAL K, POTENTIALLY
SPT 2" 0.0.55 Q 141.9~	-24"	18 30 36 45	N=66				MODERATE HORIZONTAL IS ALONG SEAMS (DISCENTINUOUS)) LOW TO SOME CLAY IN FAIN CAYERS. TO 14.9- SAME UNIT, SEE SPT & 10.9 14.9- SAT- S.S. 2" O.D. (49') GENERALLY FN-MED (49') GENERALLY FN-MED GREIDED, GENERALLY FN-MED GREIDED SILT - ITH LAMINATIONS (VARVES?) OF MORE CMY RICH LAYERS 1-2mm, OCCASIONAL 2-3cm CRYERS OF TILL-LIKE, POORLY SORTED
2) 3) -WATER THELE APPROX. Q 1 5.76 m. (55') -WATER FILLING 2-41 & EDA VALEN STOP REILLING.		4		6011	-18-28	++ ++ ++ ++ +++	SETTER GRADED SAND/SILT LAYERS WITH FINE GRADEL (UP TO ID MAP). LOW PLASTICITY IN GENERAL, LOW PERME ARICITY, MORIZONTAL STRATIFICOT: CT. ROWN FUS-MED GRAIN SAND SEAM (UP TO LEMA, THICK), RENSE, UNSATURATED, MOIST - cuttings indicate coarsening to well graded Hill-like unit -> Possibly SAND (TILL) Silty, gravelly (fn.gr) matrix. - Iriller indicates unit drills smooth and is very dense. Goal returns. INVESTIGATION KP 1-11 476 of 500

KNIGHT PIE CONSULTING	ESOLD LT ENGINEERS	D.	TE	EST	HOLE L	OG	TEST HOLE No. GW96-24/21 SHEET 3 of 4
PROJECT LOCATION OF DATE_BEGUN	<u>Mt</u> : A TEST H <u>Nov. 10/</u>	0//ey - 1 10LE 06DATE	FINISH	gical ED <u>N</u>	Unvestigation	PROJECT NO GROUND EL LOGGED BY	0. <u>/627.300</u>
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY % BLOWS/FOOT		DEPTH (m)	GRAPHIC LOG	DESCRIF	PTION AND CLASSI OF MATERIAL	FICATION
DRILLWELL - AIR ROTARY W/O WATER -57/8" & tricone bit -6" steel casing	SPT 	Dows not make much water while drilling. once drilling stopped for 10 minuts > 15 to 20 'of water in bottom of hole.	22.87 		- becomes fine some fine S moist to U low permea. SAND AND SILT fine grined with 1 to 2 m saturated silt thick fine to sand by r. V. -Last 3" SI fine gravel, moist. - cuttings retur fine gravel, moist. - cuttings retur fine gravel, moist. - cuttings retur fine gravel, moist. - cuttings retur fine gravel, moist. - cuttings retur for gravels with dir tier " by ers conternt. Wes (I.e. medium to to subrounded - sandy grave medium to cu % BO 2/. - thin silt (G - back to Glac coarse sand - trale cobbes at BO 2/min - water test	grained to Suravel, travel, trave chi ery moist, bro bility (Glaciolacusti sond and coarse medium grain Also contained medium grain ord stiff, howe LT (till-like) - massive, very s ned indicate con LT (till-like) - massive, very s contained sa alternating "Lea s due to varian coarse gravel) (, rounded to sul shed coarse fra Coarse gravel) (, rounded to sul prove gravel)	andy silt, andy silt, andy silt, andy silt, and silt grained silt ations of ad 140 3 cm and, saturated permeability sondy, trace stiff, gray, atinued and and and and aner and ble atines ction is rounded, Produces layor L - some 10%), ronthins aking water in 477 of 500

	KNIGHT PIE CONSULTING		D LTE).	TI	EST	HOLE L	OG TEST HOLE No. GW96-24/26 SHEET 4 of 4
	PROJECT LOCATION OF DATE BEGUN	<u>M-</u> TES <u>Nov.</u>	t. R. ST HO 10/90	//ey - '// DLE &DATE	FINISH	gical ED_	Vov. 17 196	PROJECT NO. /627.300 GROUND EL. LOGGED BY PJP
	NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	BLOWS/FOOT		DEPTH (m)	GRAPHIC LOG	DESCRIP	PTION AND CLASSIFICATION OF MATERIAL
	DRILLWELL - AIR ROTARY W/O WATER -57/8"\$ tricone bit -6"steel casing				36.0 		- continued (Coarse SANZ contains 100 - Lecoming le. cleaner way flow rates water test SILT (Basal gravel to gr cobbles, slight	Blociofluvial GRAVELS and S, water test -> 50-55 elimin ss fines (15%) and ler and higher water -> 200-225 elimin Till) - sandy, some avelly, true clay, rare Hy wasthered, moist
of so	Al.Im Nok: upon start up. No Water in bottom of hole		•		41.1		- beroming ve low pormos - continued gr ere multili - GRAVEL (west Coerse sand, Subrounded multilithic,	ry stiff to hard, moist, bility, massive, grey. rey till, gravel tragments thic, thered bedrock?) - some no fines matrix, clasts to angular and a not so generally clasts are
ci louir					5/.2 51.4 51.4		erosional re likely weather - making water	sistant gtz and cherts, red conglomerate. 2t 10-12 e/min
	BEDBOCK -notmaking any water			T.			Convolome RAT smooth drilling resistant quart intrusive.	E BEDROCK - Viry competent, closts composed of erosional 2, charles and occasional INVESTIGATION KP 1-11 478 of 500

KNIGHT PIE	SOLD LTD		TEST HOLE No.
CONSULTING	ENGINEERS	IEST	HOLE LOG GW96-34/3B SHEET / of 3
PROJECT LOCATION OF DATE_BEGUN	<u>Mt. Polley</u> TEST HOLE <u>Nov. 4 196</u>	(<u>- Hydro logical</u> (TSF) <u>38: N5818308</u> 38: N5818308 DATE FINISHED	Image: Construction PROJECT NO. 1627.300 8.97 E 575768.75 GROUND EL. 38: 912.06 6.52, E595765.16 GROUND EL. 38: 912.06 Nov. 9/96 LOGGED BY PJP
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY % BLOWS/FOOT	DEPTH (m) CRAPHIC LOG	DESCRIPTION AND CLASSIFICATION OF MATERIAL
DRILLWELL - AIR ROTARY WO WATER -57/8 & tricone bit -6" steel casing	-	0 - - - - - - - - - - - - - - - - - - -	SILT (FILL) - fill composed of silt till - sandy, some gravel (10-15%), some clay (10%), low prom, very moist, brown -fill is mixture of silt till and glaciolacustrine silt
52.	5PT 14"/18" 2 =78% 82 n= 12 20	4.95	SILT (Glaciolacustrine) - some clay, trace fine sand, weakly interbedded stiff to very stiff, low permeability, coarse silt - fine sand liminations, light grey to brown. - primarily coarse silt and trace very fine sand, stiff, saturated.
Note: 20min Wait, 2+03' of standing water in bottomot hole.		6.7 -	grey - prechminantly well graded sitt with up to some clay, 62% time sand, low permerbility.
8.2 m Note: Water at pond elevation in bottom of hole overnight.	5PT 241/ 6 241 97n= =100% 13)22 18	8.2	SILT (Glacio lacustrine) - some clay to clayey, very stiff, inegular ingues of slight composition change and color change, grey to grey- brown, moist, moderate plasticity, natural m/c >> PL.
I culture Plat a		9.8	- becoming SILT/CLAY (Glacio lacustrine laminated with rare to sond learne silt layors Imm.
0	-24"/ 8 137/n= -24" 19,32 =100% 22	11.6 - - - - - - - - - - - - - - - - - - -	-continued laminsted SILT and CLAY (1to 3mm) as above for 1st 12" -2nd 12" -> Coarse silt (sensitive) es quickens under viabration. Note: same unit as tested with CPT investigation earlier in year, saturated, groy, massive. - continued investigation the regulato of 300 Boue.

	KNIGHT PIE CONSULTING		D LTD		TE	EST	HOLE L	OG TEST HOLE No. GW 96-3A/3E
	PROJECT LOCATION OF DATE BEGUN	MT TES Nov	H R/ ST HO 1.4/96	ley - 1 LE DATE	FINISH	gical	Investigation Nov. 9/96	PROJECT NO. <u>/627.300</u> GROUND EL. LOGGED BY <u>PJP</u>
	NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	BLOWS/FOOT		DEPTH (m)	GRAPHIC LOG	DESCRIP	PTION AND CLASSIFICATION OF MATERIAL
	DRILLWELL - AIR ROTARY W/O WATER -57/8"\$ tricone bit -6" steel casing	24"/ - 24" = 100%	0 07n 15=1 4		14.7- - - - - 17.1 -		SILT (Glacio la primarily with Note: Low ble continement quickening o unit. (CPT d very stiff),	custrine) - coarse silt in true for sand, saturated, ow counts due to loss of and distur bruce causing f silt (non-ploctic) oto showed unit was grey, massive, saturated.
		20"/" = 21"	SPT 15 552n= 53308 60		17.5 -		returning win water, tuster, glaciotiuvist SAND (Glaciot medium to coo grey, medium SAND and SILT to some clay grivel up to - likely Basar - continued gre from 17.5 to	the workings as now generating the workings as now generating test - 50 to 60 elmin, likely sondy gravel unit. Twill) - dense to very dense, are greined, mossive, saturated, a to high permability. (TILL) - some gravel, troce well graved, very dense, well graved, very dense, to well graved, very dense, " well graved, very dense, " Till, no water produced. " very dense Basal till 19.8 m.
I CAUL Piel s 1		10"/10" = 100 %	23 80/4* 75		23.6 -		- becoming rea to be due to volconic com up in till SILT and SAN Very dense, mos - occasionol	d brown at times believed drilling through red-brown glamerate clast caught whit. when (TILL) - continued, sive, low permeability. cobbles to 25.
7	25 m Note: Approx. 10m of water in Lotlom of hole overnight				25 -		- becoming st silty some robbles, gre low permes 25m to 35m ront'd to grey	ightly more gravelly, d, true clay, likely continued y to red-brown, massive, billity likely, moist

KNIGHT PIE	5010						TEST HOLE No.
CONSULTING	ENGIN	EERS		11	EST	HOLE L	OG <u>GW96-34/38</u> SHEET 3 of 3
PROJECT LOCATION OF DATE_BEGUN	M7 TES Nov	<u>F Po</u> ST H(A /9	//ey - DLE 6DAT	Hydro lo TE FINISH	gical ED	Investigation Nov. 9/96	PROJECT NO. <u>/627.300</u> GROUND EL LOGGED BY <u>PJP</u>
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	BLOWS/FOOT		DEPTH (m)	GRAPHIC LOG	DESCRIP	PTION AND CLASSIFICATION OF MATERIAL
DRILLWELL - AIR ROTARY W/O WATER -57/8" & tricone bit -6" steel casing Note: Contact between till and bedrock is dry. Weit 20 minutes but no water, drilled dry to desty w occessional damp Zones.				35 		Volconiclestic "fragments" of sediment con drilled with -rock chips gu return dust -possible fram moterial con and damp EOH (1804 -wait 20 mi of hole. -Pull rods and in bottom o	Conglomerate-(Bedrock) - hematically altered weathend aprised of vokanic clasts, tricane bit a soft enerally damp to day with Vine (wet) zone as mes out as clumps for 0.5 to 1.0 m. (t) invks, no water in bottom remeasure - 1' of water of hole.
·							INVESTIGATION KP 1-11 481 of 500

KNIGHT PIE CONSULTING	SOLD LTD. ENGINEERS	TEST	HOLE LOG
PROJECT LOCATION OF DATE_BEGUN	Mt: Polley TEST HOLE(Nov. 18/96	- Hydro logical TSF) 4A: N5818164.50 4B: N5918162.83 DATE FINISHED M	Investigation PROJECT NO. 1627.300 A. E595147.98 GROUND EL. 48: 240.56 K.E595151.26 GROUND EL. 48: 240.46 Vov. 20/96 LOGGED BY PJP
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY % BLOWS/FOOT	DEPTH (m) GRAPHIC LOG	DESCRIPTION AND CLASSIFICATION OF MATERIAL
DRILLWELL - AIR ROTARY W/O WATER -57/8"\$ tricone bit -6" steel casing		0	SAND (TILL) - gravelly, some silt to silty, trace clay, very dense, well graded, low permeability, moist, medium brown. -(Ablation till)
45 m Weited Zominuts, Water at 10' below grade.		4.5	SAND (Glaciofluvial) - some gravel to gravelly, trace silt (10%), dense, clasts rounded to subrounded, saturated, moderate permeability, cohesionless, grey - brown - becoming slightly cleaner (less finos) and still saturated but not making any water.
I cul Plat = .		7.0 -	SAND (TILL) - silty, some gravel, trace clay, rare cobbles, very dense, well graded, low permeability, moist, grey-brown.
Not: 20' of water in bottom of hole overnight.		9.8	Volcanic lastic Conglomerate (Bedrock) - fragments of hematically altered volcanic in sediment matrix, red-brown, hard, dry. No observable facture Zones. - making dribble of water INVESTIGATION KP 1-11 482 of 500 EDH

KNIGHT PIE	LTD.		TEST HOLE LOG TEST HOLE NO. GW96-54/56						
PROJECT LOCATION OF DATE_BEGUN	M- TES Nov.	- Polle T HOLI 21/96	<u>γ - ΄Η</u> (<i>TSF</i>) DATE	<u>- Hydrological Investigation</u> PROJECT NO. 1627.30 <u>SF) 54: N5819626.68, E594330.34</u> GROUND EL. 58: 973.44 ATE FINISHED LOGGED BY PJP					
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY %	BLOWS/FOOT		DEPTH (m)	CRAPHIC LOG	DESCRIP	TION AND CLASSIFICATION OF MATERIAL		
DRILLWELL - AIR ROTARY W/O WATER -57/8" & tricone bit -6" steel casing	-			2.1		SILT (Ablat gravel and a well graded, to seturated - becoming Very mois	ion Till) - sandy, some clay, stiff, modently low permeability, wet d, dark brown. very stiff, moist to st, light to madium brown.		
No worker genersted in overburden or bedrock during drilling.				4.9		- hit 0.6m	ø boukkr		
Noto: 5.5m:left for I week, woter at surface upon re-startup.	-			6.0 -		- beroming g	revelly and dense		
	-			6.7 -		- becoming and grey and no	Very dense, moist 1, still low permesbility water generated		
101/ *at sec	-			-			ικ.		
ă			3	10.9		SYENITE INTI COARSE grained -no observab	RUSIVE (Bedrock) - to promotitic, massive, ble fractures, dry to damp		
1 1	-		2	- 15.2		-nirrow zone for 1m, u	INVESTIGATION KP 1-11 483 of 500		
				25.5		EOH			

					-	,				
1	KNIGHT PIE CONSULTING).	TEST HOLE LOG							
and the second se	PROJECT LOCATION OF DATE_BEGUN	M- TES	H B T HO 30/	1/ey DLE (1 96 D	- Hydrological Investigation PROJECT NO. 1627.300 <u>1/1/site)-N5822851.66,6593659.21</u> GROUND EL. 1058.53 ATE FINISHED Oct. 31/96 LOGGED BY PJP					
	NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	BLOWS/FOOT			DEPTH (m)	GRAPHIC LOG	DESCRIP	PTION AND CLASSIFICATION OF MATERIAL		
CUD MIC (CUD/MC/ Plat secie tant	etc. DRILLWELL - AIR ROTARY W/O WATER -57/8" & tricone bit -6" steel casing	REC REPART REPARTS REPARTS REPARTS REPARTS	BLU			0 	GRA	Intermediate Intermediate In grained, braits grick, drills grick, dry; dustif - becoming sl to micro di epidote + k relatively & produced - let hole st upon restar bottom of - trece pyrin for 1 m or continued. - let hole : upon start initially - continued Intrusive, observed. - becoming h	Volcenic (Bedrock)- dark grey, andesite to repidate atteration, IY, mederatily compatient, no indication of water lightly coasser grained locitle composition, spar alteration, day, massive, no water and for 20 minutes, t, 2ft of water in hole, le and minor chalopyrite aly, no water a dusty stand for 20 minutes, ty, no water a dusty stand for 20 minutes, ty, no water a dusty stand for 20 minutes, introdiorite tight, no fractures water to drill ar produced during drilling.	
	e=			£		43.8		EOH	INVESTIGATION KP 1-11 484 of 500	

KNIGHT PIESO	OLD LTD. GINEERS	TE	ST	HOLE L	OG TEST HOLE No. GW96-7 SHEET / of /		
PROJECT LOCATION OF T DATE_BEGUN	MT: B//ey EST HOLE(Vov.7/96	- Hydrological Investigation PROJECT NO. 162 Ailleite): N5821520.53, E592983.23 GROUND EL. 1021. ATE FINISHED Nov.7/96 LOGGED BY R					
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	BLOWS/FOOT	DEPTH (m)	GRAPHIC LOG	DESCRIP	TION AND CLASSIFICATION OF MATERIAL		
DRILLWELL - AIR ROTARY W/O WATER -57/8"\$ tricone bit -6"stee/casing		0		SILT (TILL) End clay, de low permea moist, brow Diorite (Bedr microchorite o vokinic (inte and colcite alterition?, - begins man - water \$st - becoming la fault gaug water product - large fragmen Calcite stri - still product - hole cavin EOH (51')	- Sendy, some gravel nse to very dense, massive, bility, moist to very mediste, moist to very mediste) - epidole magnetite attered, wesk chlorite tractored and worthand king water at 5 to 10.2/min at 16 2 /min highly tractured with grey e returns in water, weed et 19 2 /min. ents of rock breaking g pocket inside hole. ts cantain numerous ingers - fault zone. wing water g in.		

	KNIGHT PIE CONSULTING).	TEST HOLE LOG							
-	PROJECT LOCATION OF DATE BEGUN	M- TES Nov.	<u>F</u> BT HO 1/96	Iley DLE(Mil	- Hydrological Investigation PROJECT NO. 1627.30 16:10 08: N582 2468.46, E 59 1861.59 16:10 08: N582 2469.40, E 59 1869.31 ATE FINISHED LOGGED BY PJP					0. 1627.300 84: 1050.10 85: 1050.00 PJP
	NOTES Vater loss, type and size of hole, drilling method, proundwater level, etc.					DEPTH (m)	GRAPHIC LOG	DESCRIP	TION AND CLASSIF OF MATERIAL	FICATION
	DRILLWELL - AIR ROTARY WO WATER -57/8" & tricone bit -6" steel casing							SILT (FILL) - Sandy silt + stift, wet pull-out to trace organic permeabili SILT and SAN Clay, trace co low permea water, brow - becoming moist + - becoming GRAVEL (GIBCIC Subrounded co but not proc	fill composed fill with some to saturated, to road const s mixed in, ty. ID (TILL) - gro obsles, very m bility, not p dense to very b very mois kery dense and tosts, very m dense to very bility dense and	of reworked gravel, fill formerly ruction, gret, low ouelly, some noist, noducing dense, t, d moist. Y, dense, bist to wet high remeshility
Change (20) part 100						- -		-> let stand 5ft of u hole. Diorite (Bedro m>ssive, some chlorite alter -> begins to - becomes muc continues to - hit frecture now produce - continuing in flow rates to u EOH	tor 20 minu tor 20 minu motor in bor ck) - medium g what westing make 152/m h harder to o produce 152, d zone (softer 5 60 to 70 2 / fracture Zone EOH. INVESTIGATION KP 1	In primera in Ty. the and them of them of the them of the them of the theta the the the the the theta the

KNIGHT PIE CONSULTING	ESOLD LTD.	TES	T HOLE LOG	HOLE No. 196-9
PROJECT LOCATION OF DATE BEGUN	Mt. Polle TEST HOL Nov. 21/96	Y - Hydrologic TSF: N5818277. DATE FINISHED	Nov. 21/26 LOGGED BY	627.300 6.18 PJP
NOTES Water loss, type and size of hole, drilling method, groundwater level, etc.	CORE RECOVERY % BLOWS/FOOT	DEPTH (m) GRAPHIC LOG	DESCRIPTION AND CLASSIFICATION OF MATERIAL	DN N
DRILLWELL - AIR ROTARY W/O WATER -57/8 \$ tricone bit -6"stee/casing		5.1	SILT (TILL) - Sandy, Some grav and clay, trace cobbins, stift to very stiff, low permession will graded, very moist to grey to brown - becoming very stift and mo to very moist SAND (Glacioflouial) - fine grave, trac silt, moderate permeability, grey - brown. - contains alternating more gr rich layers 0.2 to 0.3m this - producing only dribble of wate with saturated cuttings. SILT (Glaciolacustrine) - layer silt with lesser thin fn sa and silt laminations, as well silt d clay layers, appras into stift to very stift, low per grey, moist to very moist. EOH	ed ed soturated ravel k. ravel k. ravel k. ravel soturated mod as ravel f 500

Knight Piésold Ltd. CONSULTING ENGINEERS

ł

APPENDIX B

GROUNDWATER MONITORING WELL COMPLETION DETAILS



Association des Ingénieurs-Conseils du Canada

INVESTIGATION KP 1-11 488 of 500





- tremmie pipe.
- 2. Depths shown from surface in metres.







- tremmie pipe.
- 2. Depths shown from surface in metres,













