

# FINAL REPORT

PREPARED FOR THE BC MINISTRY OF HIGHWAYS AND INFRASTRUCTURE

# HIGHWAY 1 CORRIDOR WIDENING (216 Street to 264 Street) & TRUCK PARKING AREA

**BUSINESS CASE** 

February 2017



# **Executive Summary**

Highway 1 is the primary east-west corridor serving and connecting the Lower Mainland to the rest of British Columbia and Canada. Between the Cassiar Tunnel and 216 Street, the Ministry of Transportation and Infrastructure (MoTI) invested in widening Highway 1 and replacing the Port Mann Bridge. East of the Bridge, the highway generally supports three travel lanes in each direction through to the soon to be constructed 216 Street interchange. East of 216 Street, Highway 1 is four travel lanes with the exception of the segment between 232 Street (Highway 10) and 264 Street (Highway 13) interchanges where there is a third eastbound lane.

Several segments of Highway 1 east of 216 Street currently operate at the lower end of acceptable service levels for a major highway facility during the weekday peak periods and the peak periods on the weekends. Some sections experience lower than free flow speeds, relatively high vehicle density, limited freedom to maneuver, and nonrecurring congestion resulting from minor incidents / disruptions in the traffic stream. In the short and long term future, the majority of this section of highway is projected to have insufficient capacity to meet the forecasted travel demands. These mobility, safety and reliability issues affect provincial travel between Lower Mainland communities and the rest of the province and impact the movement of goods and services.

In support of accommodating the movement of people, goods and services in British Columbia, the provincial government's BC On the Move - 10 Year Transportation Plan identified the commitment to improve highway capacity and reliability with the widening of Highway 1 between Langley and Abbotsford. Consistent with this priority, BC On the Move also identified a commitment to work with industry to identify and construct at least two new truck parking areas nearby key highway corridors in the Lower Mainland. Truck parking facilities support mobility and reliability investments on BC's highways by providing convenient and accessible areas to enable commercial vehicles to park and access appropriate amenities.

This Business Case describes the key issues and challenges on the Highway 1 corridor segment between 216 Street in Langley and Highway 11 in Abbotsford as well as the difficulties the trucking industry faces accessing truck parking and impacts on the network and environment. The options considered and recommendations for the initial stages of investment in widening Highway 1 (216 Street to 264 Street) and truck parking areas (off Highway 17 east of the Port Mann Bridge in the City of Surrey) to support BC On the Move are described.

The Highway 1 widening issues, options and recommendations were identified in a report prepared by Parsons and attached to this Business Case - Highway 1 Widening (216 Street to Highway 11) Business Case. The recommended truck parking facility reviewed by Stantec included an assessment of alternative truck parking locations near the Highway 1 corridor in the north Surrey and Langley areas. The content from the former document and reviews are slightly modified and incorporated into this overall Business Case.

### **Problem Definition**

Between 216 Street and Highway 11, several segments on Highway 1 currently operate with moderate delays (or levels of service) during both weekday and weekend peak periods. These problematic highway



segments are characterized by lower than free flow speeds, relatively high vehicle density, limited freedom to maneuver, and nonrecurring congestion resulting from minor incidents / disruptions in the traffic stream. In the short and long term future, the majority of this section of highway is projected to have insufficient capacity to meet the forecasted travel demands.

Additionally, this section of Highway 1 has a collision rate that is higher than the average for similar facilities around the province. In addition to the direct collision costs are significant delay costs that occur when the highway lanes are blocked due to an incident. With approximately 180 collisions reported to police every year, this means there is a reportable collision every two days along this section of the Highway 1 corridor.

In addition to the mobility and reliability challenges through this section of Highway 1, most structures along the corridor do not meet current clearance standards of 5.0m for large structures and 5.5m for lightweight structures. In particular, those structures which are at risk of impact include the Glover Road underpass (4.46m); Roberts Bank Rail Corridor underpass Tunnel portals (4.4m); 232 Street underpass (4.62m); 264 Street underpass (4.6m); and Peardonville Road underpass (4.92m). Further, the design of the 232 Street and 264 Street interchanges with Highway 1 are no longer considered best practices. With increasing highway traffic as well as those entering and leaving the corridor, the existing configurations contribute to short weaving and merging distances which in turn will reduce safety in the long-term.

With a growing economy and trade across British Columbia, and with other provinces, the United States and Asia Pacific Gateway regions, the Highway 1 corridor and connecting roadways are moving larger volumes of goods and services. Although investments are being made in the highway network, trucks delivering goods to and from the Lower Mainland are unable to find adequate daytime and overnight parking (Stantec estimates indicate that 35 truck parking facilities supply 2,700 heavy truck parking stalls in Surrey). Within the City of Surrey and other nearby communities south of the Fraser River, there is very little overnight parking available for trucks and residential street restrictions prohibit truck parking. The result is that truck drivers must spend significant time and expense searching for available parking which in turn impacts mobility and congestion on the Lower Mainland highway and municipal street system and increases the potential for collisions and vehicle emissions with increasing volumes. Through work undertaken by the City of Surrey, it was estimated that an additional 2,000 parking stalls are required to meet truck demands within the community.

### Improvement Possibilities Considered

As part of the Highway 1 widening, the median area is generally wide enough across the corridor to provide the additional eastbound and westbound lanes. Beyond that, the method of widening for either general purpose traffic or high-occupant vehicles (HOVs) were considered. The fundamental consideration was the safety and efficiency for the transitions at either end. The study considered 4 options:

- 1. One new general purpose lane in each direction between 202 and Highway 11;
- 2. One new HOV lane in each direction between 202 and Highway 11;
- 3. s.13
- 4. One new general purpose lane in each direction between Glover Road and Highway 11, and extend existing HOV lanes to Highway 10;



Considering highway usage, capacity and operational performance s.13,s.17 s.13,s.17

The truck parking review considered 13 potential sites within Surrey as well as others in adjacent municipalities as illustrated in **Figure ES-0.1**. Pre-screening was completed to filter the sites down to the top four areas identifying three sites for further option analysis.

Figure ES-0.1 – Candidate Truck Parking Sites

s.13.s.17

Source: Stantec Consulting

### **Recommended Improvements**

At this stage, the Ministry has worked with the City of Surrey and Township of Langley on the Highway 1 widening and truck parking facility requirements and potential partnerships for investing in each project. Assuming suitable cost sharing arrangements and affordability, the Highway 1 widening and area improvements could extend from east of the soon to be built 216 Street interchange to the 264 Street interchange. This would include the following sequence of improvements as summarized below:

 232 Street Interchange which involves reconfiguring the existing 232 Street Interchange and replacing the existing underpass structure as well as constructing a new 72 Avenue underpass structure.



- 2.1 km widening between the recently constructed interchange at 216 Street and the 232 Street Interchange as previously described. This widening would involve the removal and construction of a new CP Rail crossing and Glover Road overpass structures.
- Widening in the westbound direction for approximately 5.8km between 264 Street to 232 Street. Three eastbound general purpose lanes are already provided between 232 Street and 264 Street. No new structures or modifications to existing structures are required as part of this project.

The limits of the widening in both the eastbound and westbound directions are illustrated in Figure ES-0.2. Beyond these project limits, the Ministry will widen Highway 1 from four to six lanes in both directions through to Highway 11 as financial resources become available in future.

Conceptual cost estimates have been prepared by Parsons for all Highway 1 six laning project components. The above capital improvements are estimated at \$205.5 M (Class C). All improvements are to take place on lands that are provincially owned.

Figure ES-0.2: Project Limits for Highway 1 Widening & Area Improvements

s.13,s.17

s.13,s.17

s.13.s.1/

The site illustrated below in Figure ES-0.3 would support 158 pull through truck and 44 passenger vehicle parking stalls. The site would also be connected to Highway 17 through a new full movement intersection with left turn and right turn lanes. A protected-T partial signal at the truck parking access would signalize the westbound approach while the eastbound through movement would remain unsignalized.



Class D cost estimates have been prepared by Stantec for all Truck Parking facility and related improvements. The above capital improvements are estimated at \$29.9M. The project will require the s.13,s.17



### **Multiple Account Evaluation Highlights**

**Table ES-0.1** provides a Multiple Account Evaluation summary of Highway 1 Six Laning Improvements as well as an assessment of the Highway 17 Truck Parking Facility. Projects are assessed over a 25 year term. A 6% discount rate is assumed.

Widening Highway 1 between the new 216 Street interchange and the 264 Street interchange, including a full interchange reconfiguration at 232 St and all associated overpass improvements, results in a **Net Present Value of \$32.6 M and a benefit/cost ratio of 1.2**, which is considered very impressive due to the overall scale of the project. The project will improve mobility and safety performance along the corridor and update clearance standards at the Glover Road, CP Rail, and 232 Street underpasses. The project is anticipated to result in significant GHG reduction benefits as a result of improved operating conditions and modest sustainable transportation benefits because the improvements incorporate a 6 km extension of the s.13

The project directly aligns with the stated *BC on the Move* priority to six lane Highway 1 between from Langley to Abbotsford.

Constructing the proposed truck parking facility \$.13,s.17

results in a Net

**Present Value of \$2.6 M and a benefit/cost ratio of 1.1.** The project will provide 158 additional truck parking spaces, modestly reducing incidence of illegal parking in North Surrey. The project is anticipated to result in modest GHG reduction benefits resulting from fewer trucks travelling further distances in search of parking. The project directly aligns with the stated *BC on the Move* priority to construct at least two new truck parking areas in the Lower Mainland.

The project as a whole is anticipated to result in GHG benefits resulting from a reduction in vehicle idling on Highway 1 and overall truck travel related to searching for parking. MoTI Responses to Infrastructure Canada Annex D – Environmental and Aboriginal Consultation Information Requirements as it pertains to Highway 1 six laning is included in Appendix C of the original Parsons *Highway 1 Widening (216 Street to Highway 11) Business Case* found in **Appendix A** of this report. MoTI Responses to Infrastructure Canada Annex D as it relates to the truck parking facility is included in **Appendix B** of this report.



Table ES-0.1: Multiple Account Evaluation Summary

	Highway 1 Widening & Overpass/Interchange Improvements <sup>(1)</sup>	Truck Parking Facility (Highway 17 east of Por Mann Bridge) <sup>(2)</sup>
FINANCIAL ACCOUNT		
PV Revenue	-	\$4.4 M
PV Expenses	-	-\$4.4 M
Capital Cost	\$205.5 M	\$29.9 M
Property Cost		\$0.1 M
Capital Cost (PV)	\$179.5 M	\$27.0 M
Property Cost (PV)		s.13,s.17
Maintenance (PV)	\$2.0 M	\$0.3 M
Salvage Value (PV)	-\$24.3 M	-\$1.6 M
Total Incremental Cost	s.13,s.17	
CUSTOMER SERVICE ACCOUNT		
Travel Time Savings (PV)	\$172.2 M	\$23.8 M
Vehicle Operating Savings (PV)	\$11.1 M	\$7.0 M
Hwy 17 / Truck Access Signal Travel Time Costs (PV)		-\$2.2 M
Hwy 17 / Truck Access Signal Veh. Operating Costs (PV)		-\$0.2 M
Safety (PV)	\$6.5 M	N/A
Total Incremental Benefits (PV)	\$189.8 M	\$28.4 M
SOCIAL/COMMUNITY ACCOUNT		
Noise and Visual Impacts	•	0
Community Displacement	•	0
Community Severance	•	0
Reduction in Illegal Truck Parking	N/A	•
Sustainable Transportation	•	0
Consistency with Provincial Plans	•	•
ENVIRONMENTAL ACCOUNT		
Terrestrial	0	Unknown
Aquatic	0	•
Archaeological / Historical	0	Unknown
GHG Reduction	<u> </u>	4
KEY ECONOMIC INDICATORS	•	
Net Present Value	\$32.6	\$2.6 M
Benefit-Cost	1.2	1.1
<ol> <li>MAE evaluation from the Highway 1 Widening (216 Street assessment extrapolated from the 15 year evaluation pro</li> <li>MAE evaluation from Stantec assessment of the proposed</li> </ol>	vided in background business case	(including Class C estimates).

<sup>•</sup> 0 Significant Benefit Modest Impact Significant Impact Modest Benefit Neutral



### **Cost Sharing and Cash Flow Options**

The proposed improvements will be delivered by BC MoTI through Traditional Competitive Tendering and will be completed by way of a Major Works Contract set out by MoTI. Today, the Highway 1 widening and truck parking area have been developed to a conceptual level of design. The functional designs for each would begin in 2017-18, and the delivery for the truck parking area would be substantially complete by the end of fiscal 2019-20, and by 2021-22 for the Highway 1 widening project as highlighted in **Table ES-0.2**.

2017 - 18 | 2018 - 19 2019 - 20 2020 - 21 2021 - 22 Activity **Truck Parking** Project Design and Surveying **Environmental Assessment** Construction Permit Tender Start of on-site Construction Substantial Completion **Project Completion** Final Report Highway 1 Project Design and Surveying **Environmental Assessment Construction Permit** Tender Start of on-site Construction **Substantial Completion Project Completion** Final Report

Table ES-0.2: Estimated Project Schedule by Fiscal Year

The proposed improvements for the 232 Street interchange is expected to have significant municipal benefits in addition to the highway. Consistent with previous discussions with local agencies, the Township of Langley will be requested to funds.13,s.17 of the project costs. **Table ES-0.3** below summarizes the allocations between agencies assuming s.13, federal contributions toward eligible costs for the Highway 1 improvements (s.13, for the 232 Street interchange) and truck parking facility. **Table ES-0.4** summarizes the anticipated cash flow for each item and agency based on the delivery timeframe.



Table ES-0.3: Cost Allocations by Project Segment and Eligibility

Costs		Truck Parking		Highway 1 - 232nd Street Interchange	2	Highway 1 - 16th Street to 232nd Street Widening	۷	Highway 1 - Videning WB East of 248 erpass to 72nd Overpass	Highway 1 - Widening WB East 264th St Overpass to East of 248 St Overpass		Highway 1 Total Only		Highway 1 & Parking Area Total	
A: Non-Eligible Costs														
Pre-development Activities	\$	718,000	\$	636,000	\$	636,000	\$	159,000	\$	159,000	\$	1,590,000	\$	2,308,000
Property Acquisition	\$	s.13,s	\$	-									\$	s.13,s
Administration & Other	\$	3,352,000	\$	5,214,000	\$	4,694,000	\$	1,271,000	\$	660,000	\$	11,839,000	\$	15,191,000
Non-Eligible Costs Sub-Total	\$	s.13,s.	\$	5,850,000	\$	5,330,000	\$	1,430,000	\$	819,000	\$	13,429,000	\$	s.13,s.1
B: Eligible Costs														
Construction	\$	20,160,000	\$	55,500,000	\$	54,100,000	\$	13,287,000	\$	7,757,000	\$	130,644,000	\$	150,804,000
Engineering	\$	2,500,000	\$	6,500,000	\$	5,900,000	\$	1,800,000	\$	1,000,000	\$	15,200,000	\$	17,700,000
Environmental Mitigation	\$	700,000	\$								\$	-	\$	700,000
First Nations Consultation	\$	350,000		800,000		800,000		600,000		300,000		2,500,000		2,850,000
Contingency		2,120,000		18,600,000		18,000,000	\$	4,526,100	\$	2,627,000	_	43,753,100		45,873,100
Eligible Costs Sub-Total	_	25,830,000	_	81,400,000	_	78,800,000	_	20,213,100	_		_	192,097,100		217,927,100
Project Total	\$	30,000,000	\$	87,250,000	\$	84,130,000	\$	21,643,100	\$	12,503,000	\$	205,526,100	\$	235,526,100
Level of Contribution														

s.13,s.17

Table ES-0.4: Project Cash Flow by Fiscal Year

Costs	Previous Expenditures	2	2017 / 2018	2018 / 2019		2019/2020			2020 / 2021	20	21 / 2022	TOTAL ALLOCATIONS		
A: Non-Eligible Costs														
Pre-development Activities	\$ 2,138,000	\$	85,000	\$	85,000	\$			-	\$	-	\$	2,308,000	
Property Acquisition	\$ -	\$	s.13,s.	\$		\$		9	-	\$	-	\$	s.13,s.	
Administration & Other	\$ -	\$		\$	1,713,200	\$	4,751,400	\$	6,076,400	\$	2,650,000	\$	15,191,000	
Non-Eligible Costs Sub-Total	\$ 2,138,000	\$	s.13,s.	\$	1,798,200	\$	4,751,400	\$	6,076,400	\$	2,650,000	\$	s.13,s.1	
B: Eligible Costs														
Construction	\$ -	\$		\$	30,264,000	\$	60,321,600	\$	45,189,600	\$	15,028,800	\$	150,804,000	
Engineering	\$ -	\$	2,700,000	\$	5,310,000	\$	5,310,000	\$	3,510,000	\$	870,000	\$	17,700,000	
Environmental Mitigation	\$ -	\$		\$	350,000	\$	350,000		-	\$	-	\$	700,000	
First Nations Consultation	\$ -	\$	460,000	\$	910,000	\$	570,000	\$	570,000	\$	340,000	\$	2,850,000	
Contingency	\$ -	\$	2,072,000	\$	8,731,310	\$	13,761,930	\$	13,761,930	\$	7,545,930	\$	45,873,100	
Eligible Costs Sub-Total	\$ -	\$	5,232,000	\$	45,565,310	\$	80,313,530	\$	63,031,530	\$	23,784,730	\$	217,927,100	
Project Total	\$ 2,138,000	\$	5,417,000	\$	47,363,510	\$	85,064,930	\$	69,107,930	\$	26,434,730	\$	235,526,100	
Level of Contribution														

s.13,s.17



# **Table of Contents**

Exec	cutive Summary	
1.0	Introduction	1
2.0	Summary of Existing Conditions	3
	2.1 Highway 1	3
	2.2 Truck Parking	8
3.0	Concept Development & Cost Estimates	11
	3.1 Highway 1	11
	3.2 Truck Parking	19
4.0	Multiple Account Evaluation	25
	4.1 Financial Account	25
	4.2 Customer Service Account	27
	4.3 Social/Community Account	29
	4.4 Environmental Account	31
	4.5 Multiple Account Evaluation Summary	32
5.0	Sensitivity Analysis	35
	5.1 Discount Rates	35
	5.2 Project Cost Estimates	36
6.0	Potential Risks	39
7.0	Advancement of Provincial & Federal Transportation Strategies and Plans	41
8.0	Corridor Performance Measures	43
9.0	Project Implementation and Recommendations	45

# **Appendices**

Appendix A Highway 1 Widening (216 Street to Highway 11) Business Case (Parsons, 2016)

Appendix B Annex D – Environnemental and Aboriginal Consultation Information Requirements (Truck

Parking Facility)

Appendix C Highway 17 / Truck Access Synchro / SimTraffic Reports

This report is prepared for the sole use of BC Ministry of Transportation and Infrastructure. No representations of any kind are made by Urban Systems Ltd. or its employees to any party with whom Urban Systems Ltd. does not have a contract. Copyright 2017.



# 1.0 Introduction

Highway 1 is the primary east-west corridor serving and connecting the Lower Mainland to the rest of British Columbia and Canada. Between the Cassiar Tunnel and 216th Street, the Ministry of Transportation and Infrastructure (MoTI) invested in widening Highway 1 and replacing the Port Mann Bridge. East of the Bridge, the highway generally supports three travel lanes in each direction through to the soon to be constructed 216th Street interchange. East of 216 Street, Highway 1 is four travel lanes with the exception of the segment between 232 Street (Highway 10) and 264 Street (Highway 13) interchanges where there is a third eastbound lane.

Several segments of Highway 1 east of 216 Street currently operate at the lower end of acceptable service levels for a major highway facility during the weekday peak periods and the peak periods on the weekends. Some sections experience lower recurring as well as non-recurring delays and congestion resulting from minor incidents / disruptions in the traffic stream. In the short and long term future, the majority of this section of highway is projected to have insufficient capacity to meet the forecasted travel demands. These mobility, safety and reliability issues affect provincial travel between Lower Mainland communities and the rest of the province and impact the movement of goods and services.

In support of accommodating the movement of people, goods and services in British Columbia, the provincial government's BC On the Move - 10 Year Transportation Plan identified the commitment to improve highway capacity and reliability with the widening of Highway 1 between Langley and Abbotsford. Consistent with this priority, BC On the Move also identified a commitment to work with industry to identify and construct at least two new truck parking areas nearby key highway corridors in the Lower Mainland. Truck parking facilities support mobility and reliability investments on BC's highways by providing convenient and accessible areas to enable commercial vehicles to park and access appropriate amenities.

This Business Case describes the key issues and challenges on the Highway 1 corridor segment between 216 Street in Langley and Highway 11 in Abbotsford as well as the difficulties the trucking industry faces accessing truck parking and impacts on the network and environment. The options considered and recommendations for the initial stages of investment in widening Highway 1 (216 Street to 264 Street) and truck parking areas (off Highway 17 east of the Port Mann Bridge in the City of Surrey) to support BC On the Move are described.

The Highway 1 widening issues, options and recommendations were identified in a report prepared by Parsons and attached to this Business Case in Appendix A - Highway 1 Widening (216 Street to Highway 11) Business Case. The recommended truck parking facility reviewed by Stantec included an assessment of alternative truck parking locations near the Highway 1 corridor in the north Surrey and Langley areas. The content from the former document and reviews are slightly modified and incorporated into this overall Business Case.





# 2.0 Summary of Existing Conditions

# 2.1 Highway 1


### **Mobility Highlights**

Highway 1 between 216 Street and 264 Street services approximately 80,000 vehicles per day, including over 9,500 trucks, which make up about 12% of total corridor traffic. Approximately 430,000 truck hours are spent travelling the corridor each year, equalling about \$50M in truck travel and operating costs annually. The corridor has historically experienced continual but gradual growth, with compound annual growth rates in annual average daily traffic (AADT) near 1.2% per year.

Today, average travel speeds and times across Highway 1 east of the Port Mann Bridge through to the Vedder Canal are generally consistent for much of the day at median speeds around 100 km/h, with slight variances in the morning and afternoon peak period directions as summarized below in **Figure 2.1.** 

Hour Beginning

Figure 2.1: Highway 1 (152 Street to Vedder Canal) 2015 EB and WB Median Travel Speeds



Source: 2015 Lower Mainland Highway Assessment, Urban Systems

During the morning peak hour when the westbound direction accommodates approximately 2,700 vehicles per hour or about 1,350 vehicles per lane, westbound average travel speeds operate below the posted speed and are most variable between Highway 13 and 200<sup>th</sup> Street as illustrated in **Figure 2.2** below. Noticeable drops in median speed are observed near the Highway 13 and Highway 10 interchanges. These drops correspond with wider ranges of speed variability.

During the afternoon peak hour when the eastbound direction accommodates approximately 3,600 vehicles per hour or about 1,800 vehicles per lane, travel speeds are well below the posted speed east of 200 Street through to almost Mount Lehman Interchange in Abbotsford as illustrated below in **Figure 2.2.** As indicated, median travel speeds on the corridor decline to almost 40km/hr at the merge point east of 202 Street and to 80 km/h near the Highway 13 interchange. The corridor experiences significant levels of speed variability

<sup>&</sup>lt;sup>1</sup> 2015 annualized statistics at traffic count station P-17-4EW (Hwy 1, E of Bradner Road)



in the PM peak extending back 2.5 km from the HOV merge point east of 202 Street and separately near the Highway 13 interchange.





Figure 2.2: Highway 1 (152 Street to Vedder Canal) 2015 Peak Direction Median and Variable Speeds



Source: 2015 Lower Mainland Highway Assessment, Urban Systems

As summarized in the *Highway 1 Widening (216 Street to Highway 11) Business Case (2016)*, a number of highway segments along the section of Highway 1 between 216 Street and Highway 11 currently operate at the lower end of acceptable service levels for a major highway facility during the weekday peak periods and the peak periods on the weekends. These problematic highway segments are characterized by lower than free flow speeds, relatively high vehicle density, limited freedom to maneuver, and nonrecurring congestion resulting from minor incidents / disruptions in the traffic stream. In the short and long term future, the majority of this section of highway is projected to have insufficient capacity to meet the forecasted travel demands.



**Figure 2.3** displays the observed relationship of traffic volumes to highway speeds on Lower Mainland freeways as gathered at MoTI permanent and short count sites in 2014. Speeds begin to be affected by traffic volumes at around 1,400 vehicles per lane per hour, though impacts are relatively minor until volumes approach 1,700-1,800 vehicles per lane per hour. Above this threshold, additional volume pressure results in flow breakdown and a steep reduction of travel speeds (i.e. congestion).

Currently, peak directional traffic volumes along the segment are near or at the theoretical maximum for limited access freeways. If traffic volumes continue to grow at the established historic compound growth rate of 1.2% per year, AM and PM peak directional volumes will approach 1,950 and 2,600 vehicles per hour per lane at the end of the planning horizon, respectively. These volumes significantly exceed theoretical maximums and will likely result in dramatic reductions in travel speeds along the corridor.




Figure 2.3: Volume / Speed Relationship on Limited Access BC Highways

### **Safety Overview**

Highway 1 between 216 Street and Highway 11 has a collision rate that is higher than the average for similar facilities around the province. Figure 2.4 illustrates the historical collision rates on Highway 1 per 1 km LKI segment. While most corridor segments fall below or within range of the critical collision rate, eastbound and westbound Highway 1 near the Highway 10, Highway 13, and Mount Lehman Road interchanges experience collision rates greater than 10% above critical rates.




Figure 2.4 - Historical Collision Rates (2009-2012)

Source: 2015 Lower Mainland Highway Assessment, Urban Systems



While most collision prone segments experience collision severities below or within the range of provincial averages, as displayed in **Figure 2.5**, the collision prone segments of Eastbound Highway 1 near Highway 10 and Mount Lehman Road interchanges record collision severities well above provincial averages.




Figure 2.5 - Historical Collision Severity (2009 – 2012)

Common collision types include rear end collisions and off road collisions, with contributing factors such as driver inattention, following too closely, alcohol involvement and fatigue. In addition to the direct collision costs are significant delay costs that occur when the highway lanes are blocked due to an incident. With approximately 180 collisions reported to police every year, this means there is collision at least every two days along this section of the Highway 1 corridor between 216 Street and Highway 11.

### **Geometric Deficiencies**

In addition to the mobility and reliability challenges through this section of Highway 1, the background Business Case for Highway 1 widening indicated that most structures along the corridor do not meet current clearance standards of 5.0m for large structures and 5.5m for lightweight structures. In particular, those structures which are at risk of impact include the Glover Road underpass (4.46m); Roberts Bank Rail Corridor underpass Tunnel portals (4.4m); 232 Street underpass (4.62m); 264 Street underpass (4.6m); and Peardonville Road underpass (4.92m). Further, the design of the 232 Street and 264 Street interchanges with Highway 1 are no longer considered best practices. With increasing highway traffic as



well as those entering and leaving the corridor, the existing configurations contribute to short weaving and merging distances which in turn will reduce safety in the long-term.

In summary, the following issues are currently found or are forecast to occur within this section of Highway 1:

- Limited or insufficient capacity during the weekday AM and PM peak periods along most segments of the Highway 1 section between 216 Street and Highway 11;
- Anticipated increases in vehicle delays over time corresponding with volume growth along the corridor
- High collisions rates that exceed other similar provincial facilities;
- Vertical clearance issues at a number of existing structures including Glover Road, CP Rail overpass / portal, 232 Street, 264 Street, and Peardonville Road; and,
- Interchange configurations that no longer operate well under the higher traffic volumes experienced today or forecasted in the future planning horizon.

# 2.2 Truck Parking<sup>2</sup>

Stantec Consulting worked with MoTI on Truck Parking Site Investigations in 2016. Based on this work, several patterns of goods movement were highlighted, and the challenges affecting Lower Mainland communities regarding truck parking and overall impacts on the economy were examined and summarized.

The trucking sector is essential to supporting communities and the economy by delivering consumer goods, moving products from manufacturers to intermodal connections and markets, and facilitating the movement of goods for interprovincial and international trade. There are four distinct segments of the trucking industry:

- Local Trucking involves 18% of the trucking market moving goods within a 25 kilometre radius;
- Drayage Trucking involves 47% of the trucking market moving goods between ports and intermodal/warehouse facilities;
- Trans-Border Trucking involves 17% of the trucking market moving goods to and from the United States; and,
- Interprovincial Trucking involves 18% of the trucking market moving goods between provinces.

According to the British Columbia Trucking Association, the for-hire trucking sector (excluding private company transport fleets) creates \$2 billion of annual provincial GDP and employs over 33,500 people in British Columbia and the Territories. There are 23,274 trucking companies in the province with 90% having six or fewer trucks. There are an estimated 40,000 trucks hauling more than \$3 billion worth of goods between the province's gateway ports and other parts of Canada and there are over a million truck trips crossing at the three Lower Mainland commercial border crossings.

Between 2004 and 2009, the number of heavy trucks in BC grew at a rate of 1.3% per year and the total number of vehicle kilometres increased by 2.7% per year. The number of trucks is estimated to grow in the Lower Mainland by 10.0% between 2015 and 2020 with the Drayage segment growing the fastest at an estimated rate of 3.0% per year.



<sup>&</sup>lt;sup>2</sup> Stantec, Truck Parking Site Investigations, 2016.

The Local and Drayage segments are considered short haul trucking which is increasingly being centralized in Surrey in close proximity to numbered highways, ports, intermodal and warehouse facilities, manufacturers and suppliers. As of December 2012, of the 4,998 registered truck companies in Greater Vancouver, 2,661 (53.2%) were located in Surrey with the next highest being Langley with 475 companies (9.5%). In 2011, 19,950 (29.1%) of the 68,595 experienced transportation and warehouse workers within Greater Vancouver lived in Surrey. The net increase in the number of workers in this sector from 2006 to 2011 within Greater Vancouver (2,990) was accounted for in large part by those living in Surrey (2,590).

A major generator of commercial truck traffic on Highway 1, Highway 17 and along major streets within Surrey and other municipalities south of the Fraser is the Port of Vancouver which is the third largest port in North America handling one-fifth of Canada's total value of foreign goods trade. The Port of Vancouver includes 27 major marine terminals handling automobiles, bulk and breakbulk cargo, containers and cruise ships.

In addition to becoming a trucking central hub, Surrey is also one of the fastest growing communities in British Columbia. The population of Surrey grew by 9.0% from 2011 to 2015 which is significantly higher than the Greater Vancouver Regional District and more than double the rate of growth for the province as a whole during this time. In 2015, the population of Surrey was 526,024 which represented 11.2% of the entire provincial population.

With increased population growth and development, Surrey must balance residential, commercial and industrial development with environmental goals and retention of agricultural lands. One of the important values for the municipality is to maintain quiet conditions within residential neighbourhoods and agricultural areas. Truck drivers can start their day early in the morning and the sound of a truck engine can be very loud and disruptive. As a result, heavy trucks with a gross vehicle weights of 5,000 kilograms are banned by bylaw from parking or being stored within Surrey residential and agricultural areas. The City of Surrey permits a maximum of one heavy truck within an agricultural property.

In response to the truck parking challenges, the City of Survey has initiated a truck parking facility permitting process. Currently there are 35 truck parking facilities within different phases of the permitting process:

- 5 sites have Permanent Use Permits;
- 5 sites have Temporary Use Permits; and
- 25 sites are in the Temporary Use Permit Process.

It is estimated that the 35 truck parking facilities supply approximately 2,700 heavy truck parking stalls within Surrey but that an additional 2,000 truck stalls are required to meet truck demands within the community. In 2015, the City of Surrey estimated that 1,000 of the 6,000 registered trucks were illegally parking in the city. A potential private sector development within South Campbell Heights (near 16<sup>th</sup> Avenue and 192<sup>nd</sup> Street) could supply 900 to 1,200 additional stalls, but as of the date that the Stantec Truck Study was drafted, the City of Surrey had not received a formal application for development of this property.

North Surrey is one of the areas that truck drivers see a need for additional overnight truck parking. The City of Surrey has also long indicated a need for overnight truck parking along what is now the South Fraser Perimeter Road (Highway 17). Trucks are required to travel on designated truck routes within Surrey and there is limited opportunity to leave Highway 17 and stay on truck routes



Truck drivers that do not have overnight parking would need to take time and travel significant distances through heavy traffic during peak periods to find potential parking areas further away from the Highway 1 and 17 corridors. The truckers that would benefit the most from new parking near Highway 17 would likely be those that are the most unfamiliar with the Surrey road network, take the longest long time to find parking at night and travel well away from the highway corridors. Conversely parking near Highway 17 is likely to appeal less to those that already have or use parking facilities near this highway corridor. Based on this information, it is quite likely that truckers passing through Surrey could, like their United States counterparts, incur over an hour of time to find suitable parking each night.

Passenger vehicle stalls are also in demand at truck parking facilities. The expectation is that local truckers will drive to the parking facility, leave the passenger vehicle parked and drive away in the heavy truck. This is in response to a long standing need in Surrey for local truck drivers to park their passenger vehicles at the same lot as their heavy truck is parked and avoid the need to have a third party drop them off and pick them up at the site on a daily basis.

There are few overnight truck parking facilities located near residential areas and Surrey bylaws state that parking within residential areas is not allowed. Therefore, the current situation requires local truckers to park their trucks well away from their residence and either drive themselves to the truck parking location, use public transit (which would add increased time for the driver), or travel by taxi (at an increased cost) or with a third party.

In the absence of a new truck parking development, there is a risk that trucks will park illegally within municipalities creating potential safety risks along roadways and noise issues within residential and agricultural areas. Environmental damage from oil leaking from trucks is also a concern.

Suggestions provided during the stakeholder consultation included the need for truck parking with asphalt surfaces, fencing, lighting, security cameras and sanitation features (sani-dump, plumbed toilets and waste/recycling receptacles). The need for parking to accommodate long combination vehicles, long haul vehicles and shorter vehicles at affordable prices was also recommended by stakeholders.



# 3.0 Concept Development & Cost Estimates

This section of the Business Case highlights the options considered and the preferred concepts developed for widening Highway 1 and supplying a new truck parking facility.

# 3.1 Highway 1

### a. Mainline Capacity

As part of the Highway 1 widening, the median area is generally wide enough across the corridor to provide the additional eastbound and westbound lanes. Beyond that, the method of widening for either general purpose traffic or high-occupant vehicles (HOVs) were considered. The fundamental consideration was the safety and efficiency for the transitions at either end. Parsons' original Highway 1 Widening study considered four options, as displayed in **Figure 3.1.** These include:

- 1. One general purpose lane in each direction between 202 Street and Highway 11;
- 2. New HOV lane in each direction between 202 Street and Highway 11;
- 3. s.13
- 4. New general purpose lane in each direction between Glover Road and Highway 11, and extend existing HOV lanes to Highway 10;

Considering highway usage, capacity and operational performance, *Option 3 was selected as the preferred lane designation in each direction*. s.13 s.13

s.13 This option was considered to offer the most appropriate balance between providing corridor capacity, accommodating special purpose lanes, as well as adding / removing lanes in a safe and efficient manner that is consistent with driver expectations.







Figure 3.1 - Mainline Capacity Improvement Option Concepts

s.13




Source: Highway 1 Widening (216 Street to Highway 11) Business Case, Parsons (2016)

### b. Interchange Reconfiguration

To accommodate the additional lane in each direction of travel along the mainline, the existing overpass structures at the 232 Street and 264 Street interchanges require replacement as the current horizontal and vertical clearances are insufficient or substandard. Noting that the existing interchange configurations do not reflect current best practices given the high traffic volumes to be accommodated, and that the existing structures need to be replaced given the constraints mentioned above, a number of interchange reconfiguration options were developed. The preferred options would then form part of the Highway 1 widening project scope.


For the purpose of this Business Case, only the 232 Street Interchange options are highlighted for discussion. Several configurations were developed to improve upon the deficient geometry associated with the existing cloverleaf interchange configuration as well as to accommodate future travel demand. A total of four improvement options were developed for the 232 Street interchange and are described as follows:

Option 1: Parclo B Interchange Configuration with Roundabouts







### Option 2: Parclo B Interchange Configuration



## Option 3: Parclo B Interchange Configuration with 72 Avenue Flyover



### Option 4: Split Diamond Interchange Configuration



Focused traffic analysis, cost estimating, and other measurements were conducted to assess interchange options with respect to the evaluation criteria. As displayed in Table 3.1, Option 3 is preferred as it provides significant improvements in network connectivity compared to the base case at comparable benefit-cost ratios. Option 3 includes a new bridge structure across Highway 1 along 72 Avenue, removing east-west local traffic from the interchange.

Table 3.1: Highway 10 / 232 Street Interchange Evaluation Summary

Criteria	Option 1	Option 2	Option 3	Option 4
Travel Time	0 hrs AM peak period (2014)	20 hrs AM peak period (2014)	0 hrs AM peak period (2014)	-10 hrs AM peak period (2014)
Savings	-20 hrs PM peak period (2014)	0 hrs PM peak period (2014)	-20 hrs PM peak period (2014)	-20 hrs PM peak period (2014)
_	0 hrs AM Peak Period (2045)	30 hrs AM Peak Period (2045)	10 hrs AM Peak Period (2045)	-20 hrs AM Peak Period (2045)
	20 hrs PM Peak Period (2045)	30 hrs PM Peak Period (2045)	10 hrs PM Peak Period (2045)	40 hrs PM Peak Period (2045)
	-\$0.4 M Travel Time Savings (25 years)	\$2.4 M Travel Time Savings (25 years)	-\$0.8 M Travel Time Savings (25 years)	-\$1.2 M Travel Time Savings (25 years)
Implementation	\$40 M	\$45 M	\$57 M	\$54 M
Costs				
Property Impacts	0.0 Ha – Property Impacts	0.0 Ha – Property Impacts	0.0 Ha – Property Impacts	0.0 Ha – Property Impacts
	5.0 Ha – Potential Surplus	10.3 Ha – Potential Surplus	5.0 Ha – Potential Surplus	8.4 Ha – Potential Surplus
Network	No improvement as compared to the	No improvement as compared to the	Significant improvement compared to	Moderate improvement compared to
Connectivity	base case.	base case.	base case.	base case.
Provincial	The proposed configuration, as	The proposed configuration, as	The proposed configuration, as	The proposed configuration, as
Movements	compared to the base case, does not	compared to the base case, does not	compared to the base case, provides	compared to the base case, is
	provide any improvements for the	provide any improvements for the	some improvements to the provincial	detrimental to some provincial
	provincial movements between	provincial movements between	movements between Highway 1 and	movements between Highway 1 and
	Highway 1 and Highway 10 and may	Highway 1 and Highway 10 and may	Highway 10.	Highway 10.
	even cause some reduction in mobility	even cause some minor reduction in		
	for these key movements.	mobility for one movement.		
Benefit / Cost and	B/C = 0.2	B/C = 0.3	B/C = 0.2	B/C = 0.2
NPV	NPV= -\$30 M	NPV= -\$31 M	NPV= -\$42 M	NPV= -\$41 M
Overall	Possible	Possible	Preferred	Not Preferred

Source: Highway 1 Widening (216 Street to Highway 11) Business Case, Parsons (2016)



### c. Overall Project Scope & Cost Estimate

At this stage, the Highway 1 widening and area improvements would extend from east of the soon to be built 216 Street interchange up to but not including the 264 Street interchange. This would include the following sequence of improvements as summarized below:

- 232 Street Interchange which involves reconfiguring the existing interchange, replacing the existing underpass structure and constructing a new 72 Avenue underpass structure.
- 2.1km widening between the soon to be constructed interchange at 216 Street and the 232 Street
  Interchange as previously described. This widening would involve the removal and construction of
  a new CP Rail crossing and Glover Road underpass structure.
- Widening in the westbound direction for approximately 5.8km between 264 Street to 232 Street.
   Three eastbound general purpose lanes are already provided between 232 Street and 264 Street.
   No new structures or modifications to existing structures are required as part of this project.

The limits of the widening in both the eastbound and westbound directions are illustrated in **Figure 3.2**. Beyond these project limits, the Ministry will widen Highway 1 from four to six lanes in both directions through to Highway 11 as financial resources become available in future.




Figure 3.2 - Project Limits for Highway 1 Widening & Area Improvements

Conceptual cost estimates have been prepared by Parsons for all Highway 1 six laning project components and summarized in **Table 3.2**. The recommended capital improvements are estimated at **\$205.5 M** (Class C, 2016 \$). All improvements are to take place within the rights-of-way that are provincially owned.

Table 3.2: Highway 1 Widening Cost Estimates (2016 \$)

Costs		Highway 1 - 232nd Street Interchange	Highway 1 - 216th Street to 232nd Street Widening			Highway 1 - Nidening WB East of 248 erpass to 72nd Overpass	V	Highway 1 - Widening WB East 264th St erpass to East of 248 St Overpass	Highway 1 Total Only		
A: Non-Eligible Costs	_		_		_		_		_		
Pre-development Activities	\$	-									
Property Acquisition	\$	-									
Administration & Other	\$	5,850,000	\$	5,330,000	\$	1,430,000	\$	819,000	\$	13,429,000	
Non-Eligible Costs Sub-Total	\$	5,850,000	\$	5,330,000	\$	1,430,000	\$	819,000	\$	13,429,000	
B: Eligible Costs											
Construction	\$	55,500,000	\$	54,100,000	\$	13,287,000	\$	7,757,000	\$	130,644,000	
Engineering	\$	6,500,000	\$	5,900,000	\$	1,800,000	\$	1,000,000	\$	15,200,000	
Environmental Mitigation	\$	- Andrew Andrews							\$	-	
First Nations Consultation	\$	800,000	\$	800,000	\$	600,000	\$	300,000	\$	2,500,000	
Contingency	\$	18,600,000	\$	18,000,000	\$	4,526,100	\$	2,627,000	\$	43,753,100	
Eligible Costs Sub-Total	\$	81,400,000	\$	78,800,000	\$	20,213,100	\$	11,684,000	\$	192,097,100	
Project Total	\$	87,250,000	\$	84,130,000	\$	21,643,100	\$	12,503,000	\$	205,526,100	

Source: Parsons, Class C estimates, 2016

# 3.2 Truck Parking

The truck parking review considered thirteen potential sites within Surrey as well as others in adjacent municipalities as illustrated in **Figure 3.3**. Pre-screening was completed to filter the sites down to the top four areas identifying two sites for further option analysis.

Figure 3.3: Candidate Truck Parking Sites


s.13,s.17

Source: Stantec Consulting, 2016

Conceptual layouts were developed to determine drive-through stall capacity and other site related environmental issues. The areas were also reviewed to determine if passenger vehicle parking could be accommodated to support the storage of trucks for local truck drivers that live within the Lower Mainland. Although staging could be a potential use for these sites, the analysis did not consider any additional factors or design modifications to support commercial truck staging relating to DeltaPort.


The evaluation resulted in the following shortlisted top ranked sites that include:

 Option 1: 11688 Highway 1 (accessed via Highway 17), east of Port Mann Bridge, south of CN Rail – Large Site



Source: Stantec Consulting

 Option 2: 11688 Highway 1 (accessed via Highway 17), east of Port Mann Bridge, south of CN Rail – Small Site



Source: Stantec Consulting

s.13,s.16,s.17

Source: Stantec Consulting

It must be noted that, although Option 1 and 2 could be combined as a single site with 220 trucking stalls, it was decided to separate these into a large area with 158 truck stalls (Option 1) and a smaller area with 62 truck stalls (Option 2) for phasing purposes. A summary of the key attributes of the short-listed site options is displayed in **Table 3.3.** 

**Table 3.3 - Site Information Summary** 

Option #	Location	Features	# of Stalls	Significant Issues Identified/Risks	Estimated Cost
1	11688 Highway 1 north of SFPR, east of Port Mann Bridge, south of CN Rail	<ul> <li>Washroom/ Showers</li> <li>Sani-dump</li> <li>Lighting with standard lamps</li> <li>Security fence around parameter</li> <li>5 parking spots for B-Trains</li> <li>Protected T intersection with half signal along SFPR</li> <li>Security Gatehouse</li> </ul>	158 Pull Through Heavy Truck  44 Passenger Vehicle	<ul> <li>Near Bon Accord Creek (salmon habitat) and two small watercourses run through)</li> <li>High potential for Japanese Knotweed</li> <li>High archaeological potential at original ground elevation (under fill)</li> <li>Adjacent to railway</li> <li>Fill placed may present geotechnical settlement issues</li> <li>Requires water line extension works</li> <li>Parking area may be reduced if "no disturbance" zones are found</li> <li>Expandable to include Option 2 Site)</li> </ul>	\$30,000,000 OR \$189,900 / Truck Stall
2	11688 Highway 1 north of SFPR, east of Port Mann Bridge, south of CN Rail	Washroom/     Showers     Sani-dump     Lighting with standard lamps     Security fence around parameter     Protected T intersection with half signal along SFPR     Security     Gatehouse	62 Back-in Heavy Truck	<ul> <li>Near Bon Accord Creek (salmon habitat) and two small watercourses run through)</li> <li>High potential for Japanese Knotweed</li> <li>High archaeological potential at original ground elevation (under fill)</li> <li>Adjacent to railway</li> <li>Fill placed may present geotechnical settlement issues</li> <li>Requires water line extension works</li> <li>Parking area may be reduced if "no disturbance" zones are found</li> <li>Expandable to include Option 1 Site)</li> </ul>	\$17,000,000 OR \$274,200 / Truck Stall





**Option 1** was selected as the recommended truck parking area as it results in the greatest additional number of truck parking stalls constructed and is the least expensive to construct on a per-stall basis. The site would support 158 pull through truck and 44 passenger vehicle parking stalls. The site would be connected to Highway 17 through a new signalized protected T-intersection with left-turn and right-turn lanes.

As displayed in **Table 3.4** below, Stantec estimates the total cost of the preferred option at \$30 M (Class D, 2016 \$). This estimate includes \$29.9 M for capital works and \$13,s.17 for property acquisition.

Table 3.4: Truck Parking Area Cost Estimates (2016 \$)

Costs	Truck Parking
A: Non-Eligible Costs	
Pre-development Activities	\$ 170,000
Property Acquisition	\$ s.13,s.17
Administration & Other	\$ 3,900,000
Non-Eligible Costs Sub-Total	\$ s.13,s.17
B: Eligible Costs	
Construction	\$ 20,160,000
Engineering	\$ 2,500,000
Environmental Mitigation	\$ 700,000
First Nations Consultation	\$ 350,000
Contingency	\$ 2,120,000
Eligible Costs Sub-Total	\$ 25,830,000
Project Total	\$ 30,000,000

Source: Stantec, Class D Estimates, 2016




It should be recognized that the Ministry plans to convert or remove at-grade signalized intersections along Highway 17 as traffic volumes increase to ensure travel reliability and improve safety along the corridor. Therefore, the provision of an at-grade signal on Highway 17 for the proposed truck parking area is expected to be removed and replaced with upstream and downstream interchanges for truck and vehicle access.

To quantify signal disbenefits to Highway 17 through traffic, the operational analysis considered the impact of signals on Highway 17 based on 2017 and 2027 projected traffic volumes. A signalized protected-T configuration was modelled, consistent with Stantec's traffic impact recommendations and volumes. A signalized protected-T ensures eastbound free flow operations, with through movement traffic control on the westbound approach only.

**Figure 3.4** illustrates the estimated site and highway traffic volumes at the proposed partial signal on Highway 17 at the truck parking site. The operational assessment indicates that by managing signal interruptions, highway delays in the westbound direction may be minimized at an estimated level of service E or better during peak periods. Beyond ten years, it is anticipated that the signals will be replaced with grade-separated interchanges along Highway 17. Synchro and SimTraffic analysis results are included in **Appendix C.** 

Figure 3.4: Turning Movements at Highway 17 / Truck Access in 2017 and 2027



## 4.0 Multiple Account Evaluation

This section describes the evaluation of the costs, benefits, impacts, and risks of the preferred improvements based on a Multiple Account Evaluation (MAE) approach that is consistent with the BC Provincial Business Case Guidelines. The MAE methodology is intended to capture both the quantifiable measures of project cost and direct project benefits, in addition to more qualitative measures of direct project benefits. Within the MAE, the quantitative measures are monetized over a 25-year period using a 6% discount rate to determine the Net Present Value (NPV) and Benefit-Cost (B/C) Ratio. For this assignment, two concurrent but separate MAEs were completed for the Highway 1 six laning (216 Street to Highway 13) and Surrey Truck Parking facility improvements. The following accounts were assessed:

#### Financial

- Project Costs (construction, engineering, property)
- Truck Facility Revenue and Expenses
- Maintenance (annual and periodic rehabilitation)
- Salvage Value

#### Customer Service

- Mobility (travel time and vehicle operating cost savings)
- Safety (collision reductions)

#### Social/Community

- Noise and Visual Impacts
- Community Displacement
- o Community Severance
- Reduction in Illegal Truck Parking
- Sustainable Transportation
- Consistency with Provincial Plans

#### Environmental

- Terrestrial
- Aquatic
- Archaeological / Historical
- GHG Reduction

#### Economic

- Net Present Value
- Benefit-Cost Ratio

## 4.1 Financial Account

The financial account represents the discounted life-cycle costs over 25 years. These include the initial investment (construction, property acquisition, engineering and project management), annual maintenance and rehabilitation costs, and the salvage value at the end of the project's life cycle. In order to represent common dollars, the Present-Value (PV) method is typically used to discount future costs. A discount rate of 6% was assumed for this evaluation, as is consistent with the Provincial Business Case guidelines.

**Table 4.1** summarizes financial account components including project costs, truck facility revenue and expenses, maintenance and rehabilitation costs, and salvage value. These components are discussed in further detail below.



	Highway 1 Widening & Overpass/Interchange Improvements	s.13
FINANCIAL ACCOUNT		
PV Revenue	-	\$4.4 M
PV Expenses	-	-\$4.4 M
Capital Cost (2016 \$)	\$205.5 M	\$29.9 M
Property Cost (2016 \$)	-	s.13,s.1
Capital Cost (PV)	\$179.5 M	\$27.0 M
Property Cost (PV)	-	\$0.1 M
Maintenance (PV)	\$2.0 M	\$0.3 M
Salvage Value (PV)	-\$24.3 M	-\$1.6 M
Total Incremental Cost	\$157.2 M	s.13,s.17

Table 4.1: Estimated Project Capital and Property Costs

▶ Project Costs. Conceptual cost estimates were prepared for the Highway 1 Six Laning project by Parsons. Project costs for this business case reflect improvements between 216 Street and 264 Street only, and exclude the 264 Street interchange. The capital cost for Highway 1 six laning and associated works was estimated to be \$205.5 M (Class C). No property costs are included as all improvements are to occur within the provincial right-of-way. Further details on Parsons' project costs for the entire 216 Street to Highway 11 segment are provided in Appendix B of the original Parsons Highway 1 Widening (216 Street to Highway 11) Business Case, found in Appendix A of this report.

Conceptual level cost estimates were prepared by Stantec for the Truck Parking Facility project. The capital cost for the facility was estimated at \$29.9 M (Class D). An additional s.13,s.17 s.13,s.17

As projects will be constructed and completed over the span of the next five fiscal years, project costs are discounted to present value at a rate of 6% for economic analysis.

- Truck Facility Revenue and Expenses. Stakeholder consultation conducted by Stantec indicated that a charge of \$200 / month was considered a reasonable fee for overnight truck parking. This revenue is assumed to offset facility operating and maintenance costs so that the Province of British Columbia neither gains revenue from operations nor subsidizes operations and maintenance of the site. Projected expenses for the truck parking facility include business license fees, repairs and maintenance, supplies, janitorial, security, snow removal, sweeping and scrubbing, equipment servicing / PMP, utilities, telephone and management services. Discounted 25 year facility operating expenses were estimated by Stantec at \$4.4 M. As the facility will be managed to be revenue neutral, with user costs set to cover expenses, this number has not be factored into the overall economic assessment of the project.
- ▶ Maintenance. Annual maintenance costs are calculated using values as described in the *Default Values for Benefit Cost Analysis In British Columbia 2012*. The annual maintenance of new roads is estimated to be approximately \$3,839 per lane kilometre, while periodic rehabilitation costs which assume hot mix paving once every 15 years are estimated to be \$110,000 per lane kilometre. 25 year Maintenance costs for Highway 1 Six Laning were calculated to reflect a proportion of total



Highway 1 Six Laning (216 Street to Highway 11) maintenance costs as presented in the original Parsons Six Laning report and are estimated at **\$2.0 M**. Stantec's review provides a 25 year maintenance cost of **\$0.3 M** for the Truck Parking Facility which assumes resurfacing at the 20 year horizon.

▶ Salvage Value. The salvage value represents the value of the investment at the end of the analysis period. As a salvage value for the discrete 216 Street to 264 Street segment was not included in the Parsons analysis, a salvage value of -\$24.3 M was calculated to reflect 80% of project capital costs discounted to the end of the analysis period. The Stantec Review's stated 25 year salvage value of -\$1.6 M was used for the truck parking facility.

## 4.2 Customer Service Account

The customer service account represents the cost to the roadway users over the project's life cycle. This includes travel time and vehicle operating costs, and collisions accrued and discounted over 25 years. Improvements to the corridor that result in improved mobility and safety can be compared to the financial account of the project.

Benefits in the customer service account identify benefits to roadway users, but also reflect improvements to local, regional, and provincial connectivity because they reflect the reduced travel time and lower collision costs experienced by these trips.

Mobility. Mobility savings provides a monetary value of travel time savings for all traffic on the corridor. Travel time benefits were calculated separately for both projects for private vehicles and trucks using the assumed travel time costs as summarized in Table 4.2.

Table 4.2: Value of Travel Time

Vehicle/Driver Type	Value (\$ per hour)
Automobile	\$15.94
Single Unit Truck	\$46.03
Combination Truck	\$53.30

Source: Default Values for Benefit Cost Analysis in British Columbia, BC MoT Planning and Programming Branch, 2012.

Projected 25-year travel time and vehicle operating cost savings as are estimated for each project in **Table 4.3** (2016 dollars based on a discount rate of 6%).

The 25 year travel time and vehicle operating benefits for Highway 1 Six Laning were calculated to reflect a proportion of total Highway 1 Six Laning (216 Street to Highway 11) travel time and vehicle operations benefits as presented in the original Parsons Six Laning report and are estimated at \$172.2 M and \$11.1 M, respectively. These benefits mainly reflect changes in mainline operating speeds resulting from improvements. Present value benefits reflect a post-construction 25 year analysis period (2023 to 2047).

The 25 year travel time and vehicle operations benefits for the truck parking facility are comprised of two components. The first component reflects travel time and vehicle operating benefits to trucks and vehicles using the truck parking facility and the second component calculates the ten year disbenefits to Highway 17 through traffic of a new truck access signal at the parking facility. 25 year truck facility



user benefits are as reported in the Stantec review and result in \$23.8 M and \$7.0 M in travel time and vehicle operating savings. This calculation assumes 125 trucks will use the facility each weekday and that these trucks would otherwise travel an additional 45 minutes / 15 km per direction each day in search of parking. It is assumed that without the additional vehicle parking stalls, 33 truck drivers would be dropped off / picked-up at the parking lot each day in private vehicles that would add an additional 45 minutes and 20 km of private vehicle driving per day.

Ten year signal delay disbenefits to Highway 17 through traffic were calculated by Urban Systems using the Synchro / SimTraffic modelling application. A ten year horizon was chosen for the signal as it is likely that the facility will be served by a nearby upgraded interchange in the medium term future. A signalized protected-T configuration was modelled, consistent with Stantec's traffic impact recommendations and volumes. A signalized protected-T ensures eastbound free flow operations, with through movement traffic control on the westbound approach only. AM and PM peak hour 10 year westbound approach delays were calculated from a series of SimTraffic runs. The signal results in Highway 17 vehicle travel time and operation costs of **-\$2.2M and -\$0.2M**, respectively.

Hwy 1 Widening & Overpass/Interchange **Improvements** Travel Time Savings (PV) \$172.2 M \$23.8 M Vehicle Operating Savings (PV) \$11.1 M \$7.0 M Hwy 17 / Truck Access Signal Travel Time Costs (PV) -\$2.2 M Hwy 17 / Truck Access Signal Veh. Operating Costs -\$0.2 M (PV) Total Incremental Mobility Benefits (PV) \$183.3 M \$28.4 M

Table 4.3: Estimated Mobility Benefits (2016 \$ PV) s.13

It is worth noting that the travel time benefits noted above are incurred after project completion and do not account for the potential offsets to travel time during construction due to traffic disruption. The disruption to travel time during construction would only be temporary and should be managed through a traffic management plan.

▶ Safety. The Collision Prediction Model (CPM), a spreadsheet tool developed by BC MoTI, was used by Parsons to estimate the potential safety benefits resulting from Highway 1 Six Laning improvements along the entire 216 Street to Highway 11 segment. Using a combination of collision modification factors (CMFs) for BC and from the Highway Safety Manual, the CPM was used to evaluate and compare the safety benefits.

The Parsons Six Laning Business Case estimates an incremental 13% reduction in collisions over the analysis period. Using information provided in the original business case on total number of collisions along the entire corridor per year as well as existing and improved breakdowns in collision type, Urban Systems recalculated incremental 25 year collision benefits to reflect the 216 Street to Highway 13 segment only.

The value of various collisions (by severity), as described in the *Default Values for Benefit Cost Analysis In British Columbia 2012* is summarized in **Table 4.4.** 

Table 4.4: Cost of Collisions to Society

Severity Type	Value (\$ per hour)
Fatal	\$6,385,999
Injury	\$135,577
Property Damage	\$11,367

The proposed six laning improvements are expected to result in 25 year safety benefits valued at **\$6.5 M**.

An analysis of safety impacts resulting from the construction of the truck parking facility was not conducted.

## 4.3 Social/Community Account

This account evaluates the potential impacts of each project on the community. These are generally qualitative measures but are considered in combination with the more quantifiable economic indicators. The following factors have been included in this review:

- Noise, Visual Impacts
- Community Displacement Property takes, partial and full; and
- Community Severance the 'barrier effect' of the highway on local and pedestrian traffic.
- Reduction in Illegal Truck Parking
- Sustainable Transportation actions that promote non single-occupant vehicle modes of travel such as carpooling, walking, cycling, and public transit
- Consistency with Provincial Plans

Social/community impacts of both projects are summarized in **Table 4.5** as they relate to the existing conditions and are evaluated based on their estimated positive benefit, neutral or negative impact to key stakeholders.



Table 4.5: Summary of Socio-Community Account Indicators

Indicator	Highway 1 Six Laning	Highway 17 Truck Parking Facility
Noise and Visual Impacts	Neutral  Both noise and visual impacts are expected to remain relatively the same as today with the proposed improvements. All widening is to occur within the existing freeway median.	Neutral The truck parking facility is not located near a residential or commercial zone. Neighbouring land uses are two Provincial highways and a rail yard / shunting facility. Any additional noise or visual impacts that may occur as a result of the truck parking facility will have very limited impacts on Surrey residences and businesses.
Community Displacement	Neutral  Effects of widening on community displacement are limited as all improvements, including the 232 Street interchange reconfiguration, will occur within the provincial right-of-way.	Neutral The truck parking facility will be constructed on a vacant lot. No residential or commercial displacement is anticipated.
Community Severance	Significant Benefit Six laning improvements will add a new bridge structure across Highway 1 at 72 Avenue. This improved network connectivity reduces the barrier effect of the highway and removes east-west traffic from the interchange.	Neutral The truck parking facility will have limited effects on community severance.
Reduction in Illegal Truck Parking	N/A	Modest Benefit The proposed improvement provides 158 new truck parking stalls in the City of Surrey, which helps address the estimated 2,000 truck parking stall deficiency in that municipality.
Sustainable Transportation	Modest Benefit The proposed improvements include a 6 km extension of existing Highway 1 HOV lanes from 202 Street to Highway 10. HOV lanes provide reserved lanes for carpool vehicles and public transit and can act to incentivise sustainable transportation choices.	Neutral The truck parking facility will have limited sustainable transportation effects.
Consistency with Provincial Plans	Significant Benefit Six Laning Highway 1 through the western Fraser Valley was specifically identified in <i>BC</i> on the Move, the Province's ten year transportation plan.	Significant Benefit  BC on the Move, the Province's ten year transportation plan, commits to constructing at least two new truck parking areas in the Lower Mainland.



## 4.4 Environmental Account

The environmental account is intended to identify any significant environmental impacts resulting from the proposed improvements. This is not intended to replace an environmental assessment, if required, but only as a qualitative measure of potential impact. In addition, qualitative measures of reduced greenhouse gas (GHG) emissions have also been included. The qualitative environmental review for both projects is summarized in **Table 4.6.** 

MoTI Responses to Infrastructure Canada Annex D – Environmental and Aboriginal Consultation Information Requirements as it pertains to Highway 1 six laning is included in Appendix C of the original Parsons *Highway 1 Widening (216 Street to Highway 11) Business Case* found in **Appendix A** of this report. MoTI Responses to Infrastructure Canada Annex D as it pertains to the truck parking facility is included in **Appendix B** of this report.

Table 4.6: Summary of Environmental Account Indicators

Indicator	Highway 1 Six Laning	Highway 17 Truck Parking Facility
Terrestrial	Neutral  Effects on terrestrial resources due to the Highway 1 widening would be limited as all widening is within the median of an existing freeway.	Unknown
Aquatic	Neutral  Effects on aquatic resources due to the Highway 1 widening would be limited as all widening is within the median of an existing freeway.	Modest Impact According to Stantec's review, the truck parking facility will be constructed in an area with or adjacent to streams supporting fisheries with modest impacts that will need to be mitigated.
Archaeological / Historical	Neutral  Effects on archaeological or historical sites due to the Highway 1 widening would be limited as all widening is within the median of an existing freeway.	Unknown
GHG Reduction	Significant Benefit Highway 1 Six Laning will significantly decrease vehicle idling through the segment as a result of improvements in vehicle operating conditions and may act to promote the use of High Occupancy Vehicles with the extension HOV facilities to 232 Street.	Modest Benefit The truck parking facility will have a modest benefit on GHG emissions as fewer trucks will travel long distances in search of parking.

## 4.5 Multiple Account Evaluation Summary

A summary of all MAE accounts considered in this Business Case is provided in **Table 4.7**. These include both quantitative measures used for the economic evaluation of the project and qualitative measures of direct project benefits and wider scale indirect benefits. Key economic indicators such as Net Present Value (NPV) and Benefit-Cost Ratio (B/C), are included for a 25-year period. The costs reported in the table below have been discounted to present value (PV) using a 6% discount rate.

Widening Highway 1 between the new 216 Street interchange and the 264 Street interchange, including a full interchange reconfiguration at 232 St and all associated overpass improvements, results in a **Net Present Value of \$32.6 M and a benefit/cost ratio of 1.2**, which is considered very impressive due to the overall scale of the project. Constructing the proposed truck parking facility \$.13,s.17

s.13,s.17 results in a **Net Present Value of \$2.6 M and a benefit/cost ratio of 1.1.** The two improvements will result in overall benefits to the local, provincial and national economy. The anticipated social and economic benefits of both projects are also well aligned with provincial objectives.



Table 4.7: Multiple Account Evaluation Summary

	Highway 1 Widening &  Overpass/Interchange  Improvements (1)	
FINANCIAL ACCOUNT		
PV Revenue	-	\$4.4 M
PV Expenses	-	-\$4.4 M
Capital Cost (2016 \$)	\$205.5 M	\$29.9 M
Property Cost (2016 \$)	-	s.13,s.17
Capital Cost (PV)	\$179.5 M	\$27.0 M
Property Cost (PV)	-	\$0.1 M
Maintenance (PV)	\$2.0 M	\$0.3 M
Salvage Value (PV)	-\$24.3 M	-\$1.6 M
Total Incremental Cost	\$157.2 M	s.13,s.17
CUSTOMER SERVICE ACCOUNT		
Travel Time Savings (PV)	\$172.2 M	\$23.8 M
Vehicle Operating Savings (PV)	\$11.1 M	\$7.0 M
Hwy 17 / Truck Access Signal Travel Time Costs (PV)		-\$2.2 M
Hwy 17 / Truck Access Signal Veh. Operating Costs (PV)		-\$0.2 M
Safety (PV)	\$6.5 M	N/A
Total Incremental Benefits (PV)	\$189.8 M	\$28.4 M
SOCIAL/COMMUNITY ACCOUNT		
Noise and Visual Impacts	•	•
Community Displacement	•	•
Community Severance	•	•
Reduction in Illegal Truck Parking	N/A	•
Sustainable Transportation	•	•
Consistency with Provincial Plans	•	•
ENVIRONMENTAL ACCOUNT		
Terrestrial	•	Unknown
Aquatic	•	•
Archaeological / Historical	0	Unknown
GHG Reductions	•	•
KEY ECONOMIC INDICATORS Net Present Value	\$32.6	\$2.6 M
Benefit-Cost	\$32.0 1.2	\$2.0 WI
<ul> <li>MAE evaluation from the Highway 1 Widening (216 Street assessment extrapolated from the 15 year evaluation profize)</li> <li>MAE evaluation from Stantec assessment of the proposed</li> </ul>	to highway 11) Business Case, Parsor vided in background business case (inc	ns, 2016. Customer service luding Class C estimates).

● ● ● ● O

Significant Benefit Modest Benefit Neutral Modest Impact Significant Impact





## 5.0 Sensitivity Analysis

In order to consider the risks and uncertainties inherent in this type of evaluation appropriately, a sensitivity analysis was conducted. This approach considers a range of uncertainty for key factors in the project assessment. The result is that the conclusions reached can be tested for resiliency against potentially changed economic conditions. For this assignment, sensitivity analyses were conducted for discount rates, and cost estimates.

## 5.1 Discount Rates

To convert future project related costs and benefits to a common present value for comparison, a discount rate was used in the benefit-cost evaluation. This rate is typically set to reflect the rate of inflation and is therefore, subject to changes depending on overall economic circumstances. In this type of evaluation, the discount rate is of particular importance for future benefits (mobility and safety). However, project costs are also affected where future costs must also be discounted to represent present value. According to the *BC Ministry of Transportation's Benefit-Cost Guidebook*, a discount rate of 6% should be used for Provincial benefit-cost evaluation. This value has been used for the original analysis presented above. On the other hand, the *Transport Canada – Guide to Benefit-Cost to Analysis* indicates that a rate of 10% is appropriate for federal business cases. Consequently, in order to test the sensitivity of the results of this evaluation, the benefit-cost analysis was also calculated using the 10% discount rate as preferred by Transport Canada, and an additional 8% rate for comparison. The results of the analysis are summarized in **Table 5.1**.



Truck Parking Facility Highway 1 6 Laning **Discount Rate** Account Discount Rate 6% 8% 10% 6% 8% 10% FINANCIAL ACCOUNT PV Revenue \$4.4 M \$3.5 M \$2.8 M PV Expenses -\$4.4 M -\$3.5 M -\$2.8 M Capital Cost (PV) \$179.5 M \$172.0 M \$165.0 M \$27.0 M \$26.1 M \$25.3 M s.13,s.17 Property Cost (PV) \$2.0 M \$1.4 M \$1.1 M \$0.3 M \$0.2 M Maintenance (PV) \$0.1 M Construction Salvage Value (PV) -\$24.3 M -\$13.8 M -\$8.0 M -\$1.6 M -\$1.5 M -\$1.4 M s.13,s.17 Total Incremental Cost (PV) \$157.2 M \$159.6 M \$158.1 M CUSTOMER SERVICE ACCOUNT Travel Time Savings (PV) \$126.9 M \$95.5 M \$23.8 M \$18.8 M \$15.1 M \$172.2 M Vehicle Operating Savings (PV) \$8.1 M \$6.1 M \$7.0 M \$5.5 M \$4.4 M \$11.1 M Hwy 17 / Truck Access Signal -\$2.2 M -\$1.9 M -\$1.6 M Travel Time Costs (PV) Hwy 17 / Truck Access Signal -\$0.2 M -\$0.1 M -\$0.1 M Veh. Operating Costs (PV) \$4.9 M \$3.8 M N/A N/A N/A Safety (PV) \$6.5 M Total Incremental Benefits (PV) \$28.4 M \$22.3 M \$17.8 M \$139.9 M \$105.4 M \$189.8 M KEY ECONOMIC INDICATORS

Table 5.1: Discount Rate Sensitivity

This analysis indicates that the key economic indicators are sensitive to a reasonable variation in discount rate. As expected, the economic indicators are improved with reduced discount rate assumptions. At an 8% discount rate, the Highway 1 widening project results in a NPV of -\$19.7 M and a B/C ratio of 0.9, while the Truck Parking project results in a NPV of -\$2.6 M and a B/C ratio of 0.9. At a 10% discount rate, the Highway 1 widening project results in a NPV of -\$52.7 M and a B/C ratio of 0.7, while the Truck Parking project results in a NPV of -\$6.3 M and a B/C ratio of 0.7.

-\$52.7 M

0.7

\$2.6 M

1.1

-\$2.6 M

0.9

-\$6.3 M

0.7

-\$19.7 M

0.9

## 5.2 Project Cost Estimates

\$32.6 M

1.2

Net Present Value

Benefit-Cost Ratio

Estimated project costs are based on the best engineering data available and a reasonable contingency, but without detailed engineering, the magnitude of potential risks may not be completely captured. To test the sensitivity of key economic indicators to reasonable variations in project cost, indicators are assessed at plus or minus 25% of estimated capital costs. Results are summarized in **Table 5.2**.



This analysis indicates that the key economic indicators are sensitive to a reasonable variation in the cost estimate. As expected, the economic indicators for both projects are improved with a 25% reduced cost estimate assumption, resulting in an NPV of \$71.4 M and a B/C ratio of 1.6 for Highway 1 six laning and an NPV of \$9.0 M and B/C ratio of 1.5 for the truck parking facility. Under a 25% increased cost estimate assumption economic indicators worsen, resulting in an NPV of -\$6.2 M and a B/C ratio of 1.0 for Highway 1 6 laning and an NPV of -\$3.8 and a B/C ratio of 0.9 for the truck parking facility.

Table 5.2: Project Cost Estimate Sensitivity

	Hig	thway 1 6 Lan	ing	Truck Parking Facility Discount Rate			
Account		Discount Rate	9				
	-25%	Base	+25%	-25%	Base	+25%	
FINANCIAL ACCOUNT							
PV Revenue	-	-	-	\$4.4 M	\$4.4 M	\$4.4 M	
PV Expenses	-	-	-	-\$4.4 M	-\$4.4 M	-\$4.4 M	
Capital Cost (PV)	\$134.6 M	\$179.5 M	\$224.4 M	\$20.2 M	\$27.0 M	\$33.7 M	
Property Cost (PV)	-	-	-	s.13,s.17			
Maintenance (PV)	\$2.0 M	\$2.0 M	\$2.0 M	\$0.3 M	\$0.3 M	\$0.3 M	
Construction Salvage Value (PV)	-\$18.2 M	-\$24.3 M	-\$30.4 M	-\$1.2 M	-\$1.6 M	-\$1.9 M	
Total Incremental Cost (PV)	\$118.4 M	\$157.2 M	\$196.0 M	s.13,s.17			
CUSTOMER SERVICE ACCOL	JNT						
Travel Time Savings (PV)	\$172.2 M	\$172.2 M	\$172.2 M	\$23.8 M	\$23.8 M	\$23.8 M	
Vehicle Operating Savings (PV)	\$11.1 M	\$11.1 M	\$11.1 M	\$7.0 M	\$7.0 M	\$7.0 M	
Hwy 17 / Truck Access Signal Travel Time Costs (PV)	-	-	-	-\$2.2 M	-\$2.2 M	-\$2.2 M	
Hwy 17 / Truck Access Signal Veh. Operating Costs (PV)	-	-	-	-\$0.2 M	-\$0.2 M	-\$0.2 M	
Safety (PV)	\$6.5 M	\$6.5 M	\$6.5 M	N/A	N/A	N/A	
Total Incremental Benefits (PV)	\$189.8 M	\$189.8 M	\$189.8 M	\$28.4 M	\$28.4 M	\$28.4 M	
KEY ECONOMIC INDICATORS	5						
Net Present Value	\$71.4 M	\$32.6 M	-\$6.2 M	\$9.0 M	\$2.6 M	-\$3.8 M	
Benefit-Cost Ratio	1.6	1.2	1.0	1.5	1.1	0.9	



## 6.0 Potential Risks

In addition to the sensitivity analysis, it is important to identify potential risks to project cost and schedule. Some of the risks that have been identified are summarized in **Table 6.1.** A detailed project risk register for Highway 1 6 Laning is included in Appendix A of the original Parsons *Highway 1 Widening (216 Street to Highway 11) Business Case* found in **Appendix A** of this report.

Table 6.1: Potential Risks and Mitigation Measures

Potential Risks	Risk Description and Mitigation
Geotechnical	This area is well understood from a geotechnical perspective as a result of the Port Mann Highway 1 and South Fraser Perimeter Road projects. Preloading is anticipated in response to the soft soils in this area and this will be adequately advanced in the construction to limit any schedule delays.
Traffic Management	The construction delivery will include detour ramps and a detailed traffic management plan to reduce mobility impacts for Highway 1 users.
Property	No property is required for Highway 1 improvements as they will be contained within the existing right-of-way, therefore avoiding concerns around escalation. Property for Truck Parking Facility is already owned by the Crown.
Utilities	A Fortis Gas line exists in the Highway 1 project area. A mitigation strategy will be developed as part of the pre-load design to avoid impact.
Environmental	Detailed environmental assessments will be undertaken during the functional design stage. The Ministry will work closely with other agencies to develop an appropriate Environmental Protection Plan.
CP Rail Crossing Replacement	The Ministry will initiate discussions early with CP Rail to address design and detour needs for the project, avoiding any scheduling impacts and limiting service disruption.
First Nations	First Nations have been engaged regarding the Truck Parking Facility and there is interest in pursuing First Nations training and development opportunities as part of this project. Ongoing engagement is also occurring with impacted First Nations as part of the current Highway 1 / 216 Street Interchange Project out for tender which has allowed the Province to develop a positive relationship with the local First Nations.



# 7.0 Advancement of Provincial & Federal Transportation Strategies and Plans

Established in 1988, the National Highway System (NHS) is defined by routes that provide for interprovincial and international trade/travel by connecting capital cities, major provincial populations, commercial centres, ports of entry, and other transportation modes. As part of the NHS, the Highway 1 segment between 216 Street and 264 Street is a key link to trade and tourism.

A number of Provincial transportation strategies and Federal transportation policies support transportation improvements to provide safe, efficient and reliable movement of peoples and goods, as well as advancement of partnering relationships as they relate to transportation investment. The proposed projects are anticipated to result in benefits that are well aligned with the goals of both Federal and Provincial transportation strategies and plans including:

- BC on the Move 10 Year Transportation Plans (Provincial) In support of accommodating the movement of people, goods and services in British Columbia, the provincial government's BC On the Move 10 Year Transportation Plan identified the commitment to improve highway capacity and reliability with the widening of Highway 1 between Langley and Abbotsford. Consistent with this priority, BC On the Move also identified a commitment to work with industry to identify and construct at least two new truck parking areas nearby key highway corridors in the Lower Mainland. Truck parking facilities support mobility and reliability investments on BC's highways by providing convenient and accessible areas to enable commercial vehicles to park and access appropriate amenities.
- The Pacific Gateway Transportation Strategy 2012 2020 (Provincial) The goal of this strategy is to ensure that British Columbia is the preferred North American gateway for Asia Pacific trade through expanding the Province's transportation network, while generating sustainable economic growth and additional jobs. Recognizing the importance of both Highway 1 and convenient drayage truck parking to the Asia Pacific gateway, the proposed improvements are certainly well aligned with this particular strategy.
- Partnering for the Future A Transportation Vision for Canada (Federal) In addition to BC on the Move, this Federal strategy also supports the advancement of partnering relationships as they relate to transportation investment. The continued expansion of cost-sharing initiatives between the Government of Canada and the Province of British Columbia is supported by both levels of government as an effective means to ensuring continued economic growth and quality of life improvements for all Canadians.
- Asia-Pacific Gateway and Corridor Initiative (Federal) Led by Transport Canada, the goals of the Asia-Pacific Gateway and Corridor Initiative is to improve the efficiency and reliability of the gateway for Canadian and North American exports and imports and ensure travel routes are safe and open to through traffic, while minimizing environmental impacts. Thus, improvements to the segment of Highway 1 as well overall increases in drayage truck parking near the Port of Vancouver gateway would be consistent with federal transportation strategies and may be eligible for specific federal funding sources.



- Road Safety Strategy 2015 (Federal) The goal of this initiative is to reduce fatalities and serious injuries caused by collisions on Canada's roads through a number of strategies including road infrastructure improvements and collaboration among governmental and non-governmental organizations. The proposed improvements will be designed to meet Provincial design and safety standards. Geometric improvements at the 232 Street interchange will be made to not only address current mobility issues, but also safety issues.
- Partnering for the Future A Transportation Vision for Canada (Federal) In addition to BC on the Move, this Federal strategy also supports the advancement of partnering relationships as they relate to transportation investment. The continued expansion of cost-sharing initiatives between the Government of Canada and the Province of British Columbia is supported by both levels of government as an effective means to ensuring continued economic growth and quality of life improvements for all Canadians.

## 8.0 Corridor Performance Measures

As part of the Province's commitment to accountability under the Capital Asset Management Framework (CAMF), MoTI is expected to measure and report on the performance of its completed capital project. To support this commitment, performance measures must be developed for the recommended option at the planning and programming stage of a project. Actual performance then needs to be measured and reported on post-construction<sup>3</sup>.

For this project, performance measures were developed for the Customer Service account identified in **Section 4.0.** Additionally, truck parking facility targets were identified. Performance measures are summarized in **Table 8.1.** 

<sup>&</sup>lt;sup>3</sup> Guidelines for Preparing MoTI Business Cases, Appendix 6, Performance Measures for MoTI Business Case (November, 2015)



Table 8.1: Performance Measure Summary

Strategic Objective	Performance Measure	Method of Measurement
Customer Service – Mobility	<ul> <li>Monitor levels of service and highway capacity.</li> <li>1. Highway 1 (216 Street to 264 Street) <ul> <li>Level of Service as calculated using the Highway Capacity Manual for freeway segments; LOS is not to exceed LOS E for any extended freeway segment. Current LOS is E / F for all of the study segments during the AM or PM peak hours.</li> <li>Travel Time during the weekday AM and PM peak periods in both the eastbound and westbound directions of travel should be within 30% of free flow speeds.</li> <li>Between 200 St and 264 Street, free flow speed = 8.7 minutes and current travel time is approximately 14 to 15 minutes (EB in PM peak)</li> </ul> </li> <li>2. Highway 17 / Truck Access Signal <ul> <li>Signal delays for Highway 17 westbound through traffic (the sole signalized through movement) should not exceed LOS E in the weekday AM or PM peak hour.</li> </ul> </li> </ul>	TomTom historical traffic data; Ongoing data collection program.
Customer Service – Safety	<ul> <li>Reduce collision frequencies and reduce collision rates and severities to below current levels.</li> <li>Highway 1 (216 Street to 264 Street)         <ul> <li>Reduce collision frequency over the entire highway study section.</li> <li>Reduce the collision rate through segments currently identified as exceeding critical rates. Collision rate for corridor should not exceed provincial averages.</li> <li>Reduce collision severities through segments currently identified as exceeding critical rates as well as provincial averages for collision severity.</li> </ul> </li> </ul>	Collision data from the Ministry's Collision Infrastructure System.
Truck Parking Usage	<ul> <li>Facility usage</li> <li>80% of available parking stalls are used on a typical weekday</li> <li>Revenue neutral</li> <li>Full cost of facility operations borne by users</li> </ul>	Facility usage audits / spot inspections; full cost accounting.



## 9.0 Project Implementation and Recommendations

This Business Case is intended to examine the benefits and costs of six laning Highway 1 between the soon to be constructed 216 Street interchange and the 264 Street interchange as well constructing a new truck parking facility along Highway 17 near the Port Mann Bridge overhead. Overall, the improvements were found to address the issues identified in the problem definition stage as follows:

- Mobility Several segments on Highway 1 east of 200<sup>th</sup> Street currently operate with moderate delays during both weekday and weekend peak periods. As traffic volumes build on the corridor, these delays are expected to worsen. Adding additional lane capacity to the Highway will serve to improve operations over the short and longer-term, reducing delays for corridor travellers and improving overall levels of service in support of expected growth along the corridor over the next 25 years or so. Improving levels of service and ensuring a reliable travel experience is particularly important along Highway 1 as it is the primary corridor connecting Metro Vancouver and the Fraser Valley to the rest of the Province, and one of the primary channels for goods movement to / from the Port of Vancouver to national and international markets.
- Safety The study segment experiences a collision rate that on a whole is higher than the average for similar facilities around the province. Approximately 180 collisions are reported to police every year along Highway 1 between 216 Street and Highway 11, with a number of segments near interchanges recording historical collision rates that exceed critical levels. Improvements to the interchange configuration at 232 Street and widening the roadway to six lanes will provide safety benefits. The increase in lane capacity through the area can reduce aggressive driving behaviour and, in turn, reduce the risk of collisions.
- Clearance Standards and Interchange Geometry Most structures along this section of Highway 1 do not meet current clearance standards of 5.0m for large structures and 5.5m for lightweight structures. Moreover, the full cloverleaf design of the 232 Street (Highway 10) is no longer considered best practice as a result of the short weave and merge sections near the interchange. The improvement project will result in a full replacement of existing substandard underpasses at the CP Rail crossing, Glover Road, and 232 Street. The 232 Street interchange will be restructured as a Parclo configuration and will include an additional Highway 1 underpass at 72 Avenue.
- Insufficient Truck Parking The Port of Vancouver and associated industries rely heavily on medium distance drayage trucking to facilitate the movement of goods across the region and to / from key intermodal facilities. Within the City of Surrey there is little overnight parking available for trucks resulting in truck drivers spending significant time looking for parking. Through work undertaken by the City of Surrey, it was estimated that an additional 2,000 parking stalls are required to meet truck demands within the community. Constructing a new overnight full service truck parking facility on s.13,s.17 overhead will supply 158 additional truck parking stalls, addressing a critical regional and provincial need.



Highway 1 Six Laning and associated improvements were found to have an impressive **net present value** of \$32.6 M and a B/C ratio of 1.2 while the Truck Parking Facility was found to have a **net present value** of \$2.6 M and a B/C ratio of 1.1. As such, both projects reflect net positive economic benefits.

Benefits from the investment would accrue at the local and provincial and federal level. Partnership funding with the Federal Government for the proposed improvements is anticipated. The proposed project could be delivered either through traditional Design Bid Build or another method of Design Build or P3 arrangement. Highway 1 widening has been developed to a functional design level and Truck Parking Area to a conceptual level of detail. Further design work for each would begin in 2017-18, and the delivery for the truck parking area would be substantially complete by the end of fiscal year 2019-20, and by 2021-22 for the Highway 1 widening project as highlighted in **Table 9.1.** 

2017 - 18 2018 - 19 2019 - 20 2020 - 21 2021 - 22 Activity **Truck Parking** Project Detailed Design and Surveying **Environmental Assessment** Construction Permit Tender Start of on-site Construction **Substantial Completion Project Completion** Final Report Highway 1 **Project Functional & Detailed** Design and Surveying **Environmental Assessment** Construction Permit Tender Start of on-site Construction **Substantial Completion Project Completion** Final Report

Table 9.1: Estimated Project Schedule by Fiscal Year

The proposed improvements for the 232 Street interchange are expected to have significant municipal benefits in addition to the aforementioned benefits to the highway. Consistent with previous discussions with local agencies, the Township of Langley will be requested to fund s.13,s.17 of the project costs for the interchange. **Table 9.2** below summarizes the allocations between agencies assuming s.13 federal contributions toward eligible costs for the Highway 1 improvements s.13 for the 232 Street interchange) and truck parking facility. **Table 9.3** summarizes the anticipated cash flow for each item and agency based on the delivery timeframe.



Table 9.2: Cost Allocations by Project Segment and Eligibility

Costs	Truck Parking	Highway 1 - 232nd Street Interchange	Highway 1 - 216th Street to 232nd Street Widening	Highway 1 - Widening WB East of 248 Overpass to 72nd Overpass	Highway 1 - Widening WB East 264th St Overpass to East of 248 St Overpass	Highway 1 Total Only	Highway 1 & Parking Area Total
A: Non-Eligible Costs							
Pre-development Activities	\$ 718,000	\$ 636,000-	\$ 636,000	\$ 159,000	\$ 159,000	\$ 1,590,000	\$ 2,308,000
Property Acquisition	s.13,s.17	\$ -					s.13,s.17
Administration & Other	\$ 3,352,000	\$ 5,214,000	\$ 4,694,000	\$ 1,271,000	\$ 660,000	\$ 11,839,000	\$ 15,191,000
Non-Eligible Costs Sub-Total	s.13,s.17	\$ 5,850,000	\$ 5,330,000	\$ 1,430,000	\$ 819,000	\$ 13,429,000	s.13,s.17
B: Eligible Costs							
Construction	\$ 20,160,000	\$ 55,500,000	\$ 54,100,000	\$ 13,287,000	\$ 7,757,000	\$ 130,644,000	\$ 150,804,000
Engineering	\$ 2,500,000	\$ 6,500,000	\$ 5,900,000	\$ 1,800,000	\$ 1,000,000	\$ 15,200,000	\$ 17,700,000
Environmental Mitigation	\$ 700,000	\$ -				\$ -	\$ 700,000
First Nations Consultation	\$ 350,000	\$ 800,000	\$ 800,000	\$ 600,000	\$ 300,000	\$ 2,500,000	\$ 2,850,000
Contingency	\$ 2,120,000	\$ 18,600,000	\$ 18,000,000	\$ 4,526,100	\$ 2,627,000	\$ 43,753,100	\$ 45,873,100
Eligible Costs Sub-Total	<i>\$ 25,830,000</i>	\$ 81,400,000	\$ 78,800,000	\$ 20,213,100	\$ 11,684,000	\$ 192,097,100	\$ 217,927,100
Project Total	\$ 30,000,000	\$ 87,250,000	\$ 84,130,000	\$ 21,643,100	\$ 12,503,000	\$ 205,526,100	\$ 235,526,100
Level of Contribution							

s.13



Table 9.3: Project Cash Flow by Fiscal Year

Costs	Previous Expenditures	2017 / 2018	2018 / 2019	2019 / 2020	2020 / 2021	2021 / 2022	TOTAL ALLOCATIONS
A: Non-Eligible Costs							
Pre-development Activities	\$ 2,138,000	\$ 85,000	\$ 85,000	\$ -	\$ -	\$ -	\$ 2,308,000
Property Acquisition	\$ -	s.13	\$ -	\$ -	\$ -	\$ -	s.13,s.17
Administration & Other	\$ -	\$ -	\$ 1,713,200	\$ 4,751,400	\$ 6,076,400	\$ 2,650,000	\$ 15,191,000
Non-Eligible Costs Sub-Total	<i>\$ 2,138,000</i>	s.13,s.17	\$ 1,798,200	<i>\$ 4,751,400</i>	\$ 6,076,400	\$ 2,650,000	s.13,s.17
B: Eligible Costs							
Construction	\$ -	\$ -	\$ 30,264,000	\$ 60,321,600	\$ 45,189,600	\$ 15,028,800	\$ 150,804,000
Engineering	\$ -	\$ 2,700,000	\$ 5,310,000	\$ 5,310,000	\$ 3,510,000	\$ 870,000	¢ 17 700 000
	Ψ -	\$ 2,700,000	\$ 5,510,000	\$ 3,310,000	¥ 3,310,000	\$ 670,000	\$ 17,700,000
Environmental Mitigation	\$ -	\$ -	\$ 350,000	\$ 350,000	\$ -	\$ 670,000	\$ 700,000
Environmental Mitigation First Nations Consultation	·					\$ - \$ 340,000	
	\$ -	\$ -	\$ 350,000	\$ 350,000	\$ -	\$ -	\$ 700,000
First Nations Consultation	\$ - \$ -	\$ - \$ 460,000	\$ 350,000 \$ 910,000	\$ 350,000 \$ 570,000	\$ - \$ 570,000	\$ - \$ 340,000	\$ 700,000 \$ 2,850,000
First Nations Consultation Contingency	\$ - \$ - \$ -	\$ - \$ 460,000 \$ 2,072,000	\$ 350,000 \$ 910,000 \$ 8,731,310	\$ 350,000 \$ 570,000 \$ 13,761,930	\$ - \$ 570,000 \$ 13,761,930	\$ - \$ 340,000 \$ 7,545,930	\$ 700,000 \$ 2,850,000 \$ 45,873,100

s.13



Appendix A

Highway 1 Widening (216 Street to Highway 11) Business Case. Parsons, 2016.

Page 61 of 262 TRA-2017-72242



## Highway 1 Widening (216 Street to Highway 11) Business Case

## **PARSONS**

SEPTEMBER 2016 - Version 2 SW1200SWF



## **TABLE OF CONTENTS**

EXEC	UTIVE	SUMMARY						
1.0	INTRO	ODUCTION	1					
2.0	PROE	BLEM STATEMENT	2					
3.0	IDEN	IDENTIFICATION & ANALYSIS OF OPTIONS						
	3.1	Mainline Capacity	4					
	3.2	Interchange Reconfiguration	13					
	3.3	Auxiliary / Climbing Lanes	35					
	3.4	Replacement / Upgraded Structures	39					
4.0	PROJ	ECT OBJECTIVES	40					
5.0	PROJ	ECT SCOPE STATEMENT	41					
	5.1	Project Work Breakdown Structure	41					
	5.2	Work Breakdown Structure Dictionary	42					
6.0	PROJ	ECT TIMELINE	46					
	6.1	Proposed Staging	46					
	6.2	Potential Schedule	48					
7.0	PROJ	ECT OUTCOMES AND BENEFITS	49					
	7.1	Evaluation Criteria	49					
	7.2	Evaluation of Highway 1 Widening Project	53					
8.0	PROJ	ECT PERFORMANCE MEASURES	64					
9.0	PROJ	ECT RISK MANAGEMENT	66					
	9.1	Risk Management Planning Methodology	66					
	9.2	Project Risks and Response Strategies	68					
10.0	LEGA	L REQUIREMENTS	71					
11.0	PROJ	ECT BUDGET	72					
	11.1	Project Cost Estimate	72					
	11.2	Potential Project Cost Sharing and Cash Flow Projection	72					
12.0	CONC	CLUSIONS	74					





## **APPENDICES**

Appendix A Project Risk Management Register

Appendix B Project Cost Estimate

Appendix C Environmental & Aboriginal Consultation Information

Requirements





#### **EXECUTIVE SUMMARY**

This business case focuses on the section of Highway 1 from 216 Street to Highway 11. A number of highway segments along this section of Highway 1 currently operate at the lower end of acceptable Levels of Service for a major highway facility during the weekday peak periods and the peak periods on the weekends. These problematic highway segments are characterized by lower than free flow speeds, relatively high vehicle density, limited freedom to maneuver, and nonrecurring congestion resulting from minor incidents / disruptions in the traffic stream. In the short and long term future, the majority of this section of highway is projected to have insufficient capacity to meet the forecasted travel demands.

A number of existing structures along the section of Highway 1 do not meet current guidelines for clearance above a roadway (5.0 m for large structures, 5.5 m for lightweight structures); with the most critical being the Glover Road underpass and the Roberts Bank Rail Corridor (CP Rail) underpass tunnel portals. These structures, which are at risk of vehicle impact, include the following:

- Glover Road underpass structure: 4.46 m;
- Roberts Bank Rail Corridor underpass tunnel portals: 4.40 m;
- 232 Street underpass structure: 4.62 m;
- 264 Street underpass structure: 4.60 m;
- Peardonville Road underpass structure: 4.92 m.

Several interchanges within this section of Highway 1 currently incorporate configurations that are no longer considered best practices to accommodate high traffic volumes. The interchanges at 232 Street and 264 Street have cloverleaf configurations that can give rise to conflicts due to the short weaving section separating high speed entry / exit points.

To address these issues, the Highway 1 Widening Project proposes to include widening of Highway 1 by adding one lane in each direction into the median from 216 Street to Highway 11. The project will include the demolition of existing underpasses and reconfiguration of two interchanges, the 232 Street interchange and the 264 Street interchange. In addition, to accommodate the Highway 1 widening, a number of grade separated crossing will need to be upgraded to achieve added crossing width and / or higher clearance under the overpass structures.





The scope of the Highway 1 Widening Project will also include the following key elements:

- Demolition and reconstruction of the Glover Road underpass structure;
- Demolition and reconstruction of the rail underpass structures at the CP Rail lane (Roberts Bank Corridor);
- Widening of the two overhead structures at Bradner Road;
- Upgrade of the entrance and exit ramps to the Bradner Rest Area along the westbound lanes of Highway 1;
- Demolition and reconstruction of the Peardonville Road underpass structure;
- New structure for the eastbound off-ramp to Highway 11; and
- Upgrade of the Highway 11 on-ramp to Highway 1 eastbound.

To provide the Ministry of Transportation and Infrastructure with some implementation flexibility in widening Highway 1, the corridor was divided into multiple segments based on the priority of construction and related costs. The segmentation or construction packages have been developed such that they can be delivered individually or bundled together into various combinations. The following segmentation / construction packages are proposed.

#### Package 1: 232 Street Interchange

This package would involve reconfiguring the 232 Street interchange to allow a new underpass structure to be constructed and the existing structure to be removed. As part of this work, the proposed 72 Avenue underpass would be constructed. Only localized widening of Highway 1 would be included, but any additional lanes on Highway 1 would not be opened to traffic.

#### Package 2: 264 Street Interchange

This package would involve reconfiguring the 264 Street interchange to allow a new underpass structure to be constructed and the existing structure to be removed. Only localized widening of Highway 1 would be included, but any additional lanes on Highway 1 would not be opened to traffic.

#### Package 3: Highway 1 Widening from 216 Street to 232 Street

This package would involve widening Highway 1 between the recently constructed interchange at 216 Street and the recently constructed 232 Street interchange (Package 1), a distance of approximately 2.1 kilometres. The widening would include development of the westbound HOV lane and transition from three to two general purpose lanes in the westbound direction. This package would also involve the

PARSONS



complex removal of the box structures at the CP Rail crossing and construction of a new rail bridge. Removal and construction of a new Glover Road overpass is also included in this construction package.

#### Package 4: Highway 1 Widening from 232 Street to 264 Street

Only highway widening, over a length of approximately 5.8 kilometres, is involved in this construction package. The widening would encompass the segment of highway, in both directions of travel, between the recently constructed 232 Street interchange (Package 1) and the 264 Street interchange (Package 2). No new structures or modifications to existing structures are included in this segment.

#### Package 5: Highway 1 Widening from 264 Street to Mt. Lehman Road

Widening the highway in both directions of travel between the recently constructed 264 Street interchange and the existing Mt. Lehman Road interchange represents the majority of the scope in this package. However, widening of the Bradner Road overhead structures is included as is the upgrade of the entrance and exit ramps to the Bradner Rest Area.

#### Package 6: Highway 1 Widening from Mt. Lehman Road to Highway 11

This construction package involves approximately 9.7 kilometres of widening of Highway 1 between the Mt. Lehman Road interchange and the Highway 11 interchange. Removal and construction of the new Peardonville Road underpass structure and associated municipal road works are included in this construction package. The new eastbound off-ramp structure to Highway 11 and reconfiguration of the eastbound on-ramps from Highway 11 are also included.

As mentioned above, the proposed construction packages described above have been developed to allow flexibility in the delivery of the overall project. Separately, each construction package has been sized such that each package can be easily delivered under a conventional design bid build approach using local construction firms. However, one or more of the construction packages could be bundled together as a larger conventional design bid build contract, or as a design build delivery. Further bundling of the construction packages could lead to two or even three design build alternative delivery packages. Finally, the overall project could be delivered as a single contract under a public private partnership approach.

Furthermore, if bundling of the constructions packages is considered, then it is assumed that production related efficiencies would result and the overall schedule, shown in *Figure ES.1*, would be reduced.



Figure ES.1: Proposed Schedule

The project cost estimate, shown in *Table ES.1*, is similarly divided into the project elemental tasks and grouped by the six work packages.

Table ES.1: Project Cost Estimate Summary

	Highway 1 Widening Cost Estimate Summary								
	Package 1	Package 2	Package 3	Package 4	Package 5	Package 6	Total		
Project Management	4.5	3.4	4.1	3.5	6.5	8.3	30.3		
Engineering	6.5	5.2	5.9	5.7	10.6	12.9	46.8		
Grade Construction	14.1	15.3	15.6	31.8	55.1	43.6	175.0		
Structural	33.7	19.1	31.6	0.0	7.0	39.5	130.9		
Paving Construction	1.9	2.8	2.2	5.6	9.2	7.5	29.2		
Operational Construction	0.8	0.7	0.4	1.3	1.6	2.2	6.9		
Utilities	0.6	0.4	0.2	0.1	0.6	1.4	3.3		
Resident Engineering	4.4	3.3	4.1	3.5	6.5	8.2	30.0		
Contingency (30%)	19.9	15.1	18.5	15.5	29.1	37.1	135.0		
Total (\$M)	86.4	65.3	82.5	67.0	126.2	160.7	588.3		
Total (rounded) \$M	87	66	83	67	127	161	591		

A calculation of the potential funding for this project from Infrastructure Canada is based on eligible project costs. For provincially-owned assets, Federal Funding of 50 percent of the total eligible costs is requested. The funding contribution calculation is shown in *Table ES.2*.

SW1200SWF Page iv PARSONS



Table ES.2: Project Cash Flow Projections

Cost Type	7	2016/17		2017/18		2018/19		2019/20		2020/21	2021/22	2022/23	2023/24		Total
A: Non-Eligible Costs	: Non-Eligible Costs														
Project Management		\$50,000		\$600,000		\$1,000,000		\$1,500,000		\$1,400,000	\$1,800,000	\$1,500,000	\$800,000	\$	8,700,000
Planning	\$	250,000												\$	250,000
Environmental														\$	
Stakeholder Relations			\$	120,000	\$	180,000	\$	230,000	\$	210,000	\$ 260,000	\$ 210,000	\$ 120,000	\$	1,400,000
Corporate Services														\$	-
Engineering	\$	200,000												\$	200,000
Propety Acquisition														\$	-
Regional Recoveries														\$	-
Contingency	\$	150,000	\$	200,000	\$	400,000	\$	500,000	\$	500,000	\$ 600,000	\$ 500,000	\$ 300,000	\$	3,200,000
Sub-Total	\$	650,000	\$	900,000	\$	1,600,000	\$	2,230,000	\$	2,100,000	\$ 2,700,000	\$ 2,200,000	\$ 1,200,000	\$	13,600,000
B: Eligible Costs															
Engineering External			\$	16,600,000	\$	8,400,000	\$	7,900,000	\$	14,600,000	\$ 18,100,000			\$	65,600,000
Environmental External (included in Engineering)														\$	-
Construction Supervision			\$	1,800,000	\$	3,400,000	\$	4,600,000	\$	3,800,000	\$ 5,000,000	\$ 7,400,000	\$ 4,100,000	\$	30,100,000
Construction (Road and Bridge)			\$	20,400,000	\$	39,600,000	\$	54,400,000	\$	44,400,000	\$ 56,200,000	\$ 83,900,000	\$ 47,100,000	\$	346,000,000
First Nations Consultation & Accomodation			\$	80,000	\$	150,000	\$	200,000	\$	170,000	\$ 220,000	\$ 320,000	\$ 180,000	\$	1,300,000
Contingency			\$	11,700,000	\$	15,500,000	\$	20,100,000	\$	18,900,000	\$ 23,900,000	\$ 27,500,000	\$ 15,400,000	\$	133,000,000
Sub-Total	\$	-	\$	50,600,000	\$	67,100,000	\$	87,200,000	\$	81,900,000	\$ 103,400,000	\$ 119,100,000	\$ 67,000,000	\$	576,300,000
TOTAL	\$	650,000	\$	52,000,000	\$	69,000,000	\$	90,000,000	\$	84,000,000	\$ 107,000,000	\$ 122,000,000	\$ 69,000,000	\$	590,000,000
Federal Contribution	\$	-	\$	25,300,000	\$	33,550,000	\$	43,600,000	\$	40,950,000	\$ 51,700,000	\$ 59,550,000	\$ 33,500,000	\$	288,150,000

PARSONS



*Table ES.3* provides an "at-a-glance" summary of the multiple account evaluation for the Highway 1 Widening Project versus a "No Build" or "Do Nothing" option.

Table ES.3: Evaluation Summary

Criterion/Option	No Build	Highway 1 Widening								
Customer Service Account										
Travel Time	Highway is congested during peak and off peak periods. It is anticipated that these conditions will worsen in the short and long term futures.	Improved traffic performance will result in Travel Time Savings of approximately \$65 M / year by 2041 Total Travel Time Savings: \$334 M								
Vehicle Operating Costs	Highway is congested during peak and off peak periods. It is anticipated that these conditions will worsen in the short and long term futures.	Improved traffic performance will result in less delays that translate into Vehicle Operating Cost savings of approximately \$3.5 M / year by 2041 Total VOC Savings: \$23 M								
Road Safety Performance	Road Safety Performance is poor compared to provincial average	Improved Road Safety Performance resulting in a reduction of 400 crashes from 2025 to 2041 Total Road Safety Savings: \$14 M								
Environmental Account										
Terrestrial Impacts	NA	Low impact								
Aquatic Impacts	NA	Low impact								
Archaeological / Historical Impacts	NA	Low impact								
Financial Account										
Capital Cost (\$2016)	NA	-\$449.0 M								
Maintenance and Rehabilitation Cost (\$2016)	-\$8.2 M	-\$5.4 M								
Salvage Value (\$2016)	NA	\$83.7 M								
Net Present Value (\$2016)	NA	0.5 M								
Overall Benefit Cost Ratio	NA	1.00								

**PARSONS** 



### 1.0 INTRODUCTION

The Highway 1 study section extends from 216 Street in the Township of Langley to Whatcom Road in the City of Abbottsford. However, the enclosed business case focuses only on the section of Highway 1 from 216 Street to Highway 11. The remaining segment, between Highway 11 and Whatcom Road in the City of Abbotsford is the subject of a further study.

The business case also assumes that the proposed interchange at 216 Street will be constructed separately from and prior to the scope of work proposed under the Highway 1 widening project. The 216 Street interchange project includes the extension of the median HOV lanes further east of the current terminus at the 202 Street interchange. The Highway 1 widening project will tie into the local widening of the highway which forms part of the 216 Street interchange project.

Within the study limits, the Highway 1 section consists of a four lane freeway with two lane carriage ways separated by a wide depressed median. Full movement interchanges are located along the highway section at:

- 232 Street (Highway 10);
- 264 Street (Highway 13);
- Mt Lehman Road;
- Clearbrook Road;
- McCallum Road; and
- Highway 11.

Further east, past Highway 11, only the Whatcom Road interchange is included in the remaining highway segment which will be assessed as part of the further study.

Existing auxiliary / climbing lane segments are located along the highway in the eastbound direction between the 232 Street interchange and the 264 Street interchange for a total length of approximately 6.4 km, in the westbound direction east of Mt. Lehman Road for a total length of approximately 2.2 km, and in the westbound direction between Highway 11 and immediately west of the McCallum Road interchange for a total length of approximately 2.6 km.





# 2.0 PROBLEM STATEMENT

A number of highway segments along the section of Highway 1 between 216 Street and Highway 11 currently operate at the lower end of acceptable Levels of Service for a major highway facility during the weekday peak periods and the peak periods on the weekends. These problematic highway segments are characterized by lower than free flow speeds, relatively high vehicle density, limited freedom to maneuver, and nonrecurring congestion resulting from minor incidents / disruptions in the traffic stream. In the short and long term future, the majority of this section of highway is projected to have insufficient capacity to meet the forecasted travel demands.

This section of Highway 1 also has a collision rate that is higher than the average for similar facilities around the province. Common collision types include rear end collisions and off road collisions, with contributing factors such as driver inattention, following too closely, alcohol involvement and fatigue. In addition to the direct collision costs are significant delay costs that occur when the highway lanes are blocked due to an incident. With approximately 180 collisions reported to police every year, this means there is a reportable collision every two days along this section of the Highway 1 corridor.

A number of existing structures along the section of Highway 1 do not meet current guidelines for clearance above a roadway (5.0 m for large structures, 5.5 m for lightweight structures); with the most critical being the Glover Road underpass and the Roberts Bank Rail Corridor (CP Rail) underpass tunnel portals. These structures, which are at risk of vehicle impact, include the following:

- Glover Road underpass structure: 4.46 m;
- Roberts Bank Rail Corridor underpass tunnel portals: 4.40 m;
- 232 Street underpass structure: 4.62 m;
- 264 Street underpass structure: 4.60 m;
- Peardonville Road underpass structure: 4.92 m.

Several interchanges within this section of Highway 1 currently incorporate configurations that are no longer considered best practices to accommodate high traffic volumes. The interchanges at 232 Street and 264 Street have cloverleaf configurations that can give rise to conflicts due to the short weaving section separating high speed entry / exit points. Although the configuration of the weave operation is mitigated somewhat by physical separation from the mainline, the combination of the short weaving distance, presence of heavy trucks, and high speed / high volume traffic may contribute to the relatively high collision frequencies at these interchanges.





In summary, the following issues are currently found or are forecast to occur within this section of Highway 1:

- Limited or insufficient capacity during the weekday AM and PM peak periods along most segments of the Highway 1 section between 216 Street and Highway 11;
- High collisions rates that exceed other similar provincial facilities;
- Vertical clearance issues at a number of existing structures including Glover Road,
   CP Rail overpass / portal, 232 Street, 264 Street, and Peardonville Road; and,
- Interchange configurations that no longer operate well under the higher traffic volumes experienced today or forecasted in the future planning horizon.



# 3.0 IDENTIFICATION & ANALYSIS OF OPTIONS

The development of the project scope to address the various issues was conducted with a primary focus on adding capacity to the section of Highway 1 between 216 Street in the Township of Langley and Highway 11 in the City of Abbotsford. To accommodate any additional capacity within this section of highway, primarily in the form of an additional lane in each direction of travel, other constraints within the highway corridor needed to be upgraded. These constraints included a number of existing overpass structures and underpass structures as well as topography within this section of highway that could potentially impact the available capacity. Therefore, a systematic process was conducted to develop options or solutions for the following four areas:

- · Mainline Capacity;
- · Interchange Reconfiguration;
- · Climbing Lanes; and
- Replacement Structures.

# 3.1 Mainline Capacity

To address the identified road capacity, geometric design, and road safety problems facing Highway 1 between 216 Street and Highway 11, a number of optional solutions were generated. These options are described and evaluated below.

#### 3.1.1 GENERATED OPTIONS

As identified in the Problem Statement, additional mainline capacity is required along the length of the subject section of highway. To provide this additional capacity in the form of an additional eastbound and westbound lane, the method of widening the highway was selected to be through the median given the space availability. The critical issues to address, however, were how to designate the additional capacity (i.e. make the lane accessible to all traffic or restrict its use to selected vehicles), and if there were a difference between the lane designation at either end, how to safely and efficiently manage the transitions.



Four mainline widening options were developed, as described below:

- Mainline Option 1: Provide One New General Purpose (GP) Lane in Each Direction Between 202 Street and Highway 11:
  - In this option, one new general purpose lane will be added to Highway 1 in each direction between 202 Street and Highway 11. Specifically,
  - In the westbound direction, the westbound on-ramp from Highway 11 will form the third lane of the highway, with all lanes designated for general purpose traffic. The three westbound general purpose lane cross-section will continue to 200 Street where the slow lane will drop at the existing westbound off-ramp. A median High Occupancy Vehicle (HOV) lane will develop approximately 1 km east of 202 Street, to tie in with the existing HOV facilities on Highway 1 westbound.
  - o In the eastbound direction, the median HOV lane through 202 Street will terminate at approximately 1 km east of 202 Street, where the HOV lane designation will end and a three general purpose lane cross-section will be provided. The existing climbing lane between Highway 10 and Highway 13 may be preserved as a fourth eastbound lane. At the east end of the study corridor, the eastbound right lane will end approximately 1 km east of the Highway 11 eastbound on-ramp to preserve lane balance through the Highway 11 interchange. Two GP lanes will continue east of the Highway 11 interchange, as per existing conditions.
- Mainline Option 2: Provide One New High Occupancy Vehicle (HOV) Lane in Each Direction Between 202 Street and Highway 11:
  - In this option, an additional travel lane will be provided to Highway 1 in each direction between 202 Street and Highway 11 for the use of High Occupancy Vehicles (2+ Occupants) and Buses Only. Specifically,
  - In the westbound direction, the HOV lane will develop in the median approximately 1 km west of Highway 11. The two GP and one HOV lane cross-section will continue westbound and connect to the existing crosssection at 202 Street, which also consists of two general purpose lanes and one HOV lane.
  - In the eastbound direction, the median HOV lane through 202 Street will be carried through to approximately 1 km east of the Highway 11 eastbound on-ramp to preserve lane balance through the Highway 11 interchange, where the HOV lane designation will end. The existing climbing lane between Highway 10 and Highway 13 may be preserved as a fourth eastbound lane. There will be a short four-lane segment east of

SW1200SWF Page 5 PARSONS



McCallum Road where the eastbound deceleration lane for the off-ramp to Highway 11 is located. Two GP lanes will continue east of the Highway 11 interchange, as per existing conditions.

 For consistency with the remainder of the Highway 1 corridor, the HOV lane will have a full-time designation.

s.13




SW1200SWF

- Mainline Option 4: Provide One New General Purpose (GP) Lane in Each Direction Between Glover Road and Highway 11, Extend Existing HOV Lanes to Highway 10 with GP Lane Overlap, Provide New East Facing Ramps to / from Glover Road:
  - In this option, one new general purpose lane will be added to Highway 1 in each direction between Glover Road and Highway 11. In addition, the existing HOV lanes currently starting / ending at 202 Street will be extended eastward to Highway 10 with approximately 2 km of overlap with the new general purpose lanes. New east facing ramps to / from Glover Road will be provided also, giving a more direct access to / from the Trinity Western University Campus and Fort Langley, as well as reducing traffic volume on the mainline between Glover Road and 216 Street. Specifically,
  - o In the westbound direction, the westbound on-ramp from Highway 11 will form the third lane of the highway, with all lanes designated for general purpose traffic. The three westbound general purpose lane cross section will continue to approximately 1 km west of Glover Road, where the westbound right lane will end. A westbound off-ramp to Glover Road will be provided at 1 km east of Glover Road. Also, a westbound HOV lane will develop in the median, approximately 1 km east of Highway 10 creating a four-lane segment. The HOV lane and two general purpose lanes will continue westward and connect to the existing cross-section at 202 Street, which also consists of two general purpose lanes and one HOV lane.
  - o In the eastbound direction, the median HOV lane through 202 Street will be carried through the new Glover Road eastbound on-ramp and to approximately 1 km east of the Highway 10 interchange, where the HOV lane designation will end and a three general purpose lane cross-section will be provided. The existing climbing lane between Highway 10 and Highway 13 may be preserved as a fourth eastbound lane. At the east end of the study corridor, the eastbound right lane will end approximately 1 km east of the Highway 11 eastbound on-ramp to preserve lane balance through the Highway 11 interchange. Two GP lanes will continue east of the Highway 11 interchange, as per existing conditions.

The potential lane balancing options along the mainline using single line sketches are illustrated in *Figure 3.1* below.

Page 7 PARSONS








Figure 3.1: Mainline Capacity Improvement Options Schematics (Not to Scale)



#### 3.1.2 EVALUATION CRITERIA

For the purpose of evaluating the Highway 1 widening options, three specific and relevant evaluation criteria were identified, namely highway usage, capacity, and operations performance. The evaluation included a quantitative evaluation using TransLink's Regional Transportation Model (RTM) to forecast travel demand and capacity performance, as well as a qualitative review of operations performance based on the lane designations and management of transition of the designations at either end of the corridor. The planning horizon for evaluating the mainline widening options was chosen as the RTM planning horizon of 2045.

The option evaluation criteria are presented below.

## Highway Usage

The highway usage criterion considered the effectiveness of the HOV lane designations in serving the HOV traffic and in reducing congestion. If the forecast HOV demand derived from the RTM is not anticipated to be significantly high, the additional lane should not be restricted to HOV users but available to all users to improve traffic conditions in the general purpose lanes.

Transit vehicles are allowed in HOV lanes. However, as the forecast demand is expected to be low (with 10 buses in the AM and PM Peak Hours), transit accommodation was not considered as a part of the highway usage criterion.

#### Capacity

The capacity criterion considered quantitatively whether the lane designations and the management of the transition of the lane designations at either end of the corridor are adequate to meet the corresponding forecast demand. The highest volume-to-capacity ratios of each segment, as obtained from the RTM, were assessed.

#### Operations Performance

The operations performance criterion considered qualitatively whether traffic will operate efficiently given the lane designations and management of the transition of the lane designations at either end of the corridor in each option.



#### 3.1.3 OPTION EVALUATION

An assessment of the four mainline capacity improvement options was undertaken to select a preferred option that will best suit the long-term needs of the corridor based of the selected assessment criteria, highway usage, capacity, and operations performance. The option assessment results are presented below.

## Highway Usage

The mainline capacity options were evaluated using the RTM. The forecast AM and PM Peak Hour total demand and HOV demand of each segment are summarized in *Table 3.1* below. Also presented in the table are the highest volume-to-capacity ratios of each segment using colours, with orange and red indicating segments with capacity issues.

Table 3.1: 2045 AM and PM Peak Hour Forecast Demand (Using Emme Capacity Assumptions)

Scenario		Direction	202 St - 2	216 St	216 St - 2	232 St	232 St - 2	264 St	264 St - Lehm	Mt nan	Mt Lehr Clearbr		Clearbro McCall		McCallum - 11	Hwy
			Total Veh	HOV	Total Veh	HOV	Total Veh	HOV	Total Veh	HOV	Total Veh	HOV	Total Veh	HOV	Total Veh	HOV
	АМ	WB	3300	350	3150	350	3300	350	2950	300	3200	400	3600	400	3950	450
Base	AIVI	EB	3050	250	3350	300	3700	350	3150	300	2600	250	2950	300	2650	250
base	РМ	WB	3450	500	3200	450	3400	500	3050	450	2700	450	3200	550	3500	600
	PIVI	EB	3350	400	3700	500	4100	500	3650	450	3250	400	3600	400	3400	350
Mainline Option	^^	WB	3850	350	3750	400	3950	400	3500	350	3750	450	4050	450	4200	500
1 (A New GP	AIVI	EB	3300	300	3850	350	4150	350	3650	350	3000	300	3300	350	2900	300
Lane)	РМ	WB	3950	550	3750	500	4000	550	3550	500	3100	500	3500	550	3650	650
Lane)	PIVI	EB	3750	500	4350	550	4700	600	4400	550	3950	500	4300	500	3850	400
Mainline Option	A B.4	WB	3350	350	3250	400	3450	400	3100	350	3350	450	3650	500	3900	550
2 (A New HOV	AIVI	EB	3100	300	3400	350	3650	350	3250	300	2700	300	3000	300	2700	300
	РМ	WB	3500	500	3300	500	3550	500	3200	500	2850	500	3300	600	3500	650
Lane)	FIVI	EB	3400	450	3800	600	4050	600	3850	550	3500	500	3800	550	3600	450
Mainline Option	A B.4	WB	3400	350	3500	400	3800	400	3400	350	3700	450	4000	450	4150	500
3 (A New GP Lane	AIVI	EB	3150	300	3650	350	4000	350	3550	300	2950	300	3300	350	2900	300
+ HOV Extension)	DAA	WB	3600	500	3500	550	3850	550	3500	500	3050	500	3450	550	3600	650
+ HOV Extension)	PIVI	EB	3550	500	4050	600	4550	600	4300	550	3900	500	4250	500	3800	400
Mainline Option	A B.4	WB	3450	350	3700	450	3900	450	3500	350	3750	450	4000	450	4200	500
	VIAI	EB	3150	300	3800	400	4100	350	3600	350	3000	300	3300	350	2900	300
4 (A New GP Lane	D8.4	WB	3600	500	3750	600	3950	550	3550	500	3100	500	3450	550	3600	650
+ HOV Extension)	PIVI	EB	3550	500	4450	650	4700	600	4400	550	3950	500	4250	500	3850	400



The highest forecast HOV demand across the four options was 650 vehicles per hour. With this relatively low level of HOV demand, designating the additional lane for HOV use only throughout the study corridor will result in lane underutilization. In addition, in segments where the overall demand was forecast to exceed capacity, the HOV designation will create a negative impact on traffic congestion by increasing traffic volume in the General Purpose lanes. Also, as mentioned previously, because transit demand / service levels are anticipated to be low during peak periods where work trips prevail, an HOV lane is not warranted for transit service. Consequently, Option 2,

which will provide an HOV lane in each direction between 202 Street and Highway 11, was not considered a viable option and hence was not considered further in the evaluation process.

### Capacity

The highest volume-to-capacity ratios of each segment, shown in *Table 3.1* were extracted from the RTM using link capacity assumptions inherent in the RTM. The resultant volume-to-capacity ratios appeared to be conservative, with some of the segments exceeding 1.0 in all four options. However, if a theoretical capacity of 1700 vehicles per hour (vph) was assumed, instead of using the capacity assumptions in the RTM, the highest volume-to-capacity ratios of each segment will become lower, as presented in *Table 3.2* below.

Table 3.2: 2045 AM and PM Peak Hour Forecast Demand (Assuming Capacity = 1700 vph)

			202 St - 2	216 St	216 St - 2	232 St	232 St -	264 St	264 St -	Mt	Mt Lehr	nan -	Clearbro	oke -	McCallum -	Hwy
			202 3(-)	21030	2103(-)	232 31	252 50	20431	Lehman		Clearbrooke		McCall	lum	11	
Scenario		Direction	Total Veh	HOV	Total Veh	HOV	Total Veh	HOV	Total Veh	HOV	Total Veh	HOV	Total Veh	HOV	Total Veh	HOV
	АМ	WB	3300	350	3150	350	3300	350	2950	300	3200	400	3600	400	3950	450
Base	AIVI	EB	3050	250	3350	300	3700	350	3150	300	2600	250	2950	300	2650	250
	РМ	WB	3450	500	3200	450	3400	500	3050	450	2700	450	3200	550	3500	600
	PIVI	EB	3350	400	3700	500	4100	500	3650	450	3250	400	3600	400	3400	350
Mainline Option	484	WB	3850	350	3750	400	3950	400	3500	350	3750	450	4050	450	4200	500
	AIVI	EB	3300	300	3850	350	4150	350	3650	350	3000	300	3300	350	2900	300
1 (A New GP	РМ	WB	3950	550	3750	500	4000	550	3550	500	3100	500	3500	550	3650	650
Lane)	PIVI	EB	3750	500	4350	550	4700	600	4400	550	3950	500	4300	500	3850	400
Mainline Ontion	A B A	WB	3350	350	3250	400	3450	400	3100	350	3350	450	3650	500	3900	550
Mainline Option	Aivi	EB	3100	300	3400	350	3650	350	3250	300	2700	300	3000	300	2700	300
2 (A New HOV		WB	3500	500	3300	500	3550	500	3200	500	2850	500	3300	600	3500	650
Lane)	PM	EB	3400	450	3800	600	4050	600	3850	550	3500	500	3800	550	3600	450
14-i-li O-ti		WB	3400	350	3500	400	3800	400	3400	350	3700	450	4000	450	4150	500
Mainline Option		EB	3150	300	3650	350	4000	350	3550	300	2950	300	3300	350	2900	300
3 (A New GP Lane		WB	3600	500	3500	550	3850	550	3500	500	3050	500	3450	550	3600	650
+ HOV Extension)	PIVI	EB	3550	500	4050	600	4550	600	4300	550	3900	500	4250	500	3800	400
14-i-li O-ti		WB	3450	350	3700	450	3900	450	3500	350	3750	450	4000	450	4200	500
Mainline Option		EB	3150	300	3800	400	4100	350	3600	350	3000	300	3300	350	2900	300
4 (A New GP Lane		WB	3600	500	3750	600	3950	550	3550	500	3100	500	3450	550	3600	650
+ HOV Extension)	PM	EB	3550	500	4450	650	4700	600	4400	550	3950	500	4250	500	3850	400



According to the highest volume-to-capacity ratios in *Table 3.2*, the remaining options (Options 1, 3, and 4) will have capacity issues in the following segments:

# Option 1:

- Between 202 Street and 216 Street (eastbound); and
- o Between 232 Street and 264 Street (eastbound).

# Option 3:

- Between 202 Street and 216 Street (westbound and eastbound); and
- o Between 216 Street and 232 Street (westbound and eastbound).



### Option 4:

- Between 202 Street and 216 Street (westbound and eastbound);
- Between 216 Street and 232 Street (eastbound); and
- Between 232 Street and 264 Street (eastbound).

#### Operations Performance

In Option 1, a lane imbalance is created at the 200 Street westbound off-ramp (four lanes enter the ramp area and only three lanes carry through on the mainline), which is not desirable from a traffic operations perspective due to the forced lane changing in the vicinity of an off-ramp. This location at 200 Street is also a less appropriate place to drop a lane on a major interprovincial highway. Such a lane drop will potentially create operational issues as it will be unexpected by motorists continuing further west.

s.13

Option 4 is similar to Option 3, except for the new east facing ramps to / from Glover Road. However, the demand that will likely make use of the ramps was not considered sufficient (approximately 400 vph in the westbound direction and 600 vph in the eastbound direction) to justify the additional cost of providing a partial interchange at this location.

#### 3.1.4 RATIONALE FOR CHOSEN OPTION

Option 3 was determined to be the preferred widening option for the study highway section, s.13

This option was considered to offer the most appropriate balance between providing corridor capacity, accommodating special purpose lanes, as well as adding / removing lanes in a safe and efficient manner that is consistent with driver expectations.





# 3.2 Interchange Reconfiguration

To accommodate the additional lane in each direction of travel along the mainline, the existing overpass structures at the 232 Street and 264 Street interchanges require replacement as the current horizontal and vertical clearances are insufficient or substandard. Noting that the existing interchange configurations do not reflect current best practices given the high traffic volumes to be accommodated, and that the existing structures need to be replaced given the constraints mentioned above, a number of interchange reconfiguration options were developed. The preferred options would then form part of the Highway 1 widening project scope.

#### 3.2.1 GENERATED OPTIONS

#### 232 STREET / HIGHWAY 1 INTERCHANGE

For the interchange at 232 Street (Highway 10), several configuration options were developed to improve upon the deficient geometry associated with the existing cloverleaf interchange configuration as well as to accommodate future travel demand. A total of four improvement options were developed for the 232 Street interchange and are described as follows:

#### Option 1: Parclo B Interchange Configuration with Roundabouts

In this option, depicted in *Exhibit 3.1*, a Parclo B configuration forms the primary element of the interchange with loop ramps in the northwest quadrant and the southeast quadrant. A single exit point is proposed for the exit from Highway 1 eastbound and also for the exit from Highway 1 westbound.

The north ramp terminal would remain as a roundabout with the east leg connecting to 72 Avenue as per existing conditions. The loop ramp from Highway 1 westbound would connect directly to the roundabout to provide access to 72 Avenue (north) and 232 Street north. However, a bypass lane is proposed to allow a free flow westbound to southbound movement onto 232 Street as an add lane.

A roundabout is also proposed at the south ramp terminal which is also the junction between 232 Street and 72 Avenue (south). The eastbound loop ramp from Highway 1 is proposed to connect directly into the roundabout thus eliminating the need for the directional eastbound to southbound ramp. Access to Highway 1 eastbound would continue to use the short segment of 72 Avenue (south) east of 232 Street and the existing on-ramp connection to the eastbound highway lanes.



The new three lane structure across Highway 1 is proposed to be located to the east of the existing structure to allow traffic to continue across the existing structure during the construction period.

### Option 2: Parclo B Interchange Configuration

In this option, depicted in *Exhibit 3.2*, a Parclo B configuration forms the primary element of the interchange with loop ramps in the northwest quadrant and the southeast quadrant. A single exit point is proposed for the exit from Highway 1 eastbound and also for the exit from Highway 1 westbound.

The north ramp terminal would remain as a roundabout with the east leg connecting to 72 Avenue as per existing conditions. The loop ramp from Highway 1 westbound would connect directly to the roundabout to provide access to 72 Avenue (north) and 232 Street north. However, a bypass lane is proposed to allow a free flow westbound to southbound movement onto 232 Street as an add lane.

The single lane eastbound exit from Highway 1 is proposed to subsequently diverge into a directional ramp connection to 232 Street southbound and a loop ramp in the southeast quadrant to access 232 Street northbound – as an add lane.

Access to Highway 1 eastbound would continue to use the short segment of 72 Avenue (south) east of 232 Street and the existing on-ramp connection to the eastbound highway lanes. The existing at-grade intersection between 232 Street and 72 Avenue (south) would remain as per existing conditions.

The new four lane structure across Highway 1 is proposed to be located to the west of the existing structure to allow traffic to continue across the existing structure during the construction period.

# Option 3: Parclo B Interchange Configuration with 72 Avenue Flyover

In this option, depicted in *Exhibit 3.3*, a Parclo B configuration forms the primary element of the interchange with loop ramps in the northwest quadrant and the southeast quadrant. A single exit point is proposed for the exit from Highway 1 eastbound and also for the exit from Highway 1 westbound.

The north ramp terminal would remain as a roundabout as per existing conditions. The loop ramp from Highway 1 westbound would connect directly to the roundabout to provide access to 232 Street north. However, a bypass lane is proposed to allow a free flow westbound to southbound movement onto 232 Street as an add lane.





The single lane eastbound exit from Highway 1 is proposed to subsequently diverge into a single lane directional ramp connection to 232 Street southbound and a single lane loop ramp in the southeast quadrant to access 232 Street northbound — as an add lane. Access to Highway 1 eastbound would be reconfigured with a directional northbound to eastbound single lane ramp which will exit 232 Street north of the existing 72 Avenue (south) intersection. The southbound to eastbound movement, provided via a left turn movement at a new un-signalized intersection located north of 72 Avenue (south), would tie into the northbound to eastbound ramp prior to merging onto Highway 1.

The new four lane structure across Highway 1 is proposed to be located to the west of the existing structure to allow traffic to continue across the existing structure during the construction period. The new structure / 232 Street is orientated at a right angle to Highway 1 to minimize the overall length of the bridge. A new two lane flyover structure will provide continuity for 72 Avenue across Highway 1. The north leg of 72 Avenue, currently connecting to the north terminal roundabout, will be removed.

### Option 4: Split Diamond Interchange Configuration

In this option, depicted in *Exhibit 3.4*, the interchange exit and entrance ramps are connected to two cross streets. The east facing ramps to Highway 1 eastbound / from Highway 1 westbound are proposed to be connected to 72 Avenue which will cross Highway 1 over a new three lane east west orientated bridge structure. The west facing ramps to Highway 1 westbound / from Highway 1 eastbound are proposed to be connected to 232 Street which will cross Highway 1 over a new two lane north south orientated bridge structure.

For the highway ramp connections at 72 Avenue, the close proximity of the west ramp terminal intersection with respect to the overpass structure will require the westbound left turn lane to continue across the structure as a third lane.

The ramp terminal intersections along 232 Street, north and south of the highway, will be spaced to provide sufficient left turn storage away from the new bridge structure. This new bridge structure is proposed to be located to the west of the existing structure to allow traffic to continue across the existing structure during the construction period.

#### 264 STREET / HIGHWAY 1 INTERCHANGE

For the interchange at 264 Street (Highway 13), several configuration options were developed to improve upon the deficient geometry associated with the existing cloverleaf interchange configuration as well as to accommodate future travel demand. A total of four



improvement options were developed for the 264 Street interchange and these are described as follows:

## Option 1: Parclo B Interchange Configuration with Roundabouts

In this option, depicted in *Exhibit 3.5*, a Parclo B configuration forms the primary element of the interchange with loop ramps in the northwest quadrant and the southeast quadrant. A single exit point is proposed for the exit from Highway 1 eastbound and also for the exit from Highway 1 westbound.

The north ramp terminal would be reconstructed as a multi-lane roundabout junction connecting 264 Street and 56 Avenue. The single lane loop ramp from Highway 1 westbound would connect directly to the roundabout to provide access to 56 Avenue (north) and 264 Street north. However, a bypass lane is proposed to allow a free flow westbound to southbound movement onto 264 Street as an add lane. To reduce the complexity of the multi-lane roundabout, a bypass lane is also proposed for the northbound to eastbound movement.

A roundabout is also proposed at the south ramp terminal which is also the junction between 264 Street and 56 Avenue (south). The single lane loop ramp from Highway 1 eastbound is proposed to connect directly into the roundabout thus eliminating the need for the direct eastbound to southbound ramp. A bypass lane is proposed to allow a free flow westbound to southbound movement onto 264 Street as an add lane. Another bypass lane for the southbound to westbound right turn movement is proposed to maintain a single lane roundabout configuration. Access to Highway 1 eastbound would continue to be provided by the existing free flow directional ramp from Highway 13 northbound and from the south terminal roundabout for the 264 Street southbound left turn movement.

Access to Highway 1 westbound would be provided via 56 Avenue (north) where all movements would travel through the north ramp terminal junction / roundabout. The existing loop ramp in the northeast quadrant would be removed.

The new four lane structure across Highway 1 is proposed to be located to the west of the existing structure to allow traffic to continue across the existing structure during the construction period.

## Option 2: Parclo B Interchange Configuration

In this option, depicted in *Exhibit 3.6*, a Parclo B configuration forms the primary element of the interchange with loop ramps in the northwest quadrant and the southeast quadrant. A single exit point is proposed for the exit from Highway 1 eastbound and also for the exit from Highway 1 westbound.

SW1200SWF Page 16 PARSONS



The north ramp terminal would remain as a signalized intersection between 264 Street and 56 Avenue as per existing conditions. The loop ramp from Highway 1 westbound would connect directly to the intersection to provide access to 56 Avenue (north) and 264 Street north. However, a bypass lane is proposed to allow a free flow westbound to southbound movement onto 264 Street as an add lane.

The single lane loop ramp from Highway 1 eastbound is proposed to connect directly into the south ramp terminal signalized intersection, therefore eliminating the need for the direct eastbound to southbound ramp. To provide a free flow eastbound to northbound movement, the loop ramp will also be configured to connect to 264 Street as an add lane. Access to Highway 1 eastbound would continue to be provided by the existing free flow directional ramp from Highway 13 northbound and from the south terminal intersection for the 264Street southbound left turn movement.

Access to Highway 1 westbound would be provided via 56 Avenue (north) where all movements would travel through the north ramp terminal intersection at 264 Street. The existing loop ramp in the northeast quadrant would be removed.

The new four lane structure across Highway 1 is proposed to be located to the west of the existing structure to allow traffic to continue across the existing structure during the construction period.

# Option 3: Split Diamond Interchange Configuration

In this option, depicted in *Exhibit 3.7*, the interchange exit and entrance ramps are connected to two cross streets. The east facing ramps to Highway 1 eastbound / from Highway 1 westbound are proposed to be connected to 56 Avenue which will cross Highway 1 over a new three lane east west orientated bridge structure. The west facing ramps to Highway 1 westbound / from Highway 1 eastbound are proposed to be connected to 264 Street which will cross Highway 1 over a new two lane north south orientated bridge structure.

For the highway ramp connections at 56 Avenue, the close proximity of the west ramp terminal intersection with respect to the overpass structure will require the westbound left turn lane to continue across the structure as a third lane. A dedicated left turn and right turn lane are to be provided along the eastbound to east / west exit ramp. It is anticipated that both ramp terminals will be signalized.

The ramp terminal intersections along 264 Street, north and south of the highway, will be spaced to provide sufficient left turn storage on 264 Street away from the new bridge structure. A dedicated left turn and right turn lane are to be provided



along the westbound to north / south exit ramp. The north ramp terminal and the south ramp terminal will be signalized.

The new two lane bridge structure for 264 Street is proposed to be located to the west of the existing structure to allow traffic to continue across the existing structure during the construction period.

## Option 4: Parclo B Interchange Configuration with Directional Ramps


In this option, depicted in *Exhibit 3.8*, a Parclo B configuration forms the primary element of the interchange with loop ramps in the northwest quadrant and the southeast quadrant. A single exit point is proposed for the exit from Highway 1 eastbound and also for the exit from Highway 1 westbound.


The north ramp terminal would remain as a signalized intersection between 264 Street and 56 Avenue as per existing conditions. The loop ramp from Highway 1 westbound would connect directly to the intersection to provide access to 56 Avenue (north) and 264 Street north. However, a bypass lane is proposed to allow a free flow westbound to southbound movement onto 264 Street as an add lane.


The single lane eastbound exit from Highway 1 is proposed to subsequently diverge into a single lane directional ramp connection to 264 Street southbound and a single lane loop ramp in the southeast quadrant to access 264 Street northbound — as an add lane. Access to Highway 1 eastbound would be reconfigured with a southbound to eastbound single lane ramp which will exit 264 Street at the existing south intersection between 56 Avenue (south) and 264 Street.


A new single lane directional ramp is provided for the northbound Highway 13 to Highway 1 eastbound and westbound. The northbound to westbound movement will be provided over a separate bridge structure with a design speed of 70 km/h. Access to Highway 1 westbound from 264 Street and 56 Avenue (north) would continue to be provided via 56 Avenue (north) where all movements would travel through the north ramp terminal intersection at 264 Street. The two westbound entrance ramps would merge into a single lane prior to merging onto Highway 1.


The new four lane 264 Street bridge structure across Highway 1 is proposed to be located to the west of the existing structure to allow traffic to continue across the existing structure during the construction period.






















#### 3.2.2 EVALUATION CRITERIA

In order to determine a preferred configuration for Highway 1 interchanges, a high level assessment was conducted using traffic performance and implementation costs as the key indicators along with several other criteria. The criteria applied in the assessment are described below.

# . Network Travel Time Savings

This criteria measures the accumulated travel time for all vehicles travelling through each interchange option over an established simulation period and compares the values obtained against the network travel time value calculated for the base case / existing configuration. A traffic operations model is used to obtain the network travel time which is measured in vehicle hours. Travel time savings will also be portrayed in terms of dollars for comparison against implementation costs.

### Implementation Costs

Planning level cost estimates were produced for the proposed interchange improvements including roadways, structures, utilities and drainage, project management and design, and appropriate contingencies. The Elemental Parametric methodology was used to generate the implementation cost estimates.

#### Property Impacts / Surplus Land

As all of the options are located within the existing highway right of way, this criteria is not applicable and therefore does not form part of the assessment. However, some surplus property has been identified in some options.

### Accommodation of Provincial Movements

A qualitative assessment is conducted as to how the key movements between provincial facilities are accommodated. Direct movements are deemed to provide improved mobility for provincial movements (between numbered highways) and would be rated higher as compared to provincial movements that are provided through circuitous routing or through use of the local road network. A qualitative rating ranging between high, medium, and low will be used to compare the options against the base case / existing conditions.



## Network Connectivity

Improvements to the local road network to improve connectivity across the highway would be rated higher than options that continue to disrupt the continuity of the local road network. A qualitative rating ranging between high, medium, and low will be used to compare the options against the bases case / existing conditions.

### 3.2.3 OPTION EVALUATION

Using the evaluation criteria described above, the four interchange options developed for both the 232 Street and 264 Street interchanges were evaluated. As noted, some of the criteria were evaluated in a quantitative manner whereas others were evaluated qualitatively. Quantitative factors include performance metrics extracted from the traffic operations model as well as objective measures such as cost estimates using the Elemental Parametric methodology or the amount of property required in hectares.

For the evaluation criteria involving qualitative assessments, a descriptive assessment has been provided in relation to the base case conditions. The descriptive assessments include the use of indicators ranging from neutral, low, medium, to high impacts (or in some instances, benefits).

#### 232 STREET / HIGHWAY 1 INTERCHANGE OPTIONS

To assess the interchange options with respect to the evaluation criteria, focused traffic analysis, cost estimating, and other measurements were conducted and the results are summarized as follows:

#### Network Travel Time Savings

To obtain the network travel time savings for each option, a traffic operations model was developed for the 2015 and 2045 planning horizons. The spatial limits of the traffic operations model included the segment of Highway 1 between 232 Street and 264 Street, incorporating both interchanges and the immediate local road network. The 2015 traffic volumes were derived from the RTM and validated against several short count observations conducted on-site in the fall of 2014. The 2045 travel demand was also derived from the RTM. Within each peak period, a three hour period was simulated as follows:

- o 06:00 to 09:00 for the AM peak period;
- 15:00 to 18:00 for the PM peak period.



Once the base case (existing conditions) models were established for each time frame and peak period, the four interchange options were coded. Five model runs, with different seeds values applied to create randomness in the traffic generation, were conducted for each option for each time frame and peak period. The high and low network travel times were subsequently discarded and the average of the remaining three model runs was used in the analysis.

The following travel time savings summary table, *Table 3.3* provides the peak hour simulation results for each option and the base case. The change in travel time or travel time savings, is also provided for each option as compared to the base case.

Table 3.3: Network Travel Time Savings (rounded) - Highway 10 / 232 Street Interchange

Travel Period	Base	Option 1		Option 2		Option 3		Option 4	
Traver Feriou	veh-hrs	veh-hrs	Savings	veh-hrs	Savings	veh-hrs	Savings	veh-hrs	Savings
2014 AM peak	2566	2562	0	2551	20	2563	0	2577	-10
2014 PM peak	2984	3005	-20	2984	0	3008	-20	3004	-20
2045 AM peak	3649	3645	0	3615	30	3644	10	3668	-20
2045 PM peak	4381	4363	20	4351	30	4373	10	4345	40

In order to compare the potential benefits of the improvements against the implementation costs over the typical 25 year amortization period, the travel time savings were converted into a monetary value using BC Ministry of Transportation and Infrastructure default values for value of time. Annual savings were conservatively estimated based on the summation of the AM and PM peak period savings applied to each week day (250 days) and average of the AM and PM peak period savings applied to represent potential savings for the weekend days (100 days). Interpolation between the 2015 and 2045 planning horizon was conducted to obtain travel time savings for each of the intermediate years and these values were summed to obtain a total for the 25 year period. The 25 year travel time savings, represented in present value (\$ 2015), are shown below in **Table 3.4**.

Table 3.4: Highway 10 / 232 Street Interchange Travel Time Benefits Summary

	Option 1	Option 2	Option 3	Option 4
Travel Time Benefits (S)	-0.4 M	2.4 M	-0.8 M	-1.2 M

SW1200SWF Page 21 PARSONS



## Implementation Costs

A summary of the estimated implementation costs for each interchange option are provided in the cost summary table, *Table 3.5*. These cost estimates represent high level costs for option comparison purposes. More detailed cost estimates for the preferred interchange options are included in the project cost estimate described in Section 11 Project Budget.

Table 3.5: Highway 10 / 232 Street Interchange Options Cost Summary

	Option 1	Option 2	Option 3	Option 4
Project Management	2.0	2.2	2.8	2.6
Engineering	2.8	3.2	4.1	3.9
Grade Construction	10.5	10.8	12.0	9.2
Structural	9.8	12.2	17.1	18.0
Paving Construction	0.7	0.8	0.9	0.8
Operational Construction	0.9	1.1	1.5	1.4
Utilities	0.3	0.3	0.4	0.4
Resident Engineering	2.0	2.2	2.8	2.6
Contingency (30%)	8.6	9.8	12.4	11.6
Management Reserve	1.9	2.2	2.7	2.6
Total (rounded) \$M	40	45	57	54

## Property Impacts

Property impacts were quantified by measuring the area of the potential land impacted by an expanded interchange footprint, where applicable. Conversely, potential surplus land within the existing highway right-of-way was quantified by measuring the area that could be utilized for other purposes. The area of property impacts and potential surplus lands is summarized in *Table 3.6*.

Table 3.6: Highway 10 / 232 Street Interchange Options Property Summary

	Option 1	Option 2	Option 3	Option 4
Impacted Property (Ha)	0.0	0.0	0.0	0.0
Surplus Property (Ha)	5.0	4.5	8.4	10.3



#### Accommodation of Provincial Movements

The following discussion provides a summary of the how each interchange option accommodates the provincial movements, those key movements between Highway 10 and Highway 1.

**Option 1:** The proposed configuration, as compared to the base case, does not provide any improvements for the provincial movements between Highway 1 and Highway 10 and may even cause some reduction in mobility for these key movements.

- Highway 1 EB to Highway 10 WB Similar to the base case, this
  movement is accommodated by a loop ramp connecting to the south
  terminal junction. However, travel through the south ramp terminal
  roundabout is less desirable as compared to the existing un-signalized
  intersection.
- Highway 1 WB to Highway 10 WB Similar to the base case, this
  movement is accommodated by a single loop ramp in the northwest
  quadrant. Southbound travel through the south ramp terminal
  roundabout is however, less desirable then the existing un-signalized
  intersection.
- Highway 10 EB to Highway 1 EB Similar to the base case, this
  movement is accommodated via 72 Avenue (south). Travel through
  the south terminal roundabout is avoided with the large right turn slip
  lane.
- Highway 10 EB to Highway 1 WB –This movement is provided by a directional ramp from the roundabout at the north terminal junction. Travel through the roundabout is however, less desirable then the existing loop ramp in the northeast quadrant. It is noted that this is a low volume movement.

**Option 2:** The proposed configuration, as compared to the base case, does not provide any improvements for the provincial movements between Highway 1 and Highway 10 and may even cause some minor reduction in mobility for one movement.

- Highway 1 EB to Highway 10 WB Same as the base case, this
  movement is accommodated by a directional ramp to the south
  terminal junction.
- Highway 1 WB to Highway 10 WB Same as the base case, this
  movement is accommodated by a single loop ramp in the northwest
  quadrant.

SW1200SWF Page 23 PARSONS

- Highway 10 EB to Highway 1 EB Same as the base case, this movement is accommodated via 72 Avenue (south).
- Highway 10 EB to Highway 1 WB –This movement is provided by a directional ramp from the roundabout at the north terminal junction.
   Travel through the roundabout is less desirable then the existing loop ramp in the northeast quadrant. It is noted that this is a low volume movement.

**Option 3:** The proposed configuration, as compared to the base case, provides some improvements to the provincial movements between Highway 1 and Highway 10.

- Highway 1 EB to Highway 10 WB Same as the base case, this
  movement is accommodated by a directional ramp to the south
  terminal junction.
- Highway 1 WB to Highway 10 WB Same as the base case, this
  movement is accommodated by a single loop ramp in the northwest
  quadrant.
- Highway 10 EB to Highway 1 EB This movement is improved with a new directional ramp located in the southeast quadrant, north of 72 Avenue (south).
- Highway 10 EB to Highway 1 WB –This movement is provided by a
  directional ramp from the roundabout at the north terminal junction.
  Travel through the roundabout is less desirable then the existing loop
  ramp in the northeast quadrant. It is noted that this is a low volume
  movement.

**Option 4:** The proposed configuration, as compared to the base case, is detrimental to some provincial movements between Highway 1 and Highway 10.

- Highway 1 EB to Highway 10 WB Similar to the base case, this
  movement is accommodated by a directional ramp, although a right
  turn at the south ramp terminal is introduced.
- Highway 1 WB to Highway 10 WB This movement is circuitous with access provided via 72 Avenue. Two left turn manoeuvres are required, one onto 72 Avenue from Highway 1 and another from 72 Avenue to Highway 10 westbound.
- Highway 10 EB to Highway 1 EB Same as the base case, this
  movement is accommodated via 72 Avenue (south).
- Highway 10 EB to Highway 1 WB This movement is provided by a directional ramp at the north terminal junction through a left turn



movement. The left turn movement, at this junction, is less desirable then the existing loop ramp in the northeast quadrant. It is noted that this is a low volume movement.

### Network Connectivity

A review of each option was conducted with respect to assessing improvements in the level of connectivity within the local road network and specifically across Highway 1. The findings from this review, are as follows:

**Option 1:** The east west route, 72 Avenue, is still discontinuous across Highway 1. East west traffic on 72 Avenue must therefore continue to travel through the interchange along 232 Street. No improvement as compared to the base case.

**Option 2:** The east west route, 72 Avenue, is still discontinuous across Highway 1. East west traffic on 72 Avenue must therefore continue to travel through the interchange along 232 Street. No improvement as compared to the base case.

**Option 3:** With the new bridge structure across Highway 1, continuity along 72 Avenue is restored. This improved network connectivity removes the east west traffic from the interchange. Significant improvement compared to base case.

**Option 4:** With the new bridge structure across Highway 1, continuity along 72 Avenue is restored. This improved network connectivity removes the east west traffic from the interchange; however, significant Highway 1 interchange traffic is added to 72 Avenue. Moderate improvement compared to base case.

## Evaluation Summary

A summary of the interchange option evaluation is provided *Table 3.7*.



Table 3.7: Highway 10 / 232 Street Interchange Evaluation Summary

Criteria	Option 1	Option 2	Option 3	Option 4	
Travel Time Savings  Implementation	0 hrs AM peak period (2014) -20 hrs PM peak period (2014) 0 hrs AM Peak Period (2045) 20 hrs PM Peak Period (2045) -\$0.4 M Travel Time Savings (25 years)	20 hrs AM peak period (2014) 0 hrs PM peak period (2014) 30 hrs AM Peak Period (2045) 30 hrs PM Peak Period (2045) \$2.4 M Travel Time Savings (25 years)	0 hrs AM peak period (2014) -20 hrs PM peak period (2014) 10 hrs AM Peak Period (2045) 10 hrs PM Peak Period (2045) -\$0.8 M Travel Time Savings (25 years)	-10 hrs AM peak period (2014) -20 hrs PM peak period (2014) -20 hrs AM Peak Period (2045) 40 hrs PM Peak Period (2045) -\$1.2 M Travel Time Savings (25 years)	
Costs	\$40 W	φ <del>+</del> 3 (V)	\$37 W	IVI +C¢	
Property Impacts	0.0 Ha – Property Impacts 5.0 Ha – Potential Surplus	0.0 Ha – Property Impacts 10.3 Ha – Potential Surplus	0.0 Ha – Property Impacts 5.0 Ha – Potential Surplus	0.0 Ha – Property Impacts 8.4 Ha – Potential Surplus	
Network Connectivity	No improvement as compared to the base case.	No improvement as compared to the base case.	Significant improvement compared to base case.	Moderate improvement compared to base case.	
Provincial Movements	The proposed configuration, as compared to the base case, does not provide any improvements for the provincial movements between Highway 1 and Highway 10 and may even cause some reduction in mobility for these key movements.	The proposed configuration, as compared to the base case, does not provide any improvements for the provincial movements between Highway 1 and Highway 10 and may even cause some minor reduction in mobility for one movement.	The proposed configuration, as compared to the base case, provides some improvements to the provincial movements between Highway 1 and Highway 10.	The proposed configuration, as compared to the base case, is detrimental to some provincial movements between Highway 1 and Highway 10.	
Benefit / Cost and	B/C = 0.2	B/C = 0.3	B/C = 0.2	B/C = 0.2	
NPV	NPV= -\$30 M	NPV= -\$31 M	NPV= -\$42 M	NPV= -\$41 M	
Overall	Possible	Possible	Preferred	Not Preferred	

SW1200SWF Page 26 PARSONS



#### 264 STREET / HIGHWAY 1 INTERCHANGE OPTIONS

To assess the interchange options with respect to the evaluation criteria, focused traffic analysis, cost estimating, and other measurements were conducted and the results summarized as follows:

## Network Travel Time Savings

A similar process to that conducted for the 232 Street interchange traffic analysis was applied to the 264 Street interchange analysis in that a traffic operations model was developed for the 2015 and 2045 planning horizons to obtain the network travel time savings for each option. The spatial limits of the traffic operations model included the segment of Highway 1 between 232 Street and 264 Street, incorporating both interchanges and the immediate local road network. The 2015 traffic volumes were derived from TransLink's Regional Traffic Model and validated against several short count observations conducted on-site in the fall of 2014. The 2045 travel demand was also derived from the Regional Traffic Model. Within each peak period, a three hour period was simulated as follows:

- o 06:00 to 09:00 for the AM peak period
- 15:00 to 18:00 for the PM peak period

Once the base case (existing conditions) models were established for each time frame and peak period, the four interchange options were coded. Five model runs, with different seeds values applied to create randomness in the traffic generation, were conducted for each option for each time frame and peak period. The high and low network travel times were subsequently discarded and the average of the remaining three model runs was used in the analysis.

The following travel time savings summary table, *Table 3.8* provides the peak hour simulation results for each option and the base case. The change in travel time or travel time savings, is also provided for each option as compared to the base case.

Table 3.8: Network Travel Time Savings (rounded) – Highway 13 / 264 Street Interchange

Travel Period	Base	Option 1		Option 2		Option 3		Option 4	
Traver r errou	veh-hrs	veh-hrs	Savings	veh-hrs	Savings	veh-hrs	Savings	veh-hrs	Savings
2014 AM peak	2560	2535	30	2545	20	2601	-40	2542	20
2014 PM peak	2973	2984	-10	2981	-10	3033	-60	2957	20
2045 AM peak	3708	3627	80	3618	90	6466	-2760	3612	100
2045 PM peak	4365	4430	-170	4352	10	6294	-1930	4265	100

SW1200SWF Page 27 PARSONS

In order to compare the potential benefits of the improvements against the implementation costs over the typical 25 year amortization period, the travel time savings were converted into a monetary value using BC Ministry of Transportation and Infrastructure default values for value of time. Annual savings were conservatively estimated based on the summation of the AM and PM peak period savings applied to each week day (250 days) and average of the AM and PM peak period savings applied to represent potential savings for the weekend days (100 days). Interpolation between the 2015 and 2045 planning horizon was conducted to obtain travel time savings for each of the intermediate years and these values were summed to obtain a total for the 25 year period. The 25 year travel time savings, represented in present value (\$ 2015), are shown below in *Table 3.9*.

Table 3.9: Highway 13 / 264 Street Interchange Travel Time Benefits Summary

	Option 1	Option 2	Option 3	Option 4
Travel Time Benefits (S)	-\$1.3 M	\$2.8 M	-\$119 M	\$6.5 M

#### Implementation Costs

A summary of estimated implementation costs for each option are provided in the cost summary table, *Table 3.10*. These cost estimates represent high level costs for option comparison purposes. More detailed cost estimates for the preferred interchange options are included in the project cost estimate described in Section 10 Project Budget.

Table 3.10: Highway 13 / 264 Street Interchange Options Cost Summary

	Option 1	Option 2	Option 3	Option 4
Project Management	2.0	1.8	2.9	3.3
Engineering	3.0	2.6	4.3	5.0
Grade Construction	11.3	8.4	9.5	14.7
Structural	9.4	9.4	21.3	18.8
Paving Construction	0.9	0.7	0.7	1.2
Operational Construction	1.1	1.2	1.4	2.3
Utilities	0.4	0.3	0.4	0.6
Resident Engineering	2.0	1.8	2.9	3.3
Contingency (30%)	9.0	7.8	12.9	14.6
Management Reserve	2.0	1.7	2.8	3.2
Total (rounded) \$M	42	36	60	67



## Property Impacts

Property impacts were quantified by measuring the area of the potential land impacted by an expanded interchange footprint, where applicable. Conversely, potential surplus land within the existing highway right-of-way was quantified by measuring the area that could be utilized for other purposes. The area of property impacts and potential surplus lands is summarized in *Table 3.11*.

Table 3.11: Highway 13 / 264 Street Interchange Options Property Summary

	Option 1	Option 2	Option 3	Option 4
Impacted Property (Ha)	0	0	0.3	0
Surplus Property (Ha)	4.7	4.7	7.3	4.2

#### Accommodation of Provincial Movements

The following discussion provides a summary of the how each interchange option accommodates the provincial movements, those key movements between Highway 13 and Highway 1.

**Option 1:** The proposed configuration, as compared to the base case, does not provide any improvements for the provincial movements between Highway 1 and Highway 13 and may even cause some reduction in mobility for these key movements.

- Highway 1 EB to Highway 13 SB Similar to the base case, this
  movement is accommodated by a loop ramp connecting to the south
  terminal junction. Travel through the south ramp terminal roundabout
  is likely comparable to the existing signalized intersection with
  improvements during periods of low volumes.
- Highway 1 WB to Highway 13 SB Similar to the base case, this movement is accommodated by a single loop ramp in the northwest quadrant. Southbound travel through the south ramp terminal roundabout is likely comparable to the existing signalized intersection, with improvements during periods of low volumes.
- Highway 13 NB to Highway 1 EB Similar to the base case, this
  movement is accommodated by a directional ramp. Travel through
  the south terminal roundabout is avoided with the large right turn slip
  lane.
- Highway 13 NB to Highway 1 WB –This movement is provided via 56 Avenue (north) connecting to the roundabout at the north terminal junction. Travel through the roundabout is however, less desirable then the existing loop ramp in the northeast quadrant.

SW1200SWF Page 29 PARSONS

**Option 2:** The proposed configuration, as compared to the base case, does not provide any improvements for the provincial movements between Highway 1 and Highway 13 and may even cause some minor reduction in mobility for one movement.

- Highway 1 EB to Highway 13 SB Similar to the base case, this movement is accommodated by a loop ramp connecting to the south terminal junction. Travel through the south ramp terminal would be similar to existing conditions with a left turn movement required at the intersection.
- Highway 1 WB to Highway 13 SB Same as the base case, this
  movement is accommodated by a single loop ramp in the northwest
  quadrant. Travel through the south ramp terminal intersection would
  be similar to existing conditions.
- Highway 13 NB to Highway 1 EB Similar to the base case, this
  movement is accommodated by a directional ramp. Travel through
  the south terminal intersection is avoided with the large right turn slip
  lane.
- Highway 13 EB to Highway 1 WB –This movement is provided via 56 Avenue (north) by a directional ramp from the intersection at the north terminal junction. Travel through the intersection, via a left turn movement is however, less desirable then the existing loop ramp in the northeast quadrant.

**Option 3:** The proposed configuration, as compared to the base case, is detrimental to some provincial movements between Highway 1 and Highway 13.

- Highway 1 EB to Highway 13 SB This movement is circuitous with access provided via 56 Avenue. A left turn manoeuvre is required onto 56 Avenue from Highway 1 with a right turn required at the intersection between 264 Street and 56 Avenue. Travel through four intersections is required to complete this movement.
- Highway 1 WB to Highway 13 SB This movement is accommodated by a directional ramp with a left turn manoeuvre at the north ramp terminal, replacing the existing free flow loop ramp.
- Highway 13 NB to Highway 1 EB Same as the base case, this
  movement is accommodated by a directional ramp. Travel through
  the south terminal intersection is avoided with the large right turn slip
  lane.
- Highway 13 NB to Highway 1 WB This movement is provided via
   56 Avenue and a directional ramp to enter Highway 1. However, a left



SW1200SWF

turn manoeuvre is required at the intersection between 264 Street and 56 Avenue. The left turn movement, at this junction, is less desirable then the existing loop ramp in the northeast quadrant.

**Option 4:** The proposed configuration, as compared to the base case, provides several improvements to the provincial movements between Highway 1 and Highway 13.

- Highway 1 EB to Highway 13 SB This movement is accommodated by a directional ramp to the south terminal junction. This directional ramp replaces the existing loop ramp which connected to the same junction, but required a left turn manoeuvre to proceed southbound.
- Highway 1 WB to Highway 13 SB Same as the base case, this
  movement is accommodated by a single loop ramp in the northwest
  quadrant.
- Highway 13 NB to Highway 1 EB This movement is slightly improved with a new directional ramp which avoids the south terminal intersection.
- Highway 13 NB to Highway 1 WB –This movement is provided by a separate free flow directional ramp which diverges from Highway 13, south of the intersection at 56 Avenue (south).

## Network Connectivity

A review of each option was conducted with respect to assessing improvements in the level of connectivity within the local road network and specifically across Highway 1. The findings from this review, are as follows:

**Option 1:** The east west route, 56 Avenue, is still discontinuous across Highway 1. East west traffic on 56 Avenue must therefore continue to travel through the interchange along 264 Street. No improvement as compared to the base case.

**Option 2:** The east west route, 56 Avenue, is still discontinuous across Highway 1. East west traffic on 56 Avenue must therefore continue to travel through the interchange along 264 Street. No improvement as compared to the base case.

**Option 3:** With the new bridge structure across Highway 1, continuity along 56 Avenue is restored. This improved network connectivity removes the east west traffic from the interchange; however, significant Highway 1 interchange traffic is added to 56 Avenue. Moderate improvement compared to base case.

Page 31 PARSONS



**Option 4:** The east west route, 56 Avenue, is still discontinuous across Highway 1. East west traffic on 56 Avenue must therefore continue to travel through the interchange along 264 Street. No improvement as compared to the base case.

# Evaluation Summary

A summary of the interchange option evaluation is provided *Table 3.12*.

SW1200SWF Page 32 PARSONS



Table 3.12: Highway 13 / 264 Street Interchange Evaluation Summary

Criteria	Option 1	Option 2	Option 3	Option 4
Travel Time Savings	30 hrs AM peak period (2014) -10 hrs PM peak period (2014) 80 hrs AM Peak Period (2045) -170 hrs PM Peak Period (2045) -\$1.3 M Travel Time Savings (25 years)	20 hrs AM peak period (2014) -10 hrs PM peak period (2014) 90 hrs AM Peak Period (2045) 10 hrs PM Peak Period (2045) \$2.8 M Travel Time Savings (25 years)	-40 hrs AM peak period (2014) -60 hrs PM peak period (2014) -2760 hrs AM Peak Period (2045) -1930 hrs PM Peak Period (2045) -\$119 M Travel Time Savings (25 years)	20 hrs AM peak period (2014) 20 hrs PM peak period (2014) 100 hrs AM Peak Period (2045) 100 hrs PM Peak Period (2045) \$6.5 M Travel Time Savings (25 years)
Implementation Costs	\$42 M	\$36 M	\$60 M	\$67 M
Property Impacts	0.0 Ha – Property Impacts 4.7 Ha – Potential Surplus	0.0 Ha – Property Impacts 4.7 Ha – Potential Surplus	0.3 Ha – Property Impacts 7.3 Ha – Potential Surplus	0.0 Ha – Property Impacts 4.2 Ha – Potential Surplus
Network Connectivity	No improvement as compared to the base case.	No improvement as compared to the base case.	Moderate improvement compared to base case.	No improvement as compared to the base case.
Provincial Movements	The proposed configuration, as compared to the base case, does not provide any improvements for the provincial movements between Highway 1 and Highway 13 and may even cause some reduction in mobility for these key movements.	The proposed configuration, as compared to the base case, does not provide any improvements for the provincial movements between Highway 1 and Highway 13 and may even cause some minor reduction in mobility for one movement.	The proposed configuration, as compared to the base case, is detrimental to some provincial movements between Highway 1 and Highway 13.	The proposed configuration, as compared to the base case, provides several improvements to the provincial movements between Highway 1 and Highway 13.
Benefit / Cost and NPV	B/C = 0.2 NPV= -\$33 M	B/C = 0.3 NPV= -\$24 M	B/C = -1.9 NPV= -\$164 M	B/C = 0.3 NPV= -\$43 M
Overall	Possible	Preferred	Not Preferred	Possible

SW1200SWF Page 33 PARSONS



## 3.2.4 RATIONALE FOR CHOSEN OPTIONS

#### 232 STREET / HIGHWAY 1 INTERCHANGE

Based on the high level assessment, Option 3 was preferred for improving the interchange. In this option, the following improvements and advantages are noted:

- Removal of the undesirable geometry associated with the existing cloverleaf configuration.
- Single exits from Highway 1 in both directions.
- Improved traffic operations over the existing conditions.
- Connects 72 Avenue across Highway 1.
- No new land required for the 232 Street interchange.
- Significant surplus land in the northeast quadrant, with some surplus lands possibly available in the southwest quadrant and the southeast quadrant.
- Efficient traffic operations are provided for the key movements with direct connections between Highway 10 and Highway 1 (westbound to southbound and northbound to eastbound).

Option 3 also allows phased construction of the 72 Avenue flyover structure by retaining the existing connection of 72 Avenue to the north ramp terminal in the interim. This infrastructure deferral could reduce the initial implementation costs by approximately \$10M. Furthermore, the Highway 10 EB to Highway 1 EB movement could be retained in the existing configuration as an interim stage – until such time that the potential surplus lands immediately north of 72 Avenue are identified for development.

#### 264 STREET / HIGHWAY 1 INTERCHANGE

Based on the high level assessment, Option 2 was preferred for improving the interchange. In this option, the following improvements and advantages are noted:

- Removal of the undesirable geometry associated with the existing cloverleaf configuration.
- Single exits from Highway 1 in both directions.
- Improved operations over the existing conditions.
- No new land required for the 264 Street interchange.
- Potential surplus land in the southwest quadrant and northeast quadrants.
- Slightly improved traffic operations as compared to the base case.



Overall, Option 2 provides satisfactory mobility for the key movements between Highway 1 and Highway 13. However, the northbound to westbound highway to highway movement must pass through the intersection at 264 Street / 56 Avenue and utilize a section of 56 Avenue to gain access to Highway 1. If the highway to highway connectivity is deemed to be a critical component, then Option 4 could be considered as an alternate option instead of Option 2 in the subsequent design and implementation phases.

# 3.3 Auxiliary / Climbing Lanes

As there are significant grades in some segments of the study highway section, an analysis was conducted to assess the climbing lane requirements of Option 3 to better accommodate the slower truck traffic and preserve the capacity provided by the additional lane. The Highway Capacity Software (HCS) 2000 metric version was used, which applied the Highway Capacity Manual (HCM) procedures to analyze the Level of Service of mainline segments based on a number of factors including topography (including grade and length of grade), traffic volume, number of lanes, and percentage of heavy vehicles.

As the westbound and eastbound carriageways of the highway are separated by a wide median, the climbing segments of the two carriageways were assessed independently. In general, climbing segments with a grade greater than 2.0% were assessed, as heavy vehicles may have difficulty operating on these inclines especially if the segments are of sufficient length, causing the trucks to travel at a substantially lower speed than other vehicles in the traffic stream. For locations where the grade varies over the length of the climbing segment, each grade was assessed individually as a section, and the segment was also evaluated as a whole with an average grade weighted over the length of the segment. A Level of Service of E or F indicate that the mainline segments will likely operate at or beyond capacity, which will not be acceptable performance for Highway 1 and an auxiliary lane will be recommended.

For traffic volumes, the forecast travel demands from the RTM were adjusted to account for the differences noted between the observed and modelled volumes under existing conditions. The adjustments were applied on a directional basis for each of the peak hours assessed. For segments where an HOV lane will be provided, the HOV volume was subtracted from the total volumes such that only general purpose vehicles were considered in the analysis. Similarly, only the number of general purpose lanes was applied as opposed to the total number of lanes. For the percentage of heavy vehicles, the future modelled truck percentages were assumed to remain similar to the proportions observed under existing conditions, hence the latter were applied. One exception, however, was noted in the eastbound truck percentage at Glover Road in the afternoon peak hour, where the future modelled proportion was considerably lower than the observed proportion under



existing condition (9% compared to 14%). For this particular scenario, both truck percentages were evaluated.

In addition to the HCM procedures, the Geometric Design Guide for Canadian Roads (1999 Edition) published by the Transportation Association of Canada was also used, which states that a climbing lane will be required if a speed reduction of greater than 15 km/h will be experienced by trucks due to a combination of grade, length of grade, and the mass / power ratio of the heavy vehicle (section 2.1.8). The truck climbing lane will better accommodate the slower truck traffic while improving mobility for all motorists. Critical lengths of grade for a 15 km/h truck speed reduction are established in the Guide for various design truck mass / power ratios and grades. For analysis purposes, climbing segments evaluated to have a Level of Service of D or better but contain sections with significant grades were assessed using the truck speed reduction criterion, to examine if a truck climbing lane would be required for traffic operational reasons. The 180 g/W mass / power ratio, which is representative of the size and type of vehicle normally used for design, was assumed in the assessment.

Based on the inputs described above and illustrated in *Figure 3.2* below, the results from the HCS analysis for the preferred mainline Option 3 were obtained, as presented in *Tables 3.13* and *3.14* for the AM and PM Peak Hours, respectively.




Figure 3.2: Significant Grades in Study Highway Section



Table 3.13: Climbing Lane Analysis – 2045 AM Peak Hour

Climbing Segment	Direction	Sub Segment	Grade (%)	Length (m)	GP Volume (vph)	% Trucks	Avg Density (pc/km/h)	Avg Speed (km/h)	LOS
#1 200 St to 216 St	EB	А	2.18	1600	3200	14	19.0	100.1	D
(2GP+1HOV)	EB	В	1.01	900	3200	14	19.0	100.1	D
		AB	1.76	2500			19.0	100.1	D
#2 216 St to Glover Rd		A	1.98	1200			23.6	91.6	Е
(2GP+1HOV)	WB	В	3.61	800	3600	16	23.6	91.6	Е
		С	1.34	700			23.6	91.6	Е
		ABC	2.3	2700			-	-	F
#3 232 St to 264 St		А	0.68	500			18.1	102.8	D
(3 GP)		В	3.01	900			19.8	100.0	D
	EB	С	-0.21	1300	4700	14			
		D	0.67	400			18.1	102.8	D
		E	4.09	700			19.8	100.0	D
		F	0.42	1200			18.1	102.8	D
#4 East of Mt. Lehman to Clearbrook Rd		А	4.03	900	4300	12	18.3	102.5	D
(3 GP)	WB	В	1.58	900	1		16.1	104.8	D
		С	0.91	900	4600	12	17.4	103.7	D
		D	3.99	700	4600	12	18.2	102.7	D
		ABCD	2.55	3400	4600	12	18.7	101.9	D
#5 East of McCallum Rd to Highway 11		A	1.01	500	4900	12	18.9	101.6	D
(3 GP)	NA D	В	0.68	500			20.1	99.4	D
	WB	С	1.46	500	5100	12	20.1	99.4	D
		D	3.46	500	] 3100	'-	21.3	97.0	D
		E	1.34	700			20.1	99.4	D
		ABCDE	1.57	2700	5100	12	20.1	99.4	D

SW1200SWF Page 37 PARSONS



Table 3.14: Climbing Lane Analysis – 2045 PM Peak Hour

Climbing Segment	Direction	Sub Segment	Grade (%)	Length (m)	GP Volume (vph)	% Trucks	Avg Density (pc/km/h)	Avg Speed (km/h)	LOS
#1 200 St to 216 St		А	2.18	1600	2500	14	21.9	95.0	D
(2GP+1HOV)	EB	В	1.01	900	3500	14	21.9	95.0	D
		AB	1.76	2500			21.9	95.0	D
#2 216 St to Glover Rd		А	1.98	1200			20.3	97.9	D
(2GP+1HOV)	WB	В	3.61	800	3400	11	21.8	95.2	D
		С	1.34	700			20.3	97.9	D
		ABC	2.3	2700			22.2	94.4	Е
#3 232 St to 264 St		А	0.68	500			22.8	94.0	Е
(3 GP)		В	3.01	900	5400 14		26.4	86.2	Е
	EB	С	-0.21	1300		14			
		D	0.67	400			22.8	94.0	Е
		E	4.09	700			26.4	86.2	Е
		F	0.42	1200			22.8	94.0	Е
#4 East of Mt. Lehman to Clearbrook Rd		А	4.03	900	4100	9	16.5	104.6	D
(3 GP)	WB	В	1.58	900			15.1	105.2	С
		С	0.91	900	2700	_	13.6	105.2	С
		D	3.99	700	3700	9	14.2	105.2	С
		ABCD	2.55	3400	4100	9	15.8	105.0	С
#5 East of McCallum Rd to Highway 11		А	1.01	500	4100	9	15.1	105.2	С
(3 GP)		В	0.68	500			15.5	105.1	С
	WB	С	1.46	500	4200	9	15.5	105.1	С
		D	3.46	500	4200	, ,	16.2	104.8	D
		E	1.34	700			15.5	105.1	С
		ABCDE	1.57	2700	4200	9	15.5	105.1	С

As presented in *Tables 3.13* and *3.14*, Climbing Segments 2 and 3 are anticipated to operate at Level of Service E or F. Also, Climbing Segment 1 is at the upper limit of Level of Service D. Hence, an auxiliary lane is recommended for the three climbing segments:

 Between approximately the Glover Road overpass and the 216 Street interchange in the westbound direction;

SW1200SWF Page 38 PARSONS



- Between the 232 Street and 264 Street interchanges in the eastbound direction;
- Between the 200 Street and 216 Street interchanges in the eastbound direction.

In addition, the critical length of grade criterion was assessed for the grades greater than 2% on the remaining climbing segments, Climbing Segments 4 and 5. From the analysis, it was found that sub segments A and D on Climbing Segment 4 as well as sub segment D in Climbing Segment 5 will require a truck climbing lane for improved traffic operations. However, due to spatial constraints at the Mount Lehman Road interchange in the westbound direction, it is infeasible to provide a truck climbing lane for sub segment D in Climbing Segment 4. Similarly, due to spatial constraints at the McCallum Road interchange in the westbound direction, it is infeasible to provide a continuous truck climbing lane over the entire grade which extends just east of the McCallum Road interchange. Overall, a truck climbing lane is recommended for the following two segments:

- For the sub segment (A) with a grade of 4.03% located west of the Mount Lehman Road interchange in the westbound direction; and
- For the sub segment (D) with a grade of 3.46% located between the Highway 11 and McCallum Road interchanges in the westbound direction.

Noting the anticipated degradation in travel speeds / level of service due to the varying topography along this section of Highway 1, the auxiliary / truck climbing lane segments recommended above will assist in preserving the capacity provided by the additional lane in each direction of travel.

# 3.4 Replacement / Upgraded Structures

Although no options have been identified and therefore no option evaluation undertaken, the following structures will need to be replaced or upgraded as part of the widening of the highway mainline:

- Glover Road Underpass Structure (replacement);
- CP Rail Underpass Structures / Portals (replacement);
- 232 Street Underpass Structure (replacement);
- 264 Street Underpass Structure (replacement);
- Bradner Road Overhead Structures (widening);
- Peardonville Road Underpass Structures (replacement).

SW1200SWF Page 39 PARSONS



SW1200SWF

# 4.0 PROJECT OBJECTIVES

The objectives of the Highway 1 Widening (216 Street to Highway 11) project are:

- To provide sufficient traffic capacity along the highway to meet the current peak hour traffic demands and the demands of the future up the year 2045;
- To address critical geometric and road safety deficiencies at a number of structures along the highway;
- To renew the configuration of two interchanges to meet current best practice; and
- To reduce levels of congestion, improve levels of service and decrease travel times along the highway.

Page 40 PARSONS



# 5.0 PROJECT SCOPE STATEMENT

The project scope will generally include the widening of Highway 1 by adding one lane in each direction into the median from 216 Street to Highway 11. The project will include the demolition of existing underpass and reconfiguration of two interchanges, the 232 Street interchange and the 264 Street interchange. In addition, to accommodate the Highway 1 widening a number of grade separated crossing will need to be upgraded to achieve added crossing width and/or higher clearance under the structure. The scope of the Highway 1 Widening project will also include the following key elements:

- Demolition and reconstruction of the Glover Road underpass structure;
- Demolition and reconstruction of the rail underpass structures at the CP Rail lane (Roberts Bank Corridor);
- Widening of the two overhead structures at Bradner Road;
- Upgrade of the entrance and exit ramps to the Bradner Rest Area along the westbound lanes of Highway 1;
- Demolition and reconstruction of the Peardonville Road underpass structure;
- New structure for the eastbound off-ramp to Highway 11; and
- Upgrade of the Highway 11 on-ramp to Highway 1 eastbound.

# 5.1 Project Work Breakdown Structure

The project Work Breakdown Structure (WBS) defines the total scope of the Highway 1 Improvements project in a hierarchal format. Although it describes the same project scope as the corresponding project scope statement, it is more precise and detailed. The WBS will be the foundation of the project schedule and project resource estimates, and used to build the project work plan. The WBS for the Highway 1 Improvements project is shown in *Figure 5.1*.






Figure 5.1: WBS for Highway 1 Improvements Project

# 5.2 Work Breakdown Structure Dictionary

The Highway 1 Widening project will consist of the following components: Procurement, Package 1, Package 2, Package 3, Package 4, Package 5 and Package 6, as defined below.

**WBS 1.1 Procurement** – will be managed in-house and will use a design-bid-build procurement method. The preliminary design, detailed design, tender documents and construction supervision will be outsourced to a prequalified engineering consulting firm. The construction will be conducted by a construction company that has been selected through open tender.

WBS 1.2 Package 1 (232 Street Interchange) – this package would involve reconfiguring the 232 Street interchange to allow a new underpass structure to be constructed and the existing structure to be removed. As part of this work, the proposed 72 Avenue underpass would be constructed. Only localized widening of Highway 1 would be included, but any additional lanes on Highway 1 would not be opened to traffic.

SW1200SWF Page 42 PARSONS



The new 232 Street underpass will have a different horizontal and vertical alignment than the existing bridge. The proposed bridge width is approximately 21.9 m wide to accommodate four 3.6 m traffic lanes, two 1.5 m shoulders, concrete parapets, 3.5 m multi-use path and a bicycle fence. It is a symmetrical 2-span bridge with a pier in the median resulting in two 46 m spans for a total length of 92 m.

WBS 1.3 Package 2 (264 Street Interchange) - this package would involve reconfiguring the 264 Street interchange to allow a new underpass structure to be constructed and the existing structure to be removed. Only localized widening of Highway 1 would be included, but any additional lanes on Highway 1 would not be opened to traffic.

A new 264 Street Parclo B configuration interchange will include a new structure spanning over Highway 1 as well as over the south and north off ramps.

The new underpass will have a different horizontal and vertical alignment than the existing bridge. The proposed bridge width is approximately 21.9 m wide to accommodate four 3.6 m traffic lanes, two 1.5 m shoulders, concrete parapets, 3.5 m multi-use path and a bicycle fence. It is a symmetrical 2-span bridge with a pier in the median resulting in two 50 m spans for a total length of 100 m.

WBS 1.4 Package 3 (Highway 1 Widening from 216 Street to 232 Street) – this package would involve widening Highway 1 between the recently constructed interchange at 216 Street and the recently constructed 232 Street interchange (Package 1), a distance of approximately 2.1 kilometres. The widening would include development of the westbound HOV lane and transition from three to two general purpose lanes in the westbound direction. This package would also involve the complex removal of the box structures at the CP Rail crossing and construction of a new rail bridge. Removal and construction of a new Glover Road overpass is also included in this construction package.

The new Glover Road Underpass will follow the existing horizontal alignment but will need to be raised approximately 1.5 m to accommodate the required 5 m vertical clearance below the bridge. A full road closure is anticipated as there are alternate routes across the highway within the area. The length of the bridge from abutment to abutment is 82m. The bridge width is determined to be 14.7 m to accommodate two 3.6 m traffic lanes, a 3.5 m multiuse path, two 1.5 m shoulders, parapets and a pedestrian/bicycle fence.

The proposed new RBC Rail structure is a three span structure with constant 33.5 m spans for a total length of 100.5 m. At this time, it is understood there are no current or future plans to double or expand the tracks through this area and a single rail bridge



is all that is required. The width of the bridge will be influenced by the staging approach and where the piles/foundations can be placed.

WBS 1.5 Package 4 (Highway 1 Widening from 232 Street to 264 Street) – only highway widening, over a length of approximately 5.8 kilometres, is involved in this construction package. The widening would encompass the segment of highway, in both directions of travel, between the recently constructed 232 Street interchange (Package 1) and the 264 Street interchange (Package 2). No new structures or modifications to existing structures are included in this segment.

WBS 1.6 Package 5 (Highway 1 Widening from 264 Street to Mt. Lehman Road) — widening the highway in both directions of travel between the recently constructed 264 Street interchange and the existing Mt. Lehman Road interchange represents the majority of the scope in this package. However, widening of the Bradner Road overhead structures is included as is the upgrade of the entrance and exit ramps to the Bradner Rest area.

The horizontal and vertical alignments of Highway 1 and Bradner Road do not need to change in case of bridge replacement. In addition, the new bridge superstructure will be able to provide sufficient height to accommodate the 5.0 m vertical clearance requirement. It is understood that a full bridge closure is not permitted and staged construction is required.

The new bridges will be one span structures with approximate length of 17 m. The abutments will be placed approximately adjacent to the shoulders of Bradner Road, which width is determined to be approximately 14.3 m to accommodate two 3.6 m traffic lanes, a 3.5 m multi-use path, two 1.5 m shoulders and parapets. The bridge width will be 16. 4 m consisting of 3 - 3.7 m traffic lanes, a 1.5 m and a 3 m shoulders and parapets.

## WBS 1.7 Package 6 (Highway 1 Widening from Mt. Lehman Road to Highway 11)

- this construction package involves approximately 9.7 kilometres of widening of Highway 1 between the Mt. Lehman Road interchange and the Highway 11 interchange. Removal and construction of the new Peardonville Road underpass structure and associated municipal road works are included in this construction package. The new eastbound off-ramp structure to Highway 11 and reconfiguration of the eastbound on-ramps from Highway 11 are also included.

A new alignment is proposed which will provide a direct connection from Peardonville Road to South Fraser Way resulting in an alignment that crosses the Highway at a 63 degree skew. The current underpass is slightly below the 5.0 m vertical clearance envelope. The new alignment will need to consider this as well as any additional superstructure depth to accommodate the necessary span lengths. The full existing



bridge closure is not required because of the new horizontal alignment. The new bridge will consist of four spans with a total length of 195.5 m spanning Highway 1 and Martens Street. One pier will be located in the middle of the highway median and other adjacent to the right shoulder of eastbound Highway. The bridge will be 14.7 m wide to accommodate two 3.6 m traffic lanes, a 3.5 m multi-use path, two 1.5 m shoulders, parapets and a bicycle fence.

# Common Work Breakdown Elements to All Six Packages

The following work break down elements are generic to all six packages.

**Engineering** – will include design, project management and securing necessary approvals:

- Design includes civil, structural, and electrical design for road works, structure, traffic signals, lighting and utilities. Rail design is also required for rail line profile raising at the Highway rail overpass crossing.
- Project Management will be performed by in-house staff with construction management services being outsourced to an engineering consultant firm.
- Approvals includes environmental assessment and approvals, and archaeological assessment approvals. Approvals from CP Rail for the design, construction detours and impacts to rail traffic operations will also be required in relation to the RBRC crossing within Work Package 3. Approvals from the Townships of Langley and City of Abbotsford for cost sharing, interchange design, and tie-ins to crossing roadways and municipal utility relocations. Approvals for BC Hydro, Fortis, and Telus for relocation of regional utilities.

**Utilities** – includes the relocation and / or protection of utilities (BC Hydro, gas, communications, municipal, and other) located within the median areas of Highway 1 which will be used for the widening of the carriage way. This work element also includes watercourse crossings of the highway, which again due to the widening of the carriage way will need to be lengthened or replaced.



# 6.0 PROJECT TIMELINE

As introduced in the previous section, multiple construction packages were identified to provide implementation flexibility in widening the Highway 1 section between 216 Street and Highway 11. This proposed implementation strategy and the associated timelines are described as follows.

# 6.1 Proposed Staging

To provide the Ministry of Transportation and Infrastructure with some implementation flexibility in widening Highway 1, the corridor was divided into multiple segments based on the priority of construction and related costs. The segmentation or construction packages have been developed such that they can be delivered individually or bundled together into various combinations. The following segmentation / construction packages are proposed.

# Package 1: 232 Street Interchange

This package would involve reconfiguring the 232 Street interchange to allow a new underpass structure to be constructed and the existing structure to be removed. As part of this work, the proposed 72 Avenue underpass would be constructed. Only localized widening of Highway 1 would be included, but any additional lanes on Highway 1 would not be opened to traffic.

#### Package 2: 264 Street Interchange

This package would involve reconfiguring the 264 Street interchange to allow a new underpass structure to be constructed and the existing structure to be removed. Only localized widening of Highway 1 would be included, but any additional lanes on Highway 1 would not be opened to traffic.

#### Package 3: Highway 1 Widening from 216 Street to 232 Street

This package would involve widening Highway 1 between the recently constructed interchange at 216 Street and the recently constructed 232 Street interchange (Package 1), a distance of approximately 4.1 kilometres. The widening would include development of the westbound HOV lane and transition from three to two general purpose lanes in the westbound direction. This package would also involve the complex removal of the box structures at the CP Rail crossing and construction of a new rail bridge. Removal and construction of a new Glover Road overpass is also included in this construction package.



### Package 4: Highway 1 Widening from 232 Street to 264 Street

Only highway widening, over a length of approximately 7.2 kilometres, is involved in this construction package. The widening would encompass the segment of highway, in both directions of travel, between the recently constructed 232 Street interchange (Package 1) and the 264 Street interchange (Package 2). No new structures or modifications to existing structures are included in this segment.

## Package 5: Highway 1 Widening from 264 Street to Mt. Lehman Road

Widening the highway in both directions of travel between the recently constructed 264 Street interchange and the existing Mt. Lehman Road interchange represents the majority of the scope in this package. However, widening of the Bradner Road overhead structures is included as is the upgrade of the entrance and exit ramps to the Bradner Rest area.

## Package 6: Highway 1 Widening from Mt. Lehman Road to Highway 11

This construction package involves approximately 10.1 kilometres of widening of Highway 1 between the Mt. Lehman Road interchange and the Highway 11 interchange. Removal and construction of the new Peardonville Road underpass structure and associated municipal road works are included in this construction package. The new eastbound off-ramp structure to Highway 11 and reconfiguration of the eastbound on-ramps from Highway 11 are also included.

As mentioned above, the proposed construction packages described above have been developed to allow flexibility in the delivery of the overall project. Separately, each construction package has been sized such that each package can be easily delivered under a conventional design bid build approach using local construction firms. However, one or more of the construction packages could be bundled together as a larger conventional design bid build contract, or as a design build delivery. Further bundling of the construction packages could lead to two or even three design build alternative delivery packages. Finally, the overall project could be delivered as a single contract under a public private partnership approach.

No recommendation is being made with respect to the actual method of delivery, which is highly dependent upon available funding and cash flow. Determination of the appropriate delivery approach is therefore deferred to the time frame when the Ministry of Transportation has funding secured to move forward with actual implementation.



SW1200SWF

## 6.2 Potential Schedule

Assuming a "worst case" scenario in terms of length of time to complete the entire project, a high level schedule has been prepared to show the overall project duration if a near sequential construction sequence was chosen for each of the six construction packages described above. The proposed schedule, depicted in *Figure 6.1*, assumes a near sequential implementation of the six proposed construction packages further assuming the packages will be delivered in a sequential manner from west to east. As can be seen in this potential schedule, if the design activities are assumed to start in Q4 of 2016, then the overall project would not be completed until the end of 2024.

It should be noted that some of the packages are independent of the other construction packages, therefore, more than one construction package could be implemented simultaneously. For example, Package 1 and Package 2 could be constructed simultaneously, as could Package 6. The other construction packages would be dependent upon completion of these initial three construction packages. Significant savings in the schedule duration could be gained if one or more construction packages were implemented simultaneously.

Furthermore, if bundling of the constructions packages is considered, then it is assumed that production related efficiencies would result and the overall schedule would be reduced.

Figure 6.1: Proposed Schedule

Design / Tender
 Construction

Page 48 PARSONS



# 7.0 PROJECT OUTCOMES AND BENEFITS

This project has clear federal, provincial and municipal benefit in that current congestion along the Highway 1 corridor will be mitigated with the provision of an additional through lane in each direction, climbing lanes at critical steep highway segments, upgrades to existing grade separated crossings to gain minimum clearances for safety, and reconstruction of two existing interchanges to improve functionality and road safety. The Highway 1 corridor through the Fraser Valley provides the primary access to the provincial interior, the western provinces, and the rest of Canada. The corridor is a major goods movement route and also provides connectivity to key international border crossings at Highway 11 and Highway 13, as well as Highway 15 immediately west of the project limits.

With the reconstruction of the interchanges at Highway 10 (232 Street) and at Highway 13 (264 Street), improved access to / from the highway is provided in the Township of Langley. The additional through lane in each direction will also provide improved connectivity between the communities in the Fraser Valley and the Abbotsford International Airport.

## 7.1 Evaluation Criteria

In order to compare and contrast the relative merits and drawbacks of the Highway 1 Widening project versus a no build option, a set of high level evaluation criteria was developed based on similar Multiple Account Evaluations prepared for Ministry planning studies. The criteria are a combination of quantitative and mostly qualitative factors to assist in selecting a preferred alternative. For consistency with business case development, a 25 year project horizon has been assumed.

In keeping with the Ministry's Multiple Account categories, the evaluation criteria have been grouped into the respective Customer Service, Socio-Community, Financial, and Environmental accounts. The Economic account is not proposed at this level of analysis. Given that the Highway 1 Widening project proposes to widen the highway within the existing median, some of the evaluation criteria within the Multiple Account Evaluation are not applicable. These criteria and rationale for exclusion from the evaluation are shown in *Table 7.1*.



Table 7.1: Evaluation Criteria Application

Account	Criteria	Applicable	Comments
	Mobility Impacts	Yes	
Customer Service	Vehicle Operating Costs	Yes	
	Road Safety	Yes	
	Travel Time	Yes	
	Residential Property Impacts	No	No properties required
	Business Property Impacts	No	No properties required
	ALR Impacts	No	No properties required
	Noise Impacts	No	Highway widening in the median
Socio-Community	Visual Impacts	No	Highway widening in the median
	Target Mode Shares	No	Highway widening is GP lanes only
	Community Severance	No	Highway widening in the median
	OCP Consistency	No	Highway widening in the median
	Business Impacts	No	Highway widening in the median
	Land Requirements	No	Highway widening in the median
	GHG Impacts	No	Regional Macro Travel Demand Model
Environmental	Terrestrial Impacts	Yes	
	Aquatic Impacts	Yes	
	Archaeological / Historical Impacts	Yes	
	Capital Cost	Yes	
	Maintenance and Rehabilitation Cost	Yes	
Financial	Salvage Value	Yes	
	BC Ratio	Yes	
	NPV	Yes	

The descriptions below include a summary of the criterion characteristics and rationale, as well as a range of evaluation output are discussed below.

# A. Customer Service Account

#### A.1 Travel Time

Using the Emme3 2045 travel demand model outputs for the No Build option and Highway 1 Widening project, an assessment of the impact on level of service and mobility will be conducted at a high level.

SW1200SWF Page 50 PARSONS



Evaluation Output:

This quantitative assessment will take into consideration the AM and PM peak models which cover the entire Metro Vancouver road and transit network as well as the City of Abbotsford and Township of Langley network. The Network Travel Time Savings of the Highway 1 Widening project compared with a No Build Option will be forecast, compared and expressed as a present dollar value.

## A.2 Vehicle Operating Costs

With the proposed widening of the highway facility, it is anticipated that congestion levels will be reduced which in turn, will result in lower vehicle operating costs. Special analysis to ascertain the improvements in vehicle operating costs between the base No Build option and the Highway 1 Widening project will be conducted. The vehicle operating costs will solely represent the changes in overall fuel consumption, noting that the fuel consumption component represents the largest component of vehicle operating costs, where as other typical components such as tire wear and oil are primarily related to vehicle kilometres travelled (VKT). With the effects related to this project being very corridor focused, the VKT does not change significantly between the base No Build and the Highway 1 Widening.

Evaluation Output:

This quantitative assessment will estimate fuel consumption based on the expected reduction in travel delays (stoppages), for several typical vehicle types, over the study corridor as derived from a comparison of the base No Build and the Highway 1 Widening project. The resultant value will be expressed as a present dollar value.

#### A.3 Expected Road Safety Performance

The expected road safety performance for both the No Build option and the Highway 1 Widening project are derived from the Highway Safety Manual Part C predictive method to determine both the predicted and expected crash frequency for the highway corridor. The predicted crash frequency is widely used in safety practices, especially when comparing different improvement alternatives. Meanwhile, the expected crash frequency, which solves the "regression to mean" bias by combining the predicted and observed crash frequency using the Empirical Bayes method, is a more reliable estimator of the crash frequency.

Evaluation Output:

The Expected Crash Frequency and Severity for the Highway 1 Widening project compared with a No Build Option will be predicted and expressed as a present dollar value.





#### B. Environmental Account

## B.1 Terrestrial Impacts

The relative severity of impacts to the terrestrial environment will be noted and ranked. The qualitative evaluation will determine whether each option would have low, medium or high terrestrial requirements.

Evaluation Output: Low / Medium / High Terrestrial Impacts

#### B.2 Aquatic Impacts

The relative severity of impacts to the aquatic environment will be noted and ranked.

The qualitative evaluation will determine whether each option would have low, medium or high aquatic requirements.

Evaluation Output: Low / Medium / High Aquatic Impacts

# B.3 Archaeological / Historical Impacts

Any archaeologically or historically significant impacts will be noted and ranked in terms of the severity of impact. The qualitative evaluation will determine whether each option would have low, medium or high impacts.

Evaluation Output: Low / Medium / High Archaeological and Historical Impacts

#### C. Financial Account

# C.1 Capital Cost

The relative construction cost of the Highway 1 Widening Project will be assessed and typical unit costs referenced from the Ministry's Construction and Rehabilitation Cost Guide, and using the Elemental Parametric "Wolski" method. The cost is dependent on the extent of physical modifications, the complexity of the modifications (including geotechnical, utilities, drainage, and environmental compensation features), and right-of-way requirements.

Evaluation Output: Total Construction Cost (Including Contingencies)

#### C.2 Maintenance and Rehabilitation Cost

Consideration for annual maintenance and rehabilitation costs will be based on standard lane-kilometre costs and scheduled major rehabilitation for major roadways. The cost will be expressed as a 25 year present value.

Evaluation Output: Maintenance and Rehabilitation Cost (25 Year Present Value)





SW1200SWF

#### C.3 Salvage Value

The salvage value of the proposed infrastructure at the end of the 25 year business case period will be reported as per the assumptions listed in the Ministry's ShortBenCost business case analysis tool.

Evaluation Output: Salvage Value (25 Year Present Value)

#### C.4 Benefit Cost Ratio and Net Present Value

This calculation takes into consideration the 25 year present value of each option's travel time savings benefits, operating cost savings benefits, capital costs, maintenance and rehabilitation costs and salvage value.

Evaluation Output: B/C Ratio, NPV (25 Year Benefits – Costs)

# 7.2 Evaluation of Highway 1 Widening Project

#### A. Customer Service Account

#### A.1 Travel Time

Using the 2015 and 2045 travel demand model outputs (TransLink RTM) and proposed geometric and operational modifications, an assessment of the impact on level of service and mobility was conducted at a high level.

To quantify the reduced travel times into travel time savings, the peak period travel time savings using the consumer surplus methodology were extracted from the models, and a monetary value of time was applied. For the purpose of this analysis the following values of time were assumed:

- Automobile \$15.94 / hour;
- Straight Truck \$46.03 / hour; and
- Combo Truck \$53.30 / hour.

The resulting estimates of travel time savings (rounded) for the base model year 2015 and 2045 are shown in *Table 7.2* for the AM and PM peak hours only.

Table 7.2: Network Travel Time Savings

	•
Travel Period	Travel Time Savings
2015 AM peak	\$4,900
2015 PM peak	\$9,350
2045 AM peak	\$17,750
2045 PM peak	\$24,450

Page 53 PARSONS



To expand these hourly values to daily and then to annual values, the following assumptions were also applied:

- Expansion of the 2015 AM peak hour value by a factor of four (4) was applied to
  account for peak period travel time savings and minor off-peak period travel time
  savings on weekdays. A factor of five (5) was applied to the 2045 value.
- Expansion of the 2015 PM peak hour value by a factor of four (4) was applied to
  account for peak period travel time savings and minor off peak period travel time
  savings on weekdays. A factor of six (6) was applied to the 2045 value.
- Potential travel time savings for a typical weekend day were estimated based on the assumption that a weekend day would recognize only half the travel time savings of a typical weekday.
- Annual values were calculated by expanding the weekday values by 260 and the weekend values by 100. To be conservative, no travel time savings were estimated for holidays.

The forecasted annual travel time savings are shown in *Table 7.3*.

Table 7.3: Forecast Annual Travel Time Savings

	2015	2045
AM Peak Hour Travel Time Savings (\$)	\$4,900	\$17,750
PM Peak Hour Travel Time Savings (\$)	\$9,350	\$24,450
AM Peak Period Travel Time Savings (\$)	\$19,640	\$88,825
PM Peak Period Travel Time Savings (\$)	\$37,400	\$146,760
Weekday Travel Time Savings (\$)	\$57,050	\$235,585
Weekend Travel Time Savings (\$)	\$28,525	\$117,793
Annual Saving (\$/annum)	\$17,685,000	\$73,031,000

The net present value of the forecast travel time savings for the Highway 1 Widening project, for the benefit period between 2024 and 2041, is shown in *Table 7.4*. These values were estimated by interpolating between the 2015 and 2045 values shown in Table 7.3 and discounting the values using a 6% discount rate.

Table 7.4: Travel Time Benefits Summary (2025 – 2041) PV

	No Build	Highway 1 Widening
Travel Time Benefits	NA	\$334,000,000

Note: Only nine months of benefits were assumed for 2024

SW1200SWF Page 54 PARSONS



### A.2 Vehicle Operating Costs

Vehicle operating cost benefits were assessed at a high level, with fuel consumption representing the only factor in recognition that other typical components are related more to vehicle kilometres travelled which does change significantly in the analysis of benefits for the Highway 1 study corridor.

Fuel consumption was estimated for base traffic conditions and future base 2045 traffic conditions along the study corridor. A key assumption in estimating the vehicle operation cost savings is that the Highway 1 Widening project would eliminate the majority of congestion along the study corridor. Therefore, the amount of fuel saved is the difference between the fuel consumed during congested conditions and uncongested conditions. For the purposes of the calculations, the study corridor was divided into three segments:

- 200 Street to 264 Street
- 264 Street to Mt. Lehman Road; and
- Mt. Lehman Road to Highway 11.

It was assumed, based on observations and historical information obtained from Google Traffic, that a significant portion of each segment experiences congestion as shown in **Table 7.5**.

Congested Length (km) Segment Segment Description Segment Length (km) 200 Street to 264 Street 14.5 11.5 1 2 264 Street to Mt. Lehman Road 9.5 9.5 3 8 Mt Lehman Road to Highway 11 9.1

Table 7.5 Congested Corridor Segments

Currently, extended periods of congestion are observed on the corridor. For the purposes of estimating savings in fuel consumption, it is assumed that congestion relates to conditions where traffic occasionally is stopped, periods of idling occur, and necessary acceleration and deceleration operations occurs. Estimates of the duration of these events are shown in *Table 7.6*.

Table 7.6: Current (2016) Congestion Event Durations (hrs)

Segment		Weekend		
Segment	AM Peak	MD Peak	PM Peak	Peak
1	3.0	0.0	3.0	1.0
2	3.0	0.0	3.0	1.0
3	1.0	0.0	1.0	1.0

SW1200SWF Page 55 PARSONS



As traffic demand grows within the study corridor, it is assumed that these congested conditions will worsen over time. Estimates of the duration of these future congestion events are shown in *Table 7.7*.

Table 7.7: Future (2045) Congestion Event Durations (hrs)

Segment		Weekend		
Segment	AM Peak	MD Peak	PM Peak	Peak
1	4.5	0.0	4.5	1.5
2	4.5	0.0	4.5	1.5
3	1.5	0.0	1.5	1.5

During these congestion events, it was assumed that the highway is operating at capacity and processes approximately 3500 vehicles per hour. The assumed composition of the vehicle fleet is shown in *Table 7.8*. For simplicity, autos were further aggregated into several typical "auto" vehicle classes. Research was conducted to determine representative fuel consumption rates for each vehicle class. These fuel consumption rates are achieved under uncongested conditions.

Table 7.8: Vehicle Fleet Composition and Fuel Consumption Rates

Vehicle Class	Percent of Fleet	Fuel Consumption (L/100 km)
Passenger Vehicles	45%	6.7
SUV	32%	8.0
Pick Up	9%	10.0
Mini Van	5%	8.7
Auto Total	91%	7.6
Trucks Total	9%	35.0

In a previous study for TI Corp, travel time data was collected along several routes within the Highway 1 corridor, before and after the completion of the Port Mann Bridge and related highway improvement. This data was used as input in a vehicle emissions model to estimate fuel savings. Based on the data collected, observations indicated that a vehicle consumed 14% to 40% more fuel in congested conditions, depending on the extent of the travel time savings and the class of the vehicle. The findings from this previous study were deemed to be relevant in estimating the potential reduction in fuel consumption as related to the widening of Highway 1. It should be noted however, that this previous study did not examine fuel savings for "heavy trucks." As such, figures for the "light trucks" vehicle class were used as a proxy for the "heavy trucks" vehicle class, thus the results can be considered conservative for this vehicle class.



For the purposes of estimating fuel consumption savings, it was assumed that the average speed of the corridor will increase from 60 km/h to 100 km/h after the completion of the Highway 1 Widening Project. Based on this assumption and the findings from the previous project, it was estimated that an auto vehicle will consume 14% more fuel in congested conditions, while a truck will consume 17% more fuel in the same congested conditions.

The daily fuel savings were expanded to annual figures by assuming 260 weekdays and 100 weekend days in a year. Price of fuel was assumed to be \$1.25 / L for gasoline and \$1.20 / L for diesel. Based on these assumptions, the total benefits in fuel savings was estimated to be approximately \$2.6 million in 2016 and \$3.9 million in 2045. Vehicle operating cost savings, as related to fuel consumption benefits, accruing between these two years were linearly interpolated. The present value of vehicle operations cost savings, using a 6% discount rate for the period from 2024 to 2041, is shown in *Table 7.9*.

Table 7.9: Vehicle Operating Cost Savings Summary (2024-2041) PV

	No Build	Highway 1 Widening
Vehicle Operations Cost Savings	NA	\$22,925,000

Note: Only nine months of benefits were assumed for 2024

#### A.3 Expected Road Safety Performance

Crash data for the study area was obtained from the Ministry of Transportation and Infrastructure for the years 2009, 2010, 2011 and 2012 as shown in Table 7.10.

Table 7.10: Highway 1 Mainline Crash History

Year	Sev	Total	
real	Casualty	Property Damage Only	Total
2009	80	123	203
2010	78	131	209
2011	72	95	167
2012	87	94	181
Total	317	443	760
Average	80	110	190

The expected road safety performance for both the No Build option and the Highway 1 Widening project was derived from the Highway Safety Manual Part C predictive method to determine both the predicted and expected crash frequency for the highway corridor. The predicted crash frequency is widely used in safety practices, especially when comparing different improvement alternatives. Meanwhile, the expected crash frequency, which solves the "regression to mean" bias by combining the predicted and observed crash frequency using the Empirical Bayes method, is a more reliable estimator of the crash

SW1200SWF PARSONS Page 57



frequency. To predict the expected road safety performance, models were prepared for both the No Build option and the Highway 1 Widening project using the Interactive Highway Safety Design Model (IHSDM). The model predictions are shown in *Table 7.11*.

Table 7.11: Expected Highway 1 Mainline Crash Rates and Frequencies

Data Element	No Build Option	Highway 1 Widening	
First Year of Analysis	2024 (partial)		
Last Year of Analysis	2041		
Evaluated Length (km)	34.9	9740	
Average Future Road AADT (vpd)	60,	587	
Expected Crashes			
Total Crashes	3,259.07	2,846.95	
Fatal and Injury Crashes	1,079.67	1,015.07	
Property-Damage-Only Crashes	2,179.40	1,831.89	
Percent of Total Expected Crashes			
Percent Fatal and Injury Crashes (%)	33	36	
Percent Property-Damage-Only Crashes (%)	67	64	
Expected Crash Rate			
Crash Rate (crashes/km/yr)	5.4815	4.7884	
Fatal and Injury Crash Rate (crashes/km/yr)	1.8159	1.7073	
Property-Damage-Only Crash Rate (crashes/km/yr)	3.6656	3.0811	
Expected Travel Crash Rate			
Total Travel (million veh-km)	13,148.24		
Travel Crash Rate (crashes/million veh-km)	0.25	0.22	
Travel Fatal and Injury Crash Rate (crashes/million veh-km)	0.08	0.08	
Travel Property-Damage-Only Crash Rate (crashes/million veh-km)	0.17	0.14	

The expected difference in crash frequency between the two options, sorted by crash severity, is shown in *Table 7.12*.





Table 7.12: Highway 1 Expected Road Safety Performance (2024 – 2041)

Severity	No Build	Highway 1 Widening	
Severity	Crashes	Crashes	Difference
Fatality	34	31	-3
Incapacitating Injury	84	79	-5
Injury	963	905	-58
Property Damage Only	2,179	1,832	-347
Total	3,259	2,847	-412

Collision costs for economic analysis are based upon "Default Values for Benefit Cost Analysis in British Columbia, 2012", a reference used by the Ministry of Transportation and Infrastructure in British Columbia. This reference provides the following collision costs:

- Fatal crash \$6,385,999
- Non-fatal injury crash \$135,577
- Property damage only crash \$11,367

The present value of the expected crash cost savings for the Highway 1 Widening project, for the period from 2024 to 2041, is shown in *Table 7.13*.

Table 7.13: Road Safety Benefits Summary (2024 – 2041) PV

	No Build	Highway 1 Widening	
Road Safety Benefits	NA	\$14,125,000	

Note: Only nine months of benefits were assumed for 2024

#### B. Environmental Account

## B.1 Terrestrial Impacts

Effects on terrestrial resources due to the Highway 1 widening would be limited as all widening is within the median of an existing freeway. However, there are 77 Species at Risk that may potentially be encountered in the project area along Highway 1. Should Species at Risk be encountered in the project area, project work would stop while species are relocated. Overall Terrestrial impacts are expected to be low.

# B.2 Aquatic Impacts

Effects on aquatic resources due to the Highway 1 widening would be limited as all widening is within the median of an existing freeway. However, there are several rivers, creeks, and ditches within the project area which are known to contain fish. The project will take actions to salvage fish and protect habitat prior to construction. Also all work within

SW1200SWF Page 59 PARSONS



SW1200SWF

the area of these watercourses will be restricted to the fishery window. Overall Aquatics impacts are expected to be low.

## B.3 Archaeological / Historical Impacts

Effects on archaeological or historic sites due to the Highway 1 widening would be limited as all widening is within the median of an existing freeway. There are four pre-contact archaeological sites and one historical archaeological site exist within one kilometre of the project. Although the probability is low, the potential for encountering archaeological artifacts is greatest at the water courses and the undisturbed areas such as the 272 Street overpass, Bradner Road crossing and Townline overpass. However, in the unlikely event that archaeological artifacts are found, construction will stop in the vicinity of the affected area and the artifacts will be removed by an archaeological team. Overall archaeological and historic site impacts are expected to be low.

#### C. Financial Account

# C.1 Capital Cost

The relative construction cost was assessed at a high level using a functional design and typical unit costs referenced from the Ministry's Construction and Rehabilitation Cost Guide, and used the Elemental Parametric method. The cost is dependent on the extent of physical modifications, the complexity of the modifications (including geotechnical, utilities, drainage, and environmental compensation features), and right-of-way requirements.

Table 7.14: Highway 1 Widening Capital Cost Summary (\$2016)

	No Build	Hwy 1 Widening (\$M)
Project Management	NA	30.3
Engineering	NA	46.8
Grade Construction	NA	175.0
Structural	NA	130.9
Paving Construction	NA	29.2
Operational Construction	NA	6.9
Utilities	NA	3.3
Resident Engineering	NA	30.0
Contingency (30%)	NA	135.0
Total (rounded) \$M	NA	591

Page 60 PARSONS



#### C.2 Maintenance and Rehabilitation Cost

Consideration for annual maintenance and rehabilitation costs was based on standard lane-kilometre costs and scheduled major rehabilitation for major roadways. The cost is expressed as a 25 year present value. The No Build Option is assumed to require road surface rehabilitation in the year 2030. Based on the suggested implementation schedule, the Highway 1 Widening project would not require road surface rehabilitation until after the 2041 horizon year. The maintenance and rehabilitation cost estimates in present value are shown in *Table 7.15* for the base No Build and the Highway 1 Widening Project.

Table 7.15: Maintenance and Rehabilitation Cost Estimates (PV)

	No Build	Highway 1 Widening
Maintenance & Rehabilitation	\$8,200,000	\$5,400,000

### C.3 Salvage Value

The salvage value of the Highway 1 Widening project at the end of the 25 year business case period is assumed to be approximately 80 percent of the original construction value, which equals \$359,100,000, discounted at six percent to present value from the horizon year 2041. The estimated present value of the Salvage Value for the Highway 1 Widening project is shown in *Table 7.16*.

Table 7.16: Salvage Value Estimates (PV)

	No Build Highway 1 Widening	
Salvage Value	NA	\$83,700,000

#### C.4 Benefit Cost Ratio and Net Present Value

This calculation takes into consideration the 25 year present value of the travel time savings benefits, vehicle operating cost savings benefits, capital costs, maintenance and rehabilitation costs, and salvage value. The calculated benefit cost ratio and the net present value of the Highway 1 Widening Project are depicted in *Table 7.17*.

Table 7.17: Benefit Cost Ratio and Net Present Value (\$2016)

	No Build Hwy 1 Widening	
B/C Ratio	NA	1.00
NPV	NA	0.5 M

Table 7.18 provides an "at-a-glance" summary of the evaluation results.

SW1200SWF Page 61 PARSONS



SW1200SWF

Table 7.18: Evaluation Summary

Criterion/Option	No Build	Highway 1 Widening		
Customer Service Account				
Travel Time	Highway is congested during peak and off peak periods. It is anticipated that these conditions will worsen in the short and long term futures.	Improved traffic performance will result in Travel Time Savings of approximately \$65 M / year by 2041 Total Travel Time Savings: \$334 M		
Vehicle Operating Costs	Highway is congested during peak and off peak periods. It is anticipated that these conditions will worsen in the short and long term futures.	Improved traffic performance will result in less delays that translate into Vehicle Operating Cost savings of approximately \$3.5 M / year by 2041 Total VOC Savings: \$23 M		
Road Safety Performance	Road Safety Performance is poor compared to provincial average	Improved Road Safety Performance resulting in a reduction of 400 crashes from 2025 to 2041 Total Road Safety Savings: \$14 M		
	Environmental Account			
Terrestrial Impacts	NA	Low impact		
Aquatic Impacts	NA	Low impact		
Archaeological / Historical Impacts	NA	Low impact		
	Financial Account			
Capital Cost (\$2016)	NA	-\$449.0 M		
Maintenance and Rehabilitation Cost (\$2016)	-\$8.2 M	-\$5.4 M		
Salvage Value (\$2016)	NA	\$83.7 M		
Net Present Value (\$2016)	NA	0.5 M		
Overall Benefit Cost Ratio	NA	1.00		

The above results indicate that the estimated benefits more or less equal the estimated costs of the Highway 1 Widening project. However, it should be noted that the benefit estimates are considered conservative as the analysis assumes that all of the benefits will occur at completion of the final construction package, whereas some minor interim benefits are anticipated to accrue after completion of each construction package. Furthermore, other minor benefits such as reliability and sale of surplus lands have not been captured.

Page 62 PARSONS



**Table 7.19** presents the results of several scenarios developed to explore the Project's sensitivity to adjustments in key evaluation inputs. In the scenarios below, the discount rate and initial capital cost were varied. The sensitivity scenarios are as follows:

- Increase of the discount rate (in real terms) to 8% and 10%.
- Escalation of initial capital costs by 25%.

Table 7.19: Project Sensitivity Analysis

	Base Case	Sensitivity Cases		
	Dase Case	Α	В	С
	Discounted NPV (at 6%)	Discounted NPV (at 8%)	Discounted NPV (at 10%)	Discounted NPV (at 6%) (Capital Cost Increases by 25%)
Benefits:				
Travel Time Savings	\$334.0 million	\$248.37 million	\$187.31 million	\$334.0 million
Vehicle Operating Costs	\$22.925 million	\$17.25 million	\$13.16 million	\$22.925 million
Safety Benefits	\$14.125 million	\$10.69 million	\$8.20 million	\$14.125 million
Present Value of Benefits	\$371.05 million	\$276.31 million	\$208.67 million	\$371.05 million
Costs:				
Capital costs	-\$449.0 million	-\$412.5 million	-\$380.15 million	-\$561.25 million
O&M costs	-\$5.25 million	-\$3.95 million	-\$3.00 million	-\$5.25 million
Salvage value of asset	\$83.70 million	\$52.45 million	\$33.15 million	\$130.77 million
Present Value of Costs	-\$370.55 million	-\$364.00 million	-\$350.00 million	-\$435.73 million
Net Present Value	\$0.50 million	-\$87.69 million	-\$141.33 million	-\$64.68 million
Benefit Cost Ratio	1.00 to 1	0.76 to 1	0.60 to 1	0.85 to 1





#### PROJECT PERFORMANCE MEASURES 8.0

The primary objectives of this project are to provide additional capacity along Highway 1 in both directions of travel between 216 Street and Highway 11 to address current and future congestion as well as various safety issues.


Noting the capacity and safety objectives, performance measures will focus on throughput and travel time as well as a reduction in vehicle collisions. The following specific performance measures are proposed:

- Traffic Throughput during the weekday AM and PM peak periods in both the eastbound and westbound directions of travel (target threshold):
  - Between 232 Street and 264 Street (>4700 vph);
    - Current volumes ~ 3500 to 3600 vph
  - Between 264 Street and Mt. Lehman Road (>4400 vph)
    - Current volumes ~ 3500 to 3600 vph
  - Between Mt. Lehman Road and Clearbrook Road (>3900 vph)
    - Current volumes ~ 3500 to 3600 vph
  - Between McCallum Road and Highway 11 (>4200 vph)
    - Current volumes ~ 3500 to 3600 vph

# **Level of Service**

- As calculated using the Highway Capacity Manual for freeway segments; and,
- Level of Service not exceeding LOS D for any highway segment within the highway section. Current LOS is E / F for all of the study segments during the AM or PM peak hours.
- Travel Time during the weekday AM and PM peak periods in both the eastbound and westbound directions of travel where free flow speeds and associated travel times represent the target threshold:
  - Between 200 Street and 264 Street (@ free flow speed = 8.7 min)
    - Current travel time is approximately 14 to 15 min (EB PM Peak)
  - Between 264 Street and Mt. Lehman Road (@ free flow speed = 5.7 min)
    - Current travel time is approximately 9 to 10 min (EB PM Peak)
  - Between Mt. Lehman Road and Highway 11 (@ free flow speed = 5.5 min)
    - Current travel time is approximately 8 to 9 min (WB AM Peak)

SW1200SWF PARSONS Page 64







Reduction in vehicle collisions over the entire highway study section. The target threshold should aim for a collision rate that is less the existing collision rate for any segment within the highway section. The current collision rate as calculated in Section 7 is approximately 0.25 collisions per million vehicle kilometres travelled – averaged over the period between 2016 to 2041. The collision rate associated with the Highway 1 Widening Project is predicted to be approximately 0.22 collisions per million vehicles kilometres travelled.

To calculate the change in each performance measure in addressing the primary project objectives, additional "before" and "after" data collection activities are recommended. The "before" data collection activities should be undertaken at the outset of the project to confirm / validate the values presented above. According to the proposed schedule, the before data collection activities would be conducted either in the spring or fall of 2017. The "after" data collection activities are recommended to be conducted at the completion of the entire project. This could either occur in the fall of 2024 or the spring of 2025. The "before" and "after" data collection activities should be conducted in the same season such that the data is directly comparable.

The collision data statistics should be collected over a three to five year time frame leading up to initial construction and the after substantial completion of the entire project.



#### 9.0 PROJECT RISK MANAGEMENT

As with any project, the Highway 1 project has uncertainties and risks that could impact the project objectives (scope, budget, and schedule). These uncertainties and risks need to be identified, addressed, and managed for the project to be implemented successfully. This section discusses risk management planning, identified project risks, risk responses strategies, and the overall risk impact profile of the Highway 1 project.

#### 9.1 Risk Management Planning Methodology

The Risk Management Plan for this project followed a systematic process to identify project risks, conduct a qualitative analysis, and propose a response strategy for identified risks. The process included the following steps.

#### 9.1.1 RISK IDENTIFICATION

Determining which risks will affect the project and documenting their characteristics. Risk identification used the following risk breakdown structure:

- Environmental and Archaeological (EA);
- Structural and Geotechnical (SG);
- Design (D);
- Right-of-Way (RW);
- Utility (U);
- Hydraulics (H);
- Partner / Stakeholder (PS);
- Project Management (PM);
- Contracting (CG); and
- Construction (CN).

A review of functional project design documents was conducted to identify project risks. The functional design documents included:

- Highway 1 Functional Planning Background and Problem Definition, July 2014;
- Highway 1 Function Planning Option Generation & Evaluation Criteria, July 2014;





- Highway 1 Corridor Planning Study Draft Functional Planning Report, undated and ongoing;
- Environmental Constraints Review of the Highway 1 Corridor Between 216 Street and Highway 11, Draft Report, dated October 2014;
- Archaeological and Heritage Resources Review of Proposed Improvements along Highway 1 Between 216 Street and Highway 11, Draft Report, dated December 2014; and
- Geotechnical Overview Assessment Highway 1 Corridor 216 Street to Highway 11, Draft Report, dated December 2013.

#### 9.1.2 QUALITATIVE RISK ANALYSIS

Prioritizing risks for further analysis or action by assessing and combining their probability of occurrence and impact to the project.

#### 9.1.3 QUANTITATIVE RISK ANALYSIS

Numerically analyzing the effect of identified potential high impact risks on overall project objectives (Scope, Cost, and Schedule).

#### 9.1.4 RISK RESPONSE PLANNING

Developing options, and determining actions to be taken to reduce threats to the projects objectives. Planned risk responses must be appropriate to the significance of the risk, cost effective, timely, realistic within the project context, agreed upon by all parties involved, and owned by a responsible person.

For this project, the following strategies were used to respond to risks:

- Avoidance the team changes the project plan to eliminate the risk or to protect
  the project objectives from its impact. The team might achieve this by changing
  scope, adding time, or adding resources.
- Transference the ownership and responsibility for its management to a third party; it does not eliminate it. Transferring liability for risk is most effective in dealing with financial risk exposure.
- Mitigation the team seeks to reduce the probability or consequences of a risk event to an acceptable threshold. Mitigation costs should be appropriate, given the probability of the risk and its consequences.

SW1200SWF Page 67 PARSONS



- Acceptance the Project Manager and team decide to include a Risk Response
  Allowance in the project plan to deal with a risk. A response strategy will be
  developed and the project team will implement it, if the risk occurs.
- Recognized But No Action Taken the Project Manager and team decide not to change the project plan to deal with a risk, or cannot identify a suitable response action. Cost risks will be referred to the project contingency, and for schedule risks no action will be taken, leaving the project team to deal with the risk as it occurs.

### 9.2 Project Risks and Response Strategies

The results of the Risk Management process were documented in a project risk register. A summary of the project risks identified and response strategies are shown in *Table 9.1*. A detailed Project Risk Register is attached as *Appendix A*.



Table 9.1: Summary of Project Risks and Response Strategies

	Risk Identificati	on				Risk-Response Strategy
Risk Event	Risk Description	Risk Trigger	Impact Area	Affected WBS	Strategy	ACTION TO BE TAKEN
Soft Soil Issues in Project Area	Poor road subgrade conditions may be encountered in between 232 Street and 248 Street, near Townline Road, and near the south side of the Hwy 11 interchange.	Geotechnical investigation	Scope	WBS 1.4 & 1.7	Mitigate	Preloading / surcharging the insitu soils to consolidate soils and reduce differential settlement.
Interchange Configuration Enhancement	Should MoTI decide to place greater emphasis on Provincially significant traffic movements at the 264 St Interchange and add directional ramps.	Detailed design	Scope	WBS 1.3	Avoid	Confirm the design objectives for the 264 Street Interchange during the detailed design process.
Liquefaction	Liquefaction and softening soils under seismic conditions are a design concern primarily near the south side of the Hwy 11 interchange.	Detailed design	Scope	WBS 1.4 to 1.7	Avoid	On the south side of Highway 1 use deep foundations for the ramp abutment and mechanically stabilized earth embankments for the road fills and ramp approach.
Environmental Permits	Environmental permits within the Design Bid Build Contract process could cause undo delay to the project schedule.	Detailed design	Schedule	WBS 1.2 to 1.7	Avoid	MoTI to obtain all necessary environmental permits and provide to the successful contractor.
Archaeological Artifacts	Four pre-contact archaeological sites and one historical archaeological site exist within one kilometre of the project. Potential for encountering archaeological artifacts is greatest at the water courses and the undisturbed areas such as the 272 St overpass, Bradner Rd crossing and Townline overpass.	Archaeological artifacts uncovered during construction.	Scope	WBS 1.4 to 1.7	Accept	If Archaeological artifacts are found, construction stops in the vicinity of the affected area and the artifacts are removed by an archaeological team.
Species at Risk	Should Species at Risk be encountered in the project area during construction. There are 77 Species at Risk that may potentially be encountered in the project area along Highway 1.	Construction encounters Species at Risk.	Scope	WBS 1.2 to 1.7	Accept	Should Species at Risk be encountered in the project area, project work would stop while species are relocated.

SW1200SWF Page 69 PARSONS



	Risk Identificati	on				Risk-Response Strategy
Risk Event	Risk Description	Risk Trigger	Impact Area	Affected WBS	Strategy	ACTION TO BE TAKEN
Nesting Birds Impact	Should birds be nesting in trees within the project area, possibly in the trees located within the Highway 1 median. An existing stick nest of an unknown raptor is located near 216 Street.	Tree removal during construction.	Scope	WBS 1.4 to 1.7	Avoid	Clearing and grubbing to be undertaken outside the period of Mar. 1 to Aug. 1, which is the breeding bird period to avoid impacting active nests.
Fish Habitat Impacts	Should fish be encountered in the 7 river/creeks and / or tributaries located within the project area.	Construction encounters fish in creeks.	Scope	WBS 1.4 to 1.7	Transfer	Take actions to salvage fish and protect habitat prior to construction.
Steel Cost and Schedule Volatility	The price and delivery time of steel is very volatile and often mirrors the state of the general economy.	The procurement of the steel for the bridge.	Scope	WBS 1.1	Mitigate	The estimate for steel costs and schedule for delivery will be reviewed and updated at the time of tender for construction.
Fortis Gas Lines	Fortis gas line crossings of Highway 1. Potential impacts due to preloading of road or deep fills, especially at Townline Rd.	Detailed Design	Scope	WBS 1.2 to 1.7	Mitigate	Detailed design to review potential impacts of road preloading or deep road fills on crossing gas lines and recommend appropriate response strategy.
Funding Agreements	Agreement for partial funding of the project with other levels of government could take longer than anticipated.	Detailed Design	Schedule	WBS 1.1	Mitigate	Engage potential funding partners as early as possible to mitigate impacts to construction schedules.
Traffic Management	Maintaining adequate traffic flow during the reconstruction of the 232 St and 264 St interchanges, the RBC rail overpass, and the Glover Road overpass.	Detailed Design	Scope	WBS 1.2, 1.3 & 1.4	Avoid	Build temporary detour ramps and highway median crossovers to maintain traffic flow while avoiding the active construction areas.
Available Construction Windows (Days & Hours)	Construction on site will be restricted by fish windows and noise control bylaws.	Establishing the project base schedule timeline, and onsite construction.	Schedule	WBS 1.4 to 1.7	Transfer	Work to comply with all construction window regulations or obtain permission for variance.

SW1200SWF Page 70 PARSONS



#### 10.0 LEGAL REQUIREMENTS

The Province of British Columbia will manage the delivery of this project and confirms the following legal requirements:

- That the project will adhere to all applicable legislation and that all necessary permits and authorizations required for the project will be obtained;
- That the contract award process for eligible expenditures to be funded under the project will be in accordance with the Provinces' policies and procedures and will be transparent, competitive, fair, consistent with value for money principles, or in a manner otherwise acceptable to Canada, and if applicable, in accordance and consistent with the Agreement on Internal Trade and international trade agreements; and
- That an environmental impact assessment, Aboriginal consultations, and an Archaeological Impact Assessment have be conducted as part of this project. Consultation Logs from engagements with First Nations are available upon request.



#### 11.0 PROJECT BUDGET

The project cost estimate along with the estimated cash flow, as per the suggested implementation schedule outlined in Section 6, are summarized herein. The cash flow projection has also be prepared recognizing both eligible and ineligible costs as per Infrastructure Canada guidelines.

#### 11.1 Project Cost Estimate

The project cost estimate is partitioned by work package and work activity, as shown in *Table 11.1*. The cost estimate was prepared using an Elemental Parametric Estimating Method. This method of estimating builds up the estimate of a project from the expected cost of its elements and its parameters. The project cost estimate is divided into the project elemental tasks and grouped by the six work packages.

**Highway 1 Widening Cost Estimate Summary** Total Package Package Package Package **Package Package** 2 4 6 **Project Management** 4.5 3.4 4.1 3.5 6.5 8.3 30.3 Engineering 6.5 5.2 5.9 5.7 10.6 12.9 46.8 **Grade Construction** 14.1 15.3 15.6 31.8 55.1 43.6 175.0 Structural 33.7 19.1 31.6 0.0 7.0 39.5 130.9 **Paving Construction** 1.9 2.8 2.2 5.6 9.2 7.5 29.2 Operational Construction 8.0 0.7 0.4 1.3 1.6 2.2 6.9 Utilities 0.6 0.4 0.2 0.1 0.6 1.4 3.3 Resident Engineering 4.4 3.3 4.1 3.5 6.5 8.2 30.0 15.5 29.1 37.1 Contingency (30%) 19.9 15.1 18.5 135.0 82.5 Total (\$M) 86.4 65.3 67.0 126.2 160.7 588.3 Total (rounded) \$M 87 83 67 127 591 66 161

Table 11.1: Project Cost Estimate Summary

### 11.2 Potential Project Cost Sharing and Cash Flow Projection

A calculation of the potential funding for this project from Infrastructure Canada is based on eligible project costs. For provincially-owned assets, federal funding of 50 percent of the total eligible costs is requested. The funding contribution calculation and cash flow projection is shown in *Table 11.2*.



Table 11.2: Project Cash Flow Projection

Cost Type	;	2016/17	2017/18	2018/19	2019/20	2020/21	2021/22	2022/23	2023/24	Total
A: Non-Eligible Costs										
Project Management		\$50,000	\$600,000	\$1,000,000	\$1,500,000	\$1,400,000	\$1,800,000	\$1,500,000	\$800,000	\$ 8,700,000
Planning	\$	250,000								\$ 250,000
Environmental										\$ -
Stakeholder Relations			\$ 120,000	\$ 180,000	\$ 230,000	\$ 210,000	\$ 260,000	\$ 210,000	\$ 120,000	\$ 1,400,000
Corporate Services										\$ -
Engineering	\$	200,000								\$ 200,000
Propety Acquisition										\$ -
Regional Recoveries										\$ -
Contingency	\$	150,000	\$ 200,000	\$ 400,000	\$ 500,000	\$ 500,000	\$ 600,000	\$ 500,000	\$ 300,000	\$ 3,200,000
Sub-Total	\$	650,000	\$ 900,000	\$ 1,600,000	\$ 2,230,000	\$ 2,100,000	\$ 2,700,000	\$ 2,200,000	\$ 1,200,000	\$ 13,600,000
B: Eligible Costs										
Engineering External			\$ 16,600,000	\$ 8,400,000	\$ 7,900,000	\$ 14,600,000	\$ 18,100,000			\$ 65,600,000
Environmental External (included in Engineering)										\$ -
Construction Supervision			\$ 1,800,000	\$ 3,400,000	\$ 4,600,000	\$ 3,800,000	\$ 5,000,000	\$ 7,400,000	\$ 4,100,000	\$ 30,100,000
Construction (Road and Bridge)			\$ 20,400,000	\$ 39,600,000	\$ 54,400,000	\$ 44,400,000	\$ 56,200,000	\$ 83,900,000	\$ 47,100,000	\$ 346,000,000
First Nations Consultation & Accomodation			\$ 80,000	\$ 150,000	\$ 200,000	\$ 170,000	\$ 220,000	\$ 320,000	\$ 180,000	\$ 1,300,000
Contingency			\$ 11,700,000	\$ 15,500,000	\$ 20,100,000	\$ 18,900,000	\$ 23,900,000	\$ 27,500,000	\$ 15,400,000	\$ 133,000,000
Sub-Total	\$	-	\$ 50,600,000	\$ 67,100,000	\$ 87,200,000	\$ 81,900,000	\$ 103,400,000	\$ 119,100,000	\$ 67,000,000	\$ 576,300,000
TOTAL	\$	650,000	\$ 52,000,000	\$ 69,000,000	\$ 90,000,000	\$ 84,000,000	\$ 107,000,000	\$ 122,000,000	\$ 69,000,000	\$ 590,000,000
Federal Contribution	\$	-	\$ 25,300,000	\$ 33,550,000	\$ 43,600,000	\$ 40,950,000	\$ 51,700,000	\$ 59,550,000	\$ 33,500,000	\$ 288,150,000



### 12.0 CONCLUSIONS

There are a number issues currently present, or predicted to occur within the short term future, along Highway 1 from 216 Street to Highway 11. These issues include:

- Limited or insufficient capacity during the weekday AM and PM peak periods along most segments of the Highway 1 section between 216 Street and Highway 11;
- High collisions rates that exceed other similar provincial facilities;
- Vertical clearance issues at a number of existing structures including Glover Road,
   CP Rail overpass / portal, 232 Street, 264 Street, and Peardonville Road; and,
- Interchange configurations that no longer operate well under the higher traffic volumes experienced today or forecasted in the future planning horizon.

To address these issues, the preferred solution is to widen of Highway 1 by adding one lane in each direction into the median from 216 Street to Highway 11. The project will include the demolition of existing underpasses and reconfiguration of two interchanges, the 232 Street interchange and the 264 Street interchange. In addition, to accommodate the Highway 1 widening a number of grade separated crossings will need to be upgraded to achieve added crossing width and/or higher clearance under the structures. Consequently, the following scope of work is included in the proposed Highway 1 Widening project:

- Demolition and reconstruction of the Glover Road underpass structure;
- Demolition and reconstruction of the rail underpass structures at the CP Rail lane (Roberts Bank Corridor);
- Widening of the two overhead structures at Bradner Road;
- Upgrade of the entrance and exit ramps to the Bradner Rest Area along the westbound lanes of Highway 1;
- Demolition and reconstruction of the Peardonville Road underpass structure;
- New structure for the eastbound off-ramp to Highway 11; and
- Upgrade of the Highway 11 on-ramp to Highway 1 eastbound.

The estimated benefits of widening the highway over this section shows a benefit to cost ratio of 1.0. However, it should be noted that the estimated benefits are considered conservative and that the construction costs are high, due to the need to replace several overpass structures.

SW1200SWF Page 74 PARSONS

# **APPENDIX A**

Project Risk Management Register

# **QUANTITATIVE RISK ANALYSIS**

Project Title	Highway 1 Wi	dening (216 St to Highway 11)	) Project		RISK MANAGEMENT SUMMA	RY RESULTS			Proactive Risk		Risk Breakdown Structure (functional assignment)	Hesponse	Likely Cost Avoidance	Risk Breakdown Structure (functional assignment)	Planned Likely Response Cost Cost Avoidan				
Start Date	10/30/2016	Target Completion Date	06/30/24		Planned and Actual	MIN	MAX [	LIKELY	Management: Develop an action response strategy;		Environmental & Archaeological	0.8 \$M	-0.1 \$M	Hydraulics	0.0 \$M 0.0 \$N	м			
Project #	SW1200F	Estimated CN Duration	96.0Mo	Planned Cost	to Respond		4	40.1 \$M	assign risk owners to		Structural & Geotechnical	4.8 \$M	4.8 \$M	Partner / Stakeholder	0.2 \$M -0.1 \$I	м			
Last Review Date	9/19/2016	Estimated PE Cost	77.0 \$M	Est. \$ of Cost	Avoided (via risk management)	-23.6 \$M	-11.5 \$M -	17.6 \$M	implement action; monitor and record		Design	31.0 \$M	######	Project Management	3.0 \$M -0.3 \$I	м			
Project Manager	MoTI - TBA	Estimated ROW Cost	1.0 \$M	Actual Cost to	Respond			0.0 \$M	effectiveness of the risk response action.		Right-of-Way	0.0 \$M	0.0 \$M	Contracting	0.0 \$M 0.0 \$N	М			
Est \$ Impact of Signi		Estimated CN Cost	500.0 \$M	Est Actual \$ 0	Cost Avoided (via risk management)	0.0 \$M	0.0 \$M	0.0 \$M	response action.		Litility	0.3 \$M	-0.1 SM	Construction	0.0 \$M 0.0 \$N			& Cost Avoid	
Project Risks (exp. V	/alue)	Edinated on ood	000.0 \$111		(1000)	515 \$111	0.0 4	0.0 4		-	Cumy	0.0 4	· · · ·	3011011011011	0.0 4	(base		ed expected va	
	Risk I	dentification			Quantitative Analysis	10	Qu	alitative	Display of Most Likely Impact		Response			Monitoring and Control	Critical Issue	Estimated Response \$ Entered	Calculated Est. Cost Avoidance		Calculated Actual Cost Avoidance
Risk ID# Status RBS Group Project Phase-Date Identified	Summary Description Threat and/or Opportunity	Detailed Description of Risk Event (Specific, Measurable, Attributable, Relevant, Time bound) [SMART]	Risk Trigger	Type Probability	Risk Impact (\$M and / or Mo)	Estimated Expected Risk Impact (\$M) [min + (4 X ML) + max] X [probability])/(	Probability	Impact	Risk Matrix	Strategy		Risk Owner	Risk Review Dates	Date, Status and Review Comments (Do not delete prior comments, therefore providing a history)	Is Risk on Critical Path?	Planned Cost to Respond [\$M] (enter single number estimate)	Est Cost Avoided [\$M] (Expected Value of Risk) - (Est. Cost to Respond)	Actual Cost to Respond [\$M]	Est. Actual Costs Avoided [\$M]
(1) (2) (3) (4)	(5) (6)	(7)	(8)	(9) (10)	[10a] (11)	(12)	(13)	(14)	(15)	(16	(17)	(18)	(19)	(20)	(21)	(22)	(23)	(24)	(25)
SG1  Dormant  uctural & Geotechnical coping/ Predesign	Soft soil issues in project area.	Poor road subgrade conditions may be encountered in between 232 Street and 248 Street, near Townline Road, and near the south side of the Hwy 11 interchange.	Geotechnical investigation & Detailed Design	Oost 90%	MIN 0.2\$M  MAX 0.5\$M  Most Likely 0.3\$M  MIN 4.0Mo  MAX 12.0Mo	.4Mo 0.3\$M	Very High	derate NO RISK	AT LE M H AND MO NO MO N	Mitigation	Preloading / surcharging the insitu soils to consolidate soils and reduce differential settlement.	MoTi Project Manager	2016-Oct-1 2024-Dec-1		YES	\$0.3	-\$0.1 \$0.2 \$0.0		\$0.0 \$0.0 \$0.0
Str	Threat			SS	Most Likely 10.0Mo	∞		δ	Impact			2	201						
Dormant Utility mg / Pre- gv17/16	Threat  Fortis Gas Line	Fortis gas line crossings of Highway 1. Potential impacts due to preloading of road or deep fills, especially at Townline Rd.	Detailed Design	Cost No.	MIN 0.10\$M  MAX 0.40\$M  Most Likely 0.30\$M  MIN 2.0Mo	0.2\$M	Very High	W NO RISK	Ar A	Mitigation	Detailed design to review potential impacts of road preloading or deep road fills on crossing gas lines and recommend appropriate response strategy.	Project Manager	ct-1 2024-Dec-1		YES	\$0.3	-\$0.2 \$0.0 -\$0.1		\$0.0 \$0.0 \$0.0
Scopir	Threat			Schedu	MAX 4.0Mo Most Likely 3.0Mo	2.4Mc		Very Lc	VL L M H VH Impact			MoTI	2016-Oct-1						
Dormant Design Scoping / Pre- 9/16/16 design	All O	Should MoTI decide to place greater emphasis on Provincially significant traffic movements at the 264 St Interchange and add directional ramps.	Detailed Design	Schedule Cost	MIN 25.00\$M  MAX 35.00\$M  Most Likely 31.00\$M  MIN 5.0Mo  MAX 9.0Mo	3.5Mo 15.33\$M	Moderate	Low High	VH And	Avoidance	Confirm the design objectives for the 264 Street Interchange during the detailed design process.	MoTI Project Manager	2017-Jan-1 2017-Jun-1		YES	\$31.00	-\$18.5 -\$13.5 -\$15.5		\$0.0 \$0.0 \$0.0
	Threat			Ø	Most Likely 7.0Mo				Impact	뉴			50						
SG2  Dormant  Structural & Geotechnical  Scoping / Predesign	Threat  Liquefaction.  Threat	Liquefaction and softening soils under seismic conditions are a design concern primarily near the south side of the Hwy 11 interchange.	Detailed Design	Schedule Cost	MIN 0.8\$M  MAX 3.0\$M  Most Likely 1.5\$M  MIN 6.0Mo  MAX 12.0Mo  Most Likely 10.0Mo	9.2Mo 1.6\$M	Very High	Moderate NO RISK	VH Mo Atilige M M VL L M H VH Impact	Avoidance	On the south side of Highway 1 use deep foundations for the ramp abutment and mechanically stabilized earth embankments for the road fills and ramp approach.	MoTI Project Manager	2017-Jan-1 2017-Jun-1		YES	\$1.5	-\$0.7 \$1.4 -\$0.1		\$0.0 \$0.0 \$0.0
EA1  Dormant  vironment & Archaeologic Scoping / Pee- 9/16/16 design	artifacts in the work area.	Four pre-contact archaeological sites and one historical archaeological site exist within one kilometre of the project. Potential for encountering archaeological artifacts is greatest at the water courses and the undisturbed areas such as the 272 St overpass, Bradner Rd crossing and Townline	Archaeological artifacts uncovered during construction.	Cost 15%	Most Likely 0.50\$M  MIN 3.0Mo  MAX 8.0Mo	0.8Mo 0.08\$M	Very Low	ery Low NO RISK	AL COMPANY OF THE COM	Acceptance	If Archaeological artifacts are found, construction stops in the vicinity of the affected area and the artifacts are removed by an archaeological team.	MoTI Project Manager	16-Mar-1 2016-Dec-1		YES	\$0.10	\$0.0		\$0.0 \$0.0 \$0.0
<u> </u>	Threat	overpass.		σ	Most Likely 5.0Mo			>	Impact	丄			50						

# **QUANTITATIVE RISK ANALYSIS**

				Risk I	dentification				Quantitative Analysis			Qualitativ	Display of Most Likely Impact		Response			Monitoring and Control	Critical Issue	Estimated Response \$ Entered	Calculated Est. Cost Avoidance	Response \$ A	Calculated Actual Cost Avoidance
Risk ID#	Status	RBS Group Project PhaseDate	WBS Group	Summary Description Threat and/or Opportunity	Detailed Description of Risk Event (Specific, Measurable, Attributable, Relevant, Time bound) [SMART]	Risk Trigger	Туре	Probability	Risk Impact (\$M and / or Mo)	Estimated Expected Risk Impact (\$M) (finin + (4 X ML) + max] X [probability])/6	Probability	Impact	Risk Matrix	Strategy	including advantages and disadvantages	Risk Owner	Risk Review Dates	Date, Status and Review Comments (Do not delete prior comments, therefore providing a history)	Is Risk on Critical Path?	Planned Cost to Respond [\$M] (enter single number estimate)	Est Cost Avoided [\$M] (Expected Value of Risk) - (Est. Cost to Respond)	Actual Cost to Respond [\$M]	Est. Actual Costs Avoided [\$M]
(1)	(2)	(3) (4)	(5)	(6)	(7)	(8)	(9)	(10)	[10a] (11)	(12)	(13)	(14)	(15)	(16	(17)	(18)	(19)	(20)	(21)	(22)	(23)	(24)	(25)
EA2	Dormant	onment & Archaeologic pping / Pre- 9/16/16	onstruction	Threat  Environmental Permits	Environmental permits within the Design Bid Build Contract process could cause undo delay to the	Detailed Design	Cost	90%	MIN 0.02\$M  MAX 0.07\$M  Most Likely 0.05\$M	0.04\$M	Very High	NO RISK	Probability M H Wo Mo	voidance	MoTI to obtain all necessary environmental permits and provide to the successful contractor.	oject Manager	1 2016-Jun-1		YES	\$0.05	\$0.0 \$0.0 \$0.0		\$0.0 \$0.0 \$0.0
		gi Environme Scoping desig	All Co	Threat	project schedule.		Schedule		MIN 5.0Mo  MAX 12.0Mo  Most Likely 7.0Mo  MIN 0.30\$M	6.8Mo	>	Low	VL L M H VH	4		MoTI Pr	1 2016-Jan-				\$0.0		\$0.0
EA3	ormant	nt & Archaeolo / Pre- 9/16/1	tructic	Threat Species at Risk		Construction encounters	Cost	70%	MAX 0.50\$M  Most Likely 0.40\$M	0.28\$M	High	NO RISK	Probability H Mo Mo	septance	Should Species at Risk be encountered in the project area, project work would stop while species	oject Manager	1 2016-Dec-		YES	\$0.28	\$0.0 \$0.0 \$0.0		\$0.0 \$0.0 \$0.0
	٥	Environment Scoping / P design	All Co	Threat	potentially be encountered in the project area along Highway 1.	Species at Risk.	Schedule		MIN 6.0Mo  MAX 18.0Mo  Most Likely 12.0Mo	8.4Mo		Moderate	VL L M H VH	Acc	are relocated.	MoTI Pro	2016-Mar-1						
EA4	rmant	rt & Archaeolog Pre- 9/16/16	tructio	Threat  Nesting birds impact	Should birds be nesting in trees within the project area possibly in the trees located within the Highway 1 median. An existing	Tree removal during	Cost	50%	MIN 0.02\$M  MAX 0.10\$M  Most Likely 0.08\$M	0.04\$M	derate	NO RISK	Probability H NO	idance	Clearing and grubbing to be undertaken outside the period of Mar. 1 to Aug. 1, which is the breeding	ject Manager	2016-Dec-		YES	\$0.08	-\$0.1 \$0.0 \$0.0		\$0.0 \$0.0 \$0.0
	ŏ	Environment 8 Scoping / Pr	All Co	Threat	stick nest of an unknown raptor is located near 216 Street.	construction.	Schedule		MIN 2.0Mo MAX 8.0Mo Most Likely 4.0Mo	2.2Mo	°W	Very Low	VL L M H VH	+ Avc	bird period to avoid impacting active nests.	MoTI Pro	2016-Mar-1						
A5	rmant	nt & Archaeolog / Pre- 9/16/16	struction	Threat Fish habitat	Should fish be encountered in the 7 river/creeks and / or tributaries	Construction encounters fish	Cost	95%	MIN 0.20\$M  MAX 0.40\$M  Most Likely 0.30\$M	0.29\$M	/ High	NO RISK	Probability H NH N	ference	Take actions to salvage fish and protect habitat	tractor	2016-Dec-1		YES	\$0.30	-\$0.1 \$0.1 \$0.0		\$0.0 \$0.0 \$0.0
	°	Scoping desig	All Cor	impacts Threat	located within the project area.	in creeks.	Schedule		MIN 1.0Mo  MAX 7.0Mo  Most Likely 3.0Mo	3.2Mo	Very	Very Low	VL L M H VH	Trans	prior to construction.	Con	2016-Mar-1						
M1	mant	Reotechnical Pre- 9/16/16	rement	Threat  Steel Cost and Schedule	The price of steel, and the time for manufacture and delivery, are very volatile and often mirrors the state	procurement of	Cost	50%	MIN 1.0\$M  MAX 4.0\$M  Most Likely 3.0\$M	1.4\$M	Jerate	Very Low	VH H \$	gation	The estimate for steel costs and schedule for delivery will be reviewed and updated at the time of	ect Manager	2016-Dec-1		YES	\$3.00	-\$2.5 -\$1.0 -\$1.5		\$0.0 \$0.0 \$0.0
۵	Dor	Structural & Scoping / F	Procu	Volatility Threat	of the general economy, currency exchange rates, and the relationship of supply and demand.	the steel for the bridge.	Schedule		MIN 1.0Mo  MAX 6.0Mo  Most Likely 2.0Mo	1.3Mo	Mod	NO RISK	VL L M H VH	Mitig	tender for construction.	MoTI Proje	2016-Mar-1		<b>&gt;</b>				
IS.	mant	Stakeholder Pre- 9/16/16	rement	Threat	Agreement for partial funding of the project with other levels of	Functional and	Cost	50%	MIN 0.1\$M  MAX 0.3\$M  Most Likely 0.2\$M	0.1\$M	lerate	NO RISK	VH propability H Mo Mo	yation	Engage potential funding partners as early as possible to mitigate impacts to construction	ect Manager	2016-Dec-1		YES	\$0.2	-\$0.2 -\$0.1 -\$0.1		\$0.0 \$0.0 \$0.0
	Doi	Partner / Scoping / I design	Procu	Agreements	government could take longer than anticipated.	detailed design	Schedule		MIN 6.0Mo  MAX 24.0Mo  Most Likely 12.0Mo	6.5Mo	Moc	Moderate	VL L M H VH	+ Mitig	schedules.	MoTI Proje	2016-Mar-1						

# **QUANTITATIVE RISK ANALYSIS**


				Risk I	dentification			(	Quantitative /	Analysis		c	Qualitativ	e Display of	Most Likely Impact			Response			Monitoring and Control	Critical Issue	Respo	onse \$	Calculated Est. Cost Avoidance	Response \$	Calculated Actual Cost Avoidance
Risk ID#	Status RBS Group	Project PhaseDate	WBS Group	Summary Description Threat and/or Opportunity	Detailed Description of Risk Event (Specific, Measurable, Attributable, Relevant, Time bound) [SMART]	Risk Trigger	Туре	Probability	Risk I (\$M and	Impact 1 / or Mo)	Estimated Expected Risk Impact (\$M) [min + (4 X ML) + max] X [probability])/6	Probability	Impact		Risk Matrix		Strategy	ACTION TO BE TAKEN Response Actions including advantages and disadvantages include date	Risk Owner	Risk Review Dates	Date, Status and Review Comments (Do not delete prior comments, therefore providing a history)	Is Risk on Critical Path?	Planned Cost to Respond	[\$M] ter single number es	Est Cost Avoided [\$M] (Expected Value of Risk) - (Est. Cost to Respond)	Actual Cost to Respond [\$M]	Est. Actual Costs Avoided [\$M]
(1)	(2) (3)	) (4)	(5)	(6)	(7)	(8)	(9)	(10)	[10a]	(11)	(12)	(13)	(14)		(15)		(16)	(17)	(18)	(19)	(20)	(21)	(2	22)	(23)	(24)	(25)
PM1	Dormant Project Management		Road Works	Threat  Traffic  Management  Threat	Maintaining adequate traffic flow during the reconstruction of the 232 St and 264 St interchanges, the RBC rail overpass, and the Glover Road overpass.	Detailed Design	Schedule Cost	90%	MIN MAX Most Likely MIN MAX Most Likely	2.0\$M 5.0\$M 3.0\$M 6.0Mo 24.0Mo	11.7Mo 2.9\$M	Very High	Moderate Very Low	Probability	\$ Mo	VH	g	Build temporary detour ramps and highway median crossovers to maintain traffic flow while avoiding he active construction areas.	MoTI Project Manager	2016-Mar-1 2016-Dec-1		YES		3.0	-\$0.3		\$0.0 \$0.0 \$0.0
		11/28/11	Utilities	Threat Threat			Schedule Cost	0%	MIN MAX Most Likely  MIN MAX Most Likely	0.0Mo 0.0Mo 0.0Mo	0.0Mo	NO RISK	NO RISK NO RISK	Probability	VL L M H	VH						YES	\$0	0.0	\$0.0 \$0.0		\$0.0 \$0.0 \$0.0

Project Cost Estimate



## PACKAGE 1 - SECTIONS

ID	Chainage Start	Chainage End	Description
W.13	7+600	8+800	Highway 1 Westbound Local Widening around 232 Street
E.15	7+600	8+800	Highway 1 Eastbound Local Widening around 232 Street
72.1			72 Avenue Overpass
231.1			232 Street Overpass Replacement
232.2			Highway 1 Eastbound Off Ramp
232.3			Highway 1 Eastbound On Ramp
232.4			Highway 1 Westbound Off Ramp
232.5			Highway 1 Westbound On Ramp



File: Functional Pla Parsons	MoT A&W Contract #15/SWF - Highway 1 nning/Data\Costing/March 29th\[Package 1 - Hwy 1 Widening Package 1 - 232 IC EST.DATE April 4, 2016 R3 DATE: Sept 15, 2016	72 Avenue New Overpass and approaches 0 0	8+800 to 7+600 East and west of 232 St Interchange	8+800 to 7+600 East of 232 St IC to east of CP Rail Overpass	232 St New Overpass and approaches 0 0	232 St Interchange EB Off Ramp Loop 0	232 St Interchange EB On Ramp 0 0	232 St Interchange WB off Ramp Loop 0	232 St Interchange WB On Ramp 0 0		Total Line Cost C/LM
Conceptual Est.	Divison\site	Section 72.1	Section W.13	Section E.15	Section 232.1	Section 232.2	Section 232.3	Section 232.4	Section 232.5 MR	5120	
Blk Est. # 6.14A Version Sept.1, 200	Road Type DESCRIPTION \Length	21 570	16 1200	16 1400	21 555	21 575	21 460	21 200	21 OR 160 TR	0 5120	5120
	Engineering	MR 5,684,592	MR 1,162,546	MR 1,414,130	MR 4,652,283	MR 597,120	MR 397,531	MR 152,392	MR 219,751	14,280,346	2789
	Land Construction	0 29,483,844	0 5,394,490	0 6,610,587	0 24,327,114	0 2,806,850	0 1,770,429	0 648,855	0 1.098.028	72,140,198	0 14090
	Management Reserve Escalation	0	0	0	0	0	0	0	0	0	0
	Total	35,168,436	6,557,036	8,024,717	28,979,398	3,403,970	2,167,960	801,247	1,317,779	86,420,544	16879
	BASIC QUANTITY SUMMARY										
	Construct.Cost ONLY Per L.M. Land Area	51,726 1.6	4,495 1.9	4,722 4.5	43,833 2.1	4,881 1.3	3,849 1.1	3,244 0.5	6,863 \$/LM 0.7 ha	14,090 13.7	
	Mobilization	607.395	106.409	131.565	500.446	56,095	35.127	12.782	22.136	1,471,954	
	Land Cont.	0	0	0	0	0	0	0	0	1,471,954	
	Construction Cont.	6,273,266	1,145,509	1,403,122	5,171,249	595,024	375,605	137,651	232,800	15,334,226	16,647,738
	Engineering Cont.	1,311,829 530,698	268,280 99,373	326,338 122,398	1,073,604 442,701	137,797 52,711	91,738 32,956	35,167 12,084	50,712 20,591	3,295,465 1,313,512	
	Supervision Cont. Total Cont.	8,115,793	1,513,162	1,851,858	6,687,553	785,532	500,298	184,903	304,103	19,943,202	_
	S.G.S.B. C.B.C. Asphalt	3,977 2,288 1,338	8,714 4,611 1,971	6,512 3,484 4,812	6,405 3,944 2,420	3,333 1,845 1,645	2,666 1,476 1,316	1,159 642 572	2,505 m3 1,346 m3 1,188 t	35,271 19,635 15,261	
	Concrete Barrier	0	115	185	100	80	0	80	0 lm	560	1
	Noise Attentuation Wall	0	0	0	0	0	0	0	0 m2	0	
	No. of Light Poles Sidewalk	0	0	0	24	19	15	7	5 ea 0 lm	70 0	
	Curb and Gutter	0	0	0	0	0	0	0	0 Im	0	
	Signals	Ö	Ö	Ö	0	Ö	Ö	ō	0 ea	0	
	Bridge total area	2289	0	0	2099	0	0	0	0 m2	4,388	
											ENG
	Total Rock	0	0	0	0	0	0	0	0 m3	0	0
	Total OM Total Stripping	570 0	21,130 5,500	19,090 6,300	15,492 0	14,384 0	5,706 0	2,220 0	3,719 m3 838 m3	82,311 12,638	0 0
	Total Stripping	0	0	0,300	0	0	0	0	0 m3	12,030	ľ
	Total Cut/Excavation	570	26,630	25,390	15,492	14,384	5,706	2,220	4,556 m3	94,948	0
	Total Fill	14,749	18,251	27,784	33,772	18,513	12,509	1,702	2,851 m3	130,131	0
	Surplus or Deficit	-14,179	8,380	-2,394	-18,280	-4,130	-6,802	518	1,705 m3	-35,183	
	ENG & PM	5.685	1.163	1.414	4.652	0.597	0.398	0.152	0.220	14.280	14.281
	LAND	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
	CONST. BRIDGES-R/W	1.780 27.704	5.394 0.000	6.611 0.000	4.584 19.743	2.807 0.000	1.770 0.000	0.649 0.000	1.098 0.000	24.693 47.447	24.693 47.447
	MANAGEMENT RESERVE	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
	ESCALATION	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
	TOTAL (Millions) (2016Dollars)	35.169	6.557	8.025	28.979	3.404	2.168	0.801	1.318	86.420	86.421
	TOTAL Cost per meter		,	, ., .	, , , ,		, , -	, , , , , , , , , , , , , , , , , , , ,		\$ 16,879	
	Construction cost per meter	\$ 51,726	\$ 4,495	\$ 4,722	\$ 43,832	\$ 4,882	\$ 3,848	\$ 3,245	\$ 6,863	\$ 14,090	

File: Functional P Parson	0 - MoT A&W Contract #15\SWF - Highway 1 Planning\Data\Costing\March 29th\[Package 1 - Is Hwy 1 Widening S Package 1 - 1232 IC EST.DATE April 4, 2016 R3 DATE: Sept 15, 2016 bivison\site Road Type	72 Avenue New Overpass and approaches 0 0 Section 72.1	8+800 to 7+600 East and west of 232 St Interchange Section W.13	8+800 to 7+600 East of 232 St IC to east of CP Rail Overpass Section E.15	232 St New Overpass and approaches 0 0 Section 232.1	232 St Interchange EB Off Ramp Loop 0 Section 232.2	232 St Interchange EB On Ramp 0 0 Section 232.3	232 St Interchange WB off Ramp Loop 0 Section 232.4	232 St Interchange WB On Ramp 0 0 Section 232.5 MR	0	Total Line Cost C/LM
Version Sept.1, 2	00 DESCRIPTION \Length	570 MR	1200 MR	1400 MR	555 MR	575 MR	460 MR	200 MR	160 TR MR	5120	5120
SUMMARY	Y BY ACTIVITY LEVEL	IVIN	WITS	WIN	WIT	IVIN	IVIN	IVIN	MIN		Cost/LM
2000	PROJECT MANAGEMENT	1,811,318	337,714	413,306	1,492,557	175,318	111,659	41,267	67,871	4,451,010	869
2500 3000 3500	PLANNING PRELIMINARY DESIGN DETAILED DESIGN	0 220,634 2,340,812	0 195,600 360,952	0 228,200 446,287	0 181,490 1,904,632	93,725 190,280	0 74,980 119,154	0 32,600 43,357	0 26,080 75,088	1,053,309 5,480,563	0 206 1070
	Total Engineering	2,561,446	556,552	674,487	2,086,123	284,005	194,134	75,957	101,168	6,533,872	1276
4000	LAND ACQUISITION	0	0	0	0	0	0	0	0	0	0
5000 5200 5300	GRADE CONSTRUCTION ROAD SIDE CONSTRUCTION OTHER CONSTRUCTION	1,034,183 0 0	3,306,529 0 0	3,822,775 0 0	2,516,522 0 0	1,584,918 0 0	957,193 0 0	294,744 0 0	588,383 0 0	14,105,247 0 0	2755 0 0
5500 6000 6500	STRUCTURAL CONSTRUCTION PAVING CONSTRUCTION OPERATIONAL CONSTRUCTION	19,649,825 163,812 6,067	0 293,377 53,457	0 619,831 74,469	14,003,921 280,405 381,149	0 204,493 136,501	0 160,532 88,292	0 78,277 65,817	0 141,276 30,341	33,653,746 1,942,003 836,092	6573 379 163
6700 6800	UTILITY CONSTRUCTION RESIDENT ENGINEERING	57,000 1,768,994	165,000 331,244	160,000 407,993	55,500 1,475,668	57,500 175,703	46,000 109,852	20,000 40,281	16,000 68,636	577,000 4,378,372	113 855
	Total Construction	22,679,880	4,149,608	5,085,067	18,713,165	2,159,115	1,361,868	499,119	844,637	55,492,460	0 10838
9700	CONTINGENCY	8,115,793	1,513,162	1,851,858	6,687,553	785,532	500,298	184,903	304,103	19,943,202	3895
9800	SUB-TOTAL MANAGEMENT RESERVE	35,168,436 0	6,557,036 0	8,024,717 0	28,979,398 0	3,403,970 0	2,167,960 0	801,247 0	1,317,779 0	86,420,544 0	16879 0
	TOTAL	35,168,436	6,557,036	8,024,717	28,979,398	3,403,970	2,167,960	801,247	1,317,779	86,420,544	16879
9900	ESCALATION	0	0	0	0	0	0	0	0	0	0
	TOTAL COST	35,168,436	6,557,036	8,024,717	28,979,398	3,403,970	2,167,960	801,247	1,317,779	86,420,544	16879
	Const. Less Resident Eng.	20,910,886	3,818,363	4,677,074	17,237,496	1,983,412	1,252,016	458,838	776,001	51,114,088	9983

ACTI COD	Functional Pla Parsons (2016Dollars) VITY DE	MoT A&W Contract #15\SWF - Highway 1 Inning\Data\Costing\March 29th\[Package 1 - Hwy 1 Widening Package 1 - 232 IC EST.DATE April 4, 2016 R3 DATE: Sept 15, 2016	72 Avenue New Overpass and approaches 0 0	8+800 to 7+600 East and west of 232 St Interchange	8+800 to 7+600 East of 232 St IC to east of CP Rail Overpass	232 St New Overpass and approaches 0 0	232 St Interchange EB Off Ramp Loop 0	232 St Interchange EB On Ramp 0 0	232 St Interchange WB off Ramp Loop 0	232 St Interchange WB On Ramp 0 0		Total Line Cost
Blk Es	nceptual Est.	Road Type	Section 72.1	Section W.13	Section E.15	Section 232.1	Section 232.2	Section 232.3	Section 232.4	Section 232.5 MR 21 OR 160 TR	5120 0 5120	5120
	on Sept.1, 200		570 MR	1200 MR	1400 MR	555 MR	575 MR	460 MR	200 MR	160 TR MR	5120	5120
2500 2521		PLANNING - transport. planning study	0	0	0	0	0	0	0	0	0	0
2531	Consultant	- corridor study	0	0	0	0	0	0	0	0	0	0
2541 2502	Consultant	<ul> <li>functional plan. study</li> <li>general</li> </ul>	0	0	0	0	0	0	0	0	0	0
	Consultant s		0	0	0	0	0	0	0	0	0	0
		- project ident.	0	0	0	0	0	0	0	0	0	0
2520 2530		<ul> <li>transport. planning study</li> <li>corridor study</li> </ul>	0	0	0	0	0	0	0	0	0	0
2540	Client	<ul> <li>functional plan. study</li> </ul>	ő	0	ő	0	0	ő	0	0	ő	ŏ
2501	Client Client Sub-to	- general otal	0	0	0	0	0	0	0	0	0	0
2599	Planning Co					0	0	0		0	0	
		TOTAL PLANNING	0	0	0	0	0	0	0	0	0	
3000		PRELIMINARY DESIGN										
3013		- aerial base plan	0	0	0	0	0	0	0	0	0	0
3014 3015		- prel. design - control survey	39,900	84,000	98,000	38,850 0	40,250	32,200	14,000	11,200	358,400	70 0
3021	Consultant	- environmental impact	15,960	33,600	39,200	15,540	16,100	12,880	5,600	4,480	143,360	28
3031 3041		functroad field survey     functional design	0 28,500	0 60.000	70,000	0 27,750	0 28,750	0 23,000	0 10,000	0 8.000	0 256,000	0 50
3051		- funct. structural des.	127,724	0	0	91,025	0	0	0	0	218,749	43
3061		- geotechnical design	8,550 0	18,000	21,000	8,325 0	8,625 0	6,900	3,000	2,400	76,800 0	15 0
3071 3002		<ul> <li>right-of-way research</li> <li>general</li> </ul>	0	0	0	0	0	0	0	0	0	0
	Consultant s	sub-total	220,634	195,600	228,200	181,490	93,725	74,980	32,600	26,080	1,053,309	206
	Client Client	- aerial base plan - prel. design	0	0	0	0	0	0	0	0	0	0
3012		- control survey	0	0	0	0	0	0	0	0	0	ő
3020 3030		<ul> <li>environmental impact</li> <li>functroad field survey</li> </ul>	0	0	0	0	0	0	0	0	0	0
3040		- functional design	0	0	0	0	0	0	0	0	0	ő
3050		- funct. structural des.	0	0	0	0	0	0	0	0	0	0
3060 3070		- geotechnical design - right-of-way research	0	0	0	0	0	0	0	0	0	0
3001		- general	0	0	0	0	0	0	0	0	0	0
	Client Sub-to									0		
3099		design Contingency	66,190	58,680	68,460	54,447	28,118	22,494	9,780	7,824	315,993	62
		ELIMINARY DESIGN	286,824	254,280	296,660	235,938	121,843	97,474	42,380	33,904	1,369,302	267
6700	LINI D	UTILITIES	24.000	05.000	20.000	22.222	04.500	27.000	40.000	0.000	070 000	
	Util. Prov. Util. Prov.	- Hydro - Telephone	34,200 22,800	65,000 0	60,000 0	33,300 22,200	34,500 23,000	27,600 18,400	12,000 8.000	9,600 6,400	276,200 100,800	54 20
	Util. Prov.	sub-total	57,000	65,000	60,000	55,500	57,500	46,000	20,000	16,000	377,000	74
6712	Util.Others	- pipelines	0	100,000	100,000	0	0	0	0	0	200,000	39
6713		- telecommunication	0	0	0	0	0	0	0	0	0	0
6714		<ul> <li>storm &amp; sewer inspect.</li> <li>waterworks inspect.</li> </ul>	0	0	0	0	0	0	0	0	0	0
6716	Util.Others	- engineering services	0	0	0	0	0	0	0	0	0	0
6717 6718		<ul> <li>parks/recreation-prel.</li> <li>transit</li> </ul>	0	0	0	0	0	0	0	0	0	0
6719	Util.Others	- tr-ops/signs & detours	0	0	0	0	0	0	0	0	0	ŏ
6701	Util.Others Util.Others		0	0 100,000	0 100,000	0	0	0	0	0	200,000	0 39
6799	Util.Others 0		17,100	49,500	48,000	16,650	17,250	13,800	6,000	4,800	173,100	34
	TOTAL UTI		74,100	214,500	208,000	72,150	74,750	59.800	26,000	20.800	750,100	147
5000				,	,	,	,	,	=======================================			======
5032	Grade Cons		0	50,000	50,000	0	0	0	0	0	100,000	20
5033	Grade Cons	1 - sanitary	0	0	0	0	0	0	0	0	0	0

ACTIV	2016Dollars) Pa	lwy 1 Widening ackage 1 - 232 IC ST.DATE April 4, 2016	72 Avenue New Overpass and approaches 0	8+800 to 7+600 East and west of 232 St	8+800 to 7+600 East of 232 St IC to east of CP	232 St New Overpass and approaches 0 0	232 St Interchange EB Off Ramp Loop	232 St Interchange EB On Ramp 0 0	232 St Interchange WB off Ramp Loop 0	232 St Interchange WB On Ramp 0 0		Total Line Cost
COD	nceptual Est.	3 DATE: Sept 15, 2016 Divison\site	Section 72.1	Interchange Section W.13	Rail Overpass Section E.15	Section 232.1	Section 232.2	Section 232.3	Section 232.4	Section 232.5 MR	5120	C/LM
Blk Es	t. # 6.14A	Road Type	21	16	16	21	21	21	21	21 OR	0	
Versio	n Sept.1, 200	DESCRIPTION \Length	570 MR	1200 MR	1400 MR	555 MR	575 MR	460 MR	200 MR	160 TR MR	5120	5120
5034	Grade Const - :	storm _	0	0	0	0	0	0	0	0	0	0
	Grade Const-		0	1,500	1,500	0	0	0	0	0	3,000	1
5039		utility contingency Utilities Sub-total	0	15,450 66,950	15,450 66,950	0	0	0	0	0	30,900 133,900	6 26
	Grade Corist. (	otilities Sub-total									133,300	
		site prep./clear,grubbing	46,800	0	0	0	0	0	0	0	46,800	9
5020 5030		road grade/exc,placing,fill drainage/pipe,cul.	466,925 0	1,630,715 500,000	1,870,120 1,000,000	1,632,847	1,130,760	603,512	142,860	272,791 0	7,750,530 1,500,000	1514 293
	Grade Const - i		ő	0	0	Ö	ő	ŏ	0	Ö	0	0
5050		SGSB/produce,place,comp	278,407	610,011	455,810	448,339	233,289	186,631	81,144	175,347	2,468,978	482
5051 5060		CBC/produce,place,comp grade finishing landscaping	205,893	415,014 0	313,558	354,995 0	166,040	132,832	57,753 0	121,095	1,767,180	345 0
5061	Grade Const -	grade finishing hydro seed.	6,036	4,482	21,943	7,044	8,666	6,338	4,403	2,013	60,927	12
		grade finishing fencing	0	0	0	0	0	0	0	0	0	0
0000	Grade Const - I		0	0	0	0	0	0	0	0	0	0
5090	Grade Const - s	sidewalks,curb & gutter	0	0	0	0	0	0	0	0	0	0
5005		detours c/w ex,bf,paving	0	04 807	0 109,843	0 73,297	0	0 27,879	0 8,585	0 17,137	0 407,832	0 80
	Grade Const - (		30,122 310,255	94,807 976,509	1.131.382	754.956	46,163 475.476	27,879	88.423	17,137	4,200,674	820
0000	Grade Constru		1,344,438	4,231,538	4,902,657	3,271,478	2,060,394	1,244,350	383,168	764,898	18,202,921	3555
	GRADE CONS	STRUCTION COSTS	1,344,438	4,298,488	4,969,607	3,271,478	2,060,394	1,244,350	383,168	764,898	18,336,821	3581
3510	Grade Eng o	detailed design	94.111	300.894	347.872	229.003	144.228	87.105	26.822	53.543	1.283.577	251
		detailed design/Contingency	28,233	90,268	104,362	68,701	43,268	26,131	8,047	16,063	385,073	75
		general const. supervision quality assurance	40,333 26,889	128,955 85,970	149,088 99,392	98,144 65,430	61,812 41,208	37,331 24.887	11,495 7.663	22,947 15,298	550,105 366,736	107 72
	Grade Eng :		26,889	85,970 85,970	99,392	65,430	41,208	24,887	7,663	15,298	366,736	72
	Grade Eng I	Residency Contingency	28,233	90,268	104,362	68,701	43,268	26,131	8,047	16,063	385,073	75
	Grade Enginee	ering Sub-total	244,688	782,325	904,468	595,409	374,992	226,472	69,736	139,211	3,337,301	652
		Const. & Eng. Costs	1,589,125	5,080,813	5,874,075	3,866,887	2,435,386	1,470,822	452,904	904,110	21,674,122	4233
5500		TRUCTURAL CONSTRUCTION	0	0	0	0		0	0			0
	Struct.Const - :		0	0	0	0	0	0	0	0	0	0
5524	Struct.Const -		0	0	0	0	0	0	0	0	0	ő
	Struct.Const - I	mobilization utility contingency	0	0	0	0	0	0	0	0	0	0
5599		st. Utilities Sub-total	0	0	0	0	0	0	0	0	0	0
EE10	Struct Conet - 1	tunnel site preparation	0	0	0	0	0	0		0	0	0
		tunnel construction	0	0	0	0	0	0	0	0	0	0
5512	Struct.Const - :	snow shed site prep.	0	0	0	0	0	0	0	0	0	0
5513	Struct.Const - :	snow shed site const.	0	0	0	0	0	0	0	0	0	0
		bridge site preparation	0	0	0	1,000,000	0	0	0	0	1,000,000	195
	Struct.Const - I		0	0	0	0	0	0	0	0	0	0
		bridge abutments bridge superstructure	17,165,100	0	0	12,596,040	0	0	0	0	29,761,140	5813
5518	Struct.Const - I	retain. wall site prep.	0	Ö	Ö	0	ő	ő	0	0	0	0
		retaining wall const.	1,912,400	0	0	407.894	0	0	0	0	1,912,400	374
	Struct.Const - (		572,325 5,894,948	0	0	407,881 4,201,176	0	0	0	0	980,206 10,096,124	191 1972
		struction Sub-total	25,544,773	0	0	18,205,098	0	0	0	0	43,749,870	8545
	STRUCTURAL	CONSTRUCTION COSTS	25,544,773	0	0	18,205,098	0	0	0	0	43,749,870	8545
	Struct. Eng		2,043,582	0	0	1,456,408	0	0	0	0	3,499,990	684
		detailed design/Contingency general const. supervision	613,075 1,021,791	0	0	436,922 728,204	0	0	0	0	1,049,997 1,749,995	205 342
		general const. supervision quality assurance	1,021,791 510,895	0	0	728,204 364,102	0	0	0	0	1,749,995 874,997	171
6822	Struct. Eng s	surveying	127,724	Ö	0	91,025	0	Ō	0	0	218,749	43
6829	Struct. Eng I	Residency Contingency	498,123 4,815,190	0	0	354,999	0	0	0	0	853,122	167 1611
		ineering Sub-total	4,815,190	0	0	3,431,661	0	0		U	8,246,851	
		ral & Eng. Costs	30,359,962	0	0	21,636,758	0	0	0	0	51,996,721	10156

	Functional Planr Parsons <b>H</b> (2016Dollars) <b>F</b>	noT A&W Contract #15\SWF - Highway 1 ning\Data\Costing\March 29th\[Package 1 - dwy 1 Widening Package 1 - 232 IC	72 Avenue New Overpass and approaches	8+800 to 7+600 East and west	8+800 to 7+600 East of 232 St IC	232 St New Overpass and approaches	232 St Interchange EB Off Ramp	232 St Interchange EB On Ramp	232 St Interchange WB off Ramp	232 St Interchange WB On Ramp		Total Line Cost
ACTI		EST.DATE April 4, 2016 R3 DATE: Sept 15, 2016	0	of 232 St Interchange	to east of CP Rail Overpass	0	Loop 0	0	Loop 0	0		C/LM
	nceptual Est.	Divison\site	Section 72.1	Section W.13	Section E.15	Section 232.1	Section 232.2	Section 232.3	Section 232.4	Section 232.5 MR	5120	
	st. # 6.14A	Road Type	21	16	16	21	21	21	21	21 OR	0	F.100
Versi	on Sept.1, 200	DESCRIPTION \Length	570 MR	1200 MR	1400 MR	555 MR	575 MR	460 MR	200 MR	160 TR MR	5120	5120
			TWIL S	Nam v	NII I	NII t	TWIL S	14111	No. 5			
6000		PAVING CONSTRUCTION										
		machine paving asphalt machine paving concrete	159,041	284,832	601,777 0	272,238	198,537	155,856	75,997 0	137,162	1,885,440	368 0
	Paving Cons -		0	0	0	0	0	0	0	0	0	0
		shoulder paving	0	0	0	0	0	0	Ö	0	ő	Ö
6060		pavement finishing	0	0	0	0	0	0	0	0	0	0
6070 6001	Paving Cons - Paving Cons -		0 4,771	0 8,545	0 18,053	0 8.167	0 5.956	0 4.676	0 2,280	0 4,115	0 56,563	0 11
		pavement design	4,771	0,545	10,053	0,107	5,956	4,676	2,200	4,115	36,363	0
	Paving Cons -		49,144	88,013	185,949	84,121	61,348	48,160	23,483	42,383	582,601	114
	DAVING CON	ICTRIOTION COCTO	040.055	201 200	005.700	004 500	005.044	000.000	101.700	100.050	0.504.604	400
	PAVING CON	ISTRUCTION COSTS	212,955	381,390	805,780	364,526	265,841	208,692	101,760	183,659	2,524,604	493
		detailed design	14,907	26,697	56,405	25,517	18,609	14,608	7,123	12,856	176,722	35
		detailed design/Contingency	4,472	8,009	16,921	7,655	5,583	4,383	2,137	3,857	53,017	10
6860 6861		general const. supervision	4,259 8,518	7,628 15,256	16,116 32,231	7,291 14,581	5,317 10,634	4,174 8,348	2,035 4,070	3,673 7,346	50,492 100,984	10 20
6862	raving Eng	quality assurance surveying	1,065	1,907	4,029	1,823	1,329	1,043	509	918	12,623	2
6869		Residency Contingency	4,153 37,374	7,437	15,713	7,108 63,974	5,184	4,069	1,984	3,581	49,230 443,068	10 87
	raving Engine	eering Sub-total	37,374	66,934	141,414	03,974	46,655	36,625	17,859	32,232	443,066	
		Const. & Eng. Costs	250,329	448,325	947,194	428,500	312,496	245,317	119,619	215,892	2,967,671	580
											==========	======
6500		OPERATIONAL CONSTRUCTION										
6510 6520	Operat.Cons - Operat.Cons -		0	0	0	132,000 200,000	104,500	82,500 0	38,500 0	27,500 0	385,000 200,000	75 39
6530	Operat.Cons -		1,140	2,400	2,800	1,110	1,150	920	400	320	10,240	2
6540	Operat.Cons -	guard rail	0	34,500	55,500	30,000	24,000	0	24,000	0	168,000	33
6550		pavement markings	4,750	15,000	14,000	6,938	2,875	2,300	1,000	1,638	48,500	9
6501	Operat.Cons - Operat.Cons -		177 1.820	1,557 16,037	2,169 22,341	11,101 114,345	3,976 40,950	2,572 26,487	1,917 19,745	884 9.102	24,352 250,828	5 49
			1,020		22,341	114,040		20,407	10,740	3,102	250,020	
	OPERATIONA	AL CONSTRUCTION COSTS	7,887	69,494	96,810	495,494	177,451	114,779	85,562	39,444	1,086,920	212
3540	Operat. Eng -	detailed design	552	4.865	6,777	34,685	12,422	8,035	5,989	2,761	76,084	15
3549		detailed design/Contingency	166	1,459	2,033	10,405	3,726	2,410	1,797	828	22,825	4
6840		general const. supervision	434	3,822	5,325	27,252	9,760	6,313	4,706	2,169	59,781	12
	Operat. Eng - Operat. Eng -	quality assurance	158 39	1,390 347	1,936 484	9,910 2,477	3,549 887	2,296 574	1,711 428	789 197	21,738 5.435	4
		Residency Contingency	189	1,668	2,323	11,892	4,259	2,755	2,053	947	26,086	5
	Operational E	nginering Sub-total	1,538	13,551	18,878	96,621	34,603	22,382	16,685	7,692	211,949	41
	Total Operati	onal Const.& Eng.Costs	9,425	83.045	115,688	592,115	212,054	137,161	102,247	47,135	1,298,869	254
								=======================================		=======================================	=======================================	
5200		ROAD SIDE CONSTRUCTION										
5200			0	0	0	0	0	0	0	0	0	0
5204	RoadSide Cı -	sanitary	0	0	0	0	0	0	0	0	0	0
5205			0	0	0	0	0	0	0	0	0	0
5202	RoadSide Cr -	Utility Contingency	0	0	0	0	0	0	0	0	0	0
0200		nst. Utilities Sub-total	ő	ő	ő	ő	0	Ö	ő	Ö	ő	ő
5010	D 101 1 - 0											
5210 5220	RoadSide Cr-	weignscales safety rest areas	0	0	0	0	0	0	0	0	0	0
5230		tourist rest & view areas	0	0	0	0	0	0	0	0	ő	ő
5201	RoadSide Cı -		0	0	0	0	0	0	0	0	0	0
5299	RoadSide Cı-		0	0	0	0	0	0	0	0	0	0
	Hoad Side Co	nstruction Sub-total					0		0		0	
	ROAD SIDE C	CONSTRUCTION COSTS	0	0	0	0	0	0	0	0	0	0
	RoadSide Er-	detailed design	0	0	0	0	0	0	0	0	0	0
3559 6850	RoadSide Er-	detailed design/Contingency	0	0	0	0	0	0	0	0	0	0
6850		general const. supervision quality assurance	0	0	0	0	0	0	0	0	0	0
6852	RoadSide Er -	surveying	ő	ő	ő	ő	0	ő	ő	0	0	ő
6859	RoadSide Er-	Residency Contingency	0	0	0	0	0	0	0	0	0	0


ACTIV COD Cor Blk Es Versio	R3 DATE: Sept 15, 2016   nceptual Est.	72 Avenue New Overpass and approaches 0 0 Section 72.1 21 570 MR 0	8+800 to 7+600 East and west of 232 St Interchange Section W.13 16 1200 MR	8+800 to 7+600 East of 232 St IC to east of CP Rail Overpass Section E.15 16 1400 MR	232 St New Overpass and approaches 0 0 Section 232.1 21 555 MR 0	232 St Interchange EB Off Ramp Loop 0 Section 232.2 21 575 MR 0			232 St Interchange WB On Ramp 0 0 Section 232.5 MR 21 OR 160 TR	5120 0 5120	Total Line Cost C/LM 5120
5300 5303 5304 5305 5302	OTHER CONSTRUCTION Other Const - water Other Const - sanitary	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0
5320 5330 5340 5301	Other Const - mobilization Other Const - Contingency Other Construction Sub-total	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0
3579 6870 6871 6872		0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0
3500 3530	Total Other Const.& Eng.Costs  DETAILED DESIGN from 3510,3520,3540,3550,3570 Geotech. En - detailed design Geotech. En - Contingency	2,799,097 187,660 56,298	432,193 28,496 8,549	534,370 35,233 10,570	2,269,296 159,020 47,706	227,835 15,022 4,507	142,672 9,407 2,822	51,915 3,423 1,027	89,908 5,928 1,778	6,547,286 444,189 133,257	1279 87 26
6800	TOTAL DETAILED DESIGN COSTS  RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870	3,043,055 2,299,692	469,238	580,173 530,391	2,476,022 1,918,369	247,364	154,901 142,807	56,364 52,365	97,615	7,124,732 5,691,883	1392
	TOTAL RESIDENT ENG. COSTS	2,299,692	430,617	530,391	1,918,369	228,414	142,807	52,365	89,227	5,691,883	1112
	PART 1 SUMMARY CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY	20,910,886 4,330,439 7,572,398	3,818,363 887,796 1,411,848	4,677,074 1,082,480 1,727,866	17,237,496 3,561,791 6,239,786	1,983,412 459,708 732,936	1,252,016 303,986 466,801	458,838 116,238 172,523	776,001 169,804 283,742	51,114,088 10,912,244 18,607,900	9983 2131 3634 0
	CONSTRUCTION COST TOTAL	32,813,723	6,118,008	7,487,420	27,039,074	3,176,057	2,022,803	747,599	1,229,547	80,634,232	15749
2062 2063		738,309 0 0 0 0 738,309	137,655 0 0 0 0 137,655	168,467 0 0 0 0 168,467	608,379 0 0 0 0 608,379	71,461 0 0 0 71,461	45,513 0 0 0 0 45,513	16,821 0 0 0 16,821	27,665 0 0 0 27,665	1,814,270 0 0 0 0 1,814,270	354 0 0 0 0 354
		656,274 0 0 0 0 656,274	122,360 0 0 0 122,360	149,748 0 0 0 149,748	540,781 0 0 0 540,781	63,521 0 0 0 63,521	40,456 0 0 0 40,456	14,952 0 0 0 14,952	24,591 0 0 0 24,591	1,612,685 0 0 0 1,612,685	315 0 0 0 315

ACTI COD	Functional Pla Parsons (2016Dollars) VITY E	MoT A&W Contract #15/SWF - Highway 1 nnning/Data/Costing/March 29th/[Package 1 - Hwy 1 Widening Package 1 - 232 IC EST.DATE April 4, 2016 R3 DATE: Sept 15, 2016	72 Avenue New Overpass and approaches 0 0	8+800 to 7+600 East and west of 232 St Interchange	8+800 to 7+600 East of 232 St IC to east of CP Rail Overpass	232 St New Overpass and approaches 0 0	232 St Interchange EB Off Ramp Loop 0	232 St Interchange EB On Ramp 0 0	232 St Interchange WB off Ramp Loop 0	232 St Interchange WB On Ramp 0 0		Total Line Cost
	nceptual Est. st. # 6.14A	Divison\site Road Type	Section 72.1 21	Section W.13	Section E.15	Section 232.1 21	Section 232.2 21	Section 232.3 21	Section 232.4 21	Section 232.5 MR 21 OR	<b>5120</b>	
	on Sept.1, 200		570 MR	1200 MR	1400 MR	555 MR	575 MR	460 MR	200 MR	160 TR MR	5120	5120
2070		- wages & expenses - adv., media, displays	196,882	36,708 0	44,925 0	162,234	19,056	12,137	4,486 0	7,377	483,805 0	94 0
2073	Public Rel.	<ul> <li>opening ceremonies</li> </ul>	0	0	0	0	0	0	0	0	0	0
2071	Public Rel. Public Relat	- general tions Sub-total	0 196,882	0 36,708	0 44,925	0 162,234	0 19,056	0 12,137	0 4,486	0 7,377	0 483,805	0 94
		- lawyers fees	22,970	4,283	5,241	18,927	2,223	1,416	523	861	56,444	11
2041	Legal Costs Legal Costs		0 22,970	0 4,283	0 5,241	0 18,927	0 2,223	0 1,416	0 523	0 861	0 56,444	0 11
		- const./ liability, E&O	196,882	36,708	44,925	162,234	19,056	12,137	4,486	7,377	483,805	94
2081	Insurance Legal Costs		0 196,882	0 36,708	0 44,925	0 162,234	0 19,056	0 12,137	0 4,486	0 7,377	483,805	0 94
2099	Project Man	agement Contingency	543,395	101,314	123,992	447,767	52,595	33,498	12,380	20,361	1,335,303	261
		OJECT MANAGEMENT COSTS	2,354,713	439,028	537,297	1,940,324	227,914	145,156	53,648	88,232	5,786,312	1130
4000		LAND 4-Mrkt,ROW,Serv,Imp.V,Ease.C,T	0	0	0	0	0	0	0	0	0	0
4010	Acquisition S		0	0	0	0	0		0	0	ő	0
		4-Bus.,5%,Mrg.P,Rel\$,P/Tax,Etc	0	0	0	0	0	0	0	0	0	0
4040	Land(Code	4-Owners(LS,Apprsl,Rprt,Lgl,In 4-Demolition	0	0	0	0	0	0	0	0	0	0
		-Pro.Man,P.Tax,Util,Security	0	0	0	0	0	0	0	0	0	0
	Land(Code 4		0	0	0	0	0	0	0	0	0	0
		4-Acq.F,M/Sal,TrvIV,Cntr.S,Appr.	0	ő	ő	0	Ö	ŏ	ő	ŏ	ő	ő
	Associated (	costs-sub-total	0	0	0	0	0	0	0	0	0 0 0	0 0 0 0
4099	Land Contin	gency Sub-total	0	0	0	0	0	0	0	0	0	0
	TOTAL LAN	ND COSTS	0	0	0	0	0	0	0	0	0	0
9800		MANAGEMENT RESERVE		0		0		0	0	0	0	0
	MAN. RES. MAN. RES.		0	0	0	0	0	0	0	0	0	0
	MAN. RES.	<ul> <li>utility construction</li> </ul>	0	0	0	0	0	0	0	0	0	0
	MAN. RES. MAN. RES.		0	0	0	0	0	0	0	0	0	0
	MAN. RES.	<ul> <li>paving construction</li> </ul>	Ö	Ö	Ö	Ö	0	ō	Ö	0	Ö	ő
	MAN. RES. MAN. RES.		0	0	0	0	0	0	0	0	0	0
		- other construction	0	0	0	0	0	0	0	0	0	ő
		- project management	0	0	0	0	0	0	0	0	0	0
	MAN. RES.	- land - detailed eng.	0	0	0	0	0	0	0	0	0	0
	MAN. RES.	- residency eng.	0	0	0	0	0	0	0	0	0	0
		- risk contingency	0	0	0	0	0	0	0	0	0	0
		NAGEMENT RESERVE	0	0	0	0	0		0	0	0	0
	FISCAL	S ESCALATION										
9900	ESCALATIC YEAR	PROJECTED ESCALATION										
	2006-2007	. HOULD LOOMENTION	0	0	0	0	0	0	0	0	0	0
	2007-2008		0	0	0	0	0	0	0	0	0	0
	2008-2009 2009-2010		0	0	0	0	0	0	0	0	0	0
	2010-2011		ő	Ö	ő	0	0	0	0	ō	ő	ő
	2011-2012		0	0	0	0	0	0	0	0	0	0
	2012-2013		0	0	0	0	0	0	0	0	0	0
			•	·	· ·	v	v	v	v	- 1		

Q:\SW\1200 - MoT A&W Contract #15\SWF - Highway 1										
File: Functional Planning\Data\Costing\March 29th\[Package 1 -	72 Avenue	8+800	8+800	232 St	232 St	232 St	232 St	232 St		Total
Parsons Hwy 1 Widening	New Overpass	to 7+600	to 7+600	New Overpass	Interchange	Interchange	Interchange	Interchange		Line
(2016Dollars) Package 1 - 232 IC	and approaches	East and west	East of 232 St IC	and approaches	EB Off Ramp	EB On Ramp	WB off Ramp	WB On Ramp		Cost
ACTIVITY EST.DATE April 4, 2016	0	of 232 St	to east of CP	0	Loop	0	Loop	0		
CODE R3 DATE: Sept 15, 2016	0	Interchange	Rail Overpass	0	0	0	0	0		C/LM
Conceptual Est. Divison\site	Section 72.1	Section W.13	Section E.15	Section 232.1	Section 232.2	Section 232.3	Section 232.4	Section 232.5 MR	5120	
Blk Est. # 6.14A Road Type	21	16	16	21	21	21	21	21 OR	0	
Version Sept.1, 200 DESCRIPTION \Length	570	1200	1400	555	575	460	200	160 TR	5120	5120
	MR	MR	MR	MR	MR	MR	MR	MR		
2014-2015	0	0	0	0	0	0	0	0	0	0
TOTAL ESCALATION	0	0	0	0	0	0	0	0	0	0
PART 2 SUMMARY NON-CONSTRUCTION COSTS										
Non-Construction	1,811,318	337,714	413,306	1,492,557	175,318		41,267	67,871	4,451,010	869
Non-Const. Contingency	543,395	101,314	123,992	447,767	52,595	33,498	12,380	20,361	1,335,303	261
TOTAL NON-CONSTRUCTION COSTS	2.354.713	439.028	537.297	1.940.324	227.914	145.156	53.648	88.232	5.786.312	1130
	2,004,710	400,020	307,237	1,340,024	221,314	143,130	30,040		3,700,312	
DIVISION TOTAL FOR ROAD TYPE	35,168,436	6,557,036	8,024,717	28,979,398	3,403,970	2,167,960	801,247	1,317,779	86,420,544	16879

#### PACKAGE 2 - SECTIONS

ID	Chainage Start	Chainage End	Description
W.10	14+600	16+500	Highway 1 Westbound Lanes Local Widening around 264 Street
E.12	14+600	16+500	Highway 1 Eastbound Lanes Local Widening around 264 Street
264.1			264 Street Overpass Replacement
264.2			Highway 1 Eastbound Off Ramp
264.3			Highway 1 Westbound Off Ramp
264.4			Highway 1 Westbound On Ramp
264.5			Highway 1 Eastbound On Ramp



File: Functional Plan Parsons I (2016Dollars) I ACTIVITY	MoT A&W Contract #15\SWF - Highway 1 ning\Data\Costling\March 29th\[Package 2 - Hwy 1 Widening Package 2 - 264 IC EST.DATE April 4, 2016 R3 DATE: Sept 15, 2016	16+500 to 14+600 East and West of the 264 St Interchange Section W.10	264 Street New Overpass and approaches 0 0 Section 264.1	264 Street Interchange EB Off Ramp Loop 0 Section 264.2	264 Street Interchange WB Off Ramp Loop 0 Section 264,3	264 Street Interchange WB On Ramp 0 Section 264.4	264 Street Interchange EB On Ramp 0 Section 264.5	16+500 to 14+600 To the east and west of 264 St IC Section E.12 MF	6571	Total Line Cost C/LM
Blk Est. # 6.14A	Road Type	16	21	21	21	21	21	16 OR	0	
Version Sept.1, 200	DESCRIPTION \Length	1900 MR	507 MR	740 MR	604 MR	470 MR	450 MR	1900 TR MR	6571	6571
	Engineering	1,748,755	5,722,005	793,688	595,467	288,885	278,635	1,734,567	11,162,001	1699
	Land Construction Management Reserve Escalation	7,844,136 0 0	0 29,875,245 0 0	3,761,256 0	2,759,980 0	1,114,335 0 0	0 1,078,975 0 0	7,752,373 0 0	54,186,300 0	8246 0 0
-	Total	9,592,891	35,597,250	4,554,944	3,355,446	1,403,221	1,357,610	9,486,940	65,348,301	9945
Ċ	BASIC QUANTITY SUMMARY Construct.Cost ONLY Per L.M. Land Area	4,128 2.6	58,926 1.4	5,083 1.5	4,570 1.4	2,371 1.0	2,398 0.6	4,080 \$/L\\ 6.4 ha	8,246 14.8	
-	Mobilization Land Cont.	159,611 0	615,479 0	75,266 0	55,063 0	21,620	20,949 0	158,003	1,105,991	-
	Construction Cont. Engineering Cont. Supervision Cont.	1,661,997 403,559 148,188	6,354,648 1,320,463 539,640	797,436 183,159 70,546	585,266 137,415 51,652	236,786 66,666 20,368	229,275 64,300 19,719	1,642,428 400,285 146,581	11,507,836 2,575,846 996,695	1
-	Total Cont.	2,213,744	8,214,750	1,051,141	774,334	323,820	313,295	2,189,294	15,080,377	
	S.G.S.B. C.B.C. Asphalt	11,650 5,358 6,521	4,835 2,950 2,551	4,565 2,558 2,385	3,501 1,938 1,728	2,024 1,155 1,120	2,046 1,160 1,107	8,910 m3 4,723 m3 6,768 t	37,531 19,842 22,179	
	Concrete Barrier Noise Attentuation Wall No. of Light Poles	125 0 0	80 0 22	0 0 25	0 0 20	0 0 16	0 0 15	85 lm 0 m2 0 ea	290 0 98	1
-	Sidewalk Curb and Gutter Signals	0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0	0 Im 0 Im 0 ea	0	
-	Bridge total area	0	2701	0	0	0	0	0 ea		1
	Total Rock Total OM Total Stripping Total Borrow	0 42,740 5,200 0	0 9,025 4,563 0	0 24,615 2,220 0	0 15,878 1,812 0	0 3,663 350 0	0 2,942 1,125 0	0 m3 35,790 m3 5,100 m3 0 m3	134,653 20,370	
-	Total Cut/Excavation Total Fill Surplus or Deficit	47,940 36,605 11,336	13,588 12,121 1,467	26,835 14,759 12,076	17,690 12,494 5,195	4,013 2,808 1,205	4,067 2,255 1,811	40,890 m3 34,891 m3 5,999 m3	155,023 115,934	1 0
_	ENG & PM LAND	1.749 0.000	5.722 0.000	0.794 0.000	0.595 0.000	0.289 0.000	0.279 0.000	1.735 0.000	11.162 0.000	0.000
	CONST. BRIDGES-R/W	7.844 0.000	2.928 26.947	3.761 0.000	2.760 0.000	1.114 0.000	1.079 0.000	7.752 0.000	27.239 26.947	26.947
	MANAGEMENT RESERVE ESCALATION	0.000 0.000	0.000 0.000	0.000 0.000	0.000 0.000	0.000 0.000	0.000 0.000	0.000 0.000	0.000 0.000	
-	TOTAL (Millions) (2016Dollars)	9.593	35.597	4.555	3.355	1.403	1.358	9.487	65.348	
	TOTAL Cost per meter Construction cost per meter						\$ 3,017 \$ 2,398		\$ 9,945 \$ 8,246	

File: Functional F Parsor	Road Type	16+500 to 14+600 East and West of the 264 St Interchange Section W.10 16 1900	264 Street New Overpass and approaches 0 0 Section 264.1 21 507 MR	264 Street Interchange EB Off Ramp Loop 0 Section 264.2 21 740 MR	264 Street Interchange WB Off Ramp Loop 0 Section 264.3 21 604	264 Street Interchange WB On Ramp 0 Section 264.4 21 470 MR	264 Street Interchange EB On Ramp 0 Section 264.5 21 450 MR	16+500 to 14+600 To the east and west of 264 St IC Section E.12 MR 16 OR 1900 TR	<b>6571</b> 0 6571	Total Line Cost C/LM
SUMMAR	Y BY ACTIVITY LEVEL									Cost/LM
2000	PROJECT MANAGEMENT	494,073	1,833,403	234,598	172,819	72,272	69,922	488,616	3,365,703	512
2500 3000 3500	PLANNING PRELIMINARY DESIGN DETAILED DESIGN	0 309,700 541,423	0 206,878 2,361,261	0 120,620 255,311	0 98,452 186,780	76,610 73,338	73,350 71,062	309,700 535,966	1,195,310 4,025,142	0 182 613
	Total Engineering	851,123	2,568,139	375,931	285,232	149,948	144,412	845,666	5,220,451	794
4000	LAND ACQUISITION	0	0	0	0	0	0	0	0	0
5000 5200 5300	GRADE CONSTRUCTION ROAD SIDE CONSTRUCTION OTHER CONSTRUCTION	4,567,874 0	1,561,668 0	2,141,386 0	1,559,019 0	516,098 0	499,523 0	4,495,741 0 0	15,341,308 0	2335
5500 6000 6500	STRUCTURAL CONSTRUCTION PAVING CONSTRUCTION OPERATIONAL CONSTRUCTION	0 850,007 62,109	19,113,329 300,575 155,887	0 295,247 147,488	0 213,814 117,655	0 133,009 93,179	0 132,190 87,537	0 878,239 50,779	19,113,329 2,803,081 714.634	2909 427 109
6700 6800	UTILITY CONSTRUCTION RESIDENT ENGINEERING	60,000 493,961	50,700 1,798,799	74,000 235,153	60,400 172,174	47,000 67,895	45,000 65,731	50,000 488,605	387,100 3,322,318 0	59 506 0
	Total Construction	6,033,951	22,980,958	2,893,274	2,123,061	857,181	829,981	5,963,364	41,681,770	6343
9700	CONTINGENCY	2,213,744	8,214,750	1,051,141	774,334	323,820	313,295	2,189,294	15,080,377	2295
9800	SUB-TOTAL MANAGEMENT RESERVE	9,592,891 0	35,597,250 0	4,554,944 0	3,355,446 0	1,403,221 0	1,357,610 0	9,486,940 0	65,348,301 0	9945 0
	TOTAL	9,592,891	35,597,250	4,554,944	3,355,446	1,403,221	1,357,610	9,486,940	65,348,301	9945
9900	ESCALATION	0	0	0	0	0	0	0	0	0
	TOTAL COST	9,592,891	35,597,250	4,554,944	3,355,446	1,403,221	1,357,610	9,486,940	65,348,301	9945
====	Const. Less Resident Eng.	5,539,989	21,182,159	2,658,121	1,950,887	789,286	764,250	5,474,759	38,359,452	5838

(ACTIV COD Cor Blk Es Versio 2500 2521 2531 2541 2502	Functional Pla Parsons 2016Dollars) //ITY E nceptual Est. t. # 6.14A n Sept.1, 200	PLANNING - transport. planning study - corridor study - functional plan. study - general	16+500 to 14+600 East and West of the 264 St Interchange Section W.10 16 1900 MR	264 Street New Overpass and approaches 0 0 Section 264.1 21 507 MR 0 0 0 0 0	264 Street Interchange EB Off Ramp Loop 0 Section 264.2 21 740 MR	264 Street Interchange WB Off Ramp Loop 0 Section 264.3 21 604 MR	264 Street Interchange WB On Ramp 0 Section 264.4 21 470 MR	264 Street Interchange EB On Ramp 0 Section 264.5 21 450 MR	16+500 to 14+600 To the east and west of 264 St IC Section E.12 MR 16 1900 MR 0 0 0 0 0 0	6571 0 6571 0 0 0 0 0	Total Line Cost C/LM 6571 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
2520 2530	Client Client Client	- transport. planning study - corridor study - functional plan. study	0	0	0	0	0	0	0 0	0	0 0
2501	Client Sub-to	- general otal	0	0	0	0	0	0	0	0	0
2599	Planning Co	ntingency	0	0	0	0	0	0	0	0	0
		TOTAL PLANNING	0	0	0	0	0	0	0	0	0
3014 3015 3021 3031 3041 3051 3061 3071	Consultant Consultant Consultant Consultant Consultant Consultant Consultant Consultant	PRELIMINARY DESIGN - aerial base plan - prel. design - control survey - environmental impact - functroad field survey - functional design - funct structural des geotechnical design - right-of-way research - general	0 133,000 0 53,200 95,000 0 28,500 0 0 309,700	0 35,490 0 14,196 0 25,350 124,237 7,605 0 0 206,878	0 51,800 0 20,720 0 37,000 0 11,100 0 0	42,280 0 16,912 0 30,200 0 9,060 0	32,900 0 13,160 0 23,500 0 7,050 0 0 76,610	0 31,500 0 12,600 0 22,500 0 6,750 0 0 73,350	0 133,000 0 53,200 0 95,000 0 28,500 0 0 309,700	0 459,970 0 183,988 0 328,550 124,237 98,565 0 0	0 70 0 28 0 50 19 15 0
3011 3012 3020 3030 3040 3050 3060 3070	Client Cl	- aerial base plan - prel. design - control survey - environmental impact - funct-road field survey - functional design - funct. structural des geotechnical design - right-of-way research - general	0 0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0 0
3099		design Contingency	92,910	62,063	36,186	29,536	22,983	22,005	92,910	358,593	55
		ELIMINARY DESIGN	402,610	268,941	156,806	127,988	99,593	95,355	402,610	1,553,903	236
	Util. Prov.	UTILITIES - Hydro - Telephone sub-total	60,000 0 60,000	30,420 20,280 50,700	44,400 29,600 74,000	36,240 24,160 60,400	28,200 18,800 47,000	27,000 18,000 45,000	50,000 0 50,000	276,260 110,840 387,100	42 17 59
6713 6714 6715 6716 6717 6718 6719	Util.Others Util.Others Util.Others Util.Others Util.Others	- telecommunication - storm & sewer inspect waterworks inspect engineering services - parks/recreation-prel transit - tr-ops/signs & detours - general	0 0 0 0 0 0 0	0 0 0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0 0
6799	Util.Others (	Contingency	18,000	15,210	22,200	18,120	14,100	13,500	15,000	116,130	18
	TOTAL UTI		78,000	65,910	96,200	78,520	61,100	58,500	65,000	503,230	77
	Grade Cons Grade Cons	GRADE CONSTRUCTION 1- water	50,000 0	0	0	0	0	0	50,000	100,000	15 0

Control   Cont			16+500 to 14+600 East and West of the 264 St Interchange	264 Street New Overpass and approaches 0 0	264 Street Interchange EB Off Ramp Loop 0	264 Street Interchange WB Off Ramp Loop 0	264 Street Interchange WB On Ramp 0	264 Street Interchange EB On Ramp 0	16+500 to 14+600 To the east and west of 264 St IC		Total Line Cost C/LM
										6571	
Section   Sect										6571	6571
Section   1,500   0   0   0   0   0   0   0   0   0			MR	MR	MR	MR	MR	MR	MR		
5.696   Gala Come: Utility contriguency   15.650   0   0   0   0   0   0   0   0   0											
Control Control Utilities Sub-Initial   66,560   0   0   0   0   0   6,595   13,000   20   20   20   20   20   20   20			15.450								
\$200 Cardio Corni-road gradenesc plantry III   \$2,044.205   \$2,000 Cardio Corni-road gradenesc plantry III   \$2,044.205   \$2,000 Cardio Corni-road gradenesc plantry III   \$2,044.205   \$2,000 Cardio Corni-road gradenesc plantry III   \$2,045.005   \$2,000 Cardio Corni-road gradenesc plantry III   \$2,000 Cardio Corni-road gradenesc							0	0			20
\$200 Cardio Corni-road gradenesc plantry III   \$2,044.205   \$2,000 Cardio Corni-road gradenesc plantry III   \$2,044.205   \$2,000 Cardio Corni-road gradenesc plantry III   \$2,044.205   \$2,000 Cardio Corni-road gradenesc plantry III   \$2,045.005   \$2,000 Cardio Corni-road gradenesc plantry III   \$2,000 Cardio Corni-road gradenesc	5010	Goods Good site and Glass on this	04.400		0.040	0.000	4.040	4.005	04.400	07.500	40
500   Grade Corner cornicapperpoincil   0											
	5030	Grade Const - drainage/pipe,cul.	0	0	0	0	0	0	500,000		76
\$2.50   Grade Central - CRES   Canada Central - CRES										0 007 100	
Second Content grands from the mining hydrogenery   0	5050	Grade Const-CBC/produce,place,comp									
5022 Goald Cornst - grade finishing fencing   0   0   0   0   0   0   0   0   0	5060	Grade Const - grade finishing landscaping	0	0	0	0	0	0	0	0	0
5003 Grade Corest - nose barmiers			8,435			-,					
5064 Grade Corest - passiring liners   0   0   0   0   0   0   0   0   0			0	-	-	_	-	-	-	_	
Social Grant - Inference (we such pairing)   0			ő		-	•					
Section   131,545   54,5465   62,370   45,466   15,032   14,545   129,444   443,846   69   69   69   69   67   67   67   6			0	0	-	0	0	0	0	0	0
\$699   Grade Cornit Contingency   1,58,4912   488,500   642,416   467,706   154,830   149,857   1333,272   4,571,492   696   Grade Cornitation Sub-totals   5,871,286   2,000,168   2,783,801   2,005,724   670,928   649,379   5,777,515   138,000,00   3035   303			131 545				0				
GRADE CONSTRUCTION COSTS 5,938_25 2,003,168 2,788,001 2,005,724 670,928 649,379 5,544,463 19,943,70 3015 (GRADE CONSTRUCTION COSTS 5,938_25) 2,003,168 2,788,001 2,005,724 670,928 649,379 5,544,463 19,943,70 3015 (SAMPER) CONSTRUCTION COSTS 1,005,005 1,005,											
Second State   Content				2,030,168			670,928	649,379			3015
STRUCTURAL CONSTRUCTION   124,773   42,834   58,460   42,561   14,089   13,637   122,734   418,818   64,610		GRADE CONSTRUCTION COSTS	5,938,236	2,030,168	2,783,801	2,026,724	670,928	649,379	5,844,463	19,943,700	3035
STRUCTURAL CONSTRUCTION   124,773   42,834   58,460   42,561   14,089   13,637   122,734   418,818   64,610	3510	Grade Eng detailed design	415 677	142 112	194 866	141 871	46 965	45 457	409 112	1 396 059	212
6811 Grade Eng causelying   118,765   40,003   55,676   40,534   13,419   12,888   116,889   398,874   616   618   Grade Eng surveying   18,765   40,003   42,703   42	3519	Grade Eng detailed design/Contingency	124,703	42,634	58,460	42,561	14,089	13,637	122,734	418,818	64
6812   Grade Eng Surveying   118,765   40,603   55,676   42,581   13,419   12,888   116,889   398,874   61   616   618											
6819 Grade Eng Residency Contingency   124,7703   42,634   58,460   42,561   14,089   13,637   126,737   106,6692   3,269,783   506,6502   32,90,450   2,395,588   793,037   767,566   6,908,156   23,673,454   38,772											
Total Grade Const. & Eng. Costs 7,018,195 2,399,659 3,290,453 2,395,588 793,037 767,566 6,908,156 23,573,454 3587    STRUCTURAL CONSTRUCTION											
STRUCTURAL CONSTRUCTION   STRUCTURAL CONSTRUCTURAL CONSTRUCTION   STRUCTURAL CONSTRUCTURAL CON			1,080,759	369,491	506,652	368,864	122,109	118,187	1,063,692	3,629,753	552
5522         Struct Const - warler         0 <td></td> <td></td> <td></td> <td></td> <td>3,290,453</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>0001</td>					3,290,453						0001
5522         Struct Const - warler         0 <td></td>											
5523         Struct. Const - starinary         0	5500	STRUCTURAL CONSTRUCTION									
5524 Struct Const - storm         0 <td></td>											
Struct Const - mobilization   0			-				-	-			
Structural Const. Utilities Sub-lotal   0   0   0   0   0   0   0   0   0				-	-						
Struct Const - tunnel site preparation	5599										0
5511 Struct Const - tunnel construction         0		Structural Const. Utilities Sub-total			0	0	0	0	0	0	0
5512 Struct Const - snow shed site prep.         0											
5513         Struct.Const - snow shed site const.         0											
Struct.Const - bridge site preparation	00.0										
Struct. Const - bridge piers   0											,
Struct. Constribridge abutments			0				0				
STRUCTURAL CONSTRUCTION COSTS   0   1,987,786   0   0   0   0   0   0   0   1,987,786   3781			v	-	0		o o				
STRUCT Constract - retaining wall const.   0	5517	Struct.Const - bridge superstructure	0			-	0	-	-		
Struct. Construction Sub-total   Struct. Eng detailed design   Struct. Eng quality assurance   Struct. Eng Residency Contingency   Struct. Eng			0	0							
Struct. Construction Sub-lotal   0   5,733,999   0   0   0   0   0   0   24,847,328   3781				556.699							
STRUCTURAL CONSTRUCTION COSTS         0         24,847,328         0         0         0         0         0         24,847,328         3781           3520         Struct. Eng detailed design         0         1,987,786         0         0         0         0         0         1,987,786         303           3529         Struct. Eng detailed design/Contingency         0         596,336         0         0         0         0         0         596,336         91           6820         Struct. Eng general const. supervision         0         993,893         0         0         0         0         0         993,893         151           6821         Struct. Eng quality assurance         0         496,947         0         0         0         0         496,947         76           6822         Struct. Eng surveying         0         124,237         0         0         0         0         124,237         19           6829         Struct. Eng Residency Contingency         0         484,523         0         0         0         0         484,523         74           Structural Engineering Sub-total         0         4,683,721         0         0         0		Struct.Const - Contingency	0	5,733,999						5,733,999	873
Struct. Eng detailed design   0   1,987,786   0   0   0   0   0   0   1,987,786   303   3529   Struct. Eng detailed design/Contingency   0   596,336   0   0   0   0   0   0   596,336   91   6820   Struct. Eng general const. supervision   0   993,893   0   0   0   0   0   0   993,893   151   6821   Struct. Eng quality assurance   0   496,947   0   0   0   0   0   0   496,947   76   6822   Struct. Eng surveying   0   124,237   19   6829   Struct. Eng Residency Contingency   0   484,523   74   Struct. Eng Residency Contingency   0   484,523   74   Structural Engineering Sub-total   0   29,531,049   0   0   0   0   0   0   29,531,049   4494		Structural Construction Sub-total	0	24,847,328	0	0	0	0	0	24,847,328	3781
3529 Struct. Eng detailed design/Contingency         0         596,336         0         0         0         0         0         596,336         91           6820 Struct. Eng general const. supervision         0         993,893         0         0         0         0         0         993,893         151           6821 Struct. Eng quality assurance         0         496,947         7         76         6822         Struct. Eng surveying         0         0         0         0         124,237         19           6829 Struct. Eng seidency Contingency         0         484,523         0         0         0         0         0         484,523         74           Structural Engineering Sub-total         0         4,683,721         0         0         0         0         0         4,683,721         713           Total Structural & Eng. Costs         0         29,531,049         0         0         0         0         29,531,049         4494		STRUCTURAL CONSTRUCTION COSTS	0	24,847,328	0	0	0	0	0	24,847,328	3781
6820 Struct. Eng general const. supervision         0         993,893         0         0         0         0         993,893         151           6821 Struct. Eng quality assurance         0         496,947         0         0         0         0         0         496,947         76           6822 Struct. Eng surveying         0         124,237         0         0         0         0         0         124,237         19           6829 Struct. Eng Residency Contingency         0         484,523         0         0         0         0         0         4845,23         74           Structural Engineering Sub-total         0         4,683,721         0         0         0         0         0         4,683,721         713           Total Structural & Eng. Costs         0         29,531,049         0         0         0         0         0         29,531,049         4494	3520	Struct. Eng detailed design	0								
6821 Struct. Eng quality assurance     0     496,947     0     0     0     0     0     496,947     76       6822 Struct. Eng surveying     0     124,237     0     0     0     0     0     124,237     19       6829 Struct. Eng Residency Contingency     0     484,523     0     0     0     0     0     484,523     74       Structural Engineering Sub-total     0     4,683,721     0     0     0     0     0     4,683,721     713       Total Structural & Eng. Costs     0     29,531,049     0     0     0     0     0     29,531,049     4494	3529	Struct. Eng detailed design/Contingency	0	596,336	-		-	-		596,336	
6822 Struct. Eng surveying 0 124,237 0 0 0 0 0 0 124,237 19 6829 Struct. Eng Residency Contingency 0 484,523 0 0 0 0 0 0 0 484,523 74 Structural Engineering Sub-total 0 4,683,721 0 0 0 0 0 0 0 4,683,721 713  Total Structural & Eng. Costs 0 29,531,049 0 0 0 0 0 0 29,531,049 4494			0		-	-	-	-			
6829 Struct. Eng Residency Contingency         0         484,523         0         0         0         0         0         484,523         74           Structural Engineering Sub-total         0         4,683,721         0         0         0         0         0         4,683,721         713           Total Structural & Eng. Costs         0         29,531,049         0         0         0         0         0         29,531,049         4494					-						
Total Structural & Eng. Costs         0         29,531,049         0         0         0         0         29,531,049         4494		Struct. Eng Residency Contingency	0	484,523			0		0	484,523	74
		Structural Engineering Sub-total	0	4,683,721	0	0	0	0	0	4,683,721	713
					-						

File: Function Part (2016Dol	1200 - MoT A&W Contract #15\SWF - Highway 1 nal Planning\Data\Costing\March 29th\[Package 2 - sons Hwy 1 Widening Illars) Package 2 - 264 IC	16+500 to 14+600 East and West	264 Street New Overpass and approaches	264 Street Interchange EB Off	264 Street Interchange WB Off	264 Street Interchange WB On	264 Street Interchange EB On	16+500 to 14+600 To the east and		Total Line Cost
ACTIVITY CODE	EST.DATE April 4, 2016 R3 DATE: Sept 15, 2016	of the 264 St Interchange	0	Ramp Loop	Ramp Loop	Ramp 0	Ramp 0	west of 264 St IC		C/LM
Conceptual		Section W.10	Section 264.1	Section 264.2	Section 264.3	Section 264.4	Section 264.5	Section E.12 MR	6571	0.2
Blk Est. # 6.14		16	21	21	21	21	21	16 OR	0	
Version Sept.1	1, 200 DESCRIPTION \Length	1900 MR	507 MR	740 MR	604 MR	470 MR	450 MR	1900 TR MR	6571	6571
	-	IVID	IVII	IVID	IVIIT	IVID	IVID	IVID		
6000	PAVING CONSTRUCTION									
	Cons - machine paving asphalt	825,249	291,821	286,647	207,586	129,135	128,340	852,659	2,721,438	414
	Cons - machine paving concrete Cons - hot reprofiling	0	0	0	0	0	0	0	0	0
	Cons - shoulder paving	0	0	0	0	0	0	0	0	ő
6060 Paving	Cons - pavement finishing	0	0	0	0	0	0	0	0	0
	Cons - seal coating	0	0 755	0	0	0	0	0	0	0
	Cons - mobilization Cons - pavement design	24,757 0	8,755 0	8,599 0	6,228	3,874	3,850	25,580 0	81,643 0	12 0
	Cons - Contingency	255,002	90,173	88,574	64,144	39,903	39,657	263,472	840,924	128
DAVING	O CONCEDUCTION COCTO	4 405 000	000.740	000.004	077.050	470.040	474.040	4 4 4 7 7 4 4	0.044.005	
PAVING	G CONSTRUCTION COSTS	1,105,009	390,748	383,821	277,958	172,912	171,848	1,141,711	3,644,005	555
	Eng detailed design	77,351	27,352	26,867	19,457	12,104	12,029	79,920	255,080	39
	Eng detailed design/Contingency	23,205	8,206	8,060	5,837	3,631	3,609	23,976	76,524	12
6860 Paving 6861 Paving	Eng general const. supervision	22,100 44,200	7,815 15,630	7,676 15,353	5,559 11,118	3,458 6,916	3,437 6,874	22,834 45,668	72,880 145,760	11
6862 Paving	Eng quality assurance Eng surveying	5,525	1,954	1,919	1,390	865	859	5,709	18,220	22 3
6869 Paving	Eng Residency Contingency	21,548	7,620	7,485	5,420	3,372	3,351	22,263	71,058	11
Paving	Engineering Sub-total	193,929	68,576	67,361	48,782	30,346	30,159	200,370	639,523	97
	Paving Const. & Eng. Costs	1,298,938	459,324	451,181	326,740	203,257	202,007	1,342,081	4,283,528	652
6500	OPERATIONAL CONSTRUCTION									
	.Cons - lighting .Cons - signals	0	121,000	137,500	110,000	88,000	82,500 0	0	539,000	82
	.Cons - signals .Cons - signing	3,800	1.014	1,480	0 1,208	940	900	3,800	13,142	0 2
	.Cons - guard rail	37,500	24,000	0	0	0	0	25,500	87,000	13
6550 Operat.	.Cons - pavement markings	19,000	5,333	4,213	3,020	1,525	1,588	20,000	54,678	8
	.Cons - mobilization	1,809	4,540	4,296	3,427	2,714	2,550	1,479	20,815	3
6599 Operat.	.Cons - contingency	18,633	46,766	44,246	35,296	27,954	26,261	15,234	214,390	33
OPERA	ATIONAL CONSTRUCTION COSTS	80,742	202,653	191,735	152,951	121,133	113,798	66,013	929,024	141
	. Eng - detailed design	5,652	14,186	13,421	10,707	8,479	7,966	4,621	65,032	10
	. Eng - detailed design/Contingency	1,696	4,256	4,026	3,212	2,544	2,390	1,386	19,510	3
	. Eng - general const. supervision . Eng - quality assurance	4,441 1,615	11,146 4.053	10,545 3.835	8,412 3,059	6,662 2,423	6,259 2,276	3,631 1,320	51,096 18,580	8
	. Eng - surveying	404	1.013	959	765	606	569	330	4.645	1
6849 Operat.	. Eng - Residency Contingency	1,938	4,864	4,602	3,671	2,907	2,731	1,584	22,297	3
Operati	ional Enginering Sub-total	15,745	39,517	37,388	29,826	23,621	22,191	12,872	181,160	28
	Operational Const.& Eng.Costs	96,486	242,170	229,123	182,777	144,753	135,989	78,885	1,110,184	169
									=======================================	
5200 5203 RoadSi	ROAD SIDE CONSTRUCTION ide Cr - water	0	0	0	0	0	0	0	0	0
	ide Ci - water ide Ci - sanitary	0	0	0	0	0	0	0	0	0
5205 RoadSi		0	0	0	0	0	0	0	0	ő
	ide Cı - mobilization	0	0	0	0	0	0	0	0	0
	ide Cı - Utility Contingency Side Const. Utilities Sub-total	0	0	0	0	0	0	0	0	0
	ide Cı - weighscales	0	0	0	0	0	0	0	0	0
	ide Cı - safety rest areas ide Cı - tourist rest & view areas	0	0	0	0	0	0	0	0	0
	ide Cı - mobilization	0	0	0	0	0	0	0	0	0
5299 RoadSi	ide Cı - Contingency	0	0	0	0	0	0	0	0	0
Road S	Side Construction Sub-total	0	0	0	0	0	0	0	0	0
ROAD	SIDE CONSTRUCTION COSTS	0	0	0	0	0	0	0	0	0
3550 RoadSi	ide Er - detailed design	0	0	0	0	0	0	0	0	0
3559 RoadSi	ide Er - detailed design/Contingency	0	0	0	0	0	0	0	0	0
	ide Er - general const. supervision	0	0	0	0	0	0	0	0	0
	ide Er - quality assurance ide Er - surveying	0	0	0	0	0	0	0	0	0
6859 RoadSi	ide Er - Residency Contingency	ő	ő	ő	ŏ	ő	ŏ	ŏ	ŏ	ő

		16+500 to 14+600 East and West of the 264 St Interchange	264 Street New Overpass and approaches 0 0	264 Street Interchange EB Off Ramp Loop 0	264 Street Interchange WB Off Ramp Loop 0	264 Street Interchange WB On Ramp 0	264 Street Interchange EB On Ramp 0	16+500 to 14+600 To the east and west of 264 St IC		Total Line Cost C/LM
	nceptual Est. Divison\site	Section W.10	Section 264.1	Section 264.2	Section 264.3	Section 264.4	Section 264.5	Section E.12 MR	1	
	tt. # 6.14A Road Type on Sept.1, 200 DESCRIPTION \Length	16 1900	21 507	21 740	21 604	21 470	21 450	16 OR 1900 TR	0 6571	6571
	Road Side Engineering Sub-total	MR 0	MR 0	MR 0	MR 0	MR 0	MR 0	MR 0	0	
								-		
	Total Road Side Const.& Eng.Costs	0	0	0	0	0	0	0	0	0
5300	OTHER CONSTRUCTION									
5303	Other Const - water	0	0	0	0	0	0	0	0	0
5304 5305	Other Const - sanitary Other Const - storm	0	0	0	0	0	0	0	0	0
5302	Other Const - mobilization	0	0	0	0	0	0	0	Ö	0
5309	Other Const - utility contingency Other Const. Utilities Sub-total	0	0	0	0	0	0	0	0	0
E210	Other Const - railroads main & spur lines			0	0			0	0	0
5320	Other Const - railroad crossings	0	0	0	0	0	0	0	0	0
	Other Const - marine work Other Const - environmental mitigations	0	0	0	0	0	0	0	0	0
5301	Other Const - mobilization	0	0	0	0	0	0	0	0	0
5399	Other Construction Sub-total	0	0	0	0	0	0	0	0	0
	OTHER CONSTRUCTION COSTS								0	
2570	Other Eng detailed design				0		0	0	0	
3570	Other Eng detailed design/Contingency	0	0	0	0	0	0	0	0	0
	Other Eng general const. supervision	0	0	0	0	0	0	0	0	0
	Other Eng quality assurance Other Eng surveying	0	0	0	0	0	0	0	0	0
6879	Other Eng Residency Contingency	0	0	0	0	0	0	0	0	0
	Other Engineering Sub-total							·		
	Total Other Const.& Eng.Costs	0	0	0	0	0	0	0	0	0
3500	DETAILED DESIGN									
3530	from 3510,3520,3540,3550,3570 Geotech. En - detailed design	648,283 42,744	2,822,867 189,825	305,701 20,156	223,645 14,746	87,812 5,790	85,087 5,610	641,749 42,313	4,815,144 321,184	733 49
	Geotech. En - Contingency	12,823	56,948	6,047	4,424	1,737	1,683	12,694	96,355	15
		12,020	36,946	6,047	.,					
	TOTAL DETAILED DESIGN COSTS						92,380			796
	TOTAL DETAILED DESIGN COSTS	703,850	3,069,640	331,904	242,814	95,339	92,380	696,756	5,232,684	796
6800		703,850	3,069,640	331,904	242,814	95,339		696,756	5,232,684	796
	RESIDENT ENGINEERING	703,850	3,069,640	331,904	242,814	95,339		696,756	5,232,684	796
	RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870	703,850	2,338,439	331,904	242,814	95,339 88,263	85,450	696,756	5,232,684	
	RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870 TOTAL RESIDENT ENG. COSTS	703,850 642,150 642,150	2,338,439 2,338,439	331,904 305,699 305,699	242,814 223,826 223,826	95,339 88,263 88,263	85,450 85,450	696,756	5,232,684 4,319,013 4,319,013	
	RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870 TOTAL RESIDENT ENG. COSTS	703,850 642,150 642,150	2,338,439 2,338,439	331,904 305,699 305,699	242,814 223,826 223,826	95,339 88,263 88,263	85,450 85,450	696,756	5,232,684 4,319,013 4,319,013	657
	RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870  TOTAL RESIDENT ENG. COSTS	703,850 642,150 642,150	2,338,439 2,338,439	331,904 305,699 305,699	242,814 223,826 223,826	95,339 88,263 88,263	85,450 85,450	696,756	5,232,684 4,319,013 4,319,013	
	RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870  TOTAL RESIDENT ENG. COSTS  PART 1 SUMMARY	703,850 642,150 642,150	3,069,640 2,338,439 2,338,439	331,904 305,699 305,699	242,814 223,826 223,826	95,339 88,263 88,263	85,450 85,450	696,756 635,186 635,186	5,232,684 4,319,013 4,319,013 0	657
	RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870  TOTAL RESIDENT ENG. COSTS  PART 1 SUMMARY CONSTRUCTION ENGINEERING & SUPERVISION	703,850 642,150 642,150 5,539,989 1,345,084	2,338,439 2,338,439 2,1,182,159 4,366,938	331,904 305,699 305,699 2,658,121 611,084	242,814 223,826 223,826 1,950,887 457,406	95,339 88,263 88,263 789,286 217,843	85,450 85,450 764,250 210,142	696,756 635,186 635,186 5,474,759 1,334,271	5,232,684 4,319,013 4,319,013 0 0 38,359,452 8,542,769	657 0 5838 1300
	RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870  TOTAL RESIDENT ENG. COSTS  PART 1 SUMMARY CONSTRUCTION	703,850 642,150 642,150 5,539,989	3,069,640 2,338,439 2,338,439 21,182,159	331,904 305,699 305,699 2,658,121	242,814 223,826 223,826	95,339 88,263 88,263 789,286	85,450 85,450 764,250	696,756 635,186 635,186 5,474,759	5,232,684 4,319,013 4,319,013 0 0	657
	RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870  TOTAL RESIDENT ENG. COSTS  PART 1 SUMMARY CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY	703,850 642,150 642,150 5,539,989 1,345,084 2,065,522	2,338,439 2,338,439 2,1182,159 4,366,938 7,664,729	331,904 305,699 305,699 2,658,121 611,084 980,761	242,814 223,826 223,826 1,950,887 457,406 722,488	95,339 88,263 88,263 789,286 217,843 302,139	85,450 85,450 764,250 210,142 292,318	696,756 635,186 635,186 5,474,759 1,334,271 2,042,709	5,232,684 4,319,013 4,319,013 0 0 38,359,452 8,542,769 14,070,666 0	657 
	RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870  TOTAL RESIDENT ENG. COSTS  PART 1 SUMMARY CONSTRUCTION ENGINEERING & SUPERVISION	703,850 642,150 642,150 5,539,989 1,345,084	2,338,439 2,338,439 2,1,182,159 4,366,938	331,904 305,699 305,699 2,658,121 611,084	242,814 223,826 223,826 1,950,887 457,406	95,339 88,263 88,263 789,286 217,843	85,450 85,450 764,250 210,142	696,756 635,186 635,186 5,474,759 1,334,271	5,232,684 4,319,013 4,319,013 0 0 38,359,452 8,542,769 14,070,666	657 0 5838 1300 2141
6800 	RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870  TOTAL RESIDENT ENG. COSTS  PART 1 SUMMARY CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY  CONSTRUCTION COST TOTAL  PROJECT MANAGEMENT	703,850 642,150 642,150 5,539,989 1,345,084 2,065,522 8,950,596	2,338,439 2,338,439 2,338,439 21,182,159 4,366,938 7,664,729 33,213,826	331,904 305,699 305,699 2,658,121 611,084 980,761 4,249,966	242,814 223,826 223,826 1,950,887 457,406 722,488 3,130,781	95,339 88,263 88,263 789,286 217,843 302,139 1,309,268	85,450 85,450 764,250 210,142 292,318 1,266,710	696,756 635,186 635,186 5,474,759 1,334,271 2,042,709 8,851,739	5,232,684  4,319,013  4,319,013  0  0  38,359,452 8,542,769 14,070,666 0  60,972,887	657 0 5838 1300 2141 0
6800   2000 2060 2062	RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870  TOTAL RESIDENT ENG. COSTS  PART 1 SUMMARY CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY  CONSTRUCTION COST TOTAL  PROJECT MANAGEMENT Project Man office costs - expenses Project Man office costs - expenses	703,850 642,150 642,150 5,539,989 1,345,084 2,065,522 8,950,596	2,338,439 2,338,439 2,338,439 21,182,159 4,366,938 7,664,729 33,213,826	331,904 305,699 305,699 2,658,121 611,084 980,761 4,249,966 95,624	242,814 223,826 223,826 1,950,887 457,406 722,488 3,130,781 70,443 0	95,339 88,263 88,263 789,286 217,843 302,139 1,309,268 29,459 0	85,450 85,450 764,250 210,142 292,318 1,266,710	696,756 635,186 635,186 5,474,759 1,334,271 2,042,709 8,851,739	5,232,684 4,319,013 4,319,013 0 0 38,359,452 8,542,769 14,070,666 0 60,972,887	657 0 5838 1300 2141 0 9279 209 0
6800  2000 2060 2062 2063	RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870  TOTAL RESIDENT ENG. COSTS  PART 1 SUMMARY CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY  CONSTRUCTION COST TOTAL  PROJECT MANAGEMENT Project Man office costs - expenses Project Man printing costs	703,850 642,150 642,150 5,539,989 1,345,084 2,065,522 8,950,596	2,338,439 2,338,439 2,338,439 21,182,159 4,366,938 7,664,729 33,213,826	331,904 305,699 305,699 2,658,121 611,084 980,761 4,249,966 95,624 0	242,814 223,826 223,826 1,950,887 457,406 722,488 3,130,781 70,443 0	95,339  88,263  88,263  789,286 217,843 302,139  1,309,268  29,459 0	85,450 85,450 764,250 210,142 292,318 1,266,710	5,474,759 1,334,271 2,042,709 199,164 0	5,232,684  4,319,013  4,319,013  0  0  38,359,452 8,542,769 14,070,666 00,972,887  1,371,890 0	5838 1300 2141 0 9279
6800  2000 2060 2062 2063	RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870  TOTAL RESIDENT ENG. COSTS  PART 1 SUMMARY CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY  CONSTRUCTION COST TOTAL  PROJECT MANAGEMENT Project Man office costs - expenses Project Man office costs - expenses	703,850 642,150 642,150 5,539,989 1,345,084 2,065,522 8,950,596	2,338,439 2,338,439 2,338,439 21,182,159 4,366,938 7,664,729 33,213,826	331,904 305,699 305,699 2,658,121 611,084 980,761 4,249,966 95,624	242,814 223,826 223,826 1,950,887 457,406 722,488 3,130,781 70,443 0	95,339 88,263 88,263 789,286 217,843 302,139 1,309,268 29,459 0	85,450 85,450 764,250 210,142 292,318 1,266,710	696,756 635,186 635,186 5,474,759 1,334,271 2,042,709 8,851,739	5,232,684 4,319,013 4,319,013 0 0 38,359,452 8,542,769 14,070,666 0 60,972,887	657 0 5838 1300 2141 0 9279 209 0
2000 2060 2063 2061	RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870  TOTAL RESIDENT ENG. COSTS  PART 1 SUMMARY CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY  CONSTRUCTION COST TOTAL  PROJECT MANAGEMENT Project Man office costs - expenses Project Man printing costs Project Man printing costs Project Man general Project Man general Project Manager Sub-total	703,850 642,150 642,150 5,539,989 1,345,084 2,065,522 8,950,596 201,388 0 0 0	2,338,439 2,338,439 2,338,439 2,338,439 21,182,159 4,366,938 7,664,729 33,213,826 747,311 0 0 747,311	331,904 305,699 305,699 2,658,121 611,084 980,761 4,249,966 95,624 0 0 0 95,624	242,814 223,826 223,826 1,950,887 457,406 722,488 3,130,781 70,443 0 0 0 70,443	95,339  88,263  88,263  789,286 217,843 302,139  1,309,268  29,459 0 0 0 29,459	85,450 85,450 764,250 210,142 292,318 1,266,710 0 0 0 28,501	5,474,759 1,334,271 2,042,709 199,164 0 0 199,164	5,232,684  4,319,013  4,319,013  0  0  38,359,452 8,542,769 14,070,666 14,070,666 0,972,887  1,371,890 0 1,371,890	5838 1300 2141 0 9279 209 0 0 0 0 209
2000 2060 2063 2061 2010 2012	RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870  TOTAL RESIDENT ENG. COSTS  PART 1 SUMMARY CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY  CONSTRUCTION COST TOTAL  PROJECT MANAGEMENT Project Man office costs wages Project Man general Project Man general Project Man general Project Man general Project Man office costs wages Client - office costs wages Client - office costs wages	703,850 642,150 642,150 5,539,989 1,345,084 2,065,522 8,950,596 201,388 0 0 201,388 179,012	3,069,640 2,338,439 2,338,439 21,182,159 4,366,938 7,664,729 33,213,826 747,311 0 0 747,311 664,277	331,904 305,699 305,699 2,658,121 611,084 980,761 4,249,966 95,624 0 0 95,624 84,999 0	242,814 223,826 223,826 1,950,887 457,406 722,488 3,130,781 70,443 0 0 70,443 62,616 0	95,339  88,263  88,263  789,286 217,843 302,139  1,309,268  29,459 0 0 29,459 26,185	85,450 85,450 764,250 210,142 292,318 1,266,710 0 0 28,501 25,334	5,474,759 1,334,271 2,042,709 199,164 0 0 199,164 177,035	5,232,684  4,319,013  4,319,013  0  0  38,359,452 8,542,769 14,070,666 00,972,887  1,371,890 0 1,371,890 1,219,458 0,219,458	5838 1300 2141 0 9279 209 0 0 0 209
2000 2060 2062 2063 2061 2010 2012 2012	RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870  TOTAL RESIDENT ENG. COSTS  PART 1 SUMMARY CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY  CONSTRUCTION COST TOTAL PROJECT MANAGEMENT Project Man office costs wages Project Man printing costs Project Man printing costs Project Man general Project Manager Sub-total  Client - office costs wages Client - office costs - expenses Client - office costs - expenses Client - office costs - expenses Client - printing costs	703,850 642,150 642,150 5,539,989 1,345,084 2,065,522 8,950,596 201,388 0 0 201,388 179,012 0 0	3,069,640 2,338,439 2,338,439 2,338,439 21,182,159 4,366,938 7,664,729 33,213,826 747,311 0 0 747,311 664,277 0	331,904 305,699 305,699 2,658,121 611,084 980,761 4,249,966 95,624 0 0 95,624 84,999 0 0	242,814 223,826 223,826 1,950,887 457,406 722,488 3,130,781 70,443 0 0 70,443 62,616 0 0	95,339  88,263  88,263  789,286 217,843 302,139  1,309,268  29,459 0 0 29,459 26,185 0 0	85,450 85,450 764,250 210,142 292,318 1,266,710 28,501 0 0 28,501	5,474,759 1,334,271 2,042,709 8,851,739 199,164 0 0 199,164 177,035 0 0	5,232,684  4,319,013  0  0  38,359,452 8,542,769 14,070,666 0  60,972,887  1,371,890 0 1,371,890 1,219,458	5838 1300 2141 9279 209 0 0 0 209
2000 2060 2062 2063 2061 2010 2012 2012	RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870  TOTAL RESIDENT ENG. COSTS  PART 1 SUMMARY CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY  CONSTRUCTION COST TOTAL  PROJECT MANAGEMENT Project Man office costs wages Project Man general Project Man general Project Man general Project Man general Project Man office costs wages Client - office costs wages Client - office costs wages	703,850 642,150 642,150 5,539,989 1,345,084 2,065,522 8,950,596 201,388 0 0 201,388 179,012	3,069,640 2,338,439 2,338,439 21,182,159 4,366,938 7,664,729 33,213,826 747,311 0 0 747,311 664,277	331,904 305,699 305,699 2,658,121 611,084 980,761 4,249,966 95,624 0 0 95,624 84,999 0	242,814 223,826 223,826 1,950,887 457,406 722,488 3,130,781 70,443 0 0 70,443 62,616 0	95,339  88,263  88,263  789,286 217,843 302,139  1,309,268  29,459 0 0 29,459 26,185	85,450 85,450 764,250 210,142 292,318 1,266,710 0 0 0 28,501 25,334 0 0	5,474,759 1,334,271 2,042,709 199,164 0 0 199,164 177,035	5,232,684  4,319,013  4,319,013  0  0  38,359,452 8,542,769 14,070,666 0,972,887  1,371,890 0 1,371,890 1,219,458 0 0	5838 1300 2141 0 9279 209 0 0 0 209


( ACTIV COD Con Blk Es Versio 2070 2072 2073 2071 		16+500 10 14+600 East and West of the 264 St Interchange Section W.10  1900 MR  53,704  6,265 0 6,265 53,704	264 Street New Overpass and approaches 0 Section 264.1 21 507 MR 199,283 0 0 199,283 23,250 23,250 199,283	264 Street Interchange EB Off Ramp Loop 0 Section 264.2 21 740 MR 25,500 0 0 25,500 2,975 0 2,975 0 25,500 25,500	264 Street Interchange WB Off Ramp Loop 0 Section 264.3 21 604 MR 18,785 0 0 18,785 2,192 0 2,192 18,785 0 0	264 Street Interchange WB On Ramp 0 Section 264.4 21 470 MR 7,856 0 0 7,856 916 0 916 7,856	264 Street Interchange EB On Ramp 0 Section 264.5 21 450 MR 7,600 0 0 7,600 887 0 887 7,600 0 0 0 7,600	16+500 10 14+600 To the east and west of 264 Section E.12 16 OR TR 1900 MR 53,110 6,196 6,196 53,110 0 6,196	6571 0 6571 365,837 0 0 365,837 42,681 42,681 365,837	Total Line Cost C/LM  6571  56 0 0 0 56  6 0 6  56 0 6
	Legal Costs Sub-total	53,704	199,283	25,500	18,785	7,856	7,600	53,110	365,837	56
2099	Project Management Contingency	148,222	550,021	70,379	51,846	21,681	20,977	146,585	1,009,711	154
4000 4010	TOTAL PROJECT MANAGEMENT COSTS  LAND  LAND  Land(Code 4-Mrkt,ROW,Serv,Imp.V,Ease.C,T  Acquisition Sub-total	642,295 0 0 0	2,383,424 0 0 0	304,978 0 0 0	224,665 0 0 0	93,953 0 0 0	90,899 0 0 0	635,201 0 0 0	4,375,414 	666 ====== 0 0
4030 4040 4050 4060 4070 4080	Land(Code 4-Bus.,5%,Mrg.P,Rel\$,P/Tax,Etc Land(Code 4-Owners(LS,ApprsI,Rprt,LgI,In Land(Code 4-Demolition Land(Code 4-Pro.Man,P.Tax,Util,Security Land(Code 4-Not Used Land(Code 4-Not Used Land(Code 4-Not Used Land(Code 4-Not Used Land(Code 4-Not,P.MSaI,TrvIV,Cntr.S,Appr. Land(Code 4-Surveys	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
	Associated costs-sub-total	0	0	0	0	0	0	0	0	0
4099	Land Contingency Sub-total	0	0	0	0	0	0	0	0	0
	TOTAL LAND COSTS	0	0	0	0	0	0	0	0	0
9800	MANAGEMENT RESERVE  MAN. RES planning  MAN. RES preliminary design  MAN. RES grade construction  MAN. RES structural construction  MAN. RES paving construction  MAN. RES operation construction  MAN. RES roadside construction  MAN. RES other construction  MAN. RES other construction  MAN. RES project management  MAN. RES detailed eng.  MAN. RES residency eng.  MAN. RES residency eng.	0 0 0 0 0 0 0 0	000000000000000000000000000000000000000	000000000000000000000000000000000000000	0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0
	TOTAL MANAGEMENT RESERVE	0	0	0	0	0	0	0	0	0
	TOTAL LESS ESCALATION FISCAL ESCALATION YEAR 2006-2007 2007-2008 2008-2009 2009-2010 2010-2011 2011-2012 2012-2013 2013-2014	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0

	Q:\SW\1200 - MoT A&W Contract #15\SWF									1	1
File:	Functional Planning\Data\Costing\March 29th	\[Package 2 -	16+500	264 Street	264 Street	264 Street	264 Street	264 Street	16+500		Total
	Parsons Hwy 1 Widening		to 14+600	New Overpass	Interchange	Interchange	Interchange	Interchange	to 14+600	1	Line
(	2016Dollars) Package 2 - 264 IC		East and West	and approaches	EB Off	WB Off	WB On	EB On	To the east and		Cost
ACTIV	/ITY EST.DATE April 4, 2016	i	of the 264 St	0	Ramp Loop	Ramp Loop	Ramp	Ramp	west of 264	1	
COD	E R3 DATE: Sept 15, 2016		Interchange	0	0	0	0	0	St IC		C/LM
Cor	nceptual Est.	Divison\site	Section W.10	Section 264.1	Section 264.2	Section 264.3	Section 264.4	Section 264.5	Section E.12 MR	6571	
Blk Es	t. # 6.14A	Road Type	16	21	21	21	21	21	16 OR	0	l
Versio	n Sept.1, 200 DESCRIPT	ION \Length	1900	507	740	604	470	450	1900 TR	6571	6571
			MR	MR	MR	MR	MR	MR	MR		
	2014-2015		0	0	0	0	0	0	0	0	0
									-		
	TOTAL ESCALATION		0	0	0	0	0	0	0	0	0
====											
	PART 2 SUMMARY NON-CONSTRUC	CTION COSTS								'	
	Non-Construction		494,073	1,833,403	234,598	172,819	72,272	69,922	488,616	3,365,703	512
	Non-Const. Contingency		148,222	550,021	70,379	51,846	21,681	20,977	146,585	1,009,711	154
	TOTAL NON-CONSTRUC	CTION COSTS	642.295	2.383.424	304.978	224.665	93,953	90.899	635,201	4,375,414	666
				2,000,424		=======================================			000,201	4,070,414	
	DIVISION TOTAL FOR ROAD TYPE		9,592,891	35,597,250	4,554,944	3,355,446	1,403,221	1,357,610	9,486,940	65,348,301	9945



## PACKAGE 3 - SECTIONS

ID	Chainage Start	Chainage End	Description
G.1			Glover Road Overpass Replacement
W.15	5+500	6+800	Highway 1 Westbound Lanes
W.14	6+800	7+600	Highway 1 Westbound Lanes
E.16	6+000	7+600	Highway 1 Eastbound Lanes



Package 3 - West of 232.xls

File: Functional F Parsoi (2016Dollar ACTIVITY CODE Conceptual E: Blk Est. #6.14A	Road Type	Glover Road New Overpass and Approaches 0 0 Section G.1	6+800 to 5+500 West of CP overpass to west of Glover Rd Section W.15	Section W.14	7+600 to 6+000 East of CP Rail Overpass to west f Glover Road Overp Section E.16	MR 6 OR	<b>4080</b> 0	Total Line Cost C/LM
Version Sept.1, 2	DESCRIPTION \Length	380 MR	1300 MR	800 MR	1600 MR	) TR	4080	4080
	Engineering	2,639,794	1,792,953	6,537,207	2,098,51	5	13,068,469	3203
	Land	0	0	0		0	0	0
	Construction	13,537,680	8,905,611 0	36,709,309 0	10,320,76	0	69,473,361 0	17028 0
	Management Reserve Escalation	0	0	0		0	0	0
	Total	16,177,474	10,698,564	43,246,516	12,419,27		82,541,830	20231
	DACIO CUANTITY CUMMADY							
	BASIC QUANTITY SUMMARY Construct.Cost ONLY Per L.M.	35.625	6.850	45.887	6.450	\$/LM	17.028	
	Land Area	0.3	4.7	2.9	5.1	ha	12.9	
						-		
	Mobilization Land Cont.	278,445 0	181,678 0	706,478 0	210,428 0		1,377,028	
	Construction Cont.	2,879,384	1.886.280	7,279,723	2,185,406		14,230,792	15.461.853
	Engineering Cont.	609,183	413,758	1,508,586	484,273		3,015,800	10,101,000
	Supervision Cont.	244,697	168,862	621,194	196,308		1,231,060	
	Total Cont.	3,733,263	2,468,899	9,409,504	2,865,987		18,477,653	
	S.G.S.B.	1,221	8,554	5,242	7,396	m3	22,414	
	C.B.C.	759	4,893	3,013	3,985	m3	12,650	
	Asphalt Concrete Barrier	892 215	6,889 130	4,243 130	5,507 315	t Im	17,532 790	
	Noise Attentuation Wall	0	0	0	0	m2	0	
	No. of Light Poles	12	0	0	0	ea	12	
	Sidewalk	0	0	0	0	lm	0	
	Curb and Gutter Signals	0	0	0	0	lm ea	0	
	Bridge total area	1352	0	0	0	m2	1,352	
							, , ,	
	Total Rock	0	0	0	0	m3	0	ENG 0
	Total OM	0	23,550	18,800	32,110	m3	74,460	0
	Total Stripping	ő	3,700	1,800	4,600	m3	10,100	ŏ
	Total Borrow	0	0	0	0	m3	0	
	Total Cut/Excavation	0	27,250	20,600	36,710 26,910	m3	84,560	0
	Total Fill Surplus or Deficit	3,803 -3,803	16,629 10,621	16,802 3,799	9,800	m3 m3	64,144 20,416	"
	Sulpido di Bollok	0,000	10,021	0,700	0,000		20,110	
	ENG & PM	2.640	1.793	6.537	2.099		13.068	13.069
	LAND	0.000	0.000	0.000	0.000		0.000	0.000
	CONST.	1.540	8.906	7.666	10.321		28.432	28.433
	BRIDGES-R/W	11.998	0.000	29.043	0.000		41.041	41.041
	MANAGEMENT RESERVE ESCALATION	0.000 0.000	0.000 0.000	0.000 0.000	0.000 0.000		0.000 0.000	0.000
	TOTAL (Millions) (2016Dollars)	16.178	10.699	43.246	12.420		82.541	82.543
	TOTAL Cost per meter		\$ 8,230	\$ 54,058	\$ 7,762		\$ 20,231	
	Construction cost per meter	\$ 35,626	\$ 6,851	\$ 45,886	\$ 6,451	1	\$ 17,028	ı

Page 1

Package 3 - West of 232.xls

ACTIV COD Cor Blk Es Versio		Glover Road New Overpass and Approaches 0 0 Section G.1 21 380 MR	6+800 to 5+500 West of CP overpass to west of Glover Rd Section W.15 16 1300 MR	7+600 to 6+800 West of 232 St Ic to west of CP Rail overpass Section W.14 16 800 MR	7+600 to 6+000 East of CP Rail Overpass to west f Glover Road Overpas Section E.16 16 MR	MR 4080 OR 0	Total Line Cost C/LM 4080
2000	PROJECT MANAGEMENT	833,206	551,020	2,100,053	639,643	4,123,922	1011
2500 3000 3500	PLANNING PRELIMINARY DESIGN DETAILED DESIGN	0 117,254 1,080,151	0 211,900 616,275	0 264,300 2,664,267	0 260,800 713,799	0 854,254 5,074,492	0 209 1244
	Total Engineering	1,197,405	828,175	2,928,567	974,599	5,928,746	1453
4000	LAND ACQUISITION	0	0	0	0	0	0
5000 5200 5300	GRADE CONSTRUCTION ROAD SIDE CONSTRUCTION OTHER CONSTRUCTION	791,258 0 0	5,328,147 0 0	3,080,203 0 0	6,398,311 0 0	15,597,920 0 0	3823 0 0
5500 6000 6500	STRUCTURAL CONSTRUCTION PAVING CONSTRUCTION OPERATIONAL CONSTRUCTION	8,509,860 120,540 138,288	0 849,865 59,586	23,072,000 523,422 52,118	0 709,265 117,111	31,581,860 2,203,092 367,102	7741 540 90
6700 6800	UTILITY CONSTRUCTION RESIDENT ENGINEERING	38,000 815,655	50,000 562,872	10,000 2,070,648	60,000 654,359	158,000 4,103,534 0	39 1006 0
	Total Construction	10,413,600	6,850,470	28,808,392	7,939,046	54,011,508	13238
9700	CONTINGENCY	3,733,263	2,468,899	9,409,504	2,865,987	18,477,653	4529
9800	SUB-TOTAL MANAGEMENT RESERVE	16,177,474 0	10,698,564 0	43,246,516 0	12,419,275 0	82,541,830 0	20231 0
	TOTAL	16,177,474	10,698,564	43,246,516	12,419,275	82,541,830	20231
9900	ESCALATION	0	0	0	0	0	0
	TOTAL COST	16,177,474	10,698,564	43,246,516	12,419,275	82,541,830	20231
	Const. Less Resident Eng.	9,597,945	6,287,598	26,737,744	7,284,687	49,907,975	12232

Page 2

Package 3 - West of 232.xls

ACTI COD Co Blk Es	Functional Pla Parsons (2016Dollars) VITY	MoT A&W Contract #15\SWF - Highway 1 nning\Data\Costing\March 29th\[Package 3 - Hwy 1 Widening Package 3 - West of 232 EST.DATE April 4, 2016 R3 DATE: Sept 15, 2016 Divison\site Road Type DESCRIPTION \Length	Glover Road New Overpass and Approaches 0 0 Section G.1 21 380	6+800 to 5+500 West of CP overpass to west of Glover Rd Section W.15	Section W.14 16 800	7+600 to 6+000 East of CP Rail Overpass to west f Glover Road Overpass Section E.16 MR 16 OR	<b>4080</b> 0 4080	Total Line Cost C/LM
2500		PLANNING	MR	MR	MR	MR		
2521		- transport. planning study	0	0	0	0	0	0
		- corridor study	0	0	0	0	0	0
	Consultant	- functional plan. study - general	0	0	0	0	0	0
	Consultant s		0	0	0	0	0	0
2510	Client	- project ident.	0	0	0	0	0	0
	Client	- transport. planning study	0	0	0	0	0	0
	Client	- corridor study	0	0	0	0	0	0
	Client Client	<ul> <li>functional plan. study</li> <li>general</li> </ul>	0	0	0	0	0	0
2301	Client Sub-to		0	0	0	0	0	0
2500	Planning Co			0	0	0	0	
		TOTAL PLANNING	0	0	0	0	0	0
3000		PRELIMINARY DESIGN						
	Consultant	- aerial base plan	0	0	0	0	0	0
	Consultant Consultant	- prel. design - control survey	26,600	91,000	56,000	112,000	285,600	70 0
3021	Consultant	- environmental impact	10,640	36,400	22,400	44.800	114,240	28
3031		- functroad field survey	0	0	0	0	0	0
		- functional design	19,000	65,000	40,000	80,000	204,000	50
		- funct. structural des.	55,314	0	133,900	0	189,214	46
3061	Consultant	- geotechnical design	5,700	19,500	12,000	24,000	61,200	15
3071	Consultant	- right-of-way research	0	0	0	0	0	0
3002	Consultant s		117,254	211,900	264,300	260,800	854,254	209
	01'	and all have also						
	Client Client	- aerial base plan - prel. design	0	0	0	0	0	0
	Client	- control survey	0	0	ő	0	l ő	ő
3020	Client	- environmental impact	0	0	0	0	0	0
	Client	- functroad field survey	0	0	0	0	0	0
	Client	- functional design	0	0	0	0	0	0
	Client	- funct. structural des.	0	0	0	0	0	0
	Client Client	geotechnical design     right-of-way research	0	0	0	0	0	0
3001	Client	- general	0	0	0	0	0	0
0001	Client Sub-to		0	0	0	0	ő	ő
3099	Preliminary	design Contingency	35,176	63,570	79,290	78.240	256,276	63
		ELIMINARY DESIGN	152,430	275,470	343,590	339.040	1,110,530	272
	=======		152,430	2/5,4/0	343,590	339,040	1,110,530	======
6700		UTILITIES		_				
		- Hydro	22,800	0	10,000	10,000	42,800	10 28
6/11	Util. Prov. Util. Prov.	- Telephone sub-total	15,200 38,000	50,000 50,000	10,000	50,000 60,000	115,200 158,000	39
		- pipelines	0	0	0	0	0	0
		telecommunication     storm & sewer inspect.	0	0	0	0	0	0
		- waterworks inspect.	0	0	0	ů	l ő	0
		- engineering services	0	0	0	ő	0	ő
		- parks/recreation-prel.	0	0	0	Ō	0	0
6718	Util.Others	- transit	0	0	0	0	0	0
		- tr-ops/signs & detours	0	0	0	0	0	0
6701	Util.Others Util.Others		0	0	0	0	0	0
6799	Util.Others 0		11,400	15,000	3,000	18,000	47,400	12
	TOTAL UTI	LITIES	49,400	65,000	13,000	78,000	205,400	50
5000		GRADE CONSTRUCTION						
	Grade Cons		0	0	0	0	0	0
	Grade Cons		0	0	0	0	0	0

Page 3

ACTI COD Co		3 - Glover Road New Overpass and Approaches 0 0 0 Nsite Section G.1	6+800 to 5+500 West of CP overpass to west of Glover Rd Section W.15	7+600 to 6+800 West of 232 St Ic to west of CP Rail overpass Section W.14	7+600 to 6+000 East of CP Rail Overpass to west f Glover Road Overpass Section E.16 MR	4080	Total Line Cost C/LM
Versio	on Sept.1, 200 DESCRIPTION \Ler		1300 MR	800 MR	1600 TR	4080	4080
5031	Grade Consi - storm Grade Consi - mobilization Grade Consi - utility contingency Grade Const. Utilities Sub-total	0 0 0 0	0 0 0 0	0 0 0 0	0 0 0 0	0 0 0	0 0 0 0
5020 5030 5040	Grade Consl - site prep./clear.grubbing Grade Consl - road grade/exc.placing,fill Grade Consl - drainage/pipe,cul. Grade Consl - muiltiplate	0 114,098 0 0	4,713 1,608,370 2,500,000 0	1,340,045 1,000,000 0	11,600 2,299,700 3,000,000 0	16,313 5,362,213 6,500,000 0	4 1314 1593 0
5051 5060	Grade Const-SGSB/produce,place,comp Grade Const-CBC/produce,place,comp Grade Const- grade finishing landscaping	85,491 68,310 0 312	598,781 440,382 0	366,941 271,160 0	517,737 358,674 0	1,568,950 1,138,526 0	385 279 0
5062 5063 5064	Grade Const - grade finishing hydro seed. Grade Const - grade finishing fencing Grade Const - noise barriers Grade Const - passing lanes	0 0 0	20,713 0 0 0	12,343 0 0 0	24,242 0 0 0	57,610 0 0 0	14 0 0 0
5005 5001	Grade Consl - sidewalks,curb & gutter Grade Consl -detours c/w ex,bf,paving Grade Consl - mobilization Grade Const - Contingency Grade Construction Sub-total	0 500,000 23,046 237,377 1,028,635	0 0 155,189 1,598,444 6,926,592	0 0 89,715 924,061 4,004,264	0 0 186,359 1,919,493 8,317,805	0 500,000 454,308 4,679,376 20,277,296	0 123 111 1147 4970
	GRADE CONSTRUCTION COSTS	1,028,635	6,926,592	4,004,264	8,317,805	20,277,296	4970
3519 6810 6811 6812	Grade Eng detailed design Grade Eng detailed design/Contingency Grade Eng general const. supervision Grade Eng quality assurance Grade Eng surveying Grade Eng Residency Contingency	72,004 21,601 30,859 20,573 20,573 21,601 187,212	484,861 145,458 207,798 138,532 138,532 145,458 1,260,640	280,299 84,090 120,128 80,085 80,085 84,090 728,776	582,246 174,674 249,534 166,356 166,356 174,674	1,419,411 425,823 608,319 405,546 405,546 425,823	348 104 149 99 99 104 905
	Grade Engineering Sub-total  Total Grade Const. & Eng. Costs	1,215,847	8,187,231	4,733,040	1,513,840  9,831,645	3,690,468 23,967,764	5874
5523 5524 5521	STRUCTURAL CONSTRUCTION Struct.Const - water Struct.Const - sanitary Struct.Const - storm Struct.Const - mobilization					0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 0
5511 5512	Struct.Const - tunnel site preparation Struct.Const - tunnel construction Struct.Const - snow shed site prep. Struct.Const - snow shed site const.	0 0 0 0	0 0 0 0	0 0 0 0	0 0 0 0	0 0 0 0	0 0 0 0
5515 5516 5517 5518 5519 5501	Struct.Const - bridge site preparation Struct.Const - bridge piers Struct.Const - bridge abutments Struct.Const - bridge superstructure Struct.Const - retain, wall site prep. Struct.Const - retaining wall const. Struct.Const - mobilization Struct.Const - Contingency Structural Construction Sub-total	1,000,000 0 0,0 6,762,000 500,000 247,860 2,552,958 11,062,818	0 0 0 0 0 0 0	6,000,000 6,000,000 2,000,000 6,000,000 0 600,000 6,180,000 26,780,000	0 0 0 0 0	7,000,000 6,000,000 2,000,000 12,762,000 0 500,000 847,860 8,732,958 37,842,818	1716 1471 490 3128 0 123 208 2140 9275
	STRUCTURAL CONSTRUCTION COSTS	11,062,818		26,780,000		37,842,818	9275
3529 6820 6821 6822	Struct. Eng detailed design Struct. Eng detailed design/Contingency Struct. Eng general const. supervision Struct. Eng quality assurance Struct. Eng surveying Struct. Eng surveying Struct. Eng Residency Contingency Structural Engineering Sub-total	885,025 265,508 442,513 221,256 55,314 215,725 2,085,341	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	2,142,400 642,720 1,071,200 535,600 133,900 522,210 5,048,030	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	3,027,425 908,228 1,513,713 756,856 189,214 737,935 7,133,371	742 223 371 186 46 181
	Total Structural & Eng. Costs	13,148,159	0	31,828,030	0	44,976,189	11024

Section   Paving Cont - Davement design   0	ACTI COD Co		Glover Road New Overpass and Approaches 0 0 Section G.1 21 380 MR	6+800 to 5+500 West of CP overpass to west of Glover Rd Section W.15 16 1300 MR	7+600 to 6+800 West of 232 St Ic to west of CP Rail overpass Section W.14 16 800 MR	7+600 to 6+000 East of CP Rail Overpass to west f Glover Road Overpass <b>Section E.16 MR</b> 16 OR 1600 TR	<b>4080</b> 0 4080	Total Line Cost C/LM
Barriag Const. machine paving concrete   0   0   0   0   0   0   0   0   0	6000	PAVING CONSTRUCTION						
Geod   Paving Corns - Inchreprolling   0								
Deving Const - pawment frieshing	6040	Paving Cons - hot reprofiling	0		0	0		0
Born   Paving Cores - seal coating   0							· · · · · · · · · · · · · · · · · · ·	
Family Cont Appendix Series   Seri			-	7	-	-		_
Paving Const - Contingency   36,162   254,960   157,027   212,779   660,928   162								16
PAVING CONSTRUCTION COSTS 156,702 1,104,825 680,449 922,044 2,884,020 702 3560 Paving Eng detailed design Contingency 2,291 22,201 14,289 19,383 60,144 15 5860 Paving Eng detailed design Contingency 3,291 22,201 14,289 19,383 60,144 15 5860 Paving Eng detailed design Contingency 3,291 22,201 14,289 19,383 60,144 15 5860 Paving Eng detailed design Contingency 6,288 44,193 27,218 36,882 114,581 28 5861 Paving Eng detailed design 7,280 114,581 28 5861 Paving Eng detailed design Contingency 7,286 5,224 3,442 4,510 114,520 14,510 114,510 114,520 14,510 114,510								0
Section   Paving Eng detailed design   10.999   77.338   47.831   64.543   200.481   49.339   29.410   14.239   23.201   14.239   23.201   14.239   23.201   14.239   23.201   14.239   23.201   14.239   23.201   14.239   23.201   14.239   23.201   14.239   23.201   14.239   23.201   23.	6099	Paving Cons - Contingency	36,162	254,960	157,027	212,779	660,928	162
		PAVING CONSTRUCTION COSTS	156,702	1,104,825	680,449	922,044	2,864,020	702
See   Paving Eng general const. supervision   3,134   22,097   13,009   18,441   57,280   14,561   29   20   22   27   27   27   27   27   27								49
Best   Paving Eng Quality assurance   6,288   44,193   27,218   36,882   114,551   28   28   28   28   28   28   28   2								
September   Sept								28
Paving Engineering Sub-total   27,501   193,897   119,419   161,819   502,636   123	6862	Paving Eng surveying	/84					
Total Paving Const. & Eng. Costs   184,203   1,298,722   799,868   1,083,863   3,366,656   825	6869							123
SECO   OPERATIONAL CONSTRUCTION   SECOND   SEC		Total Paying Conet & Eng. Coete	184 203	1 208 722	799 868	1 083 863	3 366 656	825
6510   Operat.Cons - signing   66,000   0   0   0   0   0   0   0   0   0			104,203	1,250,722	799,000	1,065,665	3,360,636	
6510   Operat.Cons - signing   66,000   0   0   0   0   0   0   0   0   0								
6520   Operal. Cons - signalis   O								
6530 Operal.Cons signing 760 2,600 1,600 3,200 8,160 237,000 56540 Operal.Cons - guard rail 64,500 39,000 39,000 94,500 237,000 56550 Operal.Cons - pavement markings 3,000 16,250 10,000 16,000 45,250 11 10,692 37,000 56,000 0peral.Cons - mobilization 4,028 1,736 1,518 3,411 10,692 3 3,000 0peral.Cons - contingency 41,486 17,876 15,635 35,133 110,131 27 0PERATIONAL CONSTRUCTION COSTS 179,774 77,461 67,753 15,244 477,233 117 3540 Operal. Eng - detailed design 2,775 1,627 1,423 1,197 10,022 2 3,000 0peral. Eng - detailed design 2,775 1,627 1,423 3,197 10,022 2 2,000 0peral. Eng - detailed design 2,775 1,627 1,423 3,197 10,022 2 2,000 0peral. Eng - detailed segism 0 9,888 4,260 3,726 8,373 26,248 6,401 Operal. Eng - quality assurance 3,595 1,549 1,355 3,045 9,545 2,642 0peral. Eng - quality assurance 3,595 1,549 1,355 3,045 9,545 2,642 0peral. Eng - surveying 899 387 339 761 2,386 1 0peral. Eng - surveying 899 387 339 761 2,386 1 0peral. Eng - surveying 899 387 339 761 2,386 1 0peral. Eng - surveying 899 387 399 761 2,386 1 0peral. Eng - surveying 899 387 399 761 2,386 1 0peral. Eng - Residency Contingency 4,315 1,859 1,626 3,654 11,454 3 0peralional Enginering Sub-total 35,056 15,105 13,212 29,688 93,060 23 1 0peralional Enginering Sub-total 35,056 15,105 13,212 29,688 93,060 23 1 0peralional Enginering Sub-total 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0								
6540   Operat.Cons- guard rail   64,500   39,000   39,000   39,000   45,00   237,000   58,000   65,0								
5690   Operat.Coms - mobilization   4,028   1,736   1,518   3,411   10,692   3   5699   Operat.Coms - contingency   41,466   17,876   15,635   35,133   110,131   27				39,000			237,000	58
Comparison							45,250	11
OPERATIONAL CONSTRUCTION COSTS   179,774   77,461   67,753   152,244   477,233   117								
3540   Operat. Eng - detailed design   12,584   5,422   4,743   10,657   33,406   8   3549   Operat. Eng - detailed design/Contingency   3,775   1,627   1,423   3,197   10,022   2   2   2   2   2   2   2   2   2								
3549   Operat. Eng detailed design/Contingency   3,775   1,627   1,423   3,197   10,022   2   2,6840   Operat. Eng general const. supervision   9,888   4,280   3,726   8,373   26,248   6,6841   Operat. Eng quality assurance   3,595   1,549   1,355   3,045   9,545   2   2,986   2,987   2,988   1,859   1,626   3,654   11,454   3,889   3,875   3,99   761   2,386   1,869   0,987   2,986   1,626   3,654   11,454   3,899   3,975   3,990   761   2,386   1,989   3,980   3,990		OPERATIONAL CONSTRUCTION COSTS	179,774	77,461	67,753	152,244	477,233	117
6840 Operat. Eng. general const. supervision   9,888   4,260   3,726   8,373   26,248   6   6841 Operat. Eng. quality assurance   3,595   1,549   1,355   3,045   9,545   2,545   2,6842   0,6								8
6841 Operat. Eng - quality assurance 3,595 1,549 1,355 3,045 9,545 2 6842 Operat. Eng - surveying 899 387 339 761 2,386 1 1,454 3 Operat. Eng - Residency Contingency 4,315 1,859 1,626 3,654 11,454 3 Operational Enginering Sub-total 35,056 15,105 13,212 29,688 93,060 23    Total Operational Const. & Eng. Costs 214,830 92,566 80,965 181,932 570,293 140								
8842   Operat. Eng - Surveying   889   387   339   761   2,386   1   1,454   3   3,654   3,6								2
Total Operational Const. & Eng.Costs   214,830   92,566   80,965   181,932   570,293   140	6842	Operat. Eng - surveying	899	387	339	761	2,386	1
Total Operational Const.& Eng.Costs   214,830   92,566   80,965   181,932   570,293   140	6849							
S200   ROAD SIDE CONSTRUCTION   S203   RoadSide Cr - water   0		Operational Enginering Sub-total	35,056	15,105	13,212	29,000	93,060	
5203         RoadSide C <sub>1</sub> - water         0				92,566	80,965	181,932	570,293	140
5203         RoadSide Cı - water         0	5200	ROAD SIDE CONSTRUCTION						
S205   RoadSide Ci - storm   0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	5203	RoadSide Cı - water						
5202         RoadSide C <sub>1</sub> - mobilization         0 <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>								
S209   RoadSide Ci - Utility Contingency   0								
5210 RoadSide C <sub>1</sub> - weighscales         0         <		RoadSide Cı - Utility Contingency		0	0	0	0	0
5220 RoadSide C <sub>1</sub> - safety rest areas       0		Road Side Const. Utilities Sub-total	0	0	0	0	0	0
5230         RoadSide C₁ - tourist rest & view areas         0								0
5201     RoadSide Cı - mobilization     0     0     0     0     0       5299     RoadSide Cı - Contingency     0     0     0     0     0     0       Road Side Construction Sub-total     0     0     0     0     0     0       ROAD SIDE CONSTRUCTION COSTS     0     0     0     0     0     0       3550     RoadSide Eı - detailed design     0     0     0     0     0     0       3559     RoadSide Eı - detailed design/Contingency     0     0     0     0     0     0       6850     RoadSide Eı - general const. supervision     0     0     0     0     0     0       6851     RoadSide Eı - quality assurance     0     0     0     0     0     0       6852     RoadSide Eı - surveying     0     0     0     0     0     0				-				
5299   RoadSide C- Contingency   0   0   0   0   0   0   0   0   0								
ROAD SIDE CONSTRUCTION COSTS   0   0   0   0   0   0   0   0   0		RoadSide Cı - Contingency	0	0	0	0	0	
3550   RoadSide Er - detailed design   0   0   0   0   0   0   0   0   0		Road Side Construction Sub-total	0	0	0	0	0	0
3559     RoadSide Er - detailed design/Contingency     0     0     0     0     0       6850     RoadSide Er - general const. supervision     0     0     0     0     0       6851     RoadSide Er - quality assurance     0     0     0     0     0       6852     RoadSide Er - surveying     0     0     0     0     0		ROAD SIDE CONSTRUCTION COSTS	0	0	0	0	0	0
6850 RoadSide E1 - general const. supervision         0 </td <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>0</td>								0
6851 RoadSide Er - quality assurance 0 0 0 0 0 0 0 0 0 6852 RoadSide Er - surveying 0 0 0 0 0 0 0								
6852 RoadSide Ei - surveying 0 0 0 0 0 0 0 0	6851	RoadSide Er - quality assurance						0
AARA BI MILL BI DI LA CALLANDA DA CALLANDA	6852	RoadSide Er - surveying	-	-	0		0	0
6859 RoadSide Er - Residency Contingency         0         0         0         0         0         0         0	6859	HoadSide Ei - Residency Contingency	0	0	0	0	0	0

ACTI COD		Glover Road New Overpass and Approaches 0 0 Section G.1	6+800 to 5+500 West of CP overpass to west of Glover Rd Section W.15	7+600 to 6+800 West of 232 St Ic to west of CP Rail overpass Section W.14	7+600 to 6+000 East of CP Rail Overpass to west f Glover Road Overpass Section E.16 MR	4080	Total Line Cost C/LM
	st. # 6.14A Road Type on Sept.1, 200 DESCRIPTION \Length	21 380	16 1300	16 800	16 OR 1600 TR	0 4080	4080
	Road Side Engineering Sub-total	MR0	MR 0	MR 0	MR 0	0	0
	Total Road Side Const.& Eng.Costs	0	0	0	0	0	0
====							
5300	OTHER CONSTRUCTION			0			_
	Other Const - water Other Const - sanitary	0	0	0	0	0	0
5305	Other Const - storm	0	0	0	0	0	0
	Other Const - mobilization	0	0	0	0	0	0
5309	Other Const - utility contingency Other Const. Utilities Sub-total	0	0	0	0	0	0
5310	Other Const - railroads main & spur lines	0	0	0	0	0	0
5320	Other Const - railroad crossings	0	0	0	0	0	0
	Other Const - marine work Other Const - environmental mitigations	0	0	0	0	0	0
	Other Const - environmental mitigations Other Const - mobilization	0	0	0	0	0	0
5399	Other Const - Contingency	ő	0	Ö	Ö	ő	ő
	Other Construction Sub-total	0	0		0	0	0
	OTHER CONSTRUCTION COSTS	0	0	0	0	0	0
3570	Other Eng detailed design	0	0	0	0	0	0
	Other Eng detailed design/Contingency Other Eng general const. supervision	0	0	0	0	0	0
	Other Eng quality assurance	ő	0	ő	0	ŏ	ő
6872	Other Eng surveying	0	0	0	0	0	0
6879	Other Eng Residency Contingency Other Engineering Sub-total	0	0	0	0	0	0
	Total Other Const.& Eng.Costs	0		0	0	0	0
3500	DETAILED DESIGN						
2520	from 3510,3520,3540,3550,3570	1,274,758	737,908	3,217,594	854,681	6,084,941	1491
	Geotech. En - detailed design Geotech. En - Contingency	99,568 29,870	48,653 14,596	189,195 56,758	56,353 16,906	393,768 118,130	97 29
	TOTAL DETAILED DESIGN COSTS	1,404,196	801,157	3,463,548	927,939	6,596,840	1617
	TOTAL DETAILED DESIGN COSTS	1,404,130	001,137	3,403,340	327,333	0,030,040	1017
6800	RESIDENT ENGINEERING	4 000 050	701 701	0.001.010	050.000	5 00 1 50 1	
	from 6810,6820,6840,6850,6860,6870	1,060,352	731,734	2,691,842	850,666	5,334,594	
	TOTAL RESIDENT ENG. COSTS	1,060,352	731,734	2,691,842	850,666	5,334,594	1307
						0	
						0	0
	PART 1 SUMMARY						
	CONSTRUCTION		6,287,598	24,265,744	7,284,687	47,435,975	11626
	ENGINEERING & SUPERVISION		1,391,047	4,999,215	1,628,958	10,032,280	2459
	CONTRACTUAL CONTINGENCY	3,483,302	2,303,594	8,779,488	2,674,094	17,240,476	4226 0
	CONSTRUCTION COST TOTAL	15,094,307	9,982,239	38,044,447	11,587,739	74,708,731	18311
		10,034,007	5,302,203	30,044,447	11,567,755	74,700,731	
2000	PROJECT MANAGEMENT	000 000	004 000	050.000	000 704	1 000 010	440
2060 2062	Project Man office costs wages Project Man office costs - expenses	339,622 0	224,600	856,000 0	260,724 0	1,680,946	412 0
		0	0	0	0	0	0
2061	Project Man general	0	0	0	0	0	0
	Project Manager Sub-total	339,622	224,600	856,000	260,724	1,680,946	412
	Client - office costs wages	301,886	199,645	760,889	231,755	1,494,175	366
2012	Client - office costs - expenses Client - printing costs	0	0	0	0	0	0
2011	Client - general	0	0	0	0	0	0
	Client Sub-total	301,886	199,645	760,889	231,755	1,494,175	366
						I	

COD		Glover Road New Overpass and Approaches 0 Section G.1	6+800 to 5+500 West of CP overpass to west of Glover Rd Section W.15	7+600 to 6+800 West of 232 St Ic to west of CP Rail overpass Section W.14	7+600 to 6+000 East of CP Rail Overpass to west f Glover Road Overpass Section E.16 MI	R 4080	Total Line Cost C/LM
Blk Es Version	st. # 6.14A Road Type on Sept.1, 200 DESCRIPTION \Length	21 380	16 1300	16 800	16 OF 1600 TF		4080
2070 2072 2073	Public Rel wages & expenses Public Rel adv., media, displays Public Rel opening ceremonies	MR 90,566 0 0	MR 59,893 0 0	MR 228,267 0 0	MR 69,526 0 0	448,252 0 0	110 0 0
	Public Rel general Public Relations Sub-total	90,566	59,893	0 228,267	0 69,526	0 448,252	110
2040	Legal Costs - lawyers fees Legal Costs - general	10,566 0	6,988 0	26,631 0	8,111 0	52,296 0	13 0
	Legal Costs Sub-total	10,566	6,988	26,631	8,111	52,296	13
	Insurance - const./ liability, E&O Insurance - general	90,566 0	59,893 0	228,267 0	69,526 0	448,252 0	110 0
	Legal Costs Sub-total	90,566	59,893	228,267	69,526	448,252	110
2099	Project Management Contingency  TOTAL PROJECT MANAGEMENT COSTS	249,962	165,306 716,325	630,016 2,730,070	191,893  831,536	1,237,177	303 1314
4000 4010	LAND Land(Code 4-Mrkt,ROW,Serv,Imp.V,Ease.C,T Acquisition Sub-total	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0
4020	Land(Code 4 -Bus.,5%,Mrg.P,Rel\$,P/Tax,Etc	0	0	0	0	0	0
4030	Land(Code 4-Owners(LS,Apprsl,Rprt,Lgl,In Land(Code 4-Demolition	0	0	0	0	0	0
4050	Land(Code 4-Pro.Man,P.Tax,Util,Security	0	0	0	0	0	0
4060 4070	Land(Code 4 -Not Used Land(Code 4 -Not Used	0	0	0	0	0	0
4080	Land(Code 4-Acq.F,M/Sal,TrvIV,Cntr.S,Appr.	0	0	0	0	0	0
	Land(Code 4-Surveys  Associated costs-sub-total	0	0	0	0	0 0 0	0 0 0 0 0
4099	Land Contingency Sub-total	0	0	0	0	0	0
	TOTAL LAND COSTS	0	0	0	0	0	0
9800	MANAGEMENT RESERVE					=======================================	
	MAN. RES planning MAN. RES preliminary design	0	0	0	0	0	0
	MAN. RES utility construction	0	0	0	0	0	0
	MAN. RES grade construction MAN. RES structural construction	0	0	0	0	0	0
	MAN. RES paving construction	0	0	0	0	0	0
	MAN. RES operation construction MAN. RES roadside construction	0	0	0	0	0	0
	MAN. RES other construction	0	0	0	0	0	0
	MAN. RES project management MAN. RES land	0	0	0	0	0	0
	MAN. RES detailed eng.	0	0	0	0	0	0
	MAN. RES residency eng. MAN. RES risk contingency	0	0	0	0	0	0
	TOTAL MANAGEMENT RESERVE					0	0
			=========		=======	=======================================	======
9900	TOTAL LESS ESCALATION FISCAL ESCALATION						
	YEAR PROJECTED ESCALATION 2006-2007	0	0	0	0	0	0
	2007-2008	0	0	0	0	0	0
	2008-2009 2009-2010	0	0	0	0	0	0
	2010-2011	0	0	0	0	0	0
	2011-2012	0	0	0	0	0	0
	2012-2013 2013-2014	0	0	0	0	0	0

O:ISW\1200 - MoT A&W Contract #15\SWF - Highway 1 File: Functional Planning\Data\Costing\March 29th\[Package 3 - Parsons Hwy 1 Widening (2016Dollars) Package 3 - West of 232 ACTIVITY EST.DATE April 4, 2016 CODE R3 DATE: Sept 15, 2016 Conceptual Est. Divison\site	Glover Road New Overpass and Approaches 0 0 Section G.1	6+800 to 5+500 West of CP overpass to west of Glover Rd Section W.15	Section W.14	7+600 to 6+000 East of CP Rail Overpass to west f Glover Road Overpass Section E.16 MR	4080	Total Line Cost C/LM
Blk Est. # 6.14A Road Type Version Sept.1, 200 DESCRIPTION \Length	21 380	16 1300	16 800	16 OR 1600 TR	4080	4080
	MR	MR	MR	MR		
2014-2015	0	0	0	0	0	0
TOTAL ESCALATION	0	0	0	0	0	0
PART 2 SUMMARY NON-CONSTRUCTION COSTS	======================================					======
Non-Construction	833.206	551.020	2.100.053	639.643	4.123.922	1011
Non-Const. Contingency	249,962	165,306	630,016	191,893	1,237,177	303
TOTAL NON-CONSTRUCTION COSTS	1,083,167	716,325	2,730,070	831,536	5,361,099	1314
DIVISION TOTAL FOR ROAD TYPE	16,177,474	10,698,564	40,774,516	12,419,275	80,069,830	19625



# PACKAGE 4 - SECTIONS

ID	Chainage Start	Chainage End	Description
W.12	8+800	12+800	Highway 1 Westbound Lanes
W.11	12+800	14+600	Highway 1 Westbound Lanes
E.14	8+800	12+200	Highway 1 Eastbound Lanes
E.13	12+200	14+600	Highway 1 Eastbound Lanes

File: Planning\Data Parsons	MoT A&W Contract #15\SWF - Highway 1 Functional \Costing\March 29th\Package 4 - Between 232 and Hwy 1 Widening Package 4 - Btw 232 and 264 EST.DATE April 4, 2016 R3 DATE: Sept 15, 2016	12+800 to 8+800 East of 248 St Overpass to 72 Ave	14+600 to 12+800 West of 264 St IC to east of 248 St overpass	12+200 to 8+800 Just east of 248 St Overpass to east of 232 St IC	14+600 to 12+200 West of 264 St IC to east of 248 St Overpass			Total Line Cost C/LM
Conceptual Est.	Divison\site	Section W.12	Section W.11	Section E.14	Section E.13	MR	11600	
Blk Est. # 6.14A Version Sept.1, 200	Road Type	16 4000	16 1800	16 3400	16 2400	OR	0 11600	11600
	F	MR	MR	MR	MR	-	44.000.700	4000
	Engineering Land	3,807,086 0	2,112,378 0	3,404,209 0	2,599,117		11,922,790	1028 0
	Construction	17,215,383	10.088.309	15,636,464	12,170,501		55,110,657	4751
	Management Reserve	0	0	0	0		0	0
	Escalation	0	0	0	0		0	0
	Total	21,022,469	12,200,688	19,040,673	14,769,618		67,033,447	5779
	DAGIO QUANTITY QUILAMA DV							
	BASIC QUANTITY SUMMARY  Construct.Cost ONLY Per L.M.	4.304	5.605	4.599	5.071	\$/LM	4,751	
	Land Area	11.7	5.8	9.5	7.6	ha	34.6	
	Land Anda	****	0.0	0.0	7.0		01.0	
	Mobilization	351,927	207,280	319,489	249,821		1,128,517	
	Land Cont.	0	0	0	0		0	
	Construction Cont.	3,644,353	2,134,984	3,310,239	2,576,154		11,665,730	12,717,844
	Engineering Cont.	878,558	487,472	785,587	599,796		2,751,413	
	Supervision Cont. Total Cont.	328,428 4,851,339	193,087 2,815,543	298,176 4,394,001	232,423 3,408,373		1,052,114 15,469,257	
	Total Golit.	4,001,000	2,010,040	4,004,001	0,400,070		10,400,207	
	S.G.S.B.	18,164	8,364	15,299	11,106	m3	52,934	
	C.B.C.	9,989	4,480	8,501	5,977	m3	28,947	
	Asphalt	13,824	6,188	13,360	9,378	t	42,751	
	Concrete Barrier Noise Attentuation Wall	1,530 0	225 0	1,620 0	445 0	lm m2	3,820	
	No. of Light Poles	0	0	0	0	ea	0	
	Sidewalk	0	0	0	0	lm	0	
	Curb and Gutter	0	0	0	0	lm	0	
	Signals	0	0	0	0	ea	0	
	Bridge total area	0	0	0	0	m2	0	
								ENG
	Total Rock	0	0	0	0	m3	0	0
	Total OM	50,760	39,770	41,540	47,360	m3	179,430	ő
	Total Stripping	22,300	6,800	18,900	8,000	m3	56,000	0
	Total Borrow	0	0	0	0	m3	0	
	Total Cut/Excavation	73,060	46,570	60,440	55,360	m3	235,430	0
	Total Fill Surplus or Deficit	75,808 -2,748	37,341 9,230	84,836 -24,396	45,218 10,142	m3 m3	243,202 -7,772	0
	Surplus of Delicit	-2,740	9,230	-24,330	10,142	1113	-7,772	
	ENG & PM	3.807	2.112	3.404	2.599		11.923	11.922
	LAND	0.000	0.000	0.000	0.000		0.000	0.000
	CONST. BRIDGES-R/W	17.215 0.000	10.088 0.000	15.636 0.000	12.171 0.000		55.111 0.000	55.110 0.000
	MANAGEMENT RESERVE	0.000	0.000	0.000	0.000		0.000	0.000
	ESCALATION	0.000	0.000	0.000	0.000		0.000	0.000
	TOTAL (Millions) (2016Dollars)	21.022	12.200	19.040	14.770		67.034	67.032
	TOTAL Cost per meter	5,256	\$ 6,778	\$ 5,600	\$ 6,154		\$ 5,779	
	Construction cost per meter	4,304	\$ 5,604	\$ 4,599	\$ 5,071		\$ 4,751	

File: Planning\Dat Parson (2016Dollars ACTIVITY CODE Conceptual Est Blk Est. # 6.14A Version Sept.1, 20	Road Type	12+800 to 8+800 East of 248 St Overpass to 72 Ave Section W.12 16 4000	14+600 to 12+800 West of 264 St IC to east of 248 St overpass Section W.11 16 1800 MR	12+200 to 8+800 Just east of 248 St Overpass to east of 232 St IC Section E.14 16 3400 MR	14+600 to 12+200 West of 264 St IC to east 0248 St Overpass <b>Section E.13</b> Mi 16 OF 2400 TR	0	Total Line Cost C/LM
2000	PROJECT MANAGEMENT	1,082,743	628,385	980,672	760,695	3,452,495	298
2500 3000 3500	PLANNING PRELIMINARY DESIGN DETAILED DESIGN	0 652,000 1,193,785	0 293,400 703,121	0 554,200 1,083,750	0 391,200 847,426	1,890,800 3,828,082	0 163 330
	Total Engineering	1,845,785	996,521	1,637,950	1,238,626	5,718,882	493
4000	LAND ACQUISITION	0	0	0	0	0	0
5000 5200 5300 5500 6000 6500 6700 6800	GRADE CONSTRUCTION ROAD SIDE CONSTRUCTION OTHER CONSTRUCTION STRUCTURAL CONSTRUCTION PAVING CONSTRUCTION OPERATIONAL CONSTRUCTION UTILITY CONSTRUCTION RESIDENT ENGINEERING	9,781,110 0 0 0 1,779,522 522,210 65,000 1,094,760	6,227,769 0 0 0 797,072 91,773 0 643,624	8,658,063 0 0 0 1,759,707 551,359 65,000 993,920	7,167,670 0 0 0 1,236,163 173,349 10,000 774,742	31,834,611 0 0 0 5,572,464 1,338,691 140,000 3,507,047	2744 0 0 0 480 115 12 302
	Total Construction	13,242,602	7,760,238	12,028,049	9,361,924	42,392,813	3655
9700	CONTINGENCY	4,851,339	2,815,543	4,394,001	3,408,373	15,469,257	1334
9800	SUB-TOTAL MANAGEMENT RESERVE	21,022,469 0	12,200,688 0	19,040,673 0	14,769,618 0	67,033,447 0	5779 0
	TOTAL	21,022,469	12,200,688	19,040,673	14,769,618	67,033,447	5779
9900	ESCALATION	0	0	0	0	0	0
***************************************	TOTAL COST	21,022,469	12,200,688	19,040,673	14,769,618	67,033,447	5779
==== ======	Const. Less Resident Eng.	12,147,842	7,116,614	11,034,129	8,587,182	38,885,766	3352

ACTI COD Co Blk Es	Planning\Data Parsons (2016Dollars) VITY	MoT A&W Contract #15\SWF - Highway 1 Functional \Costing\March 29th\Package 4 - Between 232 and Hwy 1 Widening Package 4 - Btw 232 and 264 EST.DATE April 4, 2016 R3 DATE: Sept 15, 2016 Divison\site Road Type DESCRIPTION \Length	12+800 to 8+800 East of 248 St Overpass to 72 Ave Section W.12	14+600 to 12+800 West of 264 St IC to east of 248 St overpass Section W.11 16 1800	12+200 to 8+800 Just east of 248 St Overpass to east of 232 St IC Section E.14 16 3400	14+600 to 12+200 West of 264 St IC to east of 248 St Overpass <b>Section E.13 MI</b> 16 OF 2400 TF	R 0	Total Line Cost C/LM
		D	MR	MR	MR	MR		
2500	Consultant	PLANNING - transport, planning study	0	0	0	0	0	0
2521		- corridor study	0	0	0	0	0	0
2541		- functional plan. study	o o	0	ő	0	Ö	0
	Consultant		Ō	Ö	Ō	0	I 0	l ö
	Consultant s		0	0	0	0	0	0
0510	0!:	mode at Ideat						
	Client Client	- project ident transport. planning study	0	0	0	0	0	0
	Client	- corridor study	0	0	0	0	0	0
	Client	- functional plan. study	0	0	0	0	o o	0
	Client	- general	0	0	0	ő	0	0
	Client Sub-to		ő	ő	o o	o o	l ő	l ŏ
2599	Planning Co	ntingency	0	0	0	0	0	0
		TOTAL PLANNING	0	0	0	0	0	0
====		PDELIMINARY DEGICAL						
3000	Consultant	PRELIMINARY DESIGN	0	0	0	0	0	١ ,
		- aerial base plan - prel. design	280,000	126,000	238,000	168,000	812,000	70
		- control survey	200,000	120,000	230,000	0	012,000	/ 0
3021		- environmental impact	112,000	50,400	95.200	67,200	324,800	28
3031		- functroad field survey	0	0,400	00,200	0,200	02-4,000	1 0
3041		- functional design	200,000	90,000	170,000	120,000	580.000	50
3051		- funct. structural des.	0	0	0	0	0	0
3061		- geotechnical design	60,000	27,000	51,000	36,000	174,000	15
3071	Consultant	- right-of-way research	0	0	0	0	0	0
3002	Consultant		0	0	0	0	0	0
	Consultant s	sub-total	652,000	293,400	554,200	391,200	1,890,800	163
2010	Client	agrical bases plans	0	0		0	0	0
	Client	- aerial base plan - prel. design	0	0	0	0	0	0
	Client	- control survey	0	0	0	ő	o o	Ö
	Client	- environmental impact	0	0	0	0	0	Ö
3030		- functroad field survey	ō	Ö	ō	Ō	Ö	Ö
3040	Client	- functional design	0	0	0	0	0	0
3050	Client	- funct. structural des.	0	0	0	0	0	0
	Client	- geotechnical design	0	0	0	0	0	0
	Client	- right-of-way research	0	0	0	0	0	0
3001	Client	- general	0	0	0	0	0	0
	Client Sub-to	otal	0	0	0	0	0	0
3099	Preliminary of	design Contingency	195,600	88,020	166,260	117,360	567,240	49
		ELIMINARY DESIGN	847,600	381,420	720,460	508,560	2,458,040	212
6700		UTILITIES						
	Util. Prov.	- Hydro	15,000	0	15,000	10,000	40,000	3
6711	Util. Prov.	- Telephone	50,000	0	50,000	0	100,000	9
	Util. Prov.	sub-total	65,000	0	65,000	10,000	140,000	12
6746	LIELOS	pipelines	^			^		
	Util.Others		0	0	0	0	0 0	0
		telecommunication     storm & sewer inspect.	0	0	0	0	0	0
		- waterworks inspect.	0	0	ő	0	0	o o
		- engineering services	0	0	ő	ő	Ö	o o
		- parks/recreation-prel.	Ō	Ö	Ö	ő	Ö	ő
6718	Util.Others	- transit	0	0	0	0	0	0
6719	Util.Others	- tr-ops/signs & detours	0	0	0	0	0	0
6701	Util.Others		0	0	0	0	0	0
	Util.Others	sub-total	0	0	0	0	0	0
6799	Util.Others C	Contingency	19,500	0	19,500	3,000	42,000	4
	TOTAL UTI	LITIES	84,500		84,500	13.000	182,000	16
		=======================================				13,000	102,000	
5000		GRADE CONSTRUCTION						I
	Grade Cons	1- water	0	0	0	0	0	0
5033	Grade Cons	1 - sanitary	0	0	0	0	0	0

ACTI <sup>1</sup> COD Coi		12+800 to 8+800 East of 248 St Overpass to 72 Ave Section W.12	14+600 to 12+800 West of 264 St IC to east of 248 St overpass Section W.11	12+200 to 8+800 Just east of 248 St Overpass to east of 232 St IC Section E.14	14+600 to 12+200 West of 264 St IC to east of 248 St Overpass Section E.13 M	MR 11600	Total Line Cost C/LM
	n Sept.1, 200 DESCRIPTION \Length	4000 MB	1800	3400	2400 T		11600
	Grade Consi - storm	0	MR 0	MR 0	MR 0	0	0
	Grade Const - mobilization Grade Const - utility contingency	0	0	0	0	0	0
0000	Grade Const. Utilities Sub-total	0	0	Ö	0	o o	ő
5010	Grade Const - site prep./clear,grubbing	14,500	19,575	12,325	0	46,400	4
	Grade Const - road grade/exc,placing,fill Grade Const - drainage/pipe,cul.	5,256,640 2,000,000	3,010,015 2,000,000	5,013,665 1,500,000	3,606,940 2,000,000	16,887,260 7,500,000	1456 647
5030	Grade Const - drainage/pipe,cui.	2,000,000	2,000,000	1,500,000	2,000,000	7,500,000	047
	Grade Const-SGSB/produce,place,comp	1,271,479	585,514	1,070,920	777,452	3,705,365	319
5051	Grade Consi -CBC/produce,place,comp	898,991	403,200	765,134	537,926	2,605,250	225
5060 5061	Grade Const - grade finishing landscaping Grade Const - grade finishing hydro seed.	0 54,613	0 28,074	0 43,843	0 36,585	163,115	0 14
	Grade Const - grade finishing flydro seed.  Grade Const - grade finishing fencing	04,013	20,074	43,043	36,363	163,113	1 0
5063	Grade Const - noise barriers	0	0	0	0	Ö	0
5064	Grade Const - passing lanes	0	0	0	0	0	0
5090	Grade Const - sidewalks,curb & gutter	0	0	0	0	0	0
	Grade Const-detours c/w ex,bf,paving Grade Const-mobilization	0 284,887	0 181.391	252,177	0 208,767	927,222	0 80
	Grade Const - Contingency	2.934.333	1.868.331	2.597.419	2,150,301	9,550,383	823
	Grade Construction Sub-total	12,715,443	8,096,100	11,255,482	9,317,970	41,384,994	3568
	GRADE CONSTRUCTION COSTS	12,715,443	8,096,100	11,255,482	9,317,970	41,384,994	3568
3510	Grade Eng detailed design	890.081	566,727	787.884	652.258	2.896.950	250
	Grade Eng detailed design/Contingency	267,024	170,018	236,365	195,677	869,085	75
	Grade Eng general const. supervision	381,463	242,883	337,664	279,539	1,241,550	107
	Grade Eng quality assurance	254,309	161,922	225,110	186,359	827,700	71
6819	Grade Eng surveying Grade Eng Residency Contingency	254,309 267,024	161,922 170,018	225,110 236,365	186,359 195,677	827,700 869,085	71 75
0013	Grade Engineering Sub-total	2,314,211	1,473,490	2,048,498	1,695,871	7,532,069	649
	Total Grade Const. & Eng. Costs	15,029,653	9,569,590	13,303,980	11.013.841	48,917,063	4217
5500	OTRUGTURAL COMOTRUCTION						
5500 5522	STRUCTURAL CONSTRUCTION Struct.Const - water	0	0	0	0	0	0
	Struct.Const - sanitary	ő	ő	0	ő	ő	l ő
5524	Struct.Const - storm	0	0	0	0	0	0
	Struct.Const - mobilization	0	0	0	0	0	0
5599	Struct.Const - utility contingency Structural Const. Utilities Sub-total	0	0	0	0	0	0
	Struct.Const - tunnel site preparation	0	0	0	0	0	0
	Struct.Const - tunnel construction Struct.Const - snow shed site prep.	0	0	0	0	0	0
	Struct.Const - snow sned site prep. Struct.Const - snow shed site const.	0	0	0	0	0	0
							1
	Struct.Const - bridge site preparation	0	0	0	0	0	0
	Struct.Const - bridge piers Struct.Const - bridge abutments	0	0	0	0	0	0
5517	Struct.Const - bridge superstructure	0	0	0	0	0	0
5518	Struct.Const - retain. wall site prep.	0	0	0	0	0	0
5519	Struct.Const - retaining wall const.	0	0	0	0	0	0
	Struct.Const - mobilization	0	0	0	0	0	0
5529	Struct.Const - Contingency Structural Construction Sub-total	0	0	0	0	0	0
	STRUCTURAL CONSTRUCTION COSTS	0	0		0	0	0
	Struct. Eng detailed design	0	0	0	0	0	0
	Struct. Eng detailed design/Contingency Struct. Eng general const. supervision	0	0	0	0	0	0
	Struct. Eng general const. supervision Struct. Eng quality assurance	0	0	0	0	0	0
6822	Struct. Eng surveying	0	0	0	0	0	0
6829	Struct. Eng Residency Contingency	0	0	0	0	0	0
	Structural Engineering Sub-total	0	0	0	0	0	0
	Total Structural & Eng. Costs	0	0	0	0	0	0

ACTI COD Co Blk Es		12+800 to 8+800 East of 248 St Overpass to 72 Ave Section W.12 16 4000 MR	14+600 to 12+800 West of 264 St IC to east of 248 St overpass Section W.11 16 1800 MR	12+200 to 8+800 Just east of 248 St Overpass to east of 232 St IC Section E.14 16 3400 MR	14+600 to 12+200 West of 264 St IC to east of 248 St Overpass Section E.13 MR 16 OR 2400 TR	11600 0 11600	Total Line Cost C/LM
6030 6040 6050 6060	PAVING CONSTRUCTION Paving Cons - machine paving asphalt Paving Cons - machine paving concrete Paving Cons - hot reprofiling Paving Cons - shoulder paving Paving Cons - spawment finishing Paving Cons - seal coating	1,727,691 0 0 0 0	773,856 0 0 0 0	1,708,454 0 0 0 0	1,200,158 0 0 0 0	5,410,159 0 0 0 0	466 0 0 0 0
6001 6010	Paving Cons - mobilization Paving Cons - pavement design Paving Cons - Contingency	51,831 0 533,857	23,216 0 239,122	51,254 0 527,912	36,005 0 370,849	162,305 0 1,671,739	14 0 144
	PAVING CONSTRUCTION COSTS	2,313,379	1,036,193	2,287,619	1,607,012	7,244,203	625
3569 6860	Paving Eng detailed design Paving Eng detailed design/Contingency Paving Eng general const. supervision Paving Eng quality assurance Paving Eng surveying Paving Eng Residency Contingency Paving Engineering Sub-total	161,937 48,581 46,268 92,535 11,567 45,111 405,998	72,534 21,760 20,724 41,448 5,181 20,206 181,852	160,133 48,040 45,752 91,505 11,438 44,609 401,477	112,491 33,747 32,140 64,280 8,U35 31,337 282,031	507,094 152,128 144,884 289,768 36,221 141,262 1,271,358	44 13 12 25 3 12 110
	Total Paving Const. & Eng. Costs	2,719,377	1,218,045	2,689,096	1,889,042	8,515,561	734
6520 6530 6540 6550 6501 6599 3540 3549 6840 6841 6842	OPERATIONAL CONSTRUCTION Operat.Cons - lighting Operat.Cons - signals Operat.Cons - signing Operat.Cons - squard rail Operat.Cons - pawement markings Operat.Cons - contingency OPERATIONAL CONSTRUCTION COSTS  Operat. Eng - detailed design Operat. Eng - detailed design/Contingency Operat. Eng - general const. supervision Operat. Eng - quality assurance Operat. Eng - sciedency Contingency Operat. Eng - Residency Contingency	678,873 47,521 14,256 37,338 13,577 3,394 16,293	0 0 3,600 67,500 18,000 2,673 27,532 119,305 8,351 2,505 6,562 2,386 597 2,863 23,264	0 6,800 486,000 42,500 16,059 165,408 716,767 50,174 15,052 39,422 14,335 3,584 17,202 139,770	0 0 4,800 133,500 30,000 5,049 52,005 225,354 15,775 4,732 12,394 4,507 1,127 5,408 43,944	1,740,298 121,821 36,546 95,716 34,806 8,701 41,767 39,358	0 0 2 99 11 3 35 150 11 3 8 8 3 1 4 4 29
	Total Operational Const.& Eng.Costs	811,253	142,569	856,536	269,298	2,079,656	179
5204 5205	ROAD SIDE CONSTRUCTION  RoadSide Cı - water  RoadSide Cı - sanitary  RoadSide Cı - storm  RoadSide Cı - mobilization  RoadSide Cı - Utility Contingency  Road Side Const. Utilities Sub-total	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0	0 0 0 0 0
5210 5220 5230 5201 5299	RoadSide C <sub>1</sub> - weighscales RoadSide C <sub>1</sub> - safety rest areas RoadSide C <sub>1</sub> - tourist rest & view areas RoadSide C <sub>1</sub> - mobilization RoadSide C <sub>1</sub> - Contingency Road Side Construction Sub-total	0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 0
	ROAD SIDE CONSTRUCTION COSTS	0	0	0	0	0	0
3559 6850 6851 6852	RoadSide Er - general const. supervision RoadSide Er - quality assurance	0 0 0 0	0 0 0 0 0	0 0 0 0	0 0 0 0	0 0 0 0 0	0 0 0 0 0

Bit Sett 2, 15 At All	ACTIV	Planning\Data Parsons 2016Dollars) VITY	MoT A&W Contract #15\SWF - Highway 1 Functional \(\text{iCosting\)March 29th\/\(\text{Package 4}\) - Between 232 and \(\text{Hwy 1 Widening}\) \(\text{Package 4}\) - Btw 232 and 264 \(\text{EST.DATE April 4, 2016}\) \(\text{R3 DATE: Sept 15, 2016}\) \(\text{Divison\}\) \(\text{bivison\}\) \(\text{identification}\)	12+800 to 8+800 East of 248 St Overpass to 72 Ave Section W.12	14+600 to 12+800 West of 264 St IC to east of 248 St overpass Section W.11	12+200 to 8+800 Just east of 248 St Overpass to east of 232 St IC Section E.14	14+600 to 12+200 West of 264 St IC to east of 248 St Overpass Section E.13 MF	R 11600	Total Line Cost C/LM
Road Side Engineering Sub-total   0	Blk Es	t. # 6.14A	Road Type	16	16	16	16 OR	0	11600
Total Road Side Const. & Eng.Costs								0	0
OTHER CONSTRUCTION   Sold   Other Corest - water   O				0	0	0	0	0	0
5000   Other Cornel - saintary   0									
5030   Other Const - sanitary		Other Const		0	0	0	0		,
5005   Other Const Atom									
5999   Other Corest - Litility contingency   0				0					
STATE   Control Control Libration Sub-Intal   0				0					
S310   Other Const - railroads main & spur lines   0	5309	Other Const	- utility contingency						
5220 Other Const. + rainford crossings		Other Const	. Othities Sub-total						
5330   Other Const marine work	5310	Other Const	- railroads main & spur lines						
Committee   Comm									
Sa01   Other Const - mobilization   0   0   0   0   0   0   0   0   0									
Other Construction Sub-total   O									
Other Construction Sub-total 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0				-			-	-	
Section   Committee   Commit		Other Cons	truction Sub-total	0	0	0	0	0	0
2579 Other Eng.		OTHER CO	NSTRUCTION COSTS	0	0	0	0	0	0
2579 Other Eng.	3570	Other Eng.	- detailed design	0	0	0	0	0	0
Construction Cost   Construction Cost   Construction Cost   Construction Cost				0					
Construction Costs   Constru				0			0	0	
Total Other Engineering Sub-total   0	6871	Other Eng.	- quality assurance	0					
Total Other Engineering Sub-total   0	6872	Other Eng.	- surveying	0					
Total Other Const.& Eng.Costs	6879	Other Eng.	- Residency Contingency	0	-		-		
DETAILED DESIGN   From 3510,3520,3540,3550,3570   1,429,400   841,895   1,297,648   1,014,681   4,583,624   395		Other Engin	eering Sub-total						
DETAILED DESIGN		<b>Total Other</b>	Const.& Eng.Costs	0	0	0	0	0	0
From 3510,3520,3540,3550,3570									
S539   Geotech. En - Contingency   94,246   55,510   85,559   66,902   302,217   26   26   26   26   26   26   26   2									
State   Stat			DETAILED DESIGN						
TOTAL DETAILED DESIGN COSTS   1,551,920   914,058   1,408,875   1,101,653   4,976,506   429	3500	from 35	DETAILED DESIGN 510,3520,3540,3550,3570	1,429,400	841,895	1,297,648	1,014,681	4,583,624	395
RESIDENT ENGINEERING   from 6810,6820,6840,6850,6860,6870   1,423,189   836,711   1,292,096   1,007,165   4,559,161	3500 3530	from 35 Geotech. Er	DETAILED DESIGN 510,3520,3540,3550,3570 n detailed design	1,429,400 94,246	841,895 55,510	1,297,648 85,559	1,014,681 66,902	4,583,624 302,217	395 26
RESIDENT ENGINEERING	3500 3530	from 35 Geotech. Er Geotech. Er	DETAILED DESIGN 510,3520,3540,3550,3570 - detailed design - Contingency	1,429,400 94,246 28,274	841,895 55,510 16,653	1,297,648 85,559 25,668	1,014,681 66,902 20,071	4,583,624 302,217 90,665	395 26 8
TOTAL RESIDENT ENG. COSTS	3530 3539	from 35 Geotech. Er Geotech. Er TOTAL DET	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency	1,429,400 94,246 28,274	841,895 55,510 16,653	1,297,648 85,559 25,668	1,014,681 66,902 20,071	4,583,624 302,217 90,665	395 26 8
TOTAL RESIDENT ENG. COSTS 1,423,189 836,711 1,292,096 1,007,165 4,559,161 393    PART 1	3530 3539	from 35 Geotech. Er Geotech. Er TOTAL DET	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency	1,429,400 94,246 28,274	841,895 55,510 16,653	1,297,648 85,559 25,668	1,014,681 66,902 20,071	4,583,624 302,217 90,665	395 26 8
PART 1 SUMMARY  CONSTRUCTION 12,147,842 7,116,614 11,034,129 8,587,182 38,885,766 3352 26,6135 399,730 310,066 1,407,267 121 2026 Project Man printing costs wages 441,335 256,135 399,730 310,066 1,407,267 121 2010 Client - office costs - expenses 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	3530 3539	from 3: Geotech. Er Geotech. Er TOTAL DET	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING	1,429,400 94,246 28,274 1,551,920	841,895 55,510 16,653 914,058	1,297,648 85,559 25,668 1,408,875	1,014,681 66,902 20,071 1,101,653	4,583,624 302,217 90,665 4,976,506	395 26 8
PART 1 SUMMARY  CONSTRUCTION 12,147,842 7,116,614 11,034,129 8,587,182 8,885,766 3352 26,7028 1,640,145 2,631,870 2,013,368 9,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368	3530 3539	from 35 Geotech. Er Geotech. Er TOTAL DET	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870	1,429,400 94,246 28,274 1,551,920	841,895 55,510 16,653 914,058	1,297,648 85,559 25,668 1,408,875	1,014,681 66,902 20,071 1,101,653	4,583,624 302,217 90,665 4,976,506	395 26 8 429
PART 1 SUMMARY  CONSTRUCTION 12,147,842 7,116,614 11,034,129 8,587,182 8,885,766 3352 26,7028 1,640,145 2,631,870 2,013,368 9,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368 2,225,928 795 2,013,368	3530 3539	from 35 Geotech. Er Geotech. Er TOTAL DET	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870	1,429,400 94,246 28,274 1,551,920	841,895 55,510 16,653 914,058	1,297,648 85,559 25,668 1,408,875	1,014,681 66,902 20,071 1,101,653	4,583,624 302,217 90,665 4,976,506	395 26 8 429
PART 1   SUMMARY   CONSTRUCTION   12,147,842   7,116,614   11,034,129   8,587,182   38,885,766   3352   ENGINEERING & SUPERVISION   2,940,545   1,640,145   2,631,870   2,013,368   9,225,928   795	3530 3539	from 35 Geotech. Er Geotech. Er TOTAL DET	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870	1,429,400 94,246 28,274 1,551,920	841,895 55,510 16,653 914,058	1,297,648 85,559 25,668 1,408,875	1,014,681 66,902 20,071 1,101,653	4,583,624 302,217 90,665 4,976,506	395 26 8 429
PART 1   SUMMARY   CONSTRUCTION   12,147,842   7,116,614   11,034,129   8,587,182   38,885,766   3352   ENGINEERING & SUPERVISION   2,940,545   1,640,145   2,631,870   2,013,368   9,225,928   795	3530 3539	from 35 Geotech. Er Geotech. Er TOTAL DET	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870	1,429,400 94,246 28,274 1,551,920	841,895 55,510 16,653 914,058	1,297,648 85,559 25,668 1,408,875	1,014,681 66,902 20,071 1,101,653	4,583,624 302,217 90,665 4,976,506 4,559,161	395 26 8 429
CONSTRUCTION   12,147,842   7,116,614   11,034,129   8,587,182   38,885,766   3352	3530 3539	from 35 Geotech. Er Geotech. Er TOTAL DET	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870	1,429,400 94,246 28,274 1,551,920	841,895 55,510 16,653 914,058	1,297,648 85,559 25,668 1,408,875	1,014,681 66,902 20,071 1,101,653	4,583,624 302,217 90,665 4,976,506 4,559,161 4,559,161	395 26 8 429
ENGINEERING & SUPERVISION   2,940,545   1,640,145   2,631,870   2,013,368   9,225,928   795	3530 3539	from 35 Geotech. Er Geotech. Er TOTAL DET	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870	1,429,400 94,246 28,274 1,551,920	841,895 55,510 16,653 914,058	1,297,648 85,559 25,668 1,408,875	1,014,681 66,902 20,071 1,101,653	4,583,624 302,217 90,665 4,976,506 4,559,161 4,559,161	395 26 8 429
CONSTRUCTION COST TOTAL   19,614,903   11,383,787   17,765,799   13,780,714   62,545,203   5392	3530 3539	from 35 Geotech. Er Geotech. Er TOTAL DET	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870  SIDENT ENG. COSTS	1,429,400 94,246 28,274 1,551,920	841,895 55,510 16,653 914,058	1,297,648 85,559 25,668 1,408,875	1,014,681 66,902 20,071 1,101,653	4,583,624 302,217 90,665 4,976,506 4,559,161 4,559,161	395 26 8 429
CONSTRUCTION COST TOTAL   19,614,903   11,383,787   17,765,799   13,780,714   62,545,203   5392	3530 3539	from 35 Geotech. Er Geotech. Er TOTAL DET	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870  SIDENT ENG. COSTS  PART 1 SUMMARY  CONSTRUCTION	1,429,400 94,246 28,274 1,551,920 1,423,189 1,423,189	841,895 55,510 16,653 914,058 836,711 836,711	1,297,648 85,559 25,668 1,408,875 1,292,096 1,292,096	1,014,681 66,902 20,071 1,101,653 1,007,165 1,007,165	4,583,624 302,217 90,665 4,976,506 4,559,161 4,559,161	395 26 8 429 393 0
CONSTRUCTION COST TOTAL   19.614,903   11.383,787   17.765,799   13.780,714   62.545,203   5392	3530 3539	from 35 Geotech. Er Geotech. Er TOTAL DET	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870  SIDENT ENG. COSTS  PART 1 SUMMARY  CONSTRUCTION ENGINEERING & SUPERVISION	1,429,400 94,246 28,274 1,551,920 1,423,189 1,423,189	841,895 55,510 16,653 914,058 836,711 836,711	1,297,648 85,559 25,668 1,408,875 1,292,096 1,292,096	1,014,681 66,902 20,071 1,101,653 1,007,165 1,007,165	4,583,624 302,217 90,665 4,976,506 4,559,161 4,559,161 0 0	395 26 8 429 393 0
2000   PROJECT MANAGEMENT   2060   Project Man office costs wages   441,335   256,135   399,730   310,066   1,407,267   121   2062   Project Man office costs - expenses   0   0   0   0   0   0   0   0   0	3530 3539	from 35 Geotech. Er Geotech. Er TOTAL DET	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870  SIDENT ENG. COSTS  PART 1 SUMMARY  CONSTRUCTION ENGINEERING & SUPERVISION	1,429,400 94,246 28,274 1,551,920 1,423,189 1,423,189	841,895 55,510 16,653 914,058 836,711 836,711	1,297,648 85,559 25,668 1,408,875 1,292,096 1,292,096	1,014,681 66,902 20,071 1,101,653 1,007,165 1,007,165	4,583,624 302,217 90,665 4,976,506 4,559,161 4,559,161 0 0 38,885,766 9,225,928 14,433,508	395 26 8 429 393 0 3352 795 1244
PROJECT MANAGEMENT   Project Man office costs wages   41,335   256,135   399,730   310,066   1,407,267   121	3530 3539	from 35 Geotech. Er Geotech. Er TOTAL DET	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870  SIDENT ENG. COSTS  PART 1 SUMMARY  CONSTRUCTION ENGINEERING & SUPERVISION	1,429,400 94,246 28,274 1,551,920 1,423,189 1,423,189	841,895 55,510 16,653 914,058 836,711 836,711	1,297,648 85,559 25,668 1,408,875 1,292,096 1,292,096	1,014,681 66,902 20,071 1,101,653 1,007,165 1,007,165	4,583,624 302,217 90,665 4,976,506 4,559,161 4,559,161 0 0 38,885,766 9,225,928 14,433,508	395 26 8 429 393 0 3352 795 1244
2060   Project Man office costs wages   441,335   256,135   399,730   310,066   1,407,267   121     2062   Project Man office costs - expenses   0   0   0   0   0   0     2063   Project Man printing costs   0   0   0   0   0   0     2061   Project Man general   0   0   0   0   0   0     2061   Project Man general   0   0   0   0   0   0     2061   Project Man general   0   0   0   0   0   0     2061   Project Man general   0   0   0   0   0   0     2061   Project Man general   0   0   0   0   0     2061   Client   - office costs wages   392,298   227,676   355,316   275,614   1,250,904   108     2012   Client   - office costs - expenses   0   0   0   0   0     2030   Client   - printing costs   0   0   0   0     2031   Client   - general   0   0   0   0     2031   Client   - general   0   0   0   0     2032   Client   - general   0   0   0   0     2033   Client   - general   0   0   0   0     2034   Client   - general   0   0   0   0     2035   Client   - general   0   0   0   0     2036   Client   - general   0   0   0   0     2037   Client   - general   0   0   0   0     2038   Client   - general   0   0   0   0     2039   Client   - general   0   0   0   0     2039   Client   - general   0   0   0   0     2030   Client   - general   0   0   0     2030   Client   - general   0   0   0   0   0     2030   Client   - general   0   0   0   0   0     2030   Client   - general   0   0   0   0   0     2030   Client   - general   0   0   0   0   0   0     2030   Client   - general   0   0   0	3530 3539	from 3: Geotech. Er Geotech. Er TOTAL DET	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870  SIDENT ENG. COSTS  PART 1 SUMMARY	1,429,400 94,246 28,274 1,551,920 1,423,189 1,423,189 12,147,842 2,940,545 4,526,516	841,895 55,510 16,653 914,058 836,711 836,711 7,116,614 1,640,145 2,627,028	1,297,648 85,559 25,668 1,408,875 1,292,096 1,292,096 1,292,096	1,014,681 66,902 20,071 1,101,653 1,007,165 1,007,165 8,587,182 2,013,368 3,180,165	4,583,624 302,217 90,665 4,976,506 4,559,161 4,559,161 0 0 38,885,766 9,225,928 14,433,508	395 26 8 429 393 0 0 3352 795 1244
2062   Project Man office costs - expenses   0   0   0   0   0   0   0   0   0	3500 3530 3539 	from 38 Geotech. Er Geotech Er TOTAL DET from 6810 TOTAL RES	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870  SIDENT ENG. COSTS  PART 1 SUMMARY  CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY	1,429,400 94,246 28,274 1,551,920 1,423,189 1,423,189 12,147,842 2,940,545 4,526,516	841,895 55,510 16,653 914,058 836,711 836,711 7,116,614 1,640,145 2,627,028	1,297,648 85,559 25,668 1,408,875 1,292,096 1,292,096 1,292,096	1,014,681 66,902 20,071 1,101,653 1,007,165 1,007,165 8,587,182 2,013,368 3,180,165	4,583,624 302,217 90,665 4,976,506 4,559,161 4,559,161 0 0 38,885,766 9,225,928 14,433,508 0	395 26 8 429 393 0 0 3352 795 1244
2063   Project Man printing costs   0   0   0   0   0   0   0   0   0	3500 3539 	from 3: Geotech. Er Geotech Er TOTAL DET from 6810 TOTAL RES	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870  SIDENT ENG. COSTS  PART 1 SUMMARY	1,429,400 94,246 28,274 1,551,920 1,423,189 1,423,189 12,147,842 2,940,545 4,526,516	841,895 55,510 16,653 914,058 836,711 836,711 7,116,614 1,640,145 2,627,028	1,297,648 85,559 25,668 1,408,875 1,292,096 1,292,096 1,292,096 11,034,129 2,631,870 4,099,800	1,014,681 66,902 20,071 1,101,653 1,007,165 1,007,165 8,587,182 2,013,368 3,180,165 13,780,714	4,583,624 302,217 90,665 4,976,506 4,559,161 4,559,161 0 0 38,885,766 9,225,928 14,433,508 0	395 26 8 429 393 0 0 3352 795 1244 0
Project Man general   0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	3500 3530 3539 	from 3: Geotech. Er Geotech. Er TOTAL DET from 6810 TOTAL RES CONSTRUC	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870  SIDENT ENG. COSTS  PART 1 SUMMARY  CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY  CTION COST TOTAL  PROJECT MANAGEMENT - office costs wages	1,429,400 94,246 28,274 1,551,920 1,423,189 1,423,189 12,147,842 2,940,545 4,526,516	841,895 55,510 16,653 914,058 836,711 836,711 7,116,614 1,640,145 2,627,028	1,297,648 85,559 25,668 1,408,875 1,292,096 1,292,096 1,292,096 1,292,096 1,292,096 1,7,765,799 1,7,765,799	1,014,681 66,902 20,071 1,101,653 1,007,165 1,007,165 2,013,368 3,180,165 13,780,714	4,583,624 302,217 90,665 4,976,506 4,559,161 4,559,161 0 0 38,885,766 9,225,928 14,433,508 0 62,545,203	395 26 8 429 393 0 0 3352 795 1244 0 5392
Project Manager Sub-total         441,335         256,135         399,730         310,066         1,407,267         121           2010 Client         - office costs wages         392,298         227,676         355,316         275,614         1,250,904         108           2012 Client         - office costs - expenses         0         0         0         0         0         0           2030 Client         - printing costs         0         0         0         0         0         0           2011 Client         - general         0         0         0         0         0         0	3500 3530 3539 	from 38 Geotech. Er Geotech Er TOTAL DET from 6810 TOTAL RES CONSTRUC	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870  SIDENT ENG. COSTS  PART 1 SUMMARY CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY  CONTRACTUAL CONTINGENCY  CONTRACTUAL CONTINGENCY  CONTRACTOR  PROJECT MANAGEMENT - office costs wages - office costs wages - office costs - expenses	1,429,400 94,246 28,274 1,551,920 1,423,189 1,423,189 12,147,842 2,940,545 4,526,516 19,614,903	841,895 55,510 16,653 914,058 836,711 836,711 7,116,614 1,640,145 2,627,028 11,383,787	1,297,648 85,559 25,668 1,408,875 1,292,096 1,292,096 1,292,096 11,034,129 2,631,870 4,099,800 17,765,799	1,014,681 66,902 20,071 1,101,653 1,007,165 1,007,165 2,013,368 3,180,165 13,780,714	4,583,624 302,217 90,665 4,976,506 4,559,161 4,559,161 0 0 38,885,766 9,225,928 14,433,508 0 62,545,203	395 26 8 429 393 0 0 3352 795 1244 0 5392
2010         Client         - office costs wages         392,298         227,676         355,316         275,614         1,250,904         108           2012         Client         - office costs - expenses         0         0         0         0         0         0           2030         Client         - printing costs         0         0         0         0         0         0           2011         Client         - general         0         0         0         0         0         0	3500 3530 3539  6800  2000 2060 2062 2062 2063	from 38 Geotech. Er Geotech Er TOTAL DET from 6810  TOTAL RES CONSTRUC	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870  SIDENT ENG. COSTS  PART 1 SUMMARY  CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY  CTION COST TOTAL  PROJECT MANAGEMENT 1- office costs wages 1- office costs wages 1- office costs wages 1- printing costs	1,429,400 94,246 28,274 1,551,920 1,423,189 1,423,189 12,147,842 2,940,545 4,526,516 19,614,903 441,335 0 0	841,895 55,510 16,653 914,058 836,711 836,711 7,116,614 1,640,145 2,627,028 11,383,787 256,135 0	1,297,648 85,559 25,668 1,408,875 1,292,096 1,292,096 1,292,096 2,631,870 4,099,800 17,765,799	1,014,681 66,902 20,071 1,101,653 1,007,165 1,007,165 2,013,368 3,180,165 13,780,714	4,583,624 302,217 90,665 4,976,506 4,559,161 4,559,161 0 0 38,885,766 9,225,928 14,433,508 0 62,545,203	395 26 8 429 393 0 0 3352 795 1244 0 5392
2012 Client         - office costs - expenses         0         0         0         0         0         0           2030 Client         - printing costs         0         0         0         0         0         0         0           2011 Client         - general         0         0         0         0         0         0         0	3500 3530 3539  6800  2000 2060 2062 2062 2063	from 3: Geotech. Er Geotech. Er TOTAL DET from 6810 TOTAL RES CONSTRUC Project Man Project Man Project Man Project Man	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870  SIDENT ENG. COSTS  PART 1 SUMMARY  CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY  CTION COST TOTAL  PROJECT MANAGEMENT - office costs wages - printing costs - general	1,429,400 94,246 28,274 1,551,920 1,423,189 1,423,189 12,147,842 2,940,545 4,526,516 19,614,903	841,895 55,510 16,653 914,058 836,711 836,711 7,116,614 1,640,145 2,627,028 11,383,787 256,135 0	1,297,648 85,559 25,668 1,408,875 1,292,096 1,292,096 1,292,096 11,7765,799 399,730 0	1,014,681 66,902 20,071 1,101,653 1,007,165 1,007,165 2,013,368 3,180,165 13,780,714 310,066 0	4,583,624 302,217 90,665 4,976,506 4,559,161 4,559,161 0 0 38,885,766 9,225,928 14,433,508 0 62,545,203	395 26 8 429 393 0 3352 795 1244 0 5392
2030 Client         - printing costs         0 </td <td>3500 3530 3539 </td> <td>from 38 Geotech. Er Geotech Er TOTAL DET from 6810  TOTAL RES CONSTRUC</td> <td>DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870  SIDENT ENG. COSTS  PART 1 SUMMARY  CONSTRUCTION ENGINEERING &amp; SUPERVISION CONTRACTUAL CONTINGENCY  STION COST TOTAL  PROJECT MANAGEMENT - office costs - expenses - printing costs - general ager Sub-total</td> <td>1,429,400 94,246 28,274 1,551,920 1,423,189 1,423,189 12,147,842 2,940,545 4,526,516 19,614,903 441,335 0 0 0 441,335</td> <td>841,895 55,510 16,653 914,058 836,711 836,711 7,116,614 1,640,145 2,627,028 11,383,787 256,135 0 0 0 256,135</td> <td>1,297,648 85,559 25,668 1,408,875 1,292,096 1,292,096 1,292,096 2,631,870 4,099,800 17,765,799 399,730 0 0 399,730</td> <td>1,014,681 66,902 20,071 1,101,653 1,007,165 1,007,165 1,007,165 2,013,368 3,180,165 13,780,714 310,066 0 0 0 310,066</td> <td>4,583,624 302,217 90,665 4,976,506 4,559,161 4,559,161 0 0 38,885,766 9,225,928 14,433,508 0 62,545,203 1,407,267 0 0</td> <td>395 26 8 429 393 0 3352 795 1244 0 0 0 0 121</td>	3500 3530 3539 	from 38 Geotech. Er Geotech Er TOTAL DET from 6810  TOTAL RES CONSTRUC	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870  SIDENT ENG. COSTS  PART 1 SUMMARY  CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY  STION COST TOTAL  PROJECT MANAGEMENT - office costs - expenses - printing costs - general ager Sub-total	1,429,400 94,246 28,274 1,551,920 1,423,189 1,423,189 12,147,842 2,940,545 4,526,516 19,614,903 441,335 0 0 0 441,335	841,895 55,510 16,653 914,058 836,711 836,711 7,116,614 1,640,145 2,627,028 11,383,787 256,135 0 0 0 256,135	1,297,648 85,559 25,668 1,408,875 1,292,096 1,292,096 1,292,096 2,631,870 4,099,800 17,765,799 399,730 0 0 399,730	1,014,681 66,902 20,071 1,101,653 1,007,165 1,007,165 1,007,165 2,013,368 3,180,165 13,780,714 310,066 0 0 0 310,066	4,583,624 302,217 90,665 4,976,506 4,559,161 4,559,161 0 0 38,885,766 9,225,928 14,433,508 0 62,545,203 1,407,267 0 0	395 26 8 429 393 0 3352 795 1244 0 0 0 0 121
2011 Client - general 0 0 0 0 0 0	3500 3530 3539 6800 	from 38 Geotech. Er Geotech Er TOTAL DET from 6810 TOTAL RES CONSTRUC Project Man Project Man Project Man Project Man Project Man Client	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870  SIDENT ENG. COSTS  PART 1 SUMMARY CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY  TION COST TOTAL  PROJECT MANAGEMENT - office costs wages - printing costs - general ager Sub-total - office costs wages	1,429,400 94,246 28,274 1,551,920 1,423,189 1,423,189 1,21,47,842 2,940,545 4,526,516 19,614,903 441,335 0 0 0 441,335	841,895 55,510 16,653 914,058 836,711 836,711 7,116,614 1,640,145 2,627,028 11,383,787 256,135 0 0 256,135	1,297,648 85,559 25,668 1,408,875 1,292,096 1,292,096 1,292,096 2,631,870 4,099,800 17,765,799 399,730 0 0 399,730	1,014,681 66,902 20,071 1,101,653 1,007,165 1,007,165 2,013,368 3,180,165 13,780,714 310,066 0 0 310,066	4,583,624 302,217 90,665 4,976,506 4,559,161 4,559,161 0 0 38,885,766 9,225,928 14,433,508 0 62,545,203 1,407,267 0 1,407,267	395 26 8 429 393 0 0 3352 795 1244 0 0 5392
golotal of the state of the sta	3500 3530 3539 	from 38 Geotech. Er Geotech Er TOTAL DET from 6810  TOTAL RES CONSTRUC Project Man Project Man Project Man Project Man Project Man Client Client	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870  SIDENT ENG. COSTS  PART 1 SUMMARY  CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY  CTION COST TOTAL  PROJECT MANAGEMENT - office costs wages - office costs wages - general ager Sub-total  - office costs wages - office costs - expenses	1,429,400 94,246 28,274 1,551,920 1,423,189 1,423,189 12,147,842 2,940,545 4,526,516 19,614,903 441,335 0 0 0 441,335 392,298	841,895 55,510 16,653 914,058 836,711 836,711 7,116,614 1,640,145 2,627,028 11,383,787 256,135 0 0 0 256,135	1,297,648 85,559 25,668 1,408,875 1,292,096 1,292,096 1,292,096 2,631,870 4,099,800 17,765,799 399,730 0 0 399,730 355,316	1,014,681 66,902 20,071 1,101,653 1,007,165 1,007,165 2,013,368 3,180,165 13,780,714 310,066 0 0 310,066 275,614	4,583,624 302,217 90,665 4,976,506 4,559,161 4,559,161 0 0 38,885,766 9,225,928 14,433,508 0 62,545,203 1,407,267 0 0 1,407,267 1,250,904	395 26 8 429 393 0 0 3352 795 1244 0 0 0 0 0 1211 108
	3500 3530 3539 6800 	from 38 Geotech. Er Geotech. Er TOTAL DET from 6810 TOTAL RES Froject Man Project Man Proj	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870  SIDENT ENG. COSTS  PART 1 SUMMARY  CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY  CTION COST TOTAL  PROJECT MANAGEMENT - office costs wages - printing costs - general ager Sub-total  office costs wages	1,429,400 94,246 28,274 1,551,920 1,423,189 1,423,189 12,147,842 2,940,545 4,526,516 19,614,903 441,335 0 0 0 441,335 392,298 0	841,895 55,510 16,653 914,058 836,711 836,711 7,116,614 1,640,145 2,627,028 11,383,787 256,135 0 0 256,135	1,297,648 85,559 25,668 1,408,875 1,292,096 1,292,096 1,292,096 1,292,096 1,292,096 1,7765,799 399,730 0 0 0 399,730 355,316 0 0	1,014,681 66,902 20,071 1,101,653 1,007,165 1,007,165 1,007,165 2,013,368 3,180,165 13,780,714 310,066 0 0 310,066 275,614 0	4,583,624 302,217 90,665 4,976,506 4,976,506 4,559,161 4,559,161 0 0 38,885,766 9,225,928 14,433,508 0 62,545,203 1,407,267 0 0 1,407,267	395 26 8 429 393 0 0 3352 795 1244 0 0 5392 121 108 0 0
	3500 3530 3539 6800 	from 38 Geotech. Er Geotech Er TOTAL DET from 6810 TOTAL RES CONSTRUC Project Man Project Man Project Man Project Man Client Client Client	DETAILED DESIGN 510,3520,3540,3550,3570 1- detailed design 1- Contingency  FAILED DESIGN COSTS  RESIDENT ENGINEERING 0,6820,6840,6850,6860,6870  SIDENT ENG. COSTS  PART 1 SUMMARY  CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY  CTION COST TOTAL  PROJECT MANAGEMENT - office costs wages - printing costs - general ager Sub-total  - office costs wages - office costs - expenses - printing costs - general - office costs - expenses - printing costs - general - office costs - expenses - printing costs - general	1,429,400 94,246 28,274 1,551,920 1,423,189 1,423,189 2,940,545 4,526,516 19,614,903 441,335 392,298 0 0	841,895 55,510 16,653 914,058 836,711 836,711 7,116,614 1,640,145 2,627,028 11,383,787 256,135 0 0 0 256,135 227,676 0 0	1,297,648 85,559 25,668 1,408,875 1,292,096 1,292,096 1,292,096 2,631,870 4,099,800 17,765,799 399,730 0 0 399,730 355,316 0 0	1,014,681 66,902 20,071 1,101,653 1,007,165 1,007,165 1,007,165 2,013,368 3,180,165 13,780,714 310,066 0 0 310,066 275,614 0	4,583,624 302,217 90,665 4,976,506 4,976,506 4,559,161 4,559,161 0 0 38,885,766 9,225,928 14,433,508 1,407,267 0 0 1,407,267 1,250,904 0 0	395 26 8 429 393 0 0 3352 795 1244 0 0 0 0 121 1 108 0 0 0

ACTI COD Co		12+800 to 8+800 East of 248 St Overpass to 72 Ave Section W.12	14+600 to 12+800 West of 264 St IC to east of 248 St overpass Section W.11	12+200 to 8+800 Just east of 248 St Overpass to east of 232 St IC Section E.14	14+600 to 12+200 West of 264 St IC to east of 248 St Overpass Section E.13 M		Total Line Cost C/LM
	n Sept.1, 200 DESCRIPTION \Length	4000	1800	3400	2400 T		11600
2072 2073	Public Rel wages & expenses Public Rel adv., media, displays Public Rel opening ceremonies Public Rel general Public Relations Sub-total	MR 117,689 0 0 0 117,689	MR 68,303 0 0 0 68,303	MR 106,595 0 0 0 106,595	MR 82,684 0 0 0 82,684	375,271 0 0 0 0 375,271	32 0 0 0 32
	Legal Costs - lawyers fees Legal Costs - general	13,730 0	7,969 0	12,436 0	9,646 0	43,782 0	4 0
	Legal Costs Sub-total	13,730	7,969	12,436	9,646	43,782	4
	Insurance - const./ liability, E&O Insurance - general Legal Costs Sub-total	117,689 0 117,689	68,303 0 68,303	106,595 0 106,595	82,684 0 82,684	375,271 0 375,271	32 0 32
2099	Project Management Contingency	324,823	188.516	294,202	228,209	1,035,749	89
	TOTAL PROJECT MANAGEMENT COSTS	1,407,565	816,901	1,274,874	988,904	4,488,244	387
4000 4010	LAND Land(Code - Mrkt,ROW,Serv,Imp.V,Ease.C,T Acquisition Sub-total	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0
4030 4040 4050 4060 4070 4080	Land(Code 4-Bus.,5%,Mrg.P,Rel\$,P/Tax,Etc Land(Code 4-Owners(LS,ApprsI,Rprt,LgI,In Land(Code 4-Demolition Land(Code 4-Pro.Man,P.Tax,Util,Security Land(Code 4-Not Used Land(Code 4-Not Used Land(Code 4-Not Used Land(Code 4-Xet,IMSaI,TrvIV,Cntr.S,Appr. Land(Code 4-Surveys	0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
	Associated costs-sub-total	0	0	0	0	0 0 0	0 0 0
4099	Land Contingency Sub-total	0	0	0	0	0	0
	TOTAL LAND COSTS	0	0	0	0	0	0
9800	MANAGEMENT RESERVE MAN. RES planning MAN. RES preliminary design MAN. RES trilling construction MAN. RES grade construction	0 0 0 0	0 0 0 0	0 0 0	0 0 0 0	0 0 0	0 0 0 0
	MAN. RES structural construction MAN. RES paving construction MAN. RES operation construction MAN. RES roadside construction MAN. RES other construction MAN. RES project management	0 0 0 0	0 0 0 0	0 0 0 0	0 0 0 0	0 0 0 0	0 0 0 0 0
	MAN. RES land MAN. RES detailed eng. MAN. RES residency eng. MAN. RES risk contingency	0 0 0 0	0 0 0	0 0 0 0	0 0 0 0	0 0 0	0 0 0 0
	TOTAL MANAGEMENT RESERVE	0	0	0	0	0	0
9900	TOTAL LESS ESCALATION FISCAL ESCALATION YEAR PROJECTED ESCALATION 2006-2007 2007-2008 2008-2009 2009-2010 2010-2011 2011-2012	0 0 0 0	0 0 0 0 0	0 0 0 0 0 0 0 0	0 0 0 0	0 0 0 0 0	0 0 0 0 0
	2012-2013 2013-2014	0	0	0	0	0	0

	Q:\SW\1200 - Mo	T A&W Contract #15\SWF - Highwa	y 1 Functional							1
File:	Planning\Data\Co:	sting\March 29th\[Package 4 - Between	en 232 and	12+800	14+600	12+200	14+600			Total
	Parsons Hv	vy 1 Widening		to 8+800	to 12+800	to 8+800	to 12+200			Line
(	(2016Dollars) Pa	ckage 4 - Btw 232 and 264		East of 248 St	West of 264 St	Just east of 248	West of 264 St IC			Cost
ACTI	VITY ES	ST.DATE April 4, 2016		Overpass to 72	IC to east of 248	St Overpass to east	to east of 248			1
COD	DE R3	B DATE: Sept 15, 2016		Ave	St overpass	of 232 St IC	St Overpass			C/LM
Co	nceptual Est.		Divison\site	Section W.12	Section W.11	Section E.14	Section E.13	MR	11600	1
Blk Es	st. # 6.14A		Road Type	16	16	16	16	OR	0	1
Version	on Sept.1, 200	DESCRIP	ΓION \Length	4000	1800	3400	2400	TR	11600	11600
				MR	MR	MR	MR	.		
	2014-2015			0	0	0	0		0	0
	TOTAL ESCAL	ATION		0	0	0	0		0	0
====										
		IARY NON-CONSTRUCTION C	OSTS							
		n-Construction		1,082,743	628,385	980,672	760,695		3,452,495	298
	No	n-Const. Contingency		324,823	188,516	294,202	228,209		1,035,749	89
	TC	TAL NON-CONSTRUCTION C	OSTS	1,407,565	816,901	1,274,874	988,904		4,488,244	387
====										
	DIVISION TOTAL	AL FOR ROAD TYPE		21,022,469	12,200,688	19.040.673	14,769,618		67.033.447	5779



# PACKAGE 5 - SECTIONS

ID	Chainage Start	Chainage End	Description
W.9	16+500	19+800	Highway 1 Westbound Lanes
W.8	19+800	21+200	Highway 1 Westbound Lanes
W.7	21+200	22+400	Highway 1 Westbound Lanes
W.6	22+400	24+400	Highway 1 Westbound Lanes
W.5	24+400	25+400	Highway 1 Westbound Lanes
W.4	25+400	26+300	Highway 1 Westbound Lanes
E.11	16+500	18+600	Highway 1 Eastbound Lanes
E.10	18+600	21+600	Highway 1 Eastbound Lanes
E.9	21+600	24+400	Highway 1 Eastbound Lanes
E.8	24+400	26+300	Highway 1 Eastbound Lanes



Divison\site Road Type DESCRIPTION \Length  Engineering Land Construction Management Reserve Escalation Total  SUMMARY Construct.Cost ONLY Per L.M. Land Area  Mobilization Land Cont. Construction Cont. Engineering Cont.	264 St IC Section W.9  16 3300 MR  3.588,003 0 16.856,864 0 20,444,866  5,108 11.0  344,653 0 3,569,424 828,001 320,622	Rest stop Section W.8 16 1400 MR 1.693,293 0 8.148,252 0 9.841,545 5.820 6.8 167,285 0 1,723,038	Stop Off-Ramp Section W.7 16 1200 MR 1,983,651 0 9,413,839 0 0 11,397,490	east of Bradner Section W.6 16 2000 MR 2,104,970 0 9,811,434 0 0 11,916,404	of automall W tip Section W.5 16 1000 MR 1,182,300 0 5,697,212 0 0	WB on ramp Section W.4 16 900 MR 738,293 0 3,161,976 0 0	264 St IC Section E.11 16 2100 MR 2,397,930 0 11,420,367 0	East of 275 St Section E.10 16 3000 MR 3,791,702 0 17,728,893 0	Bradner Section E.9 16 3000 MR 2,807,649 0 12,627,081	1900 MR 1,954,418 ( 9,060,339	0	19800 0 19800 22,242,209 0	19800 1123
Road Type DESCRIPTION \(\text{Length}\)  Engineering Land Construction Management Reserve Escalation Total  SUMMARY Onstruct.Cost ONLY Per L.M. Land Area  Mobilization Land Cont. Construction Cont. Engineering Cont.	16 3300 MR 3,588,003 0 16,856,864 0 20,444,866 5,108 11.0 344,653 0 3,569,424 828,001	16 1400 MR 1,693,293 0 8,148,252 0 9,841,545 5,820 6.8	16 1200 MR 1,963,651 1,963,651 0 9,413,839 0 0 11,397,490 7,845 3.8	16 2000 MR 2,104,970 9,811,434 0 11,916,404	16 1000 MR 1,182,300 0 5,697,212 0	16 900 MR 738,293 0 3,161,976 0	16 2100 MR 2,397,930 0 11,420,367 0	16 3000 MR 3,791,702 0 17,728,893	16 3000 MR 2,807,649 0 12,627,081	1900 MR 1,954,418 9,060,339	6 OR 0 TR 8	0 19800 22,242,209 0	1123
DESCRIPTION \Length  Engineering Land Construction Management Reserve Escalation Total  SUMMARY Construct.Cost ONLY Per L.M. Land Area  Mobilization Land Cont. Construction Cont. Engineering Cont.	3300 MR 3,588,003 0 16,856,864 0 0 20,444,866 5,108 11.0 344,653 0 3,569,424 828,001	1400 MR 1,693,293 0 8,148,252 0 0 9,841,545 5,820 6.8 167,285 0	1200 MR 1,983,651 0 9,413,839 0 0 11,397,490 7,845 3.8	2000 MR 2,104,970 0 9,811,434 0 0 11,916,404	1000 MR 1,182,300 0 5,697,212 0	900 MR 738,293 0 3,161,976 0	2100 MR 2,397,930 0 11,420,367 0	3000 MR 3,791,702 0 17,728,893	3000 MR 2,807,649 0 12,627,081	1900 MR 1,954,418 ( 9,060,339	0 TR 8 0	22,242,209	1123
Land Construction Management Reserve Escalation Total SUMMARY Construct.Cost ONLY Per L.M. Land Area Mobilization Land Cont. Construction Cont. Engineering Cont.	3,588,003 0 16,856,864 0 0 20,444,866 5,108 11.0 344,653 0 3,569,424 828,001	1,693,293 0 8,148,252 0 9,841,545 5,820 6.8 167,285	1,983,651 0 9,413,839 0 0 11,397,490 7,845 3.8	2,104,970 0 9,811,434 0 0 11,916,404	1,182,300 0 5,697,212 0 0	738,293 0 3,161,976 0 0	2,397,930 0 11,420,367 0	3,791,702 0 17,728,893	2,807,649 0 12,627,081	1,954,418 9,060,339	0	0	
Land Construction Management Reserve Escalation Total SUMMARY Construct.Cost ONLY Per L.M. Land Area Mobilization Land Cont. Construction Cont. Engineering Cont.	5,108 11.0 344,653 0 3,569,424 828,001	0 8,148,252 0 9,841,545 5,820 6.8 167,285	9,413,839 0 0 11,397,490 7,845 3.8	9,811,434 0 0 11,916,404 4,906	5,697,212 0 0	3,161,976 0 0	0 11,420,367 0	0 17,728,893	0 12,627,081	9,060,339	0	0	
Construction Management Reserve Escalation Total SUMMARY Construct.Cost ONLY Per L.M. Land Area Mobilization Land Cont. Construction Cont. Engineering Cont.	16,856,864 0 0 20,444,866 5,108 11.0 344,653 0 3,569,424 828,001	8,148,252 0 0 9,841,545 5,820 6.8 167,285	9,413,839 0 0 11,397,490 7,845 3.8	9,811,434 0 0 11,916,404 4,906	5,697,212 0 0	3,161,976 0 0	11,420,367 0	17,728,893	12,627,081	9,060,339		·	
Escalation Total SUMMARY Construct.Cost ONLY Per L.M. Land Area Mobilization Land Cont. Construction Cont. Engineering Cont.	0 20,444,866 5,108 11.0 344,653 0 3,569,424 828,001	9,841,545 5,820 6.8 167,285	7,845 3.8	11,916,404	0	0		0	n			103,926,257	5249
SUMMARY Construct.Cost ONLY Per L.M. Land Area  Mobilization Land Cont. Construction Cont. Engineering Cont.	20,444,866 5,108 11.0 344,653 0 3,569,424 828,001	9,841,545 5,820 6.8 167,285	11,397,490 7,845 3.8	11,916,404						(	-	0	0
SUMMARY Construct.Cost ONLY Per L.M. Land Area  Mobilization Land Cont. Construction Cont. Engineering Cont.	5,108 11.0 344,653 0 3,569,424 828,001	5,820 6.8 167,285	7,845 3.8	4,906	0,078,312		13.818,297	21,520,595	15,434,730	11,014,757		126,168,465	6372
Construct.Cost ONLY Per L.M. Land Area  Mobilization Land Cont. Construction Cont. Engineering Cont.	11.0 344,653 0 3,569,424 828,001	6.8 167,285 0	3.8			3,900,268	13,010,257	21,320,353	10,434,730	11,014,75		120,100,403	0372
Mobilization Land Cont. Construction Cont. Engineering Cont.	344,653 0 3,569,424 828,001	167,285 0		6.6	5,697 3.3	3,513 2.5	5,438 6.9	5,910 9.5	4,209 10.1	4,769 6.1	\$/LM	5,249 66.6	
Land Cont. Construction Cont. Engineering Cont.	0 3,569,424 828,001	0											
Construction Cont. Engineering Cont.	3,569,424 828,001		191,334	200,306	115,602	64,956	233,058	361,633	258,179	184,661		2,121,666	
Engineering Cont.	828,001		0 2,000,742	0 2,078,150	0 1,207,205	0 669,042	0 2,418,494	0 3,760,815	0 2,674,246	0 1,918,505		22,019,663	23,982,982
		390,760	457,766	485,762	272,839	170,375	553,368	875,008	647,919	451,020		5,132,817	LU,00E,00E
Supervision Cont.		157,328	171,682	186,027	107,536	60,644	216,975	330,468	239,695	172,342		1,963,320	
Total Cont.	4,718,046	2,271,126	2,630,190	2,749,939	1,587,580	900,062	3,188,838	4,966,291	3,561,861	2,541,867		29,115,800	
S.G.S.B. C.B.C.	15,444	12,259	5,561 2,988	9,357	4,663 2,488	4,056	9,801	13,866	14,075	8,805	m3	97,886	
Asphalt	8,205 11,326	6,247 6,765	4,128	4,973 7,797	3,901	2,250 3,116	5,223 7,212	7,473 10.327	7,456 10,291	4,731 6,321	m3 t	52,033 71,184	
Concrete Barrier	220	1,155	205	140	105	415	200	595	120	325	lm	3,480	
Noise Attentuation Wall	0	0	0	0	0	0	0	0	0	0	m2	0	
No. of Light Poles Sidewalk	0	31	0	0	0	0	0	0	0	16	ea Im	47	
Curb and Gutter	0	0	0	0	0	0	0	0	0	0	lm	"	
Signals	ō	ō	ō	0	0	Ö	0	ō	ō	ō	ea	0	
Bridge total area	0	0	279	0	0	0	0	279	0	0	m2	558	
Total Rock	0	0	0	0	0	0	0	0	0	0			ENG 0
Total OM	78,840	32,140	21,630	49,970	23,130	14.080	54,430	58,530	75,710	35,970	m3 m3	444.430	0
Total Stripping	7,500	2,335	3,200	3,600	1,400	2,800	4,400	9,200	0	5,900	m3	40,335	0
Total Borrow	0	0	0	0	0	0	0	0	0	0	m3	0	
Total Cut/Excavation	86,340	34,475	24,830	53,570	24,530	16,880	58,830	67,730	75,710	41,870	m3	484,765	0
Surplus or Deficit	21,998	6,047	6,039	13,113	6,705	5,415	23,836	12,277	29,538	6,082	m3	131,048	
ENG & PM	3.588 0.000	1.693 0.000	1.984 0.000	2.105 0.000	1.182 0.000	0.738 0.000	2.398 0.000	3.792 0.000	2.808 0.000	1.954 0.000		22.242	22.242 0.000
	16.857	8.148	4.408	9.811	5.697	3.162	11.420	12.842	12.627	9.060		94.033	94.032
CONST.													9.893
CONST. BRIDGES-R/W	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000		0.000	0.000
CONST.		9.841	11.398	11.916	6.879	3.900	13.818	21.521	15.435	11.014		126.168	126.167
CONST. BRIDGES-R/W MANAGEMENT RESERVE	20.445	\$ 7,030	\$ 9,498	\$ 5,958	\$ 6,880	\$ 4,334	\$ 6,580	\$ 7,174	\$ 5,145	\$ 5,79	7	\$ 6,372	
CONST. BRIDGES-R/W MANAGEMENT RESERVE ESCALATION (Millions) (2016Dollars)						\$ 3.513						\$ 5,249	
	ENG & PM LAND CONST. BRIDGES-R/W IANAGEMENT RESERVE ESCALATION	Surplus or Deficit   21,998	Surplus or Deficit   21,998   6,047	Surplus or Deficit   21,998   6,047   6,039	Surplus or Deficit   21,998   6,047   6,039   13,113	Surplus or Deficit   21,998   6,047   6,039   13,113   6,705	Surplus or Deficit   21,998   6,047   6,039   13,113   6,705   5,415	Surplus or Deficit         21,998         6,047         6,039         13,113         6,705         5,415         23,836           ENG & PM LAND         3.588 LAND         1.693 0.000         1.984 0.000         2.105 0.000         1.182 0.000         0.738 0.000         2.398 0.000           CONST. BRIDGES-R/W 0.000         16.857 0.000         8.148 0.000         4.408 0.000         9.811 0.000         5.697 0.000         3.162 0.000         11.420 0.000           IANAGEMENT RESERVE         0.000 0.000         0.000 0.000         0.000 0.000         0.000 0.000         0.000 0.000         0.000 0.000         0.000 0.000         0.000 0.000           IIIIIons)         (2016Dollars)         20.445         9.841         11.398         11.916         6.879         3.900         13.818           TOTAL Cost per meter         6,195         7,030         9,498         5,958         6,880         4,334         6,580	Surplus or Deficit   21,998   6,047   6,039   13,113   6,705   5,415   23,836   12,277	Surplus or Deficit   21,998   6,047   6,039   13,113   6,705   5,415   23,836   12,277   29,538	Surplus or Deficit 21,998 6,047 6,039 13,113 6,705 5,415 23,836 12,277 29,538 6,082  ENG & PM 3.588 1.693 1.984 2.105 1.182 0.738 2.398 3.792 2.808 1.954  LAND 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000  CONST. 16.857 8.148 4.408 9.811 5.697 3.162 11.420 12.842 12.627 9.060  BRIDGES-R/W 0.000 0.000 5.006 0.000 0.000 0.000 0.000 0.000 4.887 0.000 0.000  IANAGEMENT RESERVE 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000  ESCALATION 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000  ESCALATION 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000  ESCALATION 0.000	Surplus or Deficit 21,998 6,047 6,039 13,113 6,705 5,415 23,836 12,277 29,538 6,082 m3  ENG & PM 3.588 1.693 1.984 2.105 1.182 0.738 2.398 3.792 2.808 1.954  LAND 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000  CONST. 16.857 8.148 4.408 9.811 5.697 3.162 11.420 12.842 12.627 9.060  BRIDGES-R/W 0.000 0.000 5.006 0.000 0.000 0.000 0.000 0.000 4.887 0.000 0.000  IANAGEMENT RESERVE 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000  ESCALATION 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000  ESCALATION 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000  ETABLE OST OF THE OST OST OF THE OST OF T	Surplus or Deficit 21,998 6,047 6,039 13,113 6,705 5,415 23,836 12,277 29,538 6,082 m3 131,048  ENG & PM 3.588 1.693 1.984 2.105 1.182 0.738 2.398 3.792 2.808 1.954 22,242 1.200 0.000 0.

File: Planning\Data Parsons (2016Dollars ACTIVITY CODE Conceptual Est Blk Est. # 6.14A Version Sept.1, 20	Road Type DESCRIPTION \Length	19+800 to 16+500 West of Rest Stop to east of 264 St IC Section W.9 16 3300 MR	21+200 to 19+800 East and West of the Rest stop Section W.8 16 1400 MR	22+400 to 21+200 East of Bradner to east of Rest Stop Off-Ramp Section W.7 16 1200 MR	24+400 to 22+400 East of Automall's Western Tip to east of Bradner Section W.6 16 2000 MR	25+400 to 24+400 E of Fraser Hwy WB On ramp to E of automall W tip Section W.5 16 1000 MR	26+300 to 25+400 W of Peardonville to E of Fraser Hwy WB on ramp Section W.4 16 900 MR	18+600 to 16+500 East of 275 St to east of 264 St IC Section E.11 16 2100 MR	21+600 to 18+600 East of Bradner Underpass to just East of 275 St Section E.10 16 3000 MR	24+400 to 21+600 W of Fraser Hwy IC to east of Bradner Section E.9 16 3000 MR	26+300 to 24+400 To the east and west of the Fraser Hwy IC Section E.8 MR 16 OR 1900 TR	<b>19800</b> 0 19800	Total Line Cost C/LM
SUMMARY	Y BY ACTIVITY LEVEL												Cost/LM
2000	PROJECT MANAGEMENT	1,052,994	506,880	587,017	613,743	354,323	200,880	711,698	1,108,398	794,951	567,305	6,498,189	328
2500 3000 3500	PLANNING PRELIMINARY DESIGN DETAILED DESIGN	0 537,900 1,169,108	0 228,200 567,454	0 218,679 720,189	0 326,000 679,464	0 163,000 392,139	0 146,700 220,338	0 342,300 790,563	0 511,530 1,296,766	0 489,000 875,779	0 309,700 626,394	0 3,273,009 7,338,193	0 165 371
	Total Engineering	1,707,008	795,654	938,868	1,005,464	555,139	367,038	1,132,863	1,808,296	1,364,779	936,094	10,611,202	536
4000	LAND ACQUISITION	0	0	0	0	0	0	0	0	0	0	0	0
5000 5200 5300	GRADE CONSTRUCTION ROAD SIDE CONSTRUCTION OTHER CONSTRUCTION	10,265,132 0 0	4,352,083 0 0	2,408,667 0 0	5,775,879 0 0	3,407,259 0 0	1,689,783 0 0	6,984,808 0 0	7,399,051 0 0	7,464,154 0 0	5,316,854 0 0	55,063,671 0 0	2781 0 0
5500 6000 6500 6700	STRUCTURAL CONSTRUCTION PAVING CONSTRUCTION OPERATIONAL CONSTRUCTION UTILITY CONSTRUCTION	0 1,459,178 108,768	836,748 554,629	3,550,616 531,681 78,177	0 1,028,159 73,130	0 514,379 47,380	400,999 139,359	929,082 87,756	3,466,156 1,329,909 220,935	0 1,325,841 74,160	0 808,614 214,549	7,016,772 9,164,589 1,598,843	354 463 81
6800	RESIDENT ENGINEERING	65,000 1,068,739	0 524,426	100,000 572,273	50,000 620,090	55,000 358,453	202,148	60,000 723,252	120,000 1,101,558	50,000 798,984	55,000 574,475	555,000 6,544,399	28 331
	Total Construction	12,966,818	6,267,886	7,241,415	7,547,257	4,382,471	2,432,289	8,784,898	13,637,610	9,713,139	6,969,492	79,943,274	0 4038
9700	CONTINGENCY	4,718,046	2,271,126	2,630,190	2,749,939	1,587,580	900,062	3,188,838	4,966,291	3,561,861	2,541,867	29,115,800	1470
9800	SUB-TOTAL MANAGEMENT RESERVE	20,444,866	9,841,545 0	11,397,490 0	11,916,404	6,879,512 0	3,900,268 0	13,818,297 0	21,520,595	15,434,730 0	11,014,757 0	126,168,465 0	6372 0
	TOTAL	20,444,866	9,841,545	11,397,490	11,916,404	6,879,512	3,900,268	13,818,297	21,520,595	15,434,730	11,014,757	126,168,465	6372
9900	ESCALATION	0	0	0	0	0	0	0	0	0	0	0	0
	TOTAL COST	20,444,866	9,841,545	11,397,490	11,916,404	6,879,512	3,900,268	13,818,297	21,520,595	15,434,730	11,014,757	126,168,465	6372
==== ======	Const. Less Resident Eng.	11,898,079	5,743,460	6,669,141	6,927,167	4,024,018	2,230,141	8,061,646	12,536,052	8,914,155	6,395,017	73,398,876	3707

ACTI COD Co	Planning\Data Parsons (2016Dollars) VITY	Road Type	to 16+500 West of Rest Stop to east of 264 St IC Section W.9	21+200 to 19+800 East and West of the Rest stop Section W.8 16 1400	22+400 to 21+200 East of Bradner to east of Rest Stop Off-Ramp Section W.7 16 1200	24+400 to 22+400 East of Automall's Western Tip to east of Bradner Section W.6	25+400 to 24+400 E of Fraser Hwy WB On ramp to E of automall W tip Section W.5	26+300 to 25+400 W of Peardonville to E of Fraser Hwy WB on ramp Section W.4 16 900	18+600 to 16+500 East of 275 St to east of 264 St IC Section E.11 16 2100	21+600 to 18+600 East of Bradner Underpass to just East of 275 St Section E.10	24+400 to 21+600 W of Fraser Hwy IC to east of Bradner Section E.9	26+300 to 24+400 To the east and west of the Fraser Hwy IC Section E.8 MR 16 OR 1900 TR	<b>19800</b> 0 19800	Total Line Cost C/LM
			MR	MR	MR	MR	MR	MR	MR	MR	MR	MR	10000	
2500 2521		PLANNING - transport, planning study	0	0	0	0	0	0	0	0	0	0	٥	0
2531	Consultant	- corridor study	0	0	0	0	0	0	0	0	0	0	0	ō
2541	Consultant Consultant	- functional plan. study	0	0	0	0	0	0	0	0	0	0	0	0
2302	Consultant s		0	0	0	0	0	0	0	0	0	0	0	0
2510	Client	- project ident.	0				0	0			0	0	0	
2520	Client	- transport. planning study	0	0	0	0	0	0	0	0	0	0	0	0
	Client Client	- corridor study - functional plan. study	0	0	0	0	0	0	0	0	0	0	0	0
	Client	- general	0	0	0	0	0	0	0	0	0	0	0	0
	Client Sub-t	otal	0	0	0	0	0	0	0	0	0	0	0	0
2599	Planning Co	ontingency	0	0	0	0	0	0	0	0	0	0	0	0
		TOTAL PLANNING	0	0	0	0	0	0	0	0	0	0	0	0
3000		PRELIMINARY DESIGN												
	Consultant	- aerial base plan	0	0	0	0	0	0	0	0	0	0	0	0
3014	Consultant	- prel. design	231,000	98,000	84,000	140,000	70,000	63,000	147,000	210,000	210,000	133,000	1,386,000	70
3015	Consultant Consultant		0 92,400	0 39,200	0 33,600	0 56,000	0 28,000	0 25,200	0 58,800	0 84,000	0 84,000	0 53,200	554,400	0 28
3031	Consultant	- functroad field survey	0	0	0	0	0	0	0	0	0	0	0	0
3041 3051			165,000	70,000	60,000 23,079	100,000	50,000 0	45,000 0	105,000	150,000 22,530	150,000	95,000 0	990,000 45,609	50
3061	Consultant	- geotechnical design	49,500	21,000	18,000	30,000	15,000	13,500	31,500	45,000	45,000	28,500	297,000	15
3071			0	0	0	0	0	0	0	0	0	0	0	0
3002	Consultant Consultant s		537,900	228,200	218,679	326,000	163,000	146,700	342,300	511,530	489,000	309,700	3,273,009	165
3010	Client	- aerial base plan					0					0		
	Client	- prel. design	0	0	0	0	0	0	0	0	0	0	0	0
	Client	- control survey	0	0	0	0	0	0	0	0	0	0	0	0
	Client Client	- environmental impact - functroad field survey	0	0	0	0	0	0	0	0	0	0	0	0
	Client	- functional design	0	0	0	0	0	0	0	0	0	0	0	0
	Client Client	- funct. structural des geotechnical design	0	0	0	0	0	0	0	0	0	0	0	0
3070	Client	- right-of-way research	0	0	ō	0	0	0	0	0	0	0	0	0
3001	Client Client Sub-to	- general	0	0	0	0	0	0	0	0	0	0	0	0
3099	Preliminary	design Contingency	161,370	68,460	65,604	97,800	48,900	44,010	102,690	153,459	146,700	92,910	981,903	50
		ELIMINARY DESIGN	699,270	296,660	284,283	423,800	211,900	190,710	444,990	664,989	635,700	402,610	4,254,912	215
6700		UTILITIES												
	Util. Prov. Util. Prov.		15,000	0	50,000	0	5,000	0	10,000 50.000	70,000	0	5,000	155,000 50,000	8
6/11		sub-total	15,000	0	50,000	0	5,000	0	60,000	70,000	0	5,000	205,000	10
6712	Util.Others	ninolinos	50,000		50,000	50,000	50.000			50,000	50,000	50,000	350,000	18
		- telecommunication	0,000	0	0,000	0,000	0	0	0	0,000	0,000	0	350,000	0
		- storm & sewer inspect.	0	0	0	0	0	0	0	0	0	0	0	0
		waterworks inspect.     engineering services	0	0	0	0	0	0	0	0	0	0	0	0
6717	Util.Others	- parks/recreation-prel.	0	0	0	0	0	0	0	0	0	0	0	0
	Util.Others	- transit - tr-ops/signs & detours	0	0	0	0	0	0	0	0	0	0	0	0
	Util.Others		ő	0	0	0	0	0	0	0	ő	o o	0	0
	Util.Others	sub-total	50,000	0	50,000	50,000	50,000	0	0	50,000	50,000	50,000	350,000	18
6799	Util.Others (	Contingency	19,500	0	30,000	15,000	16,500	0	18,000	36,000	15,000	16,500	166,500	8
	TOTAL UTI	LITIES	84,500	0	130,000	65,000	71,500	0	78,000	156,000	65,000	71,500	721,500	36
5000		GRADE CONSTRUCTION												
	Grade Cons		50,000	0	50,000	50,000	100,000	0	50,000	50,000	50,000	100,000	500,000	25
	Grade Cons		50,000	0	0	0	50,000	100,000	50,000	0	0	150,000	400,000	20
	Grade Cons Grade Cons	st - storm st - mobilization	3,000	0	0 1,500	0 1,500	50,000 6,000	0 3,000	3,000	0 1,500	0 1,500	50,000 9,000	100,000 30,000	5 2
						.,						-		

CASW1200 - MoT A&W Contract #15\SWF - Highway 1 Functional File: Planning\Data\Costing\March 29th\Package 5 - Between 264 and Mt Parsons Hwy 1 Widening (2016Dollars) Package 5 - Btw 264 & Mt Lehman ACTIVITY EST.DATE April 4, 2016 CODE R3 DATE: Sept 15, 2016 Conceptual Est.  BIK Est. # 6.14A Road Type	to 16+500 West of Rest Stop to east of 264 St IC Section W.9	21+200 to 19+800 East and West of the Rest stop Section W.8	22+400 to 21+200 East of Bradner to east of Rest Stop Off-Ramp Section W.7	24+400 to 22+400 East of Automall's Western Tip to east of Bradner Section W.6	25+400 to 24+400 E of Fraser Hwy WB On ramp to E of automall W tip Section W.5	26+300 to 25+400 W of Peardonville to E of Fraser Hwy WB on ramp Section W.4	18+600 to 16+500 East of 275 St to east of 264 St IC Section E.11	21+600 to 18+600 East of Bradner Underpass to just East of 275 St Section E.10	24+400 to 21+600 W of Fraser Hwy IC to east of Bradner Section E.9	26+300 to 24+400 To the east and west of the Fraser Hwy IC Section E.8 MR 16 OR	19800 0	Total Line Cost C/LM
Version Sept.1, 200 DESCRIPTION \Length	3300 MR	1400 MR	1200 MR	2000 MB	1000 MR	900 MR	2100 MR	3000 MB	3000 MR	1900 TR MR	19800	19800
5039 Grade Const- utility contingency Grade Const. Utilities Sub-total	30,900 133,900	0	15,450 66,950	15,450 66,950	61,800 267,800	30,900 133,900	30,900 133,900	15,450 66,950	15,450 66,950	92,700 401,700	309,000 1,339,000	16 68
5010 Grade Const- site prep./clear.grubbing 5020 Grade Const- road grade/exc.placing,fill 5030 Grade Const- drainage/pipe,cul. 5040 Grade Const- multiplate	59,813 5,433,375 2,500,000	20,300 2,252,840 500,000 0	36,975 1,574,930 0	36,250 3,386,510 1,000,000	10,875 1,530,950 1,000,000 0	9,788 1,032,665 0	57,094 3,434,535 2,000,000	27,188 4,417,790 1,000,000	32,625 4,458,575 1,000,000 0	13,775 2,776,940 1,000,000	304,681 30,299,110 10,000,000	15 1530 505 0
5050 Grade Const-SGSB/produce,place,comp 5051 Grade Const-CBC/produce,place,comp 5060 Grade Const- grade finishing landscaping	1,081,063 738,431 0	858,125 562,238 0	389,265 268,909 0	654,984 447,555 0	326,414 223,886 0	283,904 202,493 0	686,102 470,097 0	970,622 672,527 0	985,248 671,053 0	616,323 425,773 0	6,852,049 4,682,961 0	346 237 0
5061 Grade Const- grade finishing hydro seed. 5062 Grade Const- grade finishing fencing 5063 Grade Const- noise barriers 5064 Grade Const- passing lanes	53,467 0 0 0	31,820 0 0 0	18,434 0 0 0	32,350 0 0	15,893 0 0 0	11,717 0 0 0	33,540 0 0 0	45,418 0 0 0	49,252 0 0 0	29,183 0 0 0	321,074 0 0 0	16 0 0 0
5090 Grade Const - sidewalks,curb & gutter 5005 Grade Const -detours c/w ex,bf,paving 5001 Grade Const - mobilization 5099 Grade Const - Contingency	0 0 295,984 3,048,640	0 0 126,760 1,305,625	0 0 68,655 707,150	0 0 166,729 1,717,314	0 0 93,241 960.378	0 0 46,217 476,035	0 0 200,441 2,064,542	0 0 214,006 2,204,265	0 0 215,903 2,223,796	0 0 145,860 1,502,356	0 0 1,573,796 16,210,101	0 0 79 819
Grade Construction Sub-total	13,210,772	5,657,708	3,064,318	7,441,692	4,161,636	2,062,818	8,946,351	9,551,817	9,636,451	6,510,211	70,243,773	3548
GRADE CONSTRUCTION COSTS  3510 Grade Eng detailed design 3519 Grade Eng detailed design/Contingency	13,344,672 934,127 280,238	5,657,708 396,040 118,812	3,131,268 219,189 65,757	7,508,642 525,605 157,681	4,429,436 310,061 93,018	2,196,718 153,770 46,131	9,080,251 635,618 190,685	9,618,767 673,314 201,994	9,703,401 679,238 203,771	6,911,911 483,834 145,150	71,582,773 5,010,794 1,503,238	3615 253 76
6810 Grade Eng general const. supervision 6811 Grade Eng quality assurance 6812 Grade Eng surveying 6819 Grade Eng Residency Contingency	400,340 266,893 266,893 280,238	169,731 113,154 113,154 118,812	93,938 62,625 62,625 65,757	225,259 150,173 150,173 157,681	132,883 88,589 88,589 93,018	65,902 43,934 43,934 46,131	272,408 181,605 181,605 190,685	288,563 192,375 192,375 201,994	291,102 194,068 194,068 203,771	207,357 138,238 138,238 145,150	2,147,483 1,431,655 1,431,655 1,503,238	108 72 72 76
Grade Engineering Sub-total	2,428,730	1,029,703	569,891	1,366,573	806,157	399,803	1,652,606	1,750,616	1,766,019	1,257,968	13,028,065	658
Total Grade Const. & Eng. Costs  5500 STRUCTURAL CONSTRUCTION 5522 Struct.Const - water	15,773,402	0	0	8,875,215	5,235,594	2,596,521	0	11,369,382	11,469,420	0	84,610,837	4273
5523 Struct.Const - sanitary 5524 Struct.Const - storm 5521 Struct.Const - mobilization 5599 Struct.Const - utility contingency	0 0 0	0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0
Structural Const. Utilities Sub-total  5510 Struct.Const - tunnel site preparation		0	0	0	0	0	0	0	0	0	0	0
5511 Struct.Const - tunnel construction 5512 Struct.Const - snow shed site prep. 5513 Struct.Const - snow shed site const.	0 0	0	0	0	0 0	0 0	0 0	0	0 0	0 0 0	0 0	0 0 0
5514 Struct.Const - bridge site preparation 5515 Struct.Const - bridge piers 5516 Struct.Const - bridge abutments 5517 Struct.Const - bridge superstructure	0 0 0	0 0	500,000 0 0 2,365,200	0 0 0	0 0 0	0 0 0	0 0 0	500,000 0 0 2,365,200	0 0 0	0 0 0	1,000,000 0 0 4,730,400	51 0 0 239
5518 Struct.Const - retain. wall site prep. 5519 Struct.Const - retaining wall const. 5501 Struct.Const - mobilization 5529 Struct.Const - Contingency	0	0	0 582,000 103,416 1,065,185	0	0	0	0 0 0	0 500,000 100,956 1,039,847	0	0 0 0	0 1,082,000 204,372 2,105,032	0 55 10 106
Structural Construction Sub-total		0	4,615,801	0	0	0	0	4,506,003	0	0	9,121,804	461
STRUCTURAL CONSTRUCTION COSTS  3520 Struct. Eng detailed design	0	0	4,615,801 369,264	0	0 0	0	0	4,506,003 360,480	0	 0	9,121,804 729,744	461 37
3529 Struct. Eng detailed design/Contingency 6820 Struct. Eng general const. supervision 6821 Struct. Eng quality assurance	0	0	110,779 184,632 92,316	0	0 0	0	0 0	108,144 180,240 90,120	0	0 0 0	218,923 364,872 182,436	11 18 9
6822 Struct. Eng surveying 6829 Struct. Eng Residency Contingency Structural Engineering Sub-total	0	0 0 0	23,079 90,008 870,078	0	0 0 0	0	0 0 0	22,530 87,867 849,382	0	0 0 0	45,609 177,875 1,719,460	9 87
Total Structural & Eng. Costs	0	0	5,485,879	0	0	0	0	5,355,384	0	0	10,841,264	548
6000 PAVING CONSTRUCTION 6020 Paving Cons- machine paving asphalt	1,416,678	812,376	516,195	998,212	499,397	389,319	902,021	1,291,174	1,287,224	785,062	8,897,659	449

Main	(20) ACTIVIT CODE Conc Blk Est.	R3 DATE: Sept 15, 2016  eptual Est. Div # 6.14A R6	64 and Mt te We Sto vison\site Se pad Type	19+800 to 16+500 lest of Rest op to east of 264 St IC ection W.9	21+200 to 19+800 East and West of the Rest stop Section W.8	22+400 to 21+200 East of Bradner to east of Rest Stop Off-Ramp Section W.7	24+400 to 22+400 East of Automall's Western Tip to east of Bradner Section W.6	25+400 to 24+400 E of Fraser Hwy WB On ramp to E of automall W tip Section W.5	26+300 to 25+400 W of Peardonville to E of Fraser Hwy WB on ramp Section W.4	18+600 to 16+500 East of 275 St to east of 264 St IC Section E.11	21+600 to 18+600 East of Bradner Underpass to just East of 275 St Section E.10	24+400 to 21+600 W of Fraser Hwy IC to east of Bradner Section E.9	26+300 to 24+400 To the east and west of the Fraser Hwy IC Section E.8 MR 16 OR	<b>19800</b>	Total Line Cost C/LM
Second Principle Compression	version	Sept.1, 20q DESCRIPTION	Length	3300 MB	1400 MR	1200 MR	2000 MR	1000 MB	900 MB	2100 MB	3000 MB	3000 MB	1900 TR	19800	19800
Section   Process   Proc	6030 P	aving Cons- machine paving concrete	_			0	141111	0			0			0	0
Color   Propagation   Color				0	0	0	0	0	0	0	0	0	0	0	0
667) Purple Construction Construction	6050 P	aving Cons- shoulder paving		0	0	0	0	0	0	0	0	0	0	0	0
March   Propagation   4.200   26.277   15.48   25.948   14.882   11.880   27.081   33.730   33.677   23.522   26.500   13.080   28.087   27.087	6060 P	aving Cons- pavement finishing		0	_	0	0	0	0		0	0	0	0	0
PATE   Proving Contemplate   1				42 500	-	15.406	20.046	14.000	11.600	-	20 725	20 617	0 00 00	200 000	0
See   Part   Control   C		aving Cons- mobilization		42,500	24,371	15,466	29,946	14,902	11,000		30,735			200,930	0
Second Communication   132,258   71,414   43,238   19,262   44,881   19,262   19,263   19,265   19,2				437,754	251,024	159,504	308,448	154,314	120,300	278,725	398,973	397,752	242,584	2,749,377	139
Second Communication   132,258   71,414   43,238   19,262   44,881   19,262   19,263   19,265   19,2															
1,000   1,00	P	AVING CONSTRUCTION COSTS		1,896,932	1,087,772	691,185	1,336,606	668,693	521,298	1,207,807	1,728,882	1,723,593	1,051,198	11,913,966	602
1,000   1,00	3560 P	aving Eng detailed design		132.785	76.144	48.383	93.562	46.808	36.491	84.546	121.022	120.651	73.584	833.978	42
See   Part   P								,		,					
George   Part	6860 P	aving Eng general const. supervision		37,939	21,755	13,824	26,732				34,578	34,472	21,024	238,279	12
George   Part	6861 P	aving Eng quality assurance		75,877	43,511	27,647	53,464	26,748	20,852	48,312	69,155	68,944	42,048	476,559	24
Partic Engineering Sub-total 32,241 19,084 12,1303 234,77 117,365 91,48 21,970 300,419 300,419 130,485 2,890,50 100 Total Parting Const. Eng. Const. E				-,		-,				-,	-,				12
Company   Comp															
Company   Comp	 -	and Device Court & Francesta			4 070 070		4 574 404	700.040		4 440 777			4 005 000		707
OPERATIONAL CONSTRUCTION															707
Section   Comparison   Compar															
Section   Comparison   Compar	6500	OPERATIONAL CONSTRUCTION													
6500   2,800   2,800   2,800   2,800   2,800   2,800   3,500   3,500   18,500   3,500   18,500   3,5	6510 O			0	170,500	0	0	0	0	0	0	0	88,000	258,500	13
8580 Operation-parameterinal e 6,000 346,000 e 15,000 25,000 126,500 e 20,000 178,500 30,000 178,500 19,000 53 Coperation-parameterinaling 33,000 18,077 21,010 125,000 13,000 21,000 30,000 30,000 18,000 19,000 126,	6520 O	perat.Cons- signals					•		0					0	
5850   Circumstance   18,000   18,000   18,000   12,000   21,000   20,000   30,000   30,000   30,000   19,000   210,175   11,000   210				-1		-,	.,		.,						_
				,								,			2
OPERATIONAL CONSTRUCTION COSTS  141,398  721,018  101,030  85,066  61,594  181,167  114,088  207,108															24
Second Committee   Second Comm							95.069		181 167						105
3549 Operal. Eng operal local design/Corningency   2,969   15,141   2,134   1,996   1,238   3,805   2,966   6,032   2,025   5,857   43,648   2,864   0,000   2,000															
8840   Copart_Ering - general corest_supervision   7.777   39,856   5.990   5.299   3.388   9.964   6.275   15.797   5.302   15.340   114.317   6.841   Copart_Ering - callally assument corest_supervision   7.777   39,856   5.980   5.290   3.388   7.298   5.292   5.744   1.282   5.758   41.7570   2.288   41.7570   2.288   41.7570   2.289   2.282   1.748   4.388   2.238   6.893   2.214   6.694   40.888   3.294   40.593   4						.,				.,					7
B841 Operal: Eng surveying   7.07   3.695   5.08   1.470   2.083   1.901   1.232   3.623   2.282   5.744   1.928   5.578   1.935   1.935   1.9368   2.937   2.938   2.938   2.931   6.948   49.884   3.935   1.93	00.0														6
6842 Operal: Eng surveying   707   3,665   508   475   308   906   570   1,436   482   1,395   40,982   1,396   40,984   40,984   3,945   40,984   40,984   3,945   40,984									-1						2
Comparison   Com	6842 O	perat. Eng surveying		707	3,605		475	308	906	570	1,436	482	1,395	10,392	1
Total Operational Const.& Eng. Costs   168,971   861,617   121,448   113,607   73,605   216,494   196,329   343,223   115,208   333,302   2,483,803   125							-,	-,		-,		-1			3
ROAD SIDE CONSTRUCTION		Operational Enginering Sub-total		27,573	140,599	19,818	18,538	12,011	35,328	22,246	56,007	18,800	54,388	405,307	20
ROAD SIDE CONSTRUCTION   South   Sou															
S203 RoadSide C- water															
S204 RoadSide C- sanitary				0	0	0	0	0	0	0	0	0	0	ا ا	0
S205 RoadSide C- storm				0	0	0	0	0	0	-	-	-		"	0
S202   RoadSide C: -mobilization   0   0   0   0   0   0   0   0   0		loadSide Cc- storm		ő	0	0	0	0	0						0
Road Side Const. Utilities Sub-lotal   0	5202 R	loadSide Cc- mobilization		0		0	-	0	-	-	-	-	-	0	0
Section   Sect				0		0		0						0	0
5220 RoadSide Cr. safety rest areas         0	R	load Side Const. Utilities Sub-total		0	0	0	0	0	0	0	0	0	0	0	0
5220 RoadSide Cr. safety rest areas         0	5210 R	toadSide Cr- weighscales		0	0	0	0	0	0	0	0	0	0	0	0
RoadSide Cr - mobilization   0   0   0   0   0   0   0   0   0	5220 R	loadSide Cr- safety rest areas		0	0	0	0	0	0	0	0	0	0	0	0
See Section				0	-	0	0	0		-	-	-	-	0	0
Road Side Construction Sub-total   0				0	-	0	0	0	0			-	-	0	0
ROAD SIDE CONSTRUCTION COSTS   0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0				0	_	0	0	0	0	-	-			0	0
3550 RoadSide Er - detailed design 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0															
Sassa   RoadSide Er- detailed design/Contingency   0   0   0   0   0   0   0   0   0	R	IOAD SIDE CONSTRUCTION COSTS			0	0	0	0	0	0	0	0	0	0	0
6850         RoadSide Er- general const. supervision         0				0		0		0	0				0	0	0
6851 RoadSide Er-quality assurance     0     0     0     0     0     0     0     0     0       6852 RoadSide Er-surveying     0				0		0		0						0	0
8852 RoadSide Er- surveying 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0				0	0	0	0	0	0	0	0	-	-	0	0
6859 RoadSide Er. Residency Contingency         0		loadSide Er - quality assurance		0	0	0	0	0	0	0	0		-	0	0
Road Side Engineering Sub-total         0 <t< td=""><td>6859 R</td><td>loadSide Er - Residency Contingency</td><td></td><td>0</td><td></td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td></td><td></td><td></td><td>       </td><td>0</td></t<>	6859 R	loadSide Er - Residency Contingency		0		0	0	0	0	0					0
				ő	-	ő	0	0	0	ō	-	-	-	0	0
	т.	otal Road Side Conet & Eng Coete			^	^	^		^	^			^		

File: (2 ACTIV CODE Cor Blk Est		19+800 to 16+500 West of Rest Stop to east of 264 St IC Section W.9 16 3300 MR	21+200 to 19+800 East and West of the Rest stop Section W.8 16 1400 MR	22+400 to 21+200 East of Bradner to east of Rest Stop Off-Ramp Section W.7 16 1200 MR	24+400 to 22+400 East of Automall's Western Tip to east of Bradner Section W.6 16 2000 MR	25+400 to 24+400 E of Fraser Hwy WB On ramp to E of automall W tip Section W.5 16 1000 MR	26+300 to 25+400 W of Peardonville to E of Fraser Hwy WB on ramp Section W.4 16 900 MR	18+600 to 16+500 East of 275 St to east of 264 St IC Section E.11 16 2100 MR	21+600 to 18+600 East of Bradner Underpass to just East of 275 St Section E.10 16 3000 MR	24+400 to 21+600 W of Fraser Hwy IC to east of Bradner Section E.9 16 3000 MR	26+300 to 24+400 To the east and west of the Fraser Hwy IC Section E.8 MR 16 OR 1900 TR	19800 0 19800	Total Line Cost C/LM
	-												
5304 5305 5302 5309	OTHER CONSTRUCTION Other Const water Other Const sanitary Other Const storm Other Const mobilization Other Const utility contingency Other Const utility contingency Other Const. Utilities Sub-total	0 0 0 0 0	0 0 0 0	0 0 0 0 0	0 0 0 0	0 0 0 0 0	0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0
5320 5330 5340 5301 5399	Other Const railroads main & spur lines Other Const railroad crossings Other Const marine work Other Const environmental mitigations Other Const mobilization Other Const Contingency Other Const Contin	0 0 0 0 0 0	0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0	0 0 0 0 0
	OTHER CONSTRUCTION COSTS	0	0	0	0	0	0	0	0	0	0	0	0
3579 6870 6871 6872 6879	Other Eng detailed design Other Eng detailed design/Contingency Other Eng general const. supervision Other Eng quality assurance Other Eng surveying Other Eng Residency Contingency Other Eng Residency	0 0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0
	Total Other Const.& Eng.Costs	0	0	0	0	0					0	0	0
3500 3530	DETAILED DESIGN from 3510,3520,3540,3550,3570 Geotech. En - detailed design	-	679,451 44,799	-	813,569 53,642	-		946,595 62,413			750,024 49,452	8,736,014 618,182	441 31 9
	Geotech. En - Contingency		13,440		16,093			18,724			14,836	185,455	
	TOTAL DETAILED DESIGN COSTS	1,519,841	737,690	936,246	883,303	509,781	286,439	1,027,731	1,685,796	1,138,512	814,312	9,539,651	482
6800	RESIDENT ENGINEERING from 6810,6820,6840,6850,6860,6870	1,389,361	681,754	743,955	806,117	465,989	262,792	940,227	1,432,026	1,038,679	746,817	8,507,718	
	TOTAL RESIDENT ENG. COSTS	1,389,361	681,754	743,955	806,117	465,989	262,792	940,227	1,432,026	1,038,679	746,817	8,507,718	430
	PART 1 SUMMARY										*******	0	0
	CONSTRUCTION ENGINEERING & SUPERVISION CONTRACTUAL CONTINGENCY	11,898,079 2,775,748 4,402,148	5,743,460 1,320,080 2,119,062	6,669,141 1,511,141 2,454,085	6,927,167 1,625,554 2,565,816	4,024,018 913,592 1,481,283	2,230,141 569,186 839,798	8,061,646 1,856,114 2,975,328	12,536,052 2,909,854 4,633,772	8,914,155 2,163,763 3,323,375	6,395,017 1,510,568 2,371,676	73,398,876 17,155,601 27,166,343	3707 866 1372
	CONSTRUCTION COST TOTAL	19,075,974	9,182,602	10,634,368	11,118,538	6,418,893	3,639,125	12,893,089	20,079,678	14,401,293	10,277,261	117,720,819	0  5945
2000 2060 2062 2063 2061	PROJECT MANAGEMENT Project Man office costs wages Project Man office costs - expenses Project Man printing costs Project Man general Project Man general Project Manager Sub-total	429,209 0 0 0 429,209	206,609 0 0 0 206,609	239,273 0 0 0 0 239,273	250,167 0 0 0 0 250,167	144,425 0 0 0 0 144,425	81,880 0 0 0 0 81,880	290,094 0 0 0 290,094	451,793 0 0 0 0 451,793	324,029 0 0 0 0 324,029	231,238 0 0 0 0 231,238	2,648,718 0 0 0 0 2,648,718	134 0 0 0 134
2010		381,519	183,652	212,687	222,371	128,378	72,782	257,862	401,594	288,026	205,545	2,354,416	119
2012 2030 2011	Client - office costs - expenses Client - printing costs Client - general	0 0 0	0 0 0	0 0 0	0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0
	Client Sub-total	381,519	183,652	212,687	222,371	128,378	72,782	257,862	401,594	288,026	205,545	2,354,416	119
2072 2073 2071	Public Rel wages & expenses Public Rel adv., media, displays Public Rel opening ceremonies Public Rel general Public Relations Sub-total	114,456 0 0 0 114,456	55,096 0 0 0 55,096	63,806 0 0 0 63,806	66,711 0 0 0 66,711	38,513 0 0 0 38,513	21,835 0 0 0 0 21,835	77,359 0 0 0 77,359	120,478 0 0 0 120,478	86,408 0 0 0 86,408	61,664 0 0 0 0 61,664	706,325 0 0 0 0 706,325	36 0 0 0 36

	ACTI COD Co	E R3 DATE: Sept 15, 2016  nceptual Est. Divison\site tt. # 6.14A Road Type	19+800 to 16+500 West of Rest Stop to east of 264 St IC Section W.9	21+200 to 19+800 East and West of the Rest stop Section W.8	22+400 to 21+200 East of Bradner to east of Rest Stop Off-Ramp Section W.7	24+400 to 22+400 East of Automall's Western Tip to east of Bradner Section W.6	25+400 to 24+400 E of Fraser Hwy WB On ramp to E of automall W tip Section W.5	26+300 to 25+400 W of Peardonville to E of Fraser Hwy WB on ramp Section W.4	18+600 to 16+500 East of 275 St to east of 264 St IC Section E.11	21+600 to 18+600 East of Bradner Underpass to just East of 275 St Section E.10	24+400 to 21+600 W of Fraser Hwy IC to east of Bradner Section E.9	26+300 to 24+400 To the east and west of the Fraser Hwy IC Section E.8 MR	<b>19800</b> 0	Total Line Cost C/LM
Decided   Comparison   13,500   Comparison	Versio	n Sept.1, 200 DESCRIPTION \Length											19800	19800
201   Log Class general   0	2040	Logal Coets - lawyers fees											82.405	A
100   100		Legal Costs - general	0	0	0	0	0	0	0	0	0	0	0	0
258   Barraine - general   14,464   5,506   68,46   68,77   18,17   18,17   18,18   17,38   17,38   18,08   17,38   18,08   17,38   18,08   17,38   18,08		-											82,405	
Company   11-46   50,00   61,00   61,00   61,00   61,00   71,00   61,00   71										120,478			706,325 0	
TOTAL PROJECT MANAGEMENT COSTS   1,98,922   95,944   793,122   797,960   400,550   291,144   193,200   1,443,910   1,033,467   797,060   4,475,640   427,450   4,475,640   4			114,456	55,096	63,806	66,711	38,513	21,835	77,359	120,478	86,408	61,664	706,325	36
MAIL   Lang Configuration Sub-Field   Conf	2099	Project Management Contingency	315,898	152,064	176,105	184,123	106,297	60,264	213,510	332,519	238,485	170,191	1,949,457	98
MAN RES Planning Man			1,368,892	658,943	763,122	797,866	460,620	261,144	925,208	1,440,918	1,033,437	737,496	8,447,646	427
Additional Content of the Content	4000	LAND	0	0	0	0	0	0	0	0	0	0	0	
August   Control   Contr	4010	Land(Code 4-Mrkt,ROW,Serv,Imp.V,Ease.C,T Acquisition Sub-total								-				
4930 Land(Code 4-Owner(LS, Apprix Fight Light)  400 Land(Code 4-Net Utad)	4000													
4905 Langicloxe 4-Pro-Mari-Prax-URI-Security 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	4030	Land(Code 4-Owners(LS,Apprsl,Rprt,Lgl,In	0	0	0	0	0	0	0	-	0	0		0
4606 Land/Code 4-Not Used 1070 Land/Code 4-Surveys 1070 Land/Code			-	-	-	-	0	0		0	0	-	0	0
489 Langi/Cook 4-Acg F-MSA]T-VV/Crufs Appr.  0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	4060	Land(Code 4-Not Used	-	-	-	-		-	-	-	-	-	0	-
4690 Land Conte - Surveys			-	_	_	-		-	-		-		0	-
Associated continuation	4090	Land(Code 4-Surveys	0	0	0	0	0	0	0	0	0	0	0	-
A099   Land Contingency Sub-total   0													0 0	0
TOTAL LAND COSTS		Associated costs-sub-total	0	0	0	0	0	0	0	0	0	0	0	0
Section   Sect	4099	Land Contingency Sub-total	0	0	0	0	0	0	0	0	0	0	0	0
MAN. RES preliminary design 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0			0	0	0	0	0	0	0	0	0	0	0	0
MAN. RES profilmary design 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	9800													
MAN. RES parada construction 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		MAN. RES preliminary design						-						-
MAN. RES restrictural construction 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0			0	_	_	_	0	0	_	0	0	-	0	-
MAN. RES parking construction 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0			0	0	0	0	0	0	0	0	0		0	-
MAN, RES roadside construction 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		MAN. RES paving construction	0	0	0	0	0	0	0	0	0	0	0	0
MAN, RES roher construction 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		MAN. RES operation construction  MAN. RES readside construction	0	0	0	0	0	0	0	0	0	-	0	-
MAN, RES Iand 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		MAN. RES other construction	0	ō	0	0	ō	0	0	0	ō	0	0	0
MAN. RES relatelled eng. 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		MAN RES project management	0		0	0	0	0	0	0	0		0	-
MAN. RES risk contingency 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		MAN. RES detailed eng.	-	-	0	0	0	0	-	0	0	-	0	-
TOTAL MANAGEMENT RESERVE 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0					-		-		-	-	-	-		-
TOTAL LESS ESCALATION FISCAL 9900 ESCALATION YEAR PROJECTED ESCALATION 2006-2007 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0														
FISCAL 9900 ESCALATION YEAR PROJECTED ESCALATION  2006-2007			-		0	0	0	0	0	0	0	0	0	0
2006-2007	9900	FISCAL ESCALATION												
2007-2008			0	^	0			0	0			0		n
2009-2010 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		2007-2008	0	_	_	_	0	0	_		_	_	0	-
2010-2011 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0			0	0	0	0	0	0	0	0	0		0	0
2011-2012 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0			0	0	0	0	0	0	0	0	0	-	0	0
2013-2014 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		2011-2012					0	0	0	0	0		0	
2014-2015 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0				-		-	0	0	0	0			0	-
PART 2 SUMMARY NON-CONSTRUCTION COSTS Non-Construction 1,052,994 506,880 587,017 613,743 354,323 200,880 711,698 1,108,398 794,951 567,305 6,498,189 328			-				-	Ő	-	-	-	-	ő	-
PART 2 SUMMARY NON-CONSTRUCTION COSTS Non-Construction 1,052,994 506,880 587,017 613,743 354,323 200,880 711,698 1,108,398 794,951 567,305 6,498,189 328				0		0	0		0	0		0	0	0
	====	PART 2 SUMMARY NON-CONSTRUCTION COSTS												


Q:\SW\1200 - MoT A&W Contract #15\SWF - Highway 1 Functional											1 1	
File: Planning\Data\Costing\March 29th\Package 5 - Between 264 and Mt	19+800	21+200	22+400	24+400	25+400	26+300	18+600	21+600	24+400	26+300		Total
Parsons Hwy 1 Widening	to 16+500	to 19+800	to 21+200	to 22+400	to 24+400	to 25+400	to 16+500	to 18+600	to 21+600	to 24+400		Line
(2016Dollars) Package 5 - Btw 264 & Mt Lehman	West of Rest	East and	East of Bradner	East of Automall's	E of Fraser Hwy	W of Peardonville	East of 275 St	East of Bradner	W of Fraser Hwy	To the east and		Cost
ACTIVITY EST.DATE April 4, 2016	Stop to east of	West of the	to east of Rest	Western Tip to	WB On ramp to E	to E of Fraser Hwy	to east of	Underpass to just	IC to east of	west of the		
CODE R3 DATE: Sept 15, 2016	264 St IC	Rest stop	Stop Off-Ramp	east of Bradner	of automall W tip	WB on ramp	264 St IC	East of 275 St	Bradner	Fraser Hwy IC		C/LM
Conceptual Est. Divison\site	Section W.9	Section W.8	Section W.7	Section W.6	Section W.5	Section W.4	Section E.11	Section E.10	Section E.9	Section E.8 MR	19800	
Blk Est. # 6.14A Road Type	16	16	16	16	16	16	16	16	16	16 OR	0	
Version Sept.1, 200 DESCRIPTION \Length	3300	1400	1200	2000	1000	900	2100	3000	3000	1900 TR	19800	19800
	MR	MR	MR	MR	MR	MR	MR	MR	MR	MR		
TOTAL NON-CONSTRUCTION COSTS	1,368,892	658,943	763,122	797,866	460,620	261,144	925,208	1,440,918	1,033,437	737,496	8,447,646	427
DIVISION TOTAL FOR ROAD TYPE	20,444,866	9,841,545	11,397,490	11,916,404	6,879,512	3,900,268	13,818,297	21,520,595	15,434,730	11,014,757	126,168,465	6372




# PACKAGE 6 - SECTIONS

ID	Chainage Start	Chainage End	Description
P.1			Peardonville Road Overpass Replacement
P.2			S Fraser Way Extension to Peardonville Road
P.3			Livingstone Avenue Realignment to Peardonville Road
W.3	26+300	28+300	Highway 1 Westbound Lanes
W.2	28+300	29+500	Highway 1 Westbound Lanes
W.1	29+500	31+700	Highway 1 Westbound Lanes
W.0	32+700	33+700	Highway 1 Westbound Lanes
E.7	26+300	27+300	Highway 1 Eastbound Lanes
E.6	27+300	28+500	Highway 1 Eastbound Lanes
E.5	28+500	29+500	Highway 1 Eastbound Lanes
E.4	29+500	31+800	Highway 1 Eastbound Lanes
E.3	31+800	33+400	Highway 1 Eastbound Lanes
E.2	33+400	34+600	Highway 1 Eastbound Lanes
E.1	34+600	35+974	Highway 1 Eastbound Lanes
Mc.1			McCallum Road Westbound On Ramp Extension
H11.1			Highway 1 Eastbound Off Ramp to Highway 11
H11.2			Highway 11 On Ramp to Highway 1 Eastbound
H11.3			Highway 11 Northbound On Ramp to Highway 1 Westbound














File: Planning\Data	- MoT A&W Contract #15\SWF - Highway 1 Functional a\Costing\March 29th\[Package 6 - Between Mt Lehman	Peardonville	New Roadway	Livingstone Ave	31+700	33+700	35+974	Hwy 1 to Hwy 11	Hwy 11 to Hwy 1	33+500	31+900		Total
	Hwy 1 Widening	New overpass	underneath	Realignment	to 26+300	to 32+700	to 26+300	Ramp from EB	Ramp from NB	to 32+700	to 31+700		Line
	Package 6 - Mt Lehman to Hwy 11	and approaches	Peardonville	to Peardonville	Westbound	West of Rail	Eastbound	to NB	to EB	West of Rail	McCallum WB		Cost
ACTIVITY CODE	EST.DATE April 4, 2016 R3 DATE: Sept 15, 2016	0	Overpass 0	0	Widening Sections	Overpass to East of McCallum	Widening Sections	0	0	Overpass to East of McCallum	On Ramp Extension		C/LM
Conceptual Est.		Section P.1	Section P.2	Section 3.3	W.3 - W.1	Section W.0	E.7 to E.1	Section H11.1	Section H11.2	Section H11.3	Section Mc.1 MR	17944	C/LIVI
Blk Est. # 6.14A	Road Type	21	2	2	16	16	16	16	16	16	16 OR	17344	
Version Sept.1, 200		430	440	370	5400	1000	9294	400	295	207	108 TR	17944	17944
		MR	MR	MR	MR	MR	MR	MR	MR	MR	MR		
	Engineering	9,970,726	244,341	320,107	4,630,278	1,263,639	9,369,552	1,111,855	361,263	202,640	83,798	27,558,199	1536
	Land	0	0	0	0	0	0	0	0	0	0	0	0
	Construction	52,337,305	854,987	1,399,085	20,389,155	6,176,726	43,727,150	5,407,588	1,617,168	921,989	351,397	133,182,552	7422
	Management Reserve Escalation	0	0	0	0	0	0	0	0	0	0	0	0
	Total	62,308,031	1,099,328	1,719,192	25,019,433	7,440,366	53,096,703	6,519,443	1,978,430	1,124,630	435,195	160,740,751	8958
	BASIC QUANTITY SUMMARY												
	Construct.Cost ONLY Per L.M.	121,715	1,943	3,781	3,776	6,177	4,705	13,519	5,482	4,454	3,254 \$/LM	7,422	
	Land Area	0.7	1.2	1.0	16.6	2.9	29.3	1.2	0.7	0.7	0.2 ha	54.7	
	Land Area	0.7	1.2	1.0	10.0	2.9	29.3	1.2	0.7	0.7	0.2 Ha	54.7	
	Mobilization	1,080,969	17,574	28,708	410,641	125,532	870,162	111,479	33,327	18,930	7,205	2,704,527	
	Land Cont.	0	0	0	0	0	0	0	0	0	0	0	00 704 457
	Construction Cont.	11,133,977	181,015	295,690	4,322,604	1,307,979	9,280,665	1,148,238	343,267	194,979	74,216	28,282,631	30,734,435
	Engineering Cont. Supervision Cont.	2,300,937 943,862	56,386 16,289	73,871 27,176	1,068,526 382,586	291,609 117.419	2,162,204 810,216	256,582 99,667	83,368 29,925	46,763 17,788	19,338 6,876	6,359,584 2,451,804	
	Total Cont.	14,378,776	253,691	396,737	5,773,715	1,717,007	12,253,085	1,504,487	456,561	259,530	100,430	37,094,019	
	Total Gont.	14,070,770	230,001	555,757	0,770,710	1,717,007	12,200,000	1,004,407	400,001	200,000	100,400	07,004,010	
	S.G.S.B.	3,872	3,000	2,240	24,095	4,546	42,479	1,955	1,488	1,200	461 m3	85,338	
	C.B.C.	2,581	1,780	1,277	13.072	2.497	22.882	1,121	896	664	272 m3	47.041	
	Asphalt	2.023	909	765	18.614	3.206	32.712	1.277	844	604	378 t	61,332	
	Concrete Barrier	160	0	150	1,505	420	2,275	160	110	25	108 lm	4,913	
	Noise Attentuation Wall	0	0	0	0	0	0	0	0	0	0 m2	0	
	No. of Light Poles	20	0	12	0	0	0	13	10	7	4 ea	66	
	Sidewalk	430	0	0	0	0	0	0	0	0	0 lm	430	
	Curb and Gutter	0	0	0	0	0	0	0	0	0	0 lm	0	
	Signals	1	0	0	0	0	0	0	0	0	0 ea	1 1	
	Bridge total area	3982	0	0	0	0	0	480	0	0	0 m2	4,462	
	Total Rock		0	0									ENG
	Total OM	0	1,260	7,255	0 79,720	0 33,150	0 130,530	0 1,204	0	0 5,759	0 m3 1,188 m3	260,065	0
	Total Stripping	0	0	0	19,700	2,500	45,100	4,120	0	0	0 m3	71,420	0
	Total Borrow	0	0	0	0	2,300	0	0	0	0	0 m3	71,420	
	Total Cut/Excavation	0	1,260	7,255	99,420	35,650	175,630	5.324	0	5.759	1,188 m3	331,485	0
	Total Fill	7,188	0	4,429	69,736	25,174	193,994	16,374	0	4,409	911 m3	322,213	0
	Surplus or Deficit	-7,188	1,260	2,826	29,684	10,477	-18,364	-11,050	0	1,350	277 m3	9,272	
	ENG & PM	9.971	0.244	0.320	4.630	1.264	9.370	1.112	0.361	0.203	0.084	27.558	27.559
	LAND	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
	CONST. BRIDGES-R/W	1.814	0.855	1.399	20.389	6.177	43.291	1.711	0.542	0.922	0.351	77.453	77.451
	MANAGEMENT RESERVE	50.523	0.000	0.000	0.000	0.000	0.436	3.697 0.000	1.075 0.000	0.000	0.000	55.730 0.000	55.731 0.000
	ESCALATION	0.000 0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
	TOTAL (Millions) (2016Dollars)	62.308	1.099	1.719	25.019	7.441	53.097	6.520	1.978	1.125	0.435	160.741	160.741
	TOTAL Control												
	TOTAL Cost per meter				\$ 4,633		\$ 5,713					\$ 8,958	
	Construction cost per meter	\$ 121,714	\$ 1,943	\$ 3,781	\$ 3,776	\$ 6,177	\$ 4,705	\$ 13,520	\$ 5,481	\$ 4,454	\$ 3,250	\$ 7,422	

File: Planning\Da Parson (2016Dollars ACTIVITY CODE Conceptual Es Bik Est. # 6.14A Version Sept.1, 2	Road Type	Peardonville New overpass and approaches 0 0 Section P-1 21 430 MR	New Roadway underneath Peardonville Overpass 0 Section P.2 2 440 MR	Livingstone Ave Realignment to Peardonville 0 0 Section 3.3 2 370 MR	31+700 to 26+300 Westbound Widening Sections W.3 - W.1 16 5400 MR	33+700 to 32+700 West of Rail Overpass to East of McCallum Section W.0 16 1000 MR	35+974 to 26+300 Eastbound Widening Sections E.7 to E.1 16 9294 MR	Hwy 1 to Hwy 11 Ramp from EB to NB 0 0 Section H11.1 16 400 MR	Hwy 11 to Hwy 1 Ramp from NB to EB 0 0 Section H11.2 16 295 MR	33+500 to 32+700 West of Rail Overpass to East of McCallum Section H11.3 16 207	31+900 to 31+700 McCallum WB On Ramp Extension Section Mc.1 16 OR 108 TR	<b>17944</b> 0 17944	Total Line Cost C/LM  17944  Cost/LM
2000	PROJECT MANAGEMENT	3,209,117	56,620	88,545	1,288,603	383,209	2,734,696	335,778	101,897	57,923	22,414	8,278,803	461
2500 3000 3500	PLANNING PRELIMINARY DESIGN DETAILED DESIGN	0 303,021 4,157,651	0 71,720 59,614	0 60,310 97,381	0 880,200 1,392,950	0 163,000 425,821	0 1,516,931 2,955,721 0	0 82,247 437,248	0 53,039 122,958	0 33,741 64,213	0 17,604 24,442	3,181,813 9,737,999	0 177 543
	Total Engineering	4,460,672	131,334	157,691	2,273,150	588,821	4,472,652	519,495	175,997	97,954	42,046	12,919,812	720
4000	LAND ACQUISITION	0	0	0	0	0	0	0	0	0	0	0	0
5000 5200 5300 5500	GRADE CONSTRUCTION ROAD SIDE CONSTRUCTION OTHER CONSTRUCTION STRUCTURAL CONSTRUCTION	764,252 0 0 35,835,492	495,808 0 0 0	769,084 0 0	11,319,554 0 0 0	3,762,510 0 0 0	24,653,851 0 0 309,000	976,425 0 0 2,622,688	192,976 0 0 762,200	526,216 0 0 0	138,095 0 0 0	43,598,772 0 0 39,529,380	2430 0 0 2203
6000 6500 6700 6800	PAVING CONSTRUCTION OPERATIONAL CONSTRUCTION UTILITY CONSTRUCTION RESIDENT ENGINEERING	248,407 265,107 0 3,146,208	103,014 4,563 0 54,298	98,599 117,950 0 90,585	2,247,337 531,789 310,000 1,275,285	406,310 141,110 50,000 391,397	4,092,893 819,806 1,060,000 2,700,720	102,378 125,969 0 332,224	96,282 92,767 0 99,750	74,776 48,937 0 59,294	51,923 57,367 0 22,920	7,521,919 2,205,364 1,420,000 8,172,681	419 123 79 455
	Total Construction	40,259,466	657,683	1,076,219	15,683,965	4,751,328	33,636,269	4,159,683	1,243,975	709,223	270,305	0 102,448,117	0 5709
9700	CONTINGENCY	14,378,776	253,691	396,737	5,773,715	1,717,007	12,253,085	1,504,487	456,561	259,530	100,430	37,094,019	2067
9800	SUB-TOTAL MANAGEMENT RESERVE	62,308,031 0	1,099,328 0	1,719,192 0	25,019,433 0	7,440,366 0	53,096,703 0	6,519,443 0	1,978,430 0	1,124,630 0	435,195 0	160,740,751	8958 0
	TOTAL	62,308,031	1,099,328	1,719,192	25,019,433	7,440,366	53,096,703	6,519,443	1,978,430	1,124,630	435,195	160,740,751	8958
9900	ESCALATION	0	0	0	0	0	0	0	0	0	0	0	0
	TOTAL COST	62,308,031	1,099,328	1,719,192	25,019,433	7,440,366	53,096,703	6,519,443	1,978,430	1,124,630	435,195	160,740,751	8958
	Const. Less Resident Eng.	37,113,258	603,385	985,634	14,408,680	4,359,931	30,935,549	3,827,460	1,144,225	649,929	247,385	94,275,436	5254

ACTI COD Co Blk Es	Planning\Data Parsons (2016Dollars) VITY	MoT A&W Contract #15\SWF - Hi \Costing\March 29th\[Package 6 - E Hwy 1 Widening Package 6 - Mt Lehman to H EST.DATE April 4, 2016 R3 DATE: Sept 15, 2016	Between Mt Lehman	Peardonville New overpass and approaches 0 0 Section P.1	New Roadway underneath Peardonville Overpass 0 Section P.2 2 440	Livingstone Ave Realignment to Peardonville 0 0 Section 3.3	31+700 to 26+300 Westbound Widening Sections W.3 - W.1 16 5400	33+700 to 32+700 West of Rail Overpass to East of McCallum Section W.0	35+974 to 26+300 Eastbound Widening Sections E.7 to E.1 16 9294	Hwy 1 to Hwy 11 Ramp from EB to NB 0 0 Section H11.1	Hwy 11 to Hwy 1 Ramp from NB to EB 0 0 Section H11.2	33+500 to 32+700 West of Rail Overpass to East of McCallum Section H11.3 16 207	31+900 to 31+700 McCallum WB On Ramp Extension Section Mc.1 MR 16 OR 108 TR	<b>17944</b> 0 17944	Total Line Cost C/LM
				MR	MR	MR	MR	MR	MR	MR	MR	MR	MR		
2500 2521	Concultant	PLANNING - transport. planning study		0	0	0	0	0	0	0	0	0	0	ا ا	0
		- corridor study		0	0	0	0	0	0	0	0	0	0	0	0
2541	Consultant	<ul> <li>functional plan. study</li> </ul>		0	0	0	0	0	0	0	0	0	0	0	0
2502	Consultant			0	0	0	0	0	0	0	0	0	0	0	0
	Consultant s	sub-total		0	0	0	0	0	0	0	0	0	0	0	
	Client	- project ident.		0	0	0	0	0	0	0	0	0	0	0	0
	Client	transport. planning study		0	0	0	0	0	0	0	0	0	0	0	0
	Client Client	<ul> <li>corridor study</li> <li>functional plan. study</li> </ul>		0	0	0	0	0	0	0	0	0	0		0
		- general		0	0	0	0	0	0	0	0	0	0	ا ة	0
	Client Sub-t	otal		0	0	0	0	0	0	0	0	0	0	0	0
2500	Planning Co	ntingency		0	0	0	0	0	0	0			0		0
2333															
		TOTAL PLANNING		0	0	0	0	0	0	0	0	0	0	0	0
3000		PRELIMINARY DESIGN											=======================================		
	Consultant	- aerial base plan		0	0	0	0	0	0	0	0	0	0	ا ا	0
3014	Consultant	- prel. design		30,100	30,800	25,900	378,000	70,000	650,580	28,000	20,650	14,490	7,560	1,256,080	70
		- control survey		0	0	0	0	0	0	0	0	0	0	0	0
		<ul> <li>environmental impact</li> <li>functroad field survey</li> </ul>		12,040	12,320	10,360	151,200 0	28,000	260,232	11,200	8,260 0	5,796 0	3,024	502,432	28 0
3041		- functional design		21,500	22,000	18,500	270,000	50,000	464,700	20,000	14,750	10,350	5,400	897,200	50
		<ul> <li>funct. structural des.</li> </ul>		232,931	0	0	0	0	2,009	17,047	4,954	0	0	256,941	14
		- geotechnical design		6,450	6,600	5,550	81,000	15,000	139,410	6,000	4,425	3,105	1,620	269,160	15
	Consultant	- right-of-way research - general		0	0	0	0	0	0	0	0	0	0	ا ۱ ۵۱	0
0002	Consultant s			303,021	71,720	60,310	880,200	163,000	1,516,931	82,247	53,039	33,741	17,604	3,181,813	177
	01:1														
	Client Client	<ul> <li>aerial base plan</li> <li>prel. design</li> </ul>		0	0	0	0	0	0	0	0	0	0		0
	Client	- control survey		0	ő	ō	ō	0	0	0	0	0	ő	ő	0
	Client	<ul> <li>environmental impact</li> </ul>		0	0	0	0	0	0	0	0	0	0	0	0
	Client Client	<ul> <li>functroad field survey</li> <li>functional design</li> </ul>		0	0	0	0	0	0	0	0	0	0	0 0	0
	Client	- funct. structural des.		0	0	0	0	0	0	0	0	0	0	ا ا	0
	Client	<ul> <li>geotechnical design</li> </ul>		0	0	0	0	0	0	0	0	0	0	0	0
	Client	- right-of-way research		0	0	0	0	0	0	0	0	0	0	0	0
3001	Client Client Sub-t	- general otal		0	0	0	0	0	0	0	0	0	0		0
								-							
3099	Preliminary	design Contingency		90,906	21,516	18,093	264,060	48,900	455,079	24,674	15,912	10,122	5,281	954,544	53
	TOTAL PRE	ELIMINARY DESIGN		393,927	93,236	78,403	1,144,260	211,900	1,972,010	106,922	68,951	43,863	22,885	4,136,357	231
									1,072,010				=======================================		
6700		UTILITIES													
	Util. Prov.	- Hydro - Telephone		0	0	0	60,000 50.000	0	160,000 50.000	0	0	0	0	220,000 100.000	12 6
0, 11				0	0	0	110,000	0	210,000	0	0	0	0	320,000	18
	Util.Others	pipelines     telecommunication		0	0	0	200,000	50,000	850,000 0	0	0	0	0	1,100,000	61
		- storm & sewer inspect.		0	0	0	0	0	0	0	0	0	0	ا ا	0
6715	Util.Others	<ul> <li>waterworks inspect.</li> </ul>		0	0	0	0	0	0	0	0	0	0	0	0
		- engineering services		0	0	0	0	0	0	0	0	0	0	0	0
	Util.Others	<ul> <li>parks/recreation-prel.</li> <li>transit</li> </ul>		0	0	0	0	0	0	0	0	0	0	ا ۱ ۵۱	0
		- tr-ops/signs & detours		0	0	0	0	0	0	0	0	0	0	ا ة	0
6701	Util.Others			0	0	0	0	0	0	0	0	0	0	0	0
	Util.Others	sup-total		0	0	0	200,000	50,000	850,000	0	0	0	0	1,100,000	61
6799	Util.Others (	Contingency		0	0	0	93,000	15,000	318,000	0	0	0	0	426,000	24
	TOTAL UTI	LITIES		0	0	0	403,000	65,000	1,378,000	0	0	0	0	1,846,000	103
5000		GRADE CONSTRUCTION													
5032	Grade Cons	t- water		0	0	0	300,000	100,000	1,300,000	0	0	0	0	1,700,000	95
5033	Grade Cons	i - sanitary		0	0	0	300,000	50,000	900,000	0	0	0	0	1,250,000	70

O:SW11200 - MoT A&W Contract #15\SWF - Highway 1 Functional File: Planning\(\text{Dotata\costing\March 29th\[\text{Package 6 - Between Mt Lehman}\) Parsons Hwy 1 Widening (2016\text{Dotata\costing\March 29th\[\text{Package 6 - Between Mt Lehman}\) Package 6 - Mt Lehman to Hwy 11 ACTIVITY EST.DATE April 4, 2016 CODE R3 DATE: Sept 15, 2016 Conceptual Est. Divison\site		New Roadway underneath Peardonville Overpass 0 Section P.2	Livingstone Ave Realignment to Peardonville 0 0 Section 3.3	31+700 to 26+300 Westbound Widening Sections W.3 - W.1	33+700 to 32+700 West of Rail Overpass to East of McCallum Section W.0	35+974 to 26+300 Eastbound Widening Sections E.7 to E.1	Hwy 1 to Hwy 11 Ramp from EB to NB 0 0 Section H11.1	Hwy 11 to Hwy 1 Ramp from NB to EB 0 0 Section H11.2	33+500 to 32+700 West of Rail Overpass to East of McCallum Section H11.3	31+900 to 31+700 McCallum WB On Ramp Extension Section Mc.1 MR	17944	Total Line Cost C/LM
Blk Est. # 6.14A Road Type Version Sept.1, 200 DESCRIPTION \Length	21 430 MR	2 440 MR	2 370 MR	16 5400 MR	16 1000 MB	16 9294 MR	16 400 MR	16 295 MR	16 207 MB	16 OR 108 TR MR	17944	17944
5034 Grade Const - storm	0	0	0	200,000	250,000	1,000,000	0	0	NID 0	0	1,450,000	81
5031 Grade Const - mobilization 5039 Grade Const - utility contingency	0	0	0	24,000 247,200	12,000 123,600	96,000 988,800	0	0	0	0	132,000 1,359,600	7 76
Grade Const. Utilities Sub-total	ő	0	0	1,071,200	535,600	4,284,800	ő	0	0	0	5,891,600	328
5010 Grade Const - site prep./clear,grubbing	1,496	56,148	45,726	97,875	0	77,575	0	0	0	0	278,820	16
5020 Grade Const - road grade/exc,placing,fill 5030 Grade Const - drainage/pipe,cul.	215,645	50,400 0	423,060 0	6,149,880 1,000,000	2,196,205 500,000	12,984,415 2,500,000	704,151 0	0	362,644 0	76,445 0	23,162,844 4,000,000	1291 223
5040 Grade Const - muiltiplate	0	0	0	0,000,000	0 000,000	2,500,000	0	0	0	0	4,000,000	0
5050 Grade Const-SGSB/produce,place,comp	271,035	210,033	156,818	1,686,677	318,255	2,973,537	136,836	104,192	83,984	32,276	5,973,643	333
5051 Grade Const-CBC/produce,place,comp 5060 Grade Const- grade finishing landscaping	232,316 0	160,166 0	114,885 0	1,176,449 0	224,709	2,059,397	100,872 0	80,606 0	59,774 0	24,480 0	4,233,654 0	236 0
5061 Grade Const - grade finishing hydro seed.	0	4,620	6,196	78,977	13,754	140,854	6,127	2,558	4,486	872	258,443	14
5062 Grade Const - grade finishing fencing 5063 Grade Const - noise barriers	0	0	0	0	0	0	0	0	0	0	0	0
5064 Grade Const - passing lanes	0	0	0	0	0	0	0	0	0	0	0	0
5090 Grade Const - sidewalks,curb & gutter	21,500	0	0	0	0	0	0	0	0	0	21,500	1
5005 Grade Const-detours c/w ex,bf,paving 5001 Grade Const- mobilization	0 22.260	0 14,441	0 22.401	305.696	97,588	622.073	0 28.440	0 5.621	0 15,327	4.022	1,137,867	0 63
5099 Grade Const - Contingency	229,276	148,742	230,725	3,148,666	1,005,153	6,407,355	292,928	57,893	157,865	41,429	11,720,032	653
Grade Construction Sub-total	993,528	644,550	999,810	13,644,220	4,355,663	27,765,206	1,269,353	250,869	684,081	179,524	50,786,803	2830
GRADE CONSTRUCTION COSTS	993,528	644,550	999,810	14,715,420	4,891,263	32,050,006	1,269,353	250,869	684,081	179,524	56,678,403	3159
3510 Grade Eng detailed design	69,547	45,119	69,987	1,030,079	342,388	2,243,500	88,855	17,561	47,886	12,567	3,967,488	221
3519 Grade Eng detailed design/Contingency 6810 Grade Eng general const. supervision	20,864	13,536 19,337	20,996 29,994	309,024 441,463	102,717 146.738	673,050 961,500	26,656 38,081	5,268 7,526	14,366 20,522	3,770 5,386	1,190,246 1,700,352	66 95
6811 Grade Eng quality assurance	19,871	12,891	19,996	294,308	97,825	641,000	25,387	5,017	13,682	3,590	1,133,568	63
6812 Grade Eng surveying	19,871	12,891	19,996	294,308 309,024	97,825	641,000	25,387	5,017	13,682	3,590	1,133,568	63
6819 Grade Eng Residency Contingency Grade Engineering Sub-total	20,864 180,822	13,536 117,308	20,996 181,965	2,678,206	102,717 890,210	673,050 5,833,101	26,656 231,022	5,268 45,658	14,366 124,503	3,770 32,673	1,190,246 10,315,469	66 575
Total Grade Const. & Eng. Costs	1,174,350	761,858	1,181,775	17,393,627	5,781,473	37,883,107	1,500,375	296.527	808.583	212.197	66,993,873	3733
Total Grade Collst. & Eng. Costs			1,101,770	17,555,027	5,761,475	37,003,107	1,500,575	250,527	000,303	212,107		
5500 STRUCTURAL CONSTRUCTION												
5522 Struct.Const - water	0	0	0	0	0	0	0	0	0	0	0	0
5523 Struct.Const - sanitary 5524 Struct.Const - storm	0	0	0	0	0	0	0	0	0	0	0	0
5521 Struct.Const - mobilization	0	0	0	0	0	0	0	0	0	0	0	0
5599 Struct.Const - utility contingency	0	0	0	0	0	0	0	0	0	0	0	0
Structural Const. Utilities Sub-total	0	0	0	0	0	0	0		0	0	0	
5510 Struct.Const - tunnel site preparation 5511 Struct.Const - tunnel construction	0	0	0	0	0	0	0	0	0	0	0	0
5512 Struct.Const - tunner construction 5512 Struct.Const - snow shed site prep.	0	0	0	0	0	0	0	0	0	0	"	0
5513 Struct.Const - snow shed site const.	0	0	0	0	0	0	0	0	0	0	0	0
5514 Struct.Const - bridge site preparation	1,000,000	0	0	0	0	0	0	0	0	0	1,000,000	56
5515 Struct.Const - bridge piers	0	0	0	0	0	0	0	0	0	0	0	0
5516 Struct.Const - bridge abutments 5517 Struct.Const - bridge superstructure	1,000,000 31,856,000	0	0	0	0	0	1,919,920	0	0	0	1,000,000 33,775,920	56 1882
5518 Struct.Const - retain. wall site prep.	0	0	0	0	0	0	0	0	0	0	0	0
5519 Struct.Const - retaining wall const. 5501 Struct.Const - mobilization	935,740 1,043,752	0	0	0	0	300,000 9.000	626,379 76.389	740,000 22,200	0	0	2,602,119 1,151,341	145 64
5529 Struct.Const - Contingency	10,750,648	0	0	0	0	92,700	786,806	228,660	0	0	11,858,814	661
Structural Construction Sub-total	46,586,140	0	0	0	0	401,700	3,409,494	990,860	0	0	51,388,194	2864
STRUCTURAL CONSTRUCTION COSTS	46,586,140	0	0	0	0	401,700	3,409,494	990,860	0	0	51,388,194	2864
3520 Struct. Eng detailed design	3,726,891	0	0	0	0	32,136	272,760	79,269	0	0	4,111,056	229
3529 Struct. Eng detailed design/Contingency	1,118,067	0	0	0	0	9,641	81,828	23,781	0	0	1,233,317	69
6820 Struct. Eng general const. supervision 6821 Struct. Eng quality assurance	1,863,446 931,723	0	0	0	0	16,068 8.034	136,380 68.190	39,634 19.817	0	0	2,055,528 1,027,764	115 57
6822 Struct. Eng surveying	232,931	0	0	0	0	2,009	17,047	4,954	0	0	256,941	14
6829 Struct. Eng Residency Contingency	908,430	0	0	0	0	7,833	66,485	19,322	0	0	1,002,070	56
Structural Engineering Sub-total	8,781,487	0	0	0	0	75,720	642,690	186,777	0	0	9,686,675	540
Total Structural & Eng. Costs	55,367,627	0	0	0	0	477,420	4,052,184	1,177,637	0	0	61,074,869	3404

COI Co Blk E	onceptual Est. Di	It Lehman Pea New and a ivison\site Sector	pardonville w overpass approaches 0 0 ection P.1 21 430 MR	New Roadway underneath Peardornville Overpass 0 Section P.2 2 440 MR	Livingstone Ave Realignment to Peardonville 0 0 Section 3.3 2 370 MR	31+700 to 26+300 Westbound Widening Sections W.3 - W.1 16 5400 MR	33+700 to 32+700 West of Rail Overpass to East of McCallum Section W.0 16 1000 MR	35+974 to 26+300 Eastbound Widening Sections E.7 to E.1 16 9294 MR	Hwy 1 to Hwy 11 Ramp from EB to NB 0 0 Section H11.1 16 400 MR	Hwy 11 to Hwy 1 Ramp from NB to EB 0 0 Section H11.2 16 295 MR	33+500 to 32+700 West of Rail Overpass to East of McCallum Section H11.3 16 207 MR	31+900 to 31+700 McCallum WB On Ramp Extension Section Mc.1 MR 16 OR 108 TR	<b>17944</b> 0 17944	Total Line Cost C/LM
6030 6040 6050 6060 6070 6001	Paving Cons - machine paving asphalt Paving Cons - machine paving concrete Paving Cons - hot reprofiling Paving Cons - shoulder paving Paving Cons - pavement finishing Paving Cons - seal coating		241,172 0 0 0 0 0 0 7,235 0 74,522	100,014 0 0 0 0 0 0 0 3,000 0 30,904	95,727 0 0 0 0 0 2,872 0 29,580	2,181,881 0 0 0 0 0 0 65,456 0 674,201	394,476 0 0 0 0 0 11,834 0 121,893	3,973,682 0 0 0 0 0 119,210 0 1,227,868	99,396 0 0 0 0 0 2,982 0 30,713	93,477 0 0 0 0 0 2,804 0 28,884	72,598 0 0 0 0 0 0 2,178 0 22,433	50,411 0 0 0 0 0 0 1,512 0 15,577	7,302,834 0 0 0 0 0 0 219,085 0 2,256,576	407 0 0 0 0 0 12 0 126
3569 6860 6861 6862	PAVING CONSTRUCTION COSTS  Paving Eng detailed design Paving Eng detailed design/Contingency Paving Eng general const. supervision Paving Eng quality assurance Paving Eng Surveying Paving Eng Residency Contingency Paving Eng Residency Contingency Paving Engineering Sub-total		322,929 22,605 6,782 6,459 12,917 1,615 6,297 56,674	9,374 2,812 2,678 5,357 6/0 2,611 23,503	128,179 8,973 2,692 2,564 5,127 641 2,499 22,495	2,921,538 204,508 61,352 58,431 116,862 14,608 56,970 512,730	528,204 36,974 11,092 10,564 21,128 2,641 10,300 92,700	5,320,761 372,453 111,736 106,415 212,830 26,604 103,755 933,794	133,091 9,316 2,795 2,662 5,324 665 2,595 23,357	125,166 8,762 2,628 2,503 5,007 626 2,441 21,967	97,209 6,805 2,041 1,944 3,888 486 1,896 17,060	67,500 4,725 1,418 1,350 2,700 338 1,316 11,846	9,778,495 684,495 205,348 195,570 391,140 48,892 190,681 1,716,126	38 11 11 22 3 11 96
6500			379,603	157,421	150,675	3,434,268	620,903	6,254,554	156,448	147,133	114,269	79,346	11,494,621	641
6520 6530 6540 6550	Operat.Cons - signing Operat.Cons - guard rail Operat.Cons - pavement markings		110,000 90,000 860 48,000 8,525 7,722 79,532	0 880 0 3,550 133 1,369	66,000 0 740 45,000 2,775 3,435 35,385	0 10,800 451,500 54,000 15,489 159,537	0 2,000 126,000 9,000 4,110 42,333	0 0 18,588 682,500 94,840 23,878 245,942	71,500 0 800 48,000 2,000 3,669 37,791	55,000 0 590 33,000 1,475 2,702 27,830	38,500 0 414 7,500 1,098 1,425 14,681	22,000 0 216 32,400 1,080 1,671 17,210	363,000 90,000 35,888 1,473,900 178,343 64,234 661,609	20 5 2 82 10 4 37
	OPERATIONAL CONSTRUCTION COSTS		344,639	5,932	153,336	691,326	183,443	1,065,748	163,760	120,597	63,618	74,577	2,866,974	160
3549 6840 6841 6842	Operat. Eng - detailed design Operat. Eng - detailed design/Contingency Operat. Eng - general const. supervision Operat. Eng - quality assurance Operat. Eng - surveying Operat. Eng - Residency Contingency Operational Enginering Sub-total		24,125 7,237 18,955 6,893 1,723 8,271 67,205	415 125 326 119 30 142 1,157	10,733 3,220 8,433 3,067 767 3,680 29,900	48,393 14,518 38,023 13,827 3,457 16,592 134,809	12,841 3,852 10,089 3,669 917 4,403 35,771	74,602 22,381 58,616 21,315 5,329 25,578 207,821	11,463 3,439 9,007 3,275 819 3,930 31,933	8,442 2,533 6,633 2,412 603 2,894 23,516	4,453 1,336 3,499 1,272 318 1,527 12,405	5,220 1,566 4,102 1,492 373 1,790 14,543	200,688 60,206 157,684 57,339 14,335 68,807 559,060	11 3 9 3 1 4 31
	Total Operational Const.& Eng.Costs		411,843	7,088	183,236	826,134	219,214	1,273,568	195,693	144,113	76,023	89,119	3,426,034	191
5202	RoadSide Cı - water		0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0	0 0 0 0 0	0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0	0 0 0 0	0 0 0 0 0
5220 5230 5201	RoadSide Cı - Contingency Road Side Construction Sub-total		0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0
2550	ROAD SIDE CONSTRUCTION COSTS		0	0	0			0		0		0	0	0
3559 6850 6851 6852	RoadSide Er - general const. supervision		0 0 0 0	0 0 0 0 0	0 0 0 0	0 0 0 0 0	0 0 0 0	0 0 0 0 0	0 0 0 0	0 0 0 0	0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0

ACTI COD Co Blk Es	onceptual Est. Divison\site st. # 6.14A Road Type	Peardonville New overpass and approaches 0 0 Section P.1	New Roadway underneath Peardonville Overpass 0 Section P.2	Livingstone Ave Realignment to Peardonville 0 0 Section 3.3	31+700 to 26+300 Westbound Widening Sections W.3 - W.1	33+700 to 32+700 West of Rail Overpass to East of McCallum Section W.0	35+974 to 26+300 Eastbound Widening Sections E.7 to E.1	Hwy 1 to Hwy 11 Ramp from EB to NB 0 0 Section H11.1	Hwy 11 to Hwy 1 Ramp from NB to EB 0 0 Section H11.2	33+500 to 32+700 West of Rail Overpass to East of McCallum Section H11.3	31+900 to 31+700 McCallum WB On Ramp Extension Section Mc.1 MR 16 OR	<b>17944</b> 0	Total Line Cost C/LM
Version	on Sept.1, 200 DESCRIPTION \Length	430 MR	440 MR	370 MR	5400 MR	1000 MR	9294 MR	400 MR	295 MR	207 MR	108 TR MR	17944	17944
	Road Side Engineering Sub-total	0	0	0	0	0	0	0	0	0	0	0	0
	Total Road Side Const.& Eng.Costs	0	0	0	0	0	0	0	0	0	0	0	0
====													
5300	OTHER CONSTRUCTION Other Const - water	0	0	0	0	0	0	0	0	0	0	ا ا	0
5304	Other Const - sanitary	0	0	0	0	0	0	0	0	0	0	0	0
	Other Const - storm	0	0	0	0	0	0	0	0	0	0	0	0
	Other Const - mobilization Other Const - utility contingency	0	0	0	0	0	0	0	0	0	0	0	0
3303	Other Const. Utilities Sub-total	0	0	0	0	0	0	0	0	0	0	0	0
E210	Other Const - railroads main & spur lines		0	0							0		
	Other Const - railroads main & spur lines Other Const - railroad crossings	0	0	0	0	0	0	0	0	0	0	"	0
5330		0	0	0	0	0	0	0	0	0	0	o o	0
		0	0	0	0	0	0	0	0	0	0	0	0
	Other Const - mobilization Other Const - Contingency	0	0	0	0	0	0	0	0	0	0	0	0
3333	Other Construction Sub-total	0	0	0	0	0	0	0	0	0	0	0	0
	OTHER CONSTRUCTION COSTS	0	0		0	0	0		0	0	0	0	
3570	Other Eng detailed design										0	0	
	Other Eng detailed design/Contingency	0	0	0	0	0	0	0	0	0	0	ő	0
6870	Other Eng general const. supervision	0	0	0	0	0	0	0	0	0	0	0	0
		0	0	0	0	0	0	0	0	0	0	0	0
	Other Eng surveying Other Eng Residency Contingency	0	0	0	0	0	0	0	0	0	0	0	0
0070	Other Engineering Sub-total	0	0	0	0	0	0	0	0	0	0	ő	ō
	Total Other Const.& Eng.Costs	0	0	0	0	0	0	0	0	0	0	0	0
3500	DETAILED DESIGN from 3510,3520,3540,3550,3570	4,996,118	71,380	116,601	1,667,874	509,865	3 539 500	497,112	148,243	76,887	29,266	11,652,845	649
3530	Geotech. En - detailed design	314,483	4,706	7,688	109,970	33,617	233,029	54,854	8,925	5,069	1,930	774,272	43
	Geotech. En - Contingency	94,345	1,412	2,306	32,991	10,085	69,909	16,456	2,677	1,521	579	232,282	13
	TOTAL DETAILED DESIGN COSTS	5,404,947	77,499	126,595	1,810,834	553,568	3,842,438	568,422	159,845	83,477	31,774	12,659,399	705
	RESIDENT ENGINEERING												
6800	from 6810,6820,6840,6850,6860,6870	4,090,070	70,587	117,761	1,657,871	508,816	3,510,936	431,891	129,675	77,082	29,796	10,624,485	
	TOTAL RESIDENT ENG. COSTS		70.587								29.796	10.624.485	592
	TOTAL RESIDENT ENG. COSTS	4,090,070	/0,58/	117,761	1,657,871	508,816	3,510,936	431,891	129,675	77,082	29,796	10,624,485	592
												0	
												0	0
	DADT 4 COUNTABY												
	PART 1 SUMMARY  CONSTRUCTION	37,113,258	603,385	985,634	14,408,680	4,359,931	30,935,549	3,827,460	1,144,225	649,929	247,385	94,275,436	5254
	ENGINEERING & SUPERVISION	7,606,880	185,632	248,276	3,548,435	980,218	7,173,372	851,719	275,748	157,248	64,966	21,092,493	1175
	CONTRACTUAL CONTINGENCY	13,416,041	236,705	370,173	5,387,135	1,602,045	11,432,676	1,403,754	425,992	242,153	93,705	34,610,379	1929
												0	0
	CONSTRUCTION COST TOTAL	58,136,179	1,025,722	1,604,083	23,344,250	6,942,194	49,541,598	6,082,932	1,845,964	1,049,330	406,056	149,978,307	8358
2000	PROJECT MANAGEMENT Project Man office costs wages	1,308,064	23,079	36,092	525,246	156,199	1,114,686	136,866	41,534	23,610	9,136	3,374,512	188
2062	Project Man office costs wages  Project Man office costs - expenses	1,308,064	23,079	36,092	525,246	156,199	1,114,000	130,000	41,534	23,610	9,136	0,3/4,512	0
2063	Project Man printing costs	0	0	0	0	0	0	0	0	0	0	0	0
2061		0	0	0	0	156 100	1 114 696	126.966	0	0	0	0 3,374,512	0
	Project Manager Sub-total	1,308,064	23,079	36,092	525,246	156,199	1,114,686	136,866	41,534	23,610	9,136	3,3/4,512	188
	Client - office costs wages	1,162,724	20,514	32,082	466,885	138,844	990,832	121,659	36,919	20,987	8,121	2,999,566	167
	Client - office costs - expenses Client - printing costs	0	0	0	0	0	0	0	0	0	0	0 0	0
	Client - printing costs  Client - general	0	0	0	0	0	0	0	0	0	0	"	0
2011	Client Sub-total	1,162,724	20,514	32,082	466,885	138,844	990,832	121,659	36,919	20,987	8,121	2,999,566	167

ACT COI	Planning\Data Parsons (2016Dollars) IVITY DE	- MoT A&W Contract #15/SWF - Hi \(\alpha\)Costing/March 29th\(\partial\)Package 6 - I \(\text{i: Hwy 1 Widening}\) \(\text{Package 6 - Mt Lehman to H}\) \(\text{EST.DATE April 4, 2016}\) \(\text{R3 DATE: Sept 15, 2016}\)	Between Mt Lehman	Peardonville New overpass and approaches 0	New Roadway underneath Peardonville Overpass 0	Livingstone Ave Realignment to Peardonville 0 0	31+700 to 26+300 Westbound Widening Sections	33+700 to 32+700 West of Rail Overpass to East of McCallum	35+974 to 26+300 Eastbound Widening Sections	Hwy 1 to Hwy 11 Ramp from EB to NB 0	Hwy 11 to Hwy 1 Ramp from NB to EB 0 0	33+500 to 32+700 West of Rail Overpass to East of McCallum	31+900 to 31+700 McCallum WB On Ramp Extension		Total Line Cost C/LM
Blk E Versi	onceptual Est. st. # 6.14A on Sept.1, 20	1	Divison\site Road Type CRIPTION \Length	21 430	Section P.2 2 440	Section 3.3 2 370	W.3 - W.1 16 5400	Section W.0 16 1000	E.7 to E.1 16 9294	Section H11.1 16 400	Section H11.2 16 295	Section H11.3 16 207	Section Mc.1 MR 16 OR 108 TR	<b>17944</b> 0 17944	17944
2072 2073	Public Rel. Public Rel. Public Rel. Public Rel.	- wages & expenses - adv., media, displays - opening ceremonies - general tions Sub-total		MR 348,817 0 0 0 348,817	MR 6,154 0 0 0 6,154	9,624 0 0 0 9,624	MR 140,065 0 0 0 140,065	MR 41,653 0 0 0 41,653	MR 297,250 0 0 0 297,250	MR 36,498 0 0 0 36,498	MR 11,076 0 0 0 11,076	MR 6,296 0 0 0 6,296	2,436 0 0 0 2,436	899,870 0 0 0 899,870	50 0 0 0 0
	Legal Costs Legal Costs Legal Costs			40,695 0 40,695	718 0 718	1,123 0 1,123	16,341 0 16,341	4,860 0 4,860	34,679 0 34,679	4,258 0 4,258	1,292 0 1,292	735 0 735	284 0 284	104,985 0 104,985	6 0 6
	Insurance Insurance Legal Costs			348,817 0 348,817	6,154 0 6,154	9,624 0 9,624	140,065 0 140,065	41,653 0 41,653	297,250 0 297,250	36,498 0 36,498	11,076 0 11,076	6,296 0 6,296	2,436 0 2,436	899,870 0 899,870	50 0 50
2099		agement Contingency		962,735	16,986	26,564	386,581	114,963	820,409	100,733	30,569	17,377	6,724	2,483,641	138
		OJECT MANAGEMENT COST		4,171,852	73,606	115,109	1,675,183	498,172	3,555,105	436,511	132,466	75,300	29,139	10,762,443	600
4000 4010		LAND Mrkt,ROW,Serv,Imp.V,Ease. Sub-total	C,T	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0
4030 4040 4050 4060 4070 4080	Land(Code Land(Code Land(Code Land(Code Land(Code	<ul> <li>-Pro.Man,P.Tax,Util,Security</li> <li>-Not Used</li> <li>-Not Used</li> <li>-Acq.F,M/Sal,TrvIV,Cntr.S,Ap</li> </ul>	1	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
	Associated	costs-sub-total		0	0	0	0	0	0	0	0	0	0	0	0
4099	Land Contir	ngency Sub-total		0	0	0	0	0	0	0	0	0	0	0	0
9800		ND COSTS  MANAGEMENT RESERVE		0	0	0	0	0	0	0	0	0	0	0	0
3530	MAN. RES. MAN. RES. MAN. RES. MAN. RES. MAN. RES. MAN. RES. MAN. RES. MAN. RES. MAN. RES. MAN. RES.	- planning - preliminary design - utility construction - grade construction - structural construction - paving construction - operation construction - roadside construction - other construction - project management		0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0
		NAGEMENT RESERVE		0	0	0	0	0	0	0	0	0	0	0	0
9900		SS ESCALATION		0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0 0	0 0 0 0 0	0 0 0 0 0

	Q:\SW\1200 -	MoT A&W Contract #15\SWF - Highway 1 Functional											1 '	
File:	Planning\Data	Costing March 29th [Package 6 - Between Mt Lehman	Peardonville	New Roadway	Livingstone Ave	31+700	33+700	35+974	Hwy 1 to Hwy 11	Hwy 11 to Hwy 1	33+500	31+900		Total
		Hwy 1 Widening	New overpass	underneath	Realignment	to 26+300	to 32+700	to 26+300	Ramp from EB	Ramp from NB	to 32+700	to 31+700		Line
(		Package 6 - Mt Lehman to Hwy 11	and approaches	Peardonville	to Peardonville	Westbound	West of Rail	Eastbound	to NB	to EB	West of Rail	McCallum WB		Cost
ACTI		EST.DATE April 4, 2016	0	Overpass	0	Widening	Overpass to East	Widening	0	0	Overpass to East	On Ramp		
COD	E	R3 DATE: Sept 15, 2016	0	0	0	Sections	of McCallum	Sections	0	0	of McCallum	Extension		C/LM
	nceptual Est.	Divison\sit		Section P.2	Section 3.3	W.3 - W.1	Section W.0	E.7 to E.1	Section H11.1	Section H11.2	Section H11.3	Section Mc.1 MR	17944	
Blk Es	st. # 6.14A	Road Typ		2	2	16	16	16	16	16	16	16 OR	0	
Version	on Sept.1, 20	DESCRIPTION \Lengti	430	440	370	5400	1000	9294	400	295	207	108 TR	17944	17944
			- <u>MR</u>	MR	MR	MR	MR	MR	MR	MR	MR	MR		
	2014-2015		0	0	0	0	0	0	0	0	0	0	0	0
	TOTAL ESC	CALATION	0	0	0	0	0	0	0	0	0	0	0	0
====	=======		= =====================================											
	PART 2 SU	IMMARY NON-CONSTRUCTION COSTS												
		Non-Construction	3,209,117	56,620	88,545	1,288,603	383,209	2,734,696	335,778	101,897	57,923	22,414	8,278,803	461
		Non-Const. Contingency	962,735	16,986	26,564	386,581	114,963	820,409	100,733	30,569	17,377	6,724	2,483,641	138
		TOTAL NON-CONSTRUCTION COSTS	-	73.606	445 400	4.675.400	400 470	0.555.405	400 544	400.400	75.300	00.400	10.700.440	600
		TOTAL NON-CONSTRUCTION COSTS	4,171,852	/3,606	115,109	1,675,183	498,172	3,555,105	436,511	132,466	75,300	29,139	10,762,443	
====	DIVISION T	OTAL FOR ROAD TYPE	62,308,031	1,099,328	1,719,192	25,019,433	7,440,366	53,096,703	6,519,443	1,978,430	1,124,630	435,195	160,740,751	8958
	DIVISION I	OTAL FOR HOAD TIFE	02,300,031	1,000,320	1,/19,192	20,010,400	7,440,300	00,000,700	0,019,440	1,970,430	1,124,030	400,100	100,740,751	9936

# APPENDIX C

Environmental & Aboriginal Consultation Information Requirements



#### Annex D - Environmental and Aboriginal Consultation Information Requirements

As part of the application process for funding, applicants are required to complete the following questionnaire, found in Annex D of the Business Case Guide, in order for Infrastructure Canada (INFC) to determine if the *Canadian Environmental Assessment Act*, 2012 (CEAA, 2012) and/or environmental assessment process in Northern Canada apply to the project. In addition, the information provided will also be used by INFC to determine if there is a requirement to consult with Aboriginal Groups.

All yellow highlighted text is instructional and is provided to explain in more detail the type of information requested by INFC. This instructional text can be deleted once information is provided in the appropriate boxes. Please provide your response in the spaces provided in the boxes, and use as much space as necessary.

Note that if you have any questions filling out the questionnaire; please submit your questions to the following email address: <a href="mailto:INFC.AboriginalConsultEnv-consultautochtonesenv.INFC@canada.ca">INFC.AboriginalConsultEnv-consultautochtonesenv.INFC@canada.ca</a>.

#### General information

Project Name: Highway 1 Widening (216 Street to Whatcom Road)

Project Proponent: BC Ministry of Transportation and Infrastructure

<u>Contact person</u> for any question Infrastructure Canada could have regarding the <u>environmental assessment and aboriginal consultation:</u>

Name: David Mintak

Title: Regional Manager, Project Delivery

Address: 310 - 1500 Woolridge, Coquitlam, B.C. V3K 0B8

Phone: (604) 527-2171

Email: David.Mintak@gov.bc.ca

**Note** (scope change): If you are completing this questionnaire due to a proposed project amendment for a project already submitted to Infrastructure Canada (INFC), please only include the amended project information.

#### Project and existing environment description

The project scope will generally include the widening of Highway 1 by adding one lane in each direction into the median between 216 Street and eventually Whatcom Road with a focus on the segment extending to Highway 11. The segment of highway between Highway 11 and Whatcom Road will be the subject of a further study. In addition to the addition of one lane in each direction of travel, the project will include the demolition of existing underpasses and reconfiguration of two interchanges, the 232 Street interchange



and the 264 Street interchange. In addition, to accommodate the Highway 1 widening a number of grade separated crossing will need to be upgraded to achieve added crossing width and/or higher clearance under the structure. Therefore the scope of the Highway 1 Widening project will also include the following key elements:

- Demolition and reconstruction of the Glover Road underpass structure;
- Demolition and reconstruction of the rail underpass structures at the CP Rail lane (Roberts Bank Corridor);
- Widening of the two overhead structures at Bradner Road;
- Upgrade of the entrance and exit ramps to the Bradner Rest Area along the westbound lanes of Highway 1;
- Demolition and reconstruction of the Peardonville Road underpass structure;
- New structure for the eastbound off-ramp to Highway 11; and
- Upgrade of the Highway 11 on-ramp to Highway 1 eastbound.

#### Description of the existing environment:

This section of Highway 1 passes through suburban, rural agricultural, and urban areas within the municipalities of the Township of Langley and the City of Abbotsford. The majority of the proposed works is within the existing right-of-way of the highway or the cross streets. However, a number of creeks and drainage channels cross the existing highway and the widening into the median may result in some impacts. No negative impacts are anticipated with respect to the residential areas, business and industrial parks, or agricultural areas abutting the highway corridor.

A major railway crossing, CP Rail – Roberts Bank Rail Corridor, will be affected as the existing box structures will need to be removed to accommodate the additional highway lanes. A new rail bridge structure is included in the project scope.

#### **Project Location Part**

PL.1.1: Would any part of the project or activities be located on:		
Yes No V	Federal land. If yes, provide details regarding the federal lar	nd administrator:
Yes 🔽 No 🗆	Provincial land. If yes, provide details:	
Yes No V	Indian Reserve land. If yes, provide details:	
If you answered	Is the entire project footprint located on that land?	Yes No
" <u>yes</u> " to any of	If not, please indicate the portions that will take place on	
the above.	that land (provide a map).	



PL.1.2: Would any part of the project or activities be located in:		
Yes No V	Internal waters of Canada, in any area of the sea not within a province	
	Internal waters refers to: the internal waters of Canada as determined under	
	the <u>Oceans Act</u> , including the seabed and subsoil below and the airspace	
	above those waters.	
Yes No V	The territorial sea of Canada, in any area of the sea not within a province	
	Townstander and the second sec	
	Territorial sea refers to:	
	The territorial sea of Canada as determined under the <u>Oceans Act</u> , including	
	the seabed and its subsoil below and the airspace above that sea.	
Yes No V	The exclusive economic zone of Canada	
	Exclusive economic zone refers to:	
	The exclusive economic zone of Canada as determined under the <u>Oceans Act</u> ,	
	including the seabed and its subsoil.	
Yes No V	The continental shelf of Canada	
	Continental shelf refers to: the continental shelf of Canada as determined	
	under the <u>Oceans Act</u> .	
If you answered	Please provide the information regarding the land administrator.	
"yes" to any of		
the above:		



**PL.2** In order to facilitate and accelerate INFC's assessment of your application for funding, please provide an accurate project location in order for INFC to geographically locate your project.

Option 1: Project with a fixed address		
Address of the project	Location 1	Location 2
Civic Number:		
Unit/Suite/Apt:		
Street Name:		
Municipality:		
County:		
Province:		
Postal Code:		
Project Longitude:49°06'05.7"N		
Project Latitude: 122°29'31.6"W		
-		
Project Latitude:		

#### Option 2: Project with no fixed address or multiple components

Please indicate, <u>for each project component</u>, any points of interest, intersections, major highways or streets, or other physical characteristics located in the vicinity of the project (e.g. near airport, adjacent to Lions Gate Bridge, 3 km east from Centennial Park, at intersection of Fifth and Queen, etc.)

Component A: Highway 1 widening from 216 Street to Whatcom Road (section to Highway 11 is current focus). The project is located within the Township of Langley and the City of Abbotsford.

Component B: 232 Street / Highway 1 interchange Component C: 264 Street / Highway 1 interchange

# PL.3 Project Location Documents A project location map, as a minimum, has been included with this questionnaire. If available, include also any other additional project map (e.g. site plan, etc.) that may be useful in locating the project. Map Attached



# **Environmental Requirement Part**

ER.1.1: Does any part of your project involve the construction, operation, decommissioning		
or abandonment of the following infrastructure?		
Yes No 🔽	Electrical transmission lines	
Yes No 🔽	Electrical generating facility	
Yes No 🔽	Structure for the diversion of water including dam, dyke or reservoir	
Yes No 🔽	Canal, lock or structure to control water level	
Yes No 🔽	Oil and gas pipeline	
Yes No 🔽	Marine terminal	
Yes 🗹 No 🗆	Railway line and / or Railway yard	
Yes 🗹 No 🗆	All season public highway	
Yes No 🔽	Aerodrome or airport runway	
Yes No 🔽	Hazardous waste facility	
Yes No 🔽	Waste management facility	
Yes No 🔽	Industrial facility	

ER.1.2: Are any part of the project or activities proposed within:		
Yes No V	A wildlife area	
	A wildlife area means: (according to the wildlife areas listed in Schedule 1 of the Wildlife Area Regulations).	
	To use this list, find the section corresponding to the province in which the project is located and then determine if the project is located in one of the wildlife areas listed. If necessary, the cadastral lot numbers can be used.	
Yes No V	A migratory bird sanctuary	
	A migratory bird sanctuary means: (according to the migratory bird sanctuaries listed in the schedule of the <u>Migratory Bird Sanctuary Regulations</u> ).	
	To use this list, find the section corresponding to the province in which the project is located and then determine if the project is located in one of the bird sanctuaries listed. If necessary, the geographical coordinates expressed in latitude and longitude can be used.	



ER.1.3: Is the project a designated project according to the Regulations Designating			
Physical Activities*?			
http://laws-lois.justice.gc.ca/eng/regulations/SOR-2012-147/index.html			
If a project appears on the list, it will likely be considered a designated project and has to be			
	referred to the Canadian Environmental Assessment Agency. Should this be the case, it is		
Protect.	you contact them as soon as possible to confirm their requirement and process.		
Yes	Please elaborate:		
No 🔽			
Unknown 🗆	It is possible that the project's status in the Regulations Designating Physical		
	Activities is unknown at the time of the application.		
ER.1.4: If you	have answer yes to previous question ER1.3 (i.e. the project is a designated		
	ou provided the Canadian Environmental Assessment Agency with a project		
description as p	per Section 8(1) of the Canadian Environmental Assessment Act, 2012?		
Yes 🗆 No 🗀			
To learn more	about the information required by the Canadian Environmental Assessment		
Agency (Agency	), please refer to the <u>Prescribed Information for the Description of a Designated</u>		
Project Regulati	ons		
ER.2: Does th	ne project (either in full or in part) require an environmental assessment		
	rn regime or other regime?		
Yes 🗆			
	Please elaborate:		
No I	Please elaborate:		
No 🗹	Please elaborate:		
	ic concerns expected as a result of this project?		
ER.3: Are publ	ic concerns expected as a result of this project?		
ER.3: Are publ	ic concerns expected as a result of this project?  y have potential to cause significant public concern. Here is a non-exhaustive		
ER.3: Are publ	ic concerns expected as a result of this project?  y have potential to cause significant public concern. Here is a non-exhaustive		
ER.3: Are publ The project ma list of examples	ic concerns expected as a result of this project?  y have potential to cause significant public concern. Here is a non-exhaustive :		
ER.3: Are publ The project ma list of examples •Water and/or	ic concerns expected as a result of this project?  y have potential to cause significant public concern. Here is a non-exhaustive:  r land use disputes and the possible cumulative effects of an unequal		
ER.3: Are publication of a distribution of a surface of the control of the contro	ic concerns expected as a result of this project?  y have potential to cause significant public concern. Here is a non-exhaustive:  r land use disputes and the possible cumulative effects of an unequal access rights to the land or water in question;		
ER.3: Are publication of a superscript of the project magnification of a superscript of the publication of the pub	ic concerns expected as a result of this project?  y have potential to cause significant public concern. Here is a non-exhaustive:  r land use disputes and the possible cumulative effects of an unequal access rights to the land or water in question;  fety risks from potential accidents (e.g. potential spills in water bodies, etc.);		
ER.3: Are published for the project may list of examples  •Water and/ordistribution of a substitution of the earth and substit	ic concerns expected as a result of this project?  y have potential to cause significant public concern. Here is a non-exhaustive:  r land use disputes and the possible cumulative effects of an unequal access rights to the land or water in question;		
ER.3: Are publication of a superscript of the project magnification of a superscript of the publication of the pub	ic concerns expected as a result of this project?  y have potential to cause significant public concern. Here is a non-exhaustive:  r land use disputes and the possible cumulative effects of an unequal access rights to the land or water in question;  fety risks from potential accidents (e.g. potential spills in water bodies, etc.);		
ER.3: Are publication of a stribution of the electrication of the electrication.	ic concerns expected as a result of this project?  y have potential to cause significant public concern. Here is a non-exhaustive:  r land use disputes and the possible cumulative effects of an unequal access rights to the land or water in question;  fety risks from potential accidents (e.g. potential spills in water bodies, etc.);  e cultural values of local communities;		
ER.3: Are public is of examples  •Water and/ordistribution of a example of the ex	ic concerns expected as a result of this project?  y have potential to cause significant public concern. Here is a non-exhaustive:  r land use disputes and the possible cumulative effects of an unequal access rights to the land or water in question;  fety risks from potential accidents (e.g. potential spills in water bodies, etc.);  e cultural values of local communities;		
ER.3: Are public is of examples  •Water and/ordistribution of a example of the ex	ic concerns expected as a result of this project?  y have potential to cause significant public concern. Here is a non-exhaustive:  r land use disputes and the possible cumulative effects of an unequal access rights to the land or water in question;  fety risks from potential accidents (e.g. potential spills in water bodies, etc.);  e cultural values of local communities;		
ER.3: Are publication of a stribution of a stribution of a stribution of the stribut	ic concerns expected as a result of this project?  y have potential to cause significant public concern. Here is a non-exhaustive:  r land use disputes and the possible cumulative effects of an unequal access rights to the land or water in question;  fety risks from potential accidents (e.g. potential spills in water bodies, etc.);  the cultural values of local communities;  concerned about the project, information on the nature of the concern and any information must be provided to INFC.		
ER.3: Are public is a contract of examples  • Water and/or distribution of a contract of the electric of the e	ic concerns expected as a result of this project?  y have potential to cause significant public concern. Here is a non-exhaustive:  r land use disputes and the possible cumulative effects of an unequal access rights to the land or water in question;  fety risks from potential accidents (e.g. potential spills in water bodies, etc.);  e cultural values of local communities;		



ER.4.1: Are environmental issues expected as a result of this project?			
Yes 🔽	Please elaborate: The existing highway shoulder and median materials could contain heavy metals and hydrocarbons from vehicle emissions over the past several decades. However, it is anticipated that there is insufficient amounts to classify the median and shoulder materials as hazardous waste.		
No 🗆	·		

	any part of the project located in whole or in part on land potentially d by previous activities:
Yes 🗆	Please elaborate:
No 🔽	

ER.4.3: Is	an environi	mental site assessment available for this project regarding
contaminated site(s):		
Yes 🗆	No 🔽	Phase I
Yes 🗆	No 🗹	Phase II
Yes 🗆	No 🗹	Phase III
If you answered "yes" to any of the above, please provide copies of all reports related to the		
project, if not already provided. If the report(s) is/are at the development stage, please indicate the phase, and when a copy will be provided to INFC.		

ER.4.4: Do assessment?	es the project (either in full or in part) require a provincial environmental
Yes 🗆	If not already provided, please provide copies of all reports related to the project. If the report(s) is/are at the development stage, please indicate when it/they will be completed and when a copy will be provided to INFC.
No 🔽	

#### **Aboriginal Consultation Part**

This section contains a number of questions aimed at developing a better overview of the types of activities and/or work that will be carried out to determine the potential impact it could have on the Aboriginal or treaty rights of Aboriginal peoples. To determine whether the Crown conduct could have an adverse impact on established or potential Aboriginal or treaty rights, information must be compiled on those rights, which could include the right to hunt, fish, trap, gather and trade, and may either be established by a court or in a treaty, or may be asserted by an Aboriginal group, for example, in litigation or for the purpose of negotiating a treaty.

This step must be taken into consideration very early on in the process otherwise project delays can be expected if consultation is not completed satisfactorily or in a timely manner.



### AC.1: Activities Related to the Project that could potentially impact Aboriginal rights. Examples of traditional Aboriginal activities can vary, and include gathering wild mushrooms and medicinal herbs on a river bank, fishing in a salmon river, hunting moose in the forest, and may involve ceremonial sites and former burial grounds. If one or more of the questions in this part are answered in the affirmative, please provide a description of the activity or activities in the last line of the table. Yes 🔽 No 🔲 Does the project involve works or activities on, under, over, through or across a water body such as a wetland, stream, river or lake? Check all that apply. Fresh water: Stream Lake Wetland River Pond Reservoir Active Floodplain Fish Bearing Watercourse Coastal and Marine: Beach Cove ☐ Mud Flat ☐ Salt Marsh ☐ Bay ☐ Fstuary ☐ Exposed Coastline Estuary Fish Bearing Watercourse Other: Please describe: No 🔽 Yes 🔲 Can the work proposed have upstream or downstream impacts (e.g. change in water or temperature level upstream that could result in positive or negative impacts downstream, change in the turbidity, etc.)? Yes 🔲 No 🔽 Are there activities proposed that may affect aboriginal traditional activities. Check all activities that apply. Fishing (e.g., preventing access to a fishing area or work in a waterbody such as river, lake, stream, culverts) Hunting (e.g., preventing access to a hunting area or clearing of forest or other vegetation etc.) ☐ Gathering (e.g., preventing access to a gathering area or clearing of forest or other vegetation etc.) Other (e.g. work close to or preventing access to sites of cultural/historical/archeological/ceremonial significance project etc.) No 🔽 Yes 🗌 Is the project (in full or in part) occurring on undisturbed or undeveloped land? If yes, please provide information about how much land will be affected



		by the project in the appropriate space. Disturbed and/or developed land may include land that has undergone deforestation, land previously used for agricultural purposes, or land that has been built up (e.g. buildings were previously constructed upon, etc.).
Yes 🗆	No 🔽	Is any component of the proposed project located outside the existing infrastructure footprint (build up footprint)?
Yes 🔽	No 🗆	Are there any relevant project activities that might affect other aspects of the environment (e.g. increases sound and/or noise levels, creates barriers to or limits access to harvesting areas, adds runoff to a watercourse, involves excavation)?

If you answered "<u>yes</u>" to any of the above, please provide details. The existing highway will be widened by one lane in each direction which may increase runoff into the adjacent ditches and watercourses. In some areas of the median, excavation and the placement of fill will be required to widen the highway. Higher traffic volumes are expected in future years which will increase traffic noise, however, no encroachment to existing development is proposed as the majority of the construction will take place in the existing median.

AC.2: Has another federal, provincial or territorial government entity indicated that Aboriginal consultation is required for this project?		
Yes 🔽	Please specify. It is anticipated that consultation with adjacent Aboriginal groups will be required in the next phases of the project. No engagement with any Aboriginal groups has taken place during the project planning phase.	
No 🗆		
Unknown 🗆		

AC.3.1: Has	s the <u>province (or territory)</u> been in contact with any Aboriginal groups is project?
Yes 🗆	Please provide a summary of the consultation activities completed to date. If available, please provide details such as if any concerns were raised by Aboriginal groups, the nature of the concerns raised, and include in an attachment any information that may be useful (e.g. consultation plan, consultation summary, contact information, letters, emails, public notices, and any other types of communications).
No 🗹	



AC.3.2: Have you been in contact or plan to contact any Aboriginal groups regarding this		
project?		
Yes 🔽	Please provide a summary of the consultation activities completed to date. If available, please provide details such as if any concerns were raised by Aboriginal groups, the nature of the concerns raised, and include in an attachment any information that may be useful (e.g. consultation plan, consultation summary, contact information, letters, emails, public notices, and any other types of communications).	
No 🗆	It is anticipated that consultation with adjacent Aboriginal groups will be undertaken in the next phases of the project. No engagement with any Aboriginal groups has taken place during the project planning phase.	

#### AC.4: Involvement of the Crown -

Other Federal or Provincial Departments or Agencies may be involved in the project (e.g., if a <u>permit, authorization, land transfer agreement, lease</u>, etc. is required ), such as, but not limited to:

The purpose of this section is to identify if other federal or provincial departments or agencies may be undertaking Aboriginal consultation activities as a result of their involvement in the project (e.g., issuing a permit and/or authorization).

If other authorities are involved, it is important to identify them, and to describe their role, particularly if they have to issue or have issued a permit and/or authorization. This is necessary for a number of reasons: to avoid procedural duplication, to enable the coordinated actions of the various authorities involved and to avoid submitting unnecessary repetitive requests to the Aboriginal groups concerned.

The information provided about the authorities and their actual or potential involvement in the project will help INFC to confirm their collaboration as early on in the process as possible.

Yes 🗆	No 🗆	Unknown 🗹	Fisheries and Oceans Canada (e.g. Fisheries Act)	
Yes 🗆	No 🗹	Unknown 🗆	Transport Canada (e.g. Navigation Protection Act)	
Yes 🗆	No 🗹	Unknown 🗆	Natural Resources Canada (e.g. Explosives Act)	
Yes 🗆	No 🗆	Unknown 🔽	Environment Canada (e.g. Species at Risk Act, Migratory Birds Convention Act, Canadian Environmental Protection Act)	
Yes 🗆	No 🗹	Unknown 🗆	Parks Canada Agency	
Yes 🗆	No 🗆	Unknown 🔽	Other departments (e.g. federal department, provincial department, funding department,) If applicable, please identify the federal department or agency and approval required.	

If you answered "<u>yes</u>" to any of the above, please describe the involvement of the identified department(s)/agency(s) in detail. No other Federal or Provincial Agencies have been involved at this time (during the planning phase).

Please provide contact information for each department identified so INFC can coordinate with them to avoid delays and duplication.



## AC.5: Provincial (or territorial) permits

Please list all provincial (or territorial) permits that will be required for the project.

Unknown at this time.

Please provide contact information for each department already contacted so INFC can coordinate with them to avoid delays and duplication.

#### **Declaration of Information**

Please check boxes to acknowledge you understand and/or agree to the following statements:
□ INFC may have a duty to consult and, where appropriate, accommodate aboriginal groups, when the Crown contemplates conduct (such as providing funding) that might adversely impact potential or established Aboriginal or Treaty rights. INFC will rely to the extent possible on other processes that included Aboriginal consultation (e.g., a provincial environmental assessment process). However, it is understood that INFC may delegate certain procedural responsibilities to the proponent and the proponent will assist or carry out various aspects of consultation (e.g., the gathering of information). Note that a Proponent Guide and Toolkit for Aboriginal Consultation Process will be provided at the appropriate time.
$\square$ It is understood that INFC may not enter into a contribution agreement until such time as INFC has determined that its Aboriginal consultation obligations have been met.
☐ I hereby certify that the information provided is accurate to the best of my knowledge and I understand that inaccurate information may result in the requirement for additional environmental and/or aboriginal consultation review.
Questionnaire completed by:
Signature:
Date:

# Appendix B

MoTI Responses to Infrastructure Canada Annex D - Environmental and Aboriginal Consultation: Truck Parking Facility.

#### **General information**

Project Name: North Surrey Truck Parking Project

Project Proponent: British Columbia (BC) Ministry of Transportation and Infrastructure

<u>Contact person</u> for any question Infrastructure Canada could have regarding the <u>environmental</u> assessment and aboriginal consultation:

Name: Derek Drummond

Address: 300-175 2nd Avenue Kamloops BC V2C 5W1

Phone: 250-571-8708

Email: Derek.Drummond@stantec.com

**Note (scope change)**: If you are completing this questionnaire due to a proposed project amendment for a project already submitted to Infrastructure Canada (INFC), please only include the amended project information.

#### Project and existing environment description

#### **Project Description:**

The BC Ministry of Transportation & Infrastructure is proposing a commercial truck parking facility in North Surrey, BC, to improved truck parking in the Lower Mainland as part of the Ministry's 10-year strategic plan titled 'BC on the Move'. The identified project site is owned by the Province and would involve the development of approximately 158 commercial truck parking stalls and approximately 40 passenger vehicle parking stalls. The project will include new pavement structure including drainage systems with oil-water separators, water and sanitary hookups for trucks, lighting, fencing, plumbed restroom facilities, a security attendant kiosk, and waste receptacles. Direct access to the project site is proposed from Highway 17 by way of a protected-T intersection with a half traffic signal to accommodate safe left turn movements in and out of the Truck Parking Site.

The proposed Project is located on a site that was previously used as a placement area for excavated surplus soils resulting from construction of the South Fraser Perimeter Road (SFPR). The Site was planted after the placement of surplus excavated soil from SFPR and is currently in an early successional state and structural stage. In its current state, much of the replanted area provides limited ecological value with modest terrestrial habitat for birds and small mammals.

Surrounding the previously disturbed areas of the site, Bon Accord Creek and Landfill Creek and their tributaries adjacent to the west of the Site provide aquatic habitat for fish and amphibians.

#### **Project Location Part**

PL.1.1: Would any part of the project or activities be located on:			
Yes No 🗹	Federal land. If yes, provide details regarding the federal land administrator:		
Yes No No	Provincial land. If yes, provide details: BC Transportation Financing Authority (BCTFA) owned		
Yes □ No ☑ Indian Reserve land. If yes, provide details:			
•	Is the entire project footprint located on that land? If not, please indicate the portions that will take place on that land (provide a map).	Yes 🔽 No 🗆	

PL.1.2: Would an	y part of the project or activities be located in:
Yes □ No □	Internal waters of Canada, in any area of the sea not within a province
	Internal waters refers to: the internal waters of Canada as determined under
	the <u>Oceans Act</u> , including the seabed and subsoil below and the airspace
	above those waters.
Yes No V	The territorial sea of Canada, in any area of the sea not within a province
	Territorial sea refers to:
	The territorial sea of Canada as determined under the Oceans Act, including
	the seabed and its subsoil below and the airspace above that sea.
Yes No 🗹	The exclusive economic zone of Canada
	Exclusive economic zone refers to:
	The exclusive economic zone of Canada as determined under the Oceans Act,
	including the seabed and its subsoil.
Yes No V	The continental shelf of Canada
	Continental shelf refers to: the continental shelf of Canada as determined
	under the Oceans Act.
If you answered	Please provide the information regarding the land administrator.
"yes" to any of	
the above:	

**PL.2** In order to facilitate and accelerate INFC's assessment of your application for funding, please provide an accurate project location in order for INFC to geographically locate your project.

Option 1: Project with a fixed address		
Address of the project Civic Number: 11688 Unit/Suite/Apt:	Location 1	Location 2
Street Name: Highway 1 Municipality: Surrey	Highway 17 Surrey	
County: Province: BC Postal Code:	ВС	
Project Longitude: 49.213221 degrees Project Latitude:122.801480 degrees		

#### Option 1: Project with no fixed address or multiple components

Please indicate, <u>for each project component</u>, any points of interest, intersections, major highways or streets, or other physical characteristics located in the vicinity of the project (e.g. near airport, adjacent to Lions Gate Bridge, 3 km east from Centennial Park, at intersection of Fifth and Queen, etc.)

Component A: The Site is located east of the Port Mann Bridge, between Highway 17 and the Canadian National Railway (CN) tracks along the Fraser River (PID 026-242-991).

Component B:

Component C:

PL.3 Project Location Documents	
A project location map, as a minimum, has been included with this questionnaire.	Yes 🗹
If available, include also any other additional project map (e.g. site plan, etc.) that may be useful in locating the project.	

#### **Environmental Requirement Part**

ER.1.1: Does any part of your project involve the construction, operation, decommissioning		
or abandonment of the following infrastructure?		
Yes 🗆 No 💆	Electrical transmission lines	
Yes 🗆 No 🗹	Electrical generating facility	
Yes 🗆 No 💆	Structure for the diversion of water including dam, dyke or reservoir	
Yes 🗆 No 🗹	Canal, lock or structure to control water level	
Yes 🗆 No 💆	Oil and gas pipeline	
Yes 🗆 No 💆	Marine terminal	
Yes 🗆 No 💆	Railway line and / or Railway yard	
Yes 🗆 No 💆	All season public highway	
Yes 🗆 No 💆	Aerodrome or airport runway	
Yes 🗆 No 💆	Hazardous waste facility	
Yes 🗆 No 🗹	Waste management facility	
Yes 🗆 No 🗹	Industrial facility	

ER.1.2: Are an	y part of the project or activities proposed within:
Yes 🗆 No 🗹	A wildlife area
	A wildlife area means: (according to the wildlife areas listed in Schedule 1 of the Wildlife Area Regulations).
	To use this list, find the section corresponding to the province in which the project is located and then determine if the project is located in one of the wildlife areas listed. If necessary, the cadastral lot numbers can be used.
Yes 🗆 No 💆	A migratory bird sanctuary
	A migratory bird sanctuary means: (according to the migratory bird sanctuaries listed in the schedule of the <u>Migratory Bird Sanctuary Regulations</u> ).
	To use this list, find the section corresponding to the province in which the project is located and then determine if the project is located in one of the bird sanctuaries listed. If necessary, the geographical coordinates expressed in latitude and longitude can be used.

ER.1.3: Is the project a designated project according to the Regulations Designating			
	Physical Activities*?		
*http://laws-lois.justice.gc.ca/eng/regulations/SOR-2012-147/index.html			
	pears on the list, it will likely be considered a designated project and has to be		
	Canadian Environmental Assessment Agency. Should this be the case, it is		
	you contact them as soon as possible to confirm their requirement and process.  Please elaborate:		
Yes L No Z	Flease elaborate.		
	It is a social to the total and analysis of a total and the Demillation of Design at in an Objection		
Unknown 🗆	It is possible that the project's status in the Regulations Designating Physical		
	Activities is unknown at the time of the application.		
project), have y	have answer yes to previous question ER1.3 (i.e. the project is a designated you provided the Canadian Environmental Assessment Agency with a project per Section 8(1) of the Canadian Environmental Assessment Act, 2012?		
105	, 2		
	about the information required by the Canadian Environmental Assessment		
	y), please refer to the <u>Prescribed Information for the Description of a Designated</u>		
<u>Project Regulati</u>	<u>ions</u>		
	he project (either in full or in part) require an environmental assessment		
	rn regime or other regime?		
Yes _	Please elaborate:		
No 🗹			
ER.3: Are publ	lic concerns expected as a result of this project?		
The musicut was			
list of examples	y have potential to cause significant public concern. Here is a non-exhaustive s:		
•Water and/o	r land use disputes and the possible cumulative effects of an unequal		
distribution of access rights to the land or water in question;			
	fety risks from potential accidents (e.g. potential spills in water bodies, etc.);		
	e cultural values of local communities;		
●Etc.			
16.1			
	concerned about the project, information on the nature of the concern and any information must be provided to INFC.		
Yes 🗆 No 🔽	Please elaborate:		

ER.4.1: Are	environmental issues expected as a result of this project?
Yes 🔽	Please elaborate: The project site was disturbed by placement of surplus excavated soils from the South Fraser Perimeter Road (SFPR) Project along Highway 17. The soil placement activities were authorised under the SFPR Environmental Assessment Certificate (EAC) and restoration of the site was included in the EAC Commitments.
No 🗆	Despite being replanted, the site is considered to provide limited ecological value. However, if the site is left undisturbed it would have future potential to provide valuable wildlife habitat. To ensure the intentions of the EAC Commitments are respected, the project team has created a habitat offsetting plan that will compensate for the potential wildlife habitat (i.e.areas replanted post soil placement) at a 1:1 ratio at a nearby location.

	any part of the project located in whole or in part on land potentially d by previous activities:
Yes 🗆	Please elaborate: A Phase II Environmental Site Assessment was completed on the
	Project site. It was determined that the surplus soils placed on the site are of
	residential quality under the Contaminated Sites Regulation standards.
No 🗹	

ER.4.3: Is	an environm	nental site assessment available for this project regarding
contaminat	ted site(s):	
Yes 🗆	No 🗹	Phase I
Yes 🔽	No □	Phase II – Copy could be made available to INFC at any time
Yes 🗆	No 🗹	Phase III
	_	ny of the above, please provide copies of all reports related to the
project, if n	ot already provi	ded. If the report(s) is/are at the development stage, please indicate

the phase, and when a copy will be provided to INFC.

ER.4.4: Doe assessment?	es the project (either in full or in part) require a provincial environmental
	If not already provided, please provide copies of all reports related to the project. If the report(s) is/are at the development stage, please indicate when it/they will be completed and when a copy will be provided to INFC.

#### **Aboriginal Consultation Part**

This section contains a number of questions aimed at developing a better overview of the types of activities and/or work that will be carried out to determine the potential impact it could have on the Aboriginal or treaty rights of Aboriginal peoples. To determine whether the Crown conduct could have an adverse impact on established or potential Aboriginal or treaty rights, information must be compiled on those rights, which could include the right to hunt, fish, trap, gather and trade, and may either be established by a court or in a treaty, or may be asserted by an Aboriginal group, for example, in litigation or for the purpose of negotiating a treaty.

This step must be taken into consideration very early on in the process otherwise project delays can be expected if consultation is not completed satisfactorily or in a timely manner.

# AC.1: Activities Related to the Project that could potentially impact Aboriginal rights. Examples of traditional Aboriginal activities can vary, and include gathering wild mushrooms and medicinal herbs on a river bank, fishing in a salmon river, hunting moose in the forest, and may involve ceremonial sites and former burial grounds. If one or more of the questions in this part are answered in the affirmative, please provide a description of the activity or activities in the last line of the table. Yes 🗹 No 🗆 Does the project involve works or activities on, under, over, through or across a water body such as a wetland, stream, river or lake? Check all that apply. Fresh water: Stream Lake Wetland River ☐ Pond ☐ Reservoir ☐ Active Floodplain Fish Bearing Watercourse Coastal and Marine: Beach $\square$ Cove ☐ Mud Flat ☐ Salt Marsh ☐ Bay ☐ Exposed Coastline Fish Bearing Watercourse Other: Please describe: Yes 🔽 No 🗆 Can the work proposed have upstream or downstream impacts (e.g. change in water or temperature level upstream that could result in positive or negative impacts downstream, change in the turbidity, etc.)? No 🔽 $_{ m Yes} \square$ Are there activities proposed that may affect aboriginal traditional activities. Check all activities that apply. Fishing (e.g., preventing access to a fishing area or work in a waterbody such as river, lake, stream, culverts) ☐ Hunting (e.g., preventing access to a hunting area or clearing of forest or other vegetation etc.) ☐ Gathering (e.g., preventing access to a gathering area or clearing of forest or other vegetation etc.) ☐ Other (e.g. work close to or preventing access to sites of cultural/historical/archeological/ceremonial significance project etc.) Yes 🗆 No 🔽 Is the project (in full or in part) occurring on undisturbed or undeveloped land?

		If yes, please provide information about how much land will be affected by the project in the appropriate space. Disturbed and/or developed land may include land that has undergone deforestation, land previously used for agricultural purposes, or land that has been built up (e.g. buildings were previously constructed upon, etc.).
Yes 🗆	No 🗹	Is any component of the proposed project located outside the existing infrastructure footprint (build up footprint)?
Yes 🔽	No 🗆	Are there any relevant project activities that might affect other aspects of the environment (e.g. increases sound and/or noise levels, creates barriers to or limits access to harvesting areas, adds runoff to a watercourse, involves excavation)?

If you answered "yes" to any of the above, please provide details.

The following watercourses have been identified within the project site:

- One Class AO (red-dashed)ephemeral ditch (Landfill Creek tributary) potentially inhabited during the over-wintering period with access enhancement
- One wetland adjacent to the ephemeral ditch.
- One Class B (yellow) (154A Street Watercourse) non-fish-bearing cattail marsh (Wm05) blue listed wetland / with significant food/nutrient value

With the exception of a fish passage culvert on the Class AO ephemeral ditch, the project design will avoid impacts to the Class AO watercourse and the adjacent. A culvert will also be installed on the Class B non-fish-bearing cattail marsh, the culvert will allow for water flow however the functionality of the wetland will be greatly reduced. The appropriate *Water Sustainability Act* Approvals will be obtained prior to construction works on the watercourses mentioned above.

	other federal, provincial or territorial government entity indicated that
Aboriginal con	sultation is required for this project?
Yes 🔽	Please specify. As per BC MOTI best practices, Aboriginal Group notification
	letters with an invitation for comment will be submitted for the project.
No 🗆	
Unknown	

AC.3.1: Has	the province (or territory) been in contact with any Aboriginal groups
regarding thi	is project?
Yes 🗖	Please provide a summary of the consultation activities completed to date. If available, please provide details such as if any concerns were raised by Aboriginal groups, the nature of the concerns raised, and include in an attachment any information that may be useful (e.g. consultation plan, consultation summary, contact information, letters, emails, public notices, and any other types of communications).
No 🗹	

AC.3.2: Have you been in contact or plan to contact any Aboriginal groups regarding this

project?	
Yes 🗹	Please provide a summary of the consultation activities completed to date. If available, please provide details such as if any concerns were raised by Aboriginal groups, the nature of the concerns raised, and include in an attachment any information that may be useful (e.g. consultation plan, consultation summary, contact information, letters, emails, public notices, and any other types of communications).
No 🗆	

#### AC.4: Involvement of the Crown -

Other Federal or Provincial Departments or Agencies may be involved in the project (e.g., if a <u>permit, authorization, land transfer agreement, lease</u>, etc. is required ), such as, but not limited to:

The purpose of this section is to identify if other federal or provincial departments or agencies may be undertaking Aboriginal consultation activities as a result of their involvement in the project (e.g., issuing a permit and/or authorization).

If other authorities are involved, it is important to identify them, and to describe their role, particularly if they have to issue or have issued a permit and/or authorization. This is necessary for a number of reasons: to avoid procedural duplication, to enable the coordinated actions of the various authorities involved and to avoid submitting unnecessary repetitive requests to the Aboriginal groups concerned.

The information provided about the authorities and their actual or potential involvement in the project will help INFC to confirm their collaboration as early on in the process as possible.

Yes 🔽	No 🗆	Unknown 🗆	Fisheries and Oceans Canada (e.g. Fisheries Act)
Yes 🗆	No 🗆	Unknown 🗹	Transport Canada (e.g. Navigation Protection Act)
Yes 🗆	No 🔽	Unknown 🗆	Natural Resources Canada (e.g. Explosives Act)
Yes 🔽	№ □	Unknown 🗆	Environment Canada (e.g. Species at Risk Act, Migratory Birds Convention Act, Canadian Environmental Protection Act)
Yes $\square$	No 🔽	Unknown 🗆	Parks Canada Agency
Yes 🗹	No 🗆	Unknown 🗆	Other departments (e.g. federal department, provincial department, funding department,) If applicable, please identify the federal department or agency and approval required.

If you answered "<u>yes</u>" to any of the above, please describe the involvement of the identified department(s)/agency(s) in detail.

The agencies listed above will be contacted regarding environmental permits and approvals required to complete construction of the project. Upon completion of the habitat offsetting plan the BC Environmental Assessment Office and Ministry of Forest Lands and Natural Resources will be consulted. *Please provide contact information for each department identified so INFC can coordinate with them to avoid delays and duplication.* 

AC.5: Provincial (or territorial) permits

Please list all provincial (or territorial) permits that will be required for the project.

Environmental permits and approvals to complete this work will include those associated with the BC *Water Sustainability Act*, federal *Fisheries Act*, and Riparian Areas Regulations. In addition to permits, construction works will have to be in accordance with the *Wildlife Act*, *Species at Risk Act*, *Fisheries Act*, *Fisheries Protection Act*, Riparian Areas Regulations, and *Water Sustainability Act*.

#### **Declaration of Information**

Please there haves to acknowledge you understand and/or agree to the following

statements:
INFC may have a duty to consult and, where appropriate, accommodate aboriginal groups, when the Crown contemplates conduct (such as providing funding) that might adversely impact potential or established Aboriginal or Treaty rights. INFC will rely to the extent possible on other processes that included Aboriginal consultation (e.g., a provincial environmental assessment process). However, it is understood that INFC may delegate certain procedural responsibilities to the proponent and the proponent will assist or carry out various aspects of consultation (e.g., the gathering of information). Note that a Proponent Guide and Toolkit for Aboriginal Consultation Process will be provided at the appropriate time.
$\square$ It is understood that INFC may not enter into a contribution agreement until such time as INFC has determined that its Aboriginal consultation obligations have been met.
☐ I hereby certify that the information provided is accurate to the best of my knowledge and I understand that inaccurate information may result in the requirement for additional environmental and/or aboriginal consultation review.
Questionnaire completed by:
Signature:
Date:

#### **Additional Links**

Complete versions of the various acts outlined in this document please copy and paste these links into your browser.

- Oceans Act-http://laws-lois.justice.gc.ca/PDF/O-2.4.pdf
- Wild Life Regulation-http://laws-lois.justice.gc.ca/PDF/O-2.4.pdf
- Migratory Bird Sanctuary-http://laws-lois.justice.gc.ca/PDF/C.R.C.,\_c.\_1036.pdf
- Regulations Designating Physical Activities-http://laws-lois.justice.gc.ca/PDF/C.R.C.,\_c.\_1036.pdf
- Prescribed Information for the Description of a Designated Project Regulationshttp://laws-lois.justice.gc.ca/PDF/SOR-2012-148.pdf

Appendix C

Highway 17 / Truck Access Synchro / SimTraffic Model Reports



2017 AM Peak



**3**: 07/02/2017

	•	-	←	•	-	4
Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	ሻ	<b>†</b> †	<b>^</b>	7	ሻ	7
Volume (vph)	81	799	1812	56	88	132
Satd. Flow (prot)	1014	2944	2944	907	1014	907
FIt Permitted	0.950				0.950	
Satd. Flow (perm)	1014	2944	2944	907	1014	907
Satd. Flow (RTOR)				62		123
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90
Heavy Vehicles (%)	80%	24%	24%	80%	80%	80%
Shared Lane Traffic (%)						
Lane Group Flow (vph)	90	888	2013	62	98	147
Turn Type	Prot	NA	NA	pm+ov	NA	Perm
Protected Phases	5	Free!	6	4	4!	
Permitted Phases				6		4
Total Split (s)	12.0		66.0	12.0	12.0	12.0
Total Lost Time (s)	3.0		3.0	3.0	3.0	3.0
Act Effct Green (s)	9.0	92.1	65.0	77.1	9.0	9.0
Actuated g/C Ratio	0.10	1.00	0.71	0.84	0.10	0.10
v/c Ratio	0.91	0.30	0.97	0.08	0.99	0.74
Control Delay	112.6	0.3	27.6	0.6	132.9	33.9
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	112.6	0.3	27.6	0.6	132.9	33.9
LOS	F	Α	С	А	F	С
Approach Delay		10.6	26.8		73.5	
Approach LOS		В	С		E	
Queue Length 50th (m)	15.6	0.0	148.8	0.0	17.2	3.9
Queue Length 95th (m)	#43.3	0.0	#229.7	1.4	#47.4	#32.1
Internal Link Dist (m)	11 10.0	280.8	97.9		280.8	# OZ. 1
Turn Bay Length (m)	152.4	200.0	01.0		200.0	76.2
Base Capacity (vph)	99	2944	2078	769	99	199
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.91	0.30	0.97	0.08	0.99	0.74
1 todadou 1/0 l tatio	0.01	0.00	0.01	0.00	0.00	0.17

#### Intersection Summary

Cycle Length: 90

Actuated Cycle Length: 92.1 Control Type: Semi Act-Uncoord

Maximum v/c Ratio: 0.99

Intersection Signal Delay: 25.4 Intersection Capacity Utilization 69.5% Intersection LOS: C
ICU Level of Service C

Analysis Period (min) 15

# 95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

! Phase conflict between lane groups.

Splits and Phases: 3:



# 3: Performance by movement

Movement	EBL	EBT	WBT	WBR	SBL	SBR	All	
Denied Delay (hr)	0.0	0.0	0.0	0.0	0.0	0.0	0.1	
Denied Del/Veh (s)	2.8	0.2	0.0	0.0	0.2	0.2	0.2	
Total Delay (hr)	0.7	0.1	2.6	0.0	2.1	0.1	5.7	
Total Del/Veh (s)	58.0	1.2	10.5	1.4	145.3	7.2	13.7	
Travel Dist (km)	12.6	120.2	106.6	2.9	13.9	17.6	273.8	
Travel Time (hr)	0.9	1.4	3.7	0.1	2.5	0.7	9.4	
Avg Speed (kph)	14	89	29	37	5	24	29	
Fuel Used (I)	1.2	10.9	8.3	0.0	2.5	1.5	24.4	
Fuel Eff. (kpl)	10.9	11.1	12.9	70.6	5.5	11.3	11.2	
HC Emissions (g)	66	266	151	2	113	84	681	
CO Emissions (g)	1143	6552	2656	34	1541	1229	13155	
NOx Emissions (g)	122	648	376	3	182	187	1518	
Density (m/veh)							99	
Occupancy (veh)	2	3	7	0	5	1	19	

# **Total Network Performance**

enied Delay (hr) 0.1	
enied Del/Veh (s) 0.3	
tal Delay (hr) 9.7	
tal Del/Veh (s) 23.1	
avel Dist (km) 894.3	
avel Time (hr) 20.3	
g Speed (kph) 44	
el Used (I) 90.1	
el Eff. (kpl) 9.9	
C Emissions (g) 2455	
D Emissions (g) 51744	
Ox Emissions (g) 6031	
ensity (m/veh) 68	
ccupancy (veh) 40	

Surrey Truck Stop
Brent
SimTraffic Report
Page 1

2017 PM Peak

3: 07/02/2017

	•	-	•	•	<b>/</b>	4
Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	7	<b>^</b>	<b>^</b>	7	ř	7
Volume (vph)	115	1519	1076	88	56	84
Satd. Flow (prot)	1014	2944	2944	907	1014	907
Flt Permitted	0.950				0.950	
Satd. Flow (perm)	1014	2944	2944	907	1014	907
Satd. Flow (RTOR)				98		93
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90
Heavy Vehicles (%)	80%	24%	24%	80%	80%	80%
Shared Lane Traffic (%)						
Lane Group Flow (vph)	128	1688	1196	98	62	93
Turn Type	Prot	NA	NA	pm+ov	NA	Perm
Protected Phases	5	Free!	6	4	4!	
Permitted Phases				6		4
Total Split (s)	14.0		31.0	10.0	10.0	10.0
Total Lost Time (s)	3.0		3.0	3.0	3.0	3.0
Act Effct Green (s)	10.2	53.2	32.3	40.0	7.0	7.0
Actuated g/C Ratio	0.19	1.00	0.61	0.75	0.13	0.13
v/c Ratio	0.66	0.57	0.67	0.14	0.47	0.47
Control Delay	39.7	0.8	12.8	1.3	36.2	14.7
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	39.7	0.8	12.8	1.3	36.2	14.7
LOS	D	Α	В	Α	D	В
Approach Delay		3.6	11.9		23.3	
Approach LOS		Α	В		С	
Queue Length 50th (m)	11.8	0.0	47.0	0.0	5.9	0.0
Queue Length 95th (m)	#32.2	0.0	70.4	2.9	#18.4	#11.0
Internal Link Dist (m)		280.8	97.9		280.8	
Turn Bay Length (m)	152.4					76.2
Base Capacity (vph)	210	2944	1787	706	134	200
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.61	0.57	0.67	0.14	0.46	0.47

#### Intersection Summary

Cycle Length: 55

Actuated Cycle Length: 53.2 Control Type: Semi Act-Uncoord

Maximum v/c Ratio: 0.67

Intersection Signal Delay: 7.8
Intersection Capacity Utilization 52.0%

Intersection LOS: A ICU Level of Service A

Analysis Period (min) 15

# 95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

! Phase conflict between lane groups.

Splits and Phases: 3:



# 3: Performance by movement

Movement	EBL	EBT	WBT	WBR	SBL	SBR	All
Denied Delay (hr)	0.0	0.1	0.0	0.0	0.0	0.0	0.1
Denied Del/Veh (s)	2.3	0.4	0.0	0.0	0.1	0.1	0.3
Total Delay (hr)	0.4	0.3	1.2	0.0	0.2	0.0	2.2
Total Del/Veh (s)	22.7	1.5	8.2	1.8	27.3	1.3	5.3
Travel Dist (km)	17.0	228.5	63.6	5.3	9.1	12.2	335.6
Travel Time (hr)	0.7	2.7	1.9	0.1	0.5	0.4	6.4
Avg Speed (kph)	27	87	34	35	17	29	54
Fuel Used (I)	1.2	19.7	4.7	0.1	0.9	1.0	27.6
Fuel Eff. (kpl)	14.6	11.6	13.6	56.8	10.1	11.8	12.2
HC Emissions (g)	78	500	92	5	44	56	775
CO Emissions (g)	1447	11684	1830	76	631	827	16495
NOx Emissions (g)	162	1246	229	8	94	130	1868
Density (m/veh)							147
Occupancy (veh)	1	5	4	0	1	1	13

# **Total Network Performance**

Denied Delay (hr)	0.2	
Denied Del/Veh (s)	0.4	
Total Delay (hr)	4.2	
Total Del/Veh (s)	10.1	
Travel Dist (km)	898.3	
Travel Time (hr)	14.8	
Avg Speed (kph)	61	
Fuel Used (I)	85.4	
Fuel Eff. (kpl)	10.5	
HC Emissions (g)	2421	
CO Emissions (g)	53274	
NOx Emissions (g)	5992	
Density (m/veh)	93	
Occupancy (veh)	29	

Surrey Truck Stop 2017 PM

Brent

SimTraffic Report

Page 1

2027 AM Peak



**3**: 07/02/2017

	٠	<b>→</b>	<b>←</b>	•	<b>\</b>	1
Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	ሻ	<b>^</b>	<b>↑</b> ↑	#	ሻ	1
Volume (vph)	81	1023	2320	56	88	132
Satd. Flow (prot)	1014	2944	2944	907	1014	907
Flt Permitted	0.950				0.950	
Satd. Flow (perm)	1014	2944	2944	907	1014	907
Satd. Flow (RTOR)				62		83
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90
Heavy Vehicles (%)	80%	24%	24%	80%	80%	80%
Shared Lane Traffic (%)						
Lane Group Flow (vph)	90	1137	2578	62	98	147
Turn Type	Prot	NA	NA	pm+ov	NA	Perm
Protected Phases	5	Free!	6	. 4	4!	
Permitted Phases				6		4
Total Split (s)	14.0		121.0	15.0	15.0	15.0
Total Lost Time (s)	3.0		3.0	3.0	3.0	3.0
Act Effct Green (s)	11.0	150.0	118.0	133.0	12.0	12.0
Actuated g/C Ratio	0.07	1.00	0.79	0.89	0.08	80.0
v/c Ratio	1.22	0.39	1.11	0.08	1.21	0.99
Control Delay	228.4	0.4	76.2	0.4	221.6	101.9
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	228.4	0.4	76.2	0.4	221.6	101.9
LOS	F	Α	Ε	Α	F	F
Approach Delay		17.1	74.4		149.8	
Approach LOS		В	Ε		F	
Queue Length 50th (m)	~32.6	0.0	~460.8	0.0	~35.4	20.0
Queue Length 95th (m)	#69.0	0.0	#496.5	1.3	#73.7	#66.8
Internal Link Dist (m)		280.8	97.9		280.8	
Turn Bay Length (m)	152.4					76.2
Base Capacity (vph)	74	2944	2315	811	81	148
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	1.22	0.39	1.11	0.08	1.21	0.99

Intersection Summary

Cycle Length: 150
Actuated Cycle Length: 150
Control Type: Semi Act-Uncoord
Maximum v/c Ratio: 1.22
Intersection Signal Delay: 61.8
Intersection Capacity Utilization 79.0%

Intersection LOS: E ICU Level of Service D

Analysis Period (min) 15


Volume exceeds capacity, queue is theoretically infinite.
 Queue shown is maximum after two cycles.

# 95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

! Phase conflict between lane groups.

<u>3</u>: 07/02/2017



# 3: Performance by movement

Movement	EBL	EBT	WBT	WBR	SBL	SBR	All	
Denied Delay (hr)	0.0	0.0	0.0	0.0	0.0	0.0	0.1	
Denied Del/Veh (s)	2.8	0.3	0.0	0.0	0.2	0.2	0.1	
Total Delay (hr)	2.1	0.3	4.9	0.0	2.7	0.5	10.5	
Total Del/Veh (s)	169.4	2.0	15.3	1.7	193.0	27.3	20.3	
Travel Dist (km)	11.7	155.2	136.6	3.1	13.1	18.5	338.2	
Travel Time (hr)	2.3	1.9	6.3	0.1	3.2	1.2	14.9	
Avg Speed (kph)	5	84	22	36	4	16	23	
Fuel Used (I)	1.9	14.0	14.1	0.1	2.9	1.9	34.9	
Fuel Eff. (kpl)	6.1	11.1	9.7	55.4	4.5	10.0	9.7	
HC Emissions (g)	89	325	243	3	123	92	875	
CO Emissions (g)	1323	8010	3997	44	1662	1329	16365	
NOx Emissions (g)	131	803	611	5	187	192	1928	
Density (m/veh)							62	

# **Total Network Performance**

Denied Delay (hr)	1.0
Denied Del/Veh (s)	2.0
Total Delay (hr)	19.0
Total Del/Veh (s)	35.9
Travel Dist (km)	1117.9
Travel Time (hr)	32.8
Avg Speed (kph)	35
Fuel Used (I)	120.6
Fuel Eff. (kpl)	9.3
HC Emissions (g)	3034
CO Emissions (g)	61591
NOx Emissions (g)	7444
Density (m/veh)	43

Surrey Truck Stop 2027 AM SimTraffic Report
Brent Page 1

2027 PM Peak



3: 07/02/2017

	•	-	•	•	<b>&gt;</b>	4
Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	ሻ	<b>^</b>	<b>^</b>	7	ሻ	7
Volume (vph)	115	1944	1377	88	56	84
Satd. Flow (prot)	1014	2944	2944	907	1014	907
Flt Permitted	0.950				0.950	
Satd. Flow (perm)	1014	2944	2944	907	1014	907
Satd. Flow (RTOR)				98		93
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90
Heavy Vehicles (%)	80%	24%	24%	80%	80%	80%
Shared Lane Traffic (%)						
Lane Group Flow (vph)	128	2160	1530	98	62	93
Turn Type	Prot	NA	NA	pm+ov	NA	Perm
Protected Phases	5	Free!	6	4	4!	
Permitted Phases				6		4
Total Split (s)	19.0		59.0	12.0	12.0	12.0
Total Lost Time (s)	3.0		3.0	3.0	3.0	3.0
Act Effct Green (s)	14.8	91.3	58.8	70.5	8.6	8.6
Actuated g/C Ratio	0.16	1.00	0.64	0.77	0.09	0.09
v/c Ratio	0.78	0.73	0.81	0.14	0.65	0.55
Control Delay	67.4	1.7	17.0	1.1	70.7	21.5
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	67.4	1.7	17.0	1.1	70.7	21.5
LOS	Е	Α	В	Α	Е	С
Approach Delay		5.3	16.0		41.1	
Approach LOS		Α	В		D	
Queue Length 50th (m)	21.0	0.0	99.2	0.0	10.5	0.0
Queue Length 95th (m)	#47.6	0.0	133.1	3.1	#28.8	14.4
Internal Link Dist (m)		280.8	97.9		280.8	
Turn Bay Length (m)	152.4					76.2
Base Capacity (vph)	178	2944	1897	726	100	173
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.72	0.73	0.81	0.13	0.62	0.54

#### Intersection Summary

Cycle Length: 90

Actuated Cycle Length: 91.3 Control Type: Semi Act-Uncoord Maximum v/c Ratio: 0.81

Intersection Signal Delay: 11.0 Intersection Capacity Utilization 63.7%

Intersection LOS: B
ICU Level of Service B

Analysis Period (min) 15

# 95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

! Phase conflict between lane groups.

Splits and Phases: 3:



# 3: Performance by movement

Movement	EBL	EBT	WBT	WBR	SBL	SBR	All	
Denied Delay (hr)	0.0	0.2	0.0	0.0	0.0	0.0	0.2	
Denied Del/Veh (s)	2.1	0.7	0.0	0.0	0.1	0.2	0.4	
Total Delay (hr)	0.7	0.6	1.7	0.0	0.5	0.0	3.6	
Total Del/Veh (s)	42.6	2.2	9.0	2.0	55.7	2.9	7.0	
Travel Dist (km)	17.7	287.9	81.5	5.2	8.8	10.8	411.8	
Travel Time (hr)	1.0	3.7	2.5	0.1	0.8	0.4	8.6	
Avg Speed (kph)	18	82	32	35	11	27	49	
Fuel Used (I)	1.5	23.9	6.2	0.1	1.1	0.9	33.6	
Fuel Eff. (kpl)	12.1	12.1	13.1	58.3	8.3	11.6	12.2	
HC Emissions (g)	75	615	118	6	54	50	917	
CO Emissions (g)	1306	13837	2306	80	761	725	19015	
NOx Emissions (g)	150	1552	290	8	105	112	2217	
Density (m/veh)							110	
Occupancy (veh)	2	7	5	0	2	1	17	

# **Total Network Performance**

Denied Delay (hr)	0.3	
Denied Del/Veh (s)	0.5	
Total Delay (hr)	6.5	
Total Del/Veh (s)	12.7	
Travel Dist (km)	1107.6	
Travel Time (hr)	19.3	
Avg Speed (kph)	58	
Fuel Used (I)	104.2	
Fuel Eff. (kpl)	10.6	
HC Emissions (g)	2822	
CO Emissions (g)	61491	
NOx Emissions (g)	7037	
Density (m/veh)	72	
Occupancy (veh)	38	

Surrey Truck Stop 2027 PM

Brent

SimTraffic Report

Page 1